

THE NEW CAMBRIDGE
HISTORY OF

ISLAM

VOLUME 1

The Formation of the Islamic World
Sixth to Eleventh Centuries

EDITED BY
CHASE F. ROBINSON

THE NEW CAMBRIDGE
HISTORY OF
ISLAM

★

VOLUME I

The Formation of the Islamic World
Sixth to Eleventh Centuries

★

Edited by

CHASE F. ROBINSON



CAMBRIDGE
UNIVERSITY PRESS

THE NEW CAMBRIDGE HISTORY OF

ISLAM

*

VOLUME I

The Formation of the Islamic World Sixth to Eleventh Centuries

Since the 1970s, the study of early Islamic history has been transformed by new methods and sources. Volume 1 of *The New Cambridge History of Islam*, which surveys the political and cultural history of Islam from its Late Antique origins until the eleventh century, brings together contributions from leading scholars in the field. The book is divided into four parts. The first provides an overview of physical and political geography of the Late Antique Middle East. The second charts the rise of Islam and the emergence of the Islamic political order under the Umayyad and the Abbasid caliphs of the seventh, eighth and ninth centuries, followed by the dissolution of the empire in the tenth and eleventh. 'Regionalism', the overlapping histories of the empire's provinces, is the focus of part three, while part four provides a fully up to date discussion of the sources and controversies of early Islamic history, including a survey of numismatics, archaeology and material culture.

CHASE F. ROBINSON, formerly Professor of Islamic History at the Faculty of Oriental Studies, University of Oxford, is currently Distinguished Professor of History and Provost at the Graduate Centre, the City University of New York. He is the author of *The Legacy of the Prophet: The Middle East and Islam, 600–1300* (forthcoming), *Islamic Historiography* (2003) and *Empire and Elites after the Muslim Conquest: The Transformation of Northern Mesopotamia* (2000).

THE NEW CAMBRIDGE HISTORY OF
ISLAM

The New Cambridge History of Islam offers a comprehensive history of Islamic civilisation, tracing its development from its beginnings in seventh century Arabia to its wide and varied presence in the globalised world of today. Under the leadership of the Prophet Muḥammad, the Muslim community coalesced from a scattered, desert population and, following his death, emerged from Arabia to conquer an empire which, by the early eighth century, stretched from India in the east to Spain in the west. By the eighteenth century, despite political fragmentation, the Muslim world extended from West Africa to South East Asia. Today, Muslims are also found in significant numbers in Europe and the Americas, and make up about one fifth of the world's population.

To reflect this geographical distribution and the cultural, social and religious diversity of the peoples of the Muslim world, *The New Cambridge History of Islam* is divided into six volumes. Four cover historical developments, and two are devoted to themes that cut across geographical and chronological divisions – themes ranging from social, political and economic relations to the arts, literature and learning. Each volume begins with a panoramic introduction setting the scene for the ensuing chapters and examining relationships with adjacent civilisations. Two of the volumes – one historical, the other thematic – are dedicated to the developments of the last two centuries, and show how Muslims, united for so many years in their allegiance to an overarching and distinct tradition, have sought to come to terms with the emergence of Western hegemony and the transition to modernity.

The time is right for this new synthesis reflecting developments in scholarship over the last generation. *The New Cambridge History of Islam* is an ambitious enterprise directed and written by a team combining established authorities and innovative younger scholars. It will be the standard reference for students, scholars and all those with enquiring minds for years to come.

General editor

MICHAEL COOK, CLASS OF 1943 UNIVERSITY PROFESSOR OF
NEAR EASTERN STUDIES, PRINCETON UNIVERSITY

VOLUME 1

*The Formation of the Islamic World
Sixth to Eleventh Centuries*

EDITED BY CHASE F. ROBINSON

VOLUME 2

*The Western Islamic World
Eleventh to Eighteenth Centuries*

EDITED BY MARIBEL FIERRO

VOLUME 3

*The Eastern Islamic World
Eleventh to Eighteenth Centuries*

EDITED BY DAVID O. MORGAN AND ANTHONY REID

VOLUME 4

Islamic Cultures and Societies to the End of the Eighteenth Century

EDITED BY ROBERT IRWIN

VOLUME 5

The Islamic World in the Age of Western Dominance

EDITED BY FRANCIS ROBINSON

VOLUME 6

*Muslims and Modernity
Culture and Society since 1800*

EDITED BY ROBERT W. HEFNER

Grants made from an award to the General Editor by the
Andrew W. Mellon Foundation, and from the National Endowment
for the Humanities RZ-50616-06, contributed to the development of
The New Cambridge History of Islam. In particular the grants funded
the salary of William M. Blair, who served as Editorial Assistant
from 2004 to 2008.

CAMBRIDGE UNIVERSITY PRESS
Cambridge, New York, Melbourne, Madrid, Cape Town, Singapore,
São Paulo, Delhi, Dubai, Tokyo, Mexico City

Cambridge University Press
The Edinburgh Building, Cambridge CB2 8RU, UK

Published in the United States of America by Cambridge University Press, New York

www.cambridge.org
Information on this title: www.cambridge.org/9780521838238

© Cambridge University Press 2010

This publication is in copyright. Subject to statutory exception
and to the provisions of relevant collective licensing agreements,
no reproduction of any part may take place without the written
permission of Cambridge University Press.

First published 2010

Printed in the United Kingdom at the University Press, Cambridge

A catalogue record for this publication is available from the British Library

Library of Congress Cataloguing in Publication data
The new Cambridge history of Islam / general editor, Michael Cook.
p. cm.

Includes bibliographical references.

Contents : v. 1. The formation of the Islamic world, sixth to eleventh centuries / edited by Chase
F. Robinson – v. 2. The western Islamic world, eleventh to eighteenth centuries / edited by
Maribel Fierro – v. 3. The eastern Islamic world, eleventh to eighteenth centuries / edited by
David Morgan and Anthony Reid – v. 4. Islamic cultures and societies to the end of the
eighteenth century / edited by Robert Irwin with William Blair – v. 5. The Islamic world
in the age of Western dominance / edited by Francis Robinson – v. 6. Muslims and
modernity: culture and society since 1800 / edited by Robert Hefner.

ISBN 978-0-521-83823-8

1. Islamic countries – History. 2. Islamic civilization. I. Cook, M. A. II. Title.
D835.6.C3 2008
909'.09767–dc22
2010002830

ISBN 978-0-521-83823-8 Volume 1 Hardback
ISBN 978-0-521-51536-8 Set of 6 Hardback Volumes

Cambridge University Press has no responsibility for the persistence or
accuracy of URLs for external or third-party internet websites referred to in
this book, and does not guarantee that any content on such websites is,
or will remain, accurate or appropriate.

Contents

<i>List of illustrations</i>	page x
<i>List of maps</i>	xiv
<i>List of genealogies</i>	xv
<i>List of contributors</i>	xvi
<i>A note on transliteration and pronunciation</i>	xix
<i>A note on dating</i>	xxi
<i>Chronology</i>	xxii
<i>List of abbreviations</i>	xxvi
<i>Maps</i>	xxvii

Introduction 1

CHASE F. ROBINSON

PART I

THE LATE ANTIQUE CONTEXT 17

1 · The resources of Late Antiquity 19

JOHN HALDON

2 · The late Roman/early Byzantine Near East 72

MARK WHITTOW

3 · The late Sasanian Near East 98

JOSEF WIESEHÖFER

4 · Pre Islamic Arabia 153

MICHAEL LECKER

Contents

PART II
UNIVERSALISM AND IMPERIALISM 171

5 · The rise of Islam, 600 705 173

CHASE F. ROBINSON

6 · The empire in Syria, 705 763 226

PAUL M. COBB

7 · The empire in Iraq, 763 861 269

TAYEB EL HIBRI

8 · The waning of empire, 861 945 305

MICHAEL BONNER

9 · The late 'Abbasid pattern, 945 1050 360

HUGH KENNEDY

PART III
REGIONALISM 395

10 · Arabia 397

ELLA LANDAU TASSERON

11 · The Islamic east 448

ELTON L. DANIEL

12 · Syria 506

R. STEPHEN HUMPHREYS

13 · Egypt 541

MICHAEL BRETT

14 · The Iberian Peninsula and North Africa 581

EDUARDO MANZANO MORENO

Contents

PART IV
THE HISTORIOGRAPHY OF EARLY ISLAMIC
HISTORY 623

15 · Modern approaches to early Islamic history 625

FRED M. DONNER

16 · Numismatics 648

STEFAN HEIDEMANN

17 · Archaeology and material culture 664

MARCUS MILWRIGHT

Conclusion: From formative Islam to classical Islam 683

CHASE F. ROBINSON

Glossary 696

Bibliography 699

Index 784

Illustrations

Plates

The plates are to be found between pages 658 and 659

- 16.1 (a, b, obverse and reverse) Byzantium, Heraclius and Heraclius Constantine, *nomisma*, Constantinople, [c. 616–25 CE], Oriental Coin Cabinet Jena inv. no. 2007 04 I (4.21g)
- 16.2 (a, b, obverse and reverse) Byzantium, Constans II, *folles*, Constantinople, regnal year 3 (643–4 CE), Oriental Coin Cabinet Jena inv. no. 303 D5 (4.80g)
- 16.3 (a, b, obverse and reverse) Sasanians, Khusrau II, *drahm*, 'HM (Hamadhan), regnal year 29 (618–19 CE), Oriental Coin Cabinet Jena inv. no. 302 B5 (3.46g)
- 16.4 (a, b, obverse and reverse) Umayyads, *tremisses/thulth dinar*, Afrika (Qayrawan), undated [c. 90–3/708–11], Oriental Coin Cabinet Jena inv. no. 305 B2 (1.37g)
- 16.5 (a, b, obverse and reverse) Umayyads, *fals*, Emisis/Himş, [c. 50s/670s–74/692], validating mark KAAON and *ṭayyib*; Oriental Coin Cabinet Jena inv. no. 303 C8 (3.85g)
- 16.6 (a, b, obverse and reverse) Umayyads, *fals*, Damascus/Dimashq, [c. 50s/670–74/692], validating mark *ja'iz*; Oriental Coin Cabinet Jena inv. no. 303 Cro (5.19g)
- 16.7 (a, b, obverse and reverse) Umayyads, 'Abd Allah ibn 'Amir ibn Kurayz, *drahm*, abbreviation DP (probably Fasa in the Darabjird district), AH 43 (immobilised date, c. 43–7/663–8) Oriental Coin Cabinet Jena inv. no. 2005 15 2 (4.04g)
- 16.8 (a, b, obverse and reverse) Zubayrids, 'Abd Allah ibn al Zubayr, *drahm*, D'GH (Darabjird Jahrum), Yazdegerd era 60 (72/692), Oriental Coin Cabinet Jena inv. no. 2005 15 4 (4.12g)
- 16.9 (a, b, obverse and reverse) Zubayrids, 'Abd al 'Aziz ibn 'Abd Allah, *drahm*, abbreviation SK (Sistan), AH 72 (691–2 CE), coll. Mohsen Faroughi
- 16.10 (a, b, obverse and reverse) Umayyads, anonymous, *dinar*, [Damascus], AH 77 (696 CE), Oriental Coin Cabinet Jena inv. no. 303 A2 (4.45g)
- 16.11 (a, b, obverse and reverse) Umayyads, anonymous, *fals*, Manbij, [74–7/692–6], title *amir al mu'minin* and *khalifat Allah*, Oriental Coin Cabinet Jena inv. no. 303 G6 (2.70g)
- 16.12 (a, b, obverse and reverse) Umayyads, anonymous, *dinar*, [Damascus], AH 93 (711–12 CE), Oriental Coin Cabinet Jena inv. no. 306 A2 (4.23g)

- 16.13 (a, b, obverse and reverse) Umayyads, anonymous, *dirham*, al Kufa, AH 79 (698 9 CE), Oriental Coin Cabinet Jena inv. no. 305 H10 (2.87g)
- 16.14 (a, b, obverse and reverse) 'Abbasids, anonymous, *ḍinar*, [al Rafīqa], AH 191 (806 7 CE), mint mark *ra'*, Oriental Coin Cabinet Jena inv. no. 2000 II 1 (4.10g)
- 16.15 (a, b, obverse and reverse) 'Abbasids, anonymous, *dirham*, al Kufa, AH 132 (749 50 CE), Oriental Coin Cabinet Jena inv. no. 312 H7 (2.70g)
- 16.16 (a, b, obverse and reverse) 'Abbasids, al Mahdī Muḥammad as heir apparent, *dirham*, al Rayy, AH 146 (763 4 CE), Oriental Coin Cabinet Jena inv. no. 2002 9 29 (2.74g)
- 16.17 (a, b, obverse and reverse) 'Abbasids, al Amīn as heir, Khuzayma ibn Khazim as governor of Armenia and Isma'īl ibn Ibrāhīm as another official, *dirham*, Armīniya (Dabil), AH 190 (805 6 CE), Oriental Coin Cabinet Jena inv. no. 317 F9 (2.92g)
- 16.18 (a, b, obverse and reverse) 'Abbasids, 'Umar ibn al 'Ala', governor of Ṭabaristan, Ṭabarī (half) *dirham*, Ṭabaristan, 123 post Yazdegerd era (158/774 5), Oriental Coin Cabinet Jena inv. no. 1998 2 498 (1.69g)
- 16.19 (a, b, obverse and reverse) 'Abbasids, al Mahdī Muḥammad, *dirham*, [Bukhara], [158 69/775 85], Oriental Coin Cabinet Jena inv. no. 305 E7 (2.33g)
- 16.20 (a, b, obverse and reverse) 'Abbasids, al Mu'taṣim billah, Abu Ja'far Ashinas, governor of the west, Muḥammad ibn Yusuf, governor in northern Mesopotamia, *fāls*, al Rafīqa, AH 226 (840 1 CE), Oriental Coin Cabinet Jena inv. no. 321 B7 (3.41g)
- 16.21 (a, b, obverse and reverse) 'Abbasids, anonymous, *fāls*, (Syria), [c. 130 50/750 70], cast, Oriental Coin Cabinet Jena inv. no. 1998 2 378 (1.18g)
- 16.22 (a, b, obverse and reverse) 'Abbasids, al Ma'mun as *khalīfat Allah*, 'Alī al Riḍa as heir, al Faḍl ibn Sahl as *dhū 'l rīyasatayn*, *dirham*, Iṣfahan, AH 204 (819 20 CE), Oriental Coin Cabinet inv. no. 328 F1 (2.97g)
- 16.23 (a, b, obverse and reverse) 'Abbasids, anonymous, *dirham*, Madīnat al Salam, AH 208 (823 4 CE), Oriental Coin Cabinet Jena inv. no. 321 E5 (2.88g)
- 16.24 (a, b, obverse and reverse) 'Abbasids, al Mu'taṣim billah, *dirham*, Madīnat al Salam, AH 226 (840 1 CE), Oriental Coin Cabinet Jena inv. no. 321 E4 (2.88g)
- 16.25 (a, b, obverse and reverse) Ṣaffarids, Ya'qub ibn al Layth, *dirham*, Panjhir, AH 261 (874 5 CE), Oriental Coin Cabinet Jena inv. no. 327 H6 (2.82g)
- 16.26 (a, b, obverse and reverse) Dulafids in Central Iran, Aḥmad ibn 'Abd al 'Azīz, acknowledging the 'Abbasid al Mu'tamid 'ala Allah and the heir al Muwaffaq billah as overlords, *ḍinar*, Mah al Baṣra, AH 273 (886 7 CE), Oriental Coin Cabinet Jena inv. no. 323 A2 (4.11g)
- 16.27 (a, b, obverse and reverse) 'Abbasids, al Muttaqī lillah, and Bajkam as *amīr al umara'*, *dirham*, Madīnat al Salam, AH 329 (940 1 CE), Oriental Coin Cabinet Jena inv. no. 325 G7 (2.28g)
- 16.28 (a, b, obverse and reverse) Buyids of Fars, Qīwam al Dīn, acknowledging the Buyid Baha' al Dawla as overlord, good silver '*adl dirham*', Shiraz, AH 400 (1009 10 CE), Oriental Coin Cabinet inv. no. 2002 9 127 (3.07g)
- 16.29 (a, b, obverse and reverse) 'Uqaylids, Janah al Dawla, acknowledging the Buyid Baha' al Dawla as overlord, *dirham*, Naṣībīn, AH 385 (995 6 CE), Oriental Coin Cabinet Jena inv. no. 340 A6 (3.21g)

- 16.30 (a, b, obverse and reverse) Sallarids, Jastan and Ibrahim ibn al Marzuban, *dmār*, Maragha, AH 347 (958 9 CE), Oriental Coin Cabinet Jena inv. no. 326 A4 (4.41g)
- 16.31 (a, b, obverse and reverse) Samanids, Isma'īl ibn Aḥmad, *dirham*, al Shash (present day Tashkent), AH 292 (904 5 CE), Coin Cabinet Jena inv. no. 329 C4 (2.82g)
- 16.32 (a, b, obverse and reverse) Samanids, Naṣr ibn Aḥmad, *fals*, Bukhara, AH 305 (917 18 CE), Oriental Coin Cabinet Jena inv. no. 335 G9 (3.18g)
- 16.33 (a, b, obverse and reverse) Ghaznavids, Maḥmūd, *dirham yamīn*, Ghazna, AH 399 (1008 9 CE), Oriental Coin Cabinet Jena inv. no. 2006 2 67 (3.42g)
- 16.34 (a, b, obverse and reverse) Saljuqs, Malikshah, *dmār*, Nishapur, AH 484 (1091 2 CE), Oriental Coin Cabinet inv. no. 1999 14 3 (5.09g)
- 16.35 (a, b, obverse and reverse) Saljuqs of the East, Sultan Sanjar acknowledging Muḥammad Ṭāpar as supreme sultan, debased *dmār*, Walwalij (present day Qunduz), Muḥarrām AH 493 (Nov. 17 Dec. 16, 1099 CE), with *tamgha* sword, Oriental Coin Cabinet Jena inv. no. 2003 17 17 (2.82g)
- 16.36 (a, b, obverse and reverse) Faṭimids, al 'Azīz billah, *dmār maghribī* or *miṣrī*, Miṣr, AH 368 (978 9 CE), Oriental Coin Cabinet Jena inv. no. 401 H6 (4.16g)
- 16.37 (a, b, obverse and reverse) Faṭimids, al Mu'izz li Dīn Allah, *dirham*, al Maṣūniyya, AH 358 (968 9 CE), Oriental Coin Cabinet Jena inv. no. 401 G7 (1.36g)
- 16.38 Faṭimids, al Mustanṣir billah (r. 427 87/1036 94), token, dark blue glass, Oriental Coin Cabinet Jena inv. no. 440 A9 (3.02g)
- 16.39 (a, b, obverse and reverse) Numayrids, Manī' ibn Shabīb (r. c. 440 54/1050 62), acknowledging the Faṭimid caliph al Mustanṣir billah, *dirham aswad*, without mint and date, [Ruha, Ḥarran or al Raqqā], Oriental Coin Cabinet Jena inv. no. 2006 1 1 (1.11g)
- 16.40 (a, b, obverse and reverse) Zangids, Nur al Dīn Maḥmūd, *qirṭas*, Dimashq (Damascus), AH 558 (1162 3 CE), photo Oriental Coin Cabinet Jena (5.56g)
- 16.41 (a, b, obverse and reverse) Zangids, al Ṣalīḥ Isma'īl, *dirham*, Ḥalab, AH 571 (1175 6 CE), Oriental Coin Cabinet Jena inv. no. 2001 1 1 (2.79g)

Figures

- 17.1 Plan of the *dar al imara* at Kufa, Iraq, first/seventh century and later. After K. Creswell, *Early Muslim Architecture*, rev. edn (1969), vol. I.1, fig. 18 667
- 17.2 Exterior of Qaṣr al Kharana, Jordan (before 92/710). Photo: Marcus Milwright 668
- 17.3 Late Roman *castrum* known as Qaṣr al Bashīr, Jordan (293 305). Photo: Marcus Milwright 668
- 17.4 Plan of the town of 'Anjar, Lebanon. After Creswell, *Early Muslim Architecture*, vol. I.2, fig. 540 672
- 17.5 Plans of mosques I (possibly 84/703, marked in black) and II (marked in grey) in Wasīṭ. After F. Safar, *Wāsiṭ, the sixth season's excavations* (1945), fig. 5 673
- 17.6 Corona satellite photograph of al Raqqā, Syria, taken between 1960 and 1972: (1) al Raqqā (Kallinikos); (2) walled city of al Rafīqa; (3) North gate; (4) 'Baghdad gate'; (5) Congregational Mosque; (6) Possible line of the wall

List of illustrations

- enclosing al Raqqa al Muḥtariqa ('the burning Raqqa'); (7) site of an
'Abbasid period glass workshop; (8) Tal Aswad 676
- 17.7 Aerial view of Samarra' with the mosque of Abu Dulaf (245 47/859 61).
Creswell archive: EA.CA.271. Creswell Archive, courtesy of the Ashmolean
Museum, University of Oxford. 677
- 17.8 Earthenware bowl with tin glaze and cobalt (blue) and copper (green)
painting, Iraq, third/ninth century. 1978.2141. Courtesy of the
Ashmolean Museum, University of Oxford. 679

Maps

1	The physical geography of the Mediterranean and Near Eastern world	<i>page</i> xxvii
2	The political geography of the Mediterranean and Near Eastern world, <i>c.</i> 575	xxviii
3	The expansion of Islam in the east	xxix
4	The expansion of Islam in the west	xxx
5	The 'Abbasid empire in <i>c.</i> 800	xxxI
6	The Islamic world in <i>c.</i> 950	xxxii
7	Arabia	xxxiii
8	The Islamic east	xxxiv
9	Syria	xxxv
10	Egypt	xxxvi
11	Spain and North Africa	xxxvii

Genealogies

1. The 'northern' and 'southern' Arabs	<i>page</i> 156
2. The Quraysh	169
3. Muḥammad's family	188
4. The Umayyads	213
5. The Shi'ite imams	265
6. The 'Abbasids	270
7. The Buyids	366
8. The rulers of Egypt, 868–1036	562
9. The Umayyads of Spain	597

Contributors

MICHAEL BONNER is Professor of Medieval Islamic History in the Department of Near Eastern Studies at the University of Michigan. His publications on *jihad* and the medieval Islamic frontiers include *Aristocratic violence and holy war: Studies on the jihad and the Arab Byzantine frontier* (New Haven, 1996) and *Jihad in Islamic history: Doctrines and practice* (Princeton, 2006). His work on social and economic issues in the medieval Near East has resulted in several publications including *Poverty and charity in Middle Eastern contexts* (co edited with Amy Singer and Mine Ener) (Albany, 2003).

MICHAEL BRETT is Emeritus Reader in the History of North Africa at the School of Oriental and African Studies, London. He is the author (with Werner Forman) of *The Moors: Islam in the West* (London, 1980); (with Elizabeth Fentress) *The Berbers* (Oxford, 1996); *Ibn Khaldun and the medieval Maghrib* (Aldershot, 1999); and *The rise of the Fatimids: The world of the Mediterranean and the Middle East in the fourth century of the hijra, tenth century CE* (Leiden, 2001).

PAUL M. COBB is Associate Professor of Islamic History at the University of Pennsylvania. He is the author of *White banners: Contention in 'Abbasid Syria, 750–880* (Albany, 2001) and *Usama ibn Munqidh: Warrior poet of the age of Crusades* (Oxford, 2005).

ELTON L. DANIEL is Professor in the Department of History, University of Hawaii at Manoa. His publications include *The political and social history of Khurasan under Abbasid rule 747–820* (Minneapolis, 1979) and *The history of Iran* (London, 2001). He has written several articles on 'Abbasid history and the History of al Ṭabarī, among which are "The 'Ahl al Taqaddum'" and the Problem of the Constituency of the Abbasid Revolution in the Merv Oasis' (1996) and 'Manuscripts and editions of Bal'ami's *Tarjamah yi Tarikh i Tabari*' (1990).

FRED M. DONNER is Professor of Near Eastern History in the Oriental Institute and Department of Near Eastern Languages and Civilizations at the University of Chicago. He is the author of *The early Islamic conquests* (Princeton, 1981), *Narratives of Islamic origins* (Princeton, 1997) and *Muhammad and the believers: At the origins of Islam* (Cambridge, MA, 2010). He has published a translation of a section of al Ṭabarī's *History, The conquest of Arabia* (Albany, 1992), and numerous articles on early Islamic history.

List of contributors

TAYEB EL HIBRI is Associate Professor in the Department of Near Eastern Studies at the University of Massachusetts, Amherst. His book *Reinterpreting Islamic historiography: Harun al Rashid and the narrative of the Abbasid caliphate* (Cambridge, 1999) was awarded an Albert Hourani Book Award Honorable Mention at the 2000 Middle East Studies Association of North America Annual Meeting.

JOHN HALDON is Professor of History at Princeton University and a Senior Fellow at the Dumbarton Oaks Center for Byzantine Studies in Washington, DC. His publications include *Byzantium in the seventh century* (Cambridge, 1990), *Three treatises on Byzantine imperial military expeditions* (Vienna, 1990), *The state and the tributary mode of production* (London, 1993), *Warfare, state and society in Byzantium* (London, 1999), *Byzantium: A history* (Stroud, 2000) and *The Palgrave atlas of Byzantine history* (New York, 2006).

STEFAN HEIDEMANN is Hochschuldozent at the Institute for Languages and Cultures of the Middle East, Jena University. His publications include *Das Aleppiner Kalifat (AD 1261)* (Leiden, 1994) and *Die Renaissance der Städte* (Leiden, 2002). He has edited or co edited *Raqqa II: Die islamische Stadt* (Mainz, 2003), *Sylloge der Münzen des Kaukasus und Osteuropas im Orientalischen Münzkabinett Jena* (Wiesbaden, 2005) and *Islamische Numismatik in Deutschland* (Wiesbaden, 2000).

R. STEPHEN HUMPHREYS is Professor of History and Islamic Studies at the University of California, Santa Barbara. His previous books include *From Saladin to the Mongols* (Albany, 1977), *Islamic history: A framework for inquiry* (Princeton, 1991), *Between memory and desire: The Middle East in a troubled age* (Berkeley, 1999) and *Mu'awiya Ibn Abi Sufyan: From Arabia to empire* (Oxford, 2006), along with numerous articles and essays on the history of medieval Syria and Egypt, Arabic historiography, and a variety of other topics.

HUGH KENNEDY is Professor of Arabic at the School of Oriental and African Studies, University of London. He is the author of numerous books on Islamic history, including *The Prophet and the age of the caliphates* (London, 1986; new edn Harlow, 2004), *The court of the caliphs* (London, 2004) and *The great Arab conquests* (London, 2007).

ELLA LANDAU TASSERON is Professor at the Institute for Asian and African Studies at the Hebrew University. She translated and annotated al Ṭabarī's *Dhayl al mudhayyal, Biographies of companions and their successors* (Albany, 1998), and has also written on Islamic historiography, *ḥadith*, Arabian tribal society and Islamic warfare.

MICHAEL LECKER is Professor at the Institute of Asian and African Studies at the Hebrew University. His publications include *Jews and Arabs in pre and early Islamic Arabia* (Aldershot, 1998), *'The Constitution of Medina': Muhammad's first legal document* (Princeton, 2004) and *People, tribes and society in Arabia around the time of Muhammad* (Aldershot, 2005).

List of contributors

EDUARDO MANZANO MORENO is Research Professor at the Instituto de Historia of the Centro de Ciencias Humanas y Sociales (CSIC Madrid). He is the author of *Conquistadores, emires y califas: Los Omeyyas y la formación de al Andalus* (Barcelona, 2006), *Historia de las sociedades musulmanas en la Edad Media* (Madrid, 1993) and *La frontera de al Andalus en época de los Omeyyas* (Madrid, 1991).

MARCUS MILWRIGHT is Associate Professor of Islamic Art and Archaeology in the Department of History in Art at the University of Victoria, Canada. He is the author of *The fortress of the raven: Karak in the middle Islamic period (1100–1650)* (Leiden, 2008) and *An introduction to Islamic archaeology* (Edinburgh, forthcoming).

CHASE F. ROBINSON is Distinguished Professor of History and Provost of the Graduate Center, The City University of New York. He is the author of *Abd al Malik* (Oxford, 2005), *Islamic historiography* (Cambridge, 2003) and *Empire and elites after the Muslim conquest: The transformation of northern Mesopotamia* (Cambridge, 2000), amongst other edited volumes and articles on early Islamic history.

MARK WHITTO is University Lecturer in Byzantine Studies at the University of Oxford, and a Fellow of Corpus Christi College, Oxford. His publications on the history and archaeology of the Late Antique and medieval world include *The making of orthodox Byzantium, 600–1025* (Basingstoke, 1996), 'Recent research on the Late Antique city in Asia Minor: The second half of the 6th c. revisited' (2001) and 'Ruling the late Roman and early Byzantine city: A continuous history' (1990). He has carried out field work in Turkey and Jordan.

JOSEF WIESEHÖFER is Professor of Ancient History at the University of Kiel and director of its Department of Classics. His publications on early Persian history include *Das antike Persien von 550 v. Chr. bis 651 n. Chr.* (Zurich and Munich, 1994; 4th edn 2005, trans. as *Ancient Persia: From 550 BC to 650 AD* (London, 1996; 2nd edn 2001)), *Das frühe Persien* (3rd edn, Munich, 2006), (ed.) *Das Partherreich und seine Zeugnisse* *The Arsacid Empire: Sources and documentation* (Stuttgart, 1998), *Iranians, Greeks and Romans* (Paris, 2005) and (ed.), *Eran und Aniran: Studien zu den Beziehungen zwischen dem Sasanidenreich und der Mittelmeerwelt* (Stuttgart, 2006).

A note on transliteration and pronunciation

Since many of the languages used by Muslims are written in the Arabic or other non Latin scripts, these languages appear in transliteration. The transliteration of Arabic and Persian is based upon the conventions used by *The encyclopaedia of Islam*, second edition, with the following modifications. For the fifth letter of the Arabic alphabet (*jīm*), *j* is used (not *dj*), as in *jumla*. For the twenty first letter (*qāf*), *q* is used (not *k*), as in *qadī*. Digraphs such as *th*, *dh*, *gh*, *kh* and *sh* are not underlined. For terms and names in other languages, the individual chapter contributors employ systems of transliteration that are standard for those languages. Where there are well accepted Anglicised versions of proper nouns or terms (e.g. Baghdad, Mecca), these are used instead of strict transliterations.

As far as the pronunciation of Arabic is concerned, some letters can be represented by single English letters that are pronounced much as they are in English (*b*, *j*, *f*, etc.); one exception is *q*, which is a 'k' sound produced at the very back of the throat, and another is the 'r', which is the 'flap' of the Spanish 'r'. Others are represented by more than one letter. Some of these are straightforward (*th*, *sh*), but others are not (*kh* is pronounced like 'j' in Spanish, *gh* is similar to the uvular 'r' of most French speakers, and *dh* is 'th' of 'the', rather than of 'thing'). There are also pairs of letters that are distinguished by a dot placed underneath one of them: thus *t*, *s*, *d*, *z* and their 'emphatic' counterparts *ṭ*, *ṣ*, *ḍ*, and *ẓ*, and which give the surrounding vowels a thicker, duller sound (thus *s* 'sad', but *ṣ* 'sun'); *ẓ* may also be pronounced as *dh*.

The ' is the *hamza*, the glottal stop, as in the Cockney 'bu'er' ('butter'); the 'ayn, a voiced pharyngeal fricative that can be left unpronounced, which is what many non Arab speakers do when it occurs in Arabic loan words; and the *h* a voiceless pharyngeal fricative that can be pronounced as an 'h' in all positions, just as non Arabs do in Arabic loanwords. Doubled consonants are lengthened, as in the English 'hot tub'.

The vowels are written as *a*, *i*, and *u*, with *a*, *ī* and *u* signifying longer versions; thus *bit* and *beat*. *W* and *y* can function as either consonants or, when preceded by a short vowel, as part of a diphthong.

Persian uses the same alphabet as Arabic, with four extra letters: *p*, *ch*, *zh* (as in ‘pleasure’) and *g* (always hard, as in ‘get’).

A note on dating

The Islamic calendar is lunar, and divided into twelve months of twenty nine or thirty days each: Muḥarram, Šafar, Rabī‘ I, Rabī‘ II, Jumada I, Jumada II, Rajab, Sha‘ban, Ramaḍan (the month of the fast), Shawwal, Dhu al Qa‘da, and Dhu al Ḥijja (the month of the Pilgrimage). Years are numbered from the *hijra* (‘emigration’) of the Prophet Muḥammad from Mecca to Yathrib (Medina), conventionally dated to 16 July 622 of the Common (or Christian) Era; this dating is known as *hijrī*, and marked by ‘AH’. As the lunar year is normally eleven days shorter than the solar year, the Islamic months move in relation to the solar calendar, and *hijrī* years do not correspond consistently with Western ones; AH 1429, for example, both started and finished within 2008 CE (so indicated as ‘1429/2008’), but this is exceptional, and most overlap with two Common Era years, and so ‘460/1067f.’.

Chronology

224	Defeat of the Parthian king Artabanus V by Ardashīr I; Sasanian dynasty takes power in Iran
260	Shapur I's victory at Edessa; capture of the Roman emperor Valerian
284 301	Reign of Emperor Diocletian; Roman army is enlarged and administration reformed
298	'Peace of disgrace' concluded between Romans and Sasanians
306 37	Emperor Constantine I; conversion of the Roman empire to Christianity
363	Emperor Julian's Persian expedition
378	Catastrophic Roman defeat by the Goths at Adrianople
387	Partition of Armenia
410	Rome is sacked by the Goths, led by Alaric
439	Vandals conquer Carthage
484	Shah Fīruz is defeated by the Hepthalites
527 65	Reign of Justinian; administrative reforms and military victories
528 9	al Ḥarith ibn Jabala made supreme phylarch by Justinian
531 79	Reign of Shah Khusrau I; social, economic and administrative reforms undertaken
540	'Eternal peace' between Romans and Sasanians, agreed in 532, is broken by Khusrau
572	Sasanian advance into southern Arabia
c. 575	Birth of Muḥammad in Mecca
602	Assassination of the last Lakhmid ruler Nu'man III

603 28	Last great war between Romans and Sasanians, the latter occupying Syria and Egypt
610 41	Reign of Emperor Heraclius
c. 610	Muḥammad delivers first revelations in Mecca
1/ 622	The 'Emigration' (<i>hijra</i>) of Muḥammad and his followers from Mecca to Medina
628	The Sasanian shah Khusrau is murdered; civil war in Ctesiphon ensues
630	Emperor Heraclius restores True Cross to Jerusalem
11/ 632	Death of Muḥammad in Medina
11 13/ 632 4	Reign of first caliph, Abu Bakr; the 'wars of apostasy' break out
13 23/ 634 44	Reign of second caliph, 'Umar ibn al Khaṭṭab: conquest of north east Africa, the Fertile Crescent and the Iranian Plateau
23 35/ 644 56	Reign of third caliph, 'Uthman
31/ 651	Assassination of the last Sasanian king, Yazdegerd III, at Marw
35/ 656	First civil war (<i>fitna</i>) begins, triggered by the assassination of 'Uthman; the battle of the Camel
35 40/ 656 61	Reign of 'Alī ibn Abī Ṭalib, which ends with his assassination
41 60/ 661 80	Reign of the (Sufyanid) Umayyad Mu'awiya ibn Abī Sufyan
61/ 680	Killing of al Ḥusayn, the Prophet's grandson, at Karbala' by Umayyad forces
64 73/ 683 92	Second civil war: the Sufyanids fall, Ibn al Zubayr rules the caliphate from Mecca and the Marwanid Umayyads come to power
73 86/ 692 705	Reign of 'Abd al Malik ibn Marwan
79/ 698	Conquest of Carthage
86 96/ 705 15	Reign of al Walīd, first of four sons of 'Abd al Malik to rule; Qutayba ibn Muslim leads conquests in Transoxania and Central Asia
92/ 711	Ṭariq ibn Ziyad crosses the Strait of Gibraltar, and Iberia soon falls to Muslims
98 9/ 716 17	Failed siege of Constantinople

99 101/717 20	Reign of 'Umar II, later considered the fifth of the 'rightly guided' caliphs
101 2/720	Revolt of Yazīd ibn al Muhallab
104/723	Muslim campaigns beyond the Indus
106/724	Muslim defeat in Transoxania on the 'Day of Thirst'; Muslims now on defensive in the east
114/732	Muslim army defeated near Poitiers by Charles Martel
122/740	Berber revolt; Umayyad authority dissolves in North Africa and Spain; revolt led by Zayd ibn 'Alī, a grandson of al Ḥusayn
127 32/744 50	Reign of Marwan II, last Umayyad caliph
129/747	Abu Muslim leads the Hashimiyya in rebellion, conquering Marw in early 130/748
132/749	The 'Abbasid Abu al 'Abbas acclaimed as caliph in Kufa
132/750	Umayyad caliphate falls to 'Abbasid Hashimī armies; Marwan killed in Egypt
132 7/750 4	Umayyad counter revolts in Syria and al Jazīra
136 58/756 75	Reign of al Maṣṣur; Abu Muslim is murdered
137/754	Revolt of 'Abd Allah ibn 'Alī, 'Abbasid governor of Syria
145/762	Rebellion of the 'Alid Muḥammad, 'the Pure Soul'; construction of Baghdad begins
170 93/786 809	Reign of Harun al Rashīd
170 80/786 96	'Decade of the Barmakids'; vizieral family dominate 'Abbasid administration and culture
180 92/796 808	Harun al Rashīd makes al Raqqā his capital
193 8/809 13	Civil war between Harun's two sons, al Amīn and al Ma'mun; Baghdad besieged
198 218/813 33	Reign of al Ma'mun; large numbers of Turkish slave soldiers are introduced into the army from the 820s
206/821	Appointment of Ṭahir ibn al Ḥusayn as governor of Khurasan; beginning of Ṭahirid rule
218 27/833 42	Reign of al Mu'taṣim; caliphal court is moved to Samarra', where it remains until 892
218 37/833 52	The <i>miḥna</i> : the caliphs impose the doctrine of the 'createdness' of the Qur'an


232/847	Turkish commanders participate in council to decide caliphal succession
232 47/847 61	Reign of al Mutawakkil: intensive building in Samarra', struggles with the Turkish commanders
247/861	Al Mutawakkil is murdered in Samarra'
251/865	Civil war in Iraq between al Musta'in and al Mu'tazz
254/868	Ibn Tulun arrives in Egypt and begins to establish his rule there
255/869	Outbreak of Zanj revolt in southern Iraq
262/876	Ya'qub the Coppersmith is defeated near Baghdad
270/883	Defeat of the Zanj in the swamps of southern Iraq
295/908	Accession of al Muqtadir to the caliphate, followed by the revolt of Ibn al Mu'tazz
297/909	The Faṭimid 'Abd Allah the <i>mahdī</i> is declared caliph in North Africa
309/922	Execution of the mystic al Hallaj
317/930	The Qaramiṭa attack Mecca and seize the Black Stone
320/932	Death of al Muqtadir
323/935	Death of Mardavīj ibn Ziyar, warlord of northern Iran
324/936	Ibn Ra'iq becomes <i>amīr al umara'</i> in Baghdad
334/946	Aḥmad ibn Buya Mu'izz al Dawla enters Baghdad; end of the independent 'Abbasid caliphate
350/961	'Alī ibn Mazyad al Asadī establishes Mazyadid rule in Ḥilla and central Iraq
366/977	Sebüktegin seizes power in Ghazna
367 72/978 83	Rule of the Buyid 'Aḡud al Dawla in Iraq
380/990	al Ḥasan ibn Marwan establishes Marwanid rule in Mayyafariqīn and Amida
381 422/991 1031	Reign of al Qadir, resurgence of 'Abbasid authority
389/999	Ghaznavids secure power in Khurasan
420/1029	Issuing of the 'Qadirī creed' by the caliph al Qadir; Maḥmud of Ghazna takes Rayy and ends Buyid rule there
421/1030	Death of Maḥmud of Ghazna
440/1048	End of Buyid rule in Baghdad
442/1050	Death of Qirwash ibn Muqallad al 'Uqaylī

Abbreviations

BAR	British Archaeological Reports
BASOR	<i>Bulletin of the American Schools of Oriental Research</i>
BGA	Bibliotheca Geographorum Arabicorum
BSOAS	<i>Bulletin of the School of Oriental and African Studies</i>
CII	Corpus Inscriptionum Iranicarum
CSCO	Corpus Scriptorum Christianorum Orientalium
Elz	<i>Encyclopaedia of Islam</i> , 2nd edn, 12 vols., Leiden, 1960–2004
Elr	<i>Encyclopaedia Iranica</i> , London and Boston, 1982
IJMES	<i>International Journal of Middle East Studies</i>
JA	<i>Journal Asiatique</i>
JAOS	<i>Journal of the American Oriental Society</i>
JESHO	<i>Journal of the Economic and Social History of the Orient</i>
JNES	<i>Journal of Near Eastern Studies</i>
JRAS	<i>Journal of the Royal Asiatic Society</i>
JSAI	<i>Jerusalem Studies in Arabic and Islam</i>
JSS	<i>Journal of Semitic Studies</i>
MW	<i>Muslim World</i>
OrOcc	Oriens et Occidens
REI	<i>Revue des études islamiques</i>
RSO	<i>Rivista degli Studi Orientali</i>
SI	<i>Studia Islamica</i>
ZDMG	<i>Zeitschrift der Deutschen Morgenländischen Gesellschaft</i>




1. The physical geography of the Mediterranean and Near Eastern world




2. The political geography of the Mediterranean and Near Eastern world, c. 575




3. The expansion of Islam in the east



4. The expansion of Islam in the west



5. The 'Abbasid empire in c. 800



6. The Islamic world in c. 950



8. The Islamic east



9. Syria



10. Egypt



II. Spain and North Africa

Introduction

CHASE F. ROBINSON

The following story, which appears in the *History* of Abu Ja'far al Ṭabarī (d. 310/923), is one of many that describe how the 'Abbasid caliph Abu Ja'far al Maṣṣur (r. 136 58/754 75) chose the site for his new city of Baghdad. The event is said to have taken place in year 763 of the Common Era, some thirteen years after the revolution that brought the 'Abbasids to power.

It was reported on the authority of Muḥammad b. Ṣāliḥ b. al Naṭṭāḥ, on the authority of Muḥammad b. Jābir and his father, who said: When Abū Ja'far decided to build the city of Baghdad, he saw a monk, to whom he called out. When he responded, he asked him, 'Do you find in your books [a prediction] that a city will be built here?' 'Yes', said the monk, 'Miqlāṣ will build it.' Abū Ja'far exclaimed, 'I was called Miqlāṣ when I was young!', to which the monk said, 'Then you must be the one to build it!'

He [the narrator] then continued: Likewise, when Abū Ja'far decided to build the city of al Rāfiqa, which is in territory that once belonged to the Byzantines, the people of [the nearby city of] al Raqqa objected and resolved to fight him, saying, 'You will ruin our markets, take away our livelihoods and reduce our houses.' Abū Ja'far was determined to take them on, and wrote to a monk in the [nearby] monastery, asking: 'Do you know anything about a city that will be built here?' The monk replied, 'I have heard that a man called Miqlāṣ will build it,' so Abu Ja'far said, 'I am Miqlāṣ!' So he built it on the model of Baghdad, except for the walls, the iron gates and the single ditch.¹

The double anecdote, which sits near the middle of the chronological range of this first volume of the *New Cambridge history of Islam*, anticipates many of the themes and issues of this and succeeding volumes in the series, such as state (and city) building, the role of non Muslims in Muslim societies, the role

¹ I translate loosely from Abu Ja'far Muḥammad ibn Jarīr al Ṭabarī, *Ta'riḥ al rusul wa'l muluk*, ed. M. J. de Goeje et al., 15 vols. in 3 series (Leiden, 1879 1901), series III, p. 276.

of caliphs and dynastic politics. Three themes are especially significant, however, and these may profitably be put here in question form.

How do we know what we know of early Islam?

The alert reader will have noticed that while al Manṣūr's building plans are said to date from 763, the *History* in which we read of these plans was written by a historian who died in 923, about 160 years after the accounts he relates (I leave aside the question of our historian's informants, many of whom lived considerably earlier). The same reader might wonder if there was anything earlier to read, or if al Ṭabarī's description of Baghdad and al Rafīqa can be corroborated by archaeological evidence. The unfortunate fact is that although we do happen to possess some excellent archaeology for al Rafīqa (which lay on the Euphrates in present day Syria),² one cannot do better than al Ṭabarī for the founding of Baghdad; no earlier source has more to say about the foundation of this or any other early Islamic city. Meanwhile, we have no archaeological evidence from Baghdad with which to confirm his description: civil wars, economic decline, Mongols and modernity have conspired to obliterate and seal eighth and ninth century layers of the settlement.

Does this matter? After all, one might reasonably base a history of the French Revolution of 1789 upon Georges Lefebvre's *The coming of the French Revolution*, which was published in 1949. The difficulty for us is caused not merely by the passing of time. It lies more in questions of method, purpose, perspective and scope. For all that he was a great historian, al Ṭabarī was no Georges Lefebvre; he was a great historian by the standards of the day, which, being considerably lower than the *Annales* school of post war France, made ample room for myths, legends, stereotypes, distortions and polemics. It is hard to believe that al Manṣūr conversed with a local monk about his plans for Baghdad, and this for several reasons, one of which is that other Islamic cities are outfitted with similar foundation stories. Surely the nature and date of our sources *must* matter; as the editor of an earlier *Cambridge History* put it: 'It is by solidity of criticism more than by the plenitude of erudition, that the study of history strengthens, and straightens, and extends the mind.' 'For the critic', continued Lord Acton, 'is one who, when he lights on an interesting statement, begins by suspecting it.'³

2 On al Raqqā and al Rafīqa, see S. Heidemann and A. Becker (eds.), *Raqqā II: Die islamische Stadt* (Mainz am Rhein, 2003).

3 J. E. D. A. (Lord) Acton, *Lectures on modern history*, ed. J. N. Figgis and R. V. Laurence (London, 1906), p. 15.

And suspicious we have become. This – the realisation that what we know about early Islam is less certain than what we thought we knew, and that writing history in this period and region requires altogether more sophisticated and resourceful approaches – is one of a handful of notable advances made in Islamic studies since the original *Cambridge history of Islam* was published in 1970. Now it is true that Islamic studies has long tolerated and occasionally cultivated a critical spirit; Ignaz Goldziher, arguably the greatest Islamicist of all, had published his revolutionarily critical work on early Islam some five years before Lord Acton's Inaugural Lecture.⁴ The two scholars were breathing the same air. Still, these and other critical approaches to Islamic history were marginalised for much of the twentieth century, giving way to a less subtle and more credulous positivism; to Acton's dismay, 'the weighing of testimony' was *not* held 'more meritorious than the potential discovery of new matter'.⁵ It was only in the last quarter of that century that things changed, as Orientalist positivism fell into disrepute, and historical criticism was put at the heart of understanding early Islam. To some extent, this more critical attitude towards our written source reflects broader academic trends in the 1960s and early 1970s, when adjacent fields, such as the academic study of Rabbinic Judaism, raised their standards of evidence. This said, Orientalism in general and Islamic studies in particular have been relatively insular fields, and the revisionism developed from within, especially through the publication of a small handful of books, which all appeared between 1973 and 1980, and, to lesser and greater degrees, all threw into question the very possibility of reconstructing the first two centuries of Islamic history.⁶ Although relatively tame by the standards of more highly developed fields (such as scholarship on the Hebrew Bible and Christian origins), these books sparked off a great deal of controversy, and although their approaches and conclusions remain controversial, it can scarcely be doubted that they served to rouse Islamic studies from something of a post war slumber.

4 I. Goldziher, *Muhammedanische Studien* (Halle, 1889–90), trans. S. M. Stern and C. R. Barber as *Muslim Studies* (London, 1967–71).

5 Acton, *Lectures*, p. 16.

6 A. Noth, *Quellenkritische Studien zu Themen, Formen und Tendenzen frühislamischer Geschichtsüberlieferung* (Bonn, 1973), trans., rev. and expanded by A. Noth and L. I. Conrad as *The early Arabic historical tradition: A source critical study* (Princeton, 1994); P. Crone and M. Cook, *Hagarism: The making of the Islamic world* (Cambridge, 1977); J. Wansbrough, *Quranic studies: Sources and methods of scriptural interpretation* (Oxford, 1977); J. Wansbrough, *The sectarian milieu: Content and composition of Islamic salvation history* (Oxford, 1978); P. Crone, *Slaves on horses: The evolution of the Islamic polity* (Cambridge, 1980); see also P. Crone, *Meccan trade and the rise of Islam* (Princeton, 1987; repr. Piscataway, NJ, 2004).

So if it was once good enough to offer cursory comments on the principal genres of the Islamic historical tradition (as did the original *Cambridge history of Islam*, whose sedate and authoritative tone gives little indication that the post war consensus was about to fracture), it is no longer good enough. This is why the reader of this volume will find not only a very different approach to the first two centuries of Islam, but no fewer than three chapters (15, 16 and 17) devoted to a myriad of problems of evidence and interpretation, some of which are solved, but many of which remain very controversial. Few if any of the controversies will be settled here; the volume editor sees it as his responsibility to ensure only that the volume reflects the state of the field in the early twenty first century. Although this means that gaps in our knowledge have to be filled by further research and that scholars continue to disagree on both major and minor matters, the reader can still take solace in knowing that the field of early Islamic history is as exciting as any other. Recorded history scarcely knows a period more creative of religious, cultural and political traditions than the seventh, eighth and ninth centuries. The editor will regard this volume a success if its readers come to share some of this excitement.

What, in broad strokes, is the quality of our evidence for the period covered by this volume? It is mixed. On the one hand, sixth century Byzantium enjoys some respectable coverage, thanks to a handful of high quality and contemporary histories that cover war and politics relatively well, including events in the east, especially the Byzantine Persian wars that dominate the century. Written, as they generally were, in Constantinople, these Greek sources are complemented by another handful of works, these written by the Christians of Syria and Iraq in Syriac, which provide a local perspective on the *histoire événementielle*. There are, of course, problems of interpretation and perspective, but the fact remains that at least some politics and warfare can be described in some detail.⁷ Meanwhile, long term processes of economic exchange and settlement, which were conventionally ignored by historians of earlier generations, can be reconstructed to some degree by the numismatic record and the burgeoning field of Mediterranean archaeology. There are real gaps, of course, but all this contrasts sharply with the situation further east. While late Roman and early Byzantine studies prosper, bringing new texts to bear on old problems and new interpretations and methods to old texts,

7 For an example of some detailed coverage of war, see G. Greatrex, *Rome and Persia at war*, 502–535, ARCA Classical and Medieval Texts, Papers and Monographs 37 (Leeds, 1998); for some sense of the archaeology on offer, see C. Wickham, *Framing the early Middle Ages: Europe and the Mediterranean, 400–800* (Oxford, 2005).

Sasanian studies do not, at least aside from the relatively narrow sub fields of sigillography and numismatics. Very little indigenous historical writing survives; and this, combined with the fact that archaeology there lags considerably behind its Mediterranean analogue, severely handicaps all attempts to write detailed Sasanian history. (For all that it has contributed to a boom in the academic study of Islam, the Iranian Revolution of 1979 has done little to advance the study of pre Islamic Iran.) It is an unfortunate and remarkable thing that we must rely so heavily upon ninth and tenth century Muslim authors writing in Arabic to provide us with a narrative history of the sixth and seventh century Sasanian state, in which Middle Persian and Aramaic were the principal literary and administrative languages, and Zoroastrianism and Nestorian Christianity its privileged religious traditions. Not entirely dissimilar things can be said of pre Islamic Arabia, which produced virtually no narrative worthy of the name, and which is currently even more innocent of serious archaeology, especially in the west.⁸ Although the epigraphic evidence is now accumulating, what we know of the pre Islamic Hijaz derives in very large measure from what later Muslims, who were usually writing at something of a chronological, geographical and cultural distance, believed, and chose to have their readers believe.

If the sixth century historiographic state of affairs is mixed, that of the seventh century is worse: the flow of contemporaneous sources slows to a trickle, and even the Byzantine historical tradition falters.⁹ The Arabic sources pose as many questions as they answer, and although the attack made in the 1970s and 1980s against their reliability has been met with resistance in some quarters,¹⁰ a consensus about how to use them for reconstructing detailed history remains remote. What this means, then, is that the period most productive of spectacular history – of prophecy and revelation within Arabia, and sweeping conquest outside it, of state and empire formation in Syria – proved spectacularly unproductive of durable historiography. Lacking primary sources from within the Islamic tradition, we must perilously rely either on non Islamic testimony, which, though earlier, is frequently given to problems of perspective and bias,¹¹ or on

⁸ Whereas things are looking up in the east: see D. Kennet, 'The decline of eastern Arabia in the Sasanian period', *Arabian Archaeology and Epigraphy*, 18 (2007).

⁹ See, however, J. F. Haldon, *Byzantium in the seventh century: The transformation of a culture*, rev. edn (Cambridge, 1997), pp. xxiff.

¹⁰ See below, chapter 15.

¹¹ See R. Hoyland, *Seeing Islam as others saw it: A survey and evaluation of Christian, Jewish and Zoroastrian writings on early Islam* (Princeton, 1997).

relatively late Islamic ones, which rely on a mix of accounts, some orally transmitted, others textually transmitted, some both. Al Ṭabarī's history is the most important of these. It can reasonably be called one of the greatest monuments of pre modern historiography in any language, and it is our best single source for the rise and disintegration of the unified state. And because the early history that it narrates was both deeply controversial and monumentally significant – what could be of greater moment than Muḥammad's prophecy and the political events it set into motion? – it freely mixes prescription and description, polemics and facts, myth, legend and stereotype. Put more broadly, in writing his massive and universal *History*, al Ṭabarī was both recording and interpreting the rise and disintegration of the unified state. The 'Abbasid family continued to supply caliphs during and for centuries after al Ṭabarī's day, but they were now usually ineffectual, and within a generation of his death, Baghdad would be occupied by Iranian mercenaries. Baghdad survived, but al Maṣṣur's foundation had been abandoned, and much of the city lay in ruins after two civil wars (al Rafīqa had long been eclipsed by al Raqqā). Filled as it is with caliphal *Kaiserkritik*, al Ṭabarī's work can be read as both triumphalist anthem and nostalgic dirge.

For the history of the ninth, tenth and eleventh centuries, our evidence improves. There are several reasons why. For one thing, the range and quality of the written sources improve: we now have a variety of genres of historical writing, in addition to belles lettres and poetry, and the yawning chronological, cultural and political gap between event and record narrows; much history is either contemporary or nearly so, and some of it was written by those in a position to know this history well, such as administrators and bureaucrats. For another thing, official and unofficial documents begin to survive in some numbers, even if it is true that many are embedded in historical and literary texts. Finally, the lean material evidence of the seventh and eighth centuries gives way to a somewhat more generous spread of art historical and archaeological sources. For example, much of the urban fabric of Samarra', which served as capital during the period 221 79/836–93, still survives; although Faṭimid Cairo may be altogether harder to discern than Mamluk Cairo, some of it is still there. 'Abbasid Baghdad is not.

The quality of our evidence thus improves with the passing of time, and the tenth century is far less obscure than the seventh. But what is the historian to make of this evidence? What model is he to use? Is disinterested, 'scientific' history even possible? To judge from the vigorous anti Orientalist literature

that appeared in the 1960s and flourished in the 1970s,¹² one might have thought the ground prepared for repudiating altogether the project of reconstructing the past. In the event, the study of Islamic history has remained relatively conservative, with positivism of a modified sort continuing to enjoy pride of place. This takes us to a second important change of perspective.

What is Islamic history, and how does Islam relate to Late Antiquity?

Al Manṣūr designed and built his city as caliph (Ar. *khalīfa*), God's 'deputy' or 'representative', who exercised His authority on earth. Just as God's authority was indivisible, so in al Manṣūr's day was the caliph's: he possessed both spiritual and temporal authority, which in practice meant everything from leading the prayers to leading his armies into battle. To judge from the evidence, he was considered, *inter alia*, 'God's rope' and the pivot around which the world moved, an idea that was given architectural expression in the very design of his city, a design which would have been so familiar to al Ṭabarī's reader that a simple allusion would do: the 'model of Baghdad' meant a circular city plan. *Madīnat al Manṣūr* (al Manṣūr's city) thus consisted of an elaborately arcaded ring, which, perforated by four gates leading to the principal cities of the empire in the north west, south west, south east and north east, housed the state's administrative and bureaucratic agencies, and at its very centre stood the congregational mosque and caliphal palace. God's single and universal rule on earth, delegated to His caliphs, was thus given symbolic form.¹³

Much of this first volume can be construed as an attempt to understand the forces that first created and later dissolved this enormously powerful and persuasive idea. In ways made abundantly clear by the Islamic historical tradition, its inspiration lay in part in the career and ideas of Muḥammad himself, who operated in a cultural milieu (north west Arabia) that was relatively naive of the main currents of Late Antiquity; it was he, the tradition maintains, who put in place the patterns by which his successors (the caliphs) would (or should) model themselves. There is much truth to this: the early

12 See, for example, E. Said, *Orientalism* (New York, 1978); A. L. Macfie, *Orientalism: A reader* (New York, 2000); and R. Irwin, *For lust of knowing: The Orientalists and their enemies* (London, 2006).

13 For the pre Islamic antecedents, see C. Wendell, 'Baghdad: Imago Mundi and other foundation lore', *IJMES*, 2 (1971).

caliphate can hardly be understood without reference to Muḥammad's legacy of prophecy, social engineering and conquest, not to mention Arabian styles of politics. But it is also the case that in attenuated and largely untraceable ways, some of the creative forces for al Manṣur's idea lay much further afield, such as in fourth century Byzantium, when Constantine and his successors married monotheism to empire building; this was a vision that was refined during the fifth, sixth and seventh centuries, in part as a result of internal divisions and in part as a result of Byzantium's rivalry with the Sasanian state of Iraq and Iran, where Zoroastrianism generally prevailed. Such as it was, the Sasanians' embrace of monotheism came later and remained very mixed, but they, too, eventually had a formative influence upon the Islamic imperial tradition: as early as the first decades of the eighth century, Iraqi styles had filtered into Syria, and the floodgates opened after the 'Abbasid revolution, when the seat of the caliphate was moved from Syria to Iraq. In fact, al Manṣur's Round City was an easy ride from the last Sasanian capital of Ctesiphon (al Mada'in), and its circular design harks back to Sasanian city plans. Umayyad rule in formerly Byzantine Syria, 'Abbasid rule in formerly Sasanian Iraq – the cultural ambidexterity that resulted is one of the most striking features of the early Islamic tradition.

Early Islamic history, it follows, cannot be properly understood unless it is made part of the religious and political world of the Late Antique Near East. When al Manṣur is given to ask local monks for their views on his building plans, we are reminded of precisely that: Muslims and non Muslims lived in the same world, their experiences intersecting and their traditions intertwining. (Christian books contain prophecies that Muslims fulfil, the legendary 'Miqlaṣ' of al Ṭabarī's account probably alluding to an eighth century Manichaean figure from the area near Baghdad to be.) This idea that although early Muslims did break away from the pre Islamic world, they also accelerated patterns of change already in process within it – is the second of the field's notable advances of the last thirty five years. Important exceptions aside,¹⁴ the study of Late Antiquity remains fairly closely related to the study of late Roman and early Byzantine Christian societies (especially their

¹⁴ In addition to P. Brown, *The world of Late Antiquity* (London, 1971), see S. A. Harvey, *Asceticism and society in crisis: John of Ephesus and the Lives of the Eastern Saints* (Berkeley, 1990); G. Fowden, *Empire to commonwealth: Consequences of monotheism in Late Antiquity* (Princeton, 1994); E. K. Fowden, *The barbarian plain: Saint Sergius between Rome and Iran* (Berkeley and Los Angeles, 1999); A. H. Becker, *Fear of God and the beginning of wisdom: The School of Nisibis and the development of scholastic culture in Late Antique Mesopotamia* (Philadelphia, 2006); and J. Walker, *The legend of Mar Qardagh: Narrative and Christian heroism in Late Antique Iraq* (Berkeley and Los Angeles, 2006).

cities),¹⁵ so whereas the transition from Byzantine to Islamic rule in Egypt and Syria Palestine is becoming considerably clearer,¹⁶ that of the lands east of the Euphrates remains more poorly understood. This said, that early Islam 'belongs' to Late Antiquity has become nearly axiomatic among serious scholars.

Here, then, there is another contrast with the original *Cambridge history of Islam*, which was conceived and executed shortly before 'Late Antiquity' had been framed as a distinct cultural and political phase of history.¹⁷ Although earlier scholarship was deeply familiar with the Byzantine and Sasanian (or, in geographical terms, the Syrian and Iraqi/Iranian) influences that would shape Islamic history, an implicit 'Islamic exceptionalism' prevailed, and the volume accordingly began with a single chapter on 'pre Islamic Arabia'. The *New Cambridge history of Islam* reflects a generation's progress. Just as the concluding volume of the *Cambridge ancient history* integrates the rise of Islam into a more inclusive vision of historical change,¹⁸ so this volume begins with four chapters that lay out the cultural and political history of Late Antiquity in detail; subsequent chapters, which address how Islamic history was made in the empire's provinces, also give some sense of the diverse cultural geography that early Muslims walked. As the birthplace of Muḥammad and Islam, western Arabia naturally deserves special treatment, and so it has it in part I. But it has become increasingly clear that western Arabia was less sheltered from the prevailing winds of Late Antiquity than previously thought: Muḥammad was part of Heraclius' and Yazdegerd's world. What is more, as soon as the conquests had decelerated, Muslims would abandon Arabia as their political capital for Syria and Iraq, and the articulation of much early Islamic doctrine and ritual is a phenomenon of the Fertile Crescent rather than the Arabian Peninsula.

Writing early Islamic history thus means in some measure tracking one distinctive monotheist trajectory among several others (Frankish Papal, Byzantine and Eastern Christian) in western Eurasia.¹⁹ What does this mean

15 On models of 'transformation', see J. H. W. G. Liebeschuetz, 'Late Antiquity and the concept of decline', *Nottingham Medieval Studies*, 45 (2001); see also R. Martin, 'Qu'est ce que l'antiquité tardive?' in R. Chevallier (ed.), *Aïôn: Le temps chez les romains* (Paris, 1976).

16 And this in no small measure due to a series of collections and monographs published as *Studies in Late Antiquity and Early Islam* (Princeton, 1992).

17 Brown, *The world of Late Antiquity*; the most recent conspectus is G. W. Bowersock, P. Brown and O. Grabar (eds.), *Late Antiquity: A guide to the post classical world* (Cambridge, MA, 1999).

18 A. Cameron, B. Ward Perkins and M. Whitby (eds.), *The Cambridge ancient history*, vol. XIV: *Late Antiquity: Empire and successors, AD 425–600* (Cambridge, 2000), chap. 22.

19 See J. Herrin, *The formation of Christendom* (Princeton, 1987).

for this volume? One thing should be made clear: 'Islamic history' is much more than the history of a religious tradition, and those religious ideas, practices or institutions that were without clear and important social or political dimensions will figure here only marginally. Put another way, understanding the development of Muslim societies at least in part turns on an appreciation for the *Sunnī*–*Shī'ite* divide and how it came about, but not on a detailed understanding of how *Shī'ite* law or ritual differs from *Sunnī* analogues, much less on precisely how Twelver *Shī'a* differ from *Isma'īlī Shī'a* in those matters. The religious and cultural traditions that took root under Islamic rule require separate study, and so they are discussed in volume 5. For the purposes of this volume, Islamic history is the social, religious and cultural history that Muslims made, chiefly (but not exclusively) as rulers of what remained throughout almost all of this early period a predominantly non-Muslim world. As chapters in a subsequent volume make clear,²⁰ conversion is a poorly understood process, but it seems that Muslims remained in the numerical minority in many if not most of the empire's lands through the ninth century. Early Muslims were political imperialists, but only seldom religious missionaries.

Of course calling the history that Muslims made 'Islamic history' is not to suggest that their history was necessarily any less conditioned by environmental, economic, social or military factors than the history made by non-Muslims. It clearly was conditioned by these variables, and the contributions that follow will frequently measure them, at least as far as they can be measured; one can scarcely understand many of the problems of empire building in south west Asia without understanding its geography and topography. That is why the geography of the southern and eastern Mediterranean and Middle Eastern lands is carefully described in chapter 1. Nor is it to say that Muslims were necessarily any more committed to religious ideas than were contemporaneous Jews, Christians or Zoroastrians, to name only the leading traditions; indeed, many Muslim rulers were frequently taken to task by their opponents and critics for having failed to discharge fully their religious obligations, whatever these may have been. But it certainly *is* to say that Muslims understood themselves to have made history in exclusively religious terms. This is not simply because religious systems in Late Antiquity were generally as hegemonic as bourgeois liberalism and market capitalism currently are in the developed West, but because this value was given compelling paradigmatic authority in the eighth and ninth century construction of the

²⁰ See volume 3, chapter 15 (Bulliet) and volume 4, chapter 5 (Wasserstein).

Prophet's experience: the model of Muḥammad's prophecy and community not only gave birth to the conquest movements that eventually overran much of the Near East, but also shape to the polity that would rule it. Christianity was born on the margins of an empire, which it colonised only fitfully; in Islam, belief and empire fused in quick succession.

How did Muslims of this period build states and empires?

The Abu Ja'far al Manṣur of our account was the second caliph of the 'Abbasid family, which, after the Ottomans, was the longest lived major ruling dynasty of the Islamic world. Having come to power by overthrowing the Umayyads in 749–750 CE, the 'Abbasids would provide an unbroken succession of caliphs until 1258, when the last was executed during the Mongol sack of Baghdad – some 500 years of dynastic rule, which is an impressive achievement by European (if not Japanese) standards. The 'Abbasids' success in keeping their dynastic rule intact should not be confused with success in keeping their empire together, however. Already by the time of al Ṭabarī, who died during the reign of al Muqtadir (908–32), al Manṣur's Round City was in near ruins (the historian himself lived in one of its extramural quarters), and the unified state as envisioned by late Umayyads and early 'Abbasids was a distant memory. If al Ṭabarī had travelled in the year 900 CE from his home in Baghdad to the furthest western reach of the Islamic world (present day Morocco), he would have left the area under direct 'Abbasid control in a matter of days, and travelled through regions ruled by no fewer than four more or less independent dynasties, the Ṭulunids, Aghlabids, Rustamids and Idrīsids.

The main trajectory of early Islamic history therefore follows two successive phases in politics and society. The first is charted here in chapters 5, 6 and 7, and the second in chapters 8 and 9. Since these processes transcended dynastic change, so do our chapters; we thus break from the dynastic and implicitly ethnic organisation of the original *Cambridge history of Islam*, which directly and indirectly reflected nineteenth century nationalist narratives as well as the conventional narratives of the tradition itself. And since regional variation in economic, social and political history was considerable, Arabia, the Islamic east (greater Iran), Syria, Egypt and the Iberian Peninsula and North Africa are each treated in separate chapters in part III. This – a clearer sense of regional differentiation that characterises Islamic history – is a third area of research that has greatly advanced since the publication of the original

Cambridge history of Islam.²¹ So while part II can be said to chart Islamic history from the viewpoint of the caliphs, part III describes it from the provincials' points of view.

The first phase of Islamic history is the rise and consolidation of a unitary state from its murky origins in the post conquest polity of the mid seventh century to its eighth century transformation under the Umayyads and early 'Abbasids into the last and perhaps greatest land based, bureaucratic empire of Antiquity. By the late seventh century, Muslim rule extended as far west as present day Tunisia, as far north as the Syrian Turkish border and as far east as Turkmenistan, and by the early eighth, it had stretched into Spain, Transoxania and the Sind valley in present day Pakistan. The whole fell under the notional sovereignty of the Arab Muslim caliph and those delegated by him, the caliph ruling initially from Arabia, then peripatetically in Syria, and then spectacularly in the great Iraqi cities of Baghdad (at this point perhaps the world's largest) and Samarra'. What resulted was not merely a robust political order, but a hugely creative cultural moment. Empire building unleashed several processes, particularly a measure of political, social and economic integration, which resulted from a military administrative system that siphoned rural surpluses into large cities that possessed both state and mercantile elites; complemented by profits from international trade carried across the waves of the Indian Ocean and the steppes of Central Asia, this led to the production of high culture on a massive scale. Baghdad was not only one of the world's largest cities, but one of its most literate and learned ones.

I shall leave the difficult task of explaining a process of empire building as complex as this to the appropriate chapters; the enormous cultural achievements are surveyed in volume 5. Here it is enough to identify two factors that explain the process. The first was the resilience and resourcefulness of the ruling elite, which drew upon not only its own evolving and adaptive ideology of rule, but also upon indigenous traditions of state building that had survived the dislocations of the seventh century conquests. The second – and one that is

21 For examples from the period covered by this volume, see R. Bulliet, *The patricians of Nishapur: A study in medieval Islamic social history* (Cambridge, MA, 1972); E. Daniel, *The political and social history of Khurasan under Abbasid rule, 747–820* (Minneapolis, 1979); M. Morony, *Iraq after the Muslim conquest* (Princeton, 1984); M. Gil, *A history of Palestine, 634–1099* (Cambridge, 1992); R. Bulliet, *Islam: The view from the edge* (New York, 1994); P. Chalmeta, *Invasión e islamización: La sumisión de Hispania y la formación de al Andalus* (Madrid, 1994); C. F. Robinson, *Empire and elites after the Muslim conquest: The transformation of northern Mesopotamia* (Cambridge, 2000); P. Cobb, *White banners: Contention in 'Abbasid Syria, 750–880* (Albany, 2001); E. Manzano Moreno, *Conquistadores, emires y califas: Los omeyas y la formación de al Andalus* (Barcelona, 2006).

altogether more difficult to measure was the economy of the eastern Mediterranean, Fertile Crescent and Persian Gulf. Here, too, the contributors can profitably draw from recent advances in our understanding of the material culture of the seventh, eighth and ninth centuries, which decisively reject earlier views that had made agricultural decline and Islamic rule nearly synonymous. Matters are complicated by differing regional profiles and inconclusive evidence, but we now know enough to say that far from ending the economic boom of the eastern Mediterranean, in at least some areas early Islamic rule can be associated to some degree with continuing (and perhaps even increasing) patterns of trade and settlement. The material evidence being so important and generally so inaccessible, it is discussed in a separate chapter (17).

The second phase is the disintegration of this unified state, which begins in the middle of the ninth century and accelerates during the tenth. For reasons already explained, our evidence is better for this period, although much remains very unclear; here, too, economy seems to play a dynamic (and perhaps even dialectic) role with elite politics, as do cultural factors, such as the ninth century militarisation of politics. On the other hand, explaining this direction of change is somewhat easier on the historian, since, put in terms of the *longue durée* imposed by geography and pre modern technology, it may be understood as the natural reversion away from the extraordinarily resource intensive work of state building and state maintaining across huge distances especially assembling and feeding large armies, along with training and paying the legions of bureaucrats needed to raise, measure and distribute the taxes required to maintain the army and towards regionalism and some measure of particularism. The Roman and early Byzantine empires had the benefit of the Mediterranean Sea, across which men and cargoes could be moved relatively cheaply and quickly; Baghdad certainly benefited from its position on the Tigris, while Basra served as an entrepôt for goods going to and from the Indian Ocean and beyond, but the empire as a whole was too far flung and too geographically heterogeneous to remain whole in the long term.

The late ninth and tenth century disintegration of the unified state should not be confused with dissolution of a political order; nor should it be thought that high culture suffered as a result. The pattern of states and polities that emerged in the tenth century and stabilised in the eleventh is sometimes described as a commonwealth of more or less independent dynasties that shared the use of Arabic (or an Arabised language, such as Persian),²²

²² My use of the term 'commonwealth' is altogether different from Fowden's above (note 14).

a repertoire of political thought that centred on the ruling offices of imamate (in the Shī'ite cases) and caliphate (in the Sunnī ones), patterns of military recruitment (notably the employment of non Muslims of servile origins), and a commitment to the ordering of religious life, especially through the crystallisation of schools of law, the patronage of religious institutions and, in time, the Sufi brotherhoods. Put another way, if a degree of regionalism emerges in the tenth century, it was a regionalism of a particular sort, since disintegration came only after processes of conversion in particular and acculturation in general were already well advanced. To indulge in some counterfactual history: had the state fragmented after the first civil war (Ar. *fitna*) of the 650s, the second civil war of the 680s or perhaps even after the 'Abbasid revolution, one presumes that the result would have been some sort of return to the *status quo ante*: a Christian or Christianising world that remained politically and in some measure culturally divided by frontiers that lay along the Tigris and Euphrates rivers. As it happened, disintegration came some 250 years after that first civil war, by which time Arabic had established itself as the prestige language of culture and administration, and although Islam may not have yet been the majority's faith, it had long monopolised the language of politics. (Even well before the turn of the tenth century, movements of rebellion, revolution and secession had been almost invariably expressed and understood in exclusively Islamic terms – even among non Arabs, Islam provided the repertoire of political action – and movements to revive pre-Islamic religious are conspicuously rare.)

So had al Ṭabarī made his journey from Baghdad to Idrīsīd Morocco, he would have crossed what amounts to political frontiers, but throughout his travels he would have been at home culturally. The idea of commonwealth should not be taken to mean that these so called 'successor' states lived in peaceful and harmonious synchrony or symbiosis. Far from it, at least at times; dynasts were always Muslim and usually Sunnī, but their ambitions differed, sometimes even radically, from one to the next, some imperial in design, others nothing more than home rulers. Much depended on distance from Baghdad. Moreover, the tenth century rise of the Faṭīmid Isma'īlīs in North Africa and Egypt, which can be figured as the last large scale revolutionary movement of early Islam, challenged ideologically and militarily the Sunnī Twelver Shī'ite coalition of commanders, caliphs and learned men (the '*ulama*') that was taking hold in Iraq and the East. In the event, however, the Faṭīmids failed to dislodge the coalition of Easterners: Baghdad survived, the quietist Imamī Shī'ism that it patronised would flourish, and charismatic Isma'īlism, routinised in the Egyptian state, never gained much of a foothold

in the central Islamic lands. Aside from the periphery (especially in North Africa, along the Caspian coast and in Yemen), the future lay with Sunnī states of varying size and ambition, legitimised by history, caliphs, the law and, finally, the patronage of high culture. Although the political and economic integration of early Islam is often characterised as a ‘golden age’, it is incontrovertible that much of what we now reckon to be the greatest achievements of pre modern Islamic learning in literature, art, the exact and inexact sciences were produced in this subsequent period. For all that there was a measure of economic decline in the east, the tenth and eleventh centuries were not about decline, but rather about a rebalancing of political life after a relatively short and hugely spectacular experiment in empire building, and a flourishing of cultural and intellectual life in a polyfocal world of competitive courts and assertive local elites.

PART I

★

THE LATE ANTIQUE CONTEXT

The resources of Late Antiquity

JOHN HALDON

The physical and strategic environment

Landscape

The late ancient world in the lands that were to be conquered by the first Muslim armies included a number of disparate regions, each offering a particular environment: Asia Minor or Anatolia, very roughly modern Turkey; the Levant or Middle Eastern regions down to and including Egypt; Mesopotamia and the Iranian plateau to the east; North Africa, from Egypt westwards to the Atlantic; and the Balkans.¹ The Mediterranean and Black Seas united the westernmost of these very different regions, while riverine systems on the one hand and plateaux and desert on the other served both to differentiate and to connect those in the east. Climate determined the patterns of agricultural and pastoral exploitation within these zones, but it also constrained and determined in many respects the nature of state and private surplus extracting activities.

The limited but fertile agricultural lands of Palestine and western Syria have always been relatively wealthy, in contrast to the more mountainous lands to the north and the deserts to the south and east. Greater Syria, including Palestine and the Lebanon, incorporates a number of very different landscapes, the terrain alternating from rugged highlands, through the fertile plains of northern Syria or central Palestine, the hilly uplands around Jerusalem to the desert steppe of central Syria. These landscapes had stimulated the development of very different communities, and the artificial unity imposed by the Roman state and, later, the early caliphate, should not disguise these stark contrasts. South of Palestine lay the deserts of the Sinai peninsula, leading then into the fertile Nile Valley and Delta regions – an area of fundamentally different

¹ Further literature on this section can be found in the chapter bibliography. I am especially grateful to Patricia Crone, Don Whitcomb, Jairus Banaji and Michael Morony for valuable criticism, comments and suggestions; any weaknesses or gaps in the argument are, of course, the author's responsibility alone.

character, heavily dependent on the annual flooding of the great river and the irrigation agriculture which it supported. Westwards from Egypt stretched the provinces of North Africa – desert through the eastern sector of Cyrenaica and Tripolitania in modern Libya, with very limited fertile coastal stretches and inland plateaux. These graduate into the coastal plains of Tunisia and modern Algeria, delineated by the plateaux and sandy desert regions in the south east, including the al Jifāra plain (and beyond them, the great desert), by the Aurès range in the centre, and the Saharan Atlas.

The Arabian Peninsula was and is marked out by the contrast between the relatively fertile and more densely settled coastal regions of the south (Yemen) and east (Baḥrayn), on the one hand, and the vast empty centre and north, traversed by the nomadic Bedouin and with no major urban centres and, with the exception of a relatively dense group of oases in the central region (north and south of modern Riyadh), relatively few oasis or valley settlements, on the other. The oasis town of Medina was a partial exception, situated on the western edge of the interior and on the so called ‘spice route’ from the southern port of Aden and other coastal settlements further east. Mecca – frequently assumed to have been on the same route – was in fact some 100 miles off to the east, a point which raises some difficulties for traditional assumptions about the origins of Islam and the merchant activities of the Quraysh.² The deserts were not entirely devoid of habitation – in the northern Ḥijāz a number of fertile oases offered possibilities, where settlements such as Fadak, Taymā, Wādī al Qurā, al Khaybar and Dedan (mod. al ‘Ola) flourished and formed points in a peninsular network of local and long distance commerce. But relative to Iraq, Syria and Egypt, the Arabian Peninsula remained a marginal zone, impoverished and politically unstable, during the fifth, sixth and early seventh centuries partly, of course, a reflection of the frequent interventions of the neighbouring powers.

To the east of Syria the desert separates the fertile and semi fertile zone of greater Syria from Iraq or Mesopotamia, the land between the rivers, historically one of the great centres of early settled agriculture and urban development. The wealth of the Sasanian empire depended largely on the agriculture of Iraq and more especially of the region later known as the Sawād, the ‘black land’, a great expanse of alluvial and irrigated territory extending from south of Ctesiphon and, later, Baghdad, to the sea, and watered by the two great

² See P. Crone, *Meccan trade and the rise of Islam* (Princeton, 1987; repr. Piscataway, NJ, 2004), p. 7 with earlier literature.

rivers, Tigris and Euphrates.³ Since the earliest historical times the region had been the focus of human agriculture and husbandry, with a network of irrigation canals connecting the two rivers. To the east lie the mountains of Media and the great barrier of the Zagros range. In their northern foothills, pushing up towards Azerbaijan, the Diyālā valley extends the fertile zone, and to the south and east of the Sawād the plain of Khuzistān again offers rich agricultural and pastoral possibilities. The successive ridges of the Zagros separate Mesopotamia from the Iranian plateau, running down from the highlands of Kurdistan in the north to east of coastal Khuzistān and Fārs in the south, intersected by many small fertile plains and valleys. The plateau itself is sparsely populated, with settlement confined largely to the valleys formed by the rivers flowing from the eastern ridges of the Zagros, or to oases from which irrigation networks can be fed. To the east the plateau is bounded by a number of larger and smaller arid salt depressions and rocky or sandy deserts, bordered on the eastern and southern edges by further highlands. Its south central and southern fringes are characterised by arid plains where settlement depended on oases or carefully maintained irrigation, with long stretches of waterless semi desert extending along the coast into Makrān and Sind and thus into India. In the north, Media is bounded by the Elburz mountains which separate its cooler, steppe like plains from the near tropical and forested Caspian littoral. Westwards lie the Talish mountains and then the high steppe of Azerbaijan; eastwards the Elburz give way to the highlands of Ṭabaristān and the steppe of Jurjān and western Khurāsān, with the plateau of Turkistan stretching east and north into Transoxania, through the Karakum and then Kizilkum steppe, past the Aral Sea into Central Asia. To the east and across the central sector of mountain ridges and tracts of desert, intersected by more fertile river valleys, the plain extends along the valley of the Oxus between the western outliers of the Pamirs to the north and the Hindu Kush to the south.

Asia Minor can be divided into three zones: the central plateau; the coastal plains; and the mountain ranges that separate them. The plateau rises from about 3,500 feet in the west to over 6,000 feet in the east, and is typified by extremes of temperature. To the north the Pontic Alps follow the line of the

3 According to Sasanian evidence preserved in the later Arabic tradition, the annual revenues from the Sawād under Khusrau I amounted to 150 million silver drachms, as much as the combined revenues from Fārs, Kirmān and Khuzistān: see the evidence discussed in J. Banaji, 'Precious metal coinages and monetary expansion in Late Antiquity', in *Dal Denarius al Dinar: L'oriente e la moneta romana. Atti dell'incontro di studio, Roma 16-18 sett. 2004* (Rome, 2006), pp. 274-6.

southern shore of the Black Sea; to the south the Taurus and Anti Taurus ranges extend along the Mediterranean coast and across northern Syria, curving north eastwards into the Caucasus region. All the mountain zones, but particularly the southern and eastern regions, are characterised by smaller plateaux dissected by crater lakes, lava flows and depressions. Finally, the Balkan peninsula is dominated by mountains which, while not especially high, cover some two thirds of its area, the main formations being the Dinaric Alps (which run through the western Balkan region in a south easterly direction) and the associated Pindos range. Extensions and spurs of these mountains dominate southern Greece and the Peloponnese. The Balkan chain itself lies north of Greece, extending eastwards from the Morava river for about 550 kilometres as far as the Black Sea coast, with the Rhodope range forming an arc extending southwards from this range through Macedonia towards the plain of Thrace. River and coastal plains are relatively limited in extent. There are thus very distinct climatic variations between the coastal, Mediterranean type conditions and the continental type conditions of the inland and highland regions.

Climate and the problem of climate change

Climate has remained, within certain margins, relatively constant across the late ancient and medieval periods, yet there are a number of fluctuations that need to be borne in mind and which, in conjunction with natural events such as earthquakes, man made phenomena such as warfare, and catastrophes such as pandemic disease, could have dramatic short to medium term results for the human populations of the region, and thus for patterns of settlement, land use, the extraction, distribution and consumption of resources, and political systems.⁴ The climate throughout much of the late Hellenistic and Roman imperial periods was relatively warmer and milder than in the period that preceded it, and constituted a 'climatic optimum' which favoured the expansion of agriculture. This expansion is reflected in the so called Beyşehir

4 Further literature can be found in the bibliography. There is a vast literature on climate change and its impact, especially in respect of societal collapse (see J. Diamond, *Collapse: How societies choose to fail or succeed* (New York, 2005); H. Nützhel Dalfes, George Kukla and Harvey Weiss (eds.), *Third millennium BC climate change and old world collapse* (New York, 1997)), although 'environmental determinism' is an obvious danger and a major focus for debate (see A. Rosen, 'Determinist or not determinist?: Climate, environment, and archaeological explanation in the Levant', in S. Wolff (ed.), *Studies in the archaeology of Israel and neighboring lands in memory of Douglas L. Esse* (Chicago, 2001), pp. 535–54; A. Rosen, 'Environmental change and human adaptational failure at the end of the Early Bronze Age in the Southern Levant', in Dalfes, Kukla and Weiss (eds.), *Third millennium BC climate change and old world collapse*, pp. 25–38).

Occupation Phase in the southern Balkans and south western Turkey, for example.⁵ Datable by palynological and other paleoenvironmental evidence to begin in about 1250 BCE and to last through to the seventh century CE, this term has been adopted to refer to a period of human activity marked by a dramatic increase in cultivated trees and cereals, clear evidence of a major human impact on the environment which contrasts starkly with the foregoing period. Not all the sites that provide pollen evidence of this shift in vegetation patterns show exactly the same plant profile, but there is a uniform increase in the pollens of domesticated flora, including in particular vines, olives, chestnut and other fruit trees and a range of cereals. At the same time the species of coniferous *pinus* associated with non cultivated contexts show a marked retreat, whereas species of oak and various herbaceous plants, the latter associated with pastoral activities, increase. While there are a number of sub zones within the areas affected by the BO Phase, some evidencing less human activity than others, the Phase is a generally recognised phenomenon.

By about 500 CE the climatic situation was changing, with colder and wetter conditions persisting up to the mid ninth century. But within this broad pattern certain micro climatic shifts have also been noted: palynological and, more reliably, stable isotope analysis from lake beds in the Levant and Asia Minor, for example, suggest that the climate from about 300 CE until the mid fifth century was in fact slightly drier and warmer than the preceding centuries (and tree ring analysis suggests that drought was frequent between the 420s and 480s in several regions of the Levant⁶), but that some time during the later fifth century it became cooler and wetter, until a period of very gradual warming and desiccation began in the seventh century. Precipitation levels declined, affecting highland zones in particular. At the same time the evidence suggests that during the fifth century the level of the Mediterranean began to rise, although the impact of this, which reflects a global phenomenon, remains unclear. Nevertheless, it is very important to note that the characteristic evidence for human activity associated with the BO Phase ends

5 Named for the site at which it was first identified, Beyşehir Gölü, in south west Turkey: see S. Bottema, H. Woldring and B. Aytug, 'Palynological investigations on the relations between prehistoric man and vegetation in Turkey: The Beyşehir Occupation Phase', *Proceedings of the 5th Optima Congress, September 1986* (Istanbul, 1986), pp. 315–28; W. J. Eastwood, N. Roberts and H. F. Lamb, 'Palaeoecological and archaeological evidence for human occupation in southwest Turkey: The Beyşehir Occupation Phase', *Anatolian Studies*, 48 (1998), pp. 69–86.

6 S. Lev-Yadun, N. Lipschitz and Y. Waisel, 'Annual rings in trees as an index to climate changes intensity in our region in the past', *Rotem*, 22 (1987).

only in the later seventh century. This clearly suggests that climatic stimuli were *not* the major cause of shifts in patterns of human activity.⁷

These micro climatic fluctuations are important, because climate change does not affect all areas in the same way. Indeed, both the textual evidence assembled for the Late Antique period and the palaeoclimatological evidence suggest marked regional variations across quite short periods of fifty or one hundred years, with droughts alternating with extremely cold and wet conditions, bringing serious difficulties for irrigated lands, on the one hand, and for marginal dry farming zones, on the other. In those regions, such as the Mediterranean coastal plains, dominated by westerlies, a warmer climate brings less rainfall and desertification of desert marginal regions, whereas in more continental zones such as the Iranian plateau and the drainage areas of the Caspian, rainfall increases. A colder climate brings more rainfall in the former regions – thus exerting pressure on hydrological systems in general – whereas in the continental zones – such as the Anatolian or Iranian plateaux – it brings less precipitation and thus desiccation. Evidence from the Susiana plain suggests that the period around 500–650 CE was relatively dry, for example.⁸ Intermediate zones – such as the Mesopotamian lowlands – will be affected according to their position in relation to prevailing winds, rain – and highland shadow and distance from the sea. Climate change tends to show up first in marginal zones, and temperate or humid regions later. Even if we are not yet in a position anywhere to judge the impact of these shifts on either land use or the social and economic history of the regions concerned, it is nevertheless apparent that they will have played a role and cannot be written out of the causal relationships that determined the pattern of historical change in the late ancient world.

- 7 M. D. Jones, C. Neil Roberts, M. J. Leng and M. Türkeş, 'A high resolution late Holocene lake isotope record from Turkey and links to North Atlantic and monsoon climate', *Geology*, 34 (May 2006). For the anthropogenic factors leading to the end of the BO Phase, see J. F. Haldon, "'Cappadocia will be given over to ruin and become a desert': Environmental evidence for historically attested events in the 7th–10th centuries', in K. Belke, E. Kislinger, A. Külzer and M. Stassinopoulou (eds.), *Byzantina Mediterranea: Festschrift für Johannes Koder zum 65. Geburtstag* (Vienna, 2007); and A. England, W. J. Eastwood, C. N. Roberts, R. Turner and J. F. Haldon, 'Historical landscape change in Cappadocia (central Turkey): A paleoecological investigation of annually laminated sediments from Nar Lake', *The Holocene*, 18, 8 (2008), pp. 1229–45.
- 8 R. J. Wenke, 'Imperial investments and agricultural development in Parthian and Sasanian Khuzistān: 150 BC to AD 640', *Mesopotamia*, 10–11 (1975/6), p. 82; H. M. Cullen and P. B. de Menocal, 'North Atlantic influence on Tigris Euphrates stream flow', *International Journal of Climatology*, 20 (2000); Jones *et al.*, 'A high resolution late Holocene lake isotope record from Turkey'.

In any event, the shifts described above will have rendered the human environment of the later fifth to seventh centuries more challenging and the economy of existence more fragile. Combined with the great plague of the middle of the sixth century this established a short but vicious cycle which impacted upon the population and thus upon settlement patterns and density of many regions, although with very varied degrees of intensity. Although generalisations are dangerous, after a period of demographic expansion and intensification of agriculture lasting into the sixth century, a slow decline and retrenchment seems to set in from some time around the middle of the sixth century.⁹ In certain provinces of the eastern Roman empire in Asia Minor, for example, some marginal lands were abandoned, soil erosion increased where agriculture receded, and the colder climate generated increasing water volume in rivers and watercourses, contributing to a rapid alluviation accompanied by lowland flooding in many more exposed areas. And while there is some support for an overall reduction in agrarian activity around the early 540s, as reflected in the carbon dioxide content of polar ice cores, the sources of this change cannot be geographically fixed, and the pattern does not seem to be repeated in Syria and Palestine – the settlement at Nessana in the Negev, for example, flourished well into the later seventh century on the basis of its irrigation agriculture.¹⁰ In other regions an overall reduction in population and thus in the rate of exploitation of natural resources such as forest is shown by an increased variation in woodland flora over the same period. It is important to bear in mind the very different effects such shifts had on different regions, and we must not assume that similar outcomes were exhibited in Anatolia, the Balkans, the Iranian plateau, Mesopotamia, or the northern Syrian uplands; each was subject to its own particular micro climatic system.¹¹

⁹ Much ink has been expended on the question of the effects of the 'Justinianic' plague. For a reasoned comment on its potential but regionally varied effects, see C. J. Wickham, *Framing the early Middle Ages: Europe and the Mediterranean, 400–800* (Oxford, 2005), pp. 548f. But historians have, on the whole, not yet taken into account the biological and epidemiological evidence associated with the plague, which has shown it to be an especially virulent pathogen: see I. Weichmann and G. Grupe, 'Detection of *Yersinia pestis* in two early medieval skeletal finds from Aschheim (Upper Bavaria, 6th century AD)', *American Journal of Physical Anthropology*, 126 (2005); and the contributions in L. K. Little (ed.), *Plague and the end of Antiquity: The pandemic of 541–750* (Cambridge, 2006).

¹⁰ See Y. Hirschfeld, 'Farms and villages in Byzantine Palestine', *Dumbarton Oaks Papers*, 51 (1997), pp. 50ff.; and in general J. Shereshevski, *Byzantine urban settlements in the Negev desert* (Beer Sheva, 1991). For the evidence of ice cores, the levels of carbon dioxide in which have been related to the degree and intensity of agricultural and pastoral production, see W. F. Ruddiman, 'The anthropogenic greenhouse era began thousands of years ago', at courses.eas.ualberta.ca/eas457/Ruddiman2003.pdf.

¹¹ See the relevant discussion in T. J. Wilkinson, *Archaeological landscapes of the Near East* (Tucson, 2003); and the summary in M. G. Morony, 'Economic boundaries? Late

Roads and routes

Communications depended on landscape and climatic conditions, of course, but a series of major strategic routes connected these different cultural and geographical zones. The eastern Roman empire benefited from the creation of military roads, constructed largely in the period 100 BCE–100 CE by the Roman army, a network that also aided non military communications—the movement of goods, people and information. But the regular maintenance of roads, which was a state burden upon towns and which was administered and regulated at the local level, seems during the later Roman period to have suffered somewhat. Outside the boundaries of the Roman state road maintenance depended largely on local administration, although the Sasanian state certainly provided for the upkeep of certain key strategic roads through al Jazīra towards Roman territory, or to the Caucasus and along the western Caspian littoral, as well as eastwards into Khurāsān and down to Fārs and major cities such as Iṣṭakhr. Indeed, there is some evidence to suggest that road building and bridge building were on several occasions carried out using the skills of Roman captives during the third and fourth centuries.¹² The royal court certainly invested in major strategic projects, therefore, although the complex network of military roads maintained in the Roman world was not repeated in Iran or Mesopotamia. And it has been reasonably assumed, albeit on very little actual evidence other than later Islamic tradition, that a postal service and state transport system similar to the Roman *cursus publicus* was maintained by the Sasanian state.¹³

Transport by water was generally much faster and certainly far cheaper than by land, although ought not to be overstated. Long distance movement of bulk goods such as grain was generally prohibitively expensive—the cost of feeding draught oxen, maintaining drovers and carters and paying local tolls, combined with the extremely slow rate of movement of ox carts, multiplied

Antiquity and early Islam', *JESHO*, 47 (2004), pp. 172–5; and the comparative description in Wickham, *Framing the early Middle Ages*, pp. 17–31, and esp. 609ff., on the regionalised urban economies of the eastern provinces and their development

- ¹² See, for example, S. N. C. Lieu, 'Captives, refugees and exiles', in P. Freeman and D. Kennedy (eds.), *The defence of the Roman and Byzantine East*, 2 vols. (Oxford, 1986), vol. II, pp. 476–83; and M. Morony, 'Population transfers between Sasanian Iran and the Byzantine empire', in *La Persia e Bisanzio: Atti dei convegni Lincei 201* (Rome, 2004). Further literature can be found in the bibliography. And see chapter 2 below.

- ¹³ An account of various acts of Khusrāu I, transmitted through the later Arabic tradition by Miskawayh, gives a very clear picture of a centralised state with an effective and centrally supervised road system. See M. Grignaschi, 'Quelques spécimens de la littérature sassanide conservés dans les bibliothèques d'Istanbul', *JA*, 254 (1966), pp. 1–142 (Fr. trans., pp. 16–28; notes, p. 45). See p. 20 with n. 40.

the price of the goods being transported beyond the means of anyone who would otherwise have bought them. Sogdian merchants employed Bactrian camels, and the introduction of the pack saddle for camels did make the movement of bulk goods more economical. Although the bulk transport of goods over long distances did sometimes happen, it was really only the state, with some activity funded by wealthy private individuals, that could pay for this, except where the luxury value of the goods concerned made the enterprise worthwhile, as with the great silk caravans across the southern steppe zone from China and into Iran, or when conditions made a premium price possible (as with the Quraysh trade in leather in the sixth century: see below). The cost effectiveness of shipping, entailing the carriage of large quantities of goods in a single vessel handled by a small crew, also gave coastal settlements a great advantage with regard to their access to the wider world. In the case of the Roman world, and in spite of the short term disruption caused by the Vandals in the mid fifth century, the Mediterranean and Black Seas offered enormous opportunities for the movement of goods of all sorts, and the archaeological pattern of distribution of a range of products, from pottery to oil, wine, grain and minerals illustrates this very clearly. Similarly, for the Persians the Persian Gulf and the Indian Ocean offered comparable potential for a long distance commerce and movement of goods and ideas which belie the apparently westward facing aspect of Sasanian culture and politics presented by many of the sources.¹⁴

Syria and Palestine were traversed by several major routes connecting the inland regions to the coast, and by a series of major roads stretching from north to south and on down towards Sinai or around the coast through Gaza to Egypt. Travel eastwards from Syria to Mesopotamia was confined largely to the northern corridor across the plains of northern Syria and al Jazīra, from Amida down the Euphrates, or from Edessa, via Dara and Nisibis, or the Euphrates crossings at Callinicum, towards Nineveh; and although *in extremis* crossings of the Great Syrian Desert could be made (as in the expedition of Khālid ibn al Walīd in 634/5),¹⁵ this northern corridor was the only practical route for large forces and was thus the key element in the strategic geography of the whole region, determining also local economic activity and the location of fortresses and fortifications. Other routes led north and north west across what would become the Byzantine frontier during the second half of the seventh century from al Raqqa (Callinicum) to Ḥarrān or Edessa, then on to

¹⁴ See in general R. W. Bulliet, *The camel and the wheel* (Cambridge, MA, 1975).

¹⁵ See F. M. Donner, *The early Islamic conquests* (Princeton, 1981), pp. 119–28.

cross the Euphrates at Samosata, from which Melitene, Germanikeia and Adata could be reached. In northern Syria it was Chalkis (Qinnasrīn) and Beroea (Aleppo) that served as the foci for communications, with routes west to Antioch, north west into Cilicia and towns such as Tarsus and Adana, and south towards Apamea, Emesa, Damascus, the coast and the cities of Palestine and Arabia (Transjordan). To the south from the Roman provinces of Palestine III or Arabia a number of well established caravan routes passed along the wadis into the Ḥijāz and on to the coast or inland; and on the opposite side of the Arabian Peninsula a similar network of routes led up parallel to or along the coast into southern Iraq. From northern Syria also a series of key routes led across the Cilician plain and thence through the passes in particular through the so called Cilician Gates northwards onto the Anatolian plateau. From Mesopotamia and northern al Jazīra further routes led across the steppe like highlands of Azerbaijan into the southern Caucasus region, or down through the mountains of Daylam into the Caspian littoral and hence north towards Darband and a series of heavily fortified strategic passes giving access from the steppes to the north into the Caucasus and beyond. Routes eastwards from Mesopotamia were constrained primarily by the Zagros, through whose few passes access was had to Media and the Iranian plateau. The major southern road runs from Ahwāz via the so called Persian Gates across the mountains to Shīrāz. From here further routes radiate south to the coast of the Indian Ocean and the Gulf, north north east to Yazd or Iṣfahān, across the plateau and desert to the oasis of Kirmān, and then on to Makrān and Sind. From Hamadhān the northern route leads into the Ṭabaristān highlands, and on to the city of Rayy. From there another route crosses the mountains into the coastal plain of the southern Caspian, from where the road east to Jurjān runs along the coastal plain; while the eastward road continues across south of the mountains to Nishāpur in western Khurāsān. From here radiate routes north west into the Jurjān region, east and then north east through Khurasān towards Marw and Transoxania, or south towards Herat and then east on to Balkh, each supported by the agricultural output of its own river basin hinterland. From these cities roads led south into Sīstān and cities such as Zaranj and Kandahar. Eastwards the road continued to Kabul; southwards into the province of Sind and the port of Daybul on the Indian Ocean.

Asia Minor was traversed by a series of major strategic routes which crossed the Taurus and Anti Taurus via the passes already mentioned and led across the plateau, either to the northern coast and the great entrepôt of Trebizond, or to the north western and western coastal plains and cities such as

Constantinople, Nicaea and Ephesus. The Balkans likewise were characterised by the important military roads radiating out from Constantinople through Thrace, either north towards the Danube frontier, north and west towards the Adriatic, the most famous in the latter case being the Via Egnatia, of course, which crossed the mountains to Dyrrhachion (mod. Dürres), and the so called 'military road' from Constantinople up to the Danube.

Land use and exploitation of resources

The exploitation of natural resources and the ways in which human populations employ the land, flora and fauna at their disposal are closely determined by the geophysical and climatic framework described above, and can be grouped under four basic headings: arable farming; pastoral farming; the exploitation of woodland and scrubland; and the extraction and working of mineral resources. Agriculture can in turn be divided into dry rainfall dependent and wet irrigation dependent cultivation, while the type of pastoral activity depends on a range of variables, in particular height, degree of aridity, type of vegetation and grass cover, and so forth. The extent of agricultural activity, of the exploitation of natural resources such as woodlands, and of particular crops such as cereals or grapes, is reflected also in the climatic fluctuations and shifts that took place across the period in question. Yet even in apparently adverse and hostile conditions human activity produced a thriving agriculture along the desert fringes of Syria and Palestine, for example, substantial populations were served by extensive and efficient irrigation systems in late Roman times and thereafter. Egypt was the bread basket of the late Roman and early Byzantine state, just as Mesopotamia was by far the most productive and wealthiest region of the Sasanian kingdom. But cereal production was also an important feature of the limited but fertile coastal and riverine plains of central and northern Syria and parts of Palestine, alongside the equally important production of olive oil and a range of fruits and vegetables. Grain production was likewise a major feature of the Sawād and of most of the fertile river valleys and watered uplands of Iran, Anatolia and the Balkans, and rice was also cultivated in parts of Syria and Khuzistān, as well as in Bactria.¹⁶ Considerable regional variations in the types of fruits and vegetables and the different emphasis on oleoculture and viticulture

16 C. Brunner, 'Geographical and administrative divisions: Settlements and economy', in E. Yarshater (ed.), *The Cambridge history of Iran*, vol. III: *The Seleucid, Parthian and Sasanian periods* (Cambridge, 1983), p. 754. For an overview of the Mediterranean in this respect, see P. Horden and N. Purcell, *The corrupting sea: A study of Mediterranean history* (Oxford, 2000), pp. 175–224.

reflected long term cultural and economic tradition as well, with the Mediterranean lands concentrating on olives and vines in contrast to the production of nuts and a wide range of other fruits in Iraq and Iran. Apart from wheat, barley and rice, for example, al Ṭabarī lists vines, dates, alfalfa and olives as products which the Sasanian kings taxed; other sources suggest that vegetables, cotton, sesame and cucumbers were untaxed.¹⁷ Between the zones of agricultural production were substantial districts in which a pastoral economy dominated. The marginal regions between the two were the site of mixed economic activity with accordingly differently articulated social relations from those typical of the arable heartlands or the nomadic or transhumant societies of the mountains and plateaux, as in the foothills of the Zagros, for example, where sheep raising was a major aspect of the local economy but where there were small gardens and where limited cereal production was also carried on, or in the Ḥijāz and in southern Arabia. But such economies depended on an accommodation with the systems around them, and both pastoralists and more strictly agricultural economies likewise depend for the most part on a symbiotic relationship with one another, with animal husbandry generally playing an important role in most agrarian cultures. Along the Zagros chain itself and throughout the mountainous steppe of Media and Azerbaijan different groups of nomads maintained their sheep, goats and horses. Horse and cattle farming were typical of the middle and south eastern plateaux regions of Asia Minor, southern Iran and Khurāsān, and southern Azerbaijan, shared with and giving way to sheep and goats on the middle and higher ground; a transhumant economy characterised the northern face of the Pontic Alps along the southern shore of the Black Sea and much of the central and western Balkan zone, as well as the divide between the Iranian plateau and the surrounding non arid lowlands. In North Africa the semi arid zones along the Mediterranean coast in Cyrenaica and Egypt as well as in the foothills of the Atlas and related highlands supported a nomadic or semi nomadic economy based on camels, sheep and goats.

The early Islamic period saw a considerable number of changes in this traditional pattern, which had itself not been static, since state demands, on the one hand, and market demands, on the other, encouraged shifts in the patterns of production – government demands for wheat for armies impacted on both Roman and Sasanian agriculture as private landlords and taxpayers responded to market and price fluctuations. Production of cash crops for specific markets,

17 T. Nöldeke, *Geschichte der Perser und Araber zur Zeit der Sasaniden* (Leiden, 1879), p. 245.

and in the context of a highly monetised economy, directly affected the organisation of labour on the land and the ways in which it might be taxed in the late Roman empire, most notably in Egypt but almost certainly elsewhere too, as in late Sasanian Iraq.¹⁸ Warfare, natural disaster and demographic changes appear to have adversely affected irrigation systems in Iraq and the Negev, or the production of olive oil in northern Syria, during the later sixth century; although by the same token many districts continued to flourish and to maintain their agricultural and irrigation infrastructure. During the seventh and especially the eighth centuries, however, a number of new crops appear which were to transform the picture of agrarian production, making possible the development of local economic subsystems producing for local and long distance markets as well as the rapid growth of urban populations and thus taxable resources. Such developments also affected dietary and culinary traditions as well as ceramic forms, of course. And while changes such as these must in all probability have been stimulated by expanding urban demand following the conquest, the role of the new Arab Islamic elite as well as their own traditions of estate management and exploitation also played a role; and this in turn affected patterns of political power and control of resources, so that the political history of the early Islamic world cannot adequately be understood in all its complexity without reference to the history of agrarian and urban production and the distribution and pattern of consumption of resources. Some idea of the relative wealth of the different parts of the Islamic world can be gauged by comparing the very different contributions made by different provinces to late Roman and, much later, to Ottoman revenues, in which it becomes clear that Iraq, on the one hand, and Syria and Egypt, on the other, were by far the biggest contributors to government tax income in comparison with most other provinces under their respective rulers.¹⁹ What is important to note, however, is that the arrival of Islam and the rise in importance of cash crops such as sugar and cotton, as well as the introduction of many new crops, stimulated some fairly dramatic changes in this picture.²⁰

18 P. Sarris, 'The origins of the manorial economy: New insights from late Antiquity', *English Historical Review*, 119 (2004); P. Sarris, 'Rehabilitating the great estate: Aristocratic property and economic growth in the Late Antique east', in W. Bowden, L. Lavan and C. Machado (eds.), *Recent research on the Late Antique countryside* (Leiden, 2004); Morony, 'Economic boundaries?', pp. 168–72; J. Banaji, *Agrarian change in Late Antiquity: Gold, labour and aristocratic dominance* (Oxford 2001), pp. 16–18, 36ff., 100ff., 214–19.

19 See M. F. Hendy, *Studies in the Byzantine monetary economy, c. 300–1450* (Cambridge, 1985), pp. 613–18.

20 A. M. Watson, 'A medieval green revolution: New crops and farming techniques in the early Islamic world', in A. L. Udovitch (ed.), *The Islamic Middle East, 700–1900: Studies in*

Rice (from which rice flour was ground) was cultivated in southern Iraq, and bread (whether of rice flour or wheat flour) was the basic food of all the populations of the Mediterranean and Iranian worlds. Cereals were therefore the dominant crop grown by the majority of rural producers. Egypt, with the rich alluvial soils of the Nile Valley and watered by extensive local irrigation systems, probably produced by far the greatest quantity per head of the producing population; but the plains of northern Syria, the coastal regions of Asia Minor, Thrace and Thessaly, the North African provinces, the Sawād and Khuzistān floodplains also produced substantial quantities of cereals. The oasis centres of the Iranian plateau and of Khurāsān likewise provided for themselves and for a certain amount of commercial activity in respect of grain production, as well as a range of fruits and vegetables. As well as wheat, a substantial element in the grain production of the empire was barley, with smaller amounts of millet in certain zones (southern Arabia, sub Saharan Africa) regarded generally as inappropriate for human consumption. Probably from the fourth century on (although the dating is problematic) hard wheats with a greater proportion of protein per volume were gradually replacing the soft wheats that had hitherto dominated Mediterranean cereal agriculture (with certain exceptions, for example, in Egypt, where the introduction of hard wheats appears to have pre dated its appearance elsewhere in the Roman world), with important consequences for both diet and cereal production in general in the centuries to follow.²¹ In Iraq and the oases of Iran and Khurāsān, dates, nuts and fruits were also produced, often in substantial quantities sufficient for export well beyond the centres of production. Vegetables, pulses (beans etc.) and root crops were also cultivated wherever cereals were also grown, usually on the basis of household garden plots rather than extensively, so that villages and towns were for the most part supplied with all the essentials of life food, drink, clothing, the materials for housing and the livestock for transport from their immediate hinterlands.

Self sufficiency was never absolute: villages were also part of a wider world of exchange consisting of many communities within a particular region, from which the inhabitants could obtain goods and services they did not produce themselves, and through which they might also attract commerce from very much further afield. At the same time the organisation of production varied

economic and social history (Princeton, 1981); A. M. Watson, *Agricultural innovation in the early Islamic world: The diffusion of crops and farming techniques*, Cambridge Studies in Islamic Civilization (Cambridge, 1983).

- ²¹ R. S. Bagnall, *Egypt in Late Antiquity* (Princeton, 1993); C. Morrisson and J. P. Sodini, 'The sixth century economy', in A. Laiou *et al.* (eds.), *The economic history of Byzantium from the seventh through the fifteenth century* (Washington DC, 2002), p. 196.

regionally and offered a multifaceted picture: rural communities of mixed ownership marketing their own produce or that of a landlord, large estates with highly commercialised enterprises worked through wage labour, mixed estates depending less on commercial markets and more on state purchasing for the army, diversified self sufficient estates, for example, and so forth.²² Only the largest cities, and then mostly those with access to ports and the sea, had the resources to import goods from further away than their own locality on a regular basis, and these were mostly luxuries for those who could pay for them. Rome and Constantinople imported bulk goods chiefly grain and oil on a large scale; but they were notable exceptions, with unusually large urban populations and substantial governmental and ecclesiastical bureaucracies. Madā'in/Ctesiphon and its Islamic successors were supplied from their immediate hinterland and from further afield by river and canal. But dependence on distant centres of production was possible only because it was paid for by states or governments, or because supply by river and canal was practical. Inland towns were generally entirely dependent on what was produced locally, and this was strongly inflected in terms of variety and availability by seasonal and regional fluctuations.

This was especially the case in those areas where irrigation systems were essential. Particularly significant in this respect were the *qanāts* of northern Syria, Iraq, Iran and Khurāsān, underground water channels which needed careful maintenance and upon which many major settlements depended for their survival. Irrigation systems had a long history in these areas, but in certain parts of the Sasanian world saw a very considerable expansion as a result of state investment during the fourth and fifth centuries. Under Shāpur I (r. 241–72 CE), for example, there seems to have taken place a substantial restructuring of the irrigation system in Khuzistān, with new canals and extended *qanāts* being constructed and connected by a series of reservoirs and sluices, a programme that impacted on both newly irrigated marginal lands and traditionally irrigated areas, and which made possible the substantial

22 See Banaji, *Agrarian change in Late Antiquity*, pp. 6–22, for example, with literature. Village settlements were often of very mixed structure, comprising freeholding cultivators, tenants of local or urban landlords (of varying scale and situation), simple labourers, artisans who also possessed and farmed land, either directly or through the use of hired labour, and so forth. Indeed, recent work has tended to emphasise the interpenetration of large scale and small scale landholding and exploitation in both villages and estates. See, e.g., C. Zuckerman, *Du village à l'empire: Autour du registre fiscal d'Aphroditô (525/526)* (Paris, 2004), and note Wickham, *Framing the early Middle Ages*, p. 243.

growth in population and urbanism that took place over this period.²³ In Mesopotamia itself a huge investment in the northern district, probably during the later third and early fourth centuries, linked the Tigris to the Euphrates by a canal from which a network of lesser waterways irrigated the areas to the south, while further south new networks of waterways and irrigation canals were constructed, investments which further stimulated both levels of production and urbanism.²⁴ The largest and most impressive of these works, however, was carried out through the construction of the system which linked the Tigris and the Diyālā basin, vastly extending the areas already irrigated by works undertaken by the earlier Parthian kings in the region.²⁵

Sowing, harvesting and the pattern of seasonal activities depended on location. For those regions dominated by a Mediterranean climate vegetables were harvested in June, cereals in July and vines and olives in the autumn, after which the land not given over to arboriculture was normally opened to livestock for pasturage and manuring. Ploughing and tilling generally took place in October and November, and planting/sowing followed immediately thereafter in order to take advantage of the winter rains and the seasonal humidity of the soil. But the cycle might be different in more arid regions: in Syria and on the Iranian plateau harvesting also took place in November, with ploughing and planting in July and August, for example. In those areas in which agricultural activity was supported by systems of irrigation, as in the Nile Valley, or drier regions with very low annual rainfall, the pattern was

23 See R. M. Adams and D. P. Hansen, 'Archaeological reconnaissance and soundings in Jundi Shapur', *Ars Islamica*, 7 (1968). The dating of the *qanāts* is, however, problematic, by association usually with physically proximate sites, rarely by internal evidence, so that some doubts remain as to whether or not they pre date or post date the arrival of Islam.

24 R. M. Adams, *Heartland of cities: Surveys of ancient settlement and land use on the central floodplain of the Euphrates* (Chicago, 1981), pp. 179–83, 208–11; M. Gibson, *The city and area of Kish* (Miami, 1972); R. M. Adams and H. J. Nissen, *The Uruk countryside: The natural setting of urban societies* (Chicago, 1972), pp. 59–63.

25 R. M. Adams, *The land behind Baghdad: A history of settlement on the Diyala plains* (Chicago and London, 1965), pp. 61–80, 104–5; P. Christensen, *The decline of Iranshahr: Irrigation and environments in the history of the Middle East, 500 BC to AD 1500* (Copenhagen, 1993), pp. 107–12, 227, 234; M. Morony, 'The late Sasanian economic impact on the Arabian Peninsula', *Nāme ye Irān e Bāstān*, 1, 2 (2001/2), pp. 30–1 (for similar systems in sixth century Sasanian ruled Oman); J. D. Howard Johnston, 'The two great powers in Late Antiquity: A comparison', in A. Cameron (ed.), *The Byzantine and early Islamic Near East*, vol. III: *States, resources and armies*, Studies in Late Antiquity and Early Islam 1 (Princeton, 1995), pp. 199–203 (now repr. in J. Howard Johnston, *East Rome, Sasanian Persia and the end of antiquity* (Aldershot, 2006), vol. 1).

different again. Returns on planting similarly varied: the highest average returns in fertile regions appear to have been of the order of 7:1 or 8:1, with variations in either direction. Lower returns in drier or less well watered districts have been calculated at some 5:1, but might be considerably lower; and all these figures varied slightly across each district, according to the type of crop, seasonal climatic fluctuations and whether or not irrigation systems were employed.

Livestock – sheep, goats, cattle, horses and pigs – were a feature of most rural communities, but certain areas concentrated on stock raising more than on other spheres of production. The raising of mules and horses was an essential for the state, for the public postal and transport system as well as for the army. Substantial stud farms were maintained in parts of Asia Minor, but are also known from North Africa, Italy and Syria, as well as Fārs and Khurāsān. The Anatolian plateau was dominated by stock farming, often on large, ranch like estates, and while agriculture played an essential role in the maintenance of the population, the richest landlords of the region seem generally to have based their wealth on this type of production. But stock farming played an important role throughout the east Roman and Sasanian worlds, and sheep and goats, along with pigs, formed an important element in the productive capacity of many rural communities, sharing with cereal production the attentions of the peasant farmer. Livestock was the source of many essential items – not just meat, skins or milk, but also hides, leather, wool, felt, glues and horn, as well as bone and gut for both decorative and practical purposes.²⁶

Land was exploited not just by agriculture and animal husbandry, but also for timber and its derivatives – oils, bark, resins and so forth – and for minerals. Whereas the former has not been studied in any depth, with a few exceptions,²⁷ the extraction of minerals has been the subject of a good deal of research, and a reasonably accurate picture of what mineral resources were extracted from which regions of the late ancient world can now be drawn. Of the ores mined or collected, iron was probably the most important, needed for weapons and tools. Centres of iron mining included north eastern Anatolia and the central southern Black Sea coastal regions, central Syria, the Taurus mountains and the south Balkans, Oman and the Arabian

26 For patterns of agricultural production and the seasons, see M. Kaplan, *Les hommes et la terre à Byzance du VI^e au XI^e siècles* (Paris, 1992), esp. pp. 25–87.

27 A. W. Dunn, 'The exploitation and control of woodland and scrubland in the Byzantine world', *Byzantine and Modern Greek Studies*, 16 (1992).

Peninsula, and especially in the Elburz range and southern Azerbaijan high lands, as well as parts of the Zagros and, on the Iranian plateau, in the Kirmān region. Tin, generally alloyed with copper to make bronze, was mined in the Taurus and the Arabian Peninsula, but was also imported to the eastern Mediterranean from the south western parts of Britain; bronze was extremely commonly used both for low value coins and for a huge range of household utensils and tools, and ornamental objects. Copper, which could be alloyed with zinc to make brass, was extracted from the Caucasus and southern Pontic regions, northern Syria, Oman, the Zagros and the Iranian plateau, and the central Balkans and Spain. Crucial to the economy of the Roman world was gold, of course, obtained from the Caucasus, from Armenia, which had rich deposits, as did also the Arabian Peninsula, and to a lesser extent from the Balkans, although the location of Roman and Byzantine gold workings remains largely unclear.²⁸ The Sasanians competed with Rome over Caucasian sources, although limited workings in the western Elburz, as well as further afield in Oman, Nubia and Abyssinia, also provided supplies. The Arabian Peninsula appears to have been far more important as a source of precious metals than has generally been recognised, and this may provide additional reasons for the urgency of Byzantine and Sasanian interest in the area.²⁹ There were sources of silver, particularly important to the Sasanians in respect of their coinage, in the Elburz, the Iranian plateau and southern Caucasus, Oman, Arabia and also Khurāsān; as well as from the Taurus, the central Pontic Alps and Armenia, and the central Balkans. In the case of both these precious metals governments tried as hard as possible to control both their import and export. Control over stocks of precious metals was achieved partly through recycling, although this could not ensure a constant supply.³⁰

28 See in particular G. W. Heck, 'Gold mining in Arabia and the rise of the Islamic state', *JESHO*, 42 (1999); and A. H. M. Jones, *The later Roman empire 284–602: A social and administrative study* (Oxford, 1964), pp. 834–9; O. Davies, *Roman mines in Europe* (Oxford, 1935); K. Greene, *The archaeology of the Roman economy* (Berkeley, 1986), pp. 142–8; J. C. Edmondson, 'Mining in the later Roman Empire and beyond', *Journal of Roman Studies*, 79 (1989); and the brief treatment in M. McCormick, *Origins of the European economy: Communications and commerce, AD 300–900* (Cambridge, 2001), pp. 42–53.

29 See Heck, 'Gold mining in Arabia and the rise of the Islamic state', pp. 368–72.

30 For Iran see J. V. Harrison, 'Minerals', in W. B. Fisher (ed.), *The Cambridge history of Iran*, vol. I: *The land of Iran* (Cambridge, 1968); Morony, 'The late Sasanian economic impact on the Arabian Peninsula', pp. 29, 32–3, 35; and esp. D. M. Dunlop, 'Sources of gold and silver according to al-Hamdānī', *Studia Islamica*, 8 (1957) (repr. in M. G. Morony (ed.), *Production and the exploitation of resources, The Formation of the Classical Islamic World* 11 (Princeton, 2002), chap. 1).

The social environment

Population, cities and villages in the late ancient world

Discussion of the economic relationships and structures of Late Antiquity has expanded enormously over the last twenty years, a result of two tendencies to see 'Late Antiquity' as a period stretching from the fourth or even third century CE to the eighth, and to extend its geographical coverage to encompass a much wider world than the territories of the Roman empire. Sasanian Iran, parts of Central Asia and India and the Far East are now, quite reasonably, brought into the picture, as historians and archaeologists recognise the need to see Rome or Persia as parts of a much greater and more complex whole. And although there remain some important disagreements about specific regional differences in the pace and degree of development, recent work has made it possible to offer a fairly coherent account of the nature of the late ancient economy. It has become clear, in addition, that the 'economy' of the late ancient world has to be conceived of as consisting in fact of several economic sub systems, overlapping and interpenetrating at different points. At the same time, the concept of the 'economy' is complicated by the role of the state, in its Roman and Sasanian forms, in so far as government or court demands for resources in various guises, whether money, produce, services or skills, directly impacted upon the ways in which local society operated.³¹ The arrangements and institutional structures through which resources were appropriated and the legal forms that justified this process were affected by notions of property and rights but at the same time directly determined the

³¹ Such work has taken its cue in particular from the work of Brown and Mazzarino; see e.g. P. R. L. Brown, *The world of Late Antiquity: From Marcus Aurelius to Muhammed* (London, 1971); G. W. Bowersock, Peter Brown and Oleg Grabar (eds.), *Interpreting Late Antiquity: Essays on the postclassical world* (Cambridge, MA, 1999); S. Mazzarino, *La fine del mondo antico* (Milan, 1988). There are now a number of succinct summaries of the material, which provide useful syntheses of the evidence, the literature and current interpretations. See in particular M. Whittow, 'Decline and fall? Studying long term change in the east', in L. Lavan and W. Bowden (eds.), *Theory and practice in late Antique archaeology* (Leiden, 2003), pp. 404–18; Morrisson and Sodini, 'The sixth century economy'; B. Ward Perkins, 'Specialised production and exchange', in A. Cameron, B. Ward Perkins and M. Whitby (eds.), *The Cambridge ancient history*, vol. XIV: *Late Antiquity: Empire and successors, AD 425–600* (Cambridge, 2000); B. Ward Perkins, 'Land, labour and settlement', in Cameron et al. (eds.), *Late Antiquity*; C. J. Wickham, review of A. Giardina (ed.), *Società romana e impero tardoantico, III: Le merci. Gli insediamenti* (Rome Bari, 1986), in *Journal of Roman Studies*, 78 (1988); and A. Chavarría and T. Lewit, 'Archaeological research on the late antique countryside: A bibliographic essay', in Bowden, Lavan and Machado (eds.), *Recent research*. Quite apart from these, the substantial volumes of McCormick, *Origins of the European economy*, and Wickham, *Framing the early Middle Ages*, are situated in precisely this milieu.

ways in which political power and authority were expressed and exercised. The first Muslim conquerors thus inherited an exceedingly complex set of economic and political structures and relationships, and it is in consequence hardly surprising that early Islamic institutions and state systems were heavily determined by the framework within which they now had to function, the more so since that framework and its constituent elements were themselves evolving, and continued to evolve, but in an increasingly Islamised context. To speak of 'the economy of the late ancient world' is, therefore, to do this complex and multifaceted set of relationships and social practices a very considerable injustice, yet we cannot escape some degree of generalisation if we are to try to encapsulate the key features of the socio economic landscape in which Islam was to implant itself from the early 630s CE on. We may thus attempt to summarise the most significant developments under a series of headings, beginning with population and moving on to cities, urbanism and settlement, the state and fiscal systems, and commerce.

Given the geographical constraints described already, it is apparent that the pattern of settlement, and in particular its density, will reflect this environment very closely. A comparison of the areas of settlement density and locations of villages, towns or cities in the late Roman and early Byzantine world with modern demographic patterns demonstrates a remarkable continuity in all the regions with which this volume is concerned. Such a comparison says little about absolute numbers or about the fluctuations across time (seasonally or even on a day to day basis) in density and extent of settlement, as marginal lands were brought into, or fell out of, cultivation or as irrigation systems were neglected or maintained or extended; but it does point to the relationship between human populations and the ability of the land to support them. A comparison of the demographic map of Turkey before the Second World War (representing the mid 1930s) with a map showing the density of Roman cities and Byzantine episcopal sees, for example, highlights the fact that it is more or less the same areas that could maintain substantial populations in ancient and medieval times, that saw the densest concentration of urban centres, and that may thus be taken to have remained the most productive and heavily settled regions of the Byzantine period after the transformation of the late ancient city network after the seventh century. A similar pattern emerges from a comparison of Roman and medieval population centres with modern demographic concentrations in the Balkans.

Estimating pre modern population numbers and densities is notoriously difficult and fraught with dangers, methodological and factual, so while the distribution of settlement can, up to a point, be represented reasonably

accurately, the numbers suggested for mean population levels must be taken with a considerable degree of caution, however credible they may appear to be. The climatic and geographical features that determined land use likewise determined where populations were concentrated and how many people the land could support. The degree of continuity from medieval to modern times is, in this respect, considerable. But there were within our period very considerable fluctuations, both in respect of the relationship between the populations of urban and rural regions and in terms of their density. Broadly speaking, it has been assumed that there was a long downward curve in population in the Roman empire during the late ancient period, although with very marked regional variations, which continued into the later seventh and eighth centuries in what was left of the empire after the first Islamic conquests, followed by a slow recovery into the later ninth and tenth centuries, with a fairly dramatic rise in the twelfth century. In fact, archaeological data would now suggest a marked regional upturn during the fifth and sixth centuries in this pattern for much of Syria, Palestine and Egypt, and for Mesopotamia and southern Iraq, with the downturn continuing slowly in North Africa and the western parts of the Roman world at the same time. The evidence for central and eastern Iran is too sparse yet to generate such generalisations. It has been estimated that the population of Roman Europe was in the order of approximately 67–70 million at the end of the second century CE, falling to around 27–30 million by the early eighth century (but rising again by 1300 to some 73 million, with a particularly noticeable rise about 1200 CE). The most recent estimates for the late Roman and Byzantine areas proposes a population for the empire's eastern provinces of some 19–20 million just before the middle of the sixth century (before the plague of the 540s), with a further 7 million in the west; of 17 million in the early seventh century, with a reduction to about 7 million by the middle of the eighth century. But there is no real way of knowing how accurate these actually are.³²

Some evidence suggests a similar curve in the Near Eastern world, yet it should also be emphasised that there were marked regional variations. Thus in the Sasanian lands, especially Mesopotamia, the Diyālā basin and Khuzistān, population expansion based upon the evidence of expanding irrigation systems and urbanisation has been argued for the period from the

32 Banaji, *Agrarian change in Late Antiquity*, pp. 16–18, 214–19; T. J. Wilkinson, *Town and country in southeastern Anatolia*, 2 vols. (Chicago, 1990), vol. I, pp. 117–28; Ward Perkins, 'Land, labour and settlement', pp. 320–7 (but emphasising the chronological and regional fluctuations and inflections); C. Foss, 'Syria in transition, AD 550–750: An archaeological approach', *Dumbarton Oaks Papers*, 51 (1997), pp. 259–61; Morrisson and Sodini, 'The sixth century economy', pp. 174–6.

later third century CE. While it has been argued that on Roman territory this expansion in the eastern provinces may well have drawn to a close around the middle of the sixth and into the first half of the seventh century, beginning in northern Syria and its coastal towns earlier than in the south, a reconsideration of the archaeological material suggests a very much later onset of change well after the Islamic conquests, in fact;³³ and in the Sasanian world a similar slowing down and possibly an ensuing contraction is proposed, purportedly as a result of the failure of the central government to maintain the expanded irrigation networks in Mesopotamia, perhaps datable to the early seventh century. At the same time, however, the three areas where this expansion and contraction have been highlighted are also the only areas for which substantial survey material is available,³⁴ and this inevitably renders the general pattern in the Sasanian kingdom somewhat ambiguous, especially in the light of the reassessment of the eastern Roman material from Syria and Palestine. By the same token, it has been argued that demographic change throughout these regions was in fact very gradual, and the dramatic shifts of the middle and later Sasanian period reflect merely the movement of an otherwise stable population from dispersed rural habitats to more concentrated urban centres. Indeed, the expansion may itself reflect an overdevelopment that was not sustainable, so that later 'contraction' is in fact to be seen as a return to a 'normal', or at least sustainable, regime.³⁵ But while there is some disagreement about the specific demographic pattern in the different regions mentioned above, and while one can point to a number of exceptions, quite apart from a differential rate of change from east to west (including important regional and local variations), the overall pattern – a long term decline punctuated by marked regional anomalies – seems now generally agreed.³⁶

33 For the tailing off of expansion, and subsequent contraction in the later sixth century, see H. Kennedy, 'From polis to madina', *Past and Present*, 106 (1985); H. Kennedy, 'The last century of Byzantine Syria', *Byzantinische Forschungen*, 10 (1985). The tendency currently is to push these changes into the later sixth and seventh centuries, or beyond, depending upon region. See for example J. Magness, *The archaeology of the early Islamic settlements in Palestine* (Winona Lake, IN, 2003), esp. 195ff.; and J. Magness, 'Redating the forts at Ein Boqeq, Upper Zohar, and other sites in SE Judaea, and the implications for the nature of the *Limes Palaestinae*', in J. H. Humphrey (ed.), *The Roman and Byzantine Near East*, vol. II: *Some recent archaeological research*, JRA Supplementary Series 31 (Portsmouth, RI, 1999).

34 K. Abdi, 'Archaeological research in the Islamabad plain, central western Zagros mountains: Preliminary results from the first season, summer 1998', *Iran*, 37 (1999); K. M. Trinkaus, 'Pre Islamic settlement and land use in Dāmghān, north east Iran', *Iranica Antiqua*, 18 (1983).

35 R. J. Wenke, 'Western Iran in the Partho Sasanian period: The imperial transformation', in F. Hole (ed.), *The archaeology of western Iran* (Washington, DC, and London, 1987), pp. 252, 257–8, 261. I am grateful to Donald Whitcomb for discussion on these issues.

36 See for recent discussion Morony, 'Economic boundaries?', pp. 181–3.

The late Roman urban landscape

The city was one of the most important features of the late ancient landscape, both in respect of the social organisation of production and the ownership and control of resources in land and manpower. Cities exist in a physical as well as a human social context, since the territory around urban centres was populated by a vast range of types of rural habitation whose occupants were responsible for the labour and effort that transformed the landscape. Evidence for village life varies according to the quality of the written sources and the extent to which archaeological investigation has focused on non urban contexts, but the relationship between rural hinterland and village, on the one hand, and urban centre, whether large or small, on the other, is symbiotic, but in ways that cannot necessarily be used to interpret the processes of economic change and transformation evident from the archaeological and documentary record.³⁷

There are three basic paths towards urban development. First, in the sense of urban centre or 'town' that is, a location at which producers from the surrounding locality can meet on a regular basis to exchange goods and services, where local political power can be concentrated, which serve also as a cultic focus, that is to say, a religious centre, all of which presupposes physical accessibility (roads and transport from the locality to the town) and a water supply. Second, cities may grow out of settlements reflecting an original concentration of tribal or lineage population groups concentrated together for defence, which serve as centres of social and economic activity and which then evolve distinctive political and social institutions, acquiring thereby a specific status which distinguishes them from other rural settlements. Third, cities in suitable locations (the latter varying historically according to the demands of supra local political authorities) attract administrative and institutional functions, as centres of military and fiscal activities. While these are somewhat broad, they can serve as a rough typological guide for urban centres in the late ancient world, and they are not exclusive, since the vast majority of larger and middling cities represent a mixture of all three elements.

As many studies have now shown, there had been a slow process of transformation in the pattern of late Roman urban society over the centuries preceding both the Persian wars and the Arab Islamic conquests. Although archaeological surveys and excavations demonstrate a revival in the fortunes

37 For a good comparative overview and analysis, see Wickham, *Framing the early Middle Ages*, pp. 591–692.

of many eastern cities in the later fifth and early sixth centuries, accompanied by substantial investment in public and private buildings, often on a monumental scale, they also show an almost universal tendency for cities to lose many of the features familiar from their classical structure – the lesser provincial towns first, followed at a somewhat later date, and influenced also by the extent to which the government intervened to assist them, by the larger, economically and politically more important centres. Major public buildings fell into disrepair, systems of water supply were often abandoned (suggesting a drop in population), rubbish was dumped in abandoned buildings, major thoroughfares were built on. These changes may not necessarily have involved any substantial reduction in economic or exchange activity in cities, and they happened at differentiated rates across the different provinces of the empire according to local economic and political conditions. The construction of defensive walls around many cities during the fifth and sixth centuries has generally been interpreted as a shrinkage of occupied areas of many cities, but this may not always have been the case.³⁸ On the other hand, the undoubted decline in the maintenance of public structures or amenities in the major, traditional Hellenistic Roman cities – baths, aqueducts, drains, street surfaces, walls – does suggest a major shift in aspects of urban living, and of finance and administration in particular. The period after the arrival of the great Justinianic plague in the 540s is especially marked in this respect. But this shift is partly balanced by evidence for a considerable and widespread investment in church building (and related structures) of all kinds. An additional factor was the evolution of a more complex hierarchy of urbanism as many functions of the older cities began to be shared from the fourth century by smaller centres, often fortified, and often the focus of military or civil administration as well as of local exchange and production for their localities.³⁹

Many older provincial cities, where they played a role in imperial civil or military structures, changed to conform to this pattern – from the later fourth

38 H. Vanhaverbeke, F. Martens, M. Waelkens and J. Poblome, 'Late Antiquity in the territory of Sagalassos', in Bowden, Lavan and Machado (eds.), *Recent research*, at p. 253 (Sagalassos); T. Gregory, 'Fortification and urban design in early Byzantine Greece', in R. L. Hohlfelder (ed.), *City, town and countryside in the early Byzantine era* (New York, 1982) (Corinth and other Greek cities).

39 A. W. Dunn, 'Heraclius' "reconstruction of cities" and their sixth century Balkan antecedents', in *Acta XIII Congressus Internationalis Archaeologiae Christianae*, Studi di Antichità Cristiana 54 (Vatican City and Split, 1998); A. W. Dunn, 'Continuity and change in the Macedonian countryside from Gallienus to Justinian', in Bowden, Lavan and Machado (eds.), *Recent research*; Morrisson and Sadini, 'The sixth century economy', pp. 179–81. See in particular the essays in J. Henning (ed.), *Post Roman towns, trade and settlement in Europe and Byzantium*, vol. II. *Byzantium, Pliska, and the Balkans*, Millenium Studien 5/2 (Berlin and New York, 2007).

and fifth centuries in the Balkans, somewhat later in less exposed parts of the eastern empire. Their evolution on imperial territory into the typical middle Byzantine *kastron* is not difficult to follow. But the path that urban development would take thereafter is determined also by the political histories of the areas in question. While they share a common late Roman heritage, the fate of towns in territories remaining to the empire after the middle of the seventh century was very different from that of the towns and cities that were in Islamic territory, for example – a reflection of the beleaguered and impoverished situation of the eastern Roman or Byzantine empire in the seventh and eighth centuries.

There was a series of interconnected factors in this long term process. The partial confiscation of city lands which was made almost complete under Valens (r. 364–78) and Valentinian (r. 364–75) and then finalised under Justinian (r. 527–65), and a consequent decline in the independent economic resources of cities, was clearly important. An increasing level of intervention by imperial officials in local financial matters, culminating in the establishment of the *vindices* under Anastasius and the stipulations on civic building by Justinian, likewise played a key role. Significant changes in the relationship between the wealthier *curiales* and local magnates, on the one hand, and the less well off, on the other, the so called ‘decline’ of the curial order in general, also had an impact on the administrative and social function of cities. Cities as *corporate bodies* were less well off than they had been before about the middle of the sixth century. But this did not mean that urban life declined, or that towns no longer fulfilled their role as centres of exchange and production. Indeed, the literary sources and the archaeological record show that commercial activity continues into the seventh century. The Church was also from the fourth century a competitor with the city for the consumption of resources, especially with the increasing importance of the bishop in local and provincial affairs and government. Citizens, particularly the wealthy, continued to donate funds or buildings to their cities, but this can hardly have compensated for the corporate loss of resources.

Archaeological investigation has revealed an increasing localisation of exchange activity from the later sixth century, although this does not have to mean a change in the role of cities as centres of such exchange. The Roman state had quite deliberately during the third, fourth and fifth centuries followed a policy of ‘rationalising’ patterns of distribution of cities. Many cities in over densely occupied regions were deprived of the status and privileges of city, while others which were of importance to the state in its fiscal administrative structure were ‘incorporated’ and received city status for the first time. This had nothing to do with economic interests, but reflected

rather the desire of the emperors to establish a network of centres adequate to the demands of the fiscal system. Considerable numbers of the 'cities' that were suppressed in this process had been little more than villages representing the autonomous or semi autonomous communities of the pre Roman states incorporated into the empire. By endowing certain settlements with city status and, more especially, with local fiscal administrative functions and responsibility, the state assured such cities of their continued existence and at the same time enhanced their local importance. It is a logical concomitant that, when the elites in such communities were no longer able adequately to fulfil this role for the state, and when the state began to supervise city fiscal affairs directly, the continued existence of such cities would become a matter of indifference to the central government, at least in functional terms. Within the bounds of the Roman world, it was the ideological and symbolic importance of cities and urban culture, expressed through imperial involvement in urban building and renewal in several cases, that prevented this happening at this stage. In addition, cities particularly associated with Christianity through a local saint's cult, for example enhanced their chances of flourishing where they did not already possess a primary economic character (Euchaita and Resafa (al Ruṣāfa) are cases in point).⁴⁰

Yet in spite of any general tendencies which can be said to mark the development of cities and urban economies in the fifth to early seventh centuries, strong regional variations have been detected in the archaeological record and, in particular, a divergent trend between Anatolia and the European provinces of the empire, on the one hand, and Syria Palestine and Egypt, on the other. In addition, while Syria and Palestine, with Egypt and possibly the North African provinces, continued to flourish well into the seventh century and beyond, much of Anatolia and the Balkans was suffering from economic contraction, urban recession and demographic decline by the mid sixth century. As we have seen, there is also some evidence that northern Syria also experienced a different rate of change, beginning somewhat earlier, from the areas to the south.⁴¹ If this interpretation of the available evidence is accepted, it has important implications

⁴⁰ For Euchaita, see A. P. Kazhdan *et al.*, *The Oxford dictionary of Byzantium* (Oxford and New York, 1991), p. 737; for Resafa (Sergiopolis), see pp. 1877f.

⁴¹ See Morony, 'Economic boundaries?', pp. 178–80, with literature, following Ward Perkins, 'Specialised production and exchange', pp. 354–61, and Morrisson and Sodini, 'The sixth century economy', pp. 190–3, where the evidence and further literature are summarised; and now Wickham, *Framing the early Middle Ages*, pp. 613–34. For continuing prosperity and expansion in many areas of southern Syria and in Palestine beyond the middle of the seventh century, see now Magness, *Early Islamic settlements in Palestine*.

for the early stages of Islamic political development and the economies of the conquered territories.

Finally, the pattern of village communities in the eastern Roman world likewise varied from region to region, but in general it is the case that the vast majority of urban centres served as central places and thus also as markets for their surrounding districts and, until substantial changes occurred during the middle and later seventh century in what remained under imperial control in Anatolia and the Balkans, rural communities. Villages and more isolated farmsteads proliferated and there appears to have been a considerable expansion of such rural habitats across the late Roman world in the east from the fourth and in particular from the fifth century, associated with both a recession in villa type estates and farms and a shift in the hierarchy of settlement towards an increase in the number and density of what have been referred to as 'secondary', often fortified, towns with their adjacent and 'dependent' villages.⁴² This pattern seems to be found from the fifth into the seventh centuries in the Konya plain in central Anatolia, and in the territory of Sagalassos in Pisidia; in the southern Ḥawrān, the Decapolis and central Jordan plain and southern Jordan;⁴³ and elsewhere.⁴⁴

Sasanian cities and urbanism

Cities and urban centres in the Sasanian world occupied a somewhat different role in the structure of the state, although they were similar in respect of some

42 Morrison and Sodini, 'The sixth century economy', pp. 175–9 provides a brief summary with literature.

43 See D. Baird, 'Settlement expansion on the Konya plain, Anatolia: 5th–7th centuries AD', in Bowden, Lavan and Machado (eds.), *Recent research*; Vanhaverbeke *et al.*, 'Late Antiquity in the territory of Sagalassos' (Sagalassos territory); P. L. Gatier, 'Villages du Proche Orient protobyzantin (4^{ème}–7^{èmes.}): Étude régionale', in G. R. D. King and A. Cameron (eds.), *The Byzantine and early Islamic Near East*, vol. II: *Land use and settlement patterns* (Princeton, 1994) (north Syria); H. I. MacAdam, 'Settlements and settlement patterns in northern and central Transjordan, ca. 550–750', in King and Cameron (eds.), *Land use and settlement patterns*; and R. Schick, 'The settlement pattern of southern Jordan: The nature of the evidence', in King and Cameron (eds.), *Land use and settlement patterns*.

44 For central Syria and the limestone massif, see H. Kennedy and J. H. W. G. Liebeschuetz, 'Antioch and the villages of northern Syria in the 5th and 7th centuries: Trends and problems', *Nottingham Medieval Studies*, 32 (1988); C. Foss, 'The Near Eastern countryside in Late Antiquity: A review article', in Humphrey (ed.), *Some recent archaeological research*; for Lycia, Isauria and Cilicia see C. Foss, 'The Lycian coast in the Byzantine age', *Dumbarton Oaks Papers*, 48 (1994); S. Mitchell, *Anatolia: Land, men and gods in Asia Minor*, vol. II: *The rise of the Church* (Oxford, 1993); for Macedonia, see Dunn, 'Continuity and change in the Macedonian countryside'; for Greece, see S. Alcock, *Graecia capta: The landscapes of Roman Greece* (Cambridge, 1993); A. Avramea, *Le Péloponnèse du IV^e au VIII^e siècle: Changements et persistance* (Paris, 1997). See now the essays in J. Lefort, C. Morisson and J. P. Sodini (eds.), *Les villages dans l'empire byzantin (IV^e–XV^e siècle)* (Paris, 2005).

of their social and economic functions. They can be divided, very crudely, into two major types: those of the rich agricultural lands of Mesopotamia and Iraq; and those on the plateau and further east or north. One important difference between Roman and Sasanian cities, however, lies in the absence from the latter of the leading elements of the social elite, who seem to have preferred to live on their estates outside the towns, a social and cultural tradition that pre dates the formation of the Sasanian royal state, and which may itself also be reflected in the pattern of royal residences.⁴⁵ Another is the absence from Sasanian urban centres, with a few exceptions, of major centres of Zoroastrianism – some of the most important fire temples, for example, seem generally located away from towns, and often in remote areas.⁴⁶ Yet Sasanian cities did possess their own fire temples, and they certainly housed an elite – indeed, the city elites, as reflected in a text such as the late sixth century Syriac *History of Karka* (near mod. Kirkuk in northern Mesopotamia), were clearly vital to the ways Sasanian urban centres functioned and appeared.⁴⁷ Archaeological investigation of urban centres remains in many ways in its early stages, since generally accepted ceramic typologies and chronologies which make comparison across several such settlements in different regions of the empire possible have yet to be established for more than a few sites,⁴⁸ while many sites which have been excavated were examined without reference to the Sasanian levels.⁴⁹ Nevertheless, a number of regional surveys and comparisons have been carried out which permit admittedly broad generalisations about the areas in question to be made, and can be used to balance the textual evidence. At the same time, the textual evidence for

45 On the evidence for Sasanian cities and towns, see in particular Hugh Kennedy, 'From Shahrīstan to Medina', *SI*, 102, 3 (2006). For an example of what may be a noble residence in a rural location, see M. Arzanoush, *The Sasanian manor house at Hajjiabad* (Florence, 1994).

46 See K. Schippmann, *Die iranischen Feuerheiligtümer* (Berlin, 1971); M. Arzanoush, 'Fire temple and Anahita temple: A discussion on some Iranian places of worship', *Mesopotamia*, 22 (1987); M. G. Morony, *Iraq after the Muslim conquest* (Princeton, 1984; repr. Piscataway, NJ, 2006), pp. 283–4.

47 See J. M. Fiey, 'Vers la réhabilitation de l'Histoire de Karka d'Beit Sloh', *Analecta Bollandiana*, 82 (1964). The text is edited by P. Bedjan in *Acta martyrum et sanctorum*, 7 vols. (Paris and Leipzig, 1890–7), vol. II.

48 R. M. Adams, 'Tell Abu Sarifa: A Sassanian Islamic ceramic sequence from south central Iraq', *Ars Orientalis*, 8 (1970), pp. 117–18; St J. Simpson, 'Partho Sasanian ceramic industries in Mesopotamia', in I. Freeston and D. Gaimster (eds.), *Pottery in the making: World ceramic traditions* (London, 1997). See also the essays in D. Kennet and P. Luft (eds.), *Recent advances in Sasanian archaeology and history*, BAR Int. Ser. (forthcoming).

49 See St J. Simpson, 'From Tekrit to the Jaghjagh: Sasanian sites, settlement patterns and material culture', in K. Bartl and S. R. Hauser (eds.), *Continuity and change in northern Mesopotamia from the Hellenistic to the early Islamic period* (Berlin, 1996). The problem lies partly in the nature of the evidence for construction which, as Kennedy notes ('From Shahrīstan to Medina'), was largely of brick, mud brick and wood, so that few stone structures survive, in great contrast to the Roman cities of the eastern provinces.

the history of Iranian cities and urbanism during the late Sasanian era has to be derived almost entirely from later Islamic sources, which inevitably brings with it a series of methodological issues.⁵⁰

It has for some time been established that there was a considerable expansion of irrigation systems in the fifth and especially sixth centuries, particularly associated with the reign of Khusrau I (531–79 CE), and concentrated in Iraq and Oman. These have been taken to imply increasing population, an absolute as well as a relative increase in production, and expanding urbanism.⁵¹ In Mesopotamia and the western lands many of the most important urban centres were Hellenistic foundations, often constructed on or around pre-Hellenistic centres, but bearing many of the hallmarks of the *polis* familiar from the Roman and Hellenistic worlds. Such centres were foci of commerce and exchange as well as administration, and also housed substantial populations involved in the local agrarian economy, as did the majority of provincial cities in the Roman world. Yet the Sasanian world in general appears to have experienced a slow demographic downturn from the later third century onwards, as settlement surveys and sherd distribution analysis would seem to suggest; while the ceramic surveys of many of these sites and their hinterlands intimate that, while they continued to flourish into the fourth century, a recession set in towards the end of the fourth century which lasted through most of the fifth and into the sixth century, followed in many – but not all cases by a recovery in the second half of the sixth century or a little later. This appears to be the case both in Mesopotamia, at some of the sites associated with Tesfon (Ctesiphon), where evidence of severe and repeated flooding and gradual abandonment of some quarters has been identified, and an overall shrinkage of the city from the fourth into the later sixth century,⁵² as well as on

50 See, for example, T. Daryaei (ed., trans. and comm.), *Šahrestānīhā ī Ērānšāhr: A middle Persian text on late antique geography, epic and history* (Costa Mesa, 2002), the core of which derives from sixth and early seventh century material, but which was recopied and interpolated at a much later date. See also J. Markwart, *A catalogue of the provincial capitals of Ērānshahr*, ed. G. Messina (Rome, 1931); and R. Gyselen, 'Les données de géographie administrative dans le "Šahrestānīhā ī Ērān"', *Studia Iranica*, 17 (1988). See Kennedy, 'From shahrīstān to medina'.

51 For example, Adams, *Heartland of cities*, pp. 179–83, 209–11; Morony, 'Economic boundaries?', pp. 183f.; Morony, *Iraq after the Muslim conquest*, pp. 156–7. But see also M. Morony, 'Land use and settlement patterns in late Sasanian and early Islamic Iraq', in King and Cameron (eds.), *Land use and settlement patterns*, pp. 225f. for the methodological issues associated with the results of surface pottery surveys. See also, and in general on the expansion of irrigation schemes, Christensen, *The decline of Iranshahr*.

52 R. V. Ricciardi, 'The excavations at Choche', *Mesopotamia*, 5–6 (1970–1); M. Cavallero, 'The excavations at Choche (the presumed Ctesiphon), Area 2', *Mesopotamia*, 1 (1966). Choche is in fact Veh Ardashīr.

the Iranian plateau, at sites such as Bard i Neshāndeh and Masjid i Soleimān;⁵³ in Khuzistān, at Qaṣr i Abu Naṣr and Susa;⁵⁴ and in Fārs, at Iṣṭakhr or Naqsh i Rustam, in these cases based on the numismatic material.⁵⁵ Although evidence for the continued expansion of the irrigation networks in Mesopotamia, the Diyālā basin and Khuzistān, and for royal sponsorship of major urban projects and new foundations in the period from the later third to the later sixth centuries, might suggest that these cities should have been flourishing economically, this seems problematic in the light of the ceramic and numismatic material which, as it is currently understood, appears to show a decline in urban fortunes during the fifth century, followed in the middle and later sixth by a limited recovery. The targeted deportation of Roman urban and rural populations from Syria and Mesopotamia from the fourth century onwards especially may perhaps also reflect these conditions.⁵⁶

Cities had an important administrative and governmental role, as well as, in many cases, a military character, although they inevitably also attracted market activity and trade and, where their local hinterlands offered the necessary resources, substantial populations. Royal investment in cities in all the fertile and heavily irrigated western zones certainly involved the deliberate transplantation of substantial populations carried off from Roman cities in northern and central Syria, who brought with them artisanal, industrial and construction skills and knowledge, as well as some horticultural and agricultural expertise (in oleoculture, for example). The frequently circular or orthogonal plans of many Sasanian cities in Mesopotamia and Fārs implies a degree of central planning, or at least of an established or approved model for the establishment of towns. But this investment seems also to have involved the movement of substantial elements of the rural population into the urban

53 R. Ghirshman, *Terrasses sacrées de Bard e Nechandah et Masjid e Solaiman*, Mémoires de la Délégation Archéologique en Perse 45 (Paris, 1976), pp. 135, 143.

54 D. Whitcomb, *Before the roses and nightingales: Excavations at Qasr i Abu Nasr, Old Shiraz* (New York, 1985), p. 104 (with fig. 3); R. N. Frye, *Sassanian remains from Qasr i Abu Nasr: Seals, sealings and coins* (Cambridge, MA, 1973), p. 26 (Qasr i Abu Naṣr); R. Boucharlat, 'Suse à l'époque sasanide', *Mesopotamia*, 22 (1987), at pp. 358–9 (Susa). But see also D. Kennet, 'The decline of eastern Arabia in the Sasanian period', *Arabian Archaeology and Epigraphy*, 18 (2007), pp. 115 n. 123, 118 n. 258 for some ambiguities with dating.

55 Whitcomb, *Before the roses and nightingales*, fig. 4 (heavy bias towards coins of Khusrau II with a very small proportion of earlier issues).

56 Brunner, 'Geographical and administrative divisions', pp. 758–62; Morony, *Iraq after the Muslim conquest*, esp. pp. 277ff.; A. Oppenheimer, *Babylonia Judaica in the Talmudic period*, Beihefte zum Tübinger Atlas des Vorderen Orients, B 47 (Wiesbaden, 1983), pp. 179–236; Boucharlat, 'Suse à l'époque sasanide', pp. 362–4. For population deportations, see Morony, 'Population transfers'; E. Kettenhofen, 'Deportations II: In the Parthian and Sasanian periods', in E. Yarshater (ed.), *Elr*, VII (Costa Mesa, 1994) and see also chapter 3 below.

centres, which were often very extensive: ceramic surveys in several regions suggest a reduction in the total number of rural settlements, accompanied by the construction or development of fewer but much larger urban centres.⁵⁷ Apart from the well known cases from Mesopotamia,⁵⁸ the Diyālā basin and Khuzistān, other examples have now been identified, for example in the central Zagros region near the modern village of Firuzābād.⁵⁹ In the Dāmghān plain survey work has identified no obvious signs of population expansion in the later Sasanian period, but there does appear to have been a concentration of population in fewer and larger centres.⁶⁰ It is also clear that some of the very large new foundations were never fully occupied within their walls – this seems to have been the case with Jundishāpur and Ivan i Karkhah on the Susiana plain in Khuzistān, for example,⁶¹ although it is less pronounced in other, similar urban centres in other regions such as Luristān, east of central Mesopotamia.⁶² Nevertheless, this tendency, at least in those regions where major state sponsored urban development took place, is the reverse of what was happening in the Roman countryside.⁶³ Together with the evidence for regionalised urban recession, it suggests that the economy was not without its problem areas,⁶⁴ even if the state was still able to extract a substantial amount of resources through the tax system, especially after the reforms of Khusrau I.

Mesopotamia profited from its geographical position, lying as it did between the wealthy provinces of Roman Mesopotamia and Syria, the trading routes east through the Indian Ocean and westwards to the east coast of Africa, the Central Asian steppes and, ultimately, China. The caravan cities or

57 D. Metzler, *Ziele und Formen königlicher Innenpolitik im vorislamischen Iran* (Münster, 1977), esp. pp. 177ff.

58 See Adams and Nissen, *The Uruk countryside*, pp. 59–63 for the Uruk district; Adams, *Heartland of cities*, pp. 179–85; St J. Simpson, 'Mesopotamia in the Sasanian period: Settlement patterns, arts and crafts', in J. Curtis (ed.), *Mesopotamia and Iran in the Parthian and Sasanian periods: Rejection and revival c.238 BC AD 642* (London, 2000); but see also Howard Johnston, 'The two great powers', p. 200 n. 91.

59 Abdi, 'Archaeological research in the Islamabad plain'; K. Abdi, 'Islamabad 1999', *Iran*, 38 (2000).

60 Trinkaus, 'Pre Islamic settlement and land use', pp. 133–40, 144; K. M. Trinkaus, 'Settlement of highlands and lowlands in early Islamic Dāmghān', *Journal of Persian Studies*, 23 (1985), pp. 130, 136–7.

61 A. Moghaddam and N. Miri, 'Archaeological research in the Mianab Plain of lowland Susiana, south western Iran', *Iran*, 41 (2003), pp. 104–5; Wenke, 'Western Iran in the Partho Sasanian period', pp. 255–6; Adams, *The land behind Baghdad*, pp. 115–16.

62 J. A. Neely, 'Sassanian and early Islamic water control and irrigation systems on the Deh Luran plain, Iran', in T. E. Downing and M. Gibson (eds.), *Irrigation's impact on society* (Tucson, 1974).

63 See Wenke, 'Imperial investments', esp. pp. 131–9.

64 See Howard Johnston, 'The two great powers', p. 203.

ports along these routes also gained from the demand created by the markets of these cities and the royal court and its retinues: Marw,⁶⁵ Balkh, Samarqand and other cities of Khurāsān and Transoxania in the north east (although also exposed to hostile activity from various nomadic peoples to the north), the cities of Khuzistān and Fārs along the southern route, and Hormuz and Sīrāf on the Persian Gulf.⁶⁶ In contrast, the cities of the Iranian plateau and of the eastern and south eastern provinces were on the whole less fortunately placed, maintained chiefly through locations offering adequate water supplies, supplemented in the great majority of cases by *qanāts* and related irrigation systems, and owing their vitality to a combination of both administrative and military (defensive) functions with which they were endowed by the state,⁶⁷ although the ports of the south east were important links in the commercial chain that stretched along the coast towards India.⁶⁸ This does not mean that the cities of the plateau and mountain fringes were either culturally or economically unimportant – on the contrary, major towns such as Iṣṭakhr, Iṣfahān, Hamadhān or Rayy, along with many others in the west and north, or Bela, Panjgur and Quzdar in the south east, were centres of communications and commerce, in many cases had a vibrant local economy (the hinterland of Iṣfahān, for example, was famed for its grain production, and indeed the major centres around the desert fringes with which this city was connected by road were in general at the centre of relatively rich agricultural districts), and were located in relatively rich agricultural districts whose productivity was increased by extensive irrigation schemes.⁶⁹

The political and administrative role of cities in the Sasanian empire is still poorly understood, although it is clear from the *Šahrestānīhā ī Ērānšāhr* that

65 See T. Williams, K. Kurbansakhatov *et al.*, 'The ancient Merv project, Turkmenistan: Preliminary report on the second season (2002)', *Iran*, 41 (2003).

66 D. Whitehouse and A. Williamson, 'Sasanian maritime trade', *Iran*, 11 (1973); Howard Johnston, 'The two great powers', pp. 204–5; Brunner, 'Geographical and administrative divisions', pp. 755–7, 771–2; M. Tampoe, *Maritime trade between China and the west: An archaeological study of the ceramics from Sīrāf (Persian Gulf), 8th to 15th centuries AD* (Oxford, 1989), p. 2; T. Daryaei, 'Sources for the economic history of late Sasanian Fārs', in R. Gyselen and M. Szuppe (eds.), *Matériaux pour l'histoire économique du monde iranien* (Paris, 1999), pp. 135–8, 144–5; T. Daryaei, 'The Persian Gulf trade in Late Antiquity', *Journal of World History*, 14, 1 (2003); R. N. Frye, 'Byzantine and Sasanian trade relations with northeastern Russia', *Dumbarton Oaks Papers*, 26 (1972).

67 See R. N. Frye, 'The Sasanian system of walls for defense', in M. Rosen Ayalon (ed.), *Studies in memory of Gaston Wiet* (Jerusalem, 1977); A. Christensen, *L'Iran sous les Sassanides* (Copenhagen, 1944), p. 287.

68 Howard Johnston, 'The two great powers', pp. 206–10 for a useful survey of six such cities: Iṣṭakhr, Bishāpur, Qaṣr ī Abu Naṣr, Iṣfahān, Sīstān and Ganzak. See also Brunner, 'Geographical and administrative divisions', pp. 750–3, 767.

69 Brunner, 'Geographical and administrative divisions', pp. 771–7.

they had both symbolic and ideological importance as well as administrative and fiscal significance.⁷⁰ It is also apparent from the surveys that have been carried out and from extant remains that many cities in the provinces, particularly along the northern and north eastern fringes, served as significant military centres, with well maintained fortresses either within the walls or closely associated with them.⁷¹ Marw was an especially important centre on the north eastern front, serving both as a control point for trade beyond the borders of the empire and as a major strategic centre. It seems clear that Sasanian kings pursued from the beginning a long term policy of political centralisation, even if they were checked in much of their endeavour by the power of the Iranian landed elite or aristocracy, at least until the time of Khusrau I.⁷² This policy was effected in part through the establishment of new royal cities, with their territories under centrally appointed officials, largely on territory that became part of the royal domain (*dastkart*).⁷³ Where refoundation or royal intervention affected the older Hellenistic foundations, particularly in the western parts of the empire, then their older civic institutions, including the role of the council and urban elite landowners, appears to have been superseded by the royal appointments and the installation of an administrative establishment responsible either to the provincial governor or directly to the king.⁷⁴ The evidence suggests that by the sixth century the state's fiscal administration was based at three levels, not dissimilar from the praefectural, provincial and civic levels in the Roman state, with state officials responsible in each city (perhaps to be identified with the reference to the *ummāl al harāj* of later Arabic accounts, a group of notables, perhaps local urban aristocrats, associated with the *dihqāns* of the cities) for the supervision of the assessment and collection of taxes in kind and in money, responsible in

70 The text seems to date in its final form from the 'Abbāsid period, but seemingly represents the geographical extent of Sasanian authority during the later reign of Khusrau II, since it includes the cities of Roman Syria, as well as the Arabian Peninsula. But it is based in part on older material from the earlier sixth century: see Daryaei, *Šahrestānīhā ī Ērānšāhr*, pp. 1–11.

71 See Kennedy, 'From shahristan to medina'; and A. Petruccioli, *Bukhara: The myth and the architecture* (Cambridge, MA, 1999), p. 49.

72 R. N. Frye, 'The political history of Iran under the Sasanians', in E. Yarshater (ed.), *The Cambridge history of Iran*, vol. III: *The Seleucid, Parthian and Sasanian periods* (Cambridge, 1983); Howard Johnston, 'The two great powers', pp. 158–64.

73 Morony, *Iraq after the Muslim conquest*, pp. 68–9; and P. Gignoux, 'Aspects de la vie administrative et sociale en Iran du 7^{ème} siècle', in R. Gyselen (ed.), *Contributions à l'histoire et la géographie historique de l'empire sassanide*, Res Orientales 16 (Bures sur Yvette, 2004). But see Howard Johnston, 'The two great powers', p. 215, n. 127.

74 V. G. Lukonin, 'Political, social and administrative institutions: Taxes and trade', in Yarshater (ed.), *The Seleucid, Parthian and Sasanian periods*, pp. 724–6.

turn to the next senior official at district level, and then beyond to the provincial instance.⁷⁵ The sigillographic evidence further suggests an effectively centralised administrative apparatus by the fifth century, if not from the very beginning under Ardashīr I (r. 224–40 CE), upon which Kawād I (r. 488–96, 499–531 CE) began to build in the late fifth and early sixth centuries, and which was the basis for the much more widespread reforms introduced under Khusrau I. These not only increased the efficiency of the whole fiscal apparatus and the methods of assessing and collecting taxable revenues, but also successfully challenged the power of the elite by limiting their access to resources and their political and economic independence – although it is entirely unclear as to how long after Khusrau's reign the effects of the reforms and the new arrangements they introduced were maintained. The strength of the Iranian merchant elite must also have played a role in these matters.⁷⁶ While there remains considerable disagreement among historians as to the exact import of Khusrau I's reforms, and the administrative apparatus of the state, it is clear that cities, as centres for local administration and taxation, and regardless of their size, were absolutely fundamental elements in Sasanian rule, and that the focus of Sasanian elite society, with the possible exception of the very highest levels of the aristocracy, was firmly anchored within them even if we should beware of assuming too much uniformity across the provinces beneath the umbrella of the royal administration.⁷⁷

75 See Christensen, *L'Iran sous les Sassanides*, pp. 113–16, 122–6, 132–40; Lukonin, 'Political, social and administrative institutions', pp. 681–746; R. Gyselen, *La géographie administrative de l'empire sassanide: Les témoignages sigillographiques* (Paris, 1989); R. Gyselen, *Nouveaux matériaux pour la géographie historique de l'empire sassanide: Sceaux administratifs de la collection Ahmad Sa'edi*, *Studia Iranica* 24 (Paris, 2002) (especially for the sigillographic evidence for administrative structures); J. Wiesehöfer, *Ancient Persia from 550 BC to 650 AD* (London and New York, 1996), pp. 186–91. See also A. D. H. Bivar, *Catalogue of the western Asiatic seals in the British Museum. Stamp seals, vol. II: the Sassanian dynasty* (London, 1969); and R. Göbl, *Die Tonbullen vom Tacht-e Suleiman: Ein Beitrag zu spätsasanidischen Sphragistik* (Berlin, 1976), for seals and discussion, with the additional remarks of Howard Johnston, 'The two great powers', pp. 216–18; G. Gnoli, 'The quadripartition of the Sasanian empire', *East and West*, 35 (1985), pp. 1–15; R. Gyselen, *The four generals of the Sasanian empire: Some sigillographic evidence* (Rome, 2001); and Gignoux, 'Aspects de la vie administrative et sociale'. For the tax officials, see F. Altheim and R. Stiehl, 'Die Lage der Bauern unter den späten Sassaniden', in J. Herrmann and I. Sellnow (eds.), *Die Rolle der Volksmassen in der Geschichte der vor-kapitalistischen Gesellschaftsformationen* (Berlin, 1975), p. 82.

76 E. de la Vaissière, *Sogdian traders: A history* (Leiden and Boston, 2005), pp. 227–32; Banaji, 'Precious metal coinages and monetary expansion', pp. 285–6.

77 See Morony, *Iraq after the Muslim conquest*, pp. 27–32, 51–6, 99–111, 125–64; Howard Johnston, 'The two great powers', pp. 211–23; and on Khusrau's reforms, Z. Rubin, 'The reforms of Khusro Anushirwān', in Cameron (ed.), *States, resources and armies*, with previous literature; and Wiesehöfer, *Ancient Persia*, pp. 190–1. For administrative and

The great emphasis placed upon cities can be explained at least in part as an effort to maximise and maintain some central control over resources, always an issue in states with substantial elites and extensive territory. If the evidence of movement or concentration of population in such centres has been correctly interpreted, therefore, then the bulk of the populace of these large cities must have been peasants, so that the cities served in effect as vast collection points for the payment of taxes. The locations of administrative centres, residential quarters, religious foci and public spaces such as markets all remain poorly understood, although some substantial structures of monumental proportions have been located and associated with administrative functions;⁷⁸ while royal palaces and related monumental or other structures both within and outside urban contexts have received a great deal of attention.⁷⁹ The *History of Karka* makes it clear that local urban elites invested considerable effort in the maintenance and improvement of the major public and private buildings in their towns, and the limited archaeological evidence bears this out.⁸⁰ The relationship of streets to the frontages of what appear to be residential and artisanal quarters at Khoke (Choche), a suburb of Ctesiphon, appears to be not unlike that of some of the late antique towns of Syria, and in this respect determined to some extent the ensuing Islamic patterns of urban space, although at Qaşr i Abu Naşr and Marw far less regular, unpaved streets with lanes leading off to either side seem to have been the norm.⁸¹ Study of the layout of domestic dwellings is still in its infancy, although substantial urban residences as well as humbler dwellings have been excavated at Tell Baruda at Ctesiphon, at Seleucia, at Susa (where what appear to be major aristocratic residences have been identified), and at Dura Europos, styles which represent the traditional Mesopotamian patterns, while a different regional architectural tradition in domestic architecture has been identified from the Sasanian levels at

social centrality see the *Sirat Anushirvan*, trans. in Grignaschi, 'Quelques specimens de la littérature sassanide', p. 20; and for administrative diversity see Gyselen, *Nouveaux matériaux pour la géographie historique*, pp. 28ff.

78 At early Sasanian Susa, for example: Boucharlat, 'Suse à l'époque sasanide', p. 358.

79 See the summary with literature in Wiesehöfer, *Ancient Persia*, p. 162; D. Huff, 'Zur Rekonstruktion des Turmes von Firuzabad', *Istanbuler Mitteilungen*, 19 20 (1969 70), pp. 319ff.

80 A point made by N. Pigulevskaya, *Les villes de l'état iranien aux époques parthe et sassanide* (Paris, 1963), see esp. pp. 141ff.

81 See Ricciardi, 'The excavations at Choche'; Whitcomb, *Before the roses and nightingales*, pp. 87 110; G. Herrmann, K. Kurbansakhatov *et al.* (eds.), 'The International Merv Project: Preliminary report on the fifth season (1996)', *Iran*, 35 (1997), pp. 1 33; see also the report for 1997 in *Iran*, 36 (1998), pp. 53 75.

Marw.⁸² Institutional structures have, for the most part, not yet been properly recognised except through aerial survey and guesswork,⁸³ although what may be an early Sasanian governor's residence – a substantial colonnaded courtyard building – has been tentatively identified at Susa.⁸⁴

Apart from the known fact of the transplantation of captive Roman urban populations, the question arises why the state should also have transferred substantial numbers of people away from their rural habitats into larger urban settings – if this is indeed how the evidence should be interpreted. Several hypotheses have been advanced, for the most part associating the change with an assumed desire or need to exercise greater supervision or control over resources, to enhance productive output and to increase market exchange. But in the first case it remains unclear why this particular policy would have been any more effective than maintaining a regular supervision of taxpayers through local landlords or notables – the *dihqāns* – which was the traditional means and must have continued to be the case in all those areas where such concentrations of population did not take place.⁸⁵ It has already been pointed out that distancing the agrarian producers more than a few hours from their fields and irrigation systems which, at field and farm level needed constant maintenance and care, would be counter productive – indeed, would seriously damage the infrastructure necessary to maintain production in the first place.⁸⁶ The very partial nature of the archaeological record suggests that, for the moment, any conclusions based upon it should be seen as somewhat premature.

In comparison with what can be said about the evolution of cities, towns and the countryside in the late Roman east (including the Balkans), therefore, we remain very much in the dark about comparable developments in the Sasanian world. As we have seen, some have argued that there took place a

82 G. Herrmann, K. Kurbansakhatov and St J. Simpson (eds.), 'The International Merv Project: Preliminary report on the eighth year (1999)', *Iran*, 38 (2000), pp. 2–5. For the domestic structures at Ctesiphon, see R. V. Ricciardi and M. Ponzi Mancini, 'Choche', in E. Quarantelli (ed.), *The land between two rivers: Twenty years of Italian archaeology in the Middle East. The treasures of Mesopotamia* (Torino, 1985), pp. 100–4; and for Susa, see Boucharlat, 'Suse à l'époque sasanide'; and M. Kervran, 'Transformations de la ville de Susa et de son économie de l'époque sasanide à l'époque abbasside', *Paléorient*, 11 (1985), pp. 91–100.

83 See R. W. Bulliet, 'Medieval Nishapur: A topographic and demographic reconstruction', *Studia Iranica*, 5 (1976), p. 67f.; Whitcomb, *Before the roses and nightingales*.

84 Boucharlat, 'Suse à l'époque sasanide', p. 358. For some discussion see P. Wheatley, *The places where men pray together: Cities in Islamic lands, seventh through the tenth centuries* (Chicago, 2001).

85 Morony, *Iraq after the Muslim conquest*, pp. 106–7, 11–13; F. Altheim and R. Stiehl, *Finanzgeschichte der Spätantike* (Frankfurt, 1957), pp. 57–9, 75–6; Christensen, *L'Iran sous les Sassanides*, pp. 112–13.

86 Wenke, 'Imperial investments', pp. 144–53.

reduction in population and thus the size of many large cities in the region in the early seventh century, a result of a combination of natural disasters (pestilence, flooding) and, in conditions of warfare and internal political unrest in the later 620s and 630s, the breakdown or at least lack of state supported maintenance for the large irrigation networks. But the interpretation of the evidence on which this is based has been challenged, and the issue remains unresolved because of the absence of closer internal investigation of urban sites as well as reliably dated ceramic sequences from the surveys in question, and a lack of survey material as such from a wide enough range of samples.⁸⁷

It is perhaps possible, however, to bring these developments into association with a range of other factors, in particular the possibility that they were a response to a long term and incremental climatic change. We have already noted that there was a shift towards cooler climatic conditions from approximately the later fourth or early fifth century, lasting until the later eighth century. Now it is worth noting that the extensive irrigation systems of Mesopotamia and Khuzistān in particular must have been intended to support winter rainfall agriculture, ensuring thereby the regularity of two crops per year (which would have been essential to the cultivation of rice, which is both water and labour intensive).⁸⁸ There is no reason to doubt that such a regularly high level of production per capita would lead to a demographic increase, higher demand for produce, enhanced market exchange and commercial demand, and greater revenues, as well as rental income for land lords. But these agricultural traditions evolved in the context of a relatively warm period, and a cooler climate, or at least a period of temperature fluctuations, which seems to have been characteristic of the fifth to seventh centuries, would destabilise the system. In the conditions prevalent in the Mesopotamian climatic region, reduced rainfall would require constant attention to, and expansion of, the irrigation system, and it may well be as much to such long term and incremental pressures that the Sasanian kings of the fifth and especially the sixth centuries were responding, as well as the need or desire to maximise revenues, when they invested so massively in the canals and irrigation network of Mesopotamia, Khuzistān and the Diyālā basin.⁸⁹

The ceramic survey material appears to suggest two phenomena: a clustering and concentration of population in fewer centres; and the

87 Morony, 'Land use and settlement patterns'; Morony, 'Economic boundaries?', p. 181.

88 Note Wenke, 'Imperial investments', pp. 144–6.

89 J. S. Veenenbos, *Unified report of the soil and land classification of Dezful project, Khuzistān, Iran* (Tehran, 1959); Wenke, 'Imperial investments', pp. 81–3.

deliberate development of a number of very large centres into which some of this population was moved, by means about which we are entirely uninformed. While this has been seen as a sign of a flourishing and expanding agriculture, increased levels of production, urban economic vitality and demographic expansion, it is possible in fact to see it in a somewhat different light. For in a situation in which reduced natural water resources impact on agrarian production and thus state resources and in which population is not expanding but contracting (which is an equally possible interpretation of the ceramic material), the kings would have had only one option if they were to maintain their own power and a degree of internal political stability: to expand irrigation and to concentrate populations where the levels of production could be most readily assured. It is not a coincidence that the work of expanding the irrigation systems of Mesopotamia undertaken by Kawād I in the early sixth century can probably be dated to the years following a serious drought around 500, which affected both Roman and Sasanian northern Mesopotamia.⁹⁰

This is not to suggest that levels of production could not be maintained, or that the Sasanian state was impoverished – the quantity of silver and base metal coinage minted alone militates against such a proposal.⁹¹ The ambiguous evidence for the relatively limited treasury of the Persian kings at times in the fifth and sixth centuries,⁹² and firmer testimony to famines or droughts (which also affected some of the eastern provinces of the Roman empire), may not offer much support either for an expanding and flourishing Sasanian economy⁹³ but the numismatic evidence for a vast, and expanding, quantity of silver in circulation in the later sixth and early seventh centuries would appear to run counter to such an interpretation.⁹⁴ It does, on the other hand,

90 Christensen, *L'Iran sous les Sassanides*, pp. 352–3.

91 F. Thierry, 'Sur les monnaies sassanides trouvées en Chine', in R. Gyselen (ed.), *Circulation des monnaies, des marchandises et des biens* (Louvain, 1993), pp. 89–139; M. I. Mochiri, *Études de numismatique iranienne sous les Sassanides et Arabes Sassanides*, 2 vols. (Louvain, 1983); and esp. A. Kolesnikov, 'The quantity of silver coinage and levels of revenue in late Sasanian Iran', *Cahiers de Studia Iranica*, 2 (1999), pp. 123–30.

92 Greatrex, *Rome and Persia at war*, pp. 47, 50–1. Yet this may reflect royal parsimony – other evidence suggests a vast treasury in bullion, coin and other materials by the end of the sixth century: see Morony, *Iraq after the Muslim conquest*, pp. 38–41, 61–3 with literature and sources.

93 See, for example, Christensen, *L'Iran sous les Sassanides*, pp. 290–1; Frye, 'Political history', p. 147; I. G. Telelis, *Μετεωρολογικά Φαινόμενα Φαινόμενα και κλίμα στο Βυζάντιο*, 2 vols. (Athens, 2003), vol. I, nos. 101, 103 (in 464–71 CE); 110, 112 (501–2 CE).

94 See J. Sears, 'Monetary revision and monetization in the late Sasanian empire', *Cahiers de Studia Iranica*, 2 (1999), pp. 149–67; Kolesnikov, 'The quantity of silver coinage and levels of revenue'.

offer an alternative model for the royal policy of investment in both irrigation and urban construction (as well as military predation on the wealthier cities of the nearest Roman provinces – see below), and allows us to place these in a context of gradually declining population, rather than assuming a general increase. And this in turn matches what appears to be the case, at the general level, and bearing in mind the regional fluctuations already noted, in the provinces of the eastern Roman state.

The Arabian Peninsula: a land between two empires

The Arabian Peninsula fits into this pattern politically because of the strategic importance of its coastlands as a source of resources and as a focus for long distance trade. The semi nomadic populations of the northern Arabian Peninsula occasionally posed a threat as small scale raiders, but were also a source of mercenary and allied soldiers, as well as traders on a substantial scale to both Roman and Sasanian markets. The commercial centres of the south, such as Ṣan‘ā’, or of the west, such as Medina and Mecca, maintained regular trading contacts between the cities of Syria and Palestine, the Indian Ocean, the East African littoral and the Aksumite kingdom of Ethiopia. The clans and tribes of the Ḥijāz were key players in trading a variety of goods, including perfumes as well as some non luxuries, to the Roman provinces of Palestine, Syria and Arabia, and possibly beyond. The Quraysh of Mecca in particular were involved in what had by the later sixth century become a lucrative trade in leather, possibly supplying the Roman military. But gold and silver were also traded, and apparently in substantial quantities, a fact which may also contribute to explaining why Mecca in particular occupied such an important position economically.⁹⁵ Perhaps just as importantly, the role of the Ḥijāzī elites in the economic development of the region needs to be underlined, especially in view of their role in the new territories after the initial conquests – there is evidence for extensive irrigation works, dams and

95 See Crone, *Meccan trade*, pp. 98–101, 115–48; Patricia Crone, ‘How did the Quranic pagans make a living?’, *BSOAS*, 68 (2005), pp. 387–99; Patricia Crone, ‘Quraysh and the Roman army: Making sense of the Meccan leather trade’, *BSOAS*, 70 (2007), pp. 63–88. That leather played a key role in supplying the military is evident from its importance at Odessos (Varna) on the Balkan Black Sea coast, in the fifth and sixth centuries, where it was presumably destined for the armies along the Danube. The presence there of a substantial number of funerary inscriptions for leather workers or merchants, for example, largely of the sixth century, testifies to the significance of the military demand for leather from units along the Danube frontier, which Odessos served as a base for supplies and equipment. See V. Beševliev, *Spätgriechische und spätlateinische Inschriften aus Bulgarien* (Berlin, 1964), nos. 99, 100, 102, 103, 104. For precious metals: Heck, ‘Gold mining in Arabia’.

reservoirs in some regions, for example, suggestive of large scale estate management requiring the investment of substantial capital and manpower as well as organisational competence. The petty states of Aden and the Yemen (Ḥimyar) were a focus for diplomatic activity, and the kingdom of Ḥimyar in particular was a bone of contention between Persia and Rome, primarily because of its location in respect of the commercial interests of both states in the region, although ideological motives were also present. Indeed, by the later sixth century the Sasanians controlled, directly through the placement of garrisons and the building of forts or indirectly through client kings, most of the eastern coast of the Arabian Peninsula including Baḥrayn and Oman, as well as the Yemen.⁹⁶ The kingdom of Aksum, Christian since its conversion in the fourth century, figured likewise in the politics and commerce of the Arabian Peninsula, although the Aksumite rulers themselves remained entirely independent, and were key players in Roman politics in the Arabian Peninsula Red Sea region. As a focus for exchange and the long distance trade to both Rome's eastern provinces and Iraq, the significance of the region was clearly recognised, as the evidence of Persian political military involvement throughout the region suggests (see below).⁹⁷

Markets, exchange and taxation

Commerce played a crucial role in the history of those towns located in the right places with good harbours, or at important crossroads and river crossings, for example, since they attracted not only local commercial activity but interregional or long distance markets. Political boundaries could act as constraints on trade (as in the Roman Persian frontier, for example, where long distance trade between Rome and Sasanian Iran was regulated by a series of customs posts as well as by treaty throughout the fourth, fifth and sixth centuries), but many borders were in practice relatively permeable except in periods of warfare.⁹⁸ At the same time, exchange systems are rarely confined

⁹⁶ Crone, *Meccan trade*, pp. 46–50.

⁹⁷ D. Whitcomb, 'The "commercial crescent": Red Sea trade in Late Antiquity and early Islam', in L. Conrad (ed.), *Trade and exchange in the Late Antique and early Islamic Near East*, Studies in Late Antiquity and Early Islam 5 (forthcoming); Morony, 'The late Sasanian economic impact on the Arabian Peninsula'; D. T. Potts, *The Arabian Gulf in Antiquity*, vol. II: *From Alexander the Great to the coming of Islam* (Oxford, 1990), pp. 150–3, 211–18, 328–40; and note D. T. Potts, 'Late Sasanian armament from southern Arabia', *Electrum*, 1 (1997), pp. 127–37.

⁹⁸ M. Morony, 'Trade and exchange: The Sasanian world to Islam', in Conrad (ed.), *Trade and exchange*; M. Morony, 'Commerce in early Islamic Iraq', *Asien Afrika Lateinamerika*, 20 (1993), pp. 699–710; A. D. Lee, *Information and frontiers: Roman foreign relations in Late Antiquity* (Cambridge, 1993), pp. 62–5; M. Gawlikowski, 'Some directions and perspectives of research: Graeco Roman Syria', *Mesopotamia*, 22 (1987), p. 14.

to political boundaries, and both commercial and non commercial exchange and the production that lies behind them generate social and cultural patterns across frontier or marginal regions which may be quite independent of the systems dominating in their hinterlands and core territories. The presence of armies in particular, with their demands for raw materials and foodstuffs, creates patterns of production and exchange which can directly impact upon the economies of regions outside their political or military reach through a process often referred to as 'incorporation'.⁹⁹ Although all the economies of the late ancient world were predominantly rural and agrarian, total self sufficiency was relatively unusual, and involvement in a local, regional or supra regional market was common. This applied as much to nomads as it did to sedentary populations. But there are clearly different levels of trade, exchange and market activity, and different levels of incorporation, and we shall now turn our attention to these.¹⁰⁰

At the most basic level, within village communities and between such communities, the exchange of goods and products represented the long term evolution of a pattern of production which reflected needs and local conditions of production. In some contexts each community might produce most of its requirements; in others, local conditions led to a specialisation in particular crops and the establishment of a more commercially orientated production. Thus in the limestone hills of northern Syria specialised production of olive oil on a large scale appears to have been a response first to local and then regional demand in the fourth and fifth to sixth centuries in particular,¹⁰¹ and facilitated by the existence of a sufficiently monetised economy as well as the availability from other regional producers of products not otherwise available locally. The importance of this commerce in Syrian olive oil remains at issue, however. Tchalenko argued that the export of oil was crucial to the wealth of the villages he surveyed, and that it continued into the seventh century;¹⁰² in contrast, it has more recently been argued that local demand in

⁹⁹ A useful way into these issues is to be found in discussions about the value and application of 'world systems theory'. See in particular A. Gunder Frank, 'Abuses and uses of world systems theory in archaeology', in P. N. Kardulias (ed.), *World systems theory in practice: Leadership, production and exchange* (Lanham, 1999), pp. 275–95; G. L. Stein, 'Rethinking world systems: Power, distance, and diasporas in the dynamics of interregional interaction', in Kardulias (ed.), *World systems theory in practice*, pp. 153–77.

¹⁰⁰ For good comparative analysis, see Wickham, *Framing the early Middle Ages*, pp. 693–720, 759–94.

¹⁰¹ But see U. Baruch, 'The late Holocene vegetation history of Lake Kinneret (Sea of Galilee)', *Paleorient*, 12 (1986), pp. 37–48.

¹⁰² G. Tchalenko, *Villages antiques de la Syrie du nord: Le massif du Bélus à l'époque romaine* (Paris, 1953–8), vol. I, pp. 435–7; M. Decker, 'Food for an empire: Wine and oil production in North Syria', in S. Kingsley and M. Decker (eds.), *Economy and exchange in the east Mediterranean during Late Antiquity* (Oxford, 2001), pp. 69–86.

northern and central Syria was sufficient to account for the apparent increase in production; that local production was by no means as monocultural and market orientated as Tchalenko suggested; and that once the level of demand fell, beginning from the second half of the sixth century and culminating during the later seventh as the markets of the great urban centres of the region declined, so the prosperity of the region and its olive oil production went into decline.¹⁰³ Yet at the same time, the extent of the trade remains disputed, with some suggesting that the oil export went much further afield, and for far longer (into the later seventh and eighth centuries, on the basis of the numismatic evidence) and, along with a range of other long distance exports of agricultural produce, was an essential element of the late Roman economy. That there were such long distance exports, penetrating the western Mediterranean as well as adjacent eastern provinces, is clear. The question is, how significant were they in respect of the interdependence of different regional economies?

This is a difficult question, because we immediately have to confront the issue of the role of the state. While it is generally agreed that the late Roman state intervened directly in the economy in such a way as to impact on a number of key areas of production, distribution and consumption, the extent to which this then further affected aspects of production less relevant to the state's needs remains unresolved. That this impact was felt both within and without the empire is clear.¹⁰⁴ Indeed, the Quraysh leather trade with the Roman army and other customers in Syria and Palestine may be a case in point, for it will have promoted both organisational potential and knowledge of the Roman provinces and military, exerting a powerful influence on the Ḥijāz and its politics.¹⁰⁵ State factories produced weapons; clothing and military equipment of all sorts were similarly organised or levied as an element of taxation; substantial parts of the land tax were raised in kind to feed the army and provincial officials; government agents and senior officials

103 J. H. W. G. Liebeschuetz, *The decline and fall of the Roman city* (Oxford, 2001), p. 71; Morrisson and Sodini, 'The sixth century economy', p. 196; Foss, 'The Near Eastern countryside in Late Antiquity', pp. 219–20; in general, G. Tate, *Les campagnes de la Syrie du nord du II^e au VII^e siècle: Un exemple d'expansion démographique et économique dans les campagnes à la fin de l'Antiquité*, vol. I (Paris, 1992); for the later dating of this decline, see Magness, *Early Islamic settlement in Palestine*.

104 And the effect of the Roman economy on its neighbours is a significant issue which I cannot pursue here: see P. S. Wells, *The barbarians speak: How the conquered peoples shaped Roman Europe* (Princeton and Oxford, 1999); P. S. Wells, 'Production within and beyond imperial boundaries: Goods, exchange and power in Roman Europe', in Kardulias (ed.), *World systems theory in practice*, pp. 85–101.

105 Crone, 'Quraysh and the Roman army'.

were maintained at the expense of taxpayers as they journeyed across the empire, either directly by being billeted on individuals, or indirectly through the public postal system, the *cursus publicus*, which was itself maintained through similar means. Rome and Constantinople were supplied with grain from North Africa or Egypt, and a vast tonnage of grain was transferred from one to the other as part of a regular tax arrangement. The army was likewise maintained directly by the taxpayer, even if soldiers were also paid, as a body, substantial sums, which then filtered back into the market. The issue of coin was a part of this process. Large quantities of precious metal coinage ended up in private hands via commercial transactions and, perhaps more significantly, from state salaries paid to middle ranking and senior officials across the provinces of the empire. The Roman government's insistence on the collection of money taxes in gold, the existence of a stable gold coinage throughout the fourth century and beyond the period of the Islamic conquests and the pressure exerted by the state elite in the use of this coinage for investment and purchases at all levels meant an extremely high degree of monetisation across the empire's territories, although the extent of the availability of the non precious metal coinage, on the one hand, and its value against gold (and silver), on the other, determined the extent to which the less wealthy in society could access market relations without resorting to means such as credit or barter. Indeed, it has been argued that extensive credit arrangements were also in place, permitting the transfer of values without the direct transfer of coin. Even if the pattern was in places uneven, fluctuating according to local circumstances, the presence of the army, and local patterns of agrarian production and levels of output, economic life was highly monetised throughout the sixth century and into the seventh, with increasing volumes of demand across most provinces of the empire in the east.¹⁰⁶ Further, while the state undoubtedly extracted, through taxation, sufficient quantities of the overall wealth produced across the empire to support its own activities, at least in the east and until the middle of the seventh century (the case of the west is

¹⁰⁶ For the fourth century, see P. Garnsey and C. R. Whittaker, 'Trade, industry and the urban economy', in A. Cameron and P. Garnsey (eds.), *The Cambridge ancient history*, vol. XIII: *The late empire, AD 337–425* (Cambridge, 1998), pp. 316–17, 328–37; for the sixth century, see Liebeschuetz, *The decline and fall of the Roman city*, p. 45; Hendy, *Studies*, pp. 289–96, 602–7; Morrisson and Sodini, 'The sixth century economy', pp. 214–19. Most forcefully, Banaji, *Agrarian change in Late Antiquity*, 39–88; Banaji, 'Precious metal coinages and monetary expansion', pp. 267–81. For credit arrangements, see P. Sarris, 'The early Byzantine economy in context', in M. Whittow (ed.), *Byzantium's economic turn* (Oxford, 2009). This situation changed fairly radically in the Anatolian provinces of the empire in the second half of the seventh century, and had already changed in much of the Balkan territory of the empire during the course of the later sixth century.

certainly very different), this may only be a relatively small proportion of the total wealth produced that then went onto the monetised market.¹⁰⁷

The movement of some goods over long and short distances can be tracked either through references in texts and written evidence – as in Egyptian papyri for fiscal records, delivery bills, receipts and so forth, or through the pottery in which many products were themselves transported, or which was itself exported as a marketable commodity in its own right, as in the case of finer tablewares as opposed to transport containers or cooking utensils. In the latter case the two dominant exports were: African red slip ware, the archaeological evidence for which shows a pan Mediterranean distribution pattern, with a gradual reduction in the range and quality of products from the middle of the fifth century, with a revival from around 550 at a lower level of activity, and a reduction in the total number of sites at which it has been identified, especially in the eastern Mediterranean; and Phocaean red slip ware, which dominated the Aegean and eastern Mediterranean regions from the early fifth to late sixth/early seventh centuries. Both continued to make up a substantial proportion of the fine wares of the eastern Roman world until the middle of the seventh century, but the number of imitative types produced at a wide range of regional centres, and the increasing number of original local forms, show that both production and the market were increasingly fragmented.¹⁰⁸

In the case of transport containers of coarser fabric, amphorae of various sizes, shapes and capacities were transported over very considerable distances carrying wine, oil, garum and other commodities to markets where demand

¹⁰⁷ Estimates vary considerably: K. Hopkins, 'Rome, taxes, rent and trade', *Kodai: Journal of Ancient History*, 6 7 (1995 6), pp. 41 75 (repr. in W. Scheidel and S. von Reden (eds.), *The ancient economy* (Edinburgh, 2002), pp. 190 230), argues for a mere 5 7 per cent take by the Roman state; Wickham, *Framing the early Middle Ages*, pp. 64 6, argues for very much higher rates of extraction, 25 per cent or more in many cases, in the fifth early seventh centuries. A global rate of taxation of between 15 and 23 per cent has been proposed for the eastern empire in the period from the eighth century onwards, for example, varying by time and place, degree of monetisation, and other related factors: see C. Morrisson and J. C. Cheynet, 'Prices and wages in the Byzantine world', in Laiou et al. (eds.), *The economic history of Byzantium*, pp. 821f. which would tend to support Wickham's higher levels. The problem lies in the nature of the evidence and the varying and conflicting calculations it can support.

¹⁰⁸ For key issues, see Ward Perkins, 'Specialised production and exchange'; J. F. Haldon, 'Production, distribution and demand in the Byzantine world, c. 660 840', in I. L. C. Hansen and C. J. Wickham (eds.), *The long eighth century* (Leiden, 2000), pp. 247 51; McCormick, *Origins of the European economy*, pp. 53 60; Morrisson and Sodini, 'The sixth century economy', p. 210; A. Walmsley, 'Production, exchange and regional trade in the Islamic east Mediterranean: Old structures, new systems?', in Hansen and Wickham (eds.), *The long eighth century*, pp. 322 4.

was sufficient, primarily the major coastal cities of the Mediterranean world, with an onward network of routes by land to inland markets. To some extent, as with the movement of grain, oil and wine in particular, this was carried out by or at least for the state, through a system of contracting out cargoes to individuals and groups of ship owners or masters. Thus Aegean wares reached the Balkan and Danube frontier forces as the government organised the supply of the field and garrison troops based along the *limes*, while other commodities reached the eastern front garrisons from northern Syria and in locally produced transport vessels. The best known bulk movement of goods was, of course, that of grain from Egypt, but what is equally significant is the way in which smaller scale enterprises and products were shipped on the back of the North African grain transport in particular, resulting in the import of a variety of goods by ports along the route taken by the grain convoys; and similar movements almost certainly accompanied other state sponsored shipping of food or other products for the army, for example, as well as for the populace of Constantinople or Rome. The extensive movement of African fine wares and other products across the central and eastern Mediterranean can at least in part be explained through these means. But at the same time there can be little doubt that, on the basis of the numismatic and written evidence, far more trade was carried on through the medium of private entrepreneurs, markets and producers outside the state's purview.¹⁰⁹

There is continued discussion about the point in time at which levels of production and consumption in the different parts of this eastern Mediterranean exchange zone began to fall off. The mid sixth century (following plague and, in Syria, Persian inroads and economic disruption), the later sixth century (responding to loss of markets upon which certain areas depended), the first twenty or thirty years of the seventh century (a result of the Persian wars) and the mid seventh century (Arab invasions) have all been proposed for different regions, the primary difficulty being the absence of any absolute dates for specific developments. What is not in dispute is the complexity, extent or wealth of the commerce of the late Roman world in the eastern Mediterranean (which, although regionally nuanced, as noted already, contrasts very strongly with parts of formerly Roman western Europe), and the high level of monetisation that facilitated it, or the fact that there was a marked decline in production levels and a narrowing and localisation of

109 C. Haas, 'Alexandria and the Mareotis region', in T. S. Burns and J. W. Eadie (eds.), *Urban centres and rural contexts in Late Antiquity* (East Lansing, 2001), pp. 47–62; P. Reynolds, *Trade in the western Mediterranean AD 400–700: The ceramic evidence*, BAR International Series 604 (Oxford, 1995).

exchange across the period around 550–700, even if it is also clear that trade and commerce across all political boundaries continued after 700, that ceramics from territories under Islamic control continued to be exported to the Aegean and south west Anatolia, and that North African wares continued to appear in Constantinople into the early years of the eighth century at least. This narrowing of range is clearest in the Balkans, Anatolia and Africa, and less so in the Syria–Palestine region; although even here the evidence shows a shrinkage of urban space, a decline in the volume of traded imports and a reduction in port facilities. But in this area the evidence for thriving local production, if on a somewhat smaller scale than hitherto, is clear; while across the territory of the empire as a whole in the east, the decline of many middle-sized cities and the rise in importance of ‘secondary’ urban developments in the hinterlands of the largest cities suggests a shift both in patterns of settlement and in local exchange networks for reasons that remain to be determined. Yet again, however, regional variation is clear – while cities such as Apamea and others in the north appear to have gone into gradual decline from the middle of the sixth century onwards, others further south, in Palestine and Transjordan, such as Gerasa, Pella and Bostra, appear to have been flourishing until at least the early or middle years of the seventh century, and sometimes well beyond, and in the case of Gerasa, for example, as well as many others, to have produced substantial quantities of their own – often high quality – pottery, and to have maintained their prosperity through the period of conquest and into the Umayyad period.¹¹⁰

The Sasanian world was, like the Roman, the location for regionally differentiated developments. As we have already seen, there is some evidence during the fifth century for economic expansion in some areas, most particularly the irrigable lands of Mesopotamia, Khuzistān and the Diyālā basin, and the central and western regions of Fārs, an expansion that may have been compromised during the later sixth century, perhaps becoming more acute in the first half of the seventh century.¹¹¹ Mesopotamia contrasts strongly with Roman northern Mesopotamia and Syria, however, in so far as the Romans rarely penetrated into Sasanian territory to conduct the sort of plundering

¹¹⁰ A. Walmsley, ‘Byzantine Palestine and Arabia: Urban prosperity in Late Antiquity’, in N. Christie and S. T. Loseby (eds.), *Towns in transition: Urban evolution in Late Antiquity and the early Middle Ages* (Aldershot and Brookfield, 1996), esp. pp. 147–51. Summaries of the evidence with literature can be found in Ward Perkins, ‘Specialised production and exchange’, p. 354; Morrisson and Sodini, ‘The sixth century economy’, pp. 193, 212; Wickham, *Framing the early Middle Ages*, pp. 613–25.

¹¹¹ Balādhurī, *al Balādhurī, Kitāb futūḥ al Buldān: The origins of the Islamic state*, trans. P. K. Hitti (London, 1916/Beirut, 1966), pp. 453–4.

operations that Sasanian armies regularly effected during the sixth century in the 540s, 570s and 580s in particular, during which tens of thousands of people, including large numbers of craftsmen and artisans and their families were deported and resettled in new royal foundations near Ctesiphon, such as Veh az antiok Khusrau ('Khusrau's better than Antioch').¹¹² The result was that the rich western provinces of the Sasanian realm were allowed to prosper without serious interruption from the time of Julian's abortive invasion in 363, apart from occasional threats such as the campaign planned by Anastasius I (r. 491–518 CE) in 503 (or natural disasters such as flooding). Roman attacks invariably came from the north west, and Sasanian defensive arrangements were such that they hardly ever penetrated beyond Arzanene and Atropatene. Only with Heraclius' (r. 610–641 CE) invasion from the north – also involving the sack of Ganzak, for example – in 628 and then the Islamic invasions in the 630s were these heartlands penetrated, and even then physical damage appears to have been relatively limited. In this respect there is a parallel between these regions of the Sasanian state and the more prosperous southern Syrian, Transjordanian and Palestinian towns and cities and their districts in Roman territory, which may be contrasted with those of the north, more frequently affected by Persian attacks.¹¹³

Although best known for the luxury goods such as silks that were traded to the north, Sasanian commerce was by no means confined to southward or eastward looking routes. Sogdian merchants imported and passed on to the east substantial amounts of Sasanian silver and precious metal wares, for example, although relations between the Sogdians and the Sasanian state, which had a powerful vested interest in a strictly controlled trade, were strained at times.¹¹⁴ Merchants played an important role in the Sasanian state's economy, to the extent that a highly protectionist policy was maintained on all frontiers, particularly that with the Sogdian and other traders and middlemen in the north and north east, and with the Romans in the west.¹¹⁵ But it is significant that very little Roman produced pottery appears to have been

112 Brunner, 'Geographical and administrative divisions', p. 758. The effects of such transfers are still unclear for the Roman towns and regions affected, although they must have been dramatic. See F. R. Trombley, 'War and society in rural Syria c. 502–613 AD: Observations on the demography', *Byzantine and Modern Greek Studies*, 21 (1997), esp. pp. 158, 168, 182ff.; and chapter 3 below.

113 See Lee, *Information and frontiers*, pp. 15–25, 109–28; M. Whitby, *The emperor Maurice and his historian: Theophylact Simocatta on Persian and Balkan warfare* (Oxford, 1988), pp. 195–218, for a survey of Roman–Persian relations.

114 See de la Vaissière, *Sogdian traders*, esp. pp. 171–6, 207–10, 227–37.

115 *Ibid.*, pp. 228ff. Note also Amir Harrak, 'Trade routes and the Christianization of the Near East', *Journal of the Canadian Society for Syriac Studies*, 2 (2002).

found in Sasanian urban contexts, and what Sasanian material has been excavated from eastern Roman provincial sites is mostly small personal items and can probably be associated (with some exceptions) with the occupation of the eastern provinces in the period after 614.¹¹⁶ To some extent this exchange pattern can be read off retrospectively from that of the early Islamic period, when locally produced fine wares from Palestine and Transjordan rarely moved east.¹¹⁷ Commercial exchange certainly existed across the Romano Persian frontier, but as I have noted it was carefully supervised (although the effectiveness of this is not clear), and appears to have consisted largely of luxury items. But this peaceful commercial activity was also supplemented by predation. Indeed, the chief characteristic of Roman Persian exchange in the sixth century at least appears to be that the Sasanians took what they wanted when political circumstances allowed them to do so. Raiding for booty, labour and skills rather than for conquest (until the great war launched under Khusrau II (r. 590–628 CE)) was the key feature of Sasanian warfare in the west, and in so far as vast numbers of people and considerable quantities of gold were taken either in war or through 'subsides' paid by the Roman government to hold off further attacks, it was extremely successful.¹¹⁸

A substantial commerce existed via the major routes that traverse northern Mesopotamia, and Sasanian rulers had invested in the construction of caravanserais to facilitate this activity, and the profits accruing to Persia from trade were noted by Roman commentators.¹¹⁹ Trade in silks and other luxury items was important and profitable.¹²⁰ Trade eastwards, across the northern route and through Khurāsān, or via the Gulf and the Arabian Peninsula, was well established and requires little comment here,¹²¹ although it is clear that the Sasanian kings actively encouraged certain commercial links, in particular the Silk Route and the Indian Ocean trade. Sasanian political intervention in South

116 E.g. A. M. Maier, 'Sassanica varia Palaestinensia: A Sassanian seal from T. Istaba, Israel, and other Sassanian objects from the southern Levant', *Iranica Antiqua*, 35 (2000), pp. 159–83.

117 See Walmsley, 'Production, exchange and regional trade', pp. 321–9.

118 Morony, 'Trade and exchange', pp. 000–00.

119 Wiesehöfer, *Ancient Persia*, pp. 192–7.

120 M. G. Raschke, 'New studies in Roman commerce with the east', in *Aufstieg und Niedergang der römischen Welt*, 2, 9.2 (1978), pp. 606–50, 821 (for caravanserais); J. I. Miller, *The spice trade of the Roman Empire, 29 BC to AD 641* (Oxford, 1969).

121 Thierry, 'Sur les monnaies sassanides trouvées en Chine', pp. 121–5 with maps 6 and 7, pp. 125–32; V. F. Piacentini, 'Ardashīr I Pāpakān and the wars against the Arabs: Working hypothesis on the Sasanian hold of the Gulf', *Proc. Seminar in Arabian Studies*, 15 (1985), pp. 57–77.

Arabia and the establishment of permanent military and commercial bases in the south and east of the Peninsula attest to the importance ascribed to the region. A chain of small fortresses and strongholds has been tentatively identified stretching from the Gulf as far as the mouth of the Indus, for example, presumably intended to protect the coastal trade and the major entrepôts.¹²² But recent work re-assessing the archaeological evidence has cast some doubt on the picture of a flourishing eastern Arabian economy under Sasanian control; indeed an economic decline has been plausibly argued. While the advantages held by the Sasanians were considerable, there were no serious political hindrances in the Gulf and Indian Ocean to long distance trade,¹²³ the investment by the kings in port facilities (if correctly identified) suggests that it was seen as a significant element in the royal economy. Yet, the ceramic evidence is ambiguous, and hardly supports the notion that the intensity of this trade was hardly surpassed in the later Middle Ages, or that there was a near monopoly operated by Sasanian merchants supported by the state.¹²⁴ There is also good evidence of a revival in trade overland with China – a highly monetised trade – in the last forty or so years of Sasanian rule, as political conditions in China stabilised and as Sasanian power and influence in the regions beyond Khurāsān was strengthened. Sasanian commercial activity in a wide range of luxury goods, both from west to east and vice versa was influential, and played also an important role in the economies of those regions of Central Asia as well as of China with which it was associated. Trade and exchange in urban contexts was certainly a major feature of urban life, as both the textual and archaeological evidence suggests.¹²⁵

122 M. Kervran, 'Forteresses, entrepôts et commerce: Une histoire à suivre depuis les rois sassanides jusqu'aux princes d'Ormuz', in R. Curie and R. Gyselen (eds.), *Itinéraires d'Orient: Hommages à Claude Cahen* (Louvain, 1994), esp. pp. 331–8; Whitehouse and Williamson, 'Sasanian maritime trade', pp. 43–5.

123 M. Loewe, 'Spices and silk: Aspects of world trade in the first seven centuries of the Christian era', *JRAS*, n.s., 2 (1971), pp. 166–79; Thierry, 'Sur les monnaies sassanides trouvées en Chine'. For a significant challenge to the established view, see Kennet, 'The decline of eastern Arabia'.

124 Kennet, 'The decline of eastern Arabia', *passim*. Frye, 'Byzantine and Sasanian trade relations'; B. E. Colless, 'Persian merchants and missionaries in medieval Malaya', *Journal of the Malaysian Branch of the Royal Asiatic Society*, 42 (1969), pp. 10–47; Whitehouse and Williamson, 'Sasanian maritime trade', pp. 45f.; Kervran, 'Forteresses, entrepôts et commerce', pp. 338–9; summary of evidence in Banaji, 'Precious metal coinages and monetary expansion', pp. 285–90.

125 Thierry, 'Sur les monnaies sassanides trouvées en Chine', pp. 134–9; and esp. J. K. Skaff, 'Sasanian and Arab Sasanian silver coins from Turfan: Their relationship to international trade and the local economy', *Asia Major*, 11, 2 (1998), pp. 67–114. See also E. de la Vaissière, 'Les marchands d'Asie Centrale dans l'empire khazar', in M. Kazanski, A. Nercessian and C. Zuckerman (eds.), *Les centres proto urbains ruissés entre Scandinavie, Byzance et Orient* (Paris, 2000), pp. 367–78. For attitudes to commerce and the monetisation of exchange relations, see A. Panaino, 'Commerce and conflicts of religions in Sasanian Iran: Between

But it is also clear that, like Rome, the Sasanian state extracted substantial resources from the producing population in the form of crops or finished goods for its armies, as well as in terms of skills. Sasanian exchange systems seem also to have been heavily regionalised – a Mesopotamian zone overlapped to some extent with a south Iranian/Gulf/East Africa zone, which in turn connected with the Indian subcontinent – fine wares as well as domestic coarse wares from Gujarat as well as Sind and Maharashtra have been excavated from Sasanian levels at Ṣuḥār in Oman and Sīrāf, for example.¹²⁶ Yet this commerce seems hardly to have impinged, at least in terms of the movement of ceramics, on other zones to the north and east.¹²⁷ The pottery from Marw, for example, is associated stylistically with that from northern Bactria rather than Iraq or the northern Iranian plateau, while that from the Elburz regions is different again.¹²⁸ None of these types seems to have travelled far, except for certain fine wares, but these are also very limited in number.¹²⁹

This picture contrasts with the Roman evidence, and largely reflects the different patterns of commerce and transport between coastal zones and maritime trade on the one hand, inland zones and the constraints of land transport, and on the other the types of goods that were traded. Silks and bullion, for example, which constituted two of the most important materials traded, leave no ceramic traces. But like the Roman economy, by the later sixth century the Sasanian economy also involved the circulation of a vast number of coins, reaching a peak in the period between 603 and 635 and directly impacting on the economy of the post conquest period.¹³⁰ Indeed,

social identity and political ideology', in R. Rollinger and C. Ulf (eds.), *Commerce and monetary systems in the ancient world: means of transmission and cultural interaction* (Stuttgart, 2004), pp. 385–401.

¹²⁶ See in particular Kennet, 'The decline of eastern Arabia', pp. 97–100. D. Whitehouse, 'Abbasid maritime trade: Archaeology and the age of expansion', *Rivista degli Studi Orientali*, 59 (1985), p. 344; M. Kervran, 'Indian ceramics in southern Iran and eastern Arabia: Repertory, classification, chronology', in H. P. Ray and J. F. Salles (eds.), *Tradition and archaeology, early maritime contacts in the Indian Ocean: Proceedings of the international seminar Techno archaeological perspectives of seafaring in the Indian Ocean 4th cent. BC 15th cent. AD* (New Delhi, 1996), pp. 37–58; D. Kennet, *Sasanian and Islamic pottery from Ras al Khaimah: Classification, chronology and analysis of trade in the western Indian Ocean*, BAR International Series 1248 (Oxford, 2004), pp. 68–79.

¹²⁷ D. Kennet, 'Sasanian pottery in southeastern Iran and eastern Arabia', *Iran*, 40 (2002); Adams, 'Tell Abu Sarifa', for southern Iraqi types.

¹²⁸ G. Puschnigg, 'The pre Islamic pottery', in G. Herrmann, K. Kurbansakhatov and St J. Simpson (eds.), 'The International Merv Project: Preliminary report on the ninth year (2000)', *Iran*, 39 (2001), pp. 22–3.

¹²⁹ E.g. Kennet, 'Sasanian pottery in southeastern Iran', p. 159; Kennet, *Sasanian and Islamic pottery from Ras al Khaimah*, pp. 68–71.

¹³⁰ Kolesnikov, 'The quantity of silver coinage and levels of revenue'; de la Vaissière, *Sogdian traders*, pp. 228–32; Skaff, 'Sasanian and Arab Sasanian silver coins from Turfan',

the evidence has been interpreted to suggest not only that coin production was inflected by military needs, as in the Roman world, but also that the Sasanian court was quite aware both of the need to circulate coin to meet commercial demands and of the possibility of manipulating the domestic market for its own purposes.¹³¹

The extent to which the Sasanian state, like Rome, transported large quantities of goods in bulk for its armies is unclear, but it is apparent that it was able to accommodate the logistical demands of substantial bodies of troops, and it is therefore very likely that its arrangements were not dissimilar from those of the Roman state.¹³² There is some evidence for the long distance movement of storage vessels, but these are found mostly in domestic or artisanal contexts rather than obviously military locations, and appear to reflect the regionalised exchange systems noted already, since they are confined largely (thus far) to sites in Mesopotamia, southern Iran and the Gulf.¹³³ For the most part its frontier provinces could support the burden of the soldiers based there, since the greater number of mints in both frontier and inner provinces serviced the needs of the military as well as the markets on which they depended very efficiently; while in the rich provinces of Mesopotamia the relatively high levels of agricultural production, combined with the possibility of riverine transport, gave the Sasanians an advantage in defensive terms.¹³⁴ The tax system, both before and after the reforms of Khusrau I, was certainly structured to support a considerable army, and involved levies of foodstuffs as well as livestock and equipment,

pp. 85–6; R. Gyselen, 'Un trésor de monnaies sassanides tardives', *Revue Numismatique*, ser. 6, 32 (1990), pp. 212–31; R. N. Frye, 'Sasanian Central Asian trade relations', *Bulletin of the Asia Institute*, n.s. 7 (1993), pp. 73–7.

¹³¹ See esp. Sears, 'Monetary revision and monetization', pp. 161–3; Skaff, 'Sasanian and Arab Sasanian silver coins from Turfan'.

¹³² Howard Johnston, 'The two great powers', pp. 166–9, 185–6, 191–7; Morony, *Iraq after the Muslim conquest*, pp. 51–6, 61–2. Finds of Sasanian coins in districts distant from their mints may certainly reflect military as much as commercial movements: see N. Nakshabandi and F. Rashid, 'The Sassanian dirhams in the Iraq Museum', *Sumer*, 11 (1955), pp. 155–76; and esp. Sears, 'Monetary revision and monetization', pp. 161–2. For distribution of troops and arrangements for their provisioning and equipping, see Grignaschi, 'Quelques spécimens de la littérature sassanide', p. 24 and notes.

¹³³ In particular the so called 'large incised storage vessels' and 'torpedo' jars: Kennet, 'Sasanian pottery in southeastern Iran', pp. 154, 158–60.

¹³⁴ Howard Johnston, 'The two great powers', pp. 88–91. On the mints, see esp. R. Gyselen, *Arab Sasanian copper coinage*, Österreichische Akademie der Wissenschaften, Philosophisch-Historische Klasse, Denkschriften 284, Veröffentlichungen der numismatischen Kommission 34 (Vienna 2000), esp. p. 77; and cf. S. Tyler Smith, 'Sasanian mint abbreviations', *Numismatic Chronicle*, 143 (1983), pp. 240–7.

although the details recorded only obliquely in al Ṭabarī¹³⁵ remain obscure.¹³⁶

It is apparent from this introductory survey that the eastern Roman and Sasanian empires had vast resources at their disposal. Both states had evolved complex administrative and social arrangements aimed at the extraction, redistribution and consumption of such resources, yet both were constrained by the geography, climate and technologies at their disposal or to which they were subject. Paradoxically, however, it was those territories that were not to be absorbed into the newly formed world of Islam which suffered most in their material infrastructure as a result of the conquests. For the process of conquest in both the Roman and Sasanian areas was in fact remarkably rapid. Within a ten year period from 632 to 642 all Rome's eastern provinces, including Egypt, had been lost. Most cities surrendered with either no or only token resistance, their populations remained where they were, economic and social life continued. The changes that did take place were, therefore, both minimal at least in the opening decades of Islamic rule and gradual. An exception in both social and economic as well as political and cultural respects may be the fate of the elites in the formerly Roman provinces, where sometimes dramatic changes were effected as a result of the Islamic occupation and political restructuring from the 640s.¹³⁷ The fate of the Sasanian regional elites as opposed to the senior aristocrats was certainly milder, however. Apart from this, similar conditions following the conquest, with a few exceptions, applied in Iraq and Iran, and to a large degree the trajectory of development under way in the pre conquest period continued on its course in the decades following, with certain notable exceptions (for example, the establishment of the *amṣār* (garrison cities) in Iraq and Egypt). The vast quantity of coined silver and gold circulating within and across these two spheres both united and separated them, through regionalised and long distance overlapping trade and exchange networks. At the same time it emphasised their involvement and integration into a much wider Eurasian network of commercial as well as political ties or

135 Howard Johnston, 'The two great powers', pp. 169–72; M. Morony, 'Land holding in seventh century Iraq: Late Sasanian and early Islamic patterns', in Udovitch (ed.), *The Islamic Middle East, 700–1900*, pp. 136–53; Altheim and Stiehl, *Finanzgeschichte der Spätantike*, esp. pp. 7–51; T. Daryaei, 'The effect of the Arab Muslim conquest on the administrative division of Sasanian Persis/Fārs', *Iran*, 41 (2003), pp. 193–204; Trinkaus, 'Settlement of highlands and lowlands', pp. 129–30, 136–9, on the relationship between the local economy of the Dāmghān area and taxation.

136 On Khusrāu's reform, see Rubin, 'The reforms of Khusrō Anushirwān'.

137 See Wickham, *Framing the early Middle Ages*, pp. 240–55.

associations. This had a crucial impact on the ways in which the Islamic successor state evolved its own patterns of resource distribution, exchange and commerce.¹³⁸

In the surviving Byzantine lands, by contrast, a century and a half of debilitating and disruptive warfare ensued, which disrupted the provincial and rural economy and reduced the former eastern Roman imperial state to a shadow and a relatively impoverished shadow of its former self, contributing also to a radical transformation of urban life as well as of the state and eastern Roman society. But outside this war damaged zone, urban life, inter provincial and long distance trade, and local economies in the conquered lands continued to evolve in directions set before the Islamic conquests with little or no interruption, although of course the social structure of landowning, elite culture and access to resources did change in some cases substantially. Whatever the nature of the changes that affected the late ancient world in the wake of the early Islamic conquests, it was thus geography and landscape, on the one hand, and the demography and pattern of exploitation and distribution of resources of all kinds, on the other, that determined and constrained the initial trajectory of Islamic history.

¹³⁸ P. Pourshariati, *Decline and fall of the Sasanian empire: The Sasanian Parthian confederacy and the Islamic conquest of Iran* (London, 2008).

The late Roman/early Byzantine Near East

MARK WHITTOW

Rome was not 'declining' in Late Antiquity. In many ways it was thriving. Half a century of research – above all, archaeology – has shown in the Roman Near East a wealthy, well populated world, whose inhabitants enjoyed a thriving economy and spent their money on lavish building projects, on silver and on high quality textiles. In many areas of the Near East the Late Roman period, in terms of population size, settlement density and levels of exploitation, marks a pre modern high.¹ On the other hand, there is no doubt that between the third and sixth centuries the Roman empire was transformed in ways that do much to explain what happened in the seventh century. The key to this process was conflict with Sasanian Iran. In response to that threat the structure, organisation and culture of the empire was reshaped; Rome's relations with the wider world were transformed; and the empire became involved in an escalating cycle of warfare that would culminate in the crisis out of which the Islamic world would emerge.

An obvious parallel is with the way the modern world is a product of the First World War. Without it we would have had neither Soviet Russia, nor Nazi Germany, nor the European Community, nor the United Nations, nor the current multi state Middle East. That is not to say that peace in 1914 would have kept the world safe for imperialism and reaction, but that the war and its aftermath set the world on paths that would have been hardly imaginable six years earlier. In turn, the First World War can only be fully comprehended in the light of the European state system as it had evolved since the seventeenth century, a process that had divided the continent between powers equipped

¹ J. Banaji, *Agrarian change in Late Antiquity: Gold, labour, and aristocratic dominance* (Oxford, 2001), pp. 15–22; B. Ward Perkins, 'Land, labour and settlement' and 'Specialized production and exchange', in A. Cameron, B. Ward Perkins and M. Whitby (eds.), *The Cambridge ancient history*, vol. XIV: *Late Antiquity: Empire and successors, AD 425–600* (Cambridge, 2000), pp. 315–91. See pp. 352–4, 358–61 for the prosperity of the Roman Near East in Late Antiquity.

and prepared to fight war on the grandest scale, and able to do so with the support and commitment of millions of their citizens.

In a similar way the Islamic world was the product of a war between Rome and Iran that broke out in 603 and lasted for twenty five years. The war overturned an established order three centuries old, and created a power vacuum that allowed Arab armies to conquer two empires and create a third; but, although it had immediate causes, to be fully understood it needs, like the war that broke out in 1914, to be seen in terms of a political system that had evolved over several centuries, in this case since the third century CE.

To recognise this is not to say that Islam would not have come about without the wars of the Roman empire, but rather that God's purposes would have had to have been achieved in very different ways. The rise of Islam as it actually happened is comprehensible only in the context of the history of the Roman empire, a history that culminated in what James Howard Johnston has evocatively dubbed the 'the last great war of Antiquity'.²

Rome and the Near East to the fourth century CE: making and re-making an empire

The expansion of Rome

At the beginning of the third century CE the Roman empire stretched from Hadrian's Wall in the north of England to the upper Tigris in eastern Turkey, a nominal distance of about 3,700 kilometres, and for any Roman traveller actually making this journey considerably more. The empire included not only the entire Mediterranean basin, but extended far beyond into a world whose rivers drained into the Persian Gulf, the Black Sea, the North Sea and the Atlantic Ocean. Its size in part reflected the attractiveness of Roman rule. Many inhabitants of this empire wanted to be citizens or at least clients of the Romans. For the elites or would be elites of provincial society the Roman empire brought opportunities for riches and power, and the security to enjoy them: behave like a Roman and act in the name of Rome, and you would in effect be a Roman. The imperial administrative system was minimal and the tax burden light. In practice Rome's subjects governed themselves, and competed to display their loyalty to the emperor. The hundreds of temples to the cult of the emperor that dotted the Roman world are impressive

2 J. Howard Johnston, 'al Tabari on the last great war of Antiquity', in J. Howard Johnston, *East Rome, Sasanian Persia and the end of Antiquity: Historiographical and historical studies* (Aldershot, 2006), chapter 6, p. 1.

testimony to an uncontested imperialism. Revolt and resistance was rare, and when it occurred was usually more a matter of pushing for further benefits than of any rejection of Roman rule as such.³ The Jewish revolts of the first and second centuries CE, which were intended to rid Judaea of the Romans, were exceptional; the lack of any true network of fortifications in the Near East, whether to cow internal dissent or outside aggression, is a much better guide to the normal workings of the empire before the third century.⁴

The size of the empire also reflects Roman military superiority. At an operational level this was the product of a system honed in the later years of the republic and founded on the infantry of the legions; in strategic terms it was due to the lack of any great power rival. Following the defeat and destruction of Carthage in the third century BCE, Rome was only opposed by local and regional powers. Had it been otherwise, Rome could not have conquered the east and at the same time sent its armies to the Rhine and distant Britain.

The territorial expansion of Rome began in earnest in the second century BCE, and had its roots in the competitive aristocratic politics of the republic.⁵ Caesar's conquest of Gaul is typical in all but the fact that he wrote his own account of what happened. While his wars were fought chiefly to gain the very practical benefits of booty and glory, Caesar shows that he and his peers were not without a sense of strategy; not necessarily grand strategy, but certainly a practical awareness of the need to manage clients, control resources and avoid over commitment. The destruction of Octavian's aristocratic rivals, the fall of the republic and the making of the empire at the end of the first century BCE slowed but did not halt Roman expansion. Emperors continued to fight wars for much the same trio of motives that had inspired Caesar, and after Claudius' conquest of Britain in 43 CE these tended increasingly to lead them east. The spoils were richer, the prestige of following in Alexander's footsteps greater, and the Parthians, if not a real rival, were at least worth

3 C. Ando, *Imperial ideology and provincial loyalty in the Roman Empire* (Berkeley and Los Angeles, 2000), pp. 1–15; J. H. W. G. Liebeschuetz, *The decline and fall of the Roman city* (Oxford, 2001), pp. 342–6; S. Price, *Rituals and power: The Roman imperial cult in Asia Minor* (Cambridge, 1984), pp. 76–7, 234–48; G. Wolf, *Becoming Roman: The origins of provincial civilization in Gaul* (Cambridge, 1998), pp. 238–49.

4 M. Sartre, *The Middle East under Rome*, trans. C. Porter and E. Rawlings (Cambridge, MA, 2005), p. 132; N. Pollard, *Soldiers, cities, and civilians in Roman Syria* (Ann Arbor, 2000), pp. 85–110; S. T. Parker, 'The defense of Palestine and Transjordan from Diocletian to Heraclius', in L. E. Stager, J. A. Greene and M. D. Coogan (eds.), *The archaeology of Jordan and beyond: Essays in honor of James A. Sauer*, Studies in the Archaeology and History of the Levant 1 (Winona Lake, IN, 2000), pp. 369–70; cf. B. Isaac, *The limits of empire* (Oxford, 1990), pp. 156–60.

5 W. V. Harris, *War and imperialism in republican Rome, 327–70 BC* (Oxford, 1979), pp. 30–1.

taking more seriously than the tribes of Germanic Europe. Under Trajan in the early second century CE, Rome's eastern frontier for the first time reached the Tigris, and his sack of the Parthian capital at Ctesiphon near modern Baghdad set a standard which his successors were keen to follow.⁶

The rise of the Sasanians

However, the political vacuum that lay behind the expansion of Rome could hardly be expected to last forever, and in the third century a new era began. In the west Rome was faced by an evolving Germanic world where tribes were coming together in more powerful confederations. Individually groupings such as the Marcomanni, the Alamanni (the archetypal name for a confederation) and the Goths did not pose a threat to Roman hegemony, but their management did require more resources than had their first century predecessors. Half hearted measures could and did lead to disaster.⁷ The really significant change, however, was happening in the east.

The Parthian dynasty had signally failed to stop their aggressive western neighbours regularly invading Iraq through the second and early third centuries CE, and inevitably its legitimacy was called into question. The dynasty's failure was further emphasised by the inability to crush a long running rebellion in western Iran. In 224 the rebel army defeated the Parthians for the third time; King Artabanus V fell on the battlefield, and the rebel leader, Ardashīr, moved rapidly to seize Iraq, so inaugurating the Sasanian regime that was to rule Iran until the Muslim conquest.⁸ Rome was now faced by an entirely new situation. Ardashīr and his successors may initially have been drawn into war with Rome by the need to end any threat that former Parthian client states, such as Armenia, might serve as a base for a Parthian restoration, but soon war with

6 C. S. Lightfoot, 'Trajan's Parthian war and the fourth century perspective', *Journal of Roman Studies*, 80 (1990), pp. 115–26; F. Millar, *The Roman Near East, 31 BC–AD 337* (Cambridge, MA, 1993), p. 99; S. P. Mattern, *Rome and the enemy: Imperial strategy in the principate* (Berkeley and Los Angeles, 1999), pp. 1–23, 81–122.

7 M. Todd, 'The Germanic peoples and Germanic society', in A. K. Bowman, P. Garnsey and A. Cameron (eds.), *The Cambridge ancient history*, vol. XII: *The crisis of empire, AD 193–337*, 2nd edn. (Cambridge, 2005), pp. 440–7; P. Heather, 'The Late Roman art of client management', in W. Pohl, I. Wood and H. Reimitz (eds.), *The transformation of frontiers: From Late Antiquity to the Carolingians* (Leiden, 2001). On the name 'Alamanni', see J. F. Drinkwater, *The Alamanni and Rome 213–496* (Oxford, 2007), pp. 62–9.

8 J. Howard Johnston, 'The two great powers in Late Antiquity: A comparison', in A. Cameron (ed.), *The Byzantine and early Islamic Near East*, vol. III: *States, resources and armies*, Studies in Late Antiquity and Early Islam 1 (Princeton, 1995), pp. 158–62; M. H. Dodgeon and S. N. C. Lieu (eds.), *The Roman eastern frontier and the Persian Wars, part 1: AD 226–363: A documentary history* (London, 1991), pp. 9–33; cf. R. N. Frye, 'The Sassanians', in Bowman *et al.* (eds.), *The crisis of empire*, pp. 461–74.

the empire had become an end in itself. Victory demonstrated Sasanian charisma and brought huge profits. The experience of war bonded the Sasanian elite and created the infrastructure for further hostilities. Through to the 260s Sasanian armies raided throughout the Roman east, and the Roman response was largely ineffective. In 244 a Roman expedition to Ctesiphon ended with the emperor Gordian III's death and his successor, Philip the Arab,⁹ making major concessions to ensure the army's retreat. In 253 the great Syrian city of Antioch was sacked, and in 260 the emperor Valerian himself was captured and put on display, in person for the rest of his life, and in stone for eternity.¹⁰ The monumental rock cut reliefs at Naqsh i Rostam in Iran sum up the new order. The site lies 5 kilometres north west of the ancient Persian capital of Persepolis. Here were buried the great Achaemenid shahs, Darius and Xerxes, who had ruled as far as the Mediterranean; and here, next to the tomb of the great Darius and close to the huge image of Ardashir being given rule over Iran by the supreme God Ahuramazda, Ardashir's son Shapur I celebrated his victories over Rome. Shapur's relief shows one emperor (Gordian III or Philip the Arab) kneeling at the feet of the mounted shah, and another, Valerian, held prisoner by the hand.¹¹ The message is clear. The Sasanians are divinely appointed rulers of the east, whose status as the legitimate heirs of the Achaemenids is demonstrated by victory over Rome.¹²

Palmyra and the third-century crisis

The very real danger of the break up of the empire during these years is made clear by the so called revolt of Palmyra. This oasis city, about 200 kilometres east of the Mediterranean, had been part of the empire since the early first century CE, and had made itself rich as one of the chief conduits for eastern trade into the Roman world. Inscriptions in Aramaic and Greek describe the system of protected caravans that crossed the Syrian desert, and Palmyrene merchants are attested resident as far afield as the Persian Gulf. Otherwise Palmyra was

9 On Philip's description in fourth century sources as 'the Arab', see Millar, *The Roman Near East*, pp. 530–1: 'we must leave entirely open the question of what ethnic description we ought to give to the two Greek speaking (and surely also Latin speaking) sons of a local Roman citizen, Iulius Marinus, who both entered imperial service' (p. 531).

10 Dodgeon and Lieu (eds.), *The Roman eastern frontier*, pp. 34–67.

11 G. Herrmann, D. N. Mackenzie and R. Howell, *The Sasanian reliefs at Naqsh i Rostam, Naqsh i Rostam 6, The triumph of Shapur I*, *Iranische Denkmäler* 13 (Berlin, 1989).

12 Howard Johnston, 'The two great powers in Late Antiquity', p. 160; G. Fowden, *Empire to commonwealth: Consequences of monotheism in Late Antiquity* (Princeton, 1993), pp. 28–9; cf. D. S. Potter, *Prophecy and history in the crisis of the Roman Empire: A historical commentary on the Thirteenth Sibylline Oracle* (Oxford, 1990), pp. 370–6, for the view that the Sasanians were unaware of their Achaemenid predecessors.

organised as an ordinary Roman city, ruled by a council of its leading citizens.¹³ In the 260s, however, in the crisis that followed the capture of the emperor Valerian, one of its notables, Septimius Odenathus, came to prominence organising resistance to the Iranians and suppressing rivals to the new emperor, Gallienus. Odenathus' status at this stage is unclear. He was a Roman senator, and so a plausible person to exercise authority; he may have been governor of Syria, or he may have held a special regional command entrusted to him by Gallienus. The evidence is equivocal.¹⁴ But in 268 Odenathus was murdered, and his power inherited by his wife Zenobia and son Vaballathus. Over the next few years their troops overran Syria and then Egypt, the wealthiest of the eastern provinces and a crucial source of Rome's grain supply. Gallienus had been killed in 268. His successor, Claudius, died in 270. It was not until 271 that the new emperor, Aurelian, marched east, defeated the Palmyrene armies, and in 272 sacked Palmyra, and brought Zenobia captive to Rome.¹⁵

At one level this was an ordinary piece of Roman imperial politics, and the fact that Palmyra was a commercial centre, bilingual in Aramaic and Greek, does not make its leading families any the less 'Roman'. Inscriptions such as those known from milestones in the province of Arabia (mod. Jordan) describe Vaballathus as 'Imperator Caesar L. Julius Aurelius Septimius Vaballathus Athenodorus', in other words as Roman emperor, and his ascent to power would have been no more extraordinary or exotic than that of the other Roman provincials who became emperors during the second and third centuries. A document from Egypt dated by the joint regnal year of the emperors Aurelian and Vaballathus is a plain indication of how the Palmyrene 'revolt' appeared at the time.¹⁶ The fact that Aurelian defeated Vaballathus and Zenobia should not make us think that the former's power was in any way more legitimate or more 'Roman'. In many ways the story of Palmyra exemplifies the strength of the ties that bound the empire together, and enabled local notables to identify with it and use its structures for their benefit. Zenobia and Vaballathus were not Arab nationalists, nor were Palmyra's conquests the forerunners of those of the seventh century. To call Palmyra 'Arab' is a modern device with no contemporary usage.¹⁷

13 Millar, *The Roman Near East*, pp. 159–73, 319–36; M. Sartre, 'The Arabs and the desert peoples', in Bowman *et al.* (eds.), *The crisis of empire*, pp. 511–15.

14 For alternatives see Millar, *The Roman Near East*, pp. 165, 168–71; D. S. Potter, *The Roman Empire at bay, AD 180–395* (London, 2004), pp. 259–60; and U. Hartmann, *Das palmyrenische Reich* (Stuttgart, 2001), pp. 91–6.

15 Dodgeon and Lieu (eds.), *The Roman eastern frontier*, pp. 68–110.

16 *Ibid.*, pp. 88–9, 91.

17 J. Retsö, *The Arabs in Antiquity: Their history from the Assyrians to the Umayyads* (London, 2003), pp. 462–6.

But the 'revolt' did have more serious and genuinely contemporary implications. For the most part Palmyra's Aramaic inscriptions appear simply to convey Roman titles in a different idiom, but when Odenathus can be described on an inscription as 'King of Kings', in other words the title of the Iranian shah, and when Odenathus can give that same title to his elder son Herodian, who in turn can be depicted on a lead seal with a crown like that of the Parthian kings, then it indicates an ability among the Palmyrene elite to think in terms other than those derived from Rome.¹⁸ The empire had grown up, and now rested on, the centripetal desire of local elites to be Roman. In the fifth century Roman power in Gaul would dissolve when local elites there came to realise that the empire could no longer provide them with security, and began to imagine a future without Rome – a process we now describe as the fall of the Roman empire in the west.¹⁹ These Palmyrene inscriptions show the early stages of the same process. The crisis of the third century east was short lived compared with the problems that overwhelmed the fifth century west; but the response of the Palmyrene elite to failure in the face of Sasanian aggression shows the early stages of the same process. If Rome could not provide the security and rewards for these elites that had bound them to the empire in the first place, then there were alternatives available, and, if followed, the empire would fail.

Re-making the empire

The implications of the rise of the Sasanians and the Palmyrene crisis were clear enough. Emperors needed more troops, and more resources to support them. That would require asking more from the empire's landowning elites, and to do that with any long term success would require binding those individuals more closely into the administration and ideology of empire. If the early empire had flourished because it empowered local elites and asked for comparatively little in return, the empire's survival now demanded rather more.

Over the course of the late third and fourth centuries this agenda was largely achieved. It is traditional, and probably right, to give a great deal of the credit to Diocletian (r. 284–305) for increasing the size of the army and reorganising the empire's administrative and fiscal system, and to Constantine (r. 306–37) for

18 Dodgeon and Lieu (eds.), *The Roman eastern frontier*, pp. 77, 88; for the lead seal, see the illustration in E. Equini Schneider, *Septimia Zenobia Sebaste* (Rome, 1993), p. 98 and the discussion in Hartmann, *Das palmyrenische Teilreiche*, pp. 179–83.

19 P. Heather, 'The Huns and the end of the Roman Empire in Western Europe', *English Historical Review*, 110 (1995), pp. 38–9.

giving the empire a new ideological focus in Christianity, a new capital and senate in Constantinople and, arguably most important, a new gold based currency. In both cases the changes had their roots in the earlier third century, and took more than a hundred years to be worked through, but it remains true that these two regimes took the crucial steps that were to shape the empire of Late Antiquity.²⁰

The key factor was the need for more troops, from which followed the need to obtain more resources. There is no agreement on how large the increase in the size of the army was, but an increase by a third from about 350,000 at the end of the second century to nearly 500,000 by the end of the fourth would be a conservative estimate.²¹ To meet the cost Italy lost its previous tax exemption, and city revenues were in effect nationalised. On top of this the system of requisitioning by which army units were provided with goods in kind was gradually expanded, first into an empire wide system based on a census of people and land, and then commuted into a land tax which thenceforth formed the basis of the imperial budget.²²

On the face of it, such changes should have been utterly unacceptable to the provincial elites whose commitment to the empire was essential for its survival, but in the event they were wooed by imperial propaganda emphasising how much the emperor shared their interests and concerns, and more importantly they soon found that they gained more by the opportunities that a more active central government provided than they had lost by the confiscation of civic revenues. Diocletian may have broken up the large provinces of the earlier empire into smaller units principally to make it more difficult for any governor thinking of revolt, but the consequence was many more posts in imperial government. Similarly, whatever Constantine's reasons for founding a new capital at Constantinople and reorganising the currency in a system based on gold, the eventual result was to take hundreds of leading provincial families from their cities to the imperial centre, and bind them there by golden ties. In the new world of Late Antiquity being paid in gold was akin to being paid in dollars or euros in a modern Third World economy. Gold went as

20 E. Lo Cascio, 'The new state of Diocletian and Constantine: From the tetrarchy to the reunification of the empire', in Bowman *et al.* (eds.), *The crisis of empire*, pp. 170–83; Potter, *The Roman Empire at bay*, pp. 367–400.

21 B. Campbell, 'The army', in Bowman *et al.* (eds.), *The crisis of empire*, pp. 123–4; H. Elton, *Warfare in Roman Europe AD 350–425* (Oxford, 1996), pp. 118–27; A. H. M. Jones, *The Later Roman Empire, 284–602: A social, economic, and administrative study*, 3 vols. (Oxford, 1964), pp. 56–60, 679–83; cf. Potter, *The Roman Empire at bay*, pp. 455–8.

22 M. Corbier, 'Coinage and taxation: The state's point of view, A.D. 193–337', in Bowman *et al.* (eds.), *The crisis of empire*, pp. 370–86.

salaries to those who served the state, and in turn those who served the state had the resources to dominate provincial society.²³

The culmination of these changes was the new role of the emperor which emerged in the early fifth century. In the past emperors had been soldiers, and they had needed to keep on the move. Even when they were not, they needed to cultivate this image. But in the fifth century it became possible for an emperor such as Theodosius II to spend his life in Constantinople, and to proclaim his status by presiding over Christian ceremonies, like a glorious spider at the centre of a web. By the fifth century the empire was centred as never before on a capital city, on a palace, and on the emperor who resided there.²⁴

The transformation of the Roman empire inaugurated by Diocletian and Constantine enabled the empire to survive in a newly competitive world, and, as far as the Near East was concerned, to prosper too. Late Antique cities were generally less spectacular than their earlier Roman predecessors. With civic revenues in imperial hands and the foci of political life shifting elsewhere, the great building boom that had filled the region's cities with monumental public buildings was largely over by the fourth century, but the leaders of provincial society were still rich – indeed, paid in gold, their spending power was arguably greater than ever before, their investments fuelled growth, and the archaeological evidence, most obviously that from the limestone massif in northern Syria, suggests that the benefits reached a wide section of society.²⁵

What was once seen as an age of decline has therefore come to look very different. Compared with the empire of the first and second centuries, that of Late Antiquity appears more, not less, effective at binding provincial elites to the centre and transmitting central authority to the periphery.²⁶ The imposition of Christianity is a good example. It may not have been as total or as uniform as emperors would have wished, but it represents a degree of central involvement in the lives of all imperial subjects unprecedented before the fourth century. The very concept of heresy would have been strange to pagan

23 P. Heather, 'New men for new Constantines? Creating an imperial elite in the eastern Mediterranean', in P. Magdalino (ed.), *New Constantines: The rhythm of imperial renewal in Byzantium, 4th–13th centuries* (Aldershot, 1994), pp. 11–33; Banaji, *Agrarian change*, pp. 39–40, 60–70.

24 A. D. Lee, 'The eastern empire: Theodosius to Anastasius', in Cameron *et al.* (eds.), *Late Antiquity*, p. 35; M. McCormick, 'Emperor and court', in Cameron *et al.* (eds.), *Late Antiquity*, pp. 156–60; G. Dagron, *Naissance d'une capitale: Constantinople et ses institutions de 330 à 451* (Paris, 1974), pp. 77–92.

25 Liebeschuetz, *The decline and fall of the Roman city*, pp. 54–74; Banaji, *Agrarian change*, pp. 6–22; Ward Perkins, 'Land, labour and settlement', pp. 315–45; C. Wickham, *Framing the early Middle Ages: Europe and the Mediterranean, 400–800* (Oxford, 2005), pp. 443–59.

26 P. Heather, 'Senators and senates', in A. Cameron and P. Garnsey (eds.), *The Cambridge ancient history*, vol. XIII: *The late empire, AD 337–425* (Cambridge, 1998), pp. 204–9.

Romans; the idea that an emperor should declare 'all heresies forbidden by both divine and imperial laws', as did Gratian, Valentinian and Theodosius in 379, would have been bizarre.²⁷

If there was a fundamental weakness in the new order it lay in the inherent limits of such pretensions to central control. In the republic and early empire a Roman identity had been a privilege which provincials had struggled to obtain and display; now each city was as Roman as the next. The early empire was compensated for its minimal governmental structure by the desire of provincial families to be Roman. In the empire of Late Antiquity those same provincials were without question Roman citizens, and had nothing to prove. The ties that bound centre to periphery may have been stronger than before, but more depended upon them.²⁸

The other weakness was that the empire's fortunes were thenceforth irretrievably tied to its relationship with Iran.

Rome and Persia

Fortunes of war, 284 628

The crisis of the mid third century was surmounted, but it left emperors in no doubt that relations with the Persians had to be their first priority, and that major deployments anywhere other than the Persian front would depend on peace there. That fact did much to govern the history of the Roman empire through to the seventh century.

Much of the success of Diocletian's regime (284 305) followed from the victory secured in 298 by his junior colleague, the Caesar Galerius. His crushing defeat of the Persian shah Narseh was to win nearly forty years of comparative security, during which time many of the crucial reforms that were to reshape the empire took place. On the other hand, the long reign of Constantius II (337 61) was equally shaped by an inability to achieve a decisive victory over the Persians. Late in his reign his father Constantine had provoked a war with Persia, and this was inherited by Constantius, who found himself pinned to the east and unable adequately to deal with the threats posed by usurpers or barbarian neighbours in the Balkans and west. His need for someone to act as an imperial representative in Gaul eventually forced Constantius to appoint his nephew Julian as Caesar in effect junior emperor.

27 *Codex Theodosianus*, XVI.5.5, ed. T. Mommsen and P. M. Meyer (Berlin, 1905), p.856, trans. C. Pharr as *The Theodosian Code* (New York, 1952), pp. 450 1.

28 Liebeschuetz, *The decline and fall of the Roman city*, pp. 346 51.

The step was risky because the emperor had been responsible for the death of many of Julian's relatives, including that of his brother Gallus in 354, and in the event failed. When in 358 Shapur captured the great fortress city of Amida (modern Diyarbakr) and Constantius ordered Julian to send troops to the east, the Caesar refused. In 360 Julian was proclaimed emperor in Paris, and marched east to seize power for himself.²⁹

The expected showdown did not happen. Constantius died on the road, and Julian inherited the empire without a battle. Less than two years later the new emperor led his army into Iraq. The invasion force reached the Persian capital of Ctesiphon on the Tigris, but found the improved defences of the Persian capital too strong to storm. The retreat in the middle of an Iraqi summer turned to disaster when the emperor was mortally wounded in a skirmish. A group of junior officers proclaimed one of their number, Jovian, emperor. The retreat continued, but the army was now starving, and once frantic attempts to cross the Tigris back into Roman territory had failed, Jovian had little choice but to negotiate, and eventually concede a humiliating treaty in exchange for their escape.³⁰

Julian's end has inevitably coloured all perceptions of the man and his decision to invade Persia. In Ammianus' carefully constructed narrative it seems a fated error, to which Julian was lured by visions of glory; but seen from the perspective of 361 it was arguably the obvious lesson of the previous sixty three years. Galerius' victory had made the empire manageable; Constantius' inability to bring Shapur to battle had caused him to stumble from one crisis to the next. Julian 'the apostate' is famous as the emperor who wanted to roll back Christianity. If he were to have any chance of achieving that end he needed to begin with victory over Persia. A stalemate would have paralysed Julian as effectively as it had his uncle – not just as regards Christianity, but in terms of ruling the empire at all.

These conclusions were as true after 363 as before, but in the event both empires came to be preoccupied by other problems. In 376 the emperor Valens was confronting the Persians in Armenia when envoys arrived from two important Gothic groups, the Tervingi and Greuthungi, whose position

29 R. C. Blockley, *East Roman foreign policy: Formation and conduct from Diocletian to Anastasius* (Leeds, 1992), pp. 5–24; D. Hunt, 'The successors of Constantine', in Cameron and Garnsey (eds.), *The late empire*, pp. 39–43; Dodgeon and Lieu (eds.), *The Roman eastern frontier*, pp. 125–230.

30 Blockley, *East Roman foreign policy*, pp. 24–30; D. Hunt, 'Julian', in Cameron and Garnsey (eds.), *The late empire*, pp. 73–7; J. Matthews, *The Roman Empire of Ammianus* (London, 1989), pp. 130–79; Dodgeon and Lieu (eds.), *The Roman eastern frontier*, pp. 231–74.

north of the Danube was being rendered untenable by the impact of migrating Huns. The Goths were already clients of the Romans; they now wanted to be given land inside the empire. Pinned to the east by operations against the Persians, Valens had little choice but to agree for the moment, but as soon as he could disengage, the emperor marched his field army to the west, and set out to crush these unwanted immigrants. All looked set for an imperial triumph, but on 9 August 378 his army blundered into battle near Adrianople (mod. Edirne), and by the end of the day the emperor and two thirds of his army (perhaps some 15,000 men) had been killed.³¹

The consequences of this unexpected disaster were played out over the following decades. The Romans recovered, but could not defeat the Goths; the Goths could not fight their way to security, and they found it very hard to force the Romans to negotiate in good faith or to abide by anything agreed. In the early fifth century the Goths, now led by Alaric, moved to Italy in an attempt to extract terms from the western empire, but with no more success. Threatening Rome itself, and even carrying out that threat on 24 August 410, did Alaric little good. His successor, Athaulf, led the Goths to Gaul, where eventually Goths and Romans made peace in 418. But by now the context was changing radically. In 406 several barbarian groups, including Vandals, Suevi and Alans, had crossed the Rhine into Roman territory. In 410 Britain slipped from imperial control; in 439 the Vandals conquered Carthage, and with it one of the chief sources of revenue for the western empire. Although the last emperor of the west was not deposed until 476, in reality the western empire had already fallen a generation before.³²

During these years successive eastern regimes in Constantinople were pre occupied first by the remaining Goths in the Balkans, then by the appalling implications of the Vandal conquest of Africa and the appearance of a Vandal war fleet in the Mediterranean, and from the late 430s by the Huns. The latter were a steppe nomad people, whose westward migration had triggered the Gothic crisis of 376–8 and quite likely the 406 Rhine crossings too. Up to about 440 the Huns had operated as small bands, exploiting whatever opportunities arose. At this point Attila and his brother Bleda managed to establish a powerful nomad state, which in effect operated a Europe wide extortion racket for the next thirteen years. Attila's death in 453 paradoxically made the situation worse,

31 Blockley, *East Roman foreign policy*, pp. 30–9; P. Heather, *Goths and Romans 332–489* (Oxford, 1991), pp. 122–47.

32 P. Heather, *The fall of the Roman Empire: A new history* (Basingstoke, 2005), pp. 182–299; I. N. Wood, 'The barbarian invasions and first settlements', in Cameron and Garnsey (eds.), *The late empire*, pp. 516–37.

as former clients of the Huns, such as the Gepids and those Goths still in the Balkans, struggled for security and independence. It was only in 489, when Theodoric the Amal, who had eventually managed to establish his authority over the Balkan Goths, was persuaded to invade Italy, where he would rule in the name of the eastern emperor, that Constantinopolitan rulers could begin to look beyond successive crises on their Balkan doorstep.³³

The Persians might have been expected to take ruthless advantage of Roman difficulties, and there were short wars in 420–1 and again in 440, but in general throughout the late fourth and fifth centuries the Persian response was tempered by a combination of internal political problems, Roman concessions and their own growing difficulties in the east. By themselves disputed successions and unstable regimes, such as followed Shapur II's death in 379, Yazdegerd I's in 420, Wahram V's in 438, and Yazdegerd II's in 457, would have tended to provoke hostilities as new shahs looked to prove their charisma by victory over Rome, but in each case other factors worked to deter conflict. In 387 Theodosius I, heavily committed in the west, conceded effectively everything that the Persians demanded in Armenia, so giving up a Roman hegemony in this strategic mountainous region that went back to the first century CE. The Romans were also prepared to pay for peace. Whether this was a regular payment fixed by treaty, or whether it was envisaged as a Roman payment for Persian costs in blocking the Caucasian passes against enemies that might threaten both empires, or the dates when any of this happened, is all equally uncertain, but payments were made, and the Persians found these increasingly attractive the more they began to face serious difficulties on their own eastern frontiers.³⁴

Through the fifth century Roman Persian diplomacy was increasingly conducted in a language of brotherhood, friendship and coexistence as two sources of light. But we should be careful not to take this too seriously. Any diplomacy intended as more than sabre rattling has to be conducted in mutually respectful terms. Peace was a product of Roman weakness and Persian satisfaction with their gains; before the end of the century neither condition would still apply.³⁵

In about 469 Shah Fīruz was defeated and captured by the Hephthalites, an increasingly powerful nomad confederation on Persia's eastern frontier. To obtain his release he was forced to pay a huge ransom and promise not to

33 Heather, 'The Huns'; Heather, *Goths and Romans*, pp. 227–308.

34 Blockley, *East Roman foreign policy*, pp. 39–86; G. Greatrex and S. N. C. Lieu (eds.), *The Roman eastern frontier and the Persian Wars*, pt 2: AD 363–630 (London and New York, 2002), pp. 16–17, 28–30, 32–3, 36–46.

35 Blockley, *East Roman foreign policy*, pp. 106–27.

attack the Hephthalites again. His son Kawad was left as a hostage while the necessary gold treasure was gathered. For the moment these events tended to preserve peace with Rome, but if victory against the Romans was important for a Sasanian shah, success against the nomads of Central Asia was essential. One of the fundamental tasks of Persian kings was to defend the settled land of Iran against the nomads of Turan. It was a duty with sacred dimensions that lay at the heart of the Zoroastrian religion, and Fīruz returned with his charisma severely tarnished. Revolt could be expected. If Fīruz was to survive, he needed to return to the field and bring victory. But the war of revenge, eventually launched in 484, led to the Sasanian Adrianople. The Persian army was destroyed and the shah himself killed on the battlefield. The dynasty faced ruin. The new shah, Fīruz's brother, Balas, was toppled in 488; Kawad, the hostage of 469, lasted less than ten years, to be ousted by his brother, Zamasphes, but managed to regain power in 498. The success of the radical Zoroastrian Mazdakite movement during these years is a measure of how far the established order had been rocked by 484 and its aftermath. To survive Kawad needed money and military success. War with Rome was the obvious solution, and in 502 Persian armies invaded the empire.³⁶

The war of 502 opened a cycle of conflict that would continue until 628, and in many ways set the pattern for what followed. Kawad's troops captured Theodosiopolis, the key to the defence of Roman Armenia, and then switched south to attack Amida, the largest and most heavily fortified city of Roman Mesopotamia, which fell at the beginning of 503 after a hard fought siege of ninety seven days. The Romans counter attacked in 503 and 504, but achieved no more than stalemate. Having achieved his main war aims of prestige and booty, Kawad was ready to negotiate, and a seven year truce was agreed in 506. The Romans recovered Amida and Theodosiopolis, and in exchange made what must have been a substantial payment to the Persian treasury.³⁷

The Persians were to enjoy similar success on what one may call the 'central front', the traditional area of Roman Persian conflict since the third century, during most years of the wars that followed. When fighting broke out again in 527, the year that Justinian succeeded as emperor, the Romans failed to take Nisibis, or any other major Persian stronghold in the region, and equally failed to inflict a decisive defeat on the Persian army. A Roman victory

36 G. Greatrex, *Rome and Persia at war, 502–532*, ARCA Classical and Medieval Texts, Papers and Monographs 37, (Leeds, 1998), pp. 43–52; K. Schippmann, *Grundzüge der Geschichte des sasanidischen Reiches* (Darmstadt, 1990), pp. 43–50; A. Christensen, *L'Iran sous les Sassanides*, 2nd edn (Copenhagen, 1944), pp. 290–7, 335–53.

37 Greatrex, *Rome and Persia at war*, pp. 73–119.

at Dara in 530 was enthusiastically celebrated in Constantinople, but there is no evidence that it seriously hindered Persian operations, and in any case it was offset by the defeat at Callinicum in 531. The payment of 11,000 pounds of gold, made by the Romans in order to secure the 'Eternal Peace' of 532, is comment enough on where the military advantage lay. When Khusras broke the peace in 540, he managed to sack Antioch and extort huge sums from a series of Syrian cities before agreeing to a truce in 545 and again in 551. The latter involved regular Roman payments to the Persians, something Procopius tells us had not been conceded before, and were highly unpopular in Constantinople where the warm official welcome for Persian ambassadors carried its own message. The final treaty agreed in 561 was on much the same terms. The war that broke out in 572 was launched by Justinian's nephew and heir, Justin II, as a war of revenge, but Roman armies initially at least did no better in Mesopotamia than they had in the past. Another attempt on Nisibis failed, and the Persians responded by taking Dara, a disaster that seems to have sent Justin mad. During the 570s and 580s Roman raids deep into Persian territory did do something to alter the balance, but the war's triumphant conclusion in 591 owed everything to a political crisis among their enemies and little to any change of fortune in Mesopotamia. The last Roman Persian war, which broke out in 603, repeated the pattern. Dara fell to the Persians in 604, but this time it was followed by a general collapse of the Mesopotamian front during the years 607-10, which opened the way for the Persian conquest of Syria in 613, Palestine in 614 and Egypt in 616. All Roman attempts at a counter attack in this region failed utterly.³⁸

The reasons for this Persian supremacy are not entirely clear. It presumably has something to do with the qualities of the Sasanian field army. Its heavy cavalry was famous, and despite some misleading comments from Ammianus and Procopius, one may deduce the existence of an effective infantry and system of supply from the accounts of successful siege operations against a series of heavily fortified and staunchly defended Roman cities.³⁹

38 Greatrex and Lieu (eds.), *The Roman eastern frontier*, pp. 82-197; Greatrex, *Rome and Persia at war*, pp. 139-221; M. Whitby, *The emperor Maurice and his historian: Theophylact Simocatta on Persian and Balkan warfare* (Oxford, 1988), pp. 250-304; Sebeos, *The Armenian history attributed to Sebeos*, trans. R. W. Thomson, with commentary by J. Howard Johnston, *Translated Texts for Historians* 31, 2 vols. (Liverpool, 1999), vol. II, pp. 193-213; M. Whitton, *The making of orthodox Byzantium, 600-1025* (Basingstoke, 1996), pp. 69-76.

39 Howard Johnston, 'The two great powers in Late Antiquity', pp. 166-7, 174-5, 185-6; Greatrex, *Rome and Persia at war*, pp. 52-9; for misleading comments see Ammianus Marcellinus, *Rerum gestarum libri*, XXIII.6.83, ed. and trans. J. C. Rolfe, 3 vols. (Cambridge, MA, 1935-9; rev. edn. 1986), vol. II, pp. 394-7; Procopius, *History of the wars*, I.xiv.25, ed. and trans. H. B. Dewing, 5 vols. (Cambridge, MA, 1914-28), vol. II, pp. 120-1.

Some Roman troops did not perform well in face of the Persians, but one must be careful to compare like with like. The Roman army included four categories of soldier: *comitatenses*, *foederati*, *bucellarii* and *limitanei*. The *comitatenses* were the descendants of the earlier legions; the *foederati* were units recruited at least in theory from specific ethnic groups, sometimes outside the borders of the empire; the *bucellarii* were units raised personally by individual Roman generals. They were all in effect full time soldiers and together made up the field army. The *limitanei* were troops permanently based in the frontier regions and supported by a mixture of tax free estates and cash salaries. They were on occasion deployed as part of a field force, but normally it appears they were to be found scattered in small units garrisoning the empire's many hundreds of forts and cities. While there is no reason to view the *limitanei* as an ineffective peasant militia, they were unlikely to have been trained or equipped to match the shah's front line soldiers.⁴⁰ How the soldiers of the sixth century Roman field army compared to their Persian equivalents is hard to judge. There is no doubt that the Persians benefited from the fact that Roman resources were stretched thin, with the same front line troops required in both the west and the east. Persian successes tended to come early in a war, before reinforcements could arrive, after which stalemate ensued. On the other hand, even in 572, when the Roman offensive had been planned in advance to catch the Persians unawares, it was the latter who came out on top.⁴¹ In the third and fourth centuries it had been possible for Romans to assume that Persian success was merely the consequence of temporary Roman disorder; by the sixth and seventh that had long ceased to be the case, and Persian forces were recognised as formidable adversaries.⁴²

But that was not the only respect in which the sixth and seventh centuries were different from the third and fourth. In the age of Diocletian, Shapur II and Julian, the Mesopotamian front had been in effect the only front, and the conflict had been almost solely between the armies of Rome and Persia. In the age of Kawad, Justinian and Heraclius, that was no longer the case. The conflict was waged as far afield as the Yemen, the

40 M. Whitby, 'Recruitment in Roman armies from Justinian to Heraclius (ca. 565–615)', in Cameron (ed.), *States, resources and armies*, pp. 61–124; M. Whitby, 'The army, c.420–602', in Cameron et al. (eds.), *Late Antiquity*, pp. 288–93, 300–8.

41 Whitby, *The emperor Maurice and his historian*, pp. 250–8.

42 For the third and fourth centuries see Whitby, *The emperor Maurice and his historian*, pp. 203–4; see in particular the comments of Dio Cassius in Dodgeon and Lieu (eds.), *The Roman eastern frontier*, p. 16; For the sixth and seventh centuries see Greatrex and Lieu (eds.), *The Roman eastern frontier*, pp. 179–81.

Transcaucasus and the steppes of Central Asia. Those waging it had come to include Arabs, Laz, Albanians, Armenians and Turks, acting as much for their own purposes as for the war aims of the two powers. What had been a war largely confined to Mesopotamia had expanded eventually to become a Eurasian world war. Persian supremacy on the central front was not repeated everywhere else, and the wider the war became, the more fragile did the Persian position prove to be.⁴³

By the 620s the Roman empire appeared on the verge of extinction. The loss of Syria, Palestine and, above all, Egypt had taken away the empire's richest provinces. Roman rule in these regions was being supplanted by Persian administration that was set to stay. In 626 a combined siege of Constantinople by the Persians and Avars narrowly failed. The next year the emperor Heraclius opened operations in the Transcaucasus, the mountainous zone between Roman Anatolia to the west, Persia to the south and east, and the steppe world to the north. The Romans had been doing business with the powers of the steppe at least since the period of Hun dominance in Europe in the middle of the fifth century. Roman armies recruited heavily among the steppe peoples, and Roman ambassadors had learnt to negotiate with steppe rulers who spoke neither Greek nor Latin, and shared with the Romans neither religion nor political ideology. By 560 the Hephthalite hegemony in Central Asia had been replaced by that of the even more formidable Turks. In 568/9 a Turkish embassy arrived in Constantinople. In the following year a Roman embassy made a return journey of some 10,000 kilometres to visit the Turkish *khaqan*. With memories of fifth century humiliations at the hands of the steppe powers, it is no wonder that the Persians made every effort to break these links, including the attempted ambush and murder of the returning envoys.⁴⁴ In the short term Roman hopes of a combined assault on Iran came to nothing, but in 627 these links paid off. The Turks crossed the Caucasus, and with these powerful allies Heraclius launched the great counter attack that would save the Roman empire, and, after nearly twenty three years of almost uninterrupted victory, finally bring Shah Khusrau II's regime to defeat and disaster.⁴⁵

43 Greatrex and Lieu (eds.), *The Roman eastern frontier*, pp. 78–80, 82–4, 94–5, 115–20, 136–42, 149, 153, 163, 167, 171, 178.

44 *Ibid.*, pp. 136–7.

45 *Ibid.*, pp. 198–226; J. Howard Johnston, 'Heraclius' Persian campaigns and the revival of the East Roman Empire, 622–630', *War in History*, 6 (1999); J. Howard Johnston, 'Pride and fall: Khusro II and his regime, 626–628', in *La Persia e Bisanzio*, Atti dei convegni Lincei 201, Roma, 14–18 ottobre 2002 (Rome, 2004).

Rome and the Arabs: centre and periphery in the Roman Near East

The initial Roman conquest of the Near East in the first century BCE had left most of the region in the hands of greater or lesser client rulers. Over the course of the first, second and third centuries CE these kingdoms and principalities were gradually abolished or annexed. Judaea became a province for the first time in 6 CE, and then definitively in 70 when it became Syria Palestina. The Nabataean kingdom in what is now Jordan and northern Saudi Arabia was annexed in 106 to create the province of Arabia. Further north, the kingdoms of Emesa (Homs) and Commagene were annexed in 72 CE. Only east of the Euphrates did such entities survive; the kingdom of Edessa was annexed only in 212–13, while that of Hatra survived as an ally until its destruction by the Sasanians in 242.⁴⁶

Diocletian's response to the region's problems at the end of the third century would appear to have drawn on his experience of the empire's northern frontiers. The formerly very lightly fortified frontiers of the Near Eastern provinces were now lined with legionary fortresses, auxiliary forts and watchtowers to match those on the Rhine and the Danube.⁴⁷ Very soon, however, it must have been realised that the costs of completing this frontier, let alone garrisoning and maintaining it for the future, were unsustainable, and in a large degree out of all proportion to any likely threat. On the northern Mesopotamian front, where Roman and Persian armies faced each other across good campaigning country, such fortresses were essential – indeed, cost effective – but further south the only possible threat was from Arab nomads, and these needed a policing operation rather than this extraordinary fortified belt stretching for hundreds of miles through a barely inhabited landscape.⁴⁸ The obvious and traditional answer to this fairly low grade security problem was the use of clients and allies, but, possibly with the experience of Palmyra in mind, or perhaps simply because there was no

46 Sartre, *The Middle East under Rome*, pp. 70–87, 344–7; Sartre, 'The Arabs and the desert peoples', pp. 507–15.

47 Millar, *The Roman Near East*, pp. 180–90; Isaac, *The limits of empire*, pp. 161–71; Parker, 'The defense of Palestine and Transjordan', pp. 372–4; S. T. Parker, *The Roman frontier in Central Jordan: Final report on the Limes Arabicus Project, 1980–1989*, 2 vols., Dumbarton Oaks Studies 40 (Washington, DC, 2006), vol. II, pp. 541–50.

48 Isaac, *The limits of empire*, pp. 214–18; E. B. Banning, 'Peasants, pastoralists and Pax Romana: Mutualism in the southern highlands of Jordan', *BASOR*, 261 (1986); E. B. Banning, 'De Bello Paceque: A reply to Parker', *BASOR*, 265 (1987); cf. Parker, 'The defense of Palestine and Transjordan', pp. 374–9; Parker, *The Roman frontier in Central Jordan*, vol. II, pp. 538–41.

other realistic option, the traditional answer took a new form in the fourth century: Rome turned not to the sedentary elites of the Fertile Crescent, but rather to the nomads or semi nomads of the desert and its margins.

There are references to phylarchs of the Arabs, in other words shaykhs and their tribal followers, serving the Romans and Persians in the first century. There is epigraphic evidence to suggest that nomads were settling on the fringes of the Fertile Crescent. There is also explicit literary evidence that between the fourth century BCE and the first century CE the Nabataeans had followed the same path.⁴⁹ Otherwise there are the so called Šafaitic inscriptions, of which more than 20,000 have been recorded in the Syrian desert. They appear to date from the first century BCE to the fourth century CE, and they may be best regarded as the doodlings of bored nomads. Most give a name and some genealogy; some are prayers; and some talk of current events, mostly to do with the nomadic cycle, but occasionally referring to happenings in the world beyond the desert. These nomads hunt and occasionally make raids, but their primary occupation is tending their animals. Crucially, there is nothing here to suggest a powerful tribal confederation or any significant threat to the settled world.⁵⁰

Banditry was a perennial issue throughout the region. Inscriptions from Palmyra show that it was necessary to organise merchants crossing the desert into caravans, and that security could be a problem. An inscription of 199 CE honours Ogelos son of Makkaïos, 'for having given satisfaction through continual commands against the nomads and for having provided safety for the merchants and caravans in all his caravan commands'.⁵¹ But this is no more than dealing with crime; before the late third century at the earliest the desert nomads were, in military and political terms, of trivial importance.

From the fourth century this began to change. Ammianus Marcellinus, a Roman historian who had first hand experience from serving in Syria in the 350s and 360s, talks of a new Persian strategy based on 'theft and robbery

49 Sartre, *The Middle East under Rome*, pp. 233–9. For the Nabataeans see Diodorus Siculus, *Bibliotheca historica*, ed. and trans. C. H. Oldfather, C. L. Sherman, C. Bradford Welles, R. M. Geer and F. R. Walton, 12 vols. (Cambridge, MA, 1933–67), II 48.26, XIX.94.2–4, 96.3; Strabo, *Geography*, ed. and trans. H. L. Jones, 8 vols. (Cambridge, MA, 1917–32), XVI.4.18, 21; Pliny, *Naturalis historia*, ed. and trans. H. Rackham, W. H. S. Jones and D. E. Eichholz, 10 vols. (Cambridge, MA, 1917–32), VI.32.143–4; Millar, *The Roman Near East*, pp. 400–1.

50 M. C. A. Macdonald, 'Nomads and the Hawran in the late Hellenistic and Roman periods: A reassessment of the epigraphic evidence', *Syria*, 70 (1993); cf. Parker, *The Roman frontier in Central Jordan*, vol. II, pp. 535–7.

51 For banditry see Matthews, *The Roman Empire of Ammianus*, pp. 346–7; for Palmyra see J. Starcky, *Inventaire des inscriptions de Palmyre*, X: *L'agora* (Damascus, 1949), no. 44, p. 31, cited in Millar, *The Roman Near East*, p. 332.

rather than on the pitched battles that had been their previous practice', a new strategy in which 'Saracen' allies who specialised in such raiding were essential.⁵² One such ally on the Persian side described by Ammianus was a certain 'Malechus called Podosaces, phylarch of the Assanitic Saracens, a notorious robber who had long raided [the Roman] frontier districts with every kind of cruelty'. A Roman equivalent was Mavia, whose raids into Palestine and Phoenicia, and her defeat of the forces sent against her, forced the Roman authorities into recognising her as an ally in the 370s.⁵³ By the beginning of the fifth century at the latest a number of nomad shaykhs had made treaties with Rome and Persia. From these 'Saracen phylarchs', as Roman authors term them, the great powers gained cheap security and useful auxiliaries who could be used to ravage enemy territory and counter those of their opponents. In turn the shaykhs earned subsidies that enabled them to exercise a substantially new degree of authority in what had previously been a stateless tribal society. The fact that Podosaces is called 'Malechus', which is clearly the Semitic word for king, or that an inscription near the Roman fort at Namara in the Ḥawran south east of Damascus and seemingly datable to 328 CE can describe a certain Imru' al Qays son of 'Amr as 'king of all the Arabs' are signs of how the desert world was changing.⁵⁴ The sixth century citizen of Edessa in northern Syria who wrote the chronicle attributed to Joshua the Stylite was evidently right when he said that war between Rome and Persia 'was the cause of much enrichment to the Saracens of both sides'.⁵⁵ Bedouin impact on great power politics was as yet very small, but the impact of great power politics on the Bedouin world, or rather the impact of great power conflict and the subsidies and employment it engendered, was clearly profound.

By the sixth century, nomad confederations, the most important being that of the Ghassanids, played a key role in the defences of the Roman Near

52 Ammianus Marcellinus, *Rerum gestarum libri*, XVI.9.1; XXIII.3.8; XXXI.16.5.

53 For Malechus called Podosaces see *ibid.* XXIV.2.4; for Mavia see Socrates, *Ecclesiastical history*, ed. G. C. Hansen, trans. P. Périchon and P. Maraval as *Histoire ecclésiastique*, vol. I (Paris, 2004), IV.36; Sozomen, *Ecclesiastical history*, ed. J. Bidez, trans. A. J. Festugière as *Histoire ecclésiastique*, vol. I (Paris, 1983), VI.38.

54 Among the extensive literature on the Namara inscription, see P. Bordreuil, A. Desreumaux, C. Robin and J. Teixidor, in Y. Calvet and C. Robin, *Arabie heureuse Arabie déserte: Les antiquités arabiques du Musée du Louvre*, Notes et documents des musées de France 31 (Paris, 1997), pp. 267–9 (no. 205, Linteau inscrit: AO 4083); M. Zwettler, 'Imra'alqays, Son of 'Amr: King of ...??', in M. Mir and J. E. Fossu (eds.), *Literary heritage of classical Islam: Arabic and Islamic studies in honor of James A. Bellamy* (Princeton, 1993), pp. 3–37, pl. 1–5. I am very grateful to Michael Macdonald for advice on this text.

55 *The chronicle of Pseudo Joshua the Stylite*, trans. with notes and introd. by F. R. Trombley and J. W. Watt, *Translated Texts for Historians* 32 (Liverpool, 2000), p. 97.

East. In 528 or 529 the emperor Justinian elevated the Ghassanid shaykh, al Ḥarith ibn Jabala (known in Greek sources as Arethas), who was at that stage one of a number of allied phylarchs, to become supreme phylarch, and gave him the title of *basileus*, or king. Justinian was responding to the threat posed by the Sasanian shah's chief Arab ally, the Lakhmid leader, al Mundhir, whose position seems to have allowed him to mobilise resources on a scale that none of the Romans' phylarchs could match. Procopius, who provides much of our information, was not an admirer of Saracens in general, or of al Ḥarith in particular, and he blamed the latter for the Roman defeat at Callinicum in 531 and more generally for pursuing his own interests rather than the common good, but at least as a counter to the Lakhmids the policy appears to have been a complete success. Lakhmid raids had caused considerable damage in the early sixth century, but by the 550s the balance had shifted in favour of the Ghassanids. In 554 al Mundhir himself was defeated and killed, and in 575, or shortly afterwards, al Ḥarith's son and successor, al Mundhir ibn al Ḥarith, sacked the Lakhmid capital of al Ḥīra in southern Iraq. Even after al Mundhir's arrest and exile to Sicily in the 580s brought to an end the position of the Ghassanids as Rome's chief Arab allies, Lakhmid power did not recover.⁵⁶

It is important not to exaggerate the scale of these groups or their importance to their employers. Despite their titles, Imru' al Qays and Podosaces were no more than Bedouin shaykhs with subsidies – figures very similar to the Rashīdīs of Hayil who acted as clients of the Ottomans on the eve of the First World War – and those subsidies are likely to have tailed off in the fifth century as Roman Persian warfare went through an extended period of relative calm. Even the Ghassanids were no more than particularly successful examples of the phenomenon. They were Christians; they were generous patrons of the non Chalcedonian Church; they were builders of monasteries; but the Ghassanids under the Jafnid dynasty, to which al Ḥarith and al Mundhir belonged, remained essentially a nomad tribal confederation. This point is sometimes missed or resisted because of the assumption that 'nomad' and 'sedentary' are mutually exclusive categories. The fact that the Jafnids were builders, that their regular campsites became permanent and no doubt relatively prestigious settlements, that they visited Constantinople, or that

56 Greatrex and Lieu (eds.), *The Roman eastern frontier*, pp. 85–8, 93, 100, 123, 129, 153, 162–5, 168; M. Sartre, *Trois études sur l'Arabie romaine et byzantine* (Brussels, 1982), pp. 162–72, 189–94; A. H. M. Jones, J. R. Martindale and J. Morris, *The prosopography of the later Roman Empire*, 3 vols. (Cambridge, 1971–92), vol. III, s.v. 'Alamundarus' and 'Arethas', pp. 34–7, III 13.

they were regarded as among the leading laymen of the non Chalcedonian Church, is not incompatible with a Bedouin identity and culture.⁵⁷

By the 580s both Romans and Persians appear to have come to the conclusion that subsidising groups such as the Ghassanids or the Lakhmids on the scale that had made them the dominant forces among the tribes of the Syrian desert was no longer worthwhile. The story of Roman relations with the Ghassanids is told by the Syriac historian John of Ephesus in terms of Chalcedonian ingratitude to their loyal and orthodox allies, but John's is a very particular perspective. His is confessional history, and there can be little doubt that had al Mundhir not been an anti Chalcedonian John would have had little interest in or sympathy for his cause.⁵⁸ The Romans had built up the Jafnids as leaders of the Ghassanids in order to counter the threat from the Persian subsidised Lakhmids. Once that threat was over there was apparently no need for Bedouin allies so powerful, or so independent minded.

But the genie could not be put back in the bottle. The inhabitants of the empire's desert periphery were richer, more organised and much more militarily effective than they had been three hundred years earlier.

The Roman Near East and the rise of Islam

Four centuries of Roman Persian conflict had culminated in a twenty five year war that had left both empires exhausted. The state of Persia may be gauged by the fact that Heraclius' victories in 628 so rapidly triggered a

57 L.I. Conrad, 'The Arabs', in Cameron *et al.* (eds.), *Late Antiquity*, pp. 692 4; R. G. Hoyland, *Arabia and the Arabs from the Bronze Age to the coming of Islam* (London and New York, 2001), pp. 238 42; M. Whitby, 'Greek historical writing after Procopius: Variety and vitality', in A. Cameron and L. I. Conrad (eds.), *The Byzantine and early Islamic Near East*, vol. I: *Problems in the literary source material* (Princeton, 1992), pp. 74 80; M. Whittow, 'Rome and the Jafnids: Writing the history of a 6th c. tribal dynasty', in J. H. Humphrey (ed.), *The Roman and Byzantine Near East*, vol. II: *Some recent archaeological research*, JRA Supplementary series 31 (Portsmouth, RI, 1999); D. Genequand, 'Some thoughts on Qasr al Hayr al Gharbi, its dam, its monastery and the Ghassanids', *Levant*, 38 (2006); cf. I. Shahid, *Byzantium and the Arabs in the sixth century* (Washington, DC, 1995), vol. I; and his response to Whittow, 'Rome and the Jafnids', I. Shahid, 'Byzantium and the Arabs in the sixth century: A propos of a recent review', *Byzantinische Forschungen*, 26 (2000).

58 John of Ephesus, *Ecclesiastical history*, III 40 42, 54, 56, IV.36, 39, 40, 42, VI.3, 4, 16, 18, ed. E. W. Brooks, *Iohannis Ephesini Historiae Ecclesiastica pars tertia*, CSCO, Scr. Syr. III.3 (Louvain, 1935 6), text: pp. 173 7, 181 2, 216 21, 224 5, 280 7, 312 14; Latin translation: pp. 129 32, 135 6, 162 6, 168 9, 212 17, 237 8; English translation: R. Payne Smith, *The third part of the ecclesiastical history of John, Bishop of Ephesus* (Oxford, 1860), pp. 236 42, 294 300, 304 6, 370 9, 413 15; J. van Ginkel, 'John of Ephesus: A monophysite historian in sixth century Byzantium', Ph.D. thesis, Groningen (1995), pp. 99 101, 166 8, 185 94, 216 17.

political crisis, the evacuation of the occupied territories and the Persian agreement to peace on the *status quo ante*. The Roman position was only a little less serious. The war had been fought largely on Roman territory, and some of the empire's richest provinces in Egypt and the Levant had been occupied for nearly two decades. A generation had grown up for whom Roman rule was no longer an inevitable fact of life. Nonetheless, the war had ended in a Roman victory, celebrated by Heraclius when he restored the True Cross to Jerusalem on 21 March 630, and, given time, the ties that bound Constantinople to the Near Eastern provinces would presumably have been refurbished.⁵⁹ In the event, of course, that was not to happen. Within ten years imperial forces were close to being expelled from the entire region, and Christian power would not return until the Byzantine conquests of the late tenth century and the Crusades in the twelfth.

Muslim success may owe something to Roman war weariness, but that is a rather nebulous concept, possibly more appealing to scholars at their desks than to the sort of young men who actually filled the ranks of the Roman army. More important may have been the lack of ready cash. Heraclius had had to fight Persia without the revenues of Egypt and the Levant. To pay troops he had been forced to melt down silver treasures and bronze monuments, and having resorted to such expedients already, these reserves were not there to be used again in the 630s.⁶⁰ In any case it is worth remembering that all direct Roman attempts to expel the Persians from the Near East had signally failed, and Heraclius' final victory was won instead by an indirect approach through the Transcaucasus, where it had been possible to bring in the emperor's steppe nomad allies. Even then Heraclius only achieved his ends because Persia collapsed from within. None of these factors were applicable in the 630s. The Muslims did not have an accessible core territory to provide the target for such a counter blow; Heraclius' nomad allies, the Turks of the western khaqanate broke up in civil war after 630;⁶¹ and the first sign of exploitable political difficulties within the Muslim world would not come until the first *fitna* (656–61).

Muslim success clearly owes something too to the willingness of local elites to come to terms with the invaders. That willingness may have been

59 Whittow, *The making of orthodox Byzantium*, pp. 80–2; Howard Johnston, 'Pride and fall'.

60 M. Hendy, *Studies in the Byzantine monetary economy, c. 350–1450* (Cambridge, 1985), pp. 494–5, 498–9; A. Cameron and J. Herrin (eds.), *Constantinople in the early eighth century: The Parastaseis Syntomoi Chronikai* (Leiden, 1984), pp. 116–17, 229–30.

61 P. B. Golden, *An introduction to the history of the Turkic peoples: Ethnogenesis and state formation in medieval and early modern Eurasia and the Middle East* (Wiesbaden, 1992), p. 135.

reinforced by the experience of a relatively benign Persian occupation, under which life went on much as before.⁶² Why risk sack and ruin if nothing fundamental was at stake? Yet this was hardly new. The Roman empire was based on a state monopoly of military force, and imperial defence did not rest primarily on local initiative. Although it is easy to cite cases through the fourth to seventh centuries where walled cities, often led by their bishops, had been prepared to resist Persian attack, there are as many examples where cities were willing to negotiate and pay their enemies off.⁶³ A key factor was usually the proximity or otherwise of an imperial army likely to bring relief, and the situation in the Levant in the 630s, where after the battle of Yarmuk in 636 such an army was notably lacking, was one in which Roman provincials of any era would have looked to make terms.

Later Syriac and Coptic literature portrays Roman rule as alien and heretic, with the implication that much of the population was only too ready to betray the empire; but this is a view that was developed to give a meaningful historical past to Christian communities now living as second class citizens in an Islamic world, and needs to be discounted. It was comforting to believe that God's purpose in allowing the conquest might have been to protect them from oppression. The picture says little about the outlook of provincial society in 630 or before. Judging from contemporary accounts, such as the remarkable early sixth century chronicle traditionally misattributed to Joshua the Stylite, what is actually striking is the degree of identification between Near Eastern provincials and the Roman empire. Roman Persian warfare appears to have done more to bind the Near East to Rome than the reverse. Civilian military tensions, exacerbated on occasion by high taxation and inadequate protection from Persian raids, were obviously a divisive factor, but against that war tended to point up the gulf between Christian Romans and pagan Persians, and the scale of Roman deployment in the region created jobs that tied local hierarchies to the imperial centre, and brought 'Romans' from elsewhere to settle in the Near East. There clearly were groups in Near Eastern society, such as the Jews and some anti Chalcedonians, who had benefited from Persian patronage, who had no reason to celebrate with the emperor in 630, but there is no evidence that the core territories of the Roman Near East were animated by any strong separatist spirit in the early seventh century. It had taken over fifty years of complete neglect for Gaul to turn its back on the central government in the fifth

62 C. Foss, 'The Persian Near East (602–630 AD)', *JRAS*, 3rd series, 13 (2003).

63 For the various reactions of Syrian cities to Persian attacks in the 540s, see Procopius, *History of the wars*, II.xi.14–38, xii.1–2, 33–4, xiii.3–15, xx.1–16, xxi.30–32, xxvi.1–46, xxvii.1–46; ed. and trans. Dewing, vol. I, pp. 354–63, 372–7, 430–5, 448–51, 488–515.

century. Clearly such a process had started in the Near East during the Persian occupation, but it had not necessarily got very far.⁶⁴

Rome and the Arabs

A further factor was the political and military transformation of Bedouin society that had taken place since the third century. It is certainly not accurate, as was once common, to talk of the invading Muslims as simply a nomad irruption into the Fertile Crescent. Nomads were already a familiar feature of the Levant, and in any case early Islam was in many ways profoundly a culture of the sedentary world. But the fact remains that thanks to Roman Persian rivalry Arab tribal society had become much more militarised than it had been in the past, and, just as important, much more conscious of the possibility of gaining access to the wealth of the settled Near East. To judge from pre-Islamic poetry, the wealth of the Ghassanid and Lakhmid courts had had a profound impact on the Arab imagination.⁶⁵

It has been argued or implied that if only the Romans had maintained Ghassanid hegemony rather than breaking it up, then they would have been there to act as a shield against the armies of Arabia in the seventh century.⁶⁶ Given the marginal impact of the phylarchs on the course of sixth century warfare that may be hard to believe, but the end of the era of Roman and Persian subsidies may have had a less direct but equally profound effect. Writing in the ninth century, but copying an eighth century Greek translation of an older Syriac chronicle, composed somewhere in Syria Palestine,⁶⁷ Theophanes describes the origins of the Muslim invasions as follows.

Now some of the neighbouring Arabs were receiving small payments from the emperors for guarding the approaches to the desert. At that time a certain eunuch arrived to distribute the wages of the soldiers, and when the Arabs came to receive their wages according to custom, the eunuch drove them away, saying, 'The emperor can barely pay his soldiers their wages, much less these dogs!' Distressed by this, the Arabs went over to their fellow tribesmen,

64 J. Moorhead, 'The Monophysite response to the Arab invasions', *Byzantion*, 51 (1981); Whitby, *The emperor Maurice and his historian*, pp. 213–15; G. Dagron and V. Déroche, 'Juifs et Chrétiens dans l'Orient du viii^e siècle', *Travaux et Mémoires*, 11 (1991), pp. 22–32; Liebeschuetz, *The decline and fall of the Roman city*, p. 259.

65 Hoyland, *Arabia and the Arabs*, pp. 238–41; R. A. Nicholson, *A literary history of the Arabs* (Cambridge, 1930), pp. 37–54; R. Blachère, *Histoire de la littérature arabe des origines à la fin du xve siècle de J. C.*, 3 vols. (Paris, 1952–66), vol. II, p. 344, vol. III, p. 786.

66 E.g. Shahid, *Byzantium and the Arabs in the sixth century*, p. xxviii; Parker, *The Roman frontier in central Jordan*, vol. II, p. 569.

67 Theophanes, *Chronographia*, trans. C. Mango and R. Scott as *The chronicle of Theophanes Confessor* (Oxford, 1997), pp. lxxxii–iii.

and it was they that led them to the rich country of Gaza, which is the gateway to the desert in the direction of Mount Sinai.⁶⁸

The story may not be strictly true, but nonetheless embodies the truth that Roman Persian rivalry had created a society among the Arabs dependent upon subsidies. At the least the end of that subsidy era left a body of militarised tribesmen who were available to find new opportunities and even greater wealth in the service of Islam.

Conclusion

The rise of Islam is not explained by what had happened in the Roman Near East in Late Antiquity. But its phenomenal success owed much to the peculiar circumstances of the Roman Near East in the 630s, emerging from a twenty five year war with Persia, and to the militarised Arab society that more than three centuries of great power rivalry had created. In the wake of the First World War Wahhabī forces headed north from Arabia to exploit the power vacuum created by Ottoman defeat. In the event the vacuum had already been filled by the British, and the Wahhabīs retired to the south. It is hard not to suspect that early Muslim expansion would have had rather different results had the Muslim armies appeared before or after what looks like a uniquely favourable moment in Near Eastern history.

68 Theophanes, *Chronographia*, AM 6123, ed. C. de Boor as *Theophanis Chronographia*, 2 vols. (Leipzig, 1883–5), vol. I, pp. 335–6, Mango and Scott (trans.), *Chronicle*, p. 466.

The late Sasanian Near East¹

JOSEF WIESEHÖFER

The sources²

As opposed to the Arsacids, the Sasanians, like their Achaemenid ‘ancestors’ (see below), tell us a great deal about their notions of government, their public appearances and their political aspirations in both the domestic and foreign spheres. Their trilingual, bilingual or monolingual inscriptions (of the third century CE),³ the most prominent of which are probably Shapur (Shabuhr) I’s *res gestae* (ŠKZ),⁴ and the inscriptions of Diocletian’s rival Narseh from Paikuli (NPi),⁵ tell us not only about the conflicts with Rome (ŠKZ) and

- 1 I would like to thank Henning Börm (Kiel) and James Howard Johnston (Oxford) for their helpful comments and suggestions.
- 2 See J. Wiesehöfer, *Ancient Persia*, 2nd edn (London and New York, 2001), pp. 153–64 and 283–7; C. G. Cereti, ‘Primary sources for the history of inner and outer Iran in the Sasanian period’, *Archivum Eurasiae Medii Aevi*, 9 (1997) provides an excellent summary of the primary sources (epigraphy, archaeology, numismatics and sphragistics), with an extensive bibliography. The following books appeared too late to be considered in this chapter: V. S. Curtis and S. Stewart (eds.), *The Sasanian era* (London, 2008); T. Daryaei, *Sasanian Persia* (London, 2009); B. Dignas and E. Winter (eds.), *Rome and Persia in Late Antiquity* (Cambridge, 2007); R. E. Emmerick and M. Macuch (eds.), *The literature of pre Islamic Iran* (London, 2008); A. Gariboldi, *Il regno di Xusraw dall’anima immortale: Riforme economiche e rivolti sociali nell’Iran sasanide del VI secolo* (Milan, 2006); P. Pourshariati, *Decline and fall of the Sasanian Empire* (London, 2008) (which, however, does not make me change my mind on the empire’s end). For the Armenian sources see T. Greenwood, ‘Sasanian reflections in Armenian sources’, *e Sasanika* 5 (2008), at www.humanities.uci.edu/sasanika/pdf/e_sasanika5_Greenwood.pdf.
- 3 Cereti, ‘Primary sources’, pp. 19–27; edition: M. Back, *Die sassanidischen Staatsinschriften: Studien zur Orthographie und Phonologie des Mittelpersischen der Inschriften zusammen mit einem etymologischen Index des mittelpersischen Wortgutes und einem Textcorpus der behandelten Inschriften*, *Acta Iranica* 18 (Leiden, 1978); cf., however, the reviews of this book by D. N. MacKenzie, ‘Review of M. Back, *Die sassanidischen Staatsinschriften*’, *Indogermanische Forschungen*, 87 (1982); P. Gignoux, ‘Review of M. Back, *Die sassanidischen Staatsinschriften*’, *Studia Iranica*, 13 (1984); and P. Huyse, *Die dreisprachige Inschrift Šabuhurs I. an der Ka’ba i Zardūst* (ŠKZ), *CIL*, III, vol. I, texts I, vols. I–II (London, 1999), vol. I, pp. 14b–17a.
- 4 See the excellent edition of the inscription in Huyse, *Die dreisprachige Inschrift*.
- 5 See H. Humbach and P. O. Skjærvø, *The Sassanian inscription of Paikuli*, 3 parts (Wiesbaden, 1978–83).

dynastic enemies (NPi) respectively, but also reveal much about the early Sasanian court, its officials and the male and female members of the ruling family. In particular, they show how their rule was legitimised and how the kings represented themselves in their position as rulers (see below). It is no coincidence that Shapur had the 'account of his deeds' (*Tatenbericht*) placed on the Ka'ba i Zardusht at Naqsh i Rostam. This building had already been of particular importance in pre Sasanian times (although the exact nature of this importance is not known to us), and it was situated at a place where the Achaemenids (who were no longer known to the Sasanians by name) had commemorated themselves in rock tombs and bas reliefs.⁶

The trilingual nature of the inscriptions (in Middle Persian, Parthian and Greek) was also in imitation of 'the ancestors'. It is at the same time a reminder of the language policy the Arsacids adopted one, however, in which Middle Persian had supplanted Parthian as the primary official royal language.⁷ Narseh's bilingual inscription (in Middle Persian and Parthian) on the monument of Paikuli in Iraqi Kurdistan provides an account of his armed conflict with his rival Wahram III. In addition, it also provides an account of the acknowledgement rendered to him there by the great dignitaries of the empire, as well as of his coronation, which probably also took place there.⁸

Apart from those of the kings, other important third century inscriptions were only left behind by the mighty *mōbad* ('priest') Kerdīr (KKZ, KNRb, KNRm, KSM),⁹ the governor of Bīshapur (Weh Šābuhr) (ŠVŠ)¹⁰ and the

6 For the latest account regarding the importance of Ka'ba i Zardusht and Naqsh i Rostam in Sasanian times, the history of the discovery of the inscriptions, the research related to them and how they were dated, see Huyse, *Die dreisprachige Inschrift*, vol. I, pp. 6a 17b.

7 For Greek Iranian bilingualism in Sasanian times see M. Mancini, 'Bilingui greco iraniche in epoca sasanide: Il testo di Šāpuhr alla Ka'ba yi Zardušt', *Bilinguismo e biculturalismo nel mondo antico: Atti del colloquio interdisciplinare tenuto a Pisa il 28 e 29 settembre 1987* (Pisa, 1988); for parallels between Achaemenid and Sasanian inscriptions see P. O. Skjervø, 'Thematic and linguistic parallels in the Achaemenian and Sasanian inscriptions', *Acta Iranica*, 25 (1985); and P. Huyse, 'Noch einmal zu Parallelen zwischen Achämeniden und Sasanideninschriften', *Archäologische Mitteilungen aus Iran*, n.s. 23 (1990).

8 See W. Sundermann, 'Review of H. Humbach and P. O. Skjervø, *The Sassanian inscription of Paikuli*', *Kratylos*, 28 (1983); E. Kettenhofen, *Tirdad und die Inschrift von Paikuli: Kritik der Quellen zur Geschichte Armeniens im späten 3. und frühen 4. Jh. n.Chr.* (Wiesbaden, 1995).

9 For these inscriptions see D. N. MacKenzie, 'Kerdīr's inscription: Synoptic text in transliteration, transcription and commentary', in G. Herrmann and D. N. MacKenzie (eds.), *The triumph of Shapur I (together with an account of the representation of Kerdīr)*, *Iranische Denkmäler*, Lief. 13, Reihe II. Iranische Felsreliefs I: *The Sasanian rock reliefs at Naqsh i Rostam*, *Naqsh i Rostam 6* (Berlin, 1989); and P. Gignoux, *Les quatre inscriptions du mage Kirdīr: Textes et concordances* (Paris, 1991).

10 See Back, *Die sassanidischen Staatsinschriften*, pp. 378–83.

official Abnun (ABD).¹¹ Kerdīr is, above all, concerned with publicly displaying his career, his actions in the field of religious policy and his religious and spiritual excellence. The inscription of Bishapur, however, is the one to which we owe the mention of a Sasanian era, which started in 205/6 CE.¹² Abnun, then again, confirms the victory of his king Shapur I over the Romans at Misikhe (244 CE). Middle Persian papyri and parchments bear witness to the Persian occupation of Egypt under Khusrau (Khusro) II, and late Sasanian *ostraca* were discovered in archaeological digs in Iran.¹³

Secondary sources¹⁴ pertaining to the period consist of, on the one hand, the contemporary, yet foreign, Greek and Latin tradition, and, on the other, the later, yet local, Syriac Christian and Manichaean tradition.¹⁵ Cassius Dio and Herodian, who, to a certain extent, depended on the former, are among the most prominent Western authors of the early Sasanian period. In the fourth century they were joined by the partial eyewitness Ammianus Marcellinus,¹⁶ as well as the

- 11 For this inscription see M. Tavoosi and R. N. Frye, 'An inscribed capital dating from the time of Shapur I', *Bulletin of the Asia Institute*, n.s. 3 (1990); P. Gignoux, 'D'Abnun à Mahan: Étude de deux inscriptions sassanides', *Studia Iranica*, 20 (1991); V. A. Livshits and A. B. Nikitin, 'Some notes on the inscription from Nasrabad', *Bulletin of the Asia Institute*, 5 (1991); P. O. Skjærvø, 'L'inscription d'Abnun et l'imperfait moyen perse', *Studia Iranica*, 21 (1992); D. N. MacKenzie, 'The fire altar of Happy *Frayoshi', *Bulletin of the Asia Institute*, 7 (1993); W. Sundermann, 'The date of the Barm e Delak inscription', *Bulletin of the Asia Institute*, n.s. 7 (1993).
- 12 R. Altheim Stiehl, 'Das früheste Datum der sasanidischen Geschichte, vermittelt durch die Zeitangabe der mittelpersisch parthischen Inschrift aus Bīšapur', *Archäologische Mitteilungen aus Iran*, n.s. 11 (1978); but see also W. Sundermann, 'Shapur's coronation: The evidence of the Cologne Mani Codex reconsidered and compared with other texts', *Bulletin of the Asia Institute*, n.s. 4 (1990); and L. Richter Bernburg, 'Mani's Dodecads and Sasanian chronology', *Zeitschrift für Papyrologie und Epigraphik*, 95 (1993).
- 13 D. Weber, *Ostraca, Papyri und Pergamente. Textband*, CII III, 4 5 (London, 1992); D. Weber, *Berliner Papyri, Pergamente und Leinenfragmente in mittelpersischer Sprache*, CII III, 4 5 (London, 2003); see also P. Gignoux, 'Une nouvelle collection de documents en pehlevi cursif du début du septième siècle de notre ère', *Comptes Rendus de l'Académie des Inscriptions et Belles Lettres* (1991).
- 14 It is to P. Gignoux, 'Pour une nouvelle histoire de l'Iran sasanide', in W. Skalmowski and A. van Tongerloo (eds.), *Middle Iranian studies* (Louvain, 1984) that we owe a fundamental consideration of the respective weight of the sources.
- 15 For a summary of the literary sources of Sasanian history see A. Christensen, *L'Iran sous les Sassanides*, 2nd rev. edn (Copenhagen, 1944), pp. 50–83; G. Widengren, 'Sources of Parthian and Sasanian history', in E. Yarshater (ed.), *The Cambridge history of Iran*, vol. III: *The Seleucid, Parthian and Sasanian periods* (Cambridge, 1983), pp. 1261–83, 1269–82; R. N. Frye, *The history of ancient Iran*, *Handbuch der Altertumswissenschaft* III, 7 (Munich, 1984), pp. 287–91; K. Schippmann, *Grundzüge der Geschichte des sasanidischen Reiches* (Darmstadt, 1990), pp. 3–9; Wiesehöfer, *Ancient Persia*, pp. 153–9 and 283–5.
- 16 Ammianus Marcellinus, *Rerum gestarum libri*, books 23–5. For Ammian's oeuvre seen from the perspective of Iranian studies see P. Huyse, 'Vorbemerkungen zur Auswertung iranischen Sprachgutes in den Res Gestae des Ammianus Marcellinus', introduction to W. Skalmowski and A. Van Tongerloo (eds.), *Medioiranica*, *Orientalia Lovaniensia Analecta* 48 (Leuven, 1993); for Ammian and the Sasanians see chapters in J. W. Drijvers

biographies of the emperors found in the *Historia Augusta*, which, however, are to be used only with great caution. Yet what all these authors have in common is, above all else, an interest in the military conflicts between the Romans and Sasanians. Notwithstanding this and their bias against the enemy, many details in their accounts are of importance in the reconstruction of the Sasanian empire's internal affairs. Among the Byzantine witnesses of Byzantine Sasanian contacts we find Procopius, who reported on the wars against the Persians in the sixth century in his capacity as confidant of the Byzantine general Belisar.¹⁷ Procopius' historic 'successor' Agathias, who claims to have had access to the Sasanian state archives,¹⁸ as well as Zosimus (late fifth/early sixth century), John Malalas (d. c. 570), Menander Protector (sixth/seventh century)¹⁹ and Theophylactus Simocatta (d. c. 630)²⁰ were all such witnesses of Byzantine Sasanian relations.

Within the Christian Syriac tradition,²¹ numerous martyrs' accounts²² illuminate the early history of Christianity in the Sasanian empire, its view of itself and the religious policies of the empire's rulers, despite all hagiographic distortions. We also owe valuable information to chronicles (the Chronicle of Arbela,²³ the

and D. Hunt (eds.), *The late Roman world and its historian: Interpreting Ammianus Marcellinus* (London and New York, 1999) (esp. H. Teitler, 'Visa vel lecta? Ammianus on Persia and the Persians') and J. W. Drijvers, 'Ammianus Marcellinus' image of Sasanian society', in J. Wieshöfer and P. Huyse (eds.), *Ēran ud Aneran: Studien zu den Beziehungen zwischen dem Sasanidenreich und der Mittelmeerwelt*, OrOCC 13 (Stuttgart, 2006).

17 For Procopius see mainly A. Cameron, *Procopius and the sixth century* (London and New York, 1985); A. Kaldellis, *Procopius of Caesarea: Tyranny, history, and philosophy at the end of Antiquity* (Philadelphia, 2004); and esp. H. Börm, *Prokop und die Perser*, OrOCC 16 (Stuttgart, 2007).

18 Agathias, *Historiae*, 2.27.2,4, 30. 2,3,5. See A. Cameron, 'Agathias on the Sassanians', *Dumbarton Oaks Papers*, 23 4 (1969 70).

19 R. C. Blockley, 'Subsidies and diplomacy: Rome and Persia in Late Antiquity', *Phoenix*, 39 (1985).

20 M. Whitby, *The emperor Maurice and his historian: Theophylact Simocatta on Persian and Balkan warfare* (Oxford, 1988).

21 S. Döpp and W. Geerlings (eds.), *Lexikon der antiken christlichen Literatur* (Freiburg, 1998); J. Alßfalg and P. Krüger (eds.), *Kleines Wörterbuch des christlichen Orients* (Wiesbaden, 1975); A. Baumstark, *Geschichte der syrischen Literatur mit Ausschluß der christlich palästinensischen Texte* (Bonn, 1922; repr. 1968); and G. Graf, *Geschichte der christlichen arabischen Literatur*, 4 vols. (Vatican, 1944 53; repr. 1964 6) are still crucial accounts of the history of Christian literature; see now also S. P. Brock, *Brief outline of Syriac literature* (Kottayam, 1997).

22 Editions: S. E. Assemani, *Acta Sanctorum Martyrum Orientalium et Occidentalium in duas partes distributa* (Rome, 1748; repr. 1970); P. Bedjan, *Acta Martyrum et Sanctorum*, 7 vols. (Paris and Leipzig, 1890 7; repr. 1968); for translated extracts see G. Hoffmann, *Auszüge aus syrischen Akten persischer Märtyrer* (Leipzig, 1880); O. Braun, *Ausgewählte Akten persischer Märtyrer* (Kempten and Munich, 1915); S. P. Brock and S. Harvey (eds.), *Holy women of the Syrian Orient* (Berkeley, 1987).

23 P. Kawerau, *Die Chronik von Arbela*, CSCO 467 8, 2 vols., (Louvain, 1985); for the question of the authenticity of this chronicle see the dispute between J. M. Fiey, 'Review of P. Kawerau, *Die Chronik von Arbela*', *Revue d'Histoire Ecclésiastique*, 81 (1986) and

Chronicle of Se'ert (Arabic), Joshua the Stylite (sixth century)²⁴ and Church histories, which sometimes show a remarkably exact chronology and offer information of great value.

As far as Manichaean material is concerned, there are original Coptic sources of Manichaeans from Central Egypt, wide ranging discoveries of texts in Middle Persian, Old Turkic and Chinese from the Silk Route, and, finally, also findings in papyrus and parchment collections (the 'Cologne Mani Codex' (CMC)). All these have made it possible for the life and teachings of Mani, the early history of Manichaean missionary activity and the relationship between the Manichaeans and the Sasanian authorities to be appreciated from a point of view other than that of the enemies of Manichaeism.²⁵

As far as Armenian historians are concerned, they are to be used only with the utmost caution, due to their predominantly antagonistic tendency towards the Sasanians and the specific problems related to their transmission.²⁶ Nevertheless, there is Lazar of Pharb's contemporary account of the 482–4 uprising, with detailed information about Sasanian commanders and disputation at court; the encomiastic biography of Smbat Bagratuni quarried by Pseudo Sebeos, which includes an account of a grand reception at court; above all, the *History to 682*, incorporated into Movses Daskhurants'i's *History of the Caucasian Albanians*, the principal source for the 637 Persian counter attack, noted below.

In late Sasanian and even Islamic times there appeared texts in Middle Persian, which were either commentaries on the Avesta, or which constituted

P. Kawerau, 'Correspondance', *Revue d'Histoire Ecclésiastique*, 82 (1987); for the problem of the authenticity of the data see E. Kettenhofen, 'Die Chronik von Arbela in der Sicht der Althistorie', in L. Criscuolo, G. Geraci and C. Salvaterra (eds.), *Simbolos: Scritti di storia antica* (Bologna, 1995); and J. Wiesehöfer, 'Zeugnisse zur Geschichte und Kultur der Persis unter den Parthern', in J. Wiesehöfer (ed.), *Das Partherreich und seine Zeugnisse The Arsacid Empire: Sources and documentation. Beiträge des Internationalen Colloquiums, Eutin* (27. 29. Juni 1996), *Historia Einzelschriften* 122 (Stuttgart, 1998).

24 A. Luther, *Die syrische Chronik des Josua Stylites*, Untersuchungen zur antiken Literatur und Geschichte 49 (Berlin and New York, 1997); F. R. Trombley and J. W. Watt (eds.), *The chronicle of Pseudo Joshua the Stylite*, Translated Texts for Historians 32 (Liverpool, 2000).

25 Editions of Manichaean works and secondary literature until 1996 are gathered in G. B. Mikkelsen, *Bibliographia Manichaica: A comprehensive bibliography of Manichaeism through 1996*, *Corpus Fontium Manichaeorum, Subsidia* 1 (Turnhout, 1997). See now also the bibliography in I. Gardner and S. N. C. Lieu (eds.), *Manichaean texts from the Roman Empire* (Cambridge, 2004).

26 See the summaries in Christensen, *L'Iran*, pp. 77–9; Widengren, 'Sources of Parthian and Sasanian history', pp. 1274–6; for caveats see P. Gignoux, 'Pour une évaluation de la contribution des sources arméniennes à l'histoire sassanide', *Acta Antiqua Academiae Scientiarum Hungaricae*, 31 (1985: 8); E. Kettenhofen, 'Review of E. Winter, *Die sasanidisch römischen Friedensverträge des 3. Jahrhunderts n. Chr.*', *Bibliotheca Orientalis*, 47 (1990), pp. 172–3; Kettenhofen, *Tirdad*.

a sort of epic or poetic literature related to a court setting.²⁷ A sort of 'Iranian national history' was created under Khusrau I and his successors in the form of the *X^waday namag* (the 'Book of Lords'), which was a semi official history of Iran from the first king of the world, Gayomard, until the reign of Khusrau II.²⁸ After recalling Iran's glorious history in the face of a somewhat less magnificent present, this work, which has only survived in extracts, translations and later adaptations, recounts the reigns of fifty kings and queens. The text probably also had the aim of appeasing the needs of the ruled, and is characterised by certain mythical themes. An interesting feature of the Book of lords is that 'heroic' times generally alternate with periods in which soothsayers, 'holy men' or 'prophets' raise questions of ethics and morality, and in which the theme of war recedes into the background. In terms of genre, this 'national history' thus represents a mixture of heroic themes, proverbs of kings and sages, priestly disputes, philosophical meditations, moral precepts, and royal testaments and speeches. Time and again, these examine questions of justice, religiosity and the virtuous life. However, the Book of Lords was not just a semi official book of 'history', but also a tool of literary entertainment and social education. It was meant to preach moral and socio political ideals as well as the virtues of the ruled – ideals upon which Sasanian kings believed their rule to be founded and which they regarded as the means for safeguarding their continuing position of power. The biographies of kings, heroes and sages served as the background on the basis of which such ideals could be illustrated. The distinction between myth, legend and historical fact was therefore of secondary importance.²⁹

Although much more written material has survived from the Sasanian era than from Parthian times, there has nevertheless been a serious loss of sources. Many texts were lost during the conquest of Iran by the Muslims, or through later invasions. Others were censored by religious zealots, or, in later times, were not deemed worthy or sufficiently interesting to be preserved. Translations and adaptations, as well as bibliographical collections and notes in Arabic and New Persian, only feebly reflect the breadth of Sasanian literature. But, at any rate, it is known that, alongside the religious writings,

27 J. C. Tavadia, *Die mittelpersische Sprache und Literatur der Zarathustrier* (Leipzig, 1956); M. Boyce, 'Middle Persian literature', in *Iranistik II, Literatur I*, Handbuch der Orientalistik I.IV.2.1 (Leiden, 1968); J. de Menasce, 'Zoroastrian Pahlavi writings', in Yarshater (ed.), *The Cambridge history of Iran*, vol. III; C. G. Cereti, *La letteratura pahlavi* (Milan, 2001).

28 A. S. Shahbazi, 'On the *X^waday namag*', *Acta Iranica*, 30 (1990).

29 E. Yarshater, 'Iranian national history', in Yarshater (ed.), *The Cambridge history of Iran*, vol. III, part 1; for the role of the West ('Rum') in this tradition see below.

Middle Persian literature covered historical, geographical, didactic and astronomical works, and books on the natural as well as the social and cultural characteristics of countries. These included travel accounts, volumes on good manners and etiquette, legal manuals, historical novels, love stories and literature of popular entertainment.³⁰ However, much of the extant material is not contemporary to late Sasanian affairs and can only be used historically with great care.

Persian Arabic historiography³¹ (i.e. al Ṭabarī and others³²) owes its knowledge of Sasanian Iran to such late Middle Persian traditions. However, the extent of this knowledge needs to be examined in each specific case. It must also be investigated whether, in the process of being edited, facts might have been transformed organically, or adjusted to the exigencies of an Islamic view of 'salvation history'.³³

The Sasanian inscriptions discussed above are at times juxtaposed, both in space and content, with artistically remarkable bas reliefs, also mainly dating from the third and fourth centuries.³⁴ These usually portray the investiture of kings by gods. There also exist, however, bas reliefs portraying scenes of victory, and some that depict the king on his throne surrounded by his entourage. Among the most impressive of the bas reliefs portraying scenes of victory is the depiction of the battle of Hurmuzjan between Ardashīr I and Artabanus V in

30 Boyce, 'Middle Persian literature'.

31 See C. Brockelmann, *Geschichte der arabischen Literatur*, 2nd edn, 2 vols. (Leiden, 1943 9; suppl. 1 3, Leiden, 1937 42); F. Sezgin, *Geschichte des arabischen Schrifttums*, vol. I (Leiden, 1967); H. Busse, 'Arabische Historiographie und Geographie', in H. Gätje (ed.), *Grundriß der arabischen Philologie*, vol. II (Wiesbaden, 1987); J. C. Meisami and P. Starkey (eds.), *Encyclopedia of Arabic literature*, 2 vols. (London, 1998).

32 For al Ṭabarī's outstanding role (Abu Ja'far Muḥammad ibn Jarīr al Ṭabarī, *Ta'riḫ al rusul wa'l muluk*, ed. M. J. Goeje et al., 15 vols. in 3 series (Leiden, 1879 1901); translation of the Sasanian part: T. Nöldeke, *Geschichte der Perser und Araber zur Zeit der Sasaniden* (Leiden, 1878); C. E. Bosworth (ed.) *The history of al Ṭabarī*, vol. V: *The Sasanids, the Byzantines, the Lakmids, and Yemen* (Albany, 1999)), see Bosworth (ed.), *The history of al Ṭabarī*, in particular vols. XV XX; also *passim* for other works in Arabic, as well as Widengren, 'Sources of Parthian and Sasanian history', pp. 1280 1; Z. Rubin, 'Ibn al Muqaffa' and the account of Sasanian history in the Arabic Codex Sprenger 30', *JSAI*, 30 (2005).

33 For the historical and intellectual background of Arab Persian historiography of the Sasanian empire see M. Springberg Hinsén, *Die Zeit vor dem Islam in arabischen Universalgeschichten des 9. bis 12. Jahrhunderts* (Würzburg und Altenberge, 1989). For the reliability of the material concerning late Sasanian affairs see Z. Rubin, 'Nobility, monarchy and legitimization under the later Sasanians', in J. Haldon and L. I. Conrad (eds.), *The Byzantine and early Islamic Near East*, vol. VI: *Elites old and new in the Byzantine and early Islamic Near East* (Princeton, 2004); Rubin, 'Ibn al Muqaffa'.

34 See the summary given in Cereti, 'Primary sources', pp. 33 7; and M. Abka'i Khavari, *Das Bild des Königs in der Sasanidenzeit: Schriftliche Überlieferungen im Vergleich mit Antiquaria, Texte und Studien zur Orientalistik* 13 (Hildesheim, 2000), pp. 31 7.

three scenes,³⁵ as well as the five 'victory' reliefs of Shapur I (which depict the Roman emperors Gordian III, Philip the Arab and Valerian as 'victims').³⁶ The most impressive investiture reliefs are those of Ardashīr I from Naqsh-e Rostam and Naqsh-e Rostam.³⁷ The 'priest' Kerdīr, too, could not resist from drawing attention to himself by having his bust sculpted.³⁸ After a long interval devoid of depictions in stone, and in which silver vessels took on the role of bas reliefs with regard to the art of royal representation,³⁹ it was Khusrau II who again had himself immortalised in stone. The reliefs of the great *iwan* of Tāq-e Bostan in Media (close to Kirmanshah) show him as the divinely chosen ruler and as an accomplished horseman, as well as in the midst of a wild boar and deer hunt.⁴⁰

Even more remarkable than the colossal statues of Shapur I and Khusrau II, which represent rare examples of the Sasanian art of sculpture,⁴¹ are the layouts of cities, palaces, religious buildings, bridges and dams of the time.⁴² Worth mentioning among the cities are the round construction of Ardashīr Khwarrah (Gur) on the plain of Firuzabad, from the time of the founder of the dynasty,⁴³ and the main residence of his son Shapur, Weh Shabuh (Bishapur).⁴⁴ Both of these are situated in Fars, alongside Jundishapur (Mid. Pers. Weh Andiyok Shabuh; Syr. Beth Lapat) close to Susa, which was not only home to a 'university', but also a centre of Persian silk manufacturing, and the main base of Khuzistan's Christians.⁴⁵ As far as the kings' palaces are concerned,⁴⁶ it is the

35 H. von Gall, *Das Reiterkampfbild in der iranischen und iranisch beeinflussten Kunst parthischer und sasanidischer Zeit*, Teheraner Forschungen 6 (Berlin, 1990), pp. 20–30.

36 M. Meyer, 'Die Felsbilder Shapurs I.', *Jahrbuch des Deutschen Archäologischen Instituts*, 105 (1990).

37 H. Luschey, 'Ardašīr I., II: Rock reliefs', *Elr*, vol. II, pp. 329–34.

38 W. Hinz, *Altiranische Funde und Forschungen* (Berlin, 1969), pp. 189–228.

39 P. O. Harper, *Silver vessels of the Sasanian period*, vol. I: *Royal imagery* (New York, 1981); P. O. Harper, 'Sasanian silver', in J. Boardman, I. E. S. Edwards, E. Sollberger and N. G. L. Hammond (eds.), *The Cambridge ancient history*, vol. III, part 2: *The Assyrian and Babylonian empires and other states of the Near East, from the eighth to the sixth centuries BC* (Cambridge, 1983); P. O. Harper, 'La vaisselle en métal', in *Splendeur des Sassanides: L'empire perse entre Rome et la Chine* (224–642): 12 février au 25 avril 1993 (Brussels, 1993).

40 Cereti, 'Primary sources', p. 35, fn. 104 (with older literature); for the dating of the bas reliefs, see now also von Gall, *Das Reiterkampfbild*, pp. 38–47.

41 For Sasanian sculpture, see Abka'i Khavari, *Das Bild des Königs*, pp. 37–8.

42 For a summary see D. Huff, 'Sasanian cities', in M. Y. Kiani (ed.), *A general study of urbanization and urban planning in Iran* (Tehran, 1986); D. Huff, 'Architecture, III', *Elr*, vol. II, pp. 329–34; D. Huff, 'Architecture sassanide', in *Splendeur des Sassanides*; and Cereti, 'Primary sources', pp. 28–33.

43 For Sasanian city designs see Huff, 'Sasanian cities'; for Gur see L. Trümpelmann, *Zwischen Persepolis und Firuzabad* (Mainz, 1991), pp. 61–71.

44 R. Ghirshman, *Bichapur I II* (Paris, 1956–71).

45 D. T. Potts, 'Gundeshapur and the Gondeios', *Iranica Antiqua*, 24 (1989).

46 L. Bier, 'Sasanian palaces in perspective', *Archaeology*, 35, 1 (1982); W. Kleiss, *Die Entwicklung von Palästen und palastartigen Wohnbauten in Iran*, Sitzungsberichte der Österreichischen Akademie der Wissenschaften, Philosophisch-historische Klasse 524 (Vienna, 1989).

two early residences of Ardashīr I,⁴⁷ the palace of Shapur I in Bīshapur, with its mosaics modelled on Roman patterns,⁴⁸ and the late Sasanian residence of Ctesiphon on the river Tigris – or rather, the one remaining monumental arch of its *iwān*⁴⁹ – that have left the greatest impression. Roman prisoners of war built many of the roughly twenty Sasanian bridges and dams that are still to be seen today.⁵⁰ The most important sanctuary of late Sasanian times, the Takht i Sulaiman in Azerbaijan, was unearthed by German archaeologists.⁵¹

The products of Sasanian silk and textile manufacturing⁵² also deserve mention, as well as Sasanian goldsmiths' art,⁵³ cameos,⁵⁴ glass manufacturing⁵⁵ and examples of the famous Sasanian stucco work.⁵⁶ Historically more important, however, are the seals and *bullae*, which introduce Sasanian officials by their names, titles and functions,⁵⁷ as well as coins, the head of which generally depicted the ruler with his respective crown and legends, while the

47 G. Gerster and D. Huff, 'Die Paläste des Königs Ardaschir', *Bild der Wissenschaft*, 11 (1977).

48 Ghirshman, *Bichapour*.

49 E. J. Keall, 'Ayvan (or Taq) e Kesra', *Elr*, vol. III, pp. 155–9.

50 L. Bier, 'Notes on Mihr Narseh's bridge near Firuzabad', *Archäologische Mitteilungen aus Iran*, n.s. 19 (1986).

51 R. Naumann, *Die Ruinen von Tacht e Suleiman und Zendan e Suleiman* (Berlin, 1977); D. Huff, 'Recherches archéologiques à Takht i Suleiman', *Comptes Rendus de l'Académie des Inscriptions et Belles Lettres* (1978); D. Huff, 'Der Takht e Suleiman. Sassanidisches Feuerheiligtum und mongolischer Palast', in T. Stöllner et al. (eds.), *Persiens antike Pracht*, vol. II (Bochum, 2004).

52 E. H. Peck 'Clothing, IV', *Elr*, vol. V, pp. 739–52; A. Jeroussalimskaia, 'Soieries sassanides', in *Histoire culturelle*, in *Splendeur des Sassanides*; D. de Jonghe, 'Soieries sassanides', in *Splendeur des Sassanides*.

53 Harper, *Silver vessels*; Harper, 'Sasanian silver'; Harper, 'La vaisselle'; P. O. Harper, 'Sasanian silver vessels: Recent developments', in V. S. Curtis, R. Hillenbrand and J. M. Rogers (eds.), *The art and archaeology of ancient Persia: New light on the Parthian and Sasanian Empires* (London and New York, 1998). For Sasanian jewellery see B. Musche, *Vorderasiatischer Schmuck zur Zeit der Arsakiden und Sasaniden*, *Handbuch der Orientalistik VII.1.2B.5* (Leiden, 1988).

54 Von Gall, *Das Reiterkampfbild*, pp. 56–9.

55 S. Fukai, *Persian glass* (New York, 1977); D. Whitehouse, 'La verrerie', in *Splendeur des Sassanides*.

56 J. Kröger, *Sasanidischer Stuckdekor* (Mainz, 1982).

57 For a summary of Sasanian glyptography see Cereti, 'Primary sources', pp. 44–50; to this should be added *Catalogue des sceaux, camées et bulles sassanides de la Bibliothèque Nationale et du Musée du Louvre*, 2 vols., vol. I: R. Gyselen, *Collection générale* (Paris, 1993); R. Gyselen, *Sceaux magiques en Iran sassanide*, *Cahiers de Studia Iranica* 17 (Paris, 1995); R. Gyselen, *L'art sigillaire dans les collections de Leyde* (Leiden, 1997); R. Gyselen (ed.), *Sceaux d'Orient et leur emploi*, *Res Orientales* 10 (Bures sur Yvette, 1997); R. Gyselen, 'Sasanian glyptic: An example of cultural interaction between the Hellenistic world and the Iranian world', in M. Alram and D. Klimburg Salter (eds.), *Coins, art and chronology: Essays on the pre Islamic history of the Indo Iranian borderlands*, *Österreichische Akademie der Wissenschaften, philosophisch historische Klasse, Denkschriften* 280 (Vienna, 1999).

tail showed a fire altar with assistant figures.⁵⁸ Since gold and copper coins were not in wide circulation, most coins were made of thin silver. As in the case of the Parthians, the basic unit was the drachma, with a weight of 4 grams. It began to be minted *en masse* under Shapur I, probably in order to attract mercenaries from Central Asia. Although coin factories and mint offices are mentioned, their number and kind are difficult to reconstruct. From the time of Kawad I, annual figures are given canonically. The so called 'Kushano Sasanian coins' pose yet another challenge. That is to say, the dating of coins issued by Sasanian governors in the provinces of the former Kushan empire, has produced extremely contradictory results.⁵⁹

Sasanian history from Ardashīr I to Yazdgerd III⁶⁰

As in the case of the Parthians, we know very little about the Sasanians' aims and activities in the field of foreign policy, most of which concerns their western

- 58 For a summary, see H. D. Malek, 'A survey of research on Sasanian numismatics', *Numismatic Chronicle*, 153 (1993); and Cereti, 'Primary sources', pp. 38–44. A *Sylloge Nummorum Sasanidarum* is about to be created (R. Gyselen *et al.*, 'Sylloge Nummorum Sasanidarum: Die Münzen der Sasaniden aus der Bibliothèque Nationale de France, dem Münzkabinett der Staatlichen Museen zu Berlin und dem Münzkabinett am Kunsthistorischen Museum in Wien (in Zusammenarbeit mit M. Alram u.a.)', *Anzeiger der philosophisch historischen Klasse der Österreichischen Akademie der Wissenschaften*, 134 (1999); M. Alram and R. Gyselen, *Sylloge Nummorum Sasanidarum Paris* Berlin Wien, vol. I: *Ardashir I. Shapur I.* (Vienna, 2003); N. Schindel, *Sylloge Nummorum Sasanidarum Paris* Berlin Wien, vol. III, pts 1–2: *Shapur II. Kawad I./2. Regierung* (Vienna, 2004)).
- 59 J. Cribb, 'Numismatic evidence for Kushano Sasanian chronology', *Studia Iranica*, 19 (1990); R. Göbl, 'The Rabatak inscription and the date of Kanishka', in Alram and Klimburg Salter (eds.), *Coins, art and chronology*; see now also Cereti, 'Primary sources', pp. 64–8.
- 60 For a summary, see R. N. Frye, 'The political history of Iran under the Sasanians', in Yarshater (ed.), *The Cambridge history of Iran*, vol. III; and Frye, *History*, pp. 287–339; see also A. D. Lee, *Information and frontiers: Roman foreign relations in Late Antiquity* (Cambridge, 1993). Single epochs are treated by F. G. B. Millar, *The Roman Near East 31 BC–AD 337*, 2nd edn (Cambridge, MA, and London, 1994); R. C. Blockley, *East Roman foreign policy: Formation and conduct from Diocletian to Anastasius* (Leeds, 1992); and N. G. Garsoian, 'Byzantium and the Sasanians', in Yarshater (ed.), *The Cambridge history of Iran*, vol. III. Information concerning Sasanian foreign policy can also be found in I. Shahid, *Byzantium and the Arabs in the fourth century* (Washington, DC, 1984); I. Shahid, *Byzantium and the Arabs in the fifth century* (Washington, DC, 1989) and I. Shahid, *Byzantium and the Arabs in the sixth century*, vol. I, parts 1–2 (Washington, DC, 1995). J. Howard Johnston, 'The two great powers in Late Antiquity: A comparison', in A. Cameron (ed.), *The Byzantine and early Islamic Near East*, vol. III: *States, resources and armies*, *Studies in Late Antiquity and Early Islam* 1 (Princeton, 1995), provides an overview of the manifold relations between Rome/Byzantium and Persia. W. Felix, *Antike literarische Quellen zur Außenpolitik des Sasanidenstaates*, vol. I: 224–309, *Österreichische Akademie der Wissenschaften, philosophisch historische Klasse, Sitzungsberichte* 456 *Veröffentlichungen der Iranischen Kommission* 18 (Vienna, 1985), presents the classical (Greek and Roman) literary sources concerning

border. All lands of the former Parthian empire, except for Armenia, came under Sasanian control during the reign of the founder of the dynasty, Ardashīr (224–239/40?). It is under him that an offensive policy towards Rome is already discernible.⁶¹ His son Shapur I (240–271/2) was more successful in this than his father, however: his campaigns affected not only Armenia, but even shook the foundations of the Roman empire. His armies advanced briefly as far as Antioch and Cappadocia, and Valerian became the first Roman emperor to be captured by the Sasanian enemy. Despite all later setbacks (e.g. against Odenathus of Palmyra), and if we believe his own account of his reign, Shapur's empire stretched from Mesopotamia in the west to Peshawar in the east.⁶² Succession disputes, and Diocletian's aggressive eastern policy at the end of the century, caused the Sasanians to incur the loss of regions to the east of the Tigris and Armenia for several decades.⁶³ Only Shapur II could erase the memory of the 'Peace of Disgrace' concluded at Nisibis (298 CE), when he managed, after long battles, not only to drive Julian the Apostate away from Ctesiphon, but also

the foreign policy of the Sasanians (until 309 CE). A commented list of sources in translation with reference to Roman–Sasanian relations is given by M. H. Dodgeon and S. N. C. Lieu (eds.), *The Roman eastern frontier and the Persian wars*, part 1: AD 226–363: *A documentary history* (London and New York, 1991); G. Greatrex and S. N. C. Lieu, *The Roman eastern frontier and the Persian wars*, part 2: AD 363–630 (London and New York, 2002); E. Winter and B. Dignas, *Rom und das Perserreich: Zwei Weltmächte zwischen Konfrontation und Koexistenz* (Berlin, 2001).

61 J. Wiesehöfer, 'Ardašīr I, I: History', *Elr*, vol. II, pp. 371–6; E. Winter, *Die sasanidisch-römischen Friedensverträge des 3. Jahrhunderts n. Chr.: Ein Beitrag zum Verständnis der außenpolitischen Beziehungen zwischen den beiden Großmächten*, Europäische Hochschulschriften III, 350 (Frankfurt etc., 1988), pp. 45ff.; sources in Dodgeon and Lieu (eds.), *The Roman eastern frontier*, pp. 9–33; Winter and Dignas, *Rom und das Perserreich*, *passim*.

62 For Shapur's wars, see esp. E. Kettenhofen, *Die römisch-persischen Kriege des 3. Jahrhunderts n. Chr. nach der Inschrift Šāhpūhr's I. an der Ka'be ye Zartošt*, Beihefte zum Tübinger Atlas des Vorderen Orients, series B, no. 35 (Wiesbaden, 1982), and Huyse, *Die dreisprachige Inschrift*. See also Winter, *Die sasanidisch-römischen Friedensverträge*, pp. 80ff. (for this see Kettenhofen, 'Review of E. Winter, *Die sasanidisch-römischen Friedensverträge*'); D. S. Potter, *Prophecy and history in the crisis of the Roman Empire: A historical commentary on the Thirteenth Sibylline Oracle* (Oxford, 1990), pp. 189ff.; K. Strobel, *Das Imperium Romanum im 3. Jahrhundert*, *Historia Einzelschriften* 75 (Stuttgart, 1993), pp. 220ff.; Millar, *The Roman Near East*, pp. 151ff. Sources can be found in Dodgeon and Lieu (eds.), *The Roman eastern frontier*, pp. 34ff., and Winter and Dignas, *Rom und das Perserreich*, *passim*.

63 Winter, *Die sasanidisch-römischen Friedensverträge*, pp. 152ff.; E. Winter, 'On the regulation of the eastern frontier of the Roman Empire in 298', in D. H. French and C. S. Lightfoot (eds.), *The eastern frontier of the Roman Empire: Proceedings of a colloquium held at Ankara in September 1988*, BAR International Series 553, part 1 (Oxford, 1989); Blockley, *East Roman foreign policy*, pp. 5ff.; Kettenhofen, *Tirdad*, *passim*; J. Wiesehöfer, 'Narseh, Diokletian, Manichäer und Christen', in M. Arafat, J. Tubach and G. S. Vashalomidze (eds.), *Inkulturation des Christentums im Sasanidenreich* (Wiesbaden, 2007); for sources regarding Roman–Sasanian relations until 298, see Dodgeon and Lieu (eds.), *The Roman eastern frontier*, pp. 111ff.; Winter and Dignas, *Rom und das Perserreich*, *passim*.

succeeded in wresting a great part of the lost territory from Julian's successor Jovian, both by military and diplomatic means (363 CE).⁶⁴ In the course and aftermath of these wars severe persecutions of Christians took place in the Sasanian empire. From a Christological point of view these Christians were *not yet* divorced from their fellow believers in the west, and after the 'Constantine Revolution' they thus became Rome's protégés and were regarded as partisans for the Roman cause by the Sasanian authorities.⁶⁵ The eastern part of Armenia also became Sasanian again in the year 387.⁶⁶

During the subsequent century, however, the Hephthalites, or 'White Huns', were to become an even greater problem than the Romans, with whom a mutually satisfactory agreement was reached around 400.⁶⁷ The Hephthalites were tribes that had pushed forth from Dsugaria into Central Asia and now ruled, among other territories, Sogdia, Bactria, the western part of the Tarim plain and north western India.⁶⁸ They utterly defeated King Firuz (Peroz) twice (465 and 484) and forced him to pay tribute to them, which, combined with famines, led the Sasanian empire to the brink of internal collapse. It was at this time that a man by the name of Mazdak proclaimed a religious and ethical programme which called for the just distribution of ownership. His teaching, thanks to its 'Zoroastrian' terminology, its attractive dogmatics and theology and the charity practised within the Mazdakite communities in a time of widespread poverty and hardship, won over many people in Iran and Mesopotamia, not only those without means,

64 R. C. Blockley, 'The Romano Persian peace treaties of AD 299 and 363', *Florilegium*, 6 (1984); Blockley, *East Roman foreign policy*, pp. 24ff.; for sources concerning the period up until 363, see Dodgeon and Lieu (eds.), *The Roman eastern frontier*, pp. 143ff.; Winter and Dignas, *Rom und das Perserreich*, *passim*.

65 W. Schwaigert, *Das Christentum in Huzistan im Rahmen der frühen Kirchengeschichte Persiens* (Marburg, 1989), pp. 103 75; J. Wiesehöfer, 'Geteilte Loyalitäten: Religiöse Minderheiten des 3. und 4. Jahrhunderts n.Chr. im Spannungsfeld zwischen Rom und dem sasanidischen Iran', *Klio*, 75 (1993).

66 R. C. Blockley, 'The division of Armenia between the Romans and the Persians', *Historia*, 36 (1987).

67 Blockley, *East Roman foreign policy*, pp. 52ff.; for Byzantium and the Sasanians in the fifth century, see Z. Rubin, 'Diplomacy and war in the relations between Byzantium and the Sassanids in the fifth century AD', in P. W. Freeman and D. L. Kennedy (eds.), *The defence of the Roman and Byzantine east: Proceedings of a colloquium held at the University of Sheffield in April 1986*, BAR International Series 297, part 2 (Oxford, 1986); Blockley, *East Roman foreign policy*, pp. 52ff.; G. Greatrex, *Rome and Persia at war, 502 532*, ARCA Classical and Medieval Texts, Papers and Monographs 37 (Leeds, 1998); Greatrex and Lieu, *The Roman eastern frontier*, pp. 31ff.

68 E. V. Zeimal, 'The Kidarite kingdom in Central Asia', in B. A. Litvinsky (ed.), *History of civilizations of Central Asia*, vol. III: *The crossroads of civilization AD 250 to 750* (Paris, 1996); B. A. Litvinsky, 'The Hephthalite empire', in Litvinsky (ed.), *History of civilizations of Central Asia*, vol. III; A. D. H. Bivar, 'Hephthalites', *Elr*, vol. XII, pp. 198 201.

but also members of the aristocratic elite. For a long time, the reign of King Kawad (488–96, 498–531) was shaped by the conflict between the new king and his pro Hephthalite and pro Mazdakite followers and a pro Roman and anti Mazdakite party. It was probably only Kawad's wish to establish his son Khusrau as successor to the throne in the 520s that broke the bonds between the king and the Mazdakites and led to violent action by the Mazdakites against the landowning aristocracy, to which many of the empire's non urban population were liable for compulsory service and duties. Soon, however, Kawad and Khusrau would brutally suppress the uprising.⁶⁹ Both took advantage of the weakening of the aristocracy to implement fundamental social, economic and military reforms. Land ownership was registered, and a fixed land tax, as opposed to a changing income tax, was introduced. After a census had been taken, a new poll tax was also established, according to different levels of wealth. In addition, the empire was divided into four military districts,⁷⁰ and special units took on policing and border control duties. The creation of a new court elite and administration, which would no longer owe its privileges to reputation and descent, but to royal favour alone, was also in the interest of the kings, as was the backing of the lower, landowning aristocracy.⁷¹

The establishment of internal peace and stability allowed Khusrau to become active again externally.⁷² In 540 he broke the 'Eternal Peace' that had been concluded with the Byzantine emperor Justinian.⁷³ The payment of

69 For this period, see Bosworth's historical commentary of al Ṭabarī (Bosworth (ed.), *The history of al Ṭabarī*, pp. 126–39, 146–62, including a bibliography). For the Mazdakites see W. Sundermann, 'Mazdak und die mazdakitischen Volksaufstände', *Altertum*, 23 (1977); M. Guidi and M. Morony, 'Mazdak', *ELZ*, vol. VI, pp. 949–52; Z. Rubin, 'The reforms of Khusro Anushirwan', in Cameron (ed.), *The Byzantine and early Islamic Near East*, vol. III; G. Gnoli, 'Nuovi Studi sul Mazdakismo', in G. Gnoli and A. Panaino (eds.), *La Persia e Bisanzio*, Atti dei Convegni Lincei 201 (Rome, 2004); and J. Wiesehöfer, 'Chusro I. und das Sasanidenreich: Der König der Könige "mit der unsterblichen Seele"', in M. Meier (ed.), *Sie schufen Europa: Historische Portraits von Konstantin bis Karl dem Großen* (Munich, 2007).

70 See R. Gyselen, *The four generals of the Sasanian empire: Some sigillographic evidence* (Rome, 2001).

71 For the reforms of Khusrau see the different opinions of F. Altheim and R. Stiehl, *Finanzgeschichte der Spätantike* (Frankfurt, 1957), esp. pp. 31ff.; M. Grignaschi, 'La riforma tributaria di Ḥosro I e il feudalismo sassanide', in *La Persia nel medioevo* (Rome, 1971); Howard Johnston, 'The two great powers', pp. 211ff.; Rubin, 'The reforms'; and Wiesehöfer, *Ancient Persia*, pp. 190f. and 292f.

72 For Byzantine Sasanian relations under Kawad see Luther, *Die syrische Chronik*; Greatrex, *Rome and Persia at war*; Greatrex and Lieu, *The Roman eastern frontier*, pp. 62ff.

73 For the 'Eternal Peace' see Greatrex, *Rome and Persia at war*, pp. 213ff.; Greatrex and Lieu, *The Roman eastern frontier*, pp. 96–7. For Justinian's Persian wars see B. Rubin, *Das Zeitalter Justinians*, vol. I (Berlin, 1960), pp. 279–373; Greatrex and Lieu, *The Roman eastern frontier*, pp. 82ff. Cf. also Blockley, 'Subsidies and diplomacy'; G. Greatrex, 'Byzantium and the east in the sixth century', in M. Maas (ed.), *The Cambridge companion to the age of Justinian* (Cambridge, 2005).

tribute – a single payment had already been agreed upon in 532 – was raised in 562 with a new treaty. Khusrau's conquest of South Arabia, and the subsequent expulsion from there of the Aksumites (Ethiopians), who were in alliance with Byzantium, indirectly weakened Byzantium's position.⁷⁴ In the east he even managed to destroy the empire of the Hephthalites, with the help of the Western Turks, around 560.⁷⁵

Khusrau I's reign was also the cultural climax of the history of the Sasanian empire. As a ruler with manifold interests, it was under him that Iran developed into a centre for the exchange of learning between East and West.⁷⁶ However, under Khusrau's son Hormezd IV (after 579) new conflicts were already arising between king and aristocracy, and severe warfare with the Turks aggravated the situation further.⁷⁷ The tide seemed to be turning again, however, both internally and externally, when Hormezd's son Khusrau II managed to crush the rebellion of Wahram Chobīn, a pretender to the throne, with Byzantine help in 591.⁷⁸ Moreover, he was able to reach as far as Egypt⁷⁹ and the gates of Constantinople (626) in his war with Byzantium (602–28). The fragments of the True Cross were taken from Jerusalem to Ctesiphon in 614.⁸⁰ The counter attack of the Byzantine emperor Heraclius, however, forced the Sasanians to surrender the newly conquered territories.⁸¹ Khusrau II himself was brought down and killed by a revolt of the aristocracy (628). Following a period of

74 See Bosworth (ed.), *The history of al Ṭabarī*, s.v. Wahriz.

75 Litvinsky, 'The Hephthalite empire', pp. 143–4; Bosworth (ed.), *The history of al Ṭabarī*, pp. 152–3, 160.

76 Wiesehöfer, *Ancient Persia*, pp. 216–21, 298–300.

77 Bosworth (ed.), *The history of al Ṭabarī*, s.v. Hormuzd, Hormizd IV. Cf. Whitby, *The emperor Maurice*, *passim*; Rubin, 'Nobility'.

78 A. S. Shahbazi, 'Bahram VI Čobīn', *Elr*, vol. III, pp. 519–22; Greatrex and Lieu, *The Roman eastern frontier*, pp. 172ff.; F. Altheim, *Geschichte der Hunnen*, vols. IV–V (Berlin, 1962), pp. 234ff. and Rubin, 'Nobility' (for the Wahram romance).

79 For the Sasanian occupation of Egypt see R. Altheim Stiehl, 'The Sasanians in Egypt: Some evidence of historical interest', *Bulletin de la Société d'Archéologie Copte*, 31 (1992); R. Altheim Stiehl, 'Zur zeitlichen Bestimmung der sasanidischen Eroberung Ägyptens', in O. Brehm and S. Klie (eds.), *Mousikos Aner. Festschrift für M. Wegner zum 90. Geburtstag* (Bonn, 1992).

80 R. Schick, *The Christian communities of Palestine from Byzantine to Islamic rule: A historical and archaeological study*, *Studies in Late Antiquity and Early Islam* 2 (Princeton, 1995), pp. 33–9, 46.

81 For Heraclius' Persian war, see now also Greatrex and Lieu, *The Roman eastern frontier*, pp. 198ff.; J. Howard Johnston, 'Heraclius' Persian campaigns and the revival of the east Roman empire, 622–630', *War in History*, 6 (1999); W. E. Kaegi, *Heraclius: Emperor of Byzantium* (Cambridge, 2003), pp. 122ff. (including G. Greatrex, 'Review of W. E. Kaegi, *Heraclius*', *The Medieval Review* (2004), available at <http://quod.lib.umich.edu/cgi/t/text/textidx?c=tmr;cc=tmr;q1=2004;rgn=main;view=text;idno=baj9928.0401.028>). See also individual articles in G. Reinink and B. Stolte (eds.), *The reign of Heraclius (610–641): Crisis and confrontation* (Louvain, 2002).

anarchy with frequently changing rulers,⁸² Yazdgerd III was made king by Rustam's aristocratic party, thus becoming the Sasanians' last ruler. However, the empire had been considerably weakened by wars and the self interest of various parties, and Yazdgerd III was not able to defend it against the Muslim armies that were penetrating from the Arabian Peninsula. The Persians were indeed defeated, but only after making a real fight of it: after the first Arab attack (in 636), when they overran the irrigated alluvium and laid siege to Ctesiphon Weh Ardashīr, Yazdgerd's forces staged a counter attack (in 637) which drove the Arabs back into the desert; it has left a trace in the early Islamic sources, namely the battle of the Bridge; it then probably took several months for the Arabs to regroup, rally additional troops from all over Arabia, and finally dare to confront the Persians in open battle at al Qadisiyya in Iraq on 6 January 638.⁸³ Following the defeats at al Qadisiyya and at Nihawand in Media (642), Yazdgerd retired to eastern Iran, where he was assassinated at Marw (651).⁸⁴ The Sasanian empire became part of the caliphate.

When attempting to assess the reasons for the fall of Sasanian rule, the following should be noted.⁸⁵ First, Sasanian defences, both natural and man made, were strong: the outer line, the Euphrates fronted by forts, was much shorter than that of the Romans, who also had no convenient river to hold, except along the Jordan valley; the Euphrates line was backed by the Tigris (not forgetting the many canals to be crossed in the alluvium) and, behind the Tigris, by the Zagros. The main fighting force, the army which had conquered the Roman Near East, had not been defeated when it was withdrawn east under the terms of the agreement made between Heraclius and its commander, Shahrbaraz. Heraclius had achieved complete strategic surprise when he suddenly struck south across the Caucasus in autumn 627; the army which he defeated at Nineveh was a relatively small, scratch force sent north to bar the route to Ctesiphon. Of course, defeat in the war against the Romans must have had a devastating effect, but it was primarily political. It must have been a terrible

82 For the queens Puran and Āzarmīgdukht see A. Panaino, 'Women and kingship. Some remarks about the enthronisation of Queen Boran and her sister *Āzarmīgduxt', in Wiesehöfer and Huyse (eds.), *Ēran ud Aneran*.

83 This revised chronology is indebted to intensive discussions with J. Howard Johnston (Oxford).

84 For the Arab conquest of Iran and the end of the Sasanian empire see Bosworth (ed.), *The history of al Ṭabarī*, pp. 381–411.

85 The following points of argument are again strongly influenced by discussions with J. Howard Johnston.

shock to the whole Sasanian governing class. At one moment they could contemplate something close to world dominance, with the Roman empire liquidated and the *shahanshah*'s authority extended to the whole basin of the east Mediterranean, from Egypt to Asia Minor, beyond which lay a series of minor sub Roman, Germanic power, potentially open to Sasanian influence; the next, all of this had been suddenly snatched from them, when the age old enemy from the steppes, Turan in the modern guise of the Turks, intervened to decisive effect. The immediate crisis, involving competing bids for the throne, may have been short, but in the longer term serious damage must have been caused to collective confidence. How could Iran cope for generation after generation if it were to remain caught between the great powers of the steppes and the west?

Second, Khusrau II's abrogation of Lakhm kingship – a bold, apparently foolish act, which was probably intended to prepare the way for a new system of multiple client princes to be introduced after the conquest of the Roman Near East – obviously weakened the outermost defence of Iran against the desert, provoking serious disturbances among neighbouring Bedouin tribes and providing an opportunity for the *umma* to exploit.

Third, regional particularism was to become a serious weakness, once the prestige of the crown was seriously harmed – after the battles of al Qadisiyya and Nihawand.

Fourth, it was Arab strength rather than Sasanian weakness that was the principal factor. It was a combination of (a) the driving faith of the Muslim community; (b) the well developed statecraft and organisational capability of Mecca; (c) distant horizons of vision on the part of the leaders of the *umma*; and (d) the priority given to the conquest of Iran that generated and sustained an external force great enough to overwhelm the resources of the Sasanians and to overrun the whole of Iran within twenty years of the Prophet's death. The reasons for the priority for the conquest of Iran rather than the rump of the Roman empire might be the following: (a) it was Iran that had posed a steadily growing threat to the Hijaz throughout the Prophet's lifetime; (b) Islam acknowledged its affinity with Christianity, but could not but set itself against Zoroastrian dualism; (c) Iraq was much more exposed to counter attack across the Zagros than was Palestine, shielded as it was by Syria to the north. The issue of priority is crucial. For it is plain that Byzantium was ripe for the taking by the early 650s, and that it was ultimately saved by the outbreak of civil strife within the caliphate in 656. Then, and only then, were the Byzantines able to revive their spirits and reactivate the ideology of a Christian, Roman, world shaping power.

The 'King of Kings of Iran and Non-Iran' and his subjects⁸⁶

It was a decidedly Iranian (as opposed to Parthian) attitude that characterised the Sasanian image of the ruler and his qualities. Ardashīr had put himself above all other dynasties of Ēranshahr as the 'King of Kings of Iran', while his son Shapur even included newly conquered territories (Aneran, or 'Non Iran') and their dynasts.⁸⁷ The Sasanians also presented themselves as kings with divine qualities (Mpl *bayan*) and as descendants and tools of the gods (*yazdan*).⁸⁸ Out of appreciation for the gods' favours, the Sasanian kings adopted the Zoroastrian cult, bestowed benefits on priests, founded 'fires', and thus multiplied places of worship.⁸⁹ 'Fires' were also established as 'Fires of Kings' and for the spiritual welfare and salvation of living and dead members of the royal household (cf. below).⁹⁰ Individual rulers derived their legitimacy not only through their descent but also through the 'divine grace' (Mid. Pers. *xwarrah*),⁹¹ already known to us from the Parthians, and through their personal effort in war and at the hunt.⁹² The dynasty in general derived its legitimacy by the invocation of earlier heads of the clan, and even kings of Iran the Sasanids themselves no longer knew by name, but whom they described as their 'forebears' (Gk. *pappoi*)

86 See Wiesehöfer, *Ancient Persia*, pp. 165 82, 287 91.

87 Among others ŠKZ 1/1/1. For the titles of (early) Sasanian kings, Huyse, *Die dreisprachige Inschrift*, vol. II, pp. 9b 11b and P. Huyse, 'Die sasanidische Königstitulatur: Eine Gegenüberstellung der Quellen', in Wiesehöfer and Huyse (eds.), *Ēran ud Aneran*.

88 Among others ŠKZ 1/1/1. W. Sundermann, 'Ke čīr az yazdan: Zur Titulatur der Sasanidenkönige', *Archiv Orientalni*, 56 (1988); H. Humbach, 'Herrscher, Gott und Gottessohn in Iran und in angrenzenden Ländern', in D. Zeller (ed.), *Menschwerdung Gottes: Vergöttlichung von Herrschern* (Fribourg and Göttingen, 1988); A. Panaino, 'The bayan of the Fratarakas: Gods or "divine" kings?', in C. G. Cereti, M. Maggi and E. Provasi (eds.), *Religious themes and texts of pre Islamic Iran and Central Asia: Studies in honour of Prof. Gherardo Gnoli on the occasion of his 65th birthday on 6th December 2002*, Beiträge zur Iranistik 24 (Wiesbaden, 2003).

89 See ŠKZ 22/17/38. See also K. Mosig Walburg, *Die frühen sasanidischen Könige als Vertreter und Förderer der zarathustrischen Religion: Eine Untersuchung der zeitgenössischen Quellen* (Frankfurt and Bern, 1982).

90 ŠKZ 22ff./17ff./39ff. M. Macuch, 'Charitable foundations, I', *Elr*, vol. V, pp. 380 2; for the 'fires of kings' and other fires, see Huyse, *Die dreisprachige Inschrift*, vol. II, pp. 102b 3a, 105b 7a.

91 G. Gnoli, *The idea of Iran: An essay on its origin*, Serie Orientale Roma 62 (Rome, 1989), pp. 148 51; A. Hintze, *Der Zamyad Yašt: Edition, Übersetzung, Kommentar*, Beiträge zur Iranistik 15 (Wiesbaden, 1994), pp. 15 17.

92 P. Gignoux, 'La chasse dans l'Iran sasanide', in G. Gnoli (ed.), *Essays and lectures*, vol. III: *Orientalia Romana* (Rome, 1983); M. Whitby, 'The Persian king at war', in E. Dabrowa (ed.), *The Roman and Byzantine army in the east: Proceedings of a colloquium held at the Jagiellonian University, Kraków in September 1992* (Crakow, 1994), pp. 227 63.

or their ‘ancestors’ (Gk. *progonoi*).⁹³ Later they would even associate themselves with the mythical kings of Iran, and in the Iranian ‘national history’, which they themselves decisively helped shape, they thus became the Iranian rulers par excellence, alongside the East Iranian Kayanids, who, like the mythical kings, are also not verifiable historically. They live on in Firdawsī and Nizāmī’s epics, just as in Islamic chronicles and popular literature. The Sasanians also created their own legend at the expense of the Arsacids, whose legitimate share in the Iranian success story was deliberately downgraded (see below).⁹⁴

Just like the Parthians, the Sasanians held an aristocratic ‘council of the king’, which was composed of the heads of old Parthian and new south west Iranian (that is to say, Persian) clans, and the aim of which was to confirm the rules for succession to the throne.⁹⁵ A special kind of worship of the founder of the empire can also be made out in their case.⁹⁶ Royal inscriptions of the early period distinguish between four specific ‘groups’ of aristocrats: the (Middle Persian) *šahrđaran* (regional dynasts and princes entrusted with rule over important parts of the empire), the *waspuhragan* (probably members of the Sasanian dynasty, but without direct descent from the ruler), the *wuzurgan* (heads of the most important aristocratic families, as well as other members of the high aristocracy), and the *azadan* (other noble Iranians).⁹⁷ The status of a Parthian or Persian aristocrat was, for a long time, virtually independent of the king’s favour. He owed it, including all external signs of his dignity (such as tiaras with crest like symbols, belts, earrings), to his name and descent; his

93 ŠKZ 21/16/35. For the partly different opinions on the identification of these ancestors, see T. Daryaei, ‘National history or Keyanid history? The nature of Sasanid Zoroastrian historiography’, *Iranian Studies*, 28 (1995); T. Daryaei, ‘Memory and history: The reconstruction of the past in Late Antique Persia’, *Nāme ye Irān e Bāstān*, 1, 2 (2001 2); A. S. Shahbazi, ‘Early Sasanians’ claim to Achaemenid heritage’, *Nāme ye Irān e Bāstān*, 1, 1 (2001); P. Huyse, ‘La revendication de territoires achéménides par les Sassanides: Une réalité historique?’, in P. Huyse (ed.), *Iran: Questions et connaissances: Actes du IVe congrès européen des études iraniennes organisé par la Societas Iranologica Europaea*, t. 1: *La période ancienne*, Studia Iranica, Cahier 25 (Paris, 2002); J. Wiesehöfer, ‘Gebete für die “Urahnen” oder: Wann und wie verschwanden Kyros und Dareios aus der Tradition Irans?’, in E. Dabrowa (ed.), *Tradition and innovation in the ancient world*, Electrum 6 (Crakow, 2002); and E. Kettenhofen, ‘Die Einforderung der achaimenidischen Territorien durch die Sasaniden: Eine Bilanz’, in S. Kurz (ed.), *Festschrift I. Khalifeh Soltani zum 65. Geburtstag* (Aachen, 2002). See also T. Daryaei, ‘The construction of the past in Late Antique Persia’, *Historia*, 55 (2006).

94 Yarshater, ‘Iranian national history’.

95 NPī 33/29f.; 36f./33f.; 37f./34. P. O. Skjaervø, ‘Commentary’, in Humbach and Skjaervø, *The Sassanian inscription*, p. 13; Sundermann, ‘Review’, pp. 84 5.

96 NPī 31f./28f.

97 Among others NPī 2f./2f. For the hierarchical classes, cf. Sundermann, ‘Review’, p. 84; Rubin, ‘Nobility’, pp. 243ff.

rank was thus a sign of his special political and economic position.⁹⁸ This only changed in the later period, in particular due to Khusrau I's reforms, which not only extended direct taxation of the land to the possessions of the landowning aristocracy, but also defined the position of the ruler vis à vis the aristocracy in a fundamentally new way, with a new order for the court, the aristocracy and the armed forces (at least for a short while).⁹⁹ This was also the time when kings attached particular importance to the education of young court aristocrats (cf. *Husraw ud redag*)¹⁰⁰ as well as to an ever more elaborate court etiquette.¹⁰¹ Female members of the royal family were granted a particular degree of esteem and attention in the Iranian sources of the third century.¹⁰² A title such as 'Queen of Queens' (MPl *bambišnan bambišn*) is thus confirmation of the unique rank of the woman who carried it, and not a sign of the king's close or incestuous consanguineous marriage, which is certainly known to us from Sasanian Iran.¹⁰³

Next to the aristocracy, it was religious dignitaries who carried special importance in the empire. These Zoroastrian 'priests' (*mobads*, *herbeds*) were not only experts in matters of religion (e.g. through the upholding of the religious tradition), but also in matters of administration and the law (as *dadwars*, i.e. 'judges'). Christians, for example, would get to know them as harsh judges in their trials. A real hierarchy of offices and functions, however, only developed from the fourth century on, in imitation of monarchical power. This hierarchy reached from simple officials on the ground, to the 'chief of the *mobads*' (Syr. *reš mauḥpate*) at the top.¹⁰⁴

98 Cf. Ammianus Marcellinus, *Rerum gestarum libri*, 18.5.6; KKZ 4/KNRm 9f./KSM 5; Procopius, *De bello Persico*, 1.6.13, 13.16. For the signs of dignity see von Gall, *Das Reiterkampfbild*, pp. 23–6; Peck, 'Clothing, IV'.

99 See Theophylact Simocatta, *Historia*, 1.9.3.8; Procopius, *De bello Persico*, 1.17.26–28; al Tabarī, *Ta'rikh*, series I, p. 990, lines 16f.; al Dīnawarī, *al Akhbar aṭ ṭīwal*, ed. Vladimir Guirgass, Leiden, 1888, p. 85, line 6f.

100 J. M. Unvala, *Der Pahlavi Text 'Der König Husraw und sein Knabe'* (Heidelberg, 1917).

101 Wiesehöfer, *Ancient Persia*, pp. 221–300; A. de Jong, 'Sub Specie Maiestatis: Reflections on Sasanian court rituals', in M. Stausberg (ed.), *Zoroastrian ritual in context* (Leiden, 2004).

102 E.g. ŠKZ 23/18/39; 25/20/46f.; 29/23/56. For the women of the royal family (and late Sasanian queens) see Wiesehöfer, *Ancient Persia*, pp. 174–5, 289–90, as well as Panaino, 'Women and kingship'.

103 M. Macuch, 'Inzest im vorislamischen Iran', *Archäologische Mitteilungen aus Iran*, 24 (1991); Wiesehöfer, *Ancient Persia*, pp. 181–2, 291; for Byzantine reactions to such relationships, see A. D. Lee, 'Close kin marriage in Late Antique Mesopotamia', *Greek, Roman and Byzantine Studies*, 29 (1988).

104 For religious dignitaries and officials see P. Gignoux, 'Éléments de prosopographie de quelques mobads sasanides', *JA*, 270 (1982); P. Gignoux, 'Die religiöse Administration in sasanidischer Zeit: Ein Überblick', in H. Koch and D. N. MacKenzie (eds.), *Kunst, Kultur und Geschichte der Achämenidenzeit und ihr Fortleben* (Berlin, 1983); and P. Gignoux, 'Pour une esquisse des fonctions religieuses sous les Sasanides', *JSAI*, 7 (1986). For the position

Lower state functionaries, craftsmen, city merchants, physicians, astronomers, 'scientists' and 'singers', as well as the professional servants and staff of the court and the estates of the aristocracy, must be counted among the 'middle classes' of the empire.¹⁰⁵ Peasants represented the great bulk of Iran's population. But it was those lessees who for centuries had been the aristocracy's bondsmen who profited in particular from Khusrau's reforms, as they advanced to become free tillers of their own plots of land.¹⁰⁶

Although legally defined as 'objects', in the Sasanian empire slaves were also seen as human beings, which distinguished them from other property, and, at the same time, protected them from excessively cruel treatment. This did not save them from being sold, rented or given as gifts, of course, and the products of a slave's labour would also always belong to his or her owner.¹⁰⁷

Late Sasanian legal manuals also tell us a great deal about 'the household and family' at the time.¹⁰⁸ The members of a household, who represented a legal unit, as well as a unit of production and consumption, and a religious entity, were connected to each other through a wealth of regulations and responsibilities, control over which was usually in the hands of the *kadag xwaday* (the 'master of the house'). Detailed regulations also characterised marital law and the law of inheritance, as well as property law and the law of obligations.¹⁰⁹

The royal court

The prime importance of the royal family at the Sasanian court is always apparent. First, the *res gestae* of both Shapur I (ŠKZ) and Narseh (NPi), which contain lists of court personalities graded in order of rank, give first rank to the members of the royal family, including queens and other 'ladies' (Mpl *banug*).¹¹⁰ It has rightly been stressed that social, not family, status was

of Kerdīr under the early Sasanians, see P. Huyse, 'Kerdīr and the first Sasanians', in N. Sims Williams (ed.), *Proceedings of the Third European Conference of Iranian Studies, held in Cambridge, 11th to 15th September 1995*, part 1 (Wiesbaden, 1998).

¹⁰⁵ Wiesehöfer, *Ancient Persia*, pp. 176, 290; for 'singers', see V. S. Curtis, 'Minstrels in ancient Iran', in Curtis, Hillenbrand and Rogers (eds.), *The art and archaeology of ancient Persia*.

¹⁰⁶ Wiesehöfer, *Ancient Persia*, pp. 176, 290, 1.

¹⁰⁷ M. Macuch, 'Barda and Bardadārī II', *Elr*, vol. III, pp. 763–6.

¹⁰⁸ For Sasanian legal manuals and their function see the excellent work of M. Macuch, *Rechtskasuistik und Gerichtspraxis zu Beginn des siebenten Jahrhunderts in Iran*, *Iranica* 1 (Wiesbaden, 1993).

¹⁰⁹ *Ibid.*, *passim*; see also A. Perikhanian, 'Iranian society and law', in Yarshater (ed.), *The Cambridge history of Iran*, vol. III, part 2.

¹¹⁰ Many of those personalities have already prosopographically been dealt with by U. Weber, *Prosopographie des frühen Sasanidenreiches* (Kiel, 2004), available at www.uni-kiel.de/klassalt/projekte/sasaniden/index.html.

responsible for a man or woman's rank both in the royal genealogy and in the royal household. Female members of the royal family appear on the royal reliefs as well as on coins; they are also immortalised on gems and seals of their own. Both the epigraphically proven rank of queens, consorts and princesses and those works of art testify to the important social role of the women of the royal household; thus it is no longer surprising that shortly before the fall of the empire, women could even ascend the throne, as was the case with Puran and her sister Āzarmīgdukht, even if this happened for lack of male candidates.¹¹¹

Second, the rule of succession to the throne was strictly patrilineal and restricted to members of the Sasanian family. The crises over the succession that arose in the third (Narseh vs. Wahram III), fourth (Ardashīr II vs. Shapur III), and sixth centuries (Wistahm vs. Khusrau II) all demonstrate that these rules could not easily be circumvented. As already mentioned, rightful birth and election by predecessor were only two of the necessary prerequisites for ruling; there was also the idea that the future king should have divine grace (*xwarrah*), i.e. the necessary charisma of kingship.¹¹² In the inscriptions of the early kings, legitimacy could also be established by reference to preceding rulers, thus, in Shapur's case, by reference to his father Ardashīr, his grandfather Pabag, to the eponymous Sasan, or even to the former great kings of Iran (the legendary Kayanids?).¹¹³

Third, as is shown by the title *mazdesn bay ke čīhr az yazdan* ('Mazdean divine Lord, whose origin [is] from the gods') for the reigning *shahanshah* ('King of Kings') in ŠKZ, the Sasanian kings stress the Mazdean quality of their royal power and their own divine nature (which, however, is different from that of the *yazdan*, i.e. Ohrmezd and the other gods).¹¹⁴ The other male members of the royal family did not share this title with the reigning (and with the deceased) king(s). Fourth, Shapur I founded fire temples 'for his own soul and glory' (*pad ama ruwan ud pannam*) and for the souls and the glory of his relatives and deceased ancestors, and endowed them with the necessary means. Apart from their social functions – material help for relatives and friends and provision of a special 'pension' for the founder's descendants – such endowments were also meant to provide the donor with prestige, to

¹¹¹ Panaino, 'Women and kingship'.

¹¹² See G. Gnoli, 'Farr(ah)', *Elr*, vol. IX, pp. 312–19.

¹¹³ For different identifications of those 'ancestors' and 'forefathers' see Daryaei, 'National history'; Daryaei, 'Memory and history'; Shahbazi, 'Early Sasanians' claim'; Wiesehöfer, 'Gebete'; Huyse, 'La revendication'; Kettenhofen, 'Die Einforderung'.

¹¹⁴ Panaino, 'The bayan of the Fratarakas', pp. 276–83.

establish his subjects' trust and loyalty and to maintain social structures of order. The deceased members of the royal family even became objects of organised worship, analogous to the Greek cult of dead heroes.¹¹⁵ The fire temples were normally named after their founders and benefactors (for example, the fire temple founded by Shapur I for his own soul and glory was given the name *Husraw Shabuhr* ('Glorious is Shapur')). Finally, consanguineous marriage (*xwedodah*), which the Zoroastrian theologians deemed meritorious and the Sasanians actually practised, served not only to keep property within the family but also to secure kingship by maintaining endogamy within the clan.¹¹⁶ However, not all royal marriages were incestuous, as external alliances for political reasons are also recorded.

Both the royal inscriptions and Manichaean texts make it clear that not all members of the royal household were permanent members of the royal court; in particular, the king's grown up sons (and other important relatives) were only temporarily in the ruler's personal vicinity, i.e. if their administrative duties or special occasions, such as festivities or wars, made it necessary to be present at court, or if the 'travelling king' with his entourage happened to come to a prince's province. Thus we may distinguish between a 'nuclear' court of permanent members and an 'extended' court of temporarily present people. It would appear that in early Sasanian times the 'nuclear' court mainly consisted of members of the royal family and household, with the great aristocratic landholders and magnates being part of the 'extended' court, since their main sphere of activity at that time was the management of their estates and the control of the peasants and tenant farmers dependent on them (see below).

In connection with the common duty to offer sacrifices for the benefit of the souls of the living and the dead, Shapur's *res gestae* list the contemporary members of the four aristocratic status groups mentioned above, as far as they were members of the ('extended') court society, both by their names and, if they held office, by their functions at court or in the empire. In early Sasanian times social ranking certainly also manifested itself at court, but, as far as the nobility is concerned, it was not only the court's head – the king – who set the rules of that ranking: descent could be still as important as royal favour. The fact that the Sasanians had not created these 'structures of standing' themselves, but had taken them over from the Parthians – while at the

115 Macuch, 'Charitable foundations'; M. Macuch, 'Die sasanidische Stiftung "für die Seele": Vorbild für den islamischen waqf?', in P. Vavroušek (ed.), *Iranian and Indo European studies: Memorial volume of Otakar Klima* (Prague, 1994); M. Stausberg, *Die Religion Zarathushtras*, vol. I (Stuttgart, 2002), pp. 219–20.

116 Wiesehöfer, *Ancient Persia*, pp. 180, 291.

same time enhancing the rank of the Persian, i.e. south west Iranian, aristocracy is proven by the end of the 'formula' in which the groups of nobility are presented in the Paikuli inscription: 'The landholders and the princes, the grandees and the nobles and the Persians and the Parthians'.¹¹⁷ The loyal Parthian clans warranted continuity, but were now complemented by Persian clans without having to give up their leading position. At a later period, other 'clans' rose to the rank of magnates.

Depending on their social, political and economic standing, the high aristocracy was also able to play an advisory and corroborative role in the process of proclaiming the king: for Narseh and his predecessors, we might assume a 'mock consultation' of the highest dignitaries of the empire, documenting an ancient right of co determination or, rather, confirmation held by the nobility.¹¹⁸ In times of a powerful central authority, apart from the members of the royal household and of the higher and lower aristocracy, 'outsiders' and 'new men' had a good chance of being promoted to a position close to the king at the 'nuclear' court by arbitrary royal patronage.¹¹⁹ A special exemplar of such a *homo novus* was the already mentioned ambitious Zoroastrian 'priest' Kerdīr, who, from the time of Shapur I to the time of Wahram II, rose to great importance at court, and was even able to tell us about his promotion by means of inscriptions, which were carved into the rock façades or walls of important 'royal' places and monuments: 'The King of Kings Hormezd [i.e. the son of Shapur I] bestowed on me the tiara (*kulaf*) and the belt (*kamar*), and he raised my position (*gah* ['throne', i.e. the place near the king]) and my dignity' (*ptḥšly*).¹²⁰ Kerdīr is a living example of a dignitary who started his career as a rather humble 'courtier', passed on to an extremely high position, not least because of his special abilities and the way he made himself indispensable, and probably lost his influence in the course of a new king's accession to the throne. It was his closeness to the king (i.e. the position of his *gah* at royal declarations, audiences and banquets) and the function he fulfilled that reflected a person's standing at the early Sasanian court, and outward dress made it manifest to a broader public. Among the most prominent marks of dignity were the tiaras (*kulaf*), on which certain colours and symbols of a heraldic kind could point to

117 NPī 3 (§ 5) etc.

118 See Skjærvø, 'Commentary', p. 13, and Sundermann, 'Review', pp. 84–5. A 'king's council' is mentioned in NPī § 68, the 'sham consultation' in NPī §§ 73 and 75.

119 Ammianus Marcellinus, *Rerum gestarum libri*, 18.5.6.

120 KKZ 4/KNRm 9f./KSM 5 (in Gignoux, *Les quatre inscriptions*).

particular ranks or distinctions. Belts (*kamar*) studded with gems and earrings played a similar part.¹²¹

For the Iranian aristocracy, however, the real criterion for grandeur was for a long time not so much a title or royal distinction but lineage, and in times of crisis or during the reigns of 'weak' kings the higher nobility could even force a ruler to acknowledge established career structures. A respective case study is presented by Procopius for the extremely crisis prone reign of King Kawad (fifth/sixth century), the father of the famous Khusrau I: 'He [Kawad] was mindful of the rule that did not allow the Persians to transfer any offices (*archai*) to strangers, but only to such men who were entitled to the respective position of honour (*time*) through their lineage.'¹²²

As we have seen, the rank of a Parthian or Persian nobleman had been more or less independent of the king's favour before the end of the fifth century; until then, the unruly heads of the great noble houses (such as Suren, Karin, the Lords of Andegan and others) acknowledged only a nominal allegiance to the central power but were virtually independent from the king in their hereditary territorial domains, and royal power and influence depended to a large degree on effective control of the provincial governors (who were mostly members of the royal clan), as well as on the active support of the majority of the higher nobles. This changed only in the late Sasanian period, when the wearing of belts, rings, clasps and other marks of prestige required royal approval. As the Byzantine author Theophylactus maintains, (bestowed) rank now came to be esteemed more highly than name and descent.¹²³ This strengthening of royal power had become possible after the great crisis of state and empire that began in the mid fifth century.¹²⁴ Crucial factors of the crisis were the disastrous defeats of Fīruz I (r. 459–84) against the Hephthalites in the east, leading to tributary dependence on the Hephthalite 'state', in addition to several years

¹²¹ Peck, 'Clothing'.

¹²² Procopius, *De bello Persico*, 1.6.13; cf. 1.13.16 (Mihran is in fact the name of a noble clan).

¹²³ Theophylact Simocatta, *Historia*, 1.9. 'Since it is a familiar habit of Persians to bear names according to distinguished positions, as if they disdained to be called by their birth names.' See Procopius, *De bello Persico*, 1.17.26–18 (a Mihran is punished by being deprived of a golden hairband: 'For in that country no one is allowed to wear a ring or a belt, a clasp or any other object of gold without royal bestowal'). For other examples see al Ṭabarī, *Ta'rikh*, series I, p. 990, lines 16f.; Theophylact Simocatta, *Historia*, 3.8; and al Dīnawarī, *al akhbar aṭ ṭiwal*, p. 85, lines 6f.

¹²⁴ That the fifth and sixth centuries was a crucial period in Sasanian history is proven by the fact that a lot of important political developments as regards home affairs occurred during that time: the development of a hierarchical Zoroastrian clergy on the model of political power; a change in dynastic legitimisation which stresses the mythological Kayanid link, etc.

of drought and famine. Meanwhile, the twofold burden imposed on the peasants by landlords and state taxes, on the one hand, and the Hephthalite occupation of parts of the country, on the other, had led to a rural exodus and protests on the part of the peasant population. The latter had found a religious and ethical motivation for such actions in the social doctrine of Mazdak, especially in his call for communal ownership. King Kawad's wish to establish his son Khusrau as successor to the throne in the 520s put an end to the long collaboration between the ruler and the followers of Mazdak, and led to violent actions by the Mazdakites against the land owning aristocracy, which were brutally suppressed by Kawad and Khusrau.¹²⁵ The subsequent reforms by the two kings were of a fundamental nature.¹²⁶ They not only extended direct land taxation to the estates of the landed aristocracy but, by establishing a new order for the nobility and the army, tried to change the empire's social structure and the position of the ruler with respect to the aristocracy: both the restoring of their old property to the nobility and the giving away of estates that no longer had owners were measures carried out at the behest of the king. In addition, a kind of 'administrative nobility' was created, and, in the case of the 'cavaliers' (MP *aswaran*), a military nobility whose duty was to follow the king in his campaigns. The latter was apparently meant to replace the retainer units formed by self equipped members of the aristocracy, troops that had never really been at the king's command. Arab authors also introduce a new (or newly emerged) lower nobility, the *dehkanan*, who took over the administration of a village as its richest landowners, and sometimes even owned entire villages. These had been promoted by the king, who had granted them land, money and other assistance. They were to be his partisans on a local level (as against members of the high aristocracy, who were critical of the king, and the potentially rebellious peasantry), and were also, if necessary, to stand by him in military matters.¹²⁷ Al Ṭabarī's report of Khusrau's reforms, quoted above, is quite unambiguous about the fact that the late Sasanian court underwent a change, too: whereas the 'nuclear' court had so far been determined by

125 For the Mazdakites see Sundermann, 'Mazdak'; Guidi and Morony, 'Mazdak'; Rubin, 'The reforms'; Gnoli, 'Nuovi studi'; and Wiesehöfer, 'Chusro I'.

126 For the reforms of Khusrau see the different opinions of Altheim and Stiehl, *Finanzgeschichte*, esp. pp. 31ff., Grignaschi, 'La riforma'; Howard Johnston, 'The two great powers', pp. 211ff.; Rubin, 'The reforms'; and Wiesehöfer, *Ancient Persia*, pp. 190–1, 292–3.

127 For the 'cavaliers' and *dehkanan* see F. Altheim and R. Stiehl, *Ein asiatischer Staat* (Wiesbaden, 1954), pp. 129ff.; Altheim and Stiehl, *Finanzgeschichte*, pp. 57ff.

members of the king's personal household (family members and domestic staff), the other higher nobles being only temporarily members of the ('extended') court, Khusrau's 'nuclear' court now consisted both of royal relatives and of members of a kind of service nobility (*Dienstadel*), hand picked and promoted by the ruler himself and more loyal to the king than to the clans they originally came from. It is this kind of court that is mirrored in most of the Middle Persian literary works (see below).

But as early as under Khusrau's immediate successors, renewed tensions arose between king and high aristocracy. It has been suggested that the king soon lost control of the 'cavaliers', who became again retainers of greater and virtually independent landlords, and that right from the start the king's supreme military commanders must have been powerful territorial lords.¹²⁸ The renewed political influence of the great landlords not only led, in the course of time, to the development of retinues of fighting men, but also to independent taxation in their own domains. In contrast to such powerful and ambitious nobles, who, as in early Sasanian times, again only temporarily visited the court, the members of the king's 'nuclear' court took the risk of losing their political weight in the case of a weak ruler and of becoming 'courtiers' in the strict sense of the word. Temporarily hindered in their ambitions because Khusrau II had centralised the financial administration, the landed and military aristocracy nevertheless managed to conspire against the king, who was reproached for his tyrannical attitude towards the nobility, his ruinous exaction of land taxes and his bloody wars against Byzantium. After Khusrau's death, kingship remained the instrument of different factions of the aristocracy. The rapid advances of the Muslim army and the sudden collapse of Sasanian sovereignty in Iran present a most eloquent testimony to the paralysing particularism of interests among the leading classes of the empire in this last phase of Iran's pre Islamic history.

In his *res gestae*, Shapur I enumerates the dignitaries, officials and aristocrats of his empire who are, at least temporarily, close to him and in his vicinity at court, and who are therefore entitled to have offerings made for the benefit of their souls. Lists of this kind have come down to us in other inscriptions too, among them one more in the *res gestae* of the second Sasanian king (in which he refers to the reigns of Pabag and

¹²⁸ Z. Rubin, 'The Sasanid monarchy', in A. Cameron, B. Ward Perkins and M. Whitby (eds.), *The Cambridge ancient history*, 2nd edn, vol. XIV: *Late Antiquity: Empire and successors, AD 425–600* (Cambridge, 2000), p. 657.

Ardashīr I), and several in Narseh's Paikulī inscription. They are all similarly arranged, starting with the members of the royal house, followed by members of the (seven) most important noble clans and ending with other dignitaries and officials. As far as ŠKZ is concerned, the arrangement of names seems to be the result of a special mixture of personal and political considerations of the king; in other words, the list is evidence both for the dignitaries' personal relationships with the king and for Shapur's decisions to assign certain people to certain offices because of their characters and/or their professional skills.

Ardashīr, the king of Adiabene, is at the head of the sixty seven dignitaries of Shapur's court. As this man is only mentioned in ŠKZ, we can only guess if he owed his outstanding position to his personal relationship with the king or to the importance of his province at that time, or to both. Probably due to the consolidation of power under the first two Sasanids, the 'extended' royal court increased considerably: whereas the court of King Pabag (Shapur's grandfather) had only consisted of eight members, and Ardashīr I had appointed thirty one dignitaries, Shapur I doubled their number. In other words, empire building led to complexity in the court, and generated rationales and structures of its own. It is a pity that we do not have a comparable view of the Arsacid court, which would allow us to recognise the special Sasanian traits of court offices and court society. It is all the more deplorable that we also do not have a similar description of the 'nuclear' or 'extended' late Sasanian court: Byzantine historians go into detail for reports of Persian diplomatic missions to the emperor,¹²⁹ but they are rather taciturn the other way round. Even Menander the Guardsman, who says a lot about the content of Byzantine Sasanian peace talks, does not provide us with a description of Khusrau's court. And the Iranian reports are either of a literary rather than historiographical kind (the contemporary works of Middle Persian literature; see below), or they are New Persian or Arabic adaptations of late Sasanian books (Firdawsī, *Shahnameh* etc.) which should be utilised only with great care, since they are not mere translations but rather epic or historiographical texts furnished in the style of their time of origin or with a special Islamic touch.¹³⁰ It is perfectly clear that in order to get an audience with the king in early Sasanian times, people had to go through the proper channels. King Wahram, then dining with two very close 'friends', as is shown by the king's later gesture of embracement, orders Mani to wait; after the

129 See Constantine Porphyrogenitus, *De caeremoniis aulae Byzantinae*, 1.89f.

130 Abka'i Khavari, *Das Bild des Königs*, although useful for its collection of sources, is quite uncritical in this respect.

end of the meal, he goes over to the waiting 'prophet' and gives him to understand that he is not welcome.

The 'Ardashīr romance' (*Karnamag ī Ardaxšīr ī Pabagan*), which was written in the late Sasanian period and subsequently revised,¹³¹ projects the social conditions of the time when it was composed into the period of the empire's founder, and is sometimes considered as a description of the lifestyle of the court of the last Sasanians.¹³² It is certainly true that after Khusrau's reforms and the creation of a service nobility, courtly manners were now also practised in the company of the king, the noble youths being royal courtiers and hostages for their fathers' loyalty at the same time. Obedience, elegant manners, culture, games and hunting were required and practised. It is no wonder then that among the late Middle Persian *andarz* texts ('wisdom literature') or their Arabic translations there are a number of works that in the form of royal declarations, throne speeches or testaments not only discuss or prescribe the proper character, behaviour and appearance of the king, but also that of his *bandagan* (his subjects) at court (at meals, at special occasions such as festivities, audiences etc.). At the same time, those texts were probably meant to foster the idea of a god given political and social hierarchy in the empire and at court. The special position of the king¹³³ manifests itself also in the ruler's dress, jewellery, headgear, crown and throne, his display of luxury¹³⁴ and, last but not least, in the splendour and architectural layout of his residential palaces. Thus, the Arab conquerors of Iran in the seventh century were highly impressed by the enormous crown of Khusrau II¹³⁵ and by his huge carpet known as 'Khusrau's spring' in his winter residence at al Mada'in.¹³⁶

It is also the time of Khusrau I and his successors that Middle Persian texts (such as the famous *Husrav ī kawadan ud redag e* ('Khusrau and his page'))¹³⁷

¹³¹ *Karnamag ī Ardaxšīr ī Pabagan*, 2.5, 10–12. An excellent edition with a French translation and commentary was published by Grenet (F. Grenet, *La geste d'Ardashir fils de Pâbag: Karnamag ī Ardaxšēr ī Pabagan* (Paris, 2001)).

¹³² For late Sasanian court culture see Altheim, *Geschichte der Hunnen*, vol. V, pp. 195ff.

¹³³ For the titulature of the kings see above.

¹³⁴ For the respective sources see Abka'i Khavari, *Das Bild des Königs*.

¹³⁵ For the famous crown of Khusrau II see al Ṭabarī, *Ta'rikh*, series I, p. 2446, lines 11ff.

¹³⁶ *Ibid.*, series I, p. 2452, lines 7ff.: 'Sixty times sixty yards as a single carpet by the dimension of its surface, on which the paths formed figures, the separating parts rivers, the intervals between them hills. On its border earth sown with spring growth out of silk against branches of gold, and its blossoms of gold, silver and the like.' See M. Morony, 'Bahar e Kesra', *Elr*, vol. III, p. 479.

¹³⁷ Edition: J. M. Unvala, *The Pahlavi text King Husrav and his boy: Published with its translation, transcription and copious notes* (Paris, 1921). For the character of the text (and other similar texts) see Cereti, *La letteratura*, pp. 178–84.

present the court as a special place of *savoir vivre*: Waspuhr, a young man, poor and without employment, presents himself to the king, whom he asks to question him in order to test the extent of his knowledge of the most diverse aspects of luxurious living: fine food and tasty fowl, the preparation of jellied meat, ragout, preserves and stewed fruit; music, the scent of flowers; the best women, the best animals to ride and other pleasures. This text not only lists all the arts of military exercise and warfare and every kind of board game, but also all the animals that were hunted by the king and his courtiers: the bull, the wild ass, the stag, the wild boar, the young camel, the calf, buffalo, ass and gazelle, as well as hare and rabbit, partridge, pheasant, lark, crane, bustard, duck and peacock. The references to birds show that hunting, the Iranian royal 'sport' *par excellence*, was practised not only as a test of strength, but also for entertainment and subsequent consumption.¹³⁸

Khusrau's interest in foreign games such as chess – the Middle Persian text *Wizarišn ī čatrang ud nihišn ī new ardaxšīr* tells the story of its introduction to Iran¹³⁹ – leads us to his promotion of scholarship and the arts, a common feature in royal ways of self manifestation and representation. Despite the unmistakable self praise we notice in Khusrau's *res gestae* (*karnamag*),¹⁴⁰ the king's efforts for higher learning cannot be denied. Agathias reports that Khusrau had offered hospitality to the Neoplatonic philosophers, who had become homeless after their school in Athens was closed down, and when – disappointed by the country and its inhabitants – they wished to return home, he had granted them exemption from punishment in their own country during his peace negotiations with Byzantium in 532.¹⁴¹ The king's discussions with Zoroastrian, Christian and other authorities about questions of cosmogony and the end of the world, about God, primary matter and the elements are

¹³⁸ For the royal hunt see the famous hunting reliefs of the Taq i Bustan grotto near Kirmanshah (K. Tanabe, 'Iconography of the royal hunt bas reliefs at Taq i Bustan', *Orient* (Tokyo), 19 (1983); J. D. Movassat, *The large vault at Taq i Bustan: A study in late Sasanian royal art* (Lewiston, 2005)).

¹³⁹ Edition and commentary: A. Panaino, *La novella degli scacchi e della tavola reale: Un'antica fonte orientale sui due giochi da tavoliere più diffusi nel mondo eurasiatico tra Tardoantico e Medioevo e sulla loro simbologia militare e astrale. Testo pahlavi, traduzione e commento al Wizarišn ī čatrang ud nihišn ī new ardaxšīr* (Milan, 1999). Cf. T. Daryaei, 'Mind, body, and the cosmos: Chess and backgammon in ancient Persia', *Iranian Studies*, 35 (2002).

¹⁴⁰ Ibn Miskawayh, *The Tajārib al umam or History of Ibn Miskawayh* (Abu 'Alī Ahmad b. Muhammad), with a preface and summary by Leone Caetani, E.J.W. Gibb Memorial series 7, Leiden, 1913, pp. 206.4ff.

¹⁴¹ Agathias, *Historiae*, 2.30f. See U. Hartmann, 'Geist im Exil: Römische Philosophen am Hof der Sasaniden', in M. Schul, U. Hartmann and A. Luther (eds.), *Grenzüberschreitungen: Formen des Kontakts zwischen Orient und Okzident im Altertum*, *OrOcc* 3 (Stuttgart, 2002).

famous.¹⁴² Khusrau's interest in the East is shown by his initiative in commissioning a translation of a version of the Indian book of fables, the *Panchatantra*, which the physician Burzoy had brought from India.¹⁴³ Besides philosophy, theology and statesmanship, Khusrau was also interested in foreign contributions to law and medicine. Aside from medical inspirations from the West, Iranian and Indian traditions were also assimilated. Burzoy, himself a physician from Nishapur, reports about them in his introduction to the collection of fables. According to an Arabic source, Khusrau I even wrote a medical book himself, or rather compiled it from Greek and Indian works. It was through the Sasanian Middle Persian intermediary that not only medical and pharmaceutical literature from East and West, but also Romano Byzantine agricultural writings and the *Almagest* of Ptolemy, found their way into Arabic literature.¹⁴⁴

The late Sasanian period was altogether a time of literary flowering, much of it commissioned or sponsored by the royal court. Khusrau I Anushirwan and his successors are credited with having especially contributed to promoting literature: thus Weh Shapur, the head of the Zoroastrian clergy under Khusrau I, is said to have published the twenty one *nasks* of the Avesta, and the *X^waday namag* (the 'Book of Lords'), the semi official 'Iranian national history', apparently existed in an initial authoritative version in Khusrau's reign and was later repeatedly revised (and continued).

142 Wiesehöfer, *Ancient Persia*, pp. 217, 299.

143 F. de Blois, *Burzoy's voyage to India and the origin of the Book of Kalilah wa Dimna* (London, 1990).

144 For the intermediary role of Sasanian Iran in philosophy, medicine, religion, mythology, magic, technical knowledge, law and science see P. Gignoux, 'Prolégomènes pour une histoire des idées de l'Iran sassanide: Convergences et divergences', in Wiesehöfer and Huyse (eds.), *Ēran ud Aneran*; R. Gyselen (ed.), *La science des dieux: Sages, mages, astrologues*, *Res Orientales* 12 (Bures sur Yvette, 1999); R. Gyselen (ed.), *Charmes et sortilèges: Magie et magiciens*, *Res Orientales* 14 (Bures sur Yvette, 2002); A. Panaino, 'Greci e Iranici: Confronto e conflitti', in S. Settis (ed.), *I Greci*, vol. III: *I Greci oltre la Grecia* (Torino, 2001); Z. Rubin, 'Res Gestae Divi Saporis: Greek and Middle Iranian in a document of Sasanian anti Roman propaganda', in J. N. Adams, M. Janse and S. Swain (eds.), *Bilingualism in ancient society: Language contact and the written text* (Oxford, 2002); R. M. Schneider, 'Orientalism in Late Antiquity: The Oriental other in imperial and Christian imagery', in Wiesehöfer and Huyse (eds.), *Ēran ud Aneran*; M. Ullmann, *Islamic medicine* (Edinburgh, 1978); L. Richter Bernburg, 'On the diffusion of medical knowledge in Persian court culture during the fourth and fifth centuries AH', in Z. Vezel et al. (eds.), *La science dans le monde iranien à l'époque islamique* (Tehran, 1998); L. Richter Bernburg, 'Iran's contribution to medicine and veterinary science in Islam AH 100 900/AD 700 1500', in J. A. C. Greppin et al. (eds.), *The diffusion of Greco Roman medicine into the Middle East and the Caucasus* (Delmar, 1999); L. Richter Bernburg, 'Medicine, pharmacology and veterinary science in Islamic eastern Iran and Central Asia', in C. E. Bosworth and M. S. Asimov (eds.), *History of civilizations of Central Asia*, vol. IV: *The age of achievement: AD 750 to the end of the fifteenth century*, part 2: *The achievements* (Paris, 2000).

And finally, numerous compilations of *andarz* texts, as we have seen, and even the publication of treatises of this nature of his own, are attributed to Anushirwan and his entourage.

Although former studies on Sasanian 'feudalism' very often drew unjustified and inaccurate parallels between Sasanian Iran and the medieval European monarchies, the theoretical parameters of studies on late medieval and early modern courts proved to be quite useful for cutting a swathe through the source material on the Sasanian court and on power and 'state building' in Sasanian Iran. However, a lot of work is still to be done: we urgently need fresh analyses of the Arabic and New Persian texts in the light of the extant late Sasanian and the contemporary Byzantine and Syriac literature, and a closer look at possible Iranian influence on Byzantine court institutions (and vice versa). And we would greatly appreciate further philological studies on the Middle Persian and Parthian vocabulary and word fields of 'court', 'rank' and 'dignity', as well as archaeological work on palace architecture and royal representation.¹⁴⁵

Petty kings, satraps, craftsmen, merchants and soldiers

Sasanian royal inscriptions of the third century, as well as seal legends of later times, mention a host of dignitaries and officials. These included, for instance, 'petty kings' (MP *šah*) in certain regions of the empire, such as Armenia and Mesene, 'satraps' (*šahrab*) in other provinces (*šahr*), their personal assistants, as well as the officials in the 'districts', and those on the ground. As we have heard, the royal court also maintained numerous functionaries and dignitaries at all times. There were administrative, military and educational functionaries and advisers, as well as those active in the fields of etiquette and the cult.¹⁴⁶ As already mentioned, following the reforms of Khusrau, most of these officials no longer represented the interests of their own families, but were now accountable to the king alone. In early Sasanian times some parts of the land were under the direct

¹⁴⁵ But see Marion Hoffmann, 'Sasanidische Palastarchitektur' (Munich University, 2006), available at <http://edoc.ub.uni-muenchen.de/9439/>.

¹⁴⁶ Important works on this topic are R. Gyselen, *La géographie administrative de l'empire sassanide: Les témoignages sigillographiques* (Paris, 1989) and R. Gyselen, *Nouveaux matériaux pour la géographie historique de l'empire sassanide: Sceaux administratifs de la collection Ahmad Saeedi*, *Studia Iranica*, Cahier 24 (Paris, 2002); see also Wiesehöfer, *Ancient Persia*, pp. 183ff., 291ff.

control of the king, while royal control (i.e. collection of taxes, conscription into the army) affected other parts of the land, namely those in the possession of the aristocracy, only by proxy. While at that time rulers could only found cities on 'royal land', the weakening of the aristocracy through the revolts of the late fifth century allowed the kings to turn land belonging to the aristocracy into royal land.¹⁴⁷ The fiscal reforms of Khusrau I (see above), which established fixed poll taxes and land taxes (Ar. *jizya* and *kharaj*), led, albeit only temporarily, to a strengthening of royal power, as well as a relaxation on the 'fiscal front'. They provided the king with greater leeway politically, in both the domestic and foreign arenas. The patronage of the sciences, arts and literature, as well as the renewed animosity towards Byzantium, can thus be explained.

As with virtually all states of Antiquity, agriculture was the fundamental economic activity in the Sasanian empire.¹⁴⁸ Apart from this, many subjects of the 'King of kings' earned their livelihood in the various crafts, in royal 'workshops', as well as in small private businesses. Many of the professionals employed by the king were men who had been deported from Syria and other regions and resettled in Iran during the reigns of Shapur I or Khusrau I, or their descendants.¹⁴⁹ Workers recruited by the state, or prisoners of war, worked in the textile industry of Khuzistan and in the construction industry, as well as as ironsmiths, goldsmiths, locksmiths and dyers.¹⁵⁰ The bridges, dams and irrigation works built by Roman prisoners of war are still impressive today.

Like the Parthians, the Sasanians were also trading their own and foreign products from west to east and vice versa; and like the Parthians, they cultivated contact with India by sea and China by land. But both the Byzantines and the Sasanians tried to find ways to further their own advantage in trade to the exclusion of the other side.¹⁵¹

As far as the equipment and tactics of their troops was concerned, the Sasanians also stuck to the Parthian model for a long time, especially regarding the cooperation of heavily armoured cavalry and mounted archers.¹⁵² They

¹⁴⁷ Altheim and Stiehl, *Ein asiatischer Staat*, pp. 12ff.; D. Metzler, *Ziele und Formen königlicher Innenpolitik im vorislamischen Iran* (Münster, 1977), pp. 177ff.; Wiesehöfer, *Ancient Persia*, pp. 189–91, 292–3.

¹⁴⁸ Wiesehöfer, *Ancient Persia*, pp. 191–2, 293.

¹⁴⁹ E. Kettenhofen, 'Deportations, II', *Elr.*, vol. VII, pp. 297–308.

¹⁵⁰ For crafts and craftsmen see Wiesehöfer, *Ancient Persia*, pp. 192–4, 293.

¹⁵¹ *Ibid.*, pp. 194–7, 293–4.

¹⁵² Ammianus Marcellinus, *Rerum gestarum libri*, 23.6.83, 24.6.8; Procopius, *De bello Persico*, 1.14.24, 44.52; al Ṭabarī, *Ta'rikh*, series I, p. 964, lines 9f.; al Dīnawarī, *al akhbar at ṭīwal*, p. 74, lines 15f.

also became experts in siege warfare,¹⁵³ this time imitating the Roman model. Battles were usually decided by a forceful attack of the cavalry, coupled with a shower of arrows from the archers. The king or general would be situated in the centre, near the imperial standard, and protected by elite troops.¹⁵⁴ This line up, alongside the Persians' alleged lack of stamina in close contact fighting, was the reason for many a Sasanian defeat. If the commander fled or fell, the soldiers, too, would give up the fight. And in the end, their heavily armoured cavalry would be overcome by the lightly armoured and more flexible horsemen of the Muslim armies.¹⁵⁵

Religion and culture

The Sasanian empire was also characterised by the magnitude and diversity of its religious groups and communities. Most prominent among them were the Zoroastrians, who had populated Iran for centuries, but there were also Christians, Jews, Manichaeans and Mazdakites. Although Christians had settled in Mesopotamia in small numbers since the end of the second century, it was only the deportation of Roman citizens from Syria that served as the basis for a flowering of Christian communities in the Sasanian empire. Following the end of the persecution of Christians, and due to the Christological disputes that took place in the Roman empire, the Sasanian empire became a refuge for many persecuted Christians from the Roman East (Nestorians, Monophysites and others).¹⁵⁶

Jews, with their old centres in Mesopotamia, and as loyal subjects of the Sasanian kings, were, by and large, not exposed to persecution, except in a few instances. This also explains how the great rabbinic schools of Mesopotamia could engage in the process of commentary and interpretation of the Mishna, which by the end of the sixth and beginning of the seventh centuries would eventually be concluded by the completion of the Babylonian Talmud.¹⁵⁷

153 Ammianus Marcellinus, *Rerum gestarum libri*, 19.5f., 20.6f., 11.

154 For the ruler in battles, see Whitby, 'The Persian king at war'.

155 For the Sasanian military, see A. S. Shahbazi, 'Army, I', *Elr*, vol. II, pp. 489–99; Wiesehöfer, *Ancient Persia*, pp. 197–9, 294.

156 For Christians in the Sasanian empire see Wiesehöfer, 'Geteilte Loyalitäten'; and (for the early Sasanian era) C. Jullien and F. Jullien, *Apôtres des confins: Processus missionnaires chrétiens dans l'empire iranien*, *Res Orientales* 15 (Bures sur Yvette, 2002) (both containing references to older literature). See now also M. Arafat, J. Tubach and G. S. Vashalomidze (eds.), *Inkulturation des Christentums im Sasanidenreich* (Wiesbaden, 2007).

157 J. Neusner, *A history of the Jews in Babylonia*, vols. II–V (Leiden, 1960–70); J. Neusner, *Israel and Iran in Talmudic times* (Lanham, 1986); and J. Neusner, *Israel's politics in Sasanian Iran* (Lanham, 1986); A. Oppenheimer, *Babylonia Judaica in the Talmudic period*,

Lastly, the Manichaeans were founded as a religious community by Mani, who had been born as a Parthian subject in Mesopotamia in 216 CE, but later concentrated his missionary activities on the Sasanian empire and beyond. Following the death of their prophet in a Sasanian prison, the Manichaeans diverted their activities to the Roman east, Arabia, and in particular further east along the Silk Route, where they would become serious rivals to Zoroastrians, Christians, Buddhists and Muslims for the hearts of those in search of religion.¹⁵⁸

For a long time scholars have tried to juxtapose the religiously 'tolerant' Arsacids with the supposedly 'intolerant' rule of the Sasanians. Under the latter, a Zoroastrian 'state church' is supposed to have joined forces with the king, rigid in religious matters, in a so called covenant of 'throne and altar' to the detriment of the non Zoroastrian communities. Today we know that Sasanian Iran was indeed 'Zoroastrianised' to a greater extent than ever before in its history, and that the kings acted as sponsors of that faith. However, we also know that the religious and social identity of the kings and their subjects, as well as their relationships with each other, were characterised by features similar to those existent in the Roman empire. That is to say, the personal faith of each individual ruler was a factor – but, more importantly, so was the general internal and external situation of the empire and the political reaction of the kings to it (including their reaction in terms of religious policy). Also decisive was the conflict between the Zoroastrian priesthood, for whom Iranianism and Zoroastrianism were one and the same, and the faiths of the Christians and Manichaeans, which were not only theoretically directed towards universalism, but in fact had become 'universal' faiths. It was a conflict that can be described in the field of tradition as one between the 'People of the Book', on the one hand, and the followers of Zoroaster's message of salvation, on the other. Up until the fifth century, this message was only transmitted orally, in its distinctly 'Sasanian' attire. From the point of view of those affected by it, this was a conflict between 'God's people' (for the Christians), or the *electi* and *auditores* (for the Manichaeans), and the Zoroastrian 'priests', who were, above all else,

Beihefte zum Tübinger Atlas des Vorderen Orients, series B, no. 47 (Wiesbaden, 1983); R. L. Kalmin, *Jewish Babylonia between Persia and Roman Palestine: Decoding the literary record* (Oxford, 2006).

- 158 See above all S. N. C. Lieu, *Manichaeism in the later Roman empire and medieval China*, 2nd rev. edn (Tübingen, 1992); S. N. C. Lieu, *Manichaeism in Central Asia and China* (Leiden, 1998); and S. N. C. Lieu, *Manichaeism in Mesopotamia and the Roman east*, 2nd edn (Leiden, 1999); W. Sundermann, 'Studien zur kirchengeschichtlichen Literatur der iranischen Manichäer I/II', *Altorientalische Forschungen*, 13 (1986), pp. 40–92, 239–317; and W. Sundermann, 'Studien zur kirchengeschichtlichen Literatur der iranischen Manichäer III', *Altorientalische Forschungen*, 14 (1987).

especially concerned to safeguard the interests of the empire. However, state and religious authorities did not always act in harmony with each other in their interaction with minorities. The image of a covenant of 'throne and altar' is a construction of much later (Islamic?) times. There was never a Zoroastrian 'state church', or a single *religio licita* (officially authorised religion). Christians were persecuted not only when they were regarded as religious rivals, but also when they were believed to be politically unreliable subjects. However, from 424, when they organised themselves in a church with its own head, and when they finally broke with the Roman Church Christologically, after 484, through the definite adoption of the 'Nestorian' creed, the Sasanian kings contemplated this development with satisfaction. They used Christian dignitaries as ambassadors and advisers, and supported also in their own interests Nestorian education and science, such as in the 'School of the Persians', which was relocated from Edessa to Nisibis, or in the 'university' of Jundīshapur in Khuzistan.

As far as the Manichaeans are concerned, the exact historical circumstances under which they were supported (e.g. under Shapur I) or persecuted (e.g. under Wahram I and II) should be noted. The Zoroastrian authorities abhorred the Manichaeans the way they did (as, incidentally, did the Christians), because the Manichaeans dressed their message within Iran partly in Iranian Zoroastrian garb and, in addition to that, aspired to supersede and supplant all other religions. Thus, when the king needed the support of the priesthood in particular, this could very easily also lead to a persecution of Manichaeans.

The followers of Mazdak, whose call for a 'collective of possessions and women' and rejection of trial by ordeal and of oaths shook the foundations of Zoroastrian social and moral beliefs, were also 'heretics' in the eyes of the Zoroastrians. Their way of life threatened the fundamental bases and interests of the social order, grounded, as it was, in patrilineal descent and the preservation of the household in the male line. Thus, the Mazdakite 'reforms' could not in the long run be in the interests of the ruler either.¹⁵⁹

Let us cast a quick glance at the cultural achievements of Sasanian artists and scientists. The influence of Sasanian architects extended far into the Byzantine, Armenian and Islamic Orient, with their cupola designs and *iwan* constructions, as well as their specific decorative ornamentation. Iranian toreutics and textiles spread into China and western Europe. Works of literature were transmitted from West to East, and vice versa, through the mediation of late Sasanian Iran. Graeco Roman knowledge in the fields of

¹⁵⁹ For the religious policy of the Sasanians see Wiesehöfer, 'Geteilte Loyalitäten'.

philosophy, medicine, law, geography and agriculture was transmitted at the academies, where, among other places, it would later be eagerly picked up by the Muslims. Finally, Manichaeans and Christians conducted their wide reaching missionary activities from Iran, as we have seen above. Iranian literature, law, religious beliefs and *termini technici*, in their turn, also spread to both Orient and Occident.¹⁶⁰

A semi official version of Iranian history was also laid down in writing during the Sasanian era, in the form of the already mentioned 'Book of Lords' (*X^waday namag/Khwaday namag*). This book would become the most important legacy of ancient Iran within Iran itself, its legends stemming from various great epic cycles. Pertaining, in time, to both the very distant and extremely recent past, and, in space, to geographical regions both near and far, these legends were arranged in a chronological system, and adapted to the religious, moral and ethical as well as literary 'ideals' of the time. Owing to its later adaptation by the brilliant poet Firdawsī, the 'Book of Kings' (*Shahnameh*), as it was now called, would eventually become a piece of world literature.

Military encounters between Iran and Byzantium¹⁶¹

Whereas the fourth century was characterised by numerous military conflicts between the superpowers Iran and Byzantium, and, as a consequence, by massive persecutions of Christians in the Sasanian empire, the reign of Yazdgerd I (399–420), in particular, witnessed a Christian friendly policy,¹⁶² as well as an attempt at reconciliation with Byzantium. In 408/9, for example, an agreement concerning trade rules between East and West was reached.¹⁶³ Emperor Arcadius is even alleged to have expressed a wish that, after his death, the Sasanian ruler should become the 'guardian' of his son Theodosius,

¹⁶⁰ For a summary of the cultural achievements of the (late) Sasanians and their role as cultural mediators see Wiesehöfer, *Ancient Persia*, pp. 216–21, 298–300; also Panaino, *La novella*; and J. Wiesehöfer, "Randkultur" oder "Nabel der Welt"? Das Sasanidenreich und der Westen: Anmerkungen eines Althistorikers', in Wiesehöfer and Huysse (eds.), *Ēran ud Āneran*, *passim*.

¹⁶¹ The section is indebted to information found in Winter and Dignas, *Rom und das Perserreich*; Greatrex and Lieu, *The Roman eastern frontier*; and Sebeos, *The Armenian history attributed to Sebeos*, trans. R. W. Thomson with commentary by J. Howard Johnston, *Translated Texts for Historians* 31, 2 vols. (Liverpool, 1999). More detailed literature regarding specific stages of Iranian–Byzantine encounters and clashes can be found below, in the section dealing with political and military history.

¹⁶² Socrates Scholasticus, *Historia ecclesiastica*, 7.8.1–20.

¹⁶³ *Codex Justinianus*, IV.63.4.

still a minor at the time.¹⁶⁴ However, towards the end of Yazdgerd's reign there were renewed persecutions of Christians.¹⁶⁵ Numerous Persian Christians thus fled to the west with the new king, Wahram V Gor (r. 420–39), demanding their extradition. Furthermore, a war broke out with Byzantium in 421, which, due to lack of success on both sides, was brought to an end by a truce just a year later.¹⁶⁶ It subsequently only came to a limited military encounter between the two sides in 441. The reason for this may have been twofold. On the one hand, the Byzantine emperor had lost his claim to being the sole protector of the Christians. The Sasanian empire had become the new home for many of the followers of Nestorius's teaching of the dual nature of Christ following the Councils of Ephesus (431) and Chalcedon (451). Moreover, the 'Nestorianisation' of the Christian communities of the Sasanian empire, which came about at the Synod of Beth Lapat in 484, and which was supported by King Firuz (r. 459–84), was proof for the Christians' loyalty toward the Sasanian 'state'. On the other hand, Yazdgerd I and Firuz had to fight off the assault of new peoples from the east, namely the Hephthalites or 'White Huns'. Although the Sasanians suffered injurious defeats at the hands of these 'Turanians' (see below), which would eventually plunge the empire into chaos, Byzantium apparently did not use her rival's difficult situation to her own advantage,¹⁶⁷ except for a short episode, which saw the temporary suspension of payments for the defence of the passes over the Caucasus.¹⁶⁸

It was only with the return of Kawad to the throne in 499 that the focus of Sasanian foreign policy was again directed toward the west.¹⁶⁹ When, in 502, he needed money to pay the Hephthalites, with whom he had formed an alliance, he turned to Anastasius I. The latter was not forthcoming, but instead demanded the return of Nisibis, and Kawad thus used the opportunity to reopen hostilities.¹⁷⁰ The ensuing clashes, which extended over a number of years, saw Sasanian troops retain the upper hand for the most part, and in 503 led to the capture of the strategically important city of Amida. The war was temporarily halted in 505/6. After renewed troubles with Hunnic tribes, the

164 Procopius, *De bello Persico*, 1.2.7–10. See P. Pieler, 'L'aspect politique et juridique de l'adoption de Chosroes proposée par les Perses à Justin', *Revue Internationale des Droits de l'Antiquité*, 3 (1972).

165 Theodoret, *Historia ecclesiastica*, 5.39.1–6.

166 John Malalas, *Chronographia*, 14.23; Procopius, *De bello Persico*, 1.2.11–15.

167 See Procopius, *De bello Persico*, 1.3.8.

168 Priscus, *Historia Byzantiaca*, 41.1 (FHG IV fr. 31).

169 Procopius, *De bello Persico*, 1.6.1–18.

170 Johannes Laurentius Lydus, *De magistratibus populi*, 51.3; Joshua the Stylite, *Chronicle*, 7.11f.; Procopius, *De bello Persico*, 1.7.1f.

Iranians finally agreed to return Amida, and other territories they had conquered, for a substantial sum of money. A peace that was negotiated to last for only seven years in fact continued for more than twenty.¹⁷¹ Although Emperor Anastasius irritated the Sasanians by his excessive border protection policy,¹⁷² there were no more military clashes during his lifetime. War only erupted again under his successor Justin, probably due to disputes regarding the crucial border regions of Lazica and Iberia, as well as the Caspian Gates. Kawad's attempt to reach a diplomatic agreement with Byzantium, to secure his son Khusrau's succession, failed.¹⁷³ It is likely that war broke out in 526, that is to say, before Justin's death, a war that was still raging the year Kawad died (531). As neither side could attain a decisive advantage over the other, a truce was signed a year later. Byzantium agreed, on the one hand, to pay large sums for the upkeep of the Caucasus fortifications and the protection of the border there, while also agreeing to relocate the base of the *dux Mesopotamiae* from Dara, which was situated close to the border, to Constantia instead.¹⁷⁴ In return, the Sasanians gave up their claims to important sites in Lazica. Even though Procopius talks of the conclusion of an 'Eternal Peace' with regard to the treaty of 532,¹⁷⁵ the two powers were soon at war with each other again.

Diplomatic activities preceding the war were aimed at improving one's own position in the international balance of power of the time.¹⁷⁶ Apparently unresolved border disputes between the Arab tribes of the Lakhmids (clients of the Sasanians) and the Ghassanids (clients of Byzantium) and appeals for intervention in Roman Armenia served as a pretext for a new outbreak of war.¹⁷⁷ From spring 540, the two superpowers were fighting again. First it was Khusrau who was able to achieve a prestigious success with the conquest of Antioch. Heavily engaged in the west, Justinian had to accept a truce, which stipulated that Khusrau would withdraw, while Byzantium would pay a yearly tribute of five hundred pounds of gold.¹⁷⁸ Renewed military clashes erupted the following year. Khusrau, who had been called to help by the Lazicans against the deployment of Byzantine troops, agreed to provide the inhabitants

171 Procopius, *De bello Persico*, 1.9.1 25.

172 Ibid., 1.10.1 19.

173 Ibid., 1.11.6 11, 29f.

174 Ibid., 1.22.3 5, 16 18.

175 Ibid., 1.22.3.

176 Ibid., 2.2.4 11.

177 Ibid., 1.17.40f., 45 8. See Shahid, *Byzantium and the Arabs in the sixth century*, pp. 209 18; H. Börm, 'Der Perserkönig im Imperium Romanum: Chosroes I. und der sasanidische Einfall in das Oströmische Reich 540 n.Chr.', *Chiron*, 36 (2006).

178 Procopius, *De bello Persico*, 2.10.24.

of Lazica with protection.¹⁷⁹ Following a massive summons to arms, the Sasanians took Petra, a fortress on the east coast of the Black Sea.¹⁸⁰ However, the Byzantines were able to keep a balance in the battles of the subsequent years in Armenia and Mesopotamia. The Sasanians even ended the siege of Edessa in return for a payment of ransom.¹⁸¹ While a truce concluded in 545 confirmed Khusrau's dominant position in Lazica and forced Justinian to commit to considerable payments,¹⁸² a number of heavy defeats in 557 compelled Khusrau to acknowledge the status quo in a new truce that was supposed to precede a formal peace treaty.¹⁸³ This peace treaty was only concluded in 562,¹⁸⁴ and marked the climax of diplomatic relations between the two superpowers (see below).

The alliance between Byzantium and the western Turks, as well as the Sasanian advance into southern Arabia,¹⁸⁵ again led to the outbreak of a much longer war between Byzantium and the Sasanian empire in the spring of 572. Whereas Byzantine troops besieged Nisibis in vain, the Sasanians were able to take the Byzantine fortress of Dara towards the end of the following year, attack Syria and devastate it. The subsequent military encounters led to heavy losses on both sides. The war did not bring about any victories for Justin II, in particular. In addition, Byzantium was threatened by the Avars in the north, and faced a Lombard menace to its Italian possessions. As a result, Tiberius, whom Justinian had made fellow regent in 574 because of his own mental illness, decided to enter into negotiations with Khusrau I. They initially agreed a one year truce, which was eventually extended (575–8). But the state of war continued because Armenia was not included in the truce, and diplomatic efforts for a peace there remained unsuccessful. The Sasanian king thus decided to attack Mesopotamia even before the truce had expired. Despite early Sasanian successes in Armenia and in the Byzantine part of Mesopotamia, the Byzantines managed to check the Persians and drive them back (the battle of Melitene), so that Khusrau was now prepared to sign a peace treaty after all. But the great Sasanian king died before an exchange of ambassadors could take place. His son and successor Hormezd IV (r. 579–90) presented the Byzantine ambassador with demands that could not possibly have been met from a

179 Ibid., 2.15.1 31.

180 Ibid., 2.17.3 28.

181 Ibid., 2.26.5 46, 27.1 46.

182 Ibid., 2.28.6 11.

183 Agathius, *Historiae*, 4.30.8 10.

184 Menander Protector, *Historiae*, fr. 6.1 (FHG IV fr. 11).

185 Theophylact Simocatta, *Historia*, 3.9.3 11.

Byzantine point of view. Consequently, the war continued for the entire reign of Hormezd, even after Maurice had succeeded as Byzantine emperor.

While the war continued in Mesopotamia, the Sasanians also were threatened by the Turks in the east, the Khazars in the north and Arab tribes in the south. The Western Turk danger in particular began to escalate in much the same way as the Hephthalite threat had done in the fifth century, and it was only due to the exceptional military capabilities of the Sasanian general Wahram Chobīn that the enemies in the east could be defeated and made to pay tribute in 588/9. He was subsequently sent to the southern Caucasus, in order to push for a fight with Byzantium from there. Triumphant at first, he then suffered a defeat in Azerbaijan.¹⁸⁶ When Hormezd IV accused him of cowardice and discharged him,¹⁸⁷ Wahram revolted against the king, and with him the Persian army fighting in Mesopotamia.¹⁸⁸ In the end Hormezd was captured and blinded, and soon after the start of the new year in June 590¹⁸⁹ his son Khusrau II Abarwez (Parwez) (r. 590–628) was declared the new king. The latter tried in vain to come to an understanding with the rebels, but ultimately had to flee from Wahram,¹⁹⁰ who ascended to the Sasanian throne as Wahram VI Chobīn on 9 March 590.¹⁹¹ Maurice answered the territorial and financial offers of both pretenders to the throne with a clear stance in favour of Khusrau.¹⁹² As a result, Byzantine and Sasanian troops fought side by side for the first and only time ever. In the spring of 591 Khusrau II began to move against Wahram VI, and with Byzantine help he succeeded in defeating the rebel.¹⁹³ The latter fled to the western Turks, but was assassinated only a year later. The third great Iranian Byzantine conflict of the sixth century thus ended with the renewed enthronement of Khusrau II Abarwez in 591 and a peace treaty concluded the same year. Khusrau, who saw himself as the son of the Byzantine emperor,¹⁹⁴ made use of the subsequent period to consolidate his rule and restock the state treasury.

¹⁸⁶ *Ibid.*, 3.7.

¹⁸⁷ *Ibid.*, 3.8.1.

¹⁸⁸ *Ibid.*, 4.1f. See Rubin, 'Nobility'.

¹⁸⁹ See S. Tyler Smith, 'Calendars and coronations: The literary and numismatic evidence for the accession of Khusrau II', *Byzantine and Modern Greek Studies*, 28 (2004).

¹⁹⁰ Theophylact Simocatta, *Historia*, 4.10.1–11.

¹⁹¹ *Ibid.*, 4.12.6.

¹⁹² *Ibid.*, 4.13.24, 14.8; Theophanes Confessor, *Chronicle*, 265.24–6.

¹⁹³ Theophylact Simocatta, *Historia*, 5.11f.

¹⁹⁴ *Ibid.*, 5.3.11; Theophanes Confessor, *Chronicle*, 266.13.

The Arab allies of the superpowers had already been explicitly included in the great peace treaty of 562. This illustrates their crucial role as 'buffer states' in the conflicts. However, when the Lakhmid ruler Nu'man III (r. 580–602) converted to Christianity his subjects had already turned towards the Nestorian creed; this initiated a break between the Lakhmids and the Sasanians.¹⁹⁵ Furthermore, Khusrāu II, in whose eyes Nu'man had apparently become too powerful, accused the latter of not having supported him adequately at the time of his flight from Wahram Chobīn. The Lakhmid ruler was lured to the Sasanian court, where he was assassinated.¹⁹⁶ The fall of Nu'man III ended the Lakhmid kingdom, and Khusrāu II entrusted an Arab of non Lakhmid descent with the duties the old dynasty had hitherto carried out. At the same time a Sasanian governor was appointed to work alongside the new ruler.¹⁹⁷

In the dispute between the murderer of Maurice, Phocas, and the alleged son of Maurice, Theodosius, Khusrāu sided with the latter. Although the war was formally directed against the usurper of the Byzantine throne,¹⁹⁸ Khusrāu was determined to seize the opportunity to push the borders of his empire further west. Within fifteen years almost the entire east of the Byzantine empire fell into Sasanian hands (the first and second phases of the war).¹⁹⁹ With the fall of Alexandria and Byzantium's loss of Egypt in 619, the Sasanian empire stood at the pinnacle of its power. The Sasanians planned the third and decisive phase of the war with resources of their own and those of foreign territories they had conquered. They planned to attack Anatolia from their positions on the Upper Euphrates and in Cilicia, and push on to Constantinople. At first everything proceeded according to plan, not least because they had arranged coordinated action with the Avars. The Persians attacked from the east (622) and advanced to conquer the entire northern edge of the Anatolian highland, while a vanguard sought to encircle the emperor and his army in Bithynia, while they were engaged in field exercises there. Although the emperor managed to break out and achieve some minor successes, he was soon called back to Constantinople, for the Avars had started attacking in the west. The Persian advance continued

195 G. Rothstein, *Die Dynastie der Lakhmiden in al-Ḥīra: Ein Versuch zur arabisch-persischen Geschichte zur Zeit der Sasaniden* (Berlin, 1899), pp. 139ff.; H. Preißler, 'Arabien zwischen Byzanz und Persien', in L. Rathmann et al. (eds.), *Geschichte der Araber*, 2nd edn, vol. I (Berlin, 1975), pp. 47–8.

196 T. Nöldeke, *Die von Guidi herausgegebene syrische Chronik: Übersetzt und kommentiert, Sitzungsberichte der Akademie der Wissenschaften zu Wien, Philosophisch-Historische Klasse* 128 (Vienna, 1893), pp. 13ff.

197 Rothstein, *Die Dynastie*, pp. 119–20.

198 Theophylact Simocatta, *Historia*, 8.15.7.

199 Al-Ṭabarī, *Ta'rikh*, series I, p. 1002.

the following year, when they reached the north western part of the Anatolian plateau and sacked Ancyra. Heraclius' hands were tied in the west, where he tried to come to an agreement with the Avars.

What was about to follow was one of the most astonishing turning points in the history of Antiquity. Heraclius managed to turn the demoralised Byzantine military once more into a powerful army with a strong fighting spirit – an army convinced that it was engaged in a holy war against the Persians. In the spring of 624 Heraclius attacked Transcaucasia, where he was to stay for almost two years and wreak as much havoc and destruction as possible. He outmanoeuvred three Persian armies (625), called the Christians of the north to his assistance, and tried to convince the western Turks to enter the war on the Byzantine side. He even survived the crisis of 626, when two Sasanian armies attacked Anatolia, and an Avar one besieged the capital. In 627 he returned to Transcaucasia. In the meantime the Turks had responded to his plea for assistance by occupying Albania and launching an attack on Iberia.

In 627 Heraclius met Yabghu Khan, the 'viceroy' of the Turkic empire, outside Tbilisi, probably with the intention of conferring about coordinated action between them. The emperor then moved southwards to the Zagros, protected by the presence of a large Turkic contingent. The Turks left for the north in October, and Heraclius undertook a surprising push forward into the south, through the mountains. He gained a decisive victory at Nineveh (12 December 627) and threatened Khusrau II in the latter's favourite palace at Dastgerd. The Sasanian king fled to Ctesiphon, while Heraclius took Dastgerd. However, he soon retired to his winter quarters, as an attack on the heavily fortified main residence of the Sasanian king did not promise to be successful.

There was no further military conflict between the two sides. Khusrau II was deposed in a palace coup in the night of 23–24 February 628. His son Kawad II succeeded to the throne, and immediately petitioned for peace. Although negotiations proved difficult, the Sasanian occupying troops finally withdrew from Byzantine territory in 629. The return of peace and the victory of a Christian empire over the Zoroastrian opponent was celebrated ceremonially on 21 March 630. Heraclius entered Jerusalem triumphantly, with the relics of the True Cross, which the Sasanians had plundered in 614, in his possession.

Ideology, war and diplomacy

From their very beginning, Sasanian rock reliefs showed jousting scenes (probably derived from Hellenistic Parthian models), which symbolically

referred to important historical decisions and turning points.²⁰⁰ Most probably, those big sized scenes of combat were originally designed for the mosaics and paintings of Sasanian palaces and then found their way into other genres of art. The fact that the Iranian heroic tradition also presents important historical and military decisions in the form of duels (as jousting or wrestling matches) seems to speak for a common root of the literary as well as iconographic conversion of such ordeal like situations.

It has long been known that Romans and Sasanians, in the context of their triumphal art, tended to use each other's visual imagery and ideological vocabulary.²⁰¹ Iran's superiority over Rome is stressed both in the Sasanian royal inscriptions and in the Iranian mythological tradition.²⁰² The Sasanians also used other media to give expression to their striving for superiority over Rome. Particularly famous are the scenes of triumph on Sasanian rock reliefs²⁰³ and the 'Shapur Cameo' of the Bibliothèque nationale in Paris, which was rightfully interpreted as a Roman piece of art on Sasanian instructions.²⁰⁴ However, the ways in which the Iranians tried to deal with Roman ideas of world domination and the Roman language of visual art have not yet been properly analysed.

The Romans and, later, the Byzantines were never dismissed from their subordinate position in Sasanian royal ideology, even if the Sasanians had to be content with the acknowledgement of the equal rank of both realms and dynasties in diplomatic contact. It also seems that the Iranian rulers of the fifth and sixth centuries, in similar vein to Shapur's pecuniary demands on Philip the Arab in 244, passed off the Roman payments, which were meant to support Sasanian endeavours to protect the borders against nomads or mountain tribes, as Byzantine tributes, although in reality they were parts of well balanced diplomatic treaties.²⁰⁵

Even if both the Sasanian and the Roman triumphal art leaves no doubt about the outcome of the respective duel portrayed,²⁰⁶ and even if the two great

200 See von Gall, *Das Reiterkampfbild*, p. 97 for the temporary takeover of Roman imagery.

201 Schneider, 'Orientalism'.

202 Z. Rubin, 'The Roman empire in the Res Gestae Divi Saporis: The Mediterranean world in Sasanian propaganda', in E. Dabrowa (ed.), *Ancient Iran and the Mediterranean world*, Electrum 2 (Crakow, 1998), pp. 181–2; J. Wiesehöfer, 'Rum as enemy of Iran', in E. Gruen (ed.), *Cultural borrowings and ethnic appropriations in Antiquity*, OrOcc 8 (Stuttgart, 2005).

203 Schneider, 'Orientalism'.

204 Von Gall, *Das Reiterkampfbild*, pp. 56–9.

205 Yarshater, 'Iranian national history', p. 410; Rubin, 'The Roman empire', pp. 178–9.

206 Very often the enemy is unseated or taken by the hand.

powers ideologically stressed their respective superiority,²⁰⁷ it is perfectly clear that both sides, in practice, had to recognise their equal rank and to get along with each other for better or for worse. Thus it is no surprise that the peace treaties of the Romans/Byzantines and the Sasanians were not only regarded as historically most relevant events, but were also arranged in a special ceremonial way.²⁰⁸ This becomes particularly clear in Menander Protector's report on the peace treaty of 562 between Justinian and Khusrau I.²⁰⁹ The author, a man with a profound rhetorical and legal education, and, as a member of the emperor Maurice's court, very familiar with Byzantine diplomatic customs, gives us an insight into all substantial aspects of the international law of his time.

In the preamble to the Sasanian document of ratification (in Menander's version) 'the divine, good, father of peace, ancient Chosroes [Khusrau], king of kings, fortunate, pious and beneficent, to whom the gods have given great fortune and a great kingdom, giant of giants, formed in the image of the gods'²¹⁰ calls his Roman opponent 'Justinian Caesar, our brother'.²¹¹ Even if the titulature given to Justinian is plainly shorter than his own, the form of address ('brother') nevertheless shows clearly that the 'king who reigns over kings' and the 'victor of wars' grants the 'lord of all things and of the world'²¹²

207 The Sasanians did not programmatically invent and systematically cultivate a preoccupation with the Occident as the Romans did with the Orient, although Rum appears as one of the two deadly foes of Iran in the 'Iranian national history' (see below).

208 For the Romano Sasanian diplomatic encounters and peace treaties see K. Güterbock, *Byzanz und Persien in ihren diplomatisch völkerrechtlichen Beziehungen im Zeitalter Justinians* (Berlin, 1906); E. Winter, 'Legitimität als Herrschaftsprinzip: Kaiser und "König der Könige" im wechselseitigen Verkehr', in H. J. Drexhage and J. Sünskes (eds.), *Migratio et Commutatio: Studien zur Alten Geschichte und deren Nachleben. Th. Pekáry zum 60. Geburtstag am 13. September 1989 dargebracht von Freunden, Kollegen und Schülern* (St Katharinen, 1988); Winter, 'On the regulation'; Winter and Dignas, *Rom und das Perserreich*, pp. 141–81.

209 Menander Protector, *Historiae*, fr. 6.1.

210 For the titulature of the Sasanian kings see Huyse, 'Die sasanidische Königstitulatur'. Justinian normally used for himself a titulature which was still in use in the tenth century: 'the pious, the lucky, the renowned, the victorious, the triumphant, always the illustrious emperor' (*pius (eusebês), felix (eutychês), inclutus (endoxos), victor (nikêtês), triumphator (tropaiouchos), semper augustus (aie seabastos augoustos)*).

211 Totally different is the protocol of Khusrau II's letter, when he asks the emperor Maurice for help: 'Chosroes king of the Persians greets the most prudent king of the Romans, the beneficent, peaceful, masterful, lover of nobility and hater of tyranny, equitable, righteous, saviour of the injured, bountiful, forgiving' (Theophylact Simocatta, *Historia*, 4.11, trans. M. Whitby and M. Whitby as *The history of Theophylact Simocatta: An English translation with introduction* (Oxford, 1986), pp. 117f.).

212 These are the words in Ammianus Marcellinus, *Rerum gestarum libri*, 19.2.12 (*rex regibus imperans et bellorum victor dominus rerum et mundi*). Cf. 17.5.3: 'I, Sapor, king of kings, partner of the stars, brother of the sun and the moon, send my best regards to the Caesar Constantius, my brother' (*Rex regum Sapor, particeps siderum, frater Solis et*

equal rank in a diplomatic context. This is stressed particularly eloquently and colourfully in the words Byzantine authors such as Petrus Patricius and John Malalas put into the mouths of Sasanian kings and diplomats. There is mention of the two empires as two lights, which, 'like eyes, are adorned by each other's light',²¹³ or as two divinely planned centres of civilisation, which are called 'the moon of the west' and 'the sun of the east'.²¹⁴ Rome/Byzantium equally grants the same rank, the same dignity and the same autonomy to the eastern opponent, although, ideologically, the eastern *natio molestissima* ('most annoying nation') would actually deserve to be destroyed,²¹⁵ and although – or just because – Rome's claim to universal rule was in reality substantially limited by the existence of the Sasanian empire.

It was also usual for the two great powers to announce accessions to the throne by a special report, and to answer this report by a special message of greeting.²¹⁶ And it was also custom and practice to enquire of the foreign envoys after the well being of the royal 'brother' during a solemn audience,²¹⁷ and to exchange gifts.²¹⁸ The fulfilment of requests also served the keeping of good terms with the neighbours.²¹⁹

The Sasanians' view of the west²²⁰

We can only understand the neighbour's and opponent's special role in Iran in connection with the idea of Iran/Ēran and/or Ēranšahr ('Land/Realm of the

Lunae, Constantio Caesari fratri meo salutem plurimam dico), a formula which Constantius answers in the following way: 'I, Constantius, the victor on land and on the sea, always the illustrious Emperor, send my best regards to king Sapor, my brother' (*Victor terra marique Constantius semper Augustus fratri meo Saporī regi salutem plurimam dico*).

213 Petrus Patricius, *Fragmenta Historicorum Graecorum* (FHG), ed. C. Müller, vol. IV, Paris 1868, pp. 181–91, fr. 13.

214 John Malalas, *Chronographia*, 18.44 (p. 449).

215 Ammianus Marcellinus, *Rerum gestarum libri*, 23.5.19.

216 John Malalas, *Chronographia*, 18.34, 36 (p. 445, 448); Menander Protector *Historiae*, fr. 9.1; Theophylact Simocatta, *Historia*, 3.12; Theophanes Confessor, *Chronicle*, 250; *Chronicon Paschale*, 735. Such an announcement is omitted by Hormezd IV (Theophylact Simocatta, *Historia*, 3.17), whereas Khusrau II does not accept the letter of the murderer of his patron Maurice, Phocas (*ibid.*, 8.15).

217 Petrus Patricius *apud* Constantine Porphyrogenitus, *De caeremoniis aulae Byzantinae*, 1.89.

218 *Ibid.*, 1.89, 90; Procopius, *De bello Persico*, 1.24; gifts of the Augusta to the Persian queen: John Malalas, *Chronographia*, 18.61 (p. 467).

219 Thus, Justinian granted Khusrau I his wish and allowed the Neoplatonic philosophers, who had come to the Sasanian court at Ctesiphon, to return (Hartmann, 'Geist im Exil'); he also sent the physician Tribunos, whom Khusrau had asked for, to Persia for one year to cure the Sasanian king (Procopius, *De bello Gothico*, 4.10).

220 See Wiesehöfer, 'Rum'.

Aryans/Iranians').²²¹ Although the Achaemenids had attached ethnic qualities to the word *ariya* which forms the basis of Middle Persian *er* (DNa), 'Iran' as an ethnic, religious and political term was first coined in early Sasanian times. It disappeared with the fall of the dynasty, and became a historicising term for its realm, only to be revived as a political concept in the time of the Ilkhanids and under the Pahlavi dynasty. It is obvious that the Sasanians, apart from alleged ethnic common ground, used this term to emphasise to their subjects both the experiences shared in the time of the Parthian overlords and the common cultural traditions of Iran. Those rather integrative factors were probably meant not least to prevent dangerous regional particularism within Iran and to legitimise the newly established rule. It has rightly been stated that the creation of a special Iranian identity is to be seen in connection with similar tendencies towards regionalism in the Roman empire.²²² That this Sasanian concept of a connection between 'Iranism' and 'Mazdaism' and of an ethnically, culturally and religiously self contained Iranian community depended exclusively on royal ideology has correctly been postulated with reference to the numerous ethno linguistic and religious minorities in the Sasanian empire, not least in its most fertile regions.²²³

Within the Sasanian concept of Iran, a special role is assigned to the royal 'ancestors' (Mpl *niyagan*, Gkl *pappoi*) and 'forebears' (Mpl *ahenagan*, Gkl *progonoi*) and their territories, as well as to Zoroastrian religious tradition and practice.²²⁴ Specific means and institutions were meant to strengthen the idea that the ruler and his Iranian subjects shared the same destiny: symbolic references (e.g., an era, starting from 205/6); an iconography, tightly connected with the royal inscriptions and also underlining the kings' close relationship to the gods; special rites and practices (such as the lighting of royal and other fires, as well as donations for the welfare of the souls of deceased and living persons); and finally, important memorial places and monuments (as, for instance, the sacred shrine of Anahita at Iṣṭakhr, the big fire temples, the cliff of Naqsh-e Rostam, and the towers there and at Paikuli). The process of the creation of a specific identity both for members of the Sasanian dynasty and for their subjects in (south west) Iran had inclusive as well as exclusive features. Excluded from this close relationship were the

221 Gnoli, *The idea of Iran*; G. Gnoli, *Iran als religiöser Begriff im Mazdaismus*, Rheinisch Westfälische Akademie der Wissenschaften, Vorträge G 320 (Opladen, 1993).

222 Gnoli, *Iran als religiöser Begriff*, p. 6.

223 R. Gyselen (personal communication).

224 For the scholarly debate on the identification of those 'ancestors' and 'forebears' see note 93.

inhabitants of Aneran, i.e. the areas that Shapur I and his successors had been able to conquer (temporarily), and all non subjects of the 'King of kings' (in the *Res Gestae Divi Saporis* (ŠKZ) primarily the subjects of Rome). The term 'Iran' of Iranian tradition was not applied to the home countries of those people, and, ideologically, the people of Aneran remained second class inhabitants of the empire.²²⁵ In contrast, the members of the Parthian clans, who had changed sides in time or had been allowed to remain in office by the new lords for political reasons, were still considered worthy members of the 'imagined community' of Iranians. Possibly, terms such as Ēran and Aneran already had religious connotations, inasmuch as the first was considered to be under divine protection (domain of the *yazdan*), and the latter to be a place of idols (*dewan*).²²⁶ However, such a distinct, quasi 'nationalistic' Sasanian Iranism was a big drawback. It stood in the way of developing an integrative imperial ideology, which – as is shown by the Achaemenid royal inscriptions and reliefs – presents the ruler and all his subjects as a community of interests, chosen, fostered and legitimised by the gods. On the one hand, it is no wonder that the official Sasanian 'Iranism', also to be observed in Zoroastrian literature, was able to establish a kind of 'Iranian' identity (with which a universal religion such as Manichaeism had to cope and because of which it failed in the long run). On the other hand, this 'Iranism', which – not least in times of crisis – succeeded in strengthening thoughts of a clear distinction between friend and foe, stood in the way of a dissemination of an 'Iranian' (e.g. Zoroastrian) body of thought. Shapur's temporary interest in Mani's universal message, hinted at in Manichaean literature,²²⁷ might have been an expression of royal discontent with the lack of integrative power of Zoroastrianism on an imperial level.

The epigraphic and archaeological testimony obviously never determined the Iranians' views of their neighbours and enemies in the west. This is evident in the fact that soon after the fall of the Sasanian empire in the seventh century, the rock reliefs were no longer regarded as the works of Shapur I and his successors by the inhabitants of Fars, but were rather connected with characters of the Iranian legendary cycles such as Rustam.

225 For the term Aneran see Huyse, *Die dreisprachige Inschrift*, vol. II, pp. 10–11.

226 *Ibid.*, p. 11.

227 M. Hutter, *Manis kosmogonische Šabuhrağan Texte: Edition, Kommentar und literargeschichtliche Einordnung der manichäisch mittelpersischen Handschriften M 98/99 I und M 7980–7985*, *Studies in Oriental Religion* 21 (Wiesbaden, 1992), pp. 155–60.

The 'Book of Lords',²²⁸ mentioned above, bundled together into a kind of semi official Sasanian version the traditions of world and, more particularly, Iranian history. These had probably circulated previously in an independent fashion with each region of Iran undoubtedly possessing regionally specific versions of Iranian history, partly differing from those of other regions. Some of them, perhaps of an eastern Iranian provenance, must have been so popular that, in the end, they were able to displace or absorb the historical and partly legendary tradition of south west Iran – a fact that is suggested by Sasanian ignorance of their Achaemenid forerunners. As it is out of the question that the Arsacids would have consciously wanted to erase the Achaemenids from the tradition, we should explain the loss of memory of the names of Cyrus and his successors as the result of a gradual process resulting from the oral character of Iranian tradition with its fascinating and entertaining traits, attributable in part perhaps to eastern traditions of historical interpretation that place particular emphasis on the gods' saving grace. As is well known, oral tradition is characterised by (a) the special attention given to the beginning and the contemporary end of history, while only little information is made available for the so called floating gap, which bridges long periods of time; (b) the filling out of existing story patterns with new historical or mythical figures and themes. This subordinating of historical characters, events and details to the framework material, apart from other factors of deformation or transformation in oral cultures, might explain why popular knowledge of Cyrus and his successors faded or took another shape.²²⁹ The Parthians, who had epic and poetic material performed at their courts,²³⁰ are said to have helped in this process by collecting and saving the religious tradition of Iran. King Walakhsh (Vologeses I?) might be mentioned as an example.²³¹ Even if,

228 The following statements rely heavily on the observations of Yarshater, 'Iranian national history'. See also P. Huyse, 'Histoire orale et écrite en Iran ancien entre mémoire et oubli' (unpublished thesis). Huyse postulates a first compilation of 'historical' material in the time of Khusrau I. Khusrau II would then have been responsible for important additions to and revisions of that material (see Shahbazi, 'On the Xth aday namag', p. 214). There are even later additions in the time of Yazdgerd III (T. Nöldeke, *Das iranische Nationalepos* (Straßburg, 1896), pp. 12–13, §13). The first Sasanian attempt to collect all the legendary material circulating in Iran is probably to be dated to the early fifth century, when the Sasanian kings radically changed their royal titulature, not least by introducing the term 'Kayanid' into it. The first real Kayanid name of a Sasanian king is that of Kavad I (488–96, 499–531); see Huyse, 'Histoire orale'.

229 For the rules of oral tradition and the characteristics of Iranian oral tradition see Huyse, 'Histoire orale'.

230 See M. Boyce, 'The Parthian *gosan* and Iranian minstrel tradition', *JRAS* (1957); M. Boyce, 'Gosan', *Elr*, vol. XI, pp. 167–70 with the remarks of Huyse, 'Histoire orale'.

231 DkM 412.5–11.

as has rightly been stressed, the eastern Iranian epic cycles made up the core of the national saga and national history of Iran in (early) Sasanian times, this does not mean that the inhabitants of Fars ('Kings', Magi etc.) did not contribute to the Sasanian version(s) of the 'national history'.²³² For example, their version of the Avestan tradition kept its formative strength in south west Iran during Parthian rule and was finally canonised under the Sasanians. We find proof of this (partly older) south west Iranian orientation of the Avesta in the throne names Ardakhshīr, Darayan and Manchihr of Parthian Fars, and probably even in the Achaemenid use of Avestan names and concepts for their own needs.²³³ This special 'Persian' development is also exemplified by the Sasanians' recollection of Achaemenid 'Aryanism', the affinity of Sasanian royal ideology for its Achaemenid counterpart, and the thematic and linguistic parallels in the Achaemenid and Sasanian royal inscriptions. A feeling for a special 'Persian', i.e. south west Iranian, history and tradition (which differed from the Parthian version) was probably kept alive from late Achaemenid times through the time of the Frataraka and the sub Parthian kings into the early Sasanian period with the help of the 'holy places' at Naqsh-e Rostam, Persepolis and elsewhere, including their iconography. When Shapur I 'worships' his 'forebears' (who, like his 'father' and his 'ancestors', have a special connection to Fars), when he derives his own claims from their achievements and possession rights, when he stresses the special position of Ēranšahr in his empire, when a Sasanian prince as king of the Sacas prays for the builder of Persepolis at the beginning of the fourth century (the names of the place and the builder are, however, unknown to him), all these acts stand in causal connection to the impressive inheritance of the 'ancestors' and 'forebears'.²³⁴ This can only mean that the Sasanians saw themselves as proud heirs to a glorious Iranian past of either a Kayanid legendary or an uncertain 'historical' mould.

As already mentioned, 'Iranian national history' is shaped by a succession of dynasties. Among the mythical world rulers of the Pishdadian line, King Fredon is most important for us. He not only defeated the monster Dahak, but also divided the world among his three sons Salm, Tur and Ēraj. This touched off the disastrous strife between the Iranian kings (heirs of Ēraj, who were called Kayanids) and the descendants of Salm and Tur, both of whom are

232 Yarshater, 'Iranian national history', pp. 390-1.

233 J. Kellens, 'L'idéologie religieuse des inscriptions achéménides', *JA*, 290 (2002). Huyse, 'Histoire orale', tries to show that the Kayanid legendary cycle(s) already played an important role in Achaemenid Fars (and even among the Medes).

234 Wiesehöfer, 'Gebete'.

at home in the east and possess Iranian names. The Kayanid epic tradition shows a strong eastern Iranian legendary and religious slant, although some scholars would like to see in it allusions to western Iranian historical characters such as Cyrus the Great. The end of the third and last phase of Kayanid rule is heralded by the deeds of the conqueror Alexander of Rum. It has long been known that two different Alexander traditions exist in Iran, the first of which, greatly influenced by the ancient 'Alexander Romance', presents Alexander as a Persian prince and mighty king, a Muslim sage or even a prophet, whereas the second one characterises him as evil incarnate, the 'devil's' henchman and a person who, like no one else, brought mischief and destruction to Ērānšahr. Thus, the first tradition, found in the works of Muslim poets, writers and historiographers, stands in sharp contrast to the second, Middle Persian, one, found in religious and didactic literature (including the 'Book of Lords'). Here, Alexander kills the last Kayanid king, Dara, or plans his death; apart from that, the 'Roman' is said to have killed many members of the Iranian aristocracy and many priests and scholars, to have destroyed fire temples or to have extinguished Holy Fires, to have razed cities and fortresses to the ground, to have robbed, burned or scattered the Holy Scriptures, and to have divided the empire into realms of powerless and quarrelling petty kings. The traditions competed with each other in late Sasanian and early Islamic times, after a version of the 'Alexander Romance' had been translated into Middle Persian. It seems as if the positive view of Alexander enjoyed particular popularity in aristocratic circles.²³⁵

The Arsacids probably followed the Kayanids in the Parthian version(s) of the 'national history'. After consciously displacing their predecessors from it in late Sasanian times, the Sasanians took their place, systematically revising the entire tradition and presenting themselves as Iranian kings par excellence, as if the history of Iran had culminated in their rule by law of nature. It is no wonder that for many Muslim authors the Arsacid era was the result of Alexander's misdeeds and a time of instability and chaos, when the numerous rivalries of petty kings jeopardised their predecessors' successes and afforded an opportunity to Iran's enemies to take advantage of its treasures. From the point of view of the late Sasanian compilers of the 'national history', the outstanding qualities of King Ardashīr were needed to restore Iran's former greatness and power. The extent to which the conflicts between Khusrau I and

²³⁵ J. Wiesehöfer, 'Zum Nachleben von Achaimeniden und Alexander in Iran', in H. Sancisi Weerdenburg, A. Kuhrt and M. C. Root (eds.), *Achaemenid history VIII: Continuity and change* (Leiden, 1994).

his successors, on the one side, and the high nobility, on the other, especially in the fight for the throne between Khusrau II and Wahram Chobīn, have been responsible for the positive image of the founder of the Sasanian empire and the belittling of his Arsacid predecessor, has already been made clear.²³⁶ That the Sasanian view of the Parthians must originally have been more favourable is suggested not only by the historically loyal Parthian clans of early Sasanian times, but also by the remains of a favourable assessment of the Arsacids in Muslim tradition. For example, Arsacid kings are genealogically affiliated to the Kayanid dynasty, and some of them are said to have been concerned about the promotion of scholarship, culture and religion.²³⁷

As far as Iran's enemies are concerned, 'Iranian national history' was subject to particularly flagrant changes and tendencies to updating in Parthian and Sasanian times. Whereas under the Arsacids, the eastern Iranian portion of the legendary material increased and displaced western Iranian tradition, there was a systematic adjustment of the tradition to the needs of the new Sasanian dynasty. As for the emphasis on the special position of Iran in world history, both dynasties introduced blatant new trends that affected the role of their neighbours in the west as well. Thus, in the long run, the sons of Fredon became the 'progenitors' of the royal dynasties of Iran, and of Turan and Rum, the foreign arch enemies of Iran. The early Sasanians referred to the legendary and the historical Parthian opposition to Rum, as can be seen from their inscriptions and reliefs mentioned above. This was probably because they regarded south western Iran as their home and the Romans as their worst enemies. We cannot determine how much historical information entered the 'national history' in this period, since the late Sasanian version of this tradition has survived almost alone. However, in the light of the character of this tradition, there is much to suggest that (as in Parthian times) the history of events gave way very early to the didactic and entertaining parts of the tradition, not only during the fourth/fifth²³⁸ or even the sixth/seventh centuries. This follows from the disregard of the historically highly relevant Armenian question, from the rather casual treatment of the problem of social or religious minorities, and from absence of reference to the fights for the throne at the end of the third century.²³⁹ It is hard to believe that only the Sasanian compilers in the time of Khusrau I and his successors wiped out such

236 Yarshater, 'Iranian national history', p. 474.

237 Ibid., pp. 475–6.

238 Daryaei, 'National history'; Daryaei, 'Memory and history'; Shahbazi, 'Early Sasanians' claim'.

239 Yarshater, 'Iranian national history', p. 477.

historical information, since the 'national history' does not even provide any information about the western campaigns of Khusrau II.²⁴⁰

Although there is more information about royal affairs, from the reign of Yazdgerd I onwards, we cannot speak of a real history of events, which normally analyses the motives of the people involved or the general political situation. Details of foreign, administrative or military affairs are only mentioned if they are of an entertaining kind or possess a narrative quality. The anecdotes that take centre stage are those that depict court life: the coronations of kings, their inaugural speeches, royal banquets, processions and merriments, as well as hunts and gift exchange, diplomatic contacts and military parades. Great victories of Iranian kings over their enemies in the west accompany those over the Turanians, and are partly presented as campaigns to avenge Alexander's misdeeds; non Iranian forebears of Iranian kings and heroes are increasingly assessed as an apparent genealogical defect. In other words, the account of Romano Sasanian relations in the 'Book of Lords' and its oral forerunners did not aim at determining the exact reasons for the conflicts between Iran and Rome. Where allusions to historical events are discernible at all and events and characters are not confused and mixed up, everything is determined by the effort to make Rum appear as the arch enemy of Iran and to be able to tell entertaining and didactic stories about the encounters between east and west. A good example of this is the account of the life of the famous Sasanian king Shapur II in Firdawsī's *Shahnameh*. This biography is nothing more than a description of his (unhistorical) rescue from Roman captivity with the help of a pretty young maiden of Iranian descent, and of his punitive Arabian war and two campaigns against the Romans, which prove to be a mixture of the wars of his time and those of the time of Shapur I. It is also in the reign of Shapur II that Mani, coming from China, is said to have been killed.

Initially unwilling to make themselves stand out at the cost of their royal Parthian predecessors, the new kings, in the course of time and in collaboration with the Zoroastrian clergy, gave the 'national history' a special Sasanian touch. They did so especially in the second half of their reign, and then with obviously anti Parthian intentions. Rum as a metaphor for their neighbours and the historical as well as contemporary enemies in the west now included the Byzantines. As with the Romans, we do not get much reliable historical

240 The question remains, however, whether the early Sasanians' claim to legitimisation already harked back to the Kayanids, since any allusion to the dynasty's Kayanid origin is absent in Narseh's Paikuli inscription and Kayanid names only enter royal nomenclature in the late fifth century.

information about them. The special character of the Sasanian view of history becomes particularly obvious through episodes that are related to Byzantium, but are anachronistically moved back to the time of the Kayanids.

Thus, Kai Kawus is said to have dispatched an envoy to the Kaisar, the young Gushtasp to have made a journey to Rum and to have married a Byzantine princess.²⁴¹ However, the late Sasanian revision of the 'national history' led to two remarkable changes, as far as the enemies of Iran are concerned: on the one hand, probably as a result of the disastrous invasions of Hephthalites and Turks, the role of Turan became more important than that of Rum (finally leading to an identification of Turanians and Turks). On the other hand, within secular tradition, the pseudo callisthenic Alexander in Iranian shape supplemented the Alexander as destroyer of Iranian greatness; he thus became a son of Dara and the daughter of the king of Rum.

In view of the character and the attractiveness of the 'national history', it is no wonder that an early Islamic historian of Iranian descent such as al Ṭabarī, who had been interested in writing a Muslim account of pre Islamic Iranian history within the framework of universal history, thereby stressing God's saving grace, had great difficulty extracting historical facts from the mythical, legendary and anecdotal material of the 'Book of Lords' and from other similar Sasanian sources. His world history from the early Muslims' point of view gives us information both about Muḥammad's historical forerunners and about the predecessors of the political leaders of the Islamic world. To accomplish this, it neither had to break with anti Iranian taboos, as was postulated until recently, nor did it have to construct a national identity with an anti Arabian or even anti Islamic slant. The same applies to Firdawsī's epoch making *Shahnameh*. Like al Ṭabarī relying on the late Sasanian view of history, the poet used the Iranian and non Iranian dynasts' and peoples' special liking for Sasanian (especially royal) subjects, as well as the linguistic potential of the already Islamised New Persian language supremely well. He thereby helped to turn the pre Islamic legendary sagas into a piece of world literature. It is the role of Alexander and the emperors of Rum as neighbours and opponents of the mighty kings of Iran in the *Shahnameh* and in other Persian epics and poems that has determined the Iranian view of the Graeco Roman west in antiquity up to the present day.

241 Yarshater, 'Iranian national history', p. 403.

Genealogical table of the Sasanians

	Date	Name	Indigenous names	Genealogy	Commentary
1	224 41/2 CE	Artaxerxes (Artaxares) [Ardashīr] I	MP Ardašīr	son of Pābag	founder of the Sasanian empire
2	239/40 70/2	Sapor(es) [Shāpūr] I	MP Šābuhr	son of 1	until 241/2 co regent of 1
3	270/2 3	Hormisdas (Hormizdes) [Hormezd] I	MP Hormezd Ardašīr	son of 2	
4	273 6	Wahram (Va(ra)ranes) [Wahrām] I	MP Wahrām	son of 2	
5	276 93	Wahram (Va(ra)ranes) [Wahrām] II	MP Wahrām	son of 4	
6	293	Wahram (Va(ra)ranes) [Wahrām] III	MP Wahrām	son of 5	dispute for the throne with 7
7	293 302	Narses [Narseh]	MP Narseh	son of 2	dispute for the throne with 6
8	302 9	Hormisdas [Hormezd] II	MP Hormezd	son of 7	
9	309 79	Sapor(es) [Shāpūr] II	MP Šābuhr	son of 8	
10	379 83	Artaxerxes (Artaxares) [Ardashīr] II	MP Ardašīr	son (brother?) of 9	
11	383 8	Sapor(es) [Shāpūr] III	MP Šābuhr	son of 9	
12	388 99	Wahram (Va(ra)ranes) [Wahrām] IV	MP Wahrām	son (brother?) of 11	
13	399 421	Yazdgird I (Isdigerdes) [Yazdgerd]	MP Yazdgerd	son of 12	
14	421 39	Wahram (Va(ra)ranes) [Wahrām] V	MP Wahrām (Gōr)	son of 13	
15	439 457	Yazdgird II (Isdigerdes) [Yazdgerd]	MP Yazdgerd	son of 14	

Genealogical table of the Sasanians (cont.)

	Date	Name	Indigenous names	Genealogy	Commentary
16	457 9	Hormisdas [Hormezd] III	MP Hormezd	son of 15	
17	459 84	Peroz(es) [Fīrūz]	MP Pērōz	son of 15; brother of 16	
18	484 8	Balas (Blases)	MP Walaxš	son of 15; brother of 17	
19	488 96; 499 53 ^I	Kabades [Kawād] I	MP Kawād	son of 17	
20	496 8	Zamasphes (Zames)	MP Zamāsp	son of 17; brother of 19	
21	531 79	Chosroes [Khusrau] I	MP Husraw (Xusrō)	son of 19	epithet Anōšīrwān
22	579 90	Hormisdas [Hormezd] IV	MP Hormezd	son of 21	
23	590 628	Chosroes [Khusrau] II	MP Husraw (Xusrō)	son of 22	epithet Abarwēz
24	590 I	Wahram (Va(ra)ranes) [Wahrām] VI [Chōbin]	MP Wahrām Čōbin	rival claimant of 23	
25	628	Kabades [Kawād] II	MP Kawād	son of 23	
26	628 30	Artaxerxes (Artaxares) [Ardashīr] III	MP Ardašīr	son of 25	
27	630	Schahrbaraz [Shahrbarāz]	MP Šahrwarāz		
28	630	Chosroes [Khusrau] III	MP Husraw (Xusrō)	nephew of 23	
29	630 I	Boran [Pūrān]	MP Pūrān	daughter of 23	queen
30	631	Azarmigdukht	MP Azarmigdux	daughter of 23; sister of 29	queen
31	631 2	Hormisdas [Hormezd] V	MP Hormezd	grandson of 23	
32	631 3	Chosroes [Khusrau] IV	MP Husraw (Xusrō)		
33	633 51	Yazdgird III (Isdigerdes) [Yazdgerd]	MP Yazdgerd	grandson of 23	

Pre-Islamic Arabia

MICHAEL LECKER

Tribal historiography

The literary sources in Arabic dealing with pre Islamic Arabia are copious, but rarely give direct answers to questions which are of interest to modern research. Still, the following had to be based on these sources since Arabian archaeology is only emerging; one hopes that significant Arabian pre Islamic sites incur no damage before they are excavated.

Arabian society was tribal and included nomadic, semi nomadic and settled populations. The settled populations had genealogies similar to those of the nomads and semi nomads, identifying them as either 'northern' or 'southern' through the identity of their presumed eponyms. Not only did genealogy define the individual tribe, it also recorded its links with other tribes within families of tribes or tribal federations, each including several or many tribes. Muḥammad's tribe, Quraysh, for example, was part of the Kinana, and hence the other tribes of the Kinana were its closest relatives. The settled populations, which probably included more people than the nomadic and the semi nomadic populations put together, do not receive a proportionate share in the literary sources because the limelights are typically on the nomads, more precisely on their military activities, no matter how insignificant. Tribal informants focused on the military activities since the performance of town dwellers in the realms of trade and agriculture were less spectacular, and hence less contributive to tribal solidarity.

After the Islamic conquests the tribes underwent significant changes, but they preserved their genealogy and their rich oral heritage that was inseparable from the genealogy. The amount of the materials that were transmitted and preserved was naturally affected by the size and political influence of the individual tribes. It stands to reason, however, that tribes that lived in or around the main centres of intellectual endeavour, such as Baṣra and Kufa, stood a better chance of having their heritage recorded when oral accounts

became written literary history. Regarding the time of Muḥammad, the coverage of individual tribes was uneven since it was also affected by their role at that time. Tribes such as Ghifar, Muzayna, Juhayna and others roaming around Mecca and Medina (pre Islamic Yathrib)¹ are better known to us than much stronger tribes such as Asad and Ghatafan, simply because the former played a more central role in Muḥammad's history.

The attention given in the literature to the military activities of the nomads led to an unrealistic and unbalanced perception of pre Islamic Arabian society. While Mecca and Medina are described in much detail, many other settlements that were perhaps larger, wealthier and more populous than these two towns, such as Ḥajr (present day Riyadh), which was the central settlement in the al Yamama area, are hardly taken into account in scholarly descriptions of pre Islamic Arabia.

Much of the source material regarding Arabia goes back to tribal genealogists, each of whom specialised in a specific tribe or group of tribes. The tribal genealogists also mastered the tribal history and poetry, because they were both extensions of the genealogical information. Let us take for example the Taghlib. Al Akhzar ibn Suḥayma was an early Taghlibī genealogist who transmitted part of the information on his tribe later incorporated in the genealogy books. Between the early genealogists and the philologists of the second/eighth century there were intermediaries who usually remained unidentified. But expertise in Taghlibī genealogy and tribal history was not an exclusive Taghlibī domain. The most famous genealogist and philologist of early Islam, Ibn al Kalbī (d. 204/819), learned about Taghlibī matters from Abu Ra'shan Khirash ibn Isma'īl of the 'Ijl tribe who compiled a monograph about the tribal federation of Rabī'a that included both his own tribe, the 'Ijl and the Taghlib. Khirash also reported about a battle that took place in early Islam (the battle of Šiffīn, 37/657), which indicates that his scholarly interests covered both the pre and early Islamic periods. Indeed, tribal genealogists, and in their wake Muslim philologists whose scope was much wider, considered the pre and early Islamic history of the tribes as an uninterrupted whole.

The members of each tribe shared a notion of common descent from the same eponym. The eponyms in their turn were interconnected by an intricate network of family links that defined the tribal system across Arabia; tribal alliances were often concluded along genealogical lines. From time to time genealogy fluctuated according to changing military, political and ecological

¹ Both the tribes and their territories are referred to by the Arabic term *badiya*; one speaks of the *badiya* of such and such settlement.

circumstances. There were prestigious and famous lineages beside less prestigious ones. For example, detailed information about the Banu Zurara, a leading family of the Tamīm, is included in a dialogue between a member of this family and an old man who lived in the south eastern corner of Arabia but nevertheless had an impressive command of the intricacies of Tamīmī genealogy.²

By definition, tribal informants were biased and acted in an atmosphere of intertribal competition or even hostility. The formal state of truce that followed the tribes' conversion to Islam generally stopped their resort to violence. But polemics and friction, especially in the garrison cities of Iraq, were often intensified.


The bias of tribal informants must be taken into account and lead to greater prudence in using their reports. It can be demonstrated by the intertribal polemics surrounding the Arab bow of Tamīm's illustrious pre Islamic leader Ḥajib ibn Zurara, which holds a place of honour in Tamīm's pre Islamic history. During a severe drought Ḥajib asked for Khusrau's permission to graze his tribe's herds on the fringes of the sown land in south western Iraq. As a guarantee of good conduct Ḥajib pledged his bow, an unsophisticated item which nonetheless acquired great value through the eminence and authority of its owner. The Tamīm were very proud of this pledge, which showed the Sasanian emperor adopting their tribal values. Tamīm's adversaries in their turn attempted to belittle the importance of the gesture. 'Had they not been in my opinion of less value than the bow, I would not have taken it,' the emperor is made to say,³ as if explaining why he did not take Tamīmī hostages instead of a worthless bow. Other anti Tamīmī informants downgraded the authority with whom Ḥajib had negotiated. One version mentions Iyas ibn Qabīṣa al Ṭa'ī who was 'Khusrau's governor in charge of Ḥīra and the Arabs in its vicinity'; while other versions mention 'the head of the *asawira*, or heavy cavalry, charged with guarding the border between the Arabs and the Persians'⁴ and 'one of Khusrau's *marzbans*', or one of his (military, but also civil) governors.⁵ Obviously, tribal polemicists were at work here, and they were anything but innocent.

2 Abu l Baqa' Hibat Allah al Ḥillī, *al Manaqib al mazyadiyya*, ed. Ṣalīḥ Musa Daradika and Muḥammad 'Abd al Qadir Khriṣat, 2 vols. (Amman, 1404 AH [1984]), vol. I, p. 353. The late Ḥamad al Jasir wrote a monograph entitled *Bahila al qabīla l muftara 'alayha* (Riyadh, 1410 AH [1989]). Tribal genealogies remain a delicate matter in contemporary Saudi Arabia.

3 Abu Maṣṣur al Tha'alibī, *Thimar al qulub fī l muḍaf wa l mansub*, ed. Muḥammad Abu l Fadl Ibrāhīm (Cairo, 1965), p. 626.

4 Baladhurī, *Ansab al ashraf* (MS Süleymanīe Kütüphanesi, Reisülküttap Mustafa Efendi, 597, 598), 960a.

5 Abu l Baqa', *al Manaqib al mazyadiyya*, vol. I, p. 61.



1. The 'northern' and 'southern' Arabs

Yet another example of tribal bias relates to Muḥammad's tribe, Quraysh, which was considered 'northern' from the genealogical point of view; unsurprisingly, many sources reveal a pro Qurashī bias. Regarding the takeover of the Ka'ba in Mecca by Muḥammad's ancestor, Quṣayy, it is reported that a member of the Khuza'a tribe, which is usually considered a 'southern' tribe, sold the Ka'ba to Quṣayy. As usual, there are several versions regarding the mode of the takeover. However, the specific sale version that concerns us here did not come from an impartial party: it was reportedly promulgated by people fanatically hostile to the 'southern' tribes.⁶ The Khuza'a did not remain indifferent to this hostile description of a crucial chapter in their tribal history: the historian al Waqidi (d. 207/823) concludes a variant of this version with the statement that it was denied by the elders of the Khuza'a.⁷

6 Al Wazir al Maghribi, *al Inas fi 'ilm al ansab*, bound with Ibn Habib, *Mukhtalif al qaba'il wa mu'talifuha*, ed. Hamad al Jasir (Riyadh, 1980), p. 114: *fā yaqulu l muta'aṣṣibuna 'ala l Yamaniyya inna Quṣayyan sh tara l miftah*.

7 Taqi al Din Muḥammad ibn Ahmad al Fasi, *Shifa' al gharam bi akhbar al balad al haram*, ed. 'Umar 'Abd al Salam Tadmuri, 2 vols. (Beirut, 1985), vol. II, p. 87.

The nomadic and settled populations

Pre Islamic Arabia was not lawless or wild since an unwritten legal code controlled the life of its people. The law of talion and various security arrangements protected the lives of tribesmen outside their tribal territories.

The boundaries of these territories were generally acknowledged; tribesmen were supposed to know when they left the territories belonging to their tribes. But just like tribal genealogies, tribal boundaries fluctuated to reflect changing circumstances on the ground. A tribe's territory often included enclaves belonging to other tribes, which necessitated cooperation between the tribes involved; indeed, such enclaves could only survive where a clear legal code prevailed.

Although the number of literate people was limited even in the settlements, resort to written documents during the conclusion of alliances and transactions was common.⁸ The so called Constitution of Medina concluded by Muḥammad shortly after the *hijra* shows that complex legal documents and legal terminology in Arabic had existed in Arabia before the advent of Islam.

The genealogical variegation of the settled populations was probably greater than that of the nomads; indeed, one expects the population of a settlement to include several or many tribes. This was the case with the Christian tribal groups living in al Ḥīra, collectively referred to as al 'Ibad, that preserved their original tribal affiliations. Pre Islamic Medina provides further evidence of this: several towns in the Medina area were inhabited by *jumma*⁹, or groups from various tribes. 'The people of Zuhra' (*ahl Zuhra*) and 'the people of Zubala', to give but two examples of such towns, were described as *jumma*.⁹

The crucial relationship between the nomadic and settled populations across Arabia took many forms. Due to the size of their territory and their millstone like roaming around their grazing grounds and water places, the Tamīm were one of the so called 'millstones of the Arabs' (*arḥa* 'al 'arab').¹⁰

8 See M. Lecker, 'A pre Islamic endowment deed in Arabic regarding al Wahīda in the Ḥijaz', in M. Lecker, *People, tribes and society in Arabia around the time of Muḥammad* (Aldershot, 2005), no. IV.

9 'Alī ibn Aḥmad al Samhūdī, *Wafa' al wafa*, ed. Qasim al Samarra'i, 5 vols. (London and Jedda, 2001), vol. I, pp. 306-8.

10 Ibn Sa'īd al Andalusī, *Nashwat al ṭarab bi ta'rīkh jahiliyyat al 'arab*, ed. Naṣrat 'Abd al Raḥman, 2 vols. (Amman, 1982), vol. I, p. 415.

But even the powerful Tamīmīs were vulnerable to outside pressure since they had to rely on the settlements for part of their subsistence. Their massacre in the battle of Yawm al Mushaqqar could only take place because of their annual visit to Hajar on the coast of the Persian Gulf in order to receive their provisions.¹¹

Sometimes the nomads roaming around a certain settlement and the people of the settlement belonged to the same tribe. The third/ninth century geographer 'Arram al Sulamī's description of the stronghold of Suwariqiyya south east of Medina is generally true for pre Islamic times as well. He says that Suwariqiyya belonged to the Sulaym tribe alone and that each of the Sulamīs had a share in it. It had fields, dates and other kinds of fruit. The Sulamīs born in Suwariqiyya lived there, while the others were *badiya* and roamed around it, supplying food along the pilgrim roads as far as Ḍariyya seven days' journey from Suwariqiyya.¹² In other words, the Sulamī farmers of Suwariqiyya tilled the land and tended the irrigation systems, while the Sulamī nomads tended the beasts – above all the camels, which require extensive grazing grounds, and hence cannot be raised in significant numbers by farmers.

The biography of Muḥammad provides further evidence of the cooperation between the nomadic and settled populations. When the Jewish Naḍīr were expelled from Medina several years after the *hijra*, they hired hundreds of camels from a nomadic tribe roaming the vicinity of Medina; in normal circumstances these nomads would be transporting goods on behalf of the

11 Abu Ja'far Muḥammad ibn Jarīr al Ṭabarī, *Ta'rīkh al rusul wa l muluk*, ed. M. de Goeje *et al.*, 15 vols. in 3 series (Leiden, 1879–1901), series I, p. 985: 'This was close to the days of the *luqaṭ* [the picking up of dates from the stumps of the branches of palm trees after the cutting off of the dates]. The Tamīm used to go at that time to Hajar to get provisions and collect the dates left on the trees (*li l mīra wa l luqaṭ*).' Hajar was the largest date producing oasis in northern Arabia. On the connection between *al mīra wa l kayl*, or provisions, and obedience, see M. J. Kister, 'al Ḥīra: Some notes on its relations with Arabia', *Arabica*, 15 (1968), p. 168. The Bedouin who came to Yamama in the holy months (in which no warfare took place) in order to get provisions were called *al sawaqiṭ*: Abu 'Ubayda Ma'mar ibn al Muthanna, *al Dībaj*, ed. al Jarbu' and al 'Uthaymīn (Cairo, 1991), p. 53: *wa kana l sawaqiṭ min qaba'il shatta wa summu sawaqiṭ li annahum kanu ya'tuna l Yamama fī l ashhuri l ḥurum li l tamr wa l zar'*. At the time of the Prophet, when a certain Tamīmī came to Hajar in the holy month of Rajab in order to get provisions for his family (*yamīru ahlahu min Hajar*, i.e. as he used to do every year), his wife escaped from him; see e.g. Majd al Dīn Ibn al Athīr, *Manal al ṭalib fī sharḥ ṭīwal al ḡhara'ib*, ed. Maḥmud Muḥammad al Tanahī (Mecca, 1983), pp. 495–6.

12 'Arram al Sulamī, *Asma' jibal tihama*, in 'Abd al Salam Harun (ed.), *Nawadir al makhtūṭat*, 2nd edn, vol. II (Cairo, 1973), pp. 431–2; Yaqut al Ḥamawī, *Mu'jam al buldan* (Beirut, 1957), s.v. al Suwariqiyya.

Naḍīr. When the people of al Khaybar cut off the fruit of their palm trees, the nomads would arrive with their camels and carry it for them to the villages, one camel load after the other (*'urwa bi 'urwa*, literally: one loop of the camel load after the other). The nomads would sell the fruit, keeping for themselves half of the return.¹³

In the battlefield, nomads fought against other nomads, while settled people fought against other settled people. A verse by the Prophet's Companion, the poet Ḥassan ibn Thabit (who was of the Khazraj, a 'southern' tribe) demonstrates this:

Our settled men spare us the village dwellers,
while our bedouins spare us the bedouins of the Ma'add [i.e. the 'northern' tribes].¹⁴

During the *riḍḍa* wars that followed Muḥammad's death there was a dispute within the Muslim army in al Yamama between the settled (*ahl al qura*, including the *muhajirun* and the *anṣar*) and the nomads (*ahl al badiya/al bawadī*), with each accusing the other of cowardice. The settled people claimed that they knew better how to fight against their like, while the nomads said that the settled people were not good fighters and did not know what war was.¹⁵

The military aspect was dominant in the relationship between the settled and the nomads, as shown by accounts dealing with Muḥammad and his Companions. Friendly nomads were considered Muḥammad's *badiya*, with reference to their military role. Two tribes living near Medina once asked for Muḥammad's permission to build themselves a mosque in Medina similar to the mosques of other tribes. But he told them that his mosque was also their mosque, that they were his *badiya* while he was their *ḥaḍira*, or their settled counterpart (lit., 'people dwelling by waters'), and that they should provide him with succour when called upon to do so.¹⁶ The *hijra* of one of the *badiya* meant that he had to provide succour when called upon to do so (*an yujiba idha du'iya*) and to obey orders.¹⁷ A 'good' Bedouin differed from a 'bad' one in that the former provided military aid. When 'Ā'isha mentioned certain Bedouin, pejoratively calling them *a'rab*, Muḥammad corrected her: 'They

13 Samhūdī, *Wafa' al wafa*, vol. II, p. 35.

14 Ḥassan ibn Thabit, *Diwan*, ed. W. 'Arafat, 2 vols. (London, 1971), vol. I, p. 462, no. 287: *maḥaḍiruna yakfunana sakina l qura* [], *wa a'rabuna yakfunana man tama'dada*.

15 Al Ṭabarī, *Ta'rikh*, series I, pp. 1946, 1947.

16 Ibn Shabba, *Ta'rikh al madīna al munawwara*, ed. Fahīm Muḥammad Shaltut, 4 vols. (n.p. [1979]; repr. Beirut, 1990), vol. I, p. 78.

17 Abu 'Ubayd al Qasim ibn Sallam, *Kitab al amwal*, ed. Muḥammad Khalil Harras (Cairo, 1976), p. 280, no. 538.

are not *a'rab* but our *badiya*, while we are their *ḥaḍira*; when summoned, they provide us with succour.¹⁸ A fuller version of this tradition makes it clear that the commitment to give succour was reciprocal.¹⁹

With regard to the relationship between the nomadic and settled populations the question of ascendancy arises. The conquest of settlements by nomads²⁰ must have been rare because the latter did not wish to become farmers. But Muḥammad's history shows that in the major military confrontations of his time the initiative was in the hands of his Qurashī enemies, and later in those of Muḥammad himself; this suggests that the ascendancy belonged to the settled people. Let us take for example the military activity of the Sulaym at that time: first they fought with Quraysh against Muḥammad, then they fought with Muḥammad against Quraysh.²¹ In both cases the initiative was not theirs, and the same is true of the *riḍḍa* wars and the Conquests.

Closely linked to the question of ascendancy is that of the food allocations granted by the settled people to the nomads. At first glance they appear to indicate the ascendancy of the latter, but this was not the case. The people of Medina granted an annual share of their date produce to the strong tribal leader of the 'Āmir ibn Ṣa'ṣa'a, Abu Bara' 'Āmir ibn Malik (nicknamed *Mula'ib al Asinna*, or 'the one playing with spears'). He received from them annually a certain amount (*kayla*) of dates in return for a guarantee of safe conduct for the Medinans travelling in Najd.²² While protecting the lives and goods of these Medinans, the grant did not give the nomadic Banu 'Āmir ascendancy over the settled Medinans. This state of affairs remains unchanged when other terms are employed in similar contexts. In connection with the conquest (or rather temporary takeover) of Fadak by the nomadic Kalb around 570 CE it is reported that the Kalbī leader involved was entitled to a payment (*ja'ala*) from the people of Fadak. A *ja'ala* is a payment for services such as the return of a missing camel or a fugitive slave. The Tamīm transported Khusrau's caravan from al Yamama to the Yemen in return for a *ja'ala*, and the Kalb may well have earned their *ja'ala* for providing similar services. Also, the leader of the Fazara tribe, 'Uyayna ibn Ḥiṣn, received an annual

18 Ibid., no. 539.

19 Ibn Hajar al 'Asqalanī, *al Maṭalib al 'aliya bi zawa'id al masanid al thamaniya*, ed. Ḥabīb al Raḥman al A'zamī, 4 vols. (Kuwait, 1973), vol. IV, p. 144, no. 4185.

20 See M. J. Kister, 'On the wife of the goldsmith from Fadak and her progeny', *Le Muséon*, 92 (1979), pp. 321–30; repr. in M. J. Kister, *Society and religion from Jahiliyya to Islam* (Aldershot, 1990), no. V.

21 M. Lecker, *The Banu Sulaym: A contribution to the study of early Islam* (Jerusalem, 1989), pp. 136–7.

22 Ḥassan ibn Thabit, *Dīwan*, vol. II, p. 176. The term *kayla* is derived from the root *k.y.l.*, which denotes a measure of capacity. Cf. above, n. 475.

grant from the date produce of Medina. The term used in his case, *itawa*, sometimes means a tribute or tax. But here it designates an annual grant in kind to a nomadic leader, similar to those referred to by the terms *kayla* and *ja'ala*.

Medina and the other settlements could afford to grant part of their huge surplus of dates to the leaders of large nomadic tribes in order to secure their goodwill. The size of the grants must have varied according to the harvest and the changing political circumstances on the ground; but even where they amounted to a sizeable part of the annual produce they did not indicate nomadic ascendancy.

Idol worship

The pre Islamic Arabs were united by their love of poetry; many of them could probably appreciate the artistic value of the poems recited during major tribal gatherings, for example at the 'Ukaz fair, not far from Ṭa'if. In their daily life, however, they spoke a large number of dialects. Many of them acknowledged the sanctity of the Ka'ba in Mecca and made pilgrimage to it, travelling under the protection of the holy months during which all hostilities ceased. The Arab idol worshippers were polytheists, but they also believed in a High God called Allah whose house was in the Ka'ba and who had supremacy over their tribal deities.

Despite the diversity in the forms of idol worship, on the whole it was a common characteristic of pre Islamic Arabian society. In the centuries preceding the advent of Islam Christianity and Judaism were competing with each other for the hearts of the Yemenite polytheists. Medina had a large Jewish population, while al Yamama and eastern Arabia had a large Christian one. Christianity, and to a lesser extent Judaism, penetrated several nomadic tribes. The celebrated *ḥanīfs*, or ascetic seekers of true religion who abandoned idol worship, were probably few; moreover, the identification of some of them as *ḥanīfs* is questionable. Several early Tamīmī converts to Islam were former Zoroastrians. However, on the eve of Islam idol worship prevailed, with the prominent exception of the Yemen, considered by medieval Muslim historians to have been predominantly Jewish.

Idols of every shape and material were ubiquitous, and their worship showed no signs of decline. Many conversion stories regarding both former custodians of idols and ordinary worshippers specifically refer to a shift from idol worship to Islam.

The most common deity was the household idol. Several conversion accounts that prove the proliferation of household idols in Mecca are

associated with its conquest by Muḥammad (8/630). Al Waqidī adduces legendary accounts about the destruction of household idols. While the accounts aim at establishing the Islamic credentials of their protagonists, the background details are credible. One account has it that after the conquest of Mecca, Muḥammad's announcer ordered the destruction of every idol found in the houses. So whenever 'Ikrima ibn Abī Jahl (who belonged to the Qurashī branch Makhzum) heard of an idol in one of the houses of Quraysh, he went there in order to smash it; it is specifically stated in this context that every Qurashī in Mecca had an idol in his house. In al Waqidī's account we find that the announcer proclaimed that every idol had to be destroyed or burnt, and that it was forbidden to sell them (i.e. to sell wooden idols to be used as firewood). The informant himself saw the idols being carried around Mecca (i.e. by peddlers); the Bedouin used to buy them and take them to their tents. Every Qurashī, we are told, had an idol in his house. He stroked it whenever he entered or left the house to draw a blessing from it.

Yet another account in the same source has it that when Hind bint 'Utba (the mother of the future Umayyad caliph Mu'awiya) embraced Islam, she started striking an idol in her house with an adze, cutting oblong pieces from it.²³ She probably destroyed her wooden idol using the very tool with which it had been carved. The authors of the legendary accounts about 'Ikrima and Hind sought to emphasise the zeal of these new converts, but the background information is accurate: idols were found in all Meccan households.

In Medina, which was in many ways different from Mecca, idols were associated with various levels of the tribal organisation. A house idol made of wood was an obstacle for Abu Ṭalḥa of the Khazraj when he proposed to his future wife. She refused to marry 'one who worshipped a stone which did neither harm nor good and a piece of wood hewed for him by a carpenter'.²⁴ Several young Medinans from both of the dominant Arab tribes of Medina, the Aws and Khazraj, smashed the idols found among their fellow tribesmen. Here too household idols were the most common form of idol worship. We have some evidence about the attributes of one of the Medinan household idols. Before one of them was destroyed with an adze, it had to be brought down, which indicates that it had been placed in an elevated place such as a shelf; the same idol had a veil hung over it.

One level up from the household idols we find those belonging to noble men. Every nobleman in Medina owned an idol that had a name of its own.

23 Muḥammad ibn 'Umar al Waqidī, *Kitab al maghazi*, ed. Marsden Jones, 3 vols. (London, 1966), vol. II, pp. 870–1.

24 Ibn Sa'd, *al Ṭabaqat al kubra*, 8 vols. (Beirut, 1960–8), vol. VIII, pp. 425–6.

In addition, *baṭns*, or small tribal groups, had idols which, similarly, had names. The *baṭn*'s idol was placed in a sanctuary (*bayt*) and belonged to the whole *baṭn* (*li jama'ati l baṭn*). Sacrifices were offered to it. One level above the *baṭns* in the tribal system of Medina stood the major subdivisions of the Aws and Khazraj. Evidence has so far emerged regarding the idol of one such subdivision: the Banu Ḥarith ibn al Khazraj had an idol called Huzam that was placed in their *majlis*, or place of assembly, similarly called Huzam. One assumes that sacrifices were also offered to Huzam, since sacrifices were offered to the lower level idols of the *baṭns*. The idol al Khamīs was worshipped by the Khazraj,²⁵ while al Sa'ida, which was located on Mount Uhud north of Medina, was worshipped, among others, by the Azd – no doubt including the Aws and Khazraj, which belonged to the Azd.²⁶ At the top of the hierarchy of the idols worshipped by the Aws and Khazraj stood Manat. A descendant of Muḥammad's Companion Sa'd ibn 'Ubada reports that Sa'd's grandfather annually donated ten slaughter camels to Manat. Sa'd's father followed suit, and so did Sa'd himself before his conversion to Islam. Sa'd's son, Qays, donated the same number of camels to the Ka'ba.²⁷ The report is not concerned with idol worship as such but with generosity, prestige and tribal leadership. Sa'd's donation of sacrifice camels to Manat before his conversion to Islam shows that its cult continued to the very advent of Islam.

Household idols were ubiquitous in Medina, as in Mecca; noblemen, *baṭns* and major Aws and Khazraj subdivisions had idols. The Khazraj as a whole worshipped a special idol; the Aws and Khazraj were among the worshippers of another, and they were still worshipping their main idol, Manat, when Muḥammad appeared. All this does not indicate a decline in idol worship.

Expressing his opinion about the influence of monotheism on the Arabs before Islam, Ibn Ishāq says that 'it was merely superficial; the Arabs were illiterate and what they heard from Jews and Christians had no effect on their lives'. With regard to idol worship his statement is trustworthy.

Foreign powers

Pre Islamic Arabia and its tribes were not isolated from the great empires of Byzantium and Persia, with the latter probably playing a more significant

25 Al Ṭabarī, *Ta'rikh*, series I, p. 1085.

26 Muḥammad ibn Ḥabīb, *Kitab al muḥabbar*, ed. Ilse Lichtenstaedter (Hyderabad, 1361 [1942]; repr. Beirut, n.d.), pp. 316–17.

27 Ibn 'Abd al Barr, *al Isti'ab fī ma'rifat al aṣḥab*, ed. 'Alī Muḥammad al Bijawī, 4 vols. (Cairo, n.d.), vol. II, p. 595.

role. The Byzantine emperor, for example, is said to have been instrumental in the takeover of Mecca from the Khuza'a tribe by Muḥammad's ancestor Quṣayy.²⁸

The Byzantines and Sasanians conducted their Arabian affairs through their respective Arab buffer kingdoms, Ghassan and al Ḥīra. The king of al Ḥīra appointed governors to the frontiers from Iraq to Baḥrayn, each of whom ruled together with a Bedouin leader who was in fact his subordinate.²⁹

The same pattern was found in Oman: a treaty between the Sasanians and the Julanda family concluded in the second half of the sixth century stipulated that the Sasanians were entitled to station with the 'kings' of the Azd four thousand men including *marzbans* (military, but also civil, governors) and *asawira* (heavy cavalry), and an *'amil* or official. The Sasanians were stationed in the coastal regions, while the Azd were 'kings' in the mountains, in the deserts and in the other areas surrounding Oman.³⁰ In other words, authority was divided between the Arabs and the Sasanians along geographical lines.

In Baḥrayn there was an Arab governor, with a Sasanian superior. Al Mundhir ibn Sawa al Tamīmī is said to have been the governor of Baḥrayn. But the historian al Baladhurī (d. 279/892) draws a clear line at this point between Sasanians and Arabs: 'The land of Baḥrayn is part of the Persian kingdom and there were in it many Arabs from the tribes of 'Abd al Qays, Bakr ibn Wa'il and Tamīm living in its *badiya*. At the time of the Prophet, al Mundhir ibn Sawa was in charge of the Arabs living there on behalf of the Persians.'³¹ At the same time Baḥrayn had a Sasanian governor who was al Mundhir's superior, namely Sībukht, the *marzban* of Hajar.³² On the eve of Islam the Yemen was under direct Sasanian control.

Roughly until the middle of the sixth century Medina was controlled by a *marzban* whose seat was in al Zara on the coast of the Persian Gulf. The Jewish tribes Naḍir and Qurayza were 'kings', and exacted tribute from the Aws and

28 Ibn Qutayba, *al Ma'arif*, ed. Tharwat 'Ukasha (Cairo, 1969), pp. 640–1; quoted in M. J. Kister, 'Mecca and the tribes of Arabia', in M. Sharon (ed.), *Studies in Islamic history and civilization in honour of David Ayalon* (Jerusalem and Leiden, 1986), p. 50; repr. in Kister, *Society and religion*, no. II. Cf. 'Uthman ibn al Ḥuwayrith's attempt to gain control of Mecca on behalf of the Byzantine emperor: Kister, 'al Ḥīra', p. 154.

29 Abu l Baqa', *al Manaqib al mazyadiyya*, vol. II, p. 369.

30 J. C. Wilkinson, 'Arab Persian land relationships in late Sasanid Oman', in *Proceedings of the Seminar for Arabian Studies*, 3 (1973), pp. 41, 44–7.

31 Al Baladhurī, *Futuḥ*, ed. M. J. de Goeje (Leiden, 1863–6), p. 78: *wa kana 'ala l 'arab biha min qibali l furs*.

32 His name and title appear in connection with a letter allegedly sent by the Prophet to both al Mundhir ibn Sawa and Sībukht *marzban* Hajar, calling upon them to embrace Islam or pay the poll tax.

Khazraj on behalf of the Sasanians. In the last quarter of the sixth century the king of al Ḥīra, al Nu'man ibn al Mundhir, declared a member of the Khazraj, 'Amr ibn al Ḥnaba, king of Medina or of the Ḥijaz.³³ At that time the Jews were no longer 'kings' and tribute collectors, but tribute payers. 'Amr's appointment shows that Sasanian control in western Arabia continued in the latter half of the sixth century. Sasanian control there is also associated with al Nu'man ibn al Mundhir's father, al Mundhir III (c. 504–54): the Sasanian emperor Khusrau I Anushirwan (r. 531–79) made him king of the Arabs living between Oman, Bahrayn and al Yamama to al Ṭa'if and the rest of the Ḥijaz.³⁴

Caravan trade was often behind the cooperation between certain nomadic tribes and the Sasanians. The Sulaym and the Hawazin used to conclude pacts with the kings of al Ḥīra, transport the kings' merchandise and sell it for them at the fair at 'Ukaz, among others.³⁵ With regard to the above mentioned battle of Yawm al Mushaqqar it is reported that Khusrau's caravan, having travelled from Ctesiphon via al Ḥīra, was escorted by the Tamīm from al Yamama to the Yemen.

The evidence regarding military cooperation (or indeed any other form of cooperation) between the tribes and the courts of Ctesiphon and al Ḥīra reveals a certain tension between the wish to praise the tribe's military exploits, even those carried out in the service of a foreign power, and the claim of independence from the same power; tribal historiography attempted to distance the tribes from the influence of the courts, while at the same time boasting of the close contacts between them.

Many Arabs probably saw the local representatives of the great power from behind bars: the kings of al Ḥīra practised widespread incarceration as punishment and as a means of pressure. There were jails or incarceration camps at al Qutqutana in south western Iraq and at al Ḥīra itself.³⁶

The Tamīm, the Taghlib and others took part in the institution of *ridafa* (viceroysip) to the king of al Ḥīra, which was essential in establishing al Ḥīra's control over the tribes. The ceremonial and material privileges associated with it (perhaps exaggerated by the tribal informants) helped in buying

33 Kister, 'al Ḥīra', pp. 147–9; Lecker, *People, tribes and society in Arabia*, index. It would seem that at that time Medina was no longer controlled from al Zara but directly from Ḥīra.

34 Al Ṭabarī, *Ta'rikh*, series I, pp. 958–9.

35 Abu l Baqa', *al Manaḡib al mazyadiyya*, vol. II, p. 375.

36 Abu Ḥatīm al Sijistānī, *al Mu'ammara*, bound with *Al Waṣaya* by the same author, ed. 'Abd al Mun'im 'Āmir (Cairo, 1961), pp. 20–2. 'Adī ibn Zayd was jailed at al Sinnayn; al Ṭabarī, *Ta'rikh*, series I, p. 1023. A poet who lived in the transition period between *jahiliyya* and Islam (*mukhaḍram*) was jailed by the Sasanians at al Mushaqqar: Ibn Hajar al 'Asqalanī, *al Iṣāba fī tamyiz al ṣaḡaba*, ed. 'Alī Muḥammad al Bijawī, 8 vols. (Cairo, [1970]), vol. II, p. 513.

off potentially dangerous tribes. Through trade, military cooperation and diplomacy Arab tribal leaders and merchants became acquainted with the courts of the buffer kingdoms and the great empires.

Mecca: trade and agriculture

Mecca and Medina, thanks to their association with the history of the Prophet Muḥammad and the rise of Islam, are better known to us than many other settlements in Arabia that may well have been larger, wealthier and more populous.

Mecca and its dominant tribe, Quraysh, reveal a high degree of internal cohesion; but Mecca's stability was in fact based on the preservation of a balance of power between two rival alliances of Quraysh rather than on any sense of tribal solidarity. As one can expect, in accounts of Mecca's pre Islamic history – for example, concerning the establishment of its international caravan trade – the Prophet's ancestors receive more credit than is due to them. In any case, this trade was not a myth, but was Mecca's main source of revenue, regardless of the items and the income involved. In Arabian terms Mecca was a major trade centre, although it is impossible to establish whether or not it was the largest of its kind in Arabia.

Crossing evidence shows that the Prophet himself had been a merchant before receiving his first revelation. Trade partnerships were a significant aspect of the economic cooperation between Quraysh and the tribe controlling Ṭa'if, the Thaḳīf. Reportedly, the Qurashī Abu Sufyan and the Thaqaḳāī Ghaylan ibn Salama traded with Persia, accompanied by a group of people from both tribes.³⁷ Both were Muḥammad's contemporaries.

In addition to trade, the entrepreneurial Qurashīs invested in agriculture. Since conditions in Mecca itself were uninviting for agriculture, they looked for opportunities elsewhere. It can be argued that the Qurashī expansion in Arabia preceded the advent of Islam.

There is a legendary story about the death of Ḥarb ibn Umayya, the father of the above mentioned Abu Sufyan and the grandfather of the caliph Mu'awiya. He was reportedly killed by the *jinn* at al Qurayya north west of Mecca, since together with a local partner he disturbed the *jinn* or killed one of them by mistake. This occurred while they were clearing a thicket in order to prepare the land for cultivation. The story probably owes its preservation to

³⁷ Abu Hilal al 'Askarī, *al Awa'il*, ed. Muḥammad al Miṣrī and Walīd Qaṣṣab, 2 vols. (Damascus, 1975), vol. II, p. 228.

the legendary elements; but the background details are no doubt factual.³⁸ There is rich evidence of pre Islamic Qurashī involvement in agriculture in Ṭa'if, the town that supplied (and still supplies) most of Mecca's demand for fruit;³⁹ hence its appellation *bustan al ḥaram*, or the orchard of the sacred territory of Mecca.⁴⁰ Side by side with the locals who cultivated small tracts of land, Qurashī entrepreneurs developed large estates in the valleys of Ṭa'if before the advent of Islam. Many Bedouin of the Qays 'Aylan and other tribes earned their living by transporting Ṭa'ifī products to Mecca. At Nakhla north east of Mecca a caravan carrying wine, tanned skins and raisins⁴¹ on its way from Ṭa'if to Mecca was attacked shortly after the *hijra* by the Prophet's Companions.

The best known and perhaps the largest Qurashī property in the vicinity of Ṭa'if is al Waḥṭ, which is located in the valley of Wajj. The father of the Prophet's Companion 'Amr ibn al 'Āṣ owned this estate before Islam. 'Amr further developed it by raising the shoots of many thousands of grape vines on pieces of wood made to support them.⁴²

Numerous other Qurashīs owned estates near Ṭa'if. They included, among others, Abu Sufyan, 'Utba and Shayba sons of Rabī'a ibn 'Abd Shams, the Prophet's uncle al 'Abbas and al Walīd ibn al Walīd ibn al Mughīra (the brother of the famous general Khalid ibn al Walīd).

The Muslim conquests in Palestine and elsewhere are unlikely to have been accompanied by large scale devastation of agricultural land and facilities, since 'Amr ibn al 'Āṣ and the other Qurashī generals had previous experience with agriculture and appreciated the economic value of cultivated land.

Medina: a precarious balance

The cluster of towns or villages known before Islam as Yathrib was called after the town of Yathrib on its north western side. Under Islam the cluster

38 After the *hijra* it was one of Muḥammad's companions, Ṭalḥa, who introduced the sowing of wheat in Medina, while another companion, 'Abdallāh ibn 'Āmir, was famous for his talent for discovering water sources.

39 Muḥammad ibn 'Abd al Mun'im al Ḥimyarī, *al Rawḍ al mi'tar fī khabar al aqṭar*, ed. Iḥsan 'Abbas (Beirut, 1975), p. 379a.

40 Muḥammad ibn Ishaq al Fakiḥī, *Akhbar Makka*, ed. 'Abd al Malik ibn 'Abdallāh ibn Duḥaysh, 6 vols. (Mecca, 1987), vol. III, p. 206.

41 Waqīdī, *Maghazī*, vol. I, p. 16.

42 Fakiḥī, *Akhbar Makka*, vol. III, p. 205 (read 'arrasha instead of gharasa); Yaqut, *Buldan*, s.v. al Waḥṭ.

became known as al Madīna. Major political and military upheavals preceded the *hijra* contributed to Muḥammad's success there in ways that are not yet fully clear.


Medina's large Jewish population was dispersed in both the Safila, or Lower Medina, in the north and the 'Āliya, or Upper Medina, in the south. The Qurayza and Naḍīr are said to have inhabited the 'Āliya, while a third large tribe, the Qaynuqa', lived in the Safila. But the Naḍīr probably owned estates outside the 'Āliya and on its fringe as well: the town of Zuhra is defined as the town of the Naḍīr (*qaryat banī l naḍīr*); moreover, one of their notables, Ka'b ibn al Ashraf, owned land in al Jurf north west of Medina, at the upper part of the 'Aqīq valley.⁴³

The oldest stratum in the Arab population of Medina was made up of members of the Balī and of other tribes, many of whom converted to Judaism. The Aws and Khazraj, who settled in Medina at a later stage, became known under Islam by the honorific appellation *al anṣar* (the helpers). Unlike the earlier Arab settlers, most of the Aws and Khazraj remained idol worshippers. When they settled in Medina, their position vis à vis the Jewish tribes was weak. But gradually they gained strength, built fortresses and planted date orchards. The *anṣar* were ridiculed by other tribes for their initial subjection by the Jews, particularly with regard to the Arab Jewish king al Fityawn, 'the owner of Zuhra' (*ṣaḥib Zuhra*),⁴⁴ who reportedly practised the *ius prima noctis* on the Arab women. No wonder that al Fityawn figures prominently in *anṣarī* apologetic historiography. Admitting their initial weakness, they claimed that it came to an end with the killing of al Fityawn by a member of the Khazraj; from that moment onward the Jews were at the mercy of their former clients. However, *anṣarī* historiography should be taken with a grain of salt. The Jews suffered a setback, or the Khazrajī 'Amr ibn al Iṭnaba would not have become the king of Yathrib in the last quarter of the sixth century. But by the advent of Islam the main Jewish tribes Naḍīr and Qurayza had regained their power, as is shown by their victory at the battle of Bu'ath (615 or 617), together with their Awsī allies, over the powerful Khazraj.

'Amr ibn al Iṭnaba and al Fityawn were not the only kings in Medina before Islam. Several generations before Islam there lived there a king called Ama ibn Ḥaram of the Khazraj subdivision called Salima whose powers included the confiscation and redistribution of agricultural land.

⁴³ In due course Muḥammad himself owned agricultural land in al Jurf.

⁴⁴ Abu l Faraj al Isfahānī, *Kitāb al aghānī*, 24 vols. (Cairo, 1927–74), vol. III, p. 40.



2. The Quraysh

On the eve of Islam a member of the Khazraj, 'Abd Allah ibn Ubayy, was nearly crowned. Mas'ūdī reports: 'The Khazraj were superior to the Aws shortly before the advent of Islam and intended to crown 'Abd Allah ibn Ubayy ibn Salul al Khazrajī. This coincided with the arrival of the Prophet and his kingship ceased to exist.'⁴⁵

Ibn Ubayy did not fight against the Jewish Awsī coalition at Bu'ath, where his tribe, the Khazraj, was defeated. After Bu'ath he was the strongest leader among the Khazraj, and he showed great diplomatic skill in re establishing the system of alliances that had existed before Bu'ath. In

⁴⁵ Quoted in Ibn Sa'īd, *Nashwat al ṭarab*, vol. I, p. 190.

this system the Naḍīr were allied with the Khazraj,⁴⁶ while the Qurayza were allied with the Aws. At the time of the *hijra* the Naḍīr and Qurayza were the main owners of fortresses and weapons in Medina, which made them the dominant power there.

46 Samhūdī, *Wafa' al wafa*, vol. I, pp. 387–8, provides valuable evidence on the aftermath of Bu'ath.

PART II

*

UNIVERSALISM AND IMPERIALISM

The rise of Islam, 600–705

CHASE F. ROBINSON

The first Islamic century began in 622 of the Common Era with the *hijra* (Hegira), Muḥammad's 'emigration' from Mecca to the town of Yathrib, which lies about 275 miles to the north. As we shall see, the event was a turning point in Muḥammad's life: delivered from the pagan opposition of the city of his birth, he was free to preach, teach and lead in Yathrib so successfully that he remained there until his death in 632. In time it would even come to be called 'the Prophet's city' or 'the city' (Medina) *tout court*. The *hijra* thus marked a new beginning for Muḥammad and his followers. It also illustrates a striking feature of Islamic history. For Muḥammad's decision to leave Mecca was in purpose both deeply religious and deeply political.

On the one hand, he and those who believed in his prophecy were escaping polytheist intolerance towards his uncompromising monotheism. They were making their way to a town where, as the Qur'an seems to show, Muḥammad's ideas about God, man, this World and the Next, would evolve and sharpen, in part because he came into contact with the town's Jews, and in part because as Muslim numbers grew, so, too, did their demands upon him. Far more than in hostile Mecca, it was in Muḥammad's experience in Medina, as it is reflected in the Qur'an (the great bulk of which was apparently revealed there) and Prophetic tradition, that so much of Islamic belief and law came to be anchored. At the same time, the emigration to Yathrib was not *merely* religious; for Muḥammad and his contemporaries lived in a pocket of western Arabia where institutionalised forms of governance were as underdeveloped as ties of real, imagined and adopted kinship were strong. (Even in the very different settled culture of South Arabia, kingship was relatively weak.¹) In a society where social differentiation was relatively modest, it was as kinsmen (or confederates and the like) that the tribesmen married, shared and worshipped idols, herded, raided, defended and attacked, their skills often

1 A. F. L. Beeston, 'Kingship in ancient South Arabia', *JESHO*, 15 (1972).

overlapping. It was according to these ties, supplemented by traditional practices of cooperation, alliance and negotiation, that corporate action took place: they were the social ligature that organised society, constraining and conditioning the violence inherent in the fierce competition over scarce resources (especially water, pasture and animals) that characterised life in northern and central Arabian oasis settlements. There being no separate state agency, and religion being embedded as part of social life and identity, there was, then, no effective distinction between what we would regard as the 'religious' and 'political' spheres. Had he been inclined towards quietist introversion, Muḥammad might have satisfied his ambitions by making his *hijra* into desert solitude, as did many holy men of Late Antiquity. Instead, responding to an invitation to arbitrate between two tribes in Yathrib, he chose to take his message to a town where he could lead and organise men so as to organise a religious movement of radical reform. (Successful arbitration, like other forms of public diplomacy and martial valour, was an avenue towards higher social standing.)

So confessing belief in God and swearing loyalty to His Prophet meant working to effect a political order. As Muḥammad saw things, this order was willed by a God who, while promising Hellfire for polytheists, tolerated a variety of monotheist practices, on the condition that the monotheists – and indeed all creation – acknowledge His authority as delegated by Him to His Prophet Muḥammad, who was charged with the task of re-establishing this order on earth. It would thus be in Medina that Muslims embarked on the project, first by founding a simple but highly effective polity within the town, and second by launching a series of small but equally highly effective military campaigns outside it. In the short term, these brought the modest settlements of Arabia under the Prophet's control, each paying a tax or a tribute to symbolise their acknowledgement of God's authority, payable to His Prophet. In the long term, the campaigns grew into the conquest armies of the 640s and 650s (and beyond), which would overrun much of the Byzantine and all of the Sasanian Near East. Because the Prophet's and the caliphs' authority over these lands were understood to derive from God, it was as indivisible as His. It followed that prescribing and interpreting articles of Muslim belief, legislating, and ruling a multi-ethnic and religiously pluralistic empire – all these and other functions fell to the Prophet and the caliphs to carry out. The historical tradition preserves a letter purportedly written by the Prophet to a tribesman named 'Amr ibn Ḥazm, whom Muḥammad had sent to govern south Arabian tribes; whatever its exact provenance – the authenticity of this document, like that of nearly all documents from the early period,

is impossible to verify – it neatly expresses seventh and eighth century attitudes. We read that the Prophet instructs ‘Amr to fear God, to give instruction in the Qur’an, in the attractions of Heaven and fears of Hell and in various rituals and rites (including prayer) – and also to tax and distribute booty according to a regime that distinguishes between rain and spring fed lands, on the one hand, and artificially irrigated land, on the other, between cows and bulls and calves and sheep, between Muslim and non Muslim, male and female, free and slave.² Taxing was no less a religious activity than was praying.

The history made by seventh century Muslims is thus at once religious, military and political history, and it is dominated by a prophet and then caliphs who, delegated by God, enjoyed His indivisible authority. In fact, we shall see that a great deal of the century’s religious and political change was effected by three men: the Prophet Muḥammad and two long ruling caliphs: Mu‘awiya ibn Abī Sufyan (r. 661–80) and ‘Abd al Malik ibn Marwan (r. 685–705). Under their leadership the Near East would witness the last great religious movement of Antiquity. It almost goes without saying that in subsequent periods much in the Islamic religious tradition would evolve and transform; even so important a discipline as the study of Prophetic traditions only crystallised in the ninth century. Still, already by the end of the seventh century, what could be described as the core of Islamic belief had taken form: that the One God had made Himself known definitively and clearly in the Qur’an and the experience of the Prophet Muḥammad and his community. Meanwhile, the century would also witness the founding of the last great empire of Antiquity, which, at its height in the decades following the death of ‘Abd al Malik, would stretch from the Atlantic to the Oxus. In the space of three generations Arabs had moved from the periphery of the civilised world to the courts that ruled much of it, imprinting their language, culture and nascent religion upon millions. Recorded history has scarcely seen a more powerful fusion of belief and action than that effected by early Muslims.

How this happened can be answered theologically or historically. The theological answer – because God willed it so – generally lies behind all accounts provided by the pre modern tradition, whether apologetic (Islamic) or polemic (usually Christian). According to these traditions, men may receive punishment or reward, but they always remain instruments of God’s design. In the Islamic version, this design unfolds cyclically through history, as God, acting either

2 Abu Ja‘far Muḥammad ibn Jarīr al Ṭabarī, *Ta’rīkh al rusul wa’l muluk*, ed. M. J. de Goeje et al., 15 vols. in 3 series (Leiden, 1879–1901), series I, pp. 1727ff.; trans. I. K. Poonawala as *The history of al Ṭabarī*, vol. IX: *The last years of the Prophet* (Albany, 1990), pp. 85ff.

mercifully or wrathfully, makes good on His promise to Man by sending prophets or other holy men, whom men then usually ignore; He also sends down chastisements of various kinds (evil men, plagues, earthquakes), which they cannot. (God's participation in human affairs is occasionally very direct, such as when He dispatches angels to fight alongside Muslims in an early battle against polytheists.) A rather more transcendent God stands behind some modern accounts, which typically replace God's miracles with His invisible hand, but the result is much the same – an Islamic 'exceptionalism', in which the laws of history are temporarily suspended.³ Of course, God's agency is not something that we, as historians, should try to measure or describe; and even if we dismiss soldier angels and similar miracles, such modern answers are by definition as persuasive to most historians as arguments for Intelligent Design are to most palaeontologists. We must therefore content ourselves with describing and explaining the conduct of men – that is, writing history without the benefit of divine intervention.

This said, when set out with any real precision, historical reconstructions typically those that hold that Muḥammad was at once visionary, principled and pragmatic, and Hījāzī society was in a social or environmental crisis to which he offered answers,⁴ that the Byzantine and Sasanian provinces of the metropolitan Near East were poorly defended, and thus relatively easily overrun by Muslims energised by a new faith – are vulnerable to near lethal historiographic criticisms. As we shall see all too frequently throughout this chapter, the historiographic ground cannot bear interpretations that carry the freight of much real detail. For reasons made clear in chapter 15, the study of early Islam is plagued by a wide range of historiographic problems: the sources internal to the tradition purport to preserve a great deal of detailed history, but with very few exceptions they are late and polemically inclined; meanwhile, the sources external to the tradition are in many instances much earlier, but they know so little of what was happening in Arabia and Iraq that they are inadequate for detailed reconstruction.⁵ What is abundant is in general unreliable; what is relatively reliable is invariably too little; meanwhile, the painstaking work

3 C. F. Robinson, 'Reconstructing early Islam: Truth and consequences', in H. Berg (ed.), *Method and theory in the study of Islamic origins* (Leiden, 2003).

4 For the most recent attempt at an environmental explanation, see A. Korotayev, V. Klimenko and D. Proussakov, 'Origins of Islam: Political anthropological and environmental context', *Acta Orientalia Academiae Scientiarum Hungaricae*, 52 (1999).

5 On the Prophet, see F. E. Peters, 'The quest for the historical Muhammad', *IJMES*, 23 (1991); Ibn Warraq (ed.), *The quest for the historical Muhammad* (Amherst, NY, 2000); but cf. R. Hoyland, 'Writing the biography of the Prophet Muhammad: Problems and solutions', *History Compass*, 5 (2007).

required to identify and isolate reliable accounts has only relatively recently begun.⁶ Attempts to link Muḥammad's preaching to economic change or commercial dynamism in Arabia have been especially common; and not only are they typically based on unreliable sources, but they also very often reflect quaintly anachronistic models of economy, society and belief. There is nothing wrong in principle with proposing materialist interpretations of Islamic history, provided that the model is appropriate and the evidence sufficient.⁷ So far neither condition is present.

Given the state of the evidence, the most one can do is to set out some historical answers very schematically. In what follows I endeavour to do precisely that, drawing upon the Islamic and non Islamic literary evidence, in addition to the material evidence, as and when it is relevant. Alongside this historiographic prudence sits perhaps uneasily the conviction that, despite all the difficulties, early Islam is explicable, provided that it is explicated within the geographic, religious and political terms that are characteristic of the Late Antique Near East.

Hijazī monotheism?

The Islamic tradition generally came to describe pre Islamic Arabian history as the *jahiliyya* a period of 'ignorance' during which the pure monotheism that had been implanted in Arabia by Abraham was perverted by idol worshipping polytheists, leaving only minority communities of Jews, the stray Christian and *ḥanīfs* (indigenous monotheists) to worship God.⁸ Whatever its historicity, the construction of a naive *jahiliyya* clearly formed part of a broader cultural re orientation that took place during the Umayyad and 'Abbasid periods, when ethnic and religious identities took new shapes: as tribesmen settled in garrisons and towns of the Fertile Crescent during the seventh and

6 See, for some examples, M. Lecker, 'Did Muḥammad conclude treaties with the Jewish tribes Naḍīr, Qurayza and Qaynuqa?', *Israel Oriental Studies*, 17 (1997); M. Lecker, 'The death of the Prophet Muḥammad: Did Waqīdī invent some of the evidence?', *ZDMG*, 145 (1995); G. Schoeler, *Charakter und Authentie der muslimischen Überlieferung über das Leben Mohammeds* (Berlin, 1996); and H. Motzki (ed.), *The biography of Muḥammad: The issue of the sources* (Leiden, 2000).

7 See P. Gran, 'Political economy as a paradigm for the study of Islamic history', *IJMES*, 11 (1980); M. Ibrahim, *Merchant capital and Islam* (Austin, 1990); and, for materialist based sociology, M. Bamyeh, *The social origins of Islam: Mind, economy, discourse* (Minneapolis, 1999).

8 On the *ḥanīfs*, especially in terms of the epigraphic evidence (some of which is discussed below), see A. Rippin, 'RḤMNN and the Ḥanīfs', in W. B. Hallaq and D. P. Little (eds.), *Islamic studies presented to Charles J. Adams* (Leiden, 1991).

eighth centuries, what it meant to be an Arab and a Muslim came into sharper focus,⁹ and this refocusing involved the elaboration of an Arabian past consistent with the Qur'anic history. At least some of the traditional view of a pre Islamic Hijaz dominated by paganism also seems to reflect generic monotheist polemic as much as it does authentic history; Arabian 'pagans', on this reading, were monotheists who came up short. It is certainly the case that in the middle of the eighth century Muslims would accuse Christians of being idolaters because they worshipped the Cross, and this can scarcely be taken to mean that eighth century Syria was dominated by idolatry.¹⁰ Unfortunately, there is relatively little evidence with which we might test the traditional views of things, but although there is little doubt that the worship of multiple gods through idols was the prestige form of religiosity,¹¹ what we happen to have does throw some doubt upon it. Strains of monotheism (rabbinic and non rabbinic Judaism, varieties of Christianity and Jewish Christianity being its principal forms) may not have been as strong among the Arabs of the mid Peninsula as they were among those in the south or in Iraq and especially Syria, where a Ghassanid Christianity has been voluminously documented,¹² but they seem to have been stronger than the Islamic tradition describes them.

Things are less clear in Arabia than we would wish them to be, but monotheism had certainly gained a solid foothold well before Muḥammad. The clearest example of this comes in the Yemeni town of Najran, which was the centre of South Arabian Christianity from the fifth century.¹³ Tradition

9 See S. Agha and T. Khalidi, 'Poetry and identity in the Umayyad age', *al Abhath*, 50 1 (2002 3).

10 See, for example, G. R. Hawting, *The idea of idolatry and the emergence of Islam: From polemic to history* (Cambridge, 1999).

11 In general, see J. Retsö, *The Arabs in Antiquity: Their history from the Assyrians to the Umayyads* (London, 2003), pp. 600f.; R. Hoyland, *Arabia and the Arabs from the Bronze Age to the coming of Islam* (London and New York, 2001), pp. 139ff.; on Mecca in particular, C. Robin, 'Les "filles de Dieu" de Saba' à La Mecque: Réflexions sur l'agencement des panthéons dans l'Arabie ancienne', *Semitica*, 50 (2000).

12 I. Shahid, *Byzantium and the Arabs in the fifth century* (Washington, DC, 1989); I. Shahid, *Byzantium and the Arabs in the sixth century*, vol. I, parts 1 and 2 (Washington, DC, 1995 and 2002).

13 See J. S. Trimmingham, *Christianity among the Arabs in pre Islamic times* (London, 1979); Hoyland, *Arabia and the Arabs*, pp. 146 50; C. Robin, 'Judaïsme et christianisme en Arabie du sud d'après les sources épigraphiques et archéologiques', *Proceedings of the Seminar for Arabian Studies*, 10 (1980); J. Beauchamp and C. Robin, 'Le Christianisme dans le péninsule arabique dans l'épigraphie et l'archéologie', *Hommage à Paul Lemerle, Travaux et mémoires*, 8 (Paris, 1981); on Najran and Arab Christianity in general, there remain useful comments in T. Andrae, 'Der Ursprung des Islams und das Christentum', *Kyrkohistorisk Årsskrift*, 23 (1923), pp. 149 80.

explains one verse of the Qur'an (Q 2:61) by adducing a visit to the Prophet by a delegation of Christians from the town, and some reports have the town's Jews join this delegation. As noted in chapter 4, Judaism was powerfully attractive to the Himyarite kings that ruled in the south, who extended their authority during the fifth century towards the west and north, until the Christian Aksumite kingdom of Ethiopia reduced them to vassal status in the early sixth. This triggered the infamous massacre of the Christians of Najran by Dhu Nuwas in 522–3,¹⁴ an event that in turn led to an Ethiopian invasion of Arabia led by Abraha that avenged their martyrdom and brought Christian imperialism into the heart of the Peninsula. Abraha's ill-fated expedition to the Hijaz is known only to the Qur'an, but it conforms to the pattern of his Arabian expansion, which is partially documented in a number of inscriptions.¹⁵ In the east, the Nestorian Church, which is otherwise and less misleadingly known as the 'Church of the East',¹⁶ was often tolerated and less often persecuted by the Sasanians; it had earlier penetrated the Gulf and eastern Arabia, and there it established an ecclesiastical organisation and claimed adherents well down the coast as well as among the Lakhmids, the Sasanians' client kingdom centred in al-Hira. Several churches and monasteries survive in eastern Arabia, and although at least some were once thought to date from the Sasanian period, it seems that they actually belong to the eighth and ninth centuries,¹⁷ a fact that says something about the tenacity of Christian belief even within the Peninsula.

Ringed the Peninsula's Byzantine, Sasanian and Aksumite periphery, monotheism was thus becoming an increasingly compelling language of political expression. How did these beliefs – monotheistic and quasi-monotheistic (in the eyes of many, Trinitarian Christianity might sit somewhere between monotheism and polytheism) – affect Arabian polytheism? Can we detect some faint signals for either parallel or related movements towards some variety of monotheism? The evidence of pre-Islamic inscriptions, though currently limited to southern Arabia, is particularly important in

¹⁴ See, in general, C. Robin 'Le judaïsme de Himyar', *Arabia*, 1 (2003); J. Beauchamp, F. Briquel Chatonnet, and C. Robin, 'La persécution des chrétiens de Nagran et la chronologie Himyarite', *Aram*, 11–12 (1999–2000); and M. Lecker, 'Judaism among Kinda and the *rida* of Kinda', *JAOS*, 115 (1995).

¹⁵ See below, note 19.

¹⁶ A recent summary can be found in J. F. Healey, 'The Christians of Qatar in the 7th century AD', in I. R. Netton (ed.), *Studies in honour of Clifford Edmund Bosworth*, vol. 1: *Hunter of the East: Arabic and Semitic studies* (Leiden, 2000).

¹⁷ See now D. Kennet, 'The decline of eastern Arabia in the Sasanian period', *Arabian Archaeology and Epigraphy*, 18 (2007), pp. 86–122.

this regard: for there we can see how pagan formulae begin to be eclipsed by what appears to be the monotheistic marker of *al raḥman*, 'the merciful', which would come to be one of the principal epithets with which Muslims would describe Allah, the one God. Dating these inscriptions is very difficult, but it has been argued that the eclipse begins in the fourth century.¹⁸ One early sixth century inscription, which glorifies Abraha, reads: 'By the might and aid and mercy of the Merciful and His Messiah and of the Holy Spirit. They have written this inscription: Behold Abraha ... king of Saba' ... and Dhu Raydan and Ḥaḍramawt and Yamanat and of "their" Arabs on the plateau and the Tihamat.'¹⁹ With a dense fringe of Christians and Jews on the eastern and southern periphery, and some signs for the emergence of a supreme God in the inscriptions currently available from the south, one might expect to find similar developments at work in the Ḥijaz. In fact, the South Arabian inscriptions have sometimes been taken to demonstrate the presence of a religious movement (or community), which the sources describe as the Ḥanafīyya, and which began in the south and moved into the Ḥijaz.²⁰

There is much to be said for this argument, not least of which is that it makes some sense of what the tradition itself says: pre Islamic poetry and the language of early Islamic ritual hint at an earlier belief in a supreme God, one frequently known by the same name (*al raḥman*). From this perspective, Muḥammad's charge that his contemporaries were committing *shirk* ('association' and, by extension, polytheism) can be construed as a charge that they were associating other deities with the supreme God whom they already acknowledged, rather than as a blanket condemnation of polytheism.²¹ Very telling is the testimony of the Qur'an itself, which, whatever the precise course of its assembly and transmission, clearly has its origins in seventh century Arabia. It is telling in two respects. The first is that it can be read to suggest a geography of belief in which the supreme God (Allah) was acknowledged as the creator, and where lesser deities are called upon principally to intercede with Allah. According to this view (or a version of it), the old gods were in

18 A. Beeston, 'Himyarite monotheism', in A. M. Abdulla *et al.* (eds.), *Studies in the history of Arabia*, vol. II: *Pre Islamic Arabia* (Riyadh, 1984); C. Robin, 'Du paganisme au monothéisme', in C. Robin (ed.), *L'Arabie antique de Karib'il à Mahomet: Nouvelles données sur l'histoire des arabes grâce aux inscriptions* (Aix en Provence, 1991).

19 For the inscription and the events, see S. Smith, 'Events in Arabia in the 6th century AD', *BSOAS*, 16 (1954), p. 437.

20 For criticisms, see above, note 8.

21 See, for example, K. Athamina, 'Abraham in Islamic perspective: Reflections on the development of monotheism in pre Islamic Arabia', *Der Islam*, 81 (2004); M. J. Kister, 'Labbayka, allahuma, labbayka: On a monotheistic aspect of a Jahiliyya practice', *JSAI*, 2 (1980).

decline and the power of the supreme God was in the ascendant; Muḥammad's movement, it follows, accelerated a progress already in train.²² Here it should be noted that tradition acknowledges the presence in other parts of Arabia, including the Najd and al Yamama, of prophetic figures whom it discredits as pseudo and copy cat prophets. The most notorious of these was named Musaylima ibn Ḥabīb, who preached in al Yamama with a book written in rhymed prose – the very prophetic portfolio that Muḥammad himself carried. Might it be that the sixth and seventh centuries, which produced messianic and prophetic figures among the Christians and Jews, produced among the incipient monotheists of Arabia a number of legislating prophets? If so, what we have in early Islam may be the culmination of a gradual process, in which the old gods grew gradually weaker and the supreme God gradually more powerful, one pushed along by several charismatic religious figures.

The Qur'an is telling in another respect. It claims to express a 'clear Arabic', but it is an Arabic that may have been clearer to its contemporaries than it was to scholars of subsequent periods. In fact, a very conservative seventh and eighth century tradition of textual transmission has ironically conserved the text's polyglot origins: Qur'anic language actually accommodates not only a wide range of non Arabic loanwords, but also, perhaps, a Syriac Christian substrate of language and belief, which, though hardly detectable elsewhere, is what we might expect to find, given that Arabia was geographically and culturally contiguous to the heartland of Syriac Christianity. The argument for this substrate can be taken much too far, but to acknowledge it is in no sense to discredit Muḥammad or challenge the originality of his vision – at least any more than identifying the Jewish and Graeco Roman context in which Jesus operated is to challenge his. It is merely to identify some of the ingredients with which Muḥammad forged his enormously powerful ideas. The fact is that terms as crucial as *Qur'an* and *sura* are Aramaic in origin, and postulating a Syriac substrate can unlock several obscure passages, while others are resolved by positing referents in the biblical, exegetical and liturgical traditions of eastern Christianity. An example can be found in Q 108, which, read as 'pure' Arabic, is scarcely meaningful either to medieval Muslim exegetes or modern critics:

Surely we have given you abundance
 So pray to your Lord and make sacrifice
 Surely he who hates you will be disinherited/without posterity/cut off.

22 W. M. Watt, 'Belief in a "High God" in pre Islamic Mecca', *JSS*, 16 (1971).

Read as an Arabic Syriac hybrid, the text improves considerably:

Surely we have given you [the virtue] of patience
So pray to your Lord and persist [in your prayer]
Your enemy [Satan] is thus vanquished.

Muḥammad was no crypto Christian, and there is no good evidence for an Arabic bible in this period, but the dogma of his illiteracy obscures the presence of monotheistic ideas and practices with which he apparently had some real familiarity.²³

Such, in very schematic form, is the evidence for movements of (or towards) monotheism in western Arabia. Though currently inadequate, it may improve in time. But it may also be that the Hijaz was not merely sluggish in following developments taking place in the south and east, but required nothing less than revolution. This should not necessarily surprise. For one thing, the area was not tightly stitched into the regional fabric by trade patterns. When the evidence is scrutinised carefully, the argument collapses for the movement of luxury goods (especially textiles and spices) through a Meccan entrepôt, leaving local trade in heavier (and thus lower profit) animal products, perhaps especially skins.²⁴ Again, the action was on the periphery: Sasanian pressure in the Gulf and north eastern Arabia seems to have started by the middle of the third century, when cities were founded on both of its sides; by the latter half of the sixth century there seem to have been both military and trading colonies in the area.²⁵ For another – and again in contrast to the more promising south and east – a very forbidding environment and climate, combined with relatively modest natural resources,²⁶ meant that settlement in inner and western Arabia was sparse, levels of consumption and investment low, and the interest of Arabia's imperial neighbours

23 C. Luxenberg, *Die syro aramäische Lesart des Koran*, 2nd edn (Berlin, 2004), trans. as *The Syro Aramaic reading of the Koran* (Berlin, 2007), where this substrate becomes an 'original' version of a mixed language text; the argument is occasionally forced and its readings often arbitrary; cf. C. Gilliot, 'Le Coran, fruit d'un travail collectif?', in D. De Smet et al. (eds.), *al Kitab: La sacralité du texte dans le monde de l'Islam* (Brussels, 2004). I draw the example from Gilliot, 'Le Coran', pp. 220–1.

24 P. Crone, *Meccan trade and the rise of Islam* (Princeton, 1987; repr. Piscataway, NJ, 2004); P. Crone, 'Quraysh and the Roman army: Making sense of the Meccan leather trade', *BSOAS*, 70 (2007).

25 See, for example, D. Whitehouse and A. Williamson, 'Sasanian maritime trade', *Iran*, 11 (1973); D. Potts, *The Arabian Gulf in Antiquity* (Oxford, 1990).

26 See G. W. Heck, "'Arabia without spices': An alternate hypothesis", *JAOS*, 123 (2003), where the argument for a 'vibrant and productive' macroeconomy, turning especially on silver mining, is put very robustly.

accordingly limited to its borders. Inscriptional evidence suggests that Rome had brought parts of the northern Ḥijaz under its direct control in the second century, but sustained and direct control ended well before Islam began to take root. There are accounts that have the Sasanians levy the occasional tax or tribute, but the Ḥijaz itself was unattractive to the Byzantine and Sasanian states in the long term: projecting power into inner and western Arabia was costly in many respects, and the benefits would not have repaid those costs.

Muḥammad in Mecca

According to the Islamic tradition of the late eighth and ninth centuries, it was within the relatively insulated and polytheist society of Mecca that Muḥammad was born in what it calls ‘the year of the elephant’. The year is typically calculated to 570, when Mecca is said to have been threatened by an army sent by Abraha, the Ethiopian who had conquered South Arabia and was now moving into the west, his army outfitted with impressive African elephants that were presumably unfamiliar to the Ḥijazīs. The events are vaguely known to the Qurʾān (105), but tradition attaches all manner of speculation, legend and polemic to the obscure verses. This generating ‘history’ by assigning historical circumstances to verses that had become increasingly obscure is a prominent feature of the early biographical tradition,²⁷ and it places near insuperable obstacles in the path of writing detailed Prophetic history. Indeed, of Muḥammad’s birth, childhood and early adulthood we know almost nothing that can properly be called knowledge.²⁸ In this period the general problem of writing Prophetic history (the great bulk of what is transmitted as Prophetic history was actually generated during the eighth and ninth centuries by exegetes attempting to make sense of those increasingly obscure Qurʾānic terms) is compounded by the indifference of early Muslims. For Muḥammad’s experience before the Angel Gabriel first spoke to him appears to have been of little interest to the initial generations of Muslims, who focused on what he became rather than who he had been. Neither the non-Islamic sources nor material evidence can shed any real light.

When was Muḥammad born? According to fairly reliable literary and inscriptional evidence, the date of 570 is altogether too late for the tradition’s invasion to have taken place, and if one is determined to retain the association

²⁷ Crone, *Meccan trade*, pp. 203ff.

²⁸ For a discussion of this and related problems, see chapter 15; on Muḥammad’s date of birth, L. I. Conrad, ‘Abraha and Muḥammad: Some observations apropos of chronology and literary topoi in the early Arabic historical tradition’, *BSOAS*, 50 (1987).

between birth date and elephant army, it may be that he was born in the 550s instead. Muḥammad's name, which means 'the praised one', is an epithet that probably post dates his prophetic claims. The legends proliferate. In some instances inspired by Qur'anic obscurities, the tradition describes in striking detail an orphaned child who would be cared for by an uncle named Abu Ṭalib, the father of the fourth caliph to be, 'Alī ibn Abī Ṭalib, and who would travel to the north on trade. These journeys are often connected with his employment by a wealthy widow named Khadija, whom he would marry, and who would bear him many children, although no sons who survived beyond childhood. As legends, these say more about how later Muslims understood prophecy than they do the circumstances of his life.²⁹ Thus when a monk (or holy man or Jew – the specifics are fluid) realises (such as by recognising a mark between the shoulder blades) that the youthful Muḥammad will be called to prophethood, the reader is to understand that other monotheists acknowledge one of the tradition's essential claims: this prophet belongs in a long chain of monotheist prophets sent by God. Other initiation accounts have a young Muḥammad's chest opened and miraculously closed; according to one version of this story, the surgery is performed by two eagle like birds, who remove two black clots of blood, wash, and reseal the chest with 'the seal of prophethood'.³⁰ Other accounts have him participate in the purifying and rebuilding of the Ka'ba (the centre of the pagan sanctuary that would be converted into the centre of Islamic ritual). Still others describe an inchoate or incipient monotheist sensibility: we read that Muḥammad took to wandering in local hills, given over to quiet contemplation. If any of these accounts contain any kernel of truth, we cannot separate it from myth; because the non Islamic sources that know of such accounts seem to rely upon the Islamic tradition, they cannot be called in as a control. That Muḥammad belonged to the clan of the Banu Hashim of the tribe of the Quraysh, which was the leading tribe of Mecca, is probable, however.

Muḥammad only walks onto the set of history when God begins to speak to him through the Angel Gabriel. But the stage lights are very dim – virtually all we have that is early is the little that the Qur'an tells us, and both the sequence and chronology of its chapters remain unclear. (In what follows, I accept that at least some Meccan and Medinan chapters can be disentangled from each

29 See J. Wansbrough, *The Sectarian milieu: Content and composition of Islamic salvation history* (Oxford, 1978).

30 For discussions, see U. Rubin, *The eye of the beholder: The life of Muḥammad as viewed by the early Muslims* (Princeton, 1995), pp. 59ff.; see also U. Rubin, *Between Bible and Qur'an: The Children of Israel and the Islamic self image* (Princeton, 1999).

other.) Tradition associates the turning point with two Qur'anic passages. The first (96:1–5) reads as follows:

Recite in the name of your Lord who created
Created man from a blood clot.
Recite – your Lord is the most generous
Who taught by the pen
Taught man what he did not know.

The second (Q 74:1–5) reads as follows:

O you who are wrapped in your cloak
Arise and warn
And magnify your Lord
Purify your clothes
And shun pollution.

The tradition frequently holds that the first revelations were followed by a pause of three years, whereupon they came regularly for the next ten years or so. Traditional dating schemes, which generally turn on changes in style, associate short verses of striking imagery with the Meccan period. 'Arise and warn' (72:2), which is one of these, marks out Muḥammad as a 'warner', as does Q 26:214 ('And warn your nearest relatives'), a verse that is usually taken to signal the beginning of Muḥammad's public preaching. The Prophet thus follows in the footsteps of early monotheist warner prophets – some 124,000 of them, according to one count, although only 135 are said to have combined prophecy with politics.³¹ But whereas earlier prophets had typically warned their own communities of catastrophe (e.g. the 'painful chastisement' predicted by Noah), Muḥammad warned all mankind of nothing less than the Last Day (34:28 and 40:15). Thus the first verse of Q 81, which is usually said to be early: 'When the sun will be darkened, when the stars will be thrown down, when the mountains will be set moving ... then will a soul know what it has produced.'

How did God make Himself understood through Muḥammad? According to tradition, God's messages were delivered orally by Gabriel to the Prophet, who subsequently dictated them from memory to a scribe for recording on the writing material that was available, such as bones, bark and stones; after the Prophet's death, contemporaries are said to have had what amounts to personal versions of the Qur'an, but the task of establishing and distributing a single, authorised version was left to the third caliph, 'Uthman ibn 'Affan (r. 644–656).

³¹ The numbers come from P. Crone, *Medieval Islamic political thought* (Edinburgh, 2004), p. 10.

How well Muḥammad could read and write – if he could do either at all – is left unanswered by the Qur'an. Tradition would answer the question by asserting the dogma of his illiteracy, which functioned to insulate the Prophet from claims that his knowledge of monotheist history came from familiarity with the Torah or Gospels, as other monotheists had alleged. (For what they are worth, a late seventh century Armenian chronicler has it that Muḥammad was 'learned and informed in the history of Moses' (that is, the Pentateuch), while John of Damascus (d. c. 750) held that Muḥammad knew the Old and New Testaments, and had met an Arian monk.³²) The dogma also functioned to emphasise the 'miraculous inimitability' (*i'jaz*) of the Qur'an: Moses could transform walking sticks into snakes, and Jesus could heal and resurrect, but Muḥammad spoke directly for God in God's perfect speech. Dogmas aside, what is clear from the text itself is that many Qur'anic passages directly responded to problems that Muḥammad faced, both personal and communal. This is a pattern that becomes especially clear in Medina, such as when Muḥammad contravened social norms by marrying Zaynab, the divorced wife of his foster son, Zayd, a matter that was controversial enough not only to generate a Qur'anic dispensation, but also to pass into the Christian tradition;³³ other examples include the raid at Nakhla (see below).

Exactly how the revelations were received cannot be known in any detail either. The lists and accounts of early converts more clearly reflect controversies about post Prophetic politics than they do Prophetic history. Among the men, Abu Bakr (the first caliph) and 'Alī (Muḥammad's son in law and later recognised as the fourth caliph) are the favoured candidates for pride of place; among the women, Khadīja is unrivalled. Nor can much be said about how the polytheist establishment responded to Muḥammad's prophetic claims. In the moments of revelation Muḥammad was given to shaking or even seizures of one sort or another, and according to one set of traditions, even Khadīja reacted to Q 96:1–5 by summoning a local monotheist, Waraqa ibn Nawfal, who reassured her that Muḥammad was indeed a genuine prophet. 'There has come to him the greatest law that came to Moses' (law (*namus*) being glossed as 'Gabriel').³⁴ The Qur'an itself makes plain that many Meccans quite naturally

32 Sebeos, *The Armenian history attributed to Sebeos*, trans. R. W. Thomson with commentary by J. Howard Johnston, *Translated Texts for Historians* 31, 2 vols. (Liverpool, 1999), vol. I, p. 95; John of Damascus, *Œcrits sur l'Islam*, ed. and trans. R. Le Coz (Paris, 1992), pp. 211–12; cf. A. Palmer, S. Brock and R. Hoyland, *The seventh century in the West Syrian chronicles* (Liverpool, 1993), p. 130, note 293.

33 John of Damascus, *Œcrits*, pp. 221–3.

34 Ibn Hisham, *al-Sīra al-nabawiyya*, ed. M. al-Ṣaqqā et al., 4 vols. (Cairo, 1936), vol. I, p. 167.


took him to be a magician, soothsayer or otherwise possessed. There were other reasons to find Muḥammad objectionable. As a ‘warner’ in the tradition of early prophets, he emphasised man’s accountability to God, His power, the rewards of Heaven and the punishment of Hell. He also levelled criticism against the prevailing social norms, railing against female infanticide and the abuses of wealth. None of this apparently sat well with the polytheist establishment, especially because he came to attack its gods and claim the Ka’ba for the One God. As his followers grew in number and Muḥammad grew in stature, the opposition to his movement stiffened. And when his uncle and guardian Abu Ṭalib died, Muḥammad became vulnerable; some measure of persecution then followed; a flight to Abyssinia was aborted; the *hijra* to Yathrib took place.³⁵ Muḥammad lived in a society where kinship ties provided such protection and safety as were possible, and, with the death of Abu Ṭalib, these ties, long stretched by Muḥammad’s preaching, now snapped. He had to flee.

Muḥammad and his community after the *hijra*

That the *hijra* came to mark a watershed in the history of the Prophet and his community is made clear by several things, including the very frequent appearance and special significance in the Qur’an of the derived Arabic word *muḥajir* (pl. *muḥajirun*, ‘*hijra* makers’, ‘Emigrants’), and the *anṣar* (‘Helpers’ – those in Medina who would follow Muḥammad). Borrowings of *muḥajir* are used by Greek and Syriac writers as early as the 640s; there it is used to describe Muslims in general, a usage that is sometimes echoed in the Islamic tradition too. Early in the same decade, a bilingual papyrus receipt (in Arabic and Greek) refers to the ‘month of Jumada I of the year 22’ (643), which signals the use (at least in Egypt) of the new Muslim calendar based on the *hijra*; and an epitaph written as far away from Arabia as Cyprus may provide an exceptionally early attestation (AH 29) for the term *hijra* itself.³⁶ Centuries later families would crow about their descent from the ‘Emigrants’.

35 For details on this period, the standard work remains W. M. Watt, *Muhammad at Mecca* (Oxford, 1953), and, for the next, W. M. Watt, *Muhammad at Medina* (Oxford, 1956). Both are historiographically obsolete.

36 A. Grohmann, *Arabische Chronologie* (Leiden, 1966), pp. 13–14; E. Combe, J. Sauvaget and G. Wiet, *Répertoire chronologique d’épigraphie arabe I* (Cairo, 1931), pp. 5–6; and L. Halevi, ‘The paradox of Islamization: Tombstone inscriptions, Qur’anic recitations, and the problem of religious change’, *History of Religions*, 44 (2004), p. 121.



3. Muḥammad's family.

After Ira M. Lapidus, *A history of Islamic societies*, 2nd edn, 2002, p. 19, fig. 1. Copyright Cambridge University Press, reproduced with permission.

On this the question of the *hijra* and associated terms we can even do better than these relatively early attestations. The earliest use of the term 'Emigrants' comes in a contemporaneous set of documents, which are unfamiliar to the Qur'an, but preserved in several versions in the eighth and ninth century Islamic tradition; they have come to be known as the Constitution of Medina. One version begins as follows:

The Prophet, God's blessings and peace be upon him, wrote a document [governing relations] between the Emigrants and Helpers, in which he entered into a friendly compact with the Jews, confirmed their [claims] upon their religions and properties, and stipulated terms as follows:

*In the name of God, the merciful and compassionate. This is a document from Muḥammad, God's prayers and peace be upon him, between the believers and Muslims of the Quraysh and Yathrib, and those who followed them, joined them and struggled with them. They are a single community (umma) to the exclusion of [other] people.*³⁷

³⁷ Ibn Hisham, *al-Sīra al-nabawiyya*, vol. I, p. 501; for different translations, see A. Guillaume, *The life of Muḥammad* (Oxford, 1955), pp. 231–2, and now M. Lecker, 'The Constitution of Medina': Muḥammad's first legal document (Princeton, 2004).

A series of stipulations about paying bloodwit, mutual aid and support, the conditions of just retaliation and practices of warfare are then enumerated. As the only documentary material to survive from Muḥammad's time, the Constitution of Medina is of immense historiographic significance. (Precisely how soon after the *hijra* these documents were drawn up is impossible to know, but none can date much beyond the battle of Badr in AH 2.) What the Constitution shows us is two interrelated processes.

The first was how Muḥammad assembled a community (*umma*) that he would lead. In other words, he was engaged in politics. Unlike the model of community upon which classical Islam would settle – a community of Muslims who, by professing a more or less settled creed and carrying out a more or less fixed set of rituals, were distinct both from polytheists and other monotheists – the *umma* of the Constitution appears to accommodate the Jews of Medina, although they occupy a subordinate status. This inclusive sense of community reflects the relatively catholic nature of early Islamic belief: we have already seen that Muḥammad had followed in the footsteps of earlier prophets (Moses and Abraham are especially prominent in the Qur'an), and his call for monotheism was initially compatible with those made by his predecessors. In fact, the lines between Muslim and Jew were not yet firmly drawn,³⁸ evolving Muslim ritual (such as the fast of the tenth of Muharram and 'the middle prayer ritual') being still closely patterned upon Jewish traditions (such as the fast of the tenth of Tishri and the second of the three ritual prayers).³⁹ Even a matter as important as the direction of prayer (*qibla*) was not yet settled: it seems that Muslims directed their prayers to Jerusalem until what the Qur'an (see Q 2:142–150) and tradition describe as a decisive break with the Jews of Medina, which involved establishing Mecca once and for all as the normative *qibla*. The break would also involve expelling the Jewish tribes of the Banu Qaynuqa' and Banu al Naḍir and executing all of the men of a third, the Banu Qurayza.⁴⁰

The fate of the Jewish tribes of Medina is closely related in our sources to the second process that the Constitution shows at work: Muḥammad putting his nascent community into shape for war making against his polytheist opponents. In this, the Constitution conforms to the great stress laid in the

38 For a radical proposal along these lines, see F. M. Donner, 'From believers to Muslims: Confessional self identity in the early Islamic community', *al Abhath*, 50.1 (2002–3).

39 See, for example, S. Bashear, 'Āshura, an early Muslim fast', *ZDMG*, 141 (1991); repr. in S. Bashear, *Studies in early Islamic tradition* (Jerusalem, 2004).

40 M. J. Kister, 'The massacre of the Banu Qurayza: A re-examination of a tradition', *JSAI*, 8 (1986), pp. 61–96.

Qur'an upon fighting on behalf of God in general, and upon the connection between emigration or 'going out' (*khuruj*, as opposed to 'sitting', *qu'ud*) and this fighting, as Q 2:218 ('those who emigrate and fight on the path of God'), and other verses put it. The Muslim is 'one who believes in God and the last Day and fights on the path of God' (Q 9:19). We have seen that Muḥammad's thinking and preaching in Medina evolved, particularly as relations with the town's Jews evolved. But in so far as the historical tradition offers anything like an accurate record of his concerns, his attention was focused upon fighting outside it. The Medinan phase is thus dominated by his campaigns against passing caravans, settlements and Bedouin tribes. These skirmishes and battles culminated in the capitulation of Mecca itself. *Jihad* (the struggle on behalf of God, which in this context meant nothing more or less than fighting on His behalf) was at the centre of Muḥammad's programme.

Why did Muḥammad take up arms? Leaving aside the vexed question of the vulnerability of Medina to its powerful neighbour, we can be fairly sure that Muḥammad wished his followers to be able to worship in Mecca or its environs, perhaps especially on the hills of Marwa and al Ṣafa', which, as much as or even more than the Ka'ba itself, were integral to early Islamic ritual. Perhaps this wish, combined with the powerfully activist nature of his belief, led Muḥammad to begin hostilities soon after the *hijra*. His forces were typically small, but, with the exception of the battle of Uḥud, well managed and opportunistic.⁴¹ The first skirmish, which is traditionally dated to AH 2, was a caravan raid at a settlement called Nakhla. Little blood was spilt, but what was spilt was spilt in Rajab, a 'forbidden' month, when fighting was proscribed by tribal convention; the event occasioned a revelation (Q 2:217) that allayed the resulting concerns.⁴² The battle of Badr, a town that lay about 90 miles south west of Medina, soon followed; the humiliating defeat for the Meccans – some seventy of whom are said to have been killed – is celebrated in Q 8:9, 12, 17 and 42 as proof of God's providential direction of Muḥammad's forces: angels fought alongside them.

Fortunes were dramatically turned at Uḥud, which is conventionally dated to AH 3 or 4. There, a relatively large Meccan force of 3,000 horsemen, led in part

41 On these armies, see E. Landau Tasseron, 'Features of the pre conquest Muslim army in the time of Muḥammad', in A. Cameron (ed.), *The Byzantine and early Islamic Near East*, vol. III: *States, resources and armies*, Studies in Late Antiquity and Early Islam 1 (Princeton, 1995), pp. 299–336. The material evidence for military technology only begins with the Marwanids; see D. Nicolle, 'Arms of the Umayyad era: Military technology in a time of change', in Y. Lev (ed.), *War and society in the eastern Mediterranean, 7th–15th centuries* (Leiden, 1997).

42 See M. J. Kister, "'Rajab is the month of God": A study in the persistence of an early tradition', *Israel Oriental Studies*, 1 (1971).

by Khalid ibn al Walīd, who would later command spectacularly successful conquest armies, avenged the defeat of Badr by killing sixty five or seventy Muslims. (The numbers are stereotypical and probably unreliable.) We read that the Prophet himself was wounded. Jewish *Schadenfreude* about the events of Uhūd is traditionally adduced to explain Muḥammad's growing hostility towards them in this period. The Meccans were dilatory in following up the advantage they had gained at Uhūd, giving Muḥammad something like two years to dig a defensive ditch around Medina, which would give its name to the battle of the Ditch in about AH 5. With their cavalry unable to negotiate this obstacle, the Meccans were forced to break off their siege of the town. The Prophet's fortunes had been reversed again. In the meantime, and continuing thereafter, Muḥammad led or sent several successful expeditions against Ḥijāzī tribes. We can attach names to those who fought here and elsewhere because Prophetic biography (*sīra*) includes what appear to be some relatively early lists of expedition participants. What we cannot say is how they conducted themselves on the battlefield: just as conversion narratives reflect subsequent history, so, too, do battle narratives such as these. We shall never know what 'Alī, Abu Bakr, 'Umar and 'Uthman did (or failed to do) at Uhūd; what we can know is how claims about status were made in historical narrative.

At this point the fifth and sixth year of the *hijra* the traditional chronology leads in two directions. The first is towards Mecca. In AH 6 Muḥammad, confident in the aftermath of the battle of the Ditch, led a group of Muslims on pilgrimage to Mecca, and although he had to abort it, he nonetheless came away from the settlement of al Ḥudaybiya with an agreement that a pilgrimage could be conducted the following year; a ten year truce was also signed with the Meccans. The following year the oasis town of al Khaybar fell, delivering such large amounts of booty and spoils into Muslim hands that it merits mention in Q 48:18–21. Meanwhile, Muḥammad carried out the pilgrimage that had been agreed the previous year. Medina's strength had thus grown at the expense of Mecca's, and the almost bloodless capitulation of Mecca in AH 8 may have come as something of an anti climax: the Prophet had been carrying on what amounted to a charm offensive against influential Meccans. Most of those notable Qurashīs who had failed to acknowledge Muḥammad during the previous year did so now, although there were apparently some spectacular exceptions, such as Abu Sufyan, the *de facto* leader of the Meccan establishment and father of the second Umayyad caliph, Mu'awiya. Although Muḥammad had apparently been clement towards his Meccan adversaries tradition generally has him spare everyone save a few exceptionally offensive poets – one imagines that Mecca remained

inhospitable (and in some respects hostile) to the Muslims. The Prophet would return to Medina for the final two years of his life.

From AH 5 and 6, the traditional chronology also leads in a second direction – towards the conquests in general and Syria in particular. The oasis town of Dumat al Jandal lay about fifteen days' march north from Medina; it also lay about half that distance from Damascus. Its strategic position perhaps explains why it was the object of no fewer than three raids, the first of which was led by the Prophet himself in AH 5. It fell for good in AH 9 to Khalid ibn al Walīd, who had been dispatched by Muḥammad, who had himself taken another town in north western Arabia, Tabuk, in the summer of that year, having heard that a coalition of Byzantine and Arab forces had amassed there. In fact, as early as AH 6 or 7, the tradition has Muḥammad dispatch letters to Heraclius, the Negus of Abyssinia and the Sasanian Shah, among others, inviting them to acknowledge his prophecy and convert to Islam. (They all declined.) The terms of capitulation for Dumat al Jandal and Tabuk, as they had been for al Khaybar, called for a tribute payable to Muḥammad. At least in part because the Qur'anic injunction that the People of the Book (that is, monotheists who acknowledge scripture) pay a tribute (*jizya*) is so vague, these capitulation accounts would function as partial models for conquest arrangements.⁴³ After the conquest of Mecca, Muḥammad is also said to have extended his influence in eastern and southern Arabia, chiefly by treaty rather than conquest. At least one non Islamic source has Muḥammad lead a conquest army into Palestine, but this must be mistaken.⁴⁴

Whatever the accuracy of the sequence and chronology of the Prophet's campaigns, not to mention the authenticity of the texts of letters and treaties ascribed to him, the tradition – and, following it, much modern scholarship – have seen in these events the origins of the great conquest movements that post dated Muḥammad's death. In broad strokes, this must be true. The dynamic that Muḥammad had set into motion in the 620s did not go still in the 630s: manifesting and exemplifying belief by fighting on behalf of God, and reaping the rewards of this world and the next as a result, continued to exert a powerful and widespread influence long after 632. Put another way, after Muḥammad's death, God would continue to effect His will through the

43 On these and related problems, see W. Schmucker, *Untersuchungen zu einigen wichtigen bodenrechtlichen Konsequenzen der islamischen Eroberungsbewegung* (Bonn, 1972).

44 P. Crone and M. Cook, *Hagarism: The making of the Islamic world* (Cambridge, 1977), p. 4; R. Hoyland, *Seeing Islam as others saw it: A survey and evaluation of Christian, Jewish and Zoroastrian writings on early Islam* (Princeton, 1997), p. 555.

agency of tribesmen campaigning on the order of caliphs who had inherited the Prophet's authority. Only gradually and incompletely, as subsequent Islamic history would show, was taking up arms disengaged from belief, as armies were professionalised and the state claimed the exclusive right to carry out legitimate violence. 'There shall be no *hijra* after the conquest [of Mecca]' is a widespread tradition that was circulated to discourage eighth and ninth century Muslims from doing exactly what Muḥammad had urged them to do – to emigrate and fight in order to prove and manifest their belief.⁴⁵

That Muḥammad had set that dynamic into motion within Arabia is not to say it was an exclusively Arabian phenomenon. The seventh century was a time of Holy War. When Muḥammad was campaigning within the Hijaz on behalf of God, the Byzantine emperor Heraclius, having broken from the emperors' tradition by leading armies in person, was campaigning in Armenia and Iraq on behalf of Christ and God.⁴⁶ It may even be that in the very year that the Prophet entered into the treaty at al-Ḥudaybiya, thus ensuring a peaceful pilgrimage to Mecca, Heraclius' army was storming into Sasanian Iraq, thus ensuring the return of fragments of the Cross to Jerusalem. Events in and outside Arabia had been running in parallel, but they would now intersect.

The death of Muḥammad and its aftermath

Muḥammad died in early June 632 (AH 11) after a short illness. According to what emerged as the prevailing tradition, he left behind devoted followers, revelations that would subsequently be assembled into the Qur'an, clear views on matters of belief and action, and several wives and daughters; but no sons, successors or clear plan of succession. If this, the Sunnī tradition, is correct, one way to square Muḥammad's careful coalition building and prudent politics with the absence of any succession arrangement is to imagine that ensuring the success of his radical monotheism required holding to traditional tribal practices, which gave short shrift to authority that was purely inherited or transferred (rather than also earned). It may also be that, the community being so fragile, Muḥammad thought it unwise to make his wishes clear. Another is to posit on his part an impending sense of the End. There are other possibilities, but there is no way of choosing between them.

45 P. Crone, 'The first century concept of *Ḥijra*', *Arabica*, 41 (1994).

46 J. Howard Johnston, 'The official history of Heraclius' Persian campaigns', in E. Dabrowa (ed.), *The Roman and Byzantine army in the east: Proceedings of a colloquium held at the Jagiellonian University, Kraków in September 1992* (Crakow, 1994).

This is not to say that there is little to choose from: the sources of the eighth and ninth centuries have a great deal to say about the events that followed the Prophet's death. They do so not because Muslims shared a Christian fascination with death, but because it was in the events of 632 that the Sunnī Shī'ite divide would be anchored. Might it be that Muḥammad *had* appointed a successor? If not, who was present at the crucial moments after he died, when the fateful decisions were taken? Sunnīs answered the first question in the negative, holding that the community rallied around Abu Bakr, who, as both the first to convert and the most senior, was the natural choice. He would reign only briefly, from 632 to 634; unlike Muḥammad, however, he did appoint a successor, 'Umar ibn al Khaṭṭab, during whose ten year reign (634–44) the conquests exploded into the Fertile Crescent. Shī'a came to answer this question of succession in the affirmative, adducing a number of arguments that Muḥammad *had* appointed 'Alī as his successor: to the Shī'ite way of thinking, kinship ('Alī was Muḥammad's son in law and cousin) dictated it, and the facts were recorded not only by the historical record (Muḥammad presented 'Alī as his successor to assemblies of Muslims), but also scripture (where indications of Muḥammad's wish to appoint 'Alī are either read into the text or said to have been read out of it – that is, suppressed by the Sunnī tradition). For Sunnīs the succession arrangements were legitimate, if a bit chaotic, and the arrangements *ad hoc* – and this as late as 644, when an electoral conclave (*shura*) of six notables was chosen to elect 'Umar's successor. For Shī'a of the so called Rafiḍī variety, the succession amounted to a *coup d'état*: Abu Bakr, 'Umar and 'Umar's successor, 'Uthman, were all usurpers.⁴⁷

The tradition thus gave answers about who legitimately succeeded Muḥammad (or who did not). Written as it was by authors who lived under the direct or indirect patronage of eighth and ninth century caliphs, governors and rulers of various sorts, it takes for granted that the earliest Muslims should wish to fall behind a ruler. But since there was no tradition of stable rulership in either Mecca or Medina – had there been one, one imagines the succession to Muḥammad would have gone altogether more smoothly – we might wonder why so many of the tribesmen would have chosen to do so. (In describing the 'wars of apostasy', the *ridda* wars, when Arab tribes outside the Ḥijaz dissolved the treaties they had entered into with Muḥammad, the tradition concedes that many tribesmen did not.) The answer must be that

47 For a version of the Shī'ite case, see W. Madelung, *The succession to Muḥammad* (Cambridge, 1997).

belief was a strong compound, strengthened by the deep conviction that Muḥammad was a prophet acting for God, and that God rewarded those who held such a conviction in this world and the next. Worldly success was distinct from (and, according to some, inferior to) the Heavenly rewards of faith, but faith brought its rewards in the here and now as well. When the Umayyad commander and governor to be ‘Amr ibn al ‘Āṣ volunteered that he had converted, not out of any desire for wealth and possessions, but rather because of his devotion to Islam and Muḥammad, the Prophet responded: ‘How good is wealth righteously gained for a righteous man!’⁴⁸ From this perspective, we can see that believers had organised themselves into a polity that had enjoyed such miraculous success and generated such extraordinary resources that belief in its corporate survival survived Muḥammad’s death. What held the polity together was thus both belief in the next world and confidence in this one because of the rewards God offered through the spread of His dominion – that is, conquest. ‘The earth belongs to God, Who bequeaths it to whom He wishes amongst His servants’, as Q 7:128 puts it. The early Islamic polity survived in large part because it conquered.

If the conquest movement was an important ingredient in the success of early Islam, it is also very hard to describe. Neither their precise course nor their chronology can be established in any detail. In some instances, there is no prospect for recovering any authentic history; in others, a careful examination of the Arabic sources, combined with the judicious use of non Islamic sources when they are available, can lead to a reliable sequence, an outline chronology and a small handful of solid facts.⁴⁹ What follows is appropriately schematic.

As we have seen, Muḥammad’s *jihad* in the Ḥijaz was the ultimate inspiration for the conquests that would follow his death; but at least as far as Syria is concerned, their actual trigger seems to have been the small battles and skirmishes that are said to have broken out upon the Prophet’s death, when tribesmen repudiated treaties negotiated by Muḥammad.

The Islamic conquest of the Near East cannot be viewed, then, as something separate from the career of Muḥammad the Apostle or from the conquest of

48 M. J. Kister, ‘On the papyrus of Wab b. Munabbih’, *BSOAS*, 37 (1974), p. 559.

49 See L. I. Conrad, ‘The Conquest of Arwad: A source critical study in the historiography of the early medieval Near East’, in A. Cameron and L. I. Conrad (eds.), *The Byzantine and early Islamic Near East*, vol. I: *Problems in the literary source material* (Princeton, 1992); M. Hinds, ‘The first Arab conquests of Fars’, *Iran*, 22 (1984); C. F. Robinson, ‘The conquest of Khuzistan: A historiographic reassessment’, *BSOAS*, 67 (2004); C. F. Robinson, *Empire and elites after the Muslim conquest: The transformation of northern Mesopotamia* (Cambridge, 2000), chapter 1; the standard account remains F. M. Donner, *The early Islamic conquests* (Princeton, 1981).

Arabia during the *ridda* wars. It must be seen as an organic outgrowth of Muḥammad's teachings and their impact upon Arabian society, of Muḥammad's political consolidation, pursued by traditional and novel means, and especially of his efforts to bring nomadic groups firmly under state control, and of the extension of that process of consolidation by the Islamic state and its emerging élite under the leadership of Abū Bakr.⁵⁰

Commanders such as Khalid ibn al Walīd, Shurāḥbīl ibn Ḥasana and 'Arfaja ibn Harthama were accordingly sent out to Najd and beyond to the west and north, where the desert stretches into the Syrian steppe and southern Iraq. Extending power over Arab tribal groups thus brought Muslim armies within hailing distance of the two great powers of the day. And once in contact with imperial armies, the Muslims were extraordinarily successful. In three decisive battles in Syria (Ajnadayn, Fīḥl and, most important, Yarmuk), the back of the Byzantine defence was broken. The provincial city of Damascus fell around 636; within twenty five years, it would be the capital of the caliphate. The principal cities of northern Syria (Ḥimṣ, Aleppo, Qinnasrīn) followed suit soon after 636, as did Jerusalem, which 'Umar himself apparently visited; there, according to some accounts, he led prayers and began the construction of a mosque.⁵¹ From the occupation of Palestine that followed sprang a separate conquest movement to Egypt led by 'Amr ibn al 'Āṣ, in the course of which Alexandria fell in 642; Muslims would establish their main garrison in Fustāṭ, towards the southern edge of current day Cairo.

Alongside the conquest of Syria took place the conquest of Iraq, which was apparently opened from the south. After a disastrous defeat at the battle of the Bridge in late 634, the Muslims sent Sa'd ibn Abī Waqqāṣ in command of a relatively large army, which he led to al Qadisiyya, a small settlement lying south west of al Ḥīra. There, in Muḥarram (February or March) of either 636 or 637, the Sasanian commander Rustam was routed. Soon thereafter came the defeat of the Sasanians at Jalula', and then, also in 637, fell al Mada'in (Ctesiphon), the Sasanian capital. With the fall of Nihawand (641), the Sasanian defence collapsed entirely, forcing the Sasanian shah, Yazdegerd, to flee to Khurasan, where he was murdered in 651. By the late 630s or very soon after, the two garrisons of Baṣra and Kufa had been founded; both would grow into major cities. Meanwhile, northern Mesopotamia had by around 640 fallen

50 Donner, *Early Islamic conquests*, p. 90. On the matter of the Islamic 'state', see below.

51 See H. Busse, 'Omar b. al Ḥaṭṭab in Jerusalem', *JSAI*, 5 (1984).

to armies marching from the Syrian steppe in the west and armies marching up the Tigris from the south. The conquest movement did not end in the early 640s – it seems that it was not until well into the 650s that a measure of control over the Mediterranean islands of Cyprus, Rhodes and Crete was extended, and ‘Uqba ibn Nafi’ projected Islamic rule further west in north Africa in the 660s and 670s – but the first great push had ended. The Sasanian empire had collapsed, and the frontiers with Byzantium would remain relatively stable for centuries.

What explains the success of the early conquests? The size of the armies is impossible to measure with any accuracy. Some Christian sources, which are generally keen to exaggerate the catastrophe of the defeat, speak of extraordinary casualties: a contemporaneous Syriac account has 50,000 killed in a single battle in Syria; another early source, which was probably written some time in the 670s, has the Arabs kill no fewer than 100,000 Byzantines in Egypt.⁵² The figures given by the Islamic sources for the numbers of combatants are generally much more reasonable, often in the hundreds or low thousands; even a large army, such as the one that fought at al Qadisiyya, probably numbered no more than 10,000 or 12,000 men.⁵³ These more modest armies, which would be much easier to provision and manage, make considerably more sense. Since there is no good evidence for any substantial reduction in Byzantine manpower (and virtually no evidence at all for Sasanian numbers, reduced or otherwise),⁵⁴ it is probably safe to assume that Muslims were often outnumbered. Unlike their adversaries, however, Muslim armies were fast, agile, well coordinated and highly motivated. The speed of the conquests on both fronts – as we have seen, the decisive battles took place in the space of four or five years – also suggest that, whatever their numbers, both the Byzantine and Sasanian defences were brittle. In contrast to the large scale, resource intensive and protracted campaigns that were so typical of Byzantine Sasanian warfare of the sixth and early seventh centuries, and which in at least some places resulted in widespread violence and social dislocation,⁵⁵ the Islamic conquests of the mid seventh century read like a series of relatively short engagements (the great battle of al Qadisiyya is

52 Robinson, ‘Khuzistan’, p. 39.

53 Donner, *Early Islamic conquests*, p. 221.

54 C. Whitby, ‘Recruitment in Roman armies from Justinian to Heraclius (ca. 565–615)’ in A. Cameron (ed.), *The Byzantine and early Islamic Near East*, vol. III: *States, resources and armies* (Princeton, 1995), pp. 120–2.

55 For Asia Minor, see C. Foss, ‘The Persians in Asia Minor and the end of Antiquity’, *The English Historical Review*, 90 (1975); for Syria, see below, note 58.

said to have lasted three days), which were made by relatively small and hit and run armies that rarely laid sieges of any length or produced casualties in large numbers. In many and perhaps most cases in the Byzantine provinces, local elites cut deals that avoided large scale violence. Modern descriptions of systematic conquest era violence targeted at non Muslims, in addition to those of post conquest persecution before the Marwanids, are usually nothing more than poorly disguised polemics.⁵⁶

If the historical tradition would have us infer that large scale mortality and dislocation were very occasionally the exception to a general rule, the archaeological evidence clinches this inference. Unlike the barbarian invasions of the fourth and fifth century western Mediterranean,⁵⁷ the effects of the Islamic conquests were in many respects modest. There is a fair amount of regional variation, but there is no sure archaeological evidence for destruction or abrupt change in settlement patterns that we can directly associate with the events of the 640s and 650s. In Palestine and Syria, where rural settlement seems to have reached a peak in the middle or late sixth century, the conquests bore no impact upon a decline that had apparently begun before they took place.⁵⁸ In Syria, we also know that transformations in urban space that earlier generations of historians had attributed to Muslim rule may have actually been under way before the Muslims arrived.⁵⁹ Patterns of occupation and use in the towns of the northern Negev, to take an example that is particularly striking, seem to carry on through the seventh century with little appreciable change; the story changes in the course of the eighth and ninth centuries, when decline sets in, presumably accelerated by the shift of the caliphate to Iraq, although the earthquake of 747 had deleterious effects elsewhere.⁶⁰ The evidence is very poor for Iraq, but there, too, archaeology suggests that

56 See B. Ye'or, *The decline of Eastern Christianity under Islam: From jihad to dhimmitude* (Cranbury, NJ, 1996); cf. D. J. Constantelos, 'The Moslem conquests of the Near East as revealed in the Greek sources of the seventh and eighth centuries', *Byzantion*, 42 (1972).

57 For a provocative discussion of the west, see B. Ward Perkins, *The fall of Rome and the end of civilization* (Oxford, 2005).

58 See C. Foss, 'Syria in transition, AD 550–750: An archaeological approach', *Dumbarton Oaks Papers*, 51 (1997); C. Foss, 'The Near Eastern countryside in Late Antiquity: A review article', *The Roman and Byzantine Near East: Journal of Roman Archaeology*, supplementary series 14 (1995); A. Walmsley, *Early Islamic Syria: An archaeological assessment* (Bath, 2007), esp. pp. 44ff.

59 H. Kennedy, 'From polis to madina: Urban change in Late Antique and early Islamic Syria', *Past and Present*, 106 (1985); but cf. J. Magness, *The archaeology of the early Islamic settlement in Palestine* (Winona Lake, IN, 2003), and Walmsley, *Early Islamic Syria*, pp. 37f.

60 Such as in parts of Palestine, on which see Magness, *Early Islamic settlement*; cf. Fihl (Pella) in A. Walmsley, 'The social and economic regime at Fihl (Pella)', in P. Canivet and J. P. Rey Coquais (eds.), *La Syrie de Byzance à l'Islam* (Damascus, 1992), p. 255.

conquest effects were far from catastrophic.⁶¹ Of course the shift of the caliphate from Syria to Iraq may have resulted at least in part from underlying economic changes, but precisely how the political history of the early caliphate relates to the economic history of the Near East remains unclear. It is certainly the case that locating the centre of the caliphate in Syria, which was enjoying an Indian summer of a flourishing eastern Mediterranean economy, initially made much more sense than doing so in or around the Gulf, which had apparently suffered several centuries of economic decline.⁶² In this connection it is noteworthy that the political frontier in northern Syria that would long separate Byzantium from the caliphate, unlike the political frontier that had separated Byzantium from the Sasanian empire, appears to coincide with an economic (and geographic) frontier that had separated Anatolia from Syria on the eve of the Islamic period. If the waves of conquest only reached as far as the highest tide of economy had reached earlier, one might think that economy and conquest *were* fairly closely related.⁶³

Whatever the precise course of victory, to the victors went the spoils. How much wealth came into the hands of the Muslim conquerors? We know that churches and monasteries possessed objects of great value, and major Byzantine cities such as Damascus, Antioch, Edessa, even more so the Sasanian capital, Ctesiphon, must have had very considerable wealth, perhaps especially in the form of silver.⁶⁴ Although we read that Byzantine elites moved north in advance of Muslim armies, and that the conquering Muslims found al Mada'in empty of Sasanian royalty and their retainers, not everyone with movable wealth had the time or the inclination to take it with them. Indeed, it must be that many more stayed behind; and many who did leave would have left their wealth behind, as some of the hoards of coins deposited during the seventh century suggest.⁶⁵ That all the wealth added up is made clear if we consider that the first step in the direction of a rudimentary administrative system was taken in 'Umar ibn al Khaṭab's establishment of a

61 M. Morony, 'The effects of the Muslim conquest on the Persian population of Iraq', *Iran*, 14 (1976).

62 On the archaeological evidence from the western Gulf, see D. Kennet, 'On the eve of Islam: Archaeological evidence from eastern Arabia', *Antiquity*, 79 (2005).

63 M. Morony, 'Economic boundaries? Late Antiquity and early Islam', *JESHO*, 47 (2004), p. 180.

64 See, for example, S. Boyd and M. Mango (eds.), *Ecclesiastical silver plate in sixth century Byzantium* (Washington, DC, 1992).

65 On some early seventh century hoards, see S. Heidemann, 'The merger of two currency zones in early Islam: The Byzantine and Sasanian impact on the circulation in former Byzantine Syria and northern Mesopotamia', *Iran*, 36 (1998), p. 96; cf. R. Gyselen and L. Kalus, *Deux trésors monétaires des premiers temps de l'Islam* (Paris, 1983).

bureau (*dīwan*) to measure and redistribute conquest booty among the tribesmen.⁶⁶ The principle of distribution described to us by our sources is called 'precedence' (*sabiqa*), according to which the earlier in the conquest movements a given tribesman enrolled, the higher his annual stipend (*'aṭa'*). We read that a stipend of 3,000 *dirhams* was awarded to soldiers who had participated in the earliest raids into Iraq, while those who took part in the campaigns leading up to the crucial battle of al Qadisiyya in Iraq, which was the turning point in the war against the Sasanians, received 2,000.⁶⁷ Whatever the accuracy of these figures, it is clear that the wealth of many early Islamic families was rooted in conquest era spoils and booty.

Of course, most of the wealth available to the conquerors was immovable because it came in the form of land. Much of the most productive land was Crown Land, and this, in addition to the land owned by local elites (including bishops and monks), became available to conquering Muslims through abandonment and confiscation. In the Sawad – the 'black' area of alluvial soil in central and southern Iraq, where information is fullest – Crown Lands included not only all the properties of the Sasanian royal house, but also those attached to fire temples, post houses and the like; 'Umar is said to have distributed four fifths to the soldiers and kept one fifth as his share as caliph, which was to be used for the benefit of the community. As far as labour was concerned, 'Umar's policy was conservative: the peasants were left to work the land, this being part of a more general *laissez faire* style of ruling, in which non Muslims – who in the first decades of Islamic rule were generally lumped together with non Arabs – enjoyed wide ranging autonomy. Elsewhere abandoned lands were snatched up, and lands owned by those who had resisted (or could be said to have resisted) the conquests were confiscated. It may be that redistribution to conquering tribesmen was left to the discretion of local authorities; in some cases (such as well irrigated – and thus valuable – land in the northern Mesopotamian city of Mosul), it is clear that 'precedence' was in operation, as we would imagine it to be: first come, first served; the best lands often went to the earliest settlers, although there was no land grab, it appears.

Whatever the value of the booty and confiscated land, conquerors and conquered alike had to make sense of the momentous events. For Muslims, the conquests demonstrated God's continued participation in human affairs (the Islamic sources typically have it that God 'conquered by the hands of the

66 See G. Puin, *Der Dīwan von 'Umar ibn al Ḥaṭṭab: Ein Beitrag zur frühislamischen Verwaltungsgeschichte* (Bonn, 1970).

67 For an overview of this system, see Donner, *Early Islamic conquests*, pp. 231–2, 261–2.

Muslims'). The conquests were compelling proof that Muslims enjoyed God's favour and generosity. What could be more persuasive than the enormous bounty of booty taken from Ctesiphon, where the Shah's storehouses were thrown open and all manner of treasure – precious metals, vessels, garments, regalia, even foodstuffs – carried off? Arabian tribesmen were inheriting the riches of empire:

We marched into al Madā'in and came upon Turkish tents filled with baskets sealed with leaden seals. At first, we did not think they would contain any thing but food, but later they were found to contain vessels of gold and silver. These were later distributed among the men. At the time ... I saw a man running and shouting, 'Who has silver or gold in his possession?' We also came upon large quantities of camphor which we mistook for salt. So we began to knead it (in our dough) until we discovered that it made our bread taste bitter.⁶⁸

The Qur'an had made clear that God delivered bounties in this world and the next. Delivering dominion was one of these bounties. Accounts that enumerated the great treasure and booty that fell into Muslim hands thus functioned to illustrate the rewards that God delivered to His believers, and also to contrast the piety and *naïveté* of early Muslims with the wealth-induced arrogance and complaisance of the empires that they had conquered.

Of course things were very different for non-Muslims. Here the events of the conquests were typically assimilated into pre-existing patterns of monotheistic history, and the agents of those conquests, the 'Arabs', 'Saracens' or 'Hagarenes', were assimilated into ready categories of monotheistic belief. In other words, the conquests were proof of God's wrath, and Muslims were heretical monotheists. Put another way, although the deep syntax of historical explanation – history is made as God operates through men – was shared by all monotheist historians, whether Muslim or Christian, for non-Muslim monotheists the events signalled a wrathful rather than a merciful God. As early as about 634, the patriarch of Jerusalem wrote of the 'Saracens who, on account of our sins, have now risen up against us unexpectedly and ravage all with cruel and feral designs, with impious and godless audacity'.⁶⁹ Twenty or thirty years later, a chronicler in northern Mesopotamia asked: 'How, otherwise, could naked men, riding without armour or shield, have been able to win, apart from divine aid, God having called them from the ends of the earth so as to destroy, by them, "a sinful kingdom" [i.e. Byzantium] and to bring

68 Al Ṭabarī, *Ta'rikh*, series II, pp. 244f. trans. G. H. A. Juynboll as *The history of al Ṭabarī*, vol. XIII: *The conquest of Iraq, southwestern Persia, and Egypt* (Albany, 1989), p. 24.

69 Hoyland, *Seeing Islam*, p. 69.

low, through them, the proud spirit of the Persians?⁷⁰ Daniel's apocalyptic vision proved especially accommodating to Christians struggling with the significance of the conquests and early Islamic rule. Thus Daniel conditions the words of an Armenian chronicler writing some time in the early 660s: 'I shall describe the calamity which beset our time, the rupture of the vein of the old south and the blowing on us of the mortal hot wind which burned the great, leafy, beautiful, newly planted trees of the orchards. This [happened] rightly, because we sinned against the Lord and we angered the Holy One of Israel.'⁷¹

Muslims thus drew very different lessons from the spectacular success of the conquests; for them, it was in post conquest events – the first, great civil war (*fitna*) of the 650s – that God came to express His disfavour. Disunity among Muḥammad's successors imperilled the successes that his unifying vision had produced.

The early caliphate: succession, civil war and opposition movements

In Islamic historiography of the eighth and ninth centuries, the civil war between 'Alī and Mu'awiya is a topic of enormous interest, Shī'a and Sunnīs taking their respective sides and narrating contrasting accounts. For many Muslims of this and later periods, the *fitna* marked a decisive break: before it, the short but inspired moment of the time of the Prophet, the conquests, just rule and political unity; after it came the altogether more ambivalent and controversial periods of Umayyad and 'Abbasid rule. Because the events of the *fitna* were accordingly shaped and re shaped in historical narrative,⁷² knowing exactly what happened is out of the question, even if names can be identified and alignments sketched out.⁷³ Still, there can be little doubt that the

70 S. P. Brock, 'North Mesopotamia in the late seventh century: Book xv of John Bar Penkaye's *Riṣ Melle'*, *JSAI*, 9 (1987), pp. 57–8.

71 Sebeos, *Armenian history*, vol. I, p. 132; in general, H. Suermann, *Die geschichtstheologischen Reaktion auf die einfallenden muslimen in der edessenischen Apokalypstik des 7. Jahrhunderts* (Frankfurt, 1985).

72 E. L. Petersen, 'Alī and Mu'awiya in early Arabic tradition: *Studies on the genesis and growth of Islamic historical writing until the end of the ninth century*, 2nd edn (Odense, 1974 [Copenhagen, 1964]); R. S. Humphreys, 'Qur'anic myth and narrative structure in early Islamic historiography', in F. M. Clover and R. S. Humphreys (eds.), *Tradition and innovation in Late Antiquity* (Madison, 1989); B. Shoshan, *Poetics of Islamic historiography: Deconstructing Ṭabarī's History* (Leiden, 2004), pp. 173ff.

73 M. Hinds, 'Kufan political alignments and their background in the mid seventh century AD', *IJMES*, 2 (1971); for a very different view, see Madelung, *Succession*.

significance of the dreadful events – murder, Muslim set against Muslim, a divided caliphate – was recognised in its day. As an Armenian chronicler, writing within a generation of the events, put things: ‘Now God sent a disturbance amongst the armies of the sons of Ishmael, and their unity was split. They fell into mutual conflict and divided into four sections ... They began to fight with each other and to kill each other with enormous slaughter.’⁷⁴ Seventh- and early eighth-century Syriac historians were equally impressed, borrowing the Arabic term, *fitna*, a term which presumably was in broad circulation among Muslims of the period. In sum, the significance of the *fitna* is hard to overstate.⁷⁵

What does *not* seem to have been at issue – at least for those who took their principles seriously enough to try to apply them – was how God’s authority was to be effected after the Prophet had died.

Our relatively late sources generally reflect ninth- and tenth-century realities, when caliphs functioned for the most part as guardians of a society with a more or less independent religious elite. The earlier evidence shows, however, that virtually all shared the view that the office of the caliphate combined religious and political authority, and that the caliph provided salvation to those who paid him allegiance. For most, the age of prophets had come to an end, succeeded by the age of caliphs, whose status was equal (and, according to some, superior) to that of the prophets. The caliph led the community in this world towards the next one: he was ‘the *imam al huda*, an imam of guidance who could be trusted to show his followers the right paths. He was compared to way marks, lodestars, the sun, and the moon for his ability to show the direction in which one should travel.’⁷⁶ Early disagreement, then, lay not in the powers that the caliph was to exercise, but in the person (or family) who was to exercise those powers.

Civil war was thus about succession to the office of caliphate, which all Muslims acknowledged should be the ruling institution of the nascent state. We have seen that amidst the chaotic atmosphere of Muḥammad’s death, Abu Bakr had been acclaimed as caliph, and he, in turn, had designated ‘Umar as his successor. This engendered very little debate, since, according to tradition, ‘Umar had been so close to the Prophet: his name had even been mooted directly after Muḥammad’s death. For his part, ‘Umar nominated a group of six men who were to choose his successor: this group included ‘Alī, ‘Uthman and

74 Sebeos, *Armenian history*, vol. I, p. 154.

75 See H. Djait, *La grande discorde: Religion et politique dans l’Islam des origines* (Paris, 1989).

76 Crone, *Political thought*, p. 22; P. Crone and M. Hinds, *God’s caliph: Religious authority in the first centuries of Islam* (Cambridge, 1986).

(usually) four other figures, two of whom were al Zubayr ibn al 'Awwam and Ṭalḥa ibn 'Ubayd Allah, both revered as close Companions of the Prophet himself. This electoral conclave (*shura*) produced 'Uthman, a Qurashī who belonged to the Umayyad clan that had earlier been so resistant to Muḥammad's preaching in Mecca. 'Uthman did not prove to be a popular choice: initial resentment was fuelled by his family's chequered past and the disappointment felt by those who supported the claims of 'Alī. This resentment was compounded by his uninspiring character and conduct: according to our sources, he accepted gifts, which were called bribes, and appointed kinsmen to important (and lucrative) posts, a practice that was branded nepotism. All this emboldened his opponents, and in June 656, while reading the Qur'an, 'Uthman was murdered. 'Alī's supporters immediately acclaimed him as the caliph in the Prophet's Mosque in Medina.

The problem for 'Alī was that he never enjoyed much support outside Medina and Kufa. Almost immediately upon his accession he was challenged by Ṭalḥa and al Zubayr, who were joined by 'Ā'isha, the most influential of the Prophet's surviving wives. The three gathered an army and engaged 'Alī in what history would come to call 'the battle of the Camel', after the memory of 'Ā'isha, posed as she purportedly was upon a camel; this battle took place in December 656 in Iraq. 'Alī was victorious, but it was a Pyrrhic victory, the principal cost being to his reputation. More pious and gentle than he was shrewd, 'Alī was quickly outmanoeuvred by Mu'awiya, 'Uthman's governor of Syria, who argued that the murderers of 'Uthman had gone unpunished. He is said to have displayed to a Damascus crowd 'Uthman's bloody shirt and the fingers of a wife, which were severed as she tried to defend her husband. Mu'awiya's challenge to 'Alī soon led to the battle of Ṣiffin, which lay on the Euphrates south of al Raqqa, in 657. The two armies hesitated to fight, and when they finally did, tradition tells us that 'Alī, though on the verge of victory, agreed to a truce. Arbitrators were chosen, and although the events are unclear, it seems that they agreed that neither 'Alī nor Mu'awiya was fit to rule. As caliph, 'Alī had everything to lose from this decision, which was taken in 659, while Mu'awiya had everything to gain from it. In its wake 'Alī was hopelessly weak; within two years he had been murdered, and Mu'awiya was proclaimed caliph in Jerusalem (or Damascus) in 660 1. The civil war had ended. Mu'awiya would rule for nearly twenty years.

If the trigger for civil war was a dispute about succession and the killing of a just (or unjust) caliph, the underlying causes were rooted in patterns of post conquest settlement and competing models of status and privilege. It seems that the conquest polity had growth pains. In crude terms, 'Umar's policy of

'first come, first served' had meant a system that favoured the *muhajirun* those who had joined Muḥammad early on at the expense of those who had enjoyed high prestige in the clan based social order of the pre Islamic period. As the initial surge of the conquests ebbed, tensions rose, particularly over the terms on which tribesmen believers would negotiate their status. We can see this most clearly in Kufa, where the status of older settlers, who possessed 'precedence', began to be challenged by more recent settlers, who in some cases were being paid higher and higher stipends. As a result, the older settlers came to oppose not only these parvenus, but also the Umayyad governors who had permitted them to settle. In the long term, the effective bonds of kinship symbolised most clearly by the *ashraf* (tribal chiefs), who emerged victorious would dissolve, as tribesmen settled in far flung towns and cities, and took up a variety of professions and vocations. But this took some time, and a modified kinship politics of the old style was carried out by these *ashraf*, who, either chosen or acclaimed because they could wield influence among fellow kinsmen, received the salaries, favours and gifts of the caliph, in return for which they offered their loyalty and ability to muster tribal units on his behalf.⁷⁷ It took the death of Mu'awiya and a second civil war that broke out in 683 to demonstrate that the *ashraf* had outlived their usefulness.

Kinship politics of this variety was thus cultivated by Mu'awiya, and it had a relatively short shelf life. Of much more enduring significance were two religio political movements that issued from these early disputes about succession and the events of the first *fitna*, and that would mature during the second *fitna*. Shī'ism and Kharijism flourished as powerful movements of opposition to the Umayyad clan, which staked its claim to the caliphate, first with 'Uthman in 644, and second and considerably more successfully with Mu'awiya, who began to rule in 661, and who would name his son Yazīd ibn Mu'awiya as heir apparent shortly before he died in 680. Several things distinguished the Shī'a and Kharijites, but we can start with what they had in common.

Although Shī'a and Kharijites alike shared with the Umayyads the emerging conception of the caliphate, as opposition movements concentrated in the garrison towns of southern Iraq they both fed off resentment towards the Umayyads, whose late conversion had made them appear opportunistic and cynical in the past, and whose heavy handed and iniquitous policies, on the one hand, and alleged impiety, on the other, made the present intolerable too. They accordingly held that the Umayyads were entirely unqualified to occupy the

⁷⁷ Hinds, 'Kufan political alignments'; P. Crone, *Slaves on horses: The evolution of the Islamic polity* (Cambridge, 1980), pp. 30–2.

office. To most Shī'a and all Kharijites, then, Abu Bakr and 'Umar had ruled legitimately, but things went very wrong with the first Umayyad, 'Uthman (some Shī'a came to hold that the Prophet had designated 'Alī, which meant that even Abu Bakr and 'Umar were usurpers). Although the Umayyads would eventually fall to an 'Abbasid movement that was in some measure Shī'ite in inspiration, neither movement had any success in replacing Umayyad imams with imams of their own, and they survived into classical Islam only in so far as they were able to reconcile themselves to what became, during the course of the eighth and ninth centuries, Sunnī rule. In practice this eventually meant exchanging revolution for secession and political activism for sectarian quietism, a process that was nearly complete by the end of the ninth century.

If the Shī'a and Kharijites shared some common concerns, they differed in others. The chief difference lay in the qualifications they attached to the office of the caliphate. The Shī'a, who were numerous in Kufa, insisted on kinship, holding that their imams had to be drawn from the Prophet's family. Since Muḥammad had left no male heirs, in practice this meant candidates from the clan of Hashim, which included descendants of al 'Abbas (the Prophet's uncle) and the relatives and descendants of 'Alī (Muḥammad's cousin and son in law). Throughout the Umayyad period, candidates for the imamate came from several different branches of the Hashim clan, and the 'Abbasid revolution of 750 was successful in no small part because it capitalised upon the view that the 'Abbasid family might offer such candidates. But for some Shī'a the field would by the end of the seventh century begin to narrow towards the line that issued from 'Alī himself, and what would turn out to be the most important lines ran through al Ḥusayn (a son of his marriage with the Prophet's daughter Faṭima), who led a spectacularly unsuccessful rebellion near Kufa in 680, and through Muḥammad ibn al Ḥanafiyya (a son from a concubine), in whose name a nebulous figure named al Mukhtar led an altogether more successful rebellion seven years later. (There were some exceptions, most notably a mid eighth century rebellion led by a descendant of 'Alī's brother, but most Shī'ite rebellions were no more successful than these.) The line that ran from al Ḥusayn through Musa al Kazim (d. 799) would in the long term emerge as the single most important of three main Shī'ite branches (the Twelvers or Imāmīs, Zaydīs and Isma'īlīs); it would come to an end only in the late ninth century, when, allegedly, the twelfth and last of these imams disappeared into occultation. But it was from Muḥammad ibn al Ḥanafiyya that the most successful of all Shī'ite movements – the 'Abbasids – would claim to have inherited the imamate. By the time of the 'Abbasid revolution (750), genealogical claims had come to be buttressed by historical claims: not only was 'Alī said to have been designated by

the Prophet, but successive imams were said to be designating their successors. Thus the 'Abbasids claimed that they inherited the imamate from a descendant of Muḥammad ibn al-Ḥanafiyya, according to his last will and testament.⁷⁸

The Shī'a were thus devoted to a family in general (the Hashimīs) and a person in particular ('Alī), and this devotion is neatly expressed by their appellation: *shī'ī* ('partisan of 'Alī'; 'Shī'ite') derives from *shī'at* 'Alī, 'the party of 'Alī'. The Shī'a's 'Alid imams came to be endowed not only with religious authority, but also characteristics that others associated with prophets and holy men, such as inerrancy and foresight. In so far as early Shī'a had a political programme, it lay in rebellion for the sake of restoring effective political rule to the family of the Prophet – the rest would take care of itself. By contrast, the Kharijites were committed not to a family, but to an idea, and this is neatly expressed by their most common appellation: a *kharijī* is 'one who goes out [to fight on behalf of God]', just as a *muḥakkim* (a rarer Kharijite label) is one who proclaims that 'there is no judgement but God's', a slogan associated with the battle of Ṣiffin, where the Kharijites, pinning Qur'ans to their lances, abandoned 'Alī. According to the Kharijite way of looking at things, 'Alī had fatefully agreed to respect the 'judgement' of men by agreeing to enter into arbitration. If the slogan was clearly potent, we cannot say why, although it may constitute very early evidence for scripturalist attitudes that characterised Kharijite thought of a later period, especially as it is reflected in the Ibaḍī literature, which is the only Kharijite tradition to survive.⁷⁹ In any event, within a year (658) 'Alī had defeated his Kharijite opponents at the battle of Nahrawan, but far from ending the Kharijite threat, the defeat inspired more tribesmen to rebel. As we shall see, in the second *fitna* and the early Marwanid period that would follow it, Kharijites would challenge Umayyad authority and effective power.

Under whose leadership did the Kharijites 'go out' to fight on behalf of God's 'judgement'? For those who made the case for the Umayyads, Qurashī blood was sufficient, while those who made the Shī'ite case insisted upon Hashimī blood; the Kharijites imposed no genealogical restrictions whatsoever on their imams, insisting for the most part that merit and merit alone was determinant. This

78 For an overview, Crone, *Political thought*, pp. 87–94; more generally, H. Halm, *Shiism* (Edinburgh, 1991).

79 G. R. Hawting, 'The significance of the slogan *la ḥukma illa lillāh* and the references to the *ḥudūd* in the traditions about the *fitna* and the murder of 'Uthman', *BSOAS*, 41 (1978); M. Cook, 'Anan and Islam: The origins of Karaite scripturalism', *JSAL*, 9 (1987), pp. 169–72. On the Kharijites more generally, see P. Crone and F. Zimmermann, *The epistle of Salim ibn Dhakwan* (Oxford, 2001); K. H. Pampus, *Über die Rolle der Ḥarīḡīya im frühen Islam* (Wiesbaden, 1980).

repudiation of kinship is striking, and must reflect the egalitarian thinking of those living in Baṣra and Kufa more than that of the Kharijite tribesmen who had broken off from 'Alī and who, often operating in kinship groups (the Shayban and Tamīm tribes produced many Kharijites), rebelled against Umayyad and early 'Abbasid rule. Just how committed these tribesmen were to Kharijite ideals of merit is hard to know; what is clearer is that Kharijite bands were committed to violent rebellion according to a fairly consistent pattern: secession through emigration (*hijra*) and *jihad* against those whom they considered unbelievers. (In some exceptional cases, the Kharijite commitment to violence extended to non combatant women and children.) In practising emigration and *jihad*, the Kharijites were falling foul of the Umayyads, but they were holding fast to ideas that had powered Muḥammad and his contemporaries out of Arabia.⁸⁰ That they had so little success says something about how quickly things had changed in the space of a couple of generations.

The early Islamic polity: instruments and traditions of rule in the Sufyanid period

We saw earlier that 'Umar (r. 634–44) is credited with establishing the first *dīwan*, which distributed stipends to conquering soldiers. Several other administrative innovations are similarly ascribed to the second caliph, such as the introduction of the Muslim calendar and the office of the *qaḍī* (judge). So, too, is an indulgent and conservative fiscal policy towards indigenous cultivators: taxes were kept reasonable, the peasants left undisturbed, and the remnants of the Byzantine and Sasanian bureaucracies left intact. Fewer such innovations are attributed to the altogether more controversial 'Uthman and 'Alī. With the longer and more stable reigns of Mu'awiya (r. 661–80) and 'Abd al Malik (r. 685–705), the innovations appear with greater frequency: the former is commonly credited with establishing a number of other *dīwans*, and the latter with a wide range of administrative and bureaucratic measures. These include translating the tax documents from Greek and Persian into Arabic, and reforming weights, measures and coins, as we shall presently see.

The tradition, in sum, lays the foundation of the Islamic state in the inspired rule of the second of the four 'rightly guided caliphs', and describes its growth as evolutionary.⁸¹ Does it have things right? The material and documentary

⁸⁰ Robinson, *Empire and elites*, pp. 109–26.

⁸¹ For a modern version, see A. Ibrahim, *Der Herausbildungsprozeß des arabisch islamischen Staates* (Berlin, 1994), esp. pp. 163ff.

evidence tells a story that is different from that of the tradition – a story of deferred revolution, rather than gradual evolution.

The conquerors put in place a rudimentary system for the redistribution of conquest resources among the tribesmen, and tribal chieftains (*ashraf*) played a crucial role in the overlapping networks of indirect rule that characterised Mu‘awiya’s caliphate. Similarly rudimentary was the division of authority in the newly conquered territories: the caliph seems to have ruled northern Mesopotamia, Syria, Palestine and Arabia directly, and the rest of the empire was divided into three huge governorships: North Africa and Egypt; Baṣra and those eastern provinces associated with it; and Kufa and associated provinces. By later Umayyad and ‘Abbasid standards, administrative geography was thus undifferentiated and monolithic. So, too, were administration and bureaucracy. Governorships were awarded for a number of reasons, but kinship was always a criterion; and when genuine kinship was lacking, it was invented, as in the case of a famous governor of Baṣra, Ziyad ibn Abīhi (‘Ziyad, the son of his father’), whose services were so valuable to Mu‘awiya that the caliph made him a foster brother.⁸² (Mu‘awiya himself married into the Kalb tribe, thus consolidating his tribal support in Syria.) Sitting in small courts atop rump bureaucracies, his governors seem to have enjoyed broad and undifferentiated civil and military authority; the law remaining underdeveloped and authority undifferentiated, they played roles that would subsequently be played by judges, tax collectors and commanders of the later Marwanid and ‘Abbasid periods. Moreover, such power as Mu‘awiya and his governors possessed was mediated by tribal chiefs, upon whom they relied to raise armies, and non-Muslim local elites, upon whom they relied to raise taxes.⁸³ Gifting and bestowing favours and privileges were the currency of these transactions. Similarly, non-Muslim subject populations generally did not experience Islamic rule, or experienced it only indirectly: local authority was usually in the hands of non-Muslim authorities, and Mu‘awiya seems to have been considered a benevolent, hands-off ruler.⁸⁴

That Mu‘awiya apparently handled the *ashraf* as in some measure as *primi inter pares* does not mean that he failed to develop a language of caliphal authority. As the seat of the caliphate moved from Medina to Kufa to

82 On Ziyad and his rule in the east, see M. Morony, *Iraq after the Muslim conquest* (Princeton, 1984), *passim*.

83 Crone, *Slaves on horses*, pp. 30–3.

84 For northern Mesopotamia and Iraq, see Robinson, *Empire and elites*, pp. 33–62; Morony, *Iraq*; for Egypt, K. Morimoto, *The fiscal administration of Egypt in the early Islamic period* (Kyoto, 1981).

Damascus – that is, from a corner of Arabia to one of Late Antique Syria's major cities – ideas of authority and rule naturally transformed to some degree. Such as it is, the evidence does suggest that Mu'awiya innovated in ways that anticipate the later caliphate. According to the historical tradition, which is generally less than sympathetic to the caliph, Mu'awiya introduced, *inter alia*, the *maqṣura* (a private enclosure inside the mosque), a number of ceremonial practices, and a caliphal guard. Although the epigraphic record leads back to the 640s, it was Mu'awiya who appears to have been the first caliph to publicise his name and claim to rule: already in 662 or 663, his name and title appear in Greek in a monumental inscription in Palestine ('Mu'awiya, commander of the believers'), and other examples (from Egypt and Arabia) follow in graffiti, coins and papyrus protocols.⁸⁵ It is also with Mu'awiya that a record of correspondence begins – much spurious, but some at least partially authentic – between the caliph and his neighbouring sovereigns, Constans II (r. 641–68) and Constantine IV (r. 668–85).⁸⁶ Although nothing remains of it, Mu'awiya's palace in Damascus was apparently an impressive building complex, which announced itself clearly enough in the formerly Byzantine capital;⁸⁷ like other Syrian properties of his, it would be reoccupied by subsequent caliphs, including 'Abd al Malik. The evidence is very thin, but it may even be that the ingredients for what became the standard form of the mosque – a large courtyard enclosure with a hypostyle hall at one end – were first mixed in Iraq during Mu'awiya's reign.⁸⁸ In sum, he may have come to power through civil war, but his vision – of caliphal rule projected from Syria principally by Syrian tribesmen – was a powerful one, which survived nearly a century after his death.

Still, if ideas of authority and rulership were transforming during the reign of Mu'awiya, the instruments of power and persuasion remained relatively undeveloped. Mu'awiya's was a conquest polity in which regionalism was the rule;

85 J. Johns, 'Archaeology and the history of early Islam: The first seventy years', *JESHO*, 46 (2003), pp. 419–20; cf. R. Hoyland, 'New documentary texts and the early Islamic state', *BSOAS*, 69 (2006).

86 For a survey and discussion, see A. Kaplony, *Konstantinopel und Damaskus: Gesandtschaften und Verträge zwischen Kaisern und Kalifen 639–750* (Berlin, 1996).

87 For a description, see F. B. Flood, *The Great Mosque of Damascus: Studies on the makings of an Umayyad visual culture* (Leiden, 2001), pp. 147ff.

88 For reconstructions of the Kufan mosque, which was built, according to tradition, by Ziyad ibn Abihi, see B. Finster, *Frühe iranische Moscheen* (Berlin, 1994), pp. 23f.; and J. Johns, 'The "House of the Prophet" and the concept of the mosque', in J. Johns (ed.), *Bayt al Maqdis: Jerusalem and early Islam*, Oxford Studies in Islamic Art 9, part 2 (Oxford, 1999), pp. 64f. The appearance of the *mihrab* is less clearly datable to the Sufyanid period; see Finster, *Moscheen*, pp. 113ff.; and Flood, *Great Mosque of Damascus*, p. 194.

an ambitiously centralising state, one that patronised not only building projects on an unprecedented level, but also relatively stable institutions, emerged only during the reign of ‘Abd al Malik. This – the very modesty of very early Islamic rule – is clearly reflected in the coinage.

Although circulation and minting patterns are clearer in the former Byzantine provinces than they are in the east, undated issues make sequences and chronologies difficult to establish and highly controversial, even in Syria and Palestine. Even so, some basic patterns are well established, and the most important of these is an early conservatism. The pre-conquest divide in precious metal (Byzantine gold and Sasanian silver) was preserved throughout most of the seventh century. Within greater Syria, where the evidence is fullest, we know that the coinage of vanquished adversaries continued to circulate, small handfuls of Sasanian issues left over from the Sasanian occupation of 612–30, and large fistfuls of Byzantine coinage, some having survived from Byzantine rule, others filtering in across a porous frontier: thus one finds large numbers of Byzantine issues struck during the reign of Constans II (641–68), and others struck as late as the reign of Constantine IV (r. 668–85). In design, too, Byzantine and Sasanian models were closely followed, the issues of Constans II and Khusrav II (r. 590–628) proving the most popular.⁸⁹ Mu‘awiya appears on a silver coin in the fifty-fourth or fifty-fifth year of the *hijra* as the ‘commander of the believers’; but the coin, which was minted in the southern Iranian town of Darabjird, retains strikingly pre-Islamic elements: its dating is to the era of the Sasanian shah Yazdegerd, and its language is Pahlavi, or Middle Persian.⁹⁰ Within this broad conservatism there was thus a measure of innovation in the coinage, but this innovation is clearest in Iraq and Iran – that is, outside the metropolitan capital of Syria, where the caliph’s influence was presumably strongest. An argument that Mu‘awiya *did* have a hand in minting reform has been tentatively made, but it turns more on a single (and controversial) line in an early Syriac chronicle than on the surviving numismatic record. Whether any minting took place under caliphal supervision before the 690s therefore remains unproven, although the regional coinages of Syria from the 660s and 670s apparently show some increased organisation.⁹¹

89 C. Foss, ‘The coinage of Syria in the seventh century: The evidence of excavations’, *Israel Numismatic Journal*, 13 (1994–9); C. Morrison, ‘La monnaie en Syrie byzantine’, in J. M. Dentzer and W. Orthmann (eds.), *Archéologie et histoire de la Syrie II* (Saarbrücken, 1989); on this and the coinage more generally, see below, chapter 16.

90 For a description, see S. Album and T. Goodwin, *Sylloge of Islamic coins in the Ashmolean*, vol. I: *The pre-reform coinage of the early Islamic period* (London, 2002), p. 15 and plates 17 and 18.

91 H. Bone, ‘The administration of Umayyad Syria: The evidence of the copper coins’, Ph.D. thesis, Princeton University (2000), esp. pp. 26ff.; C. Foss, ‘A Syrian coinage of

What is indisputable is that clearly centralised and coordinated minting appears only in the last decade of the seventh century as and when state institutions were crystallising. For much of the seventh century a bewildering array of coins was in circulation in Syria, some genuine Byzantine issues, others imitations (particularly of Constans II), others imitations of imitations.


There is, then, no reliably early evidence for anything beyond very rudimentary instruments of rule that we can attribute to the caliphs or their courts. There is compelling evidence for a fairly sophisticated state apparatus at work throughout the seventh century, however. We find it in Egypt, where a wealth of Greek papyri (receipts of various sorts, requisitions, entagia, protocols) reflect the continuity and, as recent scholarship has shown, an apparent expansion of an early Islamic fiscal system rooted in Byzantine traditions. (Layers of the Sasanian administrative apparatus survived into the early Islamic period, too, but there is virtually no documentary or contemporaneous evidence for it.) In what ways was the Byzantine system affected by Islamic rule? Arab Muslim officials of various sorts figure in the papyri from soon after the conquest, where they appear to have been both knowledgeable about, and assertive in, the management of the fisc. As a bilingual (Greek and Arabic) papyrus dated to AH 22 puts it (in the Greek): 'In the name of God, I, Abdellas ['Abd Allah], *amīr* [commander] to you, Christophoros and Theodorakios, pagarchs of Herakleopolis. I have taken over from you for the maintenance of the Saracens being with me in Herakleopolis, 65 sheep.'⁹² In fact, the early Islamic papyri document some reorganising of Egypt's administrative geography, and perhaps also the introduction of the poll tax to Egypt, which would reflect the practical imposition of the *jizya* as it is promised in Q 9:69.⁹³ It now appears that the Muslim rulers of early and mid seventh century Egypt were not the passive receptors of Byzantine bureaucratic traditions, as some earlier scholars had argued, but assertive participants in their transformation.⁹⁴

Mu'awiya', *Revue Numismatique*, 157 (2002); C. Morrison, 'Monnayage omeyyade et l'histoire administrative et économique de la Syrie', in P. Canivet and J. P. Rey Coquais (eds.), *La Syrie de Byzance à l'Islam* (Damascus, 1992), esp. p. 312.

⁹² A. Grohmann, *The world of Arabic papyri* (Cairo, 1952), pp. 113–14.

⁹³ See F. Morelli, *Documenti Greci per la fiscalità e la amministrazione dell'Egitto Arabo* (Vienna, 2001), pp. 19–20.

⁹⁴ See J. Gascou, 'De Byzance à l'Islam: Les impôts en Egypte après la conquête arabe', *JESHO*, 26 (1983); P. Sijpesteijn, 'New rule over old structures: Egypt after the Muslim conquest', in H. Crawford (ed.), *Regime change in the Ancient Near East and Egypt, from Sargon of Agade to Saddam Hussein*, *Proceedings of the British Academy* 136 (London, 2007), pp. 183–200.



4. The Umayyads (dates of accession).

After Hugh Kennedy, *The Prophet and the age of the caliphates*, 2004, p. 403. Copyright Longman, reproduced with permission.

The papyri from Egypt, like the many fewer that survive from Palestine, thus demonstrate the continuity of Byzantine traditions and, in the Egyptian case, an expansion and elaboration of Byzantine traditions during the first half century of Islamic rule. But if Egypt possessed a sophisticated tax regime, nowhere do we find anything reliable that connects it to the imperial capital, either in Arabia, southern Iraq or Syria. Nor do we find any indication that the Arab Muslim oversight of the Byzantine machinery that they had inherited was conditioned by an imperial programme projected by Medina, Kufa or Damascus. In fact, that the impetus for maximising tax revenue was a local initiative is suggested by the contrasting histories of other provinces, such as Northern Mesopotamia, where taxation appears to have been relatively low and irregular for most of the seventh century – that is, until the Marwanids imposed an altogether new and more robust tax administration.⁹⁵ To judge from a small clutch of papyri that survive from Nessana, an irregular regime seems to have been in place there too.⁹⁶

⁹⁵ Robinson, *Empire and elites*, pp. 33ff.

⁹⁶ Johns, 'Archaeology and the history of early Islam', p. 421; cf. Hoyland, 'New documentary texts', pp. 399ff.

In sum, there is good reason to think that first and second generation conquerors may have been hesitant imperialists, who, settling more frequently at some distance from local inhabitants than next to them, looked after themselves rather than their subjects. 'What, then, did the Arabs do with the regions they conquered?', an archaeologist asks: 'For the most part, they seem to have left them alone.'⁹⁷ This is what the evidence says,⁹⁸ and it is what sense dictates: why emulate the traditions of the Byzantine and Sasanian states when God had delivered victory over them to austere monotheists, and when there already were people in place to do the job well? Precisely the same conservatism that led the early caliphs to leave indigenous Greek and Persian speaking and writing bureaucrats in place in the provinces acted as a brake upon administrative innovation at the empire's centre.

And being conservative came naturally: all of the caliphs who ruled until 680 had been born and bred in Arabia, and had witnessed the glorious moments of early Islam.⁹⁹ Mu'awiya, whose father had been a very prominent opponent of Muḥammad's and had converted only late and opportunistically, himself converted only when Mecca was conquered by Muḥammad, where upon he entered his circle of advisers and confidants (he is conventionally identified as one of the Prophet's secretaries). He was thus very much the product of the same world that had produced Muḥammad himself: a Qurashī schooled in the ways of tribal politics of Mecca and Medina, he was already in his fifties when he became caliph in 40/661. By contrast, 'Abd al Malik was born in 26/646f., that is, at the beginning of 'Uthman's reign. His formative experience was not of Qurashī Mecca or Muḥammad's community in Medina, nor even of Medina filled with the spoils of 'Umar's spectacular conquests. It was of a town riven by the controversies of 'Uthman and 'Alī's reigns. In other words, what 'Abd al Malik knew of Islam's glorious origins was mediated by others, and the lessons he learned during his childhood were about the

97 Foss, 'Syria in transition', p. 266.

98 Even much later, in the middle decades of the eighth century that is, when state institutions had developed considerably, and the instruments of state power had become more coercive conquering Muslims seem to have balked before imposing state structures in their newly acquired territories: Islamic coinage began to circulate in northern Afghanistan only after a full century of hands off rule; and although the tradition describes a late seventh and eighth century programme of Arabicising official documents, the surviving material remains in Bactrian. See N. Sims Williams, *Bactrian documents from northern Afghanistan*, vol. I: *Legal and economic documents* (Oxford, 2000), pp. 116, 134 ('Arab dirhams in silver' appear in 507/739 and again in 525/757); the poll tax only appears in the latter.

99 See Crone, *Slaves on horses*, p. 5: 'Rarely have a preacher and his followers lived in such discontinuous environments: what made sense to Muḥammad made none to Mu'awiya, let alone to 'Abd al Malik.'

fragility of the early Islamic elite. These lessons would be repeated during the second civil war, when the elite fragmented further. Historical discontinuities may have taken an enormous toll on the preservation of their history, but it freed Muslims of the early period to innovate and experiment.

Little wonder, then, that it is only with ‘Abd al Malik and his generation of Muslims that we have clear evidence for a programme of state building that was driven by the Muslim ruling elite, and which systematically diffused new ideas of power and authority.¹⁰⁰ Since the evidence for all of this explodes onto the scene within a short time – the late 680s and early 690s – we must accordingly describe the process of early Islamic state building as revolutionary, rather than evolutionary.

The second *fitna* and the Marwanid revolution

The second *fitna*,¹⁰¹ like the first, was triggered by problems of succession. Mu‘awiya’s appointment of his son as heir apparent seems to have been unpopular in principle, since it departed from traditions of acclamation and election. Yazīd’s difficulties were compounded by his conduct: the son possessed little of the father’s nous and forbearance, and it was at the beginning of Yazīd’s reign that an Umayyad army suppressed a rebellion led by the Prophet’s grandson, al Ḥusayn. In the long term, his gruesome slaying at Karbala’ (680) came to exemplify Umayyad brutality and provide inspiration to subsequent Shī‘ite movements, especially as it followed earlier instances of Sufyanid abuse of the Shī‘a, such as Mu‘awiya’s execution of the Kufan Shī‘ite al Ḥujr ibn ‘Adī; in the short term, it deepened the crisis for Mu‘awiya’s successor. Umayyad rule was further weakened with the succession in 683 of the sickly and incompetent Mu‘awiya II, who ruled for a matter of months. Umayyad authority outside Syria had started to dissolve earlier, but now it collapsed almost entirely, with the result that several Umayyads and non Umayyads emerged as candidates for the caliphate. Of these, four are especially prominent in the sources: ‘Abd Allah ibn al Zubayr, the pious son of a revered Companion who would rule effectively from Mecca; al Ḍaḥḥāk ibn Qays al Fihri, a governor of Mu‘awiya’s; Ḥassan ibn Malik ibn Bahdal, a cousin of his son, Yazīd; and ‘Amr ibn Sa‘īd, an Umayyad who had served Mu‘awiya.

100 For a different view, see F. M. Donner, ‘The formation of the Islamic state’, *JAOS*, 106 (1986), pp. 283–96.

101 The fullest discussion remains G. Rotter, *Die Umayyaden und der Zweite Bürgerkrieg (680–692)* (Wiesbaden, 1982).

In the event, Umayyad rule would be reconstituted, but the process would be slow and difficult. It started in the early summer of 684 with the acclamation in al Jabiya (near Damascus) of Marwan ibn al Ḥakam, a well respected and senior member of the Umayyad house; Marwan promptly set about establishing himself in Syria, defeating al Ḍahḥak at Marj Rahit, and then moving to Damascus. He died in the spring of the following year, and was succeeded by his son, ‘Abd al Malik. It was ‘Abd al Malik who, after several false starts and heavy campaigning, completed the process eight years later by defeating his Syrian rivals (notably ‘Amr ibn Sa‘īd), campaigning in Iraq and Northern Mesopotamia, and eventually sending an army against Ibn al Zubayr’s Mecca. There, in March 691, ‘Abd al Malik’s most trusted commander and future governor of the east, al Ḥajjaj ibn Yusuf, laid siege to the city and put an end to the caliphate of Ibn al Zubayr.¹⁰² Although ‘Abd al Malik’s bid for the caliphate dates from 685, when he received the oath of allegiance in Syria, it was probably only with the death of Ibn al Zubayr late in 692 that he was widely acknowledged as caliph. Regnal dates that conventionally put the beginning of his caliphate in 685 say more about subsequent Umayyad claims than they do about contemporaneous attitudes.

Indeed, there can be little doubt that Ibn al Zubayr, although portrayed by much of the primary and secondary literature as a pretender or rebel (one most frequently described as ‘he who takes refuge in the house’, i.e. the Ka’ba),¹⁰³ had been widely acknowledged as caliph – certainly much more so than Yazīd, Mu‘awiya II, Marwan and, at least until 692, ‘Abd al Malik himself. A political and dynastic dead end who had the great misfortune to have been overthrown by the extraordinarily successful ‘Abd al Malik, Ibn al Zubayr then had his caliphate written out of most (if not all) of the history books. History itself was different. Almost universally respected because of his descent from al Zubayr, the Prophet’s Companion who had rebelled alongside ‘Ā’isha in the battle of the Camel, Ibn al Zubayr had firm control of the Prophet’s homeland and the emerging cultic centre of Mecca, and minted coins as early as 684 (using what was becoming the standard caliphal title, ‘the commander of the faithful’). He ruled lands stretching from Egypt in the west to eastern Iran and parts of Afghanistan in the east by appointing governors,

102 The following is spelled out in much more detail in C. F. Robinson, *‘Abd al Malik* (Oxford, 2005). The politics of the period is very usefully summarised in A. A. Dixon, *The Umayyad caliphate 65–86/684–705 (a political study)* (London, 1971).

103 In addition to Robinson, *‘Abd al Malik*, pp. 31ff., see Abu al Faḥ al Samirī, *The continuation of the Samaritan chronicle of Abu al Faḥ al Samirī al Danafī*, ed. and trans. M. Levy Rubin (Princeton, 2002), pp. 54f.

levying taxes and dispatching armies, and successfully suppressed the most potent opposition movement of the civil war, a Shī'ite rebellion in southern Iraq (685–7) led by a shadowy figure named 'al Mukhtar', who championed the right to the caliphate of Muḥammad ibn al Ḥanafīyya, a son of 'Alī's by a concubine. It is true that his vision of a Ḥijazī based empire turns out to have been naive and nostalgic, but in several respects he was an innovator: for example, it is during his reign that part of the Muslim profession of faith ('Muḥammad is the messenger of God') first appears on coinage, one of several practices that would survive his death in 692. He also undertook what appears to have been a substantial rebuilding programme in Mecca, which anticipates 'Abd al Malik's. In overthrowing Ibn al Zubayr, 'Abd al Malik thus defeated the man who was at once the most effective spokesman for the interests of the Ḥijazīs left behind by Umayyad rule, the most respected opponent of Umayyad dynastic claims, and the one most widely acknowledged as caliph.

'Abd al Malik's revolutionary impulse carried him beyond his defeat of Ibn al Zubayr. For it was during his reign that we witness nothing less than the transformation of the loosely federal, ideologically inchoate conquest polity of the early caliphs into the land based, bureaucratic state that lay at the heart of the Marwanid empire – and one that, within a generation of 'Abd al Malik's death, would reach its greatest size. Just how fragile the conquest polity had been can be seen in its catastrophic collapse upon the death of Mu'awiya. Just how robust 'Abd al Malik's state was can be seen in the events following his death, when he was succeeded by no fewer than four sons, three grandsons and two nephews. And because his and his sons' rule was so successful in the short term, the traditions, institutions and ideas they put in place survived in the longer term, underpinning the 'Abbasid empire of the eighth and ninth centuries.

The changes were military, administrative and ideological; all contributed to the complex process itself already under way in which Islamic society became in many respects increasingly differentiated and complex, and the instruments of rule more powerful and persuasive. We may begin with the army.

Having settled in the provinces in the 640s and 650s, by the 670s and 680s many conquering tribesmen would have begun to take up a variety of occupations, depending on their resources, abilities and opportunities; and in some instances we know that sedentarisation was encouraged among pastoralists, and that garrisons were being transformed into towns.¹⁰⁴ Even

¹⁰⁴ For an overview, see K. 'Athamina, 'Arab settlement during the Umayyad caliphate', *JSAI*, 8 (1986).

so, the contrast between civilian and soldier remained indistinct until 'Abd al Malik's military reforms, when the tribesmen soldiers of the conquest armies, generally mustered and led by chieftains drawn from high status kinship groups, began to be replaced by a professional soldiery of Syrians. The lesson taught by the civil war, when fickle chieftains had abandoned the Sufyanids for rival candidates, was duly learned. What resulted was thus an altogether clearer contrast between civilian and soldier, which, in the view of a state claiming a monopoly on legitimate violence, transformed the armed civilian into a brigand or rebel. At the same time, because the army was overwhelmingly Syrian in composition, it also resulted in an altogether clearer distinction between (ruling) Syrian and (ruled) non Syrian.

In the short term, the new style Syrian army was a success: within three years of defeating Ibn al Zubayr, 'Abd al Malik had launched what would turn out to be a four year campaign on the Byzantine frontier, and parts of Armenia would fall under Islamic rule for the first time. (The *jihad* would be expanded with considerable success by 'Abd al Malik's son and successor, al Walid, especially in North Africa and Sind.) But problems naturally appeared. We occasionally read of desertion and the soldiers' reluctance to fight; we also read of spectacular rebellions led by commanders on extended campaigns (thus a dangerous revolt in the east led by the celebrated Kindi commander, Ibn al Ash'ath, in 699) and of soldiers who had fallen off the *dīwan* and thus out of favour with the Umayyads (thus the Kharijite rebellion led by Shabīb ibn Yazīd al Shaybanī in Northern Mesopotamia and Iraq in late 695 and 696).¹⁰⁵ Perhaps most important, the distinction between Syrian and non Syrian became politically explosive. The occupation of Iraq and Iran by Syrian soldiers Syrian garrisons were established in Iraq and Iran, the garrison of Wasīṭ being built in 702 or 703, equidistant between Baṣra and Kufa as a base against their restive tribesmen provided the coercion necessary to extract taxes and tribute from non Syrians. This would lead in the short term to endemic rebellion in the provinces, most notably by Kharijites, and, in the long term, to the catastrophic revolution of 749–50. Meanwhile, the professionalisation of the army led to the emergence of two rival factions (the Qays/Yaman, or 'northerner'/'southerner'); and this rivalry would also subvert Umayyad rule until its end.¹⁰⁶

105 On Ibn al Ash'ath, see R. Sayed, *Die Revolte des Ibn al Ash'at und die Koranleser* (Freiburg, 1977); on Shabīb, see Robinson, *Empire and elites*, pp. 109ff.

106 P. Crone, 'Were the Qays and Yemen of the Umayyad period political parties?', *Der Islam*, 71 (1994).

Military reforms thus strengthened Umayyad power in the short term, as they reflected the shift away from a relatively undifferentiated conquest society. The same processes characterised the administrative and fiscal reforms of the period. Here, too, we find indirect influence being replaced by direct control. The scale of these reforms is hard to exaggerate. As the Islamic historical tradition makes clear, the changes were in part linguistic: the language of tax administration, which until this period had remained unchanged in Greek and Persian, was now replaced by Arabic. The surviving documentary evidence offers some corroboration for this shift, although the pace of change in the Islamic east seems to have been considerably slower than the historical tradition would have it.¹⁰⁷ The introduction of Arabic into the tax administration had the effect of opening up bureaucratic careers to Arabs and to non Arab converts (*mawālī*), who were incorporated into Islam through admission as clients by Arab patrons, although Christians and Jews would continue to serve; the Marwanid period is consequently filled with examples of extraordinary social climbing, as Arabs and *mawālī* alike joined the ranks of administrators and tax officials. A relatively closed elite of tribesmen soldiers was cracking open. Effects aside, the intention of this linguistic change must have been to extend Umayyad control over tax revenues so as to maximise the elite's share. Indeed, there is no doubt that the last two decades of the seventh century and first two of the eighth were a watershed in the fiscal history of the Near East, as irregular and inconsistent tribute taking was replaced by regular and more systematic taxing. The documentary and Syriac historical traditions show this at work in Syria and Northern Mesopotamia; in the latter we have a handful of apocalypses and apocalyptic histories that describe in hyperbolic detail the devastating effects of the new taxing regime.¹⁰⁸ Even in Egypt, where the engines of the Byzantine tax machine had never stopped firing, we read of the unprecedented extension of tax liabilities to mobile peasants and monks, and the unrest that resulted from the new regime. Arabs, too, now became increasingly liable to taxation, as the poll and land taxes were firmly established for the first time, the former on non Muslims, the latter on non Muslim and Muslim alike.¹⁰⁹

The scale and nature of these changes are reflected in the material evidence. Leaving aside all the papyri generated by the Byzantine machinery of Egypt,

¹⁰⁷ See above, note 98.

¹⁰⁸ For a survey, see Hoyland, *Seeing Islam*, pp. 257ff.; Robinson, *Empire and elites*, pp. 48ff.

¹⁰⁹ See J. B. Simonsen, *Studies in the genesis and early development of the caliphal taxation system* (Copenhagen, 1988), esp. pp. 113ff.; Morimoto, *Fiscal administration of Egypt*, pp. 139ff.

we have precious little elite sponsored documentary and inscriptional material (which is to be distinguished from occasional graffiti) dating from the conquest and Sufyanid periods, but with the Marwanids the corpus not only grows larger, but also more consistent. For example, while no pre Marwanid milestones have been discovered, no fewer than six date from the reign of 'Abd al Malik.¹¹⁰ Patterns of non elite settlement and land use may have been slow to change in this period, but new tools and techniques of rule were being adopted: it is at the tail end of the seventh and early eighth centuries, to take another example, that mobile non Muslim taxpayers were made to wear seal pendants to mark their tax status.¹¹¹ The best evidence for the scale and nature of change comes in the coinage. We saw earlier that coinage had been diverse, preserving (and elaborating upon) the varieties of Byzantine and Sasanian minting traditions that had carried on through the conquests. Starting almost immediately upon the defeat of Ibn al Zubayr, 'Abd al Malik's minters abandoned the conservatism of their forebears, first (starting in c. 692) by introducing distinctively Islamic designs and motifs (such as a portrait of 'Abd al Malik; what may be a spear in a prayer niche), and second, starting with gold coins in around 696–7, by abandoning altogether the figural imagery and languages of pre Islamic coinage in favour of purely non figural, epigraphic coins with exclusively Arabic legends that expressed in formulaic ways distinctively Islamic ideas.¹¹² Alongside these coinage reforms, which centralised minting and imposed standard weights,¹¹³ sits a reform of weights and measures. In addition to circulating tokens that broadcast legitimising and universalising claims, the elite was thus taking an unprecedented interest in fostering economic exchange. The Marwanids certainly patronised commercial building projects in Palestine and Syria.¹¹⁴

What we have, in sum, is the relatively sudden appearance of a cluster of institutions and practices: an imperial state designed for the systematic extraction of agricultural revenues was being engineered. It was to be effected by a professional soldiery resourced by an increasingly thorough tax regime, which

110 A. Elad, 'The southern Golan in the early Muslim period: The significance of two newly discovered milestones of 'Abd al Malik', *Der Islam*, 76 (1999).

111 C. F. Robinson, 'Neck sealing in early Islam', *JESHO*, 48 (2005).

112 Bone, 'Copper coins'.

113 P. Grierson, 'The monetary reforms of 'Abd al Malik: Their metrological basis and their financial repercussions', *JESHO*, 3 (1960).

114 See R. M. Foote, 'Commerce, industrial expansion, and orthogonal planning: Mutually compatible terms in settlements of Bilad al Sham during the Umayyad period', *Mediterranean Archaeology*, 13 (2000); and S. Berthier (ed.), *Peuplement rural et aménagements hydroagricoles dans la moyenne vallée de l'Euphrate, fin VIIe–XIXe siècle* (Damascus, 2001).

was managed by new cadres of bureaucrats and administrators. Its authority was to be anchored in that unitary conception of authority with which this chapter began, and which was now crystallising. As the poetry and prose of this and subsequent periods shows, ‘Abd al Malik was ‘God’s caliph’, heir to the Prophet’s authority and God’s ‘shadow on earth’, a legislator, judge, guide, warrior, rain maker, prayer leader, perhaps an editor (the Qur’anic text may have been fixed only in the early Marwanid period)¹¹⁵ and certainly a builder of what remains the oldest intact Islamic building: the domed, octagonal building in Jerusalem that is called the Dome of the Rock. Completed in around 72/691f., the Dome of the Rock sits atop the Temple Mount, which looks down upon Christian Jerusalem. The building is a monument to victory: not merely victory over Ibn al Zubayr (its construction seems to have taken place during or soon after the end of the *fitna*) but, more importantly, victory over rival monotheisms. In fact, it was an imposing reminder of their obsolescence: just as the building was made to sit at the heart of the Holy Land, literally upon the foundations of the Jews’ Temple, so did the faith that it symbolised claim to reform and perfect earlier revelations. Thus its inscriptions announce that God is merciful and compassionate, that He is alone and has no sons (‘The messiah Jesus, son of Mary, was only a messenger of God ... [Who] is too exalted to have a son’), that Muḥammad is His Prophet, and that:

Religion with God is Islam. Those who received the scripture differed only after knowledge came to them, out of envy for one another. Whoever denies the signs of God [beware], for God is swift to call to account.¹¹⁶

Conclusion

Given the extraordinarily modest cultural and political traditions generally associated with western Arabia in Late Antiquity, how is it that Muḥammad and the Arab caliphs and commanders who immediately succeeded him had both the vision and perspicacity to forge a new religio political tradition that would survive in post conquest Syria and Iraq? Sophisticated religious traditions generally emerge in societies with relatively high levels of social differentiation; the rule of history calls for the assimilation of conquering pastoral

¹¹⁵ Thus M. Sfar, *Le coran est il authentique?* (Paris, 2000), pp. 83ff.; Robinson, ‘Abd al Malik, pp. 100ff.

¹¹⁶ Hoyland, *Seeing Islam*, pp. 696ff.

and semi pastoral tribesmen, along with their political and cultural traditions, into the more developed, sedentary culture so conquered, be it fifth century Roman Italy or twelfth century Saljuq Iraq. Why were seventh century Arabs so different? These questions can be answered in a variety of ways, but it may be useful to contrast two of them.

The first, here put in its most extreme form, is to argue that the Ḥijaz had nothing to do with earliest Islam. Because religious traditions have a habit of misrepresenting their origins, and because we lack corroborating evidence that is contemporaneous to the crucial events of the seventh century, there is no reason to suppose that everything happened as the Islamic tradition tells us it happened. One may accordingly assert that Muḥammad did not exist, that the conquests – that is, the Ḥijazī Arabs' violent seizure of power from the Byzantines (and Sasanians) – did not take place, and that the Qur'an, with all of its debts to Judaism and Christianity, was compiled at least a century (and perhaps two centuries) later.¹¹⁷ (Islamic history would thus be comparable to Israelite history, its scripture, conquest and early polity as enigmatic as those ascribed to Moses and David.) There being no historical basis for early Islamic narratives, the problematic Ḥijazī context of earliest Islam is thus solved at a stroke: Islam's origins lie not in Arabia, but in the Late Antique world of the eighth and ninth century Fertile Crescent, in the religious, ethnic and linguistic matrix that produced comparable forms of monotheism, such as, especially, rabbinic Judaism. According to this line of argument, Arabian origins reflect not historical reality, but an invented tradition.

Now, it can hardly be doubted that the early Islamic historiographic tradition was at once deeply conditioned by polemical assertions regarding identity, origin and social status, and preserves only very incompletely any authentic material from the seventh century. But if it is one thing to envision the growth of the Islamic tradition as part of a much broader process, in which monotheist identity of several varieties took shape, it is altogether something else to reject in its entirety the tradition's claim for Arabian origins. In fact, revisionism of this sort can readily be blunted by adducing a variety of seventh century evidence. The fact is that Christian and Jewish sources confirm that Muḥammad *did* exist and did make prophetic claims, that some kind

¹¹⁷ For revisionism of the most radical kind, see Y. Nevo and J. Koren, *Crossroads to Islam: The origins of the Arab religion and the Arab state* (Amherst, NY, 2003), inspired, in part, by the work of Wansbrough, which is usefully discussed in H. Berg, 'Islamic origins reconsidered: John Wansbrough and the study of early Islam', *Method and Theory in the Study of Religion*, 9 (1997); cf. I. Olagüe, *Les arabes n'ont jamais envahi l'Espagne* (Paris, 1969).

of violent political change effected by monotheist tribesmen soldiers from Arabia *did* occur, and that, at least in some fragmentary form, some kind of an Islamic scripture *can* be dated to the seventh century. Non Islamic and material evidence is far too sketchy to produce a coherent account of Islam's beginnings, but it securely locates those beginnings in events that are familiar to us from the Islamic tradition itself. In any case, if one deprives the conquests of the great motive force of Muḥammad's revelations and politics, one makes them altogether harder to understand.

One solution to the problem of the Ḥijaz's cultural insularity is thus to pull Islamic origins entirely out of Arabia and into the Late Antique Fertile Crescent of the eighth and ninth centuries. The second, which is more promising, is to pull Late Antiquity into the seventh century Ḥijaz. For the more evidence we have that it was open to the political, cultural and religious currents of Late Antiquity, the easier it is for us to understand not merely the Qur'an that 'text without a context' but also early Islam more generally. There is disappointingly little of it that we can securely date to the sixth and early seventh centuries, however. (Arguments for Christian, Jewish or Manichaean influence upon Muḥammad and his contemporaries typically adduce the biographical and historical tradition, especially Prophetic *sīra*, which generally dates from eighth and ninth century Iraq;¹¹⁸ until the genesis and transmission of this tradition are understood more fully, evidence such as this is far from clinching.) The political and cultural circumstances for Arabian archaeology are admittedly very unfavourable, but, such as the archaeology is, it yields virtually no sure evidence for the extension of political and cultural influences from the Late Antique heartland into the sixth and seventh century Ḥijaz; this contrasts with earlier periods and other regions of Arabia, particularly the south and the east, which, according to the material and historical record, were frequently brought into the orbit of the Byzantine and Sasanian empires.¹¹⁹ To assemble the thin evidence for local monotheisms, we must fall back upon the incidental references in the slim non Islamic tradition, and, as we have already seen, the testimony of the one text that was generated in the seventh century Ḥijaz – the Qur'an.

In the present state of our knowledge, the most we can do is propose hypotheses that accommodate the available evidence according to models appropriate to the Late Antique world in which early Muslims evolved. Arabia

118 For a Manichaean example, see M. Gil, 'The creed of Abu 'Āmir,' *Israel Oriental Studies*, 12 (1992).

119 For an overview, Hoyland, *Arabia and the Arabs*.

was moving perhaps sluggishly towards monotheism, and Muḥammad seems to have greatly accelerated this process. Beyond adducing the force of his personality, political acuity and the victories of the early Medinan period, explaining why his vision of reform and political action should have been so successful is very difficult, but it may be because western Arabia lay outside the dense network of Christian and Jewish belief and institutions that Muḥammad was free to innovate in the long abandoned style of a Hebrew prophet, legislating, leading and warring, and that this style had such appeal; had he been born and raised in Syria, one might expect a very different career, perhaps as a more typical (but equally charismatic) holy man. What is clearer is that he articulated a religious vision that was at once reassuringly familiar and passionately revolutionary – and this, in a distinctively Arabian idiom. Thus paganism is repudiated, but the pagan sanctuary of Mecca is reinterpreted as Abrahamic and integrated into the new dispensation; similarly, the Arabic Qur'an rejects the *jahiliyya* ethos, but draws upon registers of orality that had been closely associated with the very kinship patterns that were at the heart of *jahilī* paganism.¹²⁰ While the universality of Islam took some time to develop, the special role of the Arabs and their traditions of kinship had to have a place from the start. Indeed, from as early as we can trace things, we know that the central institution of rule (the caliphate) was dominated by Arabs, while, at least in theory, the only institution of incorporation (conversion) was effected through the adoption of Arab tribal lineage.

Whatever their Ḥijazī origins, Arab identity and the nascent religious tradition were subsequently conditioned by patterns of post conquest settlement and assimilation. There is no reason to doubt that the garrisons founded apart from or adjacent to pre Islamic settlements were intended at least in part to insulate Arab Muslims from non Arab non Muslims; but they inevitably attracted and generated trade and exchange, and, with it, the influx of non Arabs. What appears to have been an initial experiment, in which an ethnic and religious elite would rule at arm's length, was overtaken by the realities of settlement. From this perspective, the late seventh century programme of Arabisation marks a transitional phase between the relative insularity of the first generations, born and bred in Arabia and among the Arabs of Syria, and the clear universalism and cosmopolitanism of the Iraqi based caliphate of the 'Abbasid period. In the meantime Muslims developed their religious tradition in response to, and in interaction with, their fellow monotheists, even if the

120 A. Jones, 'The language of the Qur'an', in K. Dévényi, T. Iványi and A. Shvitzel (eds.), *Proceedings of the Colloquium on Arabic Lexicology and Lexicography* (Budapest, 1993).

early Islamic tradition is disappointingly taciturn about the world in which these interactions took place. Muslims having been small minorities throughout the seventh, eighth and ninth centuries, classical Islam – that is, the religious and political system that crystallised during the ninth century – owes innumerable debts to the prevailing, majority cultures of the day,¹²¹ which were evolving and transforming as well, at least sometimes in response to Islam.¹²² Disputation and controversy began very early on,¹²³ but much of classical tradition was forged in multi-ethnic Iraq and the Islamic east. As Muslim rulers left Arabia and Arabian Syria, Islamic society and belief were changing.

¹²¹ For Muslim debts to the rabbis, see M. Cook, 'The opponents of the writing of tradition in early Islam', *Arabica*, 44 (1997), pp. 437–530; M. Cook, 'Magian cheese: An archaic problem in Islamic law', *BSOAS*, 47 (1984); for background, M. J. Kister, 'Ḥaddithu 'an banī isra'īla wa la ḥaraja', *Israel Oriental Studies*, 2 (1972).

¹²² For Karaite debts to Muslims, see Cook, 'Anan and Islam'.

¹²³ See S. H. Griffith, 'Disputes with Muslims in Syriac Christian texts: From Patriarch John (d. 648) to Bar Hebraeus (d. 1286)', in B. Lewis and R. Niewöhner (eds.), *Religionsgespräche in Mittelalter* (Wiesbaden, 1992).

The empire in Syria, 705–763

PAUL M. COBB

Introduction

Syria is usually where empires end, not where they begin. Throughout its long history the region between the Euphrates and the Mediterranean has been a theatre for imperial designs concocted elsewhere: in Babylon, Rome, Constantinople, Cairo. After the collapse of the Seleucid state (323–64 BCE), only once, and only briefly, did Syria itself serve as the metropole to an empire. Like its Seleucid ancestor, the Marwanid experiment in Syria showed that a far flung Middle Eastern empire was still possible without Iraq or Egypt to serve as its centre. Yet without the intensively harvested revenues of the Nile Valley and Mesopotamia and the military and cultural production they allowed, the Marwanid caliphate would not have lasted as long as it did. And if the Seleucid empire was a successor state to Alexander's Hellenistic venture, then the Marwanid reprise must be reckoned a precursor state. Providing as it did the framework in which Islam and Arabic culture spread beyond the Nile to Oxus core of the caliphate, the Marwanid caliphate set Islamic civilisation on course to be fully realised by other polities. Greater in size if not duration than the Seleucid empire, the Marwanid caliphate gave Islamic Syria its place, however fleeting, in the sun.

The fruitful combination of empire and monotheism that cemented the ascendancy of 'Abd al Malik and his successors was a transregional – indeed, universal – system of ideas. But the fact that the Marwanid house depended so heavily for its might upon Syrian troops meant that the world view that the caliphs encouraged was expressed in Syrian terms and backed up by Syrian muscle. For all that the Marwanid caliphs saw themselves as God's caliphs, from France to Farghana it was the Syrian tribal armies who were the real world conquerors. In the end, the contradictions inherent in a theoretically universalist ruling ideology based upon the privileges of a small regional elite caused the Marwanid structure of empire to come crashing down. It is no

accident that opposition to the caliphs was expressed in resentment against Syrian privilege, in tribal factionalism, and in claims for Islamic alternatives to the empire of Marwanid Syria.

The Marwanid dynasty and its structure: an overview

Even before the death of ‘Abd al Malik, succession disputes created tensions within the Marwanid house. Two mutually exclusive modes of succession kept family tensions simmering until the overthrow of the dynasty in 750. On the one hand, the sons of Marwan were expected to share the office of caliph ‘horizontally’ from brother to brother, following common Arab tribal political traditions. This meant that after ‘Abd al Malik, his brother ‘Abd al ‘Azīz was expected to rule, though in the end the latter predeceased him. On the other, this fraternal arrangement conflicted with a desire for primogeniture, which hoped to see the caliphate passed ‘vertically’ from father to son. Thus, ‘Abd al Malik tried to get his brother to renounce his claim and to confirm the succession instead to his son al Walīd, but he refused, noting, according to one account, that he cherished hopes for his own sons just as much as ‘Abd al Malik did for his. Nonetheless, of ‘Abd al Malik’s ten successors, four were his sons, and three his grandsons. The Marwanids were thus in many ways more the dynasty of ‘Abd al Malik than of his father Marwan. But the dynasty was not without its fault lines and, given the growing problem of tribal factionalism under the later Marwanids, it is remarkable that dynastic tensions did not explode into open conflict sooner than they did.

When ‘Abd al Malik died in 705, the caliphate, and the new vision of Islamic empire that he had fostered, passed smoothly to his own son, al Walīd. The reign of al Walīd I (r. 705–15) is often seen as the high water mark of the Umayyad period, but it is not clear whether this is a result of any of the caliph’s own talents or of the accomplishments of his father. Certainly, given the contentious decades of civil war that preceded it, the reign of al Walīd seems a miracle of calm and prosperity. Al Walīd also continued his father’s interest in public statements of Marwanid religious authority, and the ‘Umayyad Mosques’ that he founded or restored in Medina, Jerusalem, and Damascus are every bit the fitting sequels to ‘Abd al Malik’s projects in Jerusalem. And as Marwanid troops continued the conquest of North Africa, Sind and Central Asia (to name only the most active fronts), the caliphate achieved its greatest territorial extent.

The impression of continuity is no doubt partly a result of the continued presence of the mighty and irascible al Ḥajjaj, who served both ‘Abd al Malik and al Walid as governor of Iraq and the east. It was he who directed the conquests and maintained pressures on the caliphate’s foes on the eastern frontier, who continued to develop the infrastructure of Iraq and who, in return, was given a relatively free hand in appointing his own men to whatever positions in the caliphate he wished, even when it discomfited members of the dynasty, among whom, it is worth noting, was the next caliph, Sulayman, al Walid’s brother. Sulayman had long before been named heir apparent, and, although there is some indication that al Walid hoped he could pass the caliphate on to his own son, Sulayman succeeded without controversy.¹

Sulayman ibn ‘Abd al Malik (r. 715–17) had been governor of the sub district of Filastīn during his brother’s caliphate, so he had had ample time to foster ties with the all important Syrian tribal armies. Indeed, his reign witnessed the first stirrings of what would in later years become full fledged factional politics among the Syrian troops. That Sulayman was sensitive to these developments in the army can be seen both in his efforts to ‘clean house’ by appointing new men to provincial positions almost across the empire, and in his desire to keep the armies on campaign. By previous accord, Sulayman was to pass the caliphate on to his brothers Yazīd and Marwan but, Marwan having died, Sulayman too tried to get his own son recognised as his heir. In the end, this son himself died unexpectedly, and so Sulayman’s ambitions were thwarted. On his death bed, Sulayman was persuaded to pass over his remaining sons as too young and to name his cousin, ‘Umar ibn ‘Abd al ‘Azīz, to succeed him, with Yazīd ibn ‘Abd al Malik, now bumped from the previous succession arrangement, to follow ‘Umar.²

‘Umar II (r. 717–20) came to power without any significant opposition. Of all his kinsmen, he alone has a distinctively positive reputation among later writers as a pious figure who tried to rein in the fiscal and military excesses

1 For the reign of al Walid, see Abu Ja’far Muḥammad ibn Jarīr al Ṭabarī, *Ta’rīkh al rusul wa al muluk*, ed. M. J. de Goeje et al., 15 vols. in 3 series (Leiden, 1879–1901), series II, pp. 1172–281; Julius Wellhausen, *Das arabische Reich und sein Sturz*, Berlin, (1902, trans. M. G. Weir as *The Arab kingdom and its fall* (Calcutta, 1927), pp. 224–57; G. R. Hawting, *The first dynasty of Islam: The Umayyad caliphate, AD 661–750*, 2nd edn (London, 2000), pp. 58–71. On what has been called ‘the Age of Ḥajjaj’, see M. A. Shaban, *Islamic history: A new interpretation*, 2 vols. (Cambridge, 1971–6), vol. I, pp. 100–26.

2 On Sulayman, see Reinhard Eisener, *Zwischen Faktum und Fiktion: Eine Studie zum Umayyadenkalifen Sulaiman b. ‘Abdalmalik und seinem Bild in den Quellen* (Wiesbaden, 1987).

of his predecessors, consciously evoking the right guidance of his earlier namesake, 'Umar ibn al Khaṭṭab. Such reform as he may have intended, however, did not outlive his short reign. Moreover, some of the remaining sons of 'Abd al Malik are said to have expressed their dissatisfaction at the fact that the caliphate had, with 'Umar, left the line of 'Abd al Malik. This dissent seems not to have been warranted, as 'Umar himself appears to have had no dynastic ambitions of his own, and at his death (which some said was engineered by his resentful cousins), the caliphate passed, as agreed, back to the line of 'Abd al Malik via Yazīd ibn 'Abd al Malik, known as Yazīd II (r. 720–4). Somewhat to his later regret, Yazīd was persuaded to forgo his own inclinations to pass the caliphate on to his sons and instead to acknowledge his brother Hisham as heir. As a consolation, Yazīd's son, al Walīd ibn Yazīd, was named to succeed Hisham.³

The accession of Hisham ibn 'Abd al Malik (r. 724–43), which some sources describe as the work of his brother Maslama, brought to power someone who consistently extended the power of the caliphate: on its rapidly expanding frontiers, over its tax paying subjects, and its diplomatic contacts. Indeed, Hisham's success as a state builder can be seen both in the 'Abbasids' grudging praise of his ability and the many outbursts of provincial unrest during his reign: a sure sign that the state was making new inroads. Hisham's reign also marks the end of the line for the sons of 'Abd al Malik. At his death in 743 there were no sons of 'Abd al Malik left to take the throne. The likeliest candidate was probably Maslama himself, but he had died in 738. And so, as planned, al Walīd II (r. 743–4), the son of Yazīd II and grandson of 'Abd al Malik, came to the throne; Hisham's own sons seem not, initially, to have contested the arrangement.⁴

The fact that the horizontal succession arrangements between the sons of 'Abd al Malik had now run their course may have contributed to the onset of

3 On 'Umar II, C. H. Becker, 'Studien zur Omajjadengeschichte. A) 'Omar II', *Zeitschrift für Assyriologie*, 15 (1900) is the starting point; see also Wellhausen, *Arab kingdom*, pp. 267–311. On the succession, see C. E. Bosworth, 'Raja' b. Haywa al Kindī and the Umayyad caliphs', *Islamic Quarterly*, 15 (1971). See most recently Antoine Borrut, 'Entre tradition et histoire: Genèse et diffusion de l'image de 'Umar b. 'Abd al 'Azīz', *Mélanges de l'Université Saint Joseph*, 58 (2005). On Yazīd II, see Wellhausen, *Arab kingdom*, pp. 312–25; and H. Lammens and K. Blankinship, 'Yazīd (II) b. 'Abd al Malik', *EL*, vol. XI, pp. 310–11.

4 On Hisham, see Francesco Gabrieli, *Il Califatto di Hisham: Studi di storia omayyade*, Mémoires de la Société Royale d'Archéologie d'Alexandrie 7 (Alexandria, 1935); Khalid Yahya Blankinship, *The end of the jihad state: The reign of Hisham Ibn 'Abd al Malik and the collapse of the Umayyads* (Albany, 1994). On the reign of al Walīd II, see Francesco Gabrieli, 'al Walīd b. Yazīd, il califfo e il poeta', *RSO*, 15 (1935); Dieter Derenk, *Leben und Dichtung des Omayyadenkalifen al Walīd ibn Yazīd* (Freiburg im Breisgau, 1974).

civil war following the succession of al Walīd II. The field, in effect, was now wide open, and al Walīd's personal conduct and reputation for impiety seem to have provided enough of a pretext for other claimants to contest his right to rule, sparking what became known as the third *fitna* or civil war. From 744 until as late as 754 the office of caliph was contested by members of a younger generation of Umayyad claimants, most of them by this time solidly entrenched in the factional politics of the Syrian army (on this aspect of the third *fitna*, see below). With the Marwanids themselves barely able to agree upon the legitimacy of a given caliph during these years, it was perhaps inevitable that other bloodlines, with their own dynastic ambitions, would enter the fray. But few would have imagined that the 'Abbasids, from an entirely separate clan within Quraysh, would be the claimants who won the caliphal prize, and put an end to Marwanid and Syrian power.⁵

Imperial expansion, from France to Farghana

Despite the tensions surrounding succession within the Marwanid family, the territorial expansion of the caliphate proceeded apace without any noticeable slowing until the eve of the third *fitna* (744). In keeping with the imperial vision established by the time of 'Abd al Malik, Marwanid imperial designs were in theory limitless. In practice, however, an Islamic empire centred upon Syria and based upon the military capabilities of Syrian tribal armies could only expand so far before breaking apart. Nevertheless, the immense territorial expansion of the caliphate is one of the Marwanid dynasty's great lasting achievements, establishing as it did the boundaries of the *dar al islam* (the 'abode of Islam'), which, excepting the case of Spain, would remain essentially the same well after the Marwanids had left the scene and Syria had ceased to be the centre of empire.

The west: North Africa, al-Andalus and the Berber revolt

At the death of 'Abd al Malik, the Maghrib – the region of North Africa excluding Egypt – was still an active military zone and an expanding imperial frontier. Indeed, by the reign of al Walīd, Cyrenaica was largely under control and securely attached to Egypt, and so a second base was required, close to the western lands that remained unconquered and nominally under Byzantine and Visigothic control. It was thus probably around 705 that Ifrīqiya was created as an administrative district (*wilaya*) in its own right. This region

⁵ On the third *fitna* and the rise of the 'Abbasids, see below.

(roughly modern Tunisia) had long been a theatre for raiding by Muslim troops from Egypt, though it had only recently been pacified in any definitive fashion. Its small garrison settlement at Qayrawan became the district's capital.⁶

Starting in 705, the Marwanids' western conquests, led by the talented commander and governor Musa ibn Nuṣayr, were directed at securing the central and western Maghrib. To extend their conquests the Marwanids, whose armies were already overextended on other fronts, badly needed cooperation from the Berber peoples of North Africa. This was not easily obtained. On the one hand, if most of the Berbers appear at least to have superficially converted to Islam and recognised Marwanid authority, many still provided fierce resistance. On the other, and perhaps because of this resistance, the Marwanids insisted upon exacting a levy of slaves from Muslim Berber tribes – a practice unknown in any other part of the caliphate.⁷ But Musa was ultimately able to make allies in the region and, with every mile westward, the importance of Berber manpower increased. By 710 the conquest of northern Africa was effectively complete. Musa withdrew to Qayrawan, leaving his *mawla*, the Berber Ṭariq ibn Ziyad, with a small body of Berber, Arab and black African troops in Tangier to take charge of affairs at the western limit of the Islamic world.⁸

With the Sahara providing an effective obstacle to expansion in the south, Spain or al Andalus, as it became known, was Ṭariq's next logical destination. The Iberian Peninsula was a wealthy and fertile land, and the kingdom of the Visigoths under Roderic was politically divided. After a desultory test raid onto its southern shores, Ṭariq led a full scale invasion in April 711, occupying the Straits and the area immediately around Algeciras. In July he decisively defeated the forces of Roderic in Sidonia; by October, Muslim troops had captured the old Visigothic capital of Toledo and what would later become

6 On the Muslim conquest of al Andalus, the classic point of departure is Evariste Lévi-Provençal, *Histoire de l'Espagne musulmane*, 3 vols. (Leiden, 1950–3), vol. I, pp. 1–89. More recently, and with more coverage of North Africa, Pedro Chalmeta, *Invasión e islamización: La sumisión de Hispania y la formación de al Andalus* (Madrid, 1994), is superb; see also Michael Brett, 'The Arab conquest and the rise of Islam in North Africa', in J. D. Fage and Roland Oliver (eds.), *The Cambridge history of Africa*, 8 vols. (Cambridge, 1978), vol. II: *From c. 500 BC to AD 1050*; Hugh Kennedy, *Muslim Spain and Portugal: A political history of al Andalus* (London, 1996), pp. 1–29.

7 On the Berber slave levy, see Brett, 'Arab conquest', pp. 506–7; and Elizabeth Savage, *A gateway to hell, a gateway to paradise: The North African response to the Arab conquest* (Princeton, 1997), pp. 67–79.

8 Against claims that the 'Arab conquests' in the west were really mass conversions in disguise, see the response of Pierre Guichard, 'Les Arabes ont bien envahi l'Espagne: Les structures sociales de l'Espagne musulmane', *Annales*, 29 (1974).

one of the capitals of al Andalus, Cordoba. In the mountainous north and north east, Visigothic elements held on by making separate treaties with the Muslims. In the summer of 712 Musa returned to Spain and captured Seville, which became his seat in the province. The next year he took Mérida, while another body of troops, under his son 'Abd al 'Azīz, turned its attention to Málaga and the south east and, later, central Portugal, establishing treaties with cities such as Lisbon and Coimbra. By 714 Muslim troops had followed the remnants of the Visigothic army into the Cantabrian mountains, finally subduing Galicia and Asturias.

Further campaigns continued intermittently after 714, but by this time news of the startling successes of Ṭariq and Musa had reached al Walīd in Syria. Significantly, he is said to have been most alarmed at Musa's ambitions and, one presumes, that he was acting a little too independently in such a remote and wealthy province.⁹ Musa and Ṭariq were ordered back to Syria at once, and they brought with them a vast amount of plunder and slaves intended to propitiate the caliph. But even without Musa and Ṭariq, Muslim troops continued to make raids. To the south, armies penetrated deep beyond the Atlas into the Sus around 736, reaching 'the land of the Blacks' and taking great plunder. In the north, from al Andalus, armies raided across the Pyrenees into southern Gaul and the Languedoc, occupying some towns and establishing a short lived base at Narbonne. But, like the contemporary naval raids from Ifriqiya into Byzantine Sicily and Sardinia, these forays into southern France were ephemeral. Toulouse was attacked in 721, Autun pillaged in 725 and, near Poitiers, a Muslim army was defeated by Charles Martel in 732. Although raids would continue across the Pyrenees, historical hindsight would view this otherwise unimportant failure near Poitiers as the high water mark of Muslim expansion in the west.¹⁰

It is tempting to view the remarkable expansion of the caliphate's western borders as testimony of the strength of the caliph in Syria. But such a view ignores the high degree of autonomy that commanders in the field possessed and the rather uneven spread of caliphal authority in lands that had been conquered. Indeed, on almost every front, Muslim armies that were engaged in external conquests of expansion were also called upon to pacify populations

9 See, for example, Abu al Qasim 'Abd al Raḥman ibn 'Abd al Ḥakam, *Futuḥ Miṣr wa akhbaruha*, ed. C. C. Torrey (New Haven, 1922), pp. 210 11, where al Walīd is angered that Musa has thrown Ṭariq in prison without consulting the caliph.

10 On transpyrenean conquest and settlement, see Philippe Sénac, *Musulmans et Sarrazins dans le Sud de la Gaule du VIIIe au XIe siècle* (Paris, 1980); Roger Collins, *The Arab conquest of Spain, 710 797* (Oxford, 1989), pp. 86 96.

well within the frontiers of the caliphate who had not yet been subdued or who had thrown off their allegiance to the caliphs.

The Berber revolt of 740–1 is instructive for what it reveals not only about the ethnic exclusivity of Marwanid Islam, but also about the ebb and flow of central power in the Maghrib.¹¹ The revolt spanned territories from Spain to Tunisia, pitted Berbers against their conquerors and effectively removed the Maghrib from control of Syria under Hisham. It is often described in medieval and modern sources as a ‘Kharijite’ rebellion, but the causes for the revolt have more to do with the unequal treatment of the Berbers at the hands of their Arab conquerors than with issues of doctrine or leadership of the Muslim community. And while the revolt at times adopted the language of Islam to validate its actions, rebel leaders identified as Kharijites (especially of the Ṣufriyya variety) were only part of the larger movement. Indeed, it may best be seen as the response of one conquered region’s formerly non-Muslim populace to the pressures of a centralising administrative apparatus and the cultural contradictions that were imported with it, as the provincial populace found themselves squeezed by the demands of the central government and blocked by prevailing notions of Arab privilege.

Hisham, like his predecessors, endeavoured to keep the distant Maghrib tight in the administrative grip of Syria, transferring, in 734, the governor of Egypt, ‘Ubayd Allah ibn al Ḥabḥab, to Ifrīqiya in the hope of bringing the taxation and fiscal administration of the Maghrib into step with the rest of the caliphate. The reaction to his policies took time, but was explosive. In 740 ‘Ubayd Allah’s representatives in Tangier and Tlemcen were murdered by the followers of a Berber who is described as a Ṣufī Kharijite and who took the caliphal title of *amīr al mu’minīn*.¹² ‘Ubayd Allah sent a large body of troops from Qayrawan against the rebels, but, in a bloody confrontation known as the ‘battle of the Nobles’, they were defeated. At this point Hisham reacted decisively, sending in a massive new army recruited from various sub districts of Syria and from Egypt. The Syrians reached the rebels late in 741 on the Sebou river in northern Morocco and were, once again, roundly defeated.

In the meantime, the Berber revolt had had its impact in al Andalus, where Berber troops revolted in the north of the peninsula and marched on Cordoba. Desperate for support, the governor there joined forces with the Syrians who

11 On the Berber revolt, see Brett, ‘Arab conquest’, pp. 517–21; Savage, *Gateway to hell*, pp. 43–5 and *passim*, and Blankinship, *Jihad state*, pp. 203–22.

12 Aḥmad ibn Muḥammad ibn ‘Idharī, *al Bayan al mughrib fī akhbar al Andalus wa al Maghrib*, ed. G. S. Colin and E. Levi Provençal, 4 vols. (Leiden, 1948–51), vol. I, p. 53; cf. Ibn ‘Abd al Ḥakam, *Futuḥ Miṣr*, p. 218.

survived the debacle at the Sebou river and urged them to join him across the Straits. These combined forces finally defeated the Berbers outside Toledo in 742. All seemed well, but the arrival in al Andalus of large numbers of Syrian troops brought with it traditions of tribal factionalism and tensions with the early settlers already in place, and these would frustrate further attempts at central control from Syria.¹³

Finally, things fell apart in Qayrawan and Tunis, where Kharijite rebels had taken over. A new army was sent from Egypt (significantly not from Syria) that finally took Qayrawan back in 742, pushing the rebels into the oases of southern Ifrīqiya. But in 743 Berber rebels seized Tripoli, and ‘Abd al Raḥman ibn Ḥabīb al Fihri, a commander who had survived the battle of the Nobles and fled into al Andalus, now returned to North Africa and seized power as autonomous governor of the Maghrib. With the murder of the caliph al Walid II in 744, as Syria descended into the third *fitna*, the Maghrib and al Andalus were autonomous regions themselves divided by unabated Berber revolts and military factionalism. The Maghrib would have to wait until the arrival of ‘Abbasid authorities from Baghdad before feeling the firm hand of central authority again. But by then it was Iraq and Khurasan that established order, and al Andalus would in any case be removed altogether, taken by a Marwanid prince fleeing the horrors of an ‘Abbasid revolution in the east.

The north: Byzantium and the Caucasus

In most medieval and modern accounts of the expansion of the Marwanid caliphate, the Byzantine empire is taken to be the caliphate’s primordial enemy. And while there is ample evidence of non military contact between Byzantium and the caliphate in the realms of commerce and intellectual culture, for example it is war that is the defining feature of Byzantine Muslim relations under the Umayyads.¹⁴ However, the historical record of actual conquest on this frontier pales in comparison to the activities of Marwanid armies on other fronts in the west, and most notably on the

¹³ On the situation in al Andalus during the Berber revolt and the coming of the Syrians and its fallout, see Chalmers, *Invasión*, pp. 307–48; Kennedy, *Muslim Spain and Portugal*, pp. 23–9.

¹⁴ On non military contacts, see H. A. R. Gibb, ‘Arab Byzantine relations under the Umayyad caliphate’, *Dumbarton Oaks Papers*, 12 (1958); Hugh Kennedy, ‘Byzantine Arab diplomacy in the Near East from the Islamic conquests to the mid eleventh century’, in J. Shepard and S. Franklin (eds.), *Papers from the twenty fourth Spring Symposium of Byzantine Studies* (Aldershot, 1992). On the alleged influence of Islamic attitudes towards images upon Byzantine iconoclasm, see Sidney H. Griffith, ‘Images, Islam and Christian icons’, in Pierre Canivet and Jean Paul Rey Coquais (eds.), *La Syrie de Byzance à l’Islam, VIIe–VIIIe siècles* (Damascus, 1992).

Caucasus frontier to the immediate east, where the Khazars threatened to strike into eastern Anatolia and even northern Iraq. The stasis on the Byzantine frontier is especially marked in the period after the failed siege of Constantinople in 718. By then, both the caliphate and Byzantium had their own concerns that kept them from further conquests of any significance.¹⁵

While the Byzantine emperor Justinian II reigned, Marwanid armies in Anatolia were not able to conquer any significant new lands (the capture of the fortress of Tyana in 708 being an important exception), even if they did repeatedly defeat their Byzantine adversaries in the field. After Justinian II's murder in 711, however, the Byzantine empire destabilised, and so Sulayman seized the moment to embark on a massive campaign aimed at nothing less than the conquest of Constantinople. By 717 a massive army under Maslama was encamped before the Byzantine capital, while a fleet blockaded the port. The siege stretched on for months, with supplies for the Muslims becoming scarce. When 'Umar II succeeded as caliph, therefore, he inherited an expensive campaign that was more and more obviously fruitless; and so, in 718, he ordered Maslama and the armies to lift their siege. 'Umar further withdrew all troops from the frontiers to the region of Malatya, and sent no further troops against the Byzantines.

Thenceforth, until the collapse of the Umayyad dynasty itself, most military activity directed against the Byzantines consisted of desultory raiding rather than permanent conquest. After the failed siege of 718, it was the reign of Hisham that saw the most significant action. The year 725 was particularly busy, with Hisham's son Mu'awiya raiding deep into Anatolia around Dorylaeum, and a fleet attacking Cyprus. In the next year Maslama made an equally stunning raid into Cappadocia, followed by a lightning raid by Mu'awiya ibn Hisham on Nicaea itself, the closest the Muslims would come to Constantinople until the reign of the 'Abbasid caliph al Rashid. But in 739, at Ancyra, the Umayyad dynasty made its last capture of a Byzantine town, a success as minor as the defeat that followed was grand, when a Byzantine campaign in 740 led in person by the emperor Leo III and his son Constantine destroyed the Muslim army. Hisham himself took to the field to defend

15 On Umayyad Byzantine warfare, a starting point is E. W. Brooks, 'The Arabs in Asia Minor 641–750, from Arabic sources', *Journal of Hellenic Studies*, 18 (1898), a collection of reports from some of the better known Arabic sources. On sieges of Constantinople, see Marius Canard, 'Les expéditions des Arabes contre Constantinople dans l'histoire et dans la légende', *JA*, 208 (1926). On the siege of 718, see Rodolphe Guiland, 'L'expédition de Maslama contre Constantinople (717–718)', *Revue des études byzantines*, 17 (1959). For the reign of Hisham, see Blankinship, *Jihad state*, pp. 117–21, 162–3, 168–70, 200–2.

Malatya from the reinvigorated Byzantines, but territorial conquest was still out of the question. The Umayyads' last raid was under al Walid II in 743, an uneventful foray whose destination is not even recorded. Shortly thereafter al Walid ordered the Muslim populace of Cyprus to be evacuated. On the eve of the third *fitna* Muslims on the Byzantine front were running scared.

Further to the east, on the Caucasus front, Marwanid troops acquitted themselves much more admirably, establishing by the beginning of the third *fitna* a secure frontier south of the Caucasus bolstered by fortresses and garrisons at the major passes.¹⁶ But this was not an easy achievement, requiring as it did a quiescent Armenia and the subjugation of the Khazar khaqanate, which was, now that the Byzantines were on the defensive, the greatest threat to the survival of the caliphate. Indeed, by the time al Walid took power in 705, the Marwanids and the Khazars were Transcaucasia's principal 'super powers', Byzantium having been eclipsed as a political (but not cultural) force. Only the neighbouring Christian region of Georgia would resist outright annexation by the Marwanids or the Khazars, but it would be devastated in the process.¹⁷

The provinces of Armenia, with its capital at Dabīl (Dvin), and Azerbaijan, with its capital at Ardabīl, provided the main jumping off points for Marwanid expansion into Transcaucasia. Of these two provinces, Christian Armenia was the latecomer to caliphal rule. In 705 the Muslim governor had to brutally crush a widespread rebellion of Armenian princes who had, with Byzantine help, resisted Muslim annexation. But after 711, when a Muslim garrison was established at Dabīl, local elites more or less acquiesced to the situation and Armenia was integrated into the caliphate, even supplying local troops as needed. Conflicts between the Khazars and the Muslim armies in the region intensified only after 715, when a Muslim garrison was established at al Bab (or Bab al Abwab). In the winter of 722, for example, the Khazars made a spectacular raid into Muslim held Armenia and inflicted heavy losses. This was followed by a Muslim retaliatory raid in the same year, which drove the

16 On the Caucasus in Umayyad times, see J. Laurent, *L'Arménie entre Byzance et l'Islam depuis la conquête arabe jusqu'en 886*, rev. Marius Canard (Paris, 1980); René Grousset, *Histoire de l'Arménie des origines à 1071* (Paris, 1947). On the Khazars, see Peter B. Golden, *Khazar studies: An historico philosophical inquiry into the origins of the Khazars*, 2 vols. (Budapest, 1980); D. M. Dunlop, *A history of the Jewish Khazars* (New York, 1954); Blankinship, *Jihad state*, pp. 106–9, 121–5, 149–54, 170–5.

17 On Marwanid raids into Georgia, see B. Martin Hisard, 'Les Arabes en Géorgie occidentale au VIII^e siècle: Étude sur l'idéologie politique Géorgienne', *Bedi Kartlisa*, 40 (1982).

Khazars back across the Caucasus. Subsequent Khazar raids on Armenia were repelled until the reign of Hisham.

In 725 Maslama ibn ‘Abd al Malik was named governor of Armenia and Azerbaijan, and we find him campaigning in Khazar territory in 727 and successfully repelling the Khazars’ raids into Azerbaijan, which seems to have attracted Khazar attention now that Armenia was denied them. Indeed, in 730, with Maslama removed from office, the Khazars inflicted a huge disaster on the Muslims there. While most of the Muslim army was scattered in the field, the Khazars outmanoeuvred them and attacked the capital, Ardabil. A desperate attempt by the Muslim armies to save the city failed at the battle of Marj al Sabalan outside the city, during which the governor was killed. A large number of Muslim troops and civilians were likewise killed or taken prisoner. All of Azerbaijan was given over to plunder, and outliers of the Khazar forces even turned up in the vicinity of Mosul, a clear demonstration of the vulnerability of the central lands of Iraq and Syria should the northern front collapse. Hisham ordered a massive and immediate riposte. By 731 Azerbaijan had been recaptured and the war had been brought to the Khazars, who were regrouping in the northern steppe.

In 732 Marwan ibn Muḥammad, the future caliph Marwan II, was named governor of Armenia and Azerbaijan. So desperate were the Marwanids for assistance against the Khazars (who had themselves allied with Byzantium in the meantime) that Marwan granted Armenia virtual autonomy under Ashot Bagratouni in return for military support. Marwan also embarked on a fiscal reorganisation of the province, and re garrisoned the northern front almost exclusively with his Qaysī troops. With regard to Marwan’s immediate military concerns, these steps seem to have resulted in a stable frontier. Most subsequent campaigns north of the Caucasus were unspectacular: no lasting conquests, but no startling defeats either. The only exception was in 737, when Marwan campaigned deep into Khazar lands, reaching the *khaqan*’s capital on the Volga, al Bayḍa’ (Itil). While this did not eliminate the *khaqan* or the Khazar threat, many prisoners were taken, and there were no further Khazar raids south of the Caucasus in Umayyad times.

The east: Transoxania and Sind

In the eastern reaches of the caliphate, the Marwanids expanded primarily on two fronts: in Transoxania in the north east and Sind in the south east. These two fronts were separated by a third region of conflict, comprising Sīstan and neighbouring Zabulistan, which never yielded to Umayyad attempts to control it. Indeed, in 727, its ruler, the *zunbīl*, annihilated a Muslim army in the

region, including its commander. The region, with its imposing deserts and mountains, remained a glaring exception to Marwanid imperial success.¹⁸

In the north east, Khurasan served as the base for the conquest of Transoxania, including the rich trading cities of Sogdia, and for attempts to subjugate the Turkish Türgesh confederation that dominated the region.¹⁹ Al Walid's governor of Khurasan, Qutayba ibn Muslim, was responsible for some of the most significant early conquests into Transoxania, thanks largely to his close (if not always warm) cooperation with al Ḥajjaj. Starting in 705, Qutayba subjugated much of Tūkhārīstan, capturing Balkh, Āmul and Bukhara by 709. Nearby Samarqand remained unconquered, but paid Qutayba tribute. The next few years were years of consolidation, with mopping up campaigns in Tūkhārīstan (whose ruler, the *jabghu*, was sent to Damascus as a trophy). As in North Africa and the Caucasus, local levies played an important role in furthering the conquests for a caliphate that was finding itself overstretched. By 712 the rear position of Khwarazm had been conquered and colonised, allowing Qutayba to return in force to Transoxania, capturing Samarqand outright and establishing a garrison there.

A more prudent commander would have stopped to strengthen his hold over these newly conquered territories. But Qutayba pressed on, leaving much of Sogdia unsubdued, and headed for the lands across the Jaxartes. While his Iranian troops subdued Shash, Qutayba pushed into Farghana. To the rear, however, the local princes of Sogdia took advantage of Qutayba's preoccupations far to the east, and called out for aid to rid them of Muslim rule. They first appealed to the Türgesh *khaqan* without success, and then to the Chinese emperor. As a result, in 713 Qutayba (or al Ḥajjaj) was likewise obliged to open negotiations with the Chinese emperor to make his claims. According to Chinese sources, the Muslim embassy was favourably received despite the fact that the ambassadors refused to kow tow before the emperor.²⁰

The raids into the Jaxartes provinces recommenced, with the outright conquest of Farghana the clear goal. But the death of al Ḥajjaj in 714 and

18 On Sistan in early Islamic times, see C. E. Bosworth, *Sistan under the Arabs, from the Islamic conquest to the rise of the Ṣaffarids (30 250/651 864)* (Rome, 1968).

19 On Umayyad expansion in the north east, see H. A. R. Gibb, *The Arab conquests in Central Asia* (London, 1923); and M. A. Shaban, *The 'Abbasid revolution* (Cambridge, 1971).

20 On Muslim embassies to China, see E. Chavannes, *Documents sur les Tou Kiue (Turcs) occidentaux* (St. Petersburg, 1903); and H. A. R. Gibb, 'Chinese records of the Arabs in Central Asia', *BSOAS*, 2 (1922); Zhang Jun yan, 'Relations between China and the Arabs in early times', *Journal of Oman Studies*, 6 (1983).

then of al Walīd in 715 prevented any such activity. Later in 715, unwilling to relinquish command to any new governor that the new caliph, Sulayman, might send, Qutayba revolted. But he had misjudged his own men, who turned on him, and killed him in Farghana. Sulayman ordered these troops to be immediately withdrawn to Marw, where they were disbanded. As it would happen, Qutayba's death marked the end of Umayyad expansion in the north east. When 'Umar II took power he ordered the garrisons in Transoxania disbanded, but he died before they were obliged to obey. Trouble for the Muslim garrisons continued as the local princes of the region were increasingly restless and sent many embassies appealing to the Chinese emperor or his Türgesh vassals for aid. The Chinese never became directly involved in Transoxanian affairs, but the Türgesh were not shy. In 720 they came to the aid of some Sogdian rulers and marched on Samarqand, but this only elicited a Muslim counter attack, which routed the Türgesh and recaptured all of Sogdia.

Under Yazīd II, raiding into Transoxania culminated in the 'Day of Thirst' (724), a debacle from which the Muslims of the north east never fully recovered. Thenceforth the Muslims were on the defensive, their hold on lands east of the Oxus shaky. The Türgesh raided across into Khurasan and local populations rose in revolt, even in long subdued locales such as Khwarazm. In 731 a further blow came at the battle of the Pass, in which the Muslims barely managed to fend off a joint Türgesh–Sogdian assault on Samarqand. To make matters worse, in 734 a pious and battle-scarred veteran named al Ḥarith ibn Surayj revolted against what he perceived to be Marwanid iniquities in the province. After capturing Balkh he and his Khurasanī followers were forced to retreat into Ṭukharistan, and from there he joined the side of the Türgesh *khaqan*. In 737 the Türgesh and their new allies renewed their attacks, launching raids into Transoxania, Ṭukharistan, and even Khurasan itself. But this time, at the battle of Kharīstan, the Muslims were prepared and, with help from Iranian allies, they captured the *khaqan*'s encampment, and the Türgesh were thrown into confusion and fled. Al Ḥarith escaped to Shash, but later a second attempt at rebellion on his part ended in his death. In 738 the *khaqan* was assassinated and the Türgesh confederation dissolved amidst internal rivalries. While this put an end to any further threat from the Türgesh to the Muslims, it also removed the only buffer in Central Asia between the Muslim caliphs and the Chinese emperors.

In the same year Naṣr ibn Sayyar was named governor of Khurasan; he would be the last Umayyad governor of the province. An old Khurasan hand, Naṣr seems to have been well liked by locals, and he did his best to remain

above tribal factionalism in the army. In 741 he launched a campaign on Shash, and passed through but did not formally conquer the region of Ushrusana, and raided into Farghana, where the local king agreed to pay tribute. In 744, in recognition of the new political situation between them, Naṣr sent a huge delegation to China, including representatives of many of the local princes of Transoxania and Ṭukharistan. As the caliphate slipped into civil war, then, it seemed as if the Umayyads would finally have the success they had sought in the north east, with a subjugated Transoxania, an expanding frontier of influence, a respected governor and a relatively calm population.

In the south east, the Marwanids experienced equally spectacular successes and failures as their armies consolidated their hold on Sind and, briefly, extended their conquests into India.²¹ At the death of ‘Abd al Malik Sind was still unconquered, a largely Hindu kingdom with a Buddhist minority ruled by a monarch named Dahir from his capital, Daybul. In 711, however, al Ḥajjaj appointed Muḥammad ibn Qasim al Thaqafi at the head of a large body of Syrian troops over the district of Makran, entrusting him with the task of extending Marwanid rule into Sind. By the time of his death three years later, Marwanid rule extended over the lower Indus Valley and even beyond. Resistance was fiercest at Daybul, which fell after a few months of siege, in 711. The king, Dahir, was later killed in battle near Rawar, and the country was opened to Marwanid conquest.

Still, control of these distant lands stretched the abilities of the caliphate, and for most of the Marwanid period the Indus river formed the border between the western lands of Sind under Marwanid control and eastern lands in, at best, a tributary relationship. In 723 the Qaysī commander Junayd ibn ‘Abd al Raḥman al Murri was named governor, and he extended Marwanid control east of the Indus for the first time, securing Daybul and subduing rebellious princes by 724. He then embarked on extensive campaigns in the wealthy lands of north west India, Rajasthan and Gujarat, but information on the precise locales involved, not to mention the chronology, is very unclear.²² But whatever the case, these conquests, even Daybul, were soon lost, perhaps a result of local rebellions against attempts at Muslim rule.

Some time in the 730s two new forward positions were established at al Maḥfuza and al Maṣūra, near Brahmanabad. These were to serve as

21 On Sind, see Francesco Gabrieli, ‘Muḥammad ibn Qasim ath Thaqafi and the Arab conquest of Sind’, *East and West*, n.s., 15 (1964 5); and Derryl N. Maclean, *Religion and society in Arab Sind* (Leiden, 1989).

22 Blankinship provides a convincing reconstruction: *Jihad state*, pp. 131 4, 147 9, 186 90, 202 3.

bases from which to consolidate Muslim rule over Sind and to relaunch conquests into India: many lands in Gujarat that had been lost earlier were now recaptured, and even Kashmir appears to have been threatened. By 739 Marwanid armies ranged as far south as Navasarika in southern Gujarat, the furthest into India the Umayyads would ever go. It was not to last. After the Muslim defeat at Navasarika a new governor arrived in 740, the son of the great conqueror Muḥammad ibn Qasim. But an alliance of local princes revolted against the Muslims, rolling back definitively the conquests east of the Indus and besieging the governor at al Manṣura. New troops arrived to crush the rebellious Sindis, but, as the constant see-sawing of conquests in the area suggests, the Marwanids had reached the limits of their expansion.

Administrative centralising

The Marwanids are said to have taken the decentralised system of regional leaders and tribal groupings that made up the Sufyanid conquest state and transformed it into a centralised empire. This is true in broad terms, and the later heavily centralised state of the ‘Abbasids certainly owes its existence to the experiments of the Marwanids.²³ In general, the expanding empire under Marwanid control was divided into a number of provinces (*wilayat*), themselves divided and subdivided down to the local district (the *kura*, *rustaq* or *tassuj*), and each level of the administration had, in theory, its responsible official in charge of, at the very least, revenue collection. At the highest level, that of the provincial governor (known variously as the *walī*, *amīr* or ‘*amil*’), responsibilities were often divided between a military official and an administrative/fiscal official, who might be appointed by the caliph himself. Any provincial governor might be expected to have subordinates and a staff assigned with him, a body of guardsmen (*shurṭa*), and perhaps a judge (*qaḍī*). As provincial administration was the most lucrative and powerful position one could obtain, these positions attracted the most competition among tribal factions and the most anxiety from caliphs wary of over-powerful governors in distant corners of the caliphate.

But centralisation is a slow and messy process. Indeed, one should properly speak of Marwanid *centralising* rather than Marwanid centralisation, as the direct power of the caliph over provincial matters was at no time a *fait accompli*. This was largely due to practical concerns: it was easier for central

²³ Irit Bligh Abramski, ‘Evolution vs. revolution: Umayyad elements in the ‘Abbasid regime 133/75–32 932’, *Der Islam*, 65 (1988).

control to take root in those provinces that were closer to Syria and in which Muslim populations had long been resident. In newly conquered or distant provinces other arrangements prevailed. Thus Greek continued to be used as the administrative language in Egyptian papyri until early in the reign of al Walīd, in 706; in Khurasan Arabic did not take over as the administrative language until 742. Moreover, provincial and sub provincial boundaries were not etched in stone and could change as circumstances, and individual governors, warranted.

There is sufficient numismatic and literary evidence to suggest that most of the provinces of the caliphate were grouped into three or four 'superprovinces': Ifrīqiya and the West; al Jazīra and the North; and Iraq and the East (with an occasionally independent Khurasan).²⁴ However, it is likewise clear that, from the point of view of Syria's governing elite, the caliphate was divided into a core zone of firmly held provinces frequently governed by close kinsmen or protégés of the caliphs and a periphery of more remote provinces administered by other parties, who might enjoy a certain autonomy from Syrian demands.

The heart of the caliphate was thus the core area of provinces that experienced frequent direct rule by Umayyad kinsmen, a family preserve that included Egypt, al Jazīra, Iraq and the Hijaz. But the heart of this heart was of course Syria, the metropolitan province, where, until the Marwanid system collapsed during the third *fitna*, all the caliphs made their home. Unique among all other provinces, Syria was originally divided into four sub districts or *ajnad* (sing. *jund*), a term designating both these districts and the armies (most of them Yamanī tribes) levied in them. They were, from south to north: Filastīn (with its capital at al Ramla); al Urdunn (with its capital at Tiberias); Damascus; and Ḥimṣ (these last two named after their capital cities). At a later date, perhaps under the Sufyanids, the *jund* of Qinnasrīn, with its heavy concentrations of Qaysī tribes, was created, and detached from Ḥimṣ. This unique administrative arrangement can be explained by the importance of the Syrian tribal armies as props of the Marwanid dynasty and as the elite military forces of their expanding caliphate. Although the Qaysī troops of the nearby province of al Jazīra would come to dominate political and military matters more and more, it was upon the troops of Syria that the Marwanids relied in

²⁴ I borrow the term 'superprovince' from Blankinship, *Jihad state*, p. 39. For numismatic evidence, see Denise A. Spellberg, 'The Umayyad North: Numismatic evidence for frontier administration', *American Numismatic Society Museum Notes*, 33 (1988); Michael Bates, 'History, geography and numismatics in the first century of Islamic coinage', *Revue Suisse de Numismatique*, 65 (1986).

their rise to power after the second *fitna*, and it was these troops, the *ahl al Sham*, that they used to subdue and occupy Iraq, and were sent as needed even to the most distant provinces of the caliphate – not without tensions with the Muslim armies and settlers who had preceded them.

Of the remaining provinces of this core area, Egypt, al Jazīra and Iraq served as the centres of larger superprovinces – but only in the case of Egypt, thanks to the papyri, do we have any detailed sense of the actual mechanics of Marwanid administration and the stakes involved. Here, the earliest Muslim administrators adopted much of the extant Byzantine administrative system. But by Marwanid times the system had become much more efficient and centralised within the province, with greater powers for the local level tax officials (called *pagarchs*) who were placed directly under the control of the governor in Fustāt.²⁵ And a succession of skilled, if not ruthless, administrators such as Qurra ibn Sharīk (709–15) and ‘Ubayd Allah ibn al Ḥabḥab (724–34) initiated land surveys and censuses, reorganised the *dīwan*, built and expanded mosques, improved irrigation, imposed new taxes on Muslims, limited movement of the subject population, settled new areas, built up the Umayyad fleet and encouraged conversion to Islam. The result was an increase in state revenues and central authority, and, inevitably, revolts of segments of the indigenous Coptic populace.²⁶

But even in these more centralised core areas, flexibility and change were the rule. Thus, even in Egypt caliphal appointees had to bow to local sentiment when choosing subordinate officials and, at least in some places, the central power of Fustāt was diffused at the local level.²⁷ In parts of the province of Mosul (which was often separate from al Jazīra) the governors had little influence in the countryside, and instead relied upon the Christian

25 On the generalities of Umayyad administration in Egypt, see H. I. Bell, ‘The administration of Egypt under the Umayyad khalifs’, *Byzantinische Zeitschrift*, 28 (1928); G. Frantz Murphy, *The agrarian administration of Egypt from the Arabs to the Ottomans* (Cairo, 1986). Petra M. Sijpesteijn, ‘Shaping a Muslim state: Papyri related to a mid eighth century Egyptian official’, Ph.D. thesis, Princeton University (2004), pp. 18–33, 92–118, offers the clearest exposition to date.

26 On Qurra, see Nabia Abbott, *The Qurrah papyri from Aphroditō in the Oriental Institute* (Chicago, 1930); Y. Ragib, ‘Lettres nouvelles de Qurra ibn Šarīk’, *JNES*, 49 (1981). On ‘Ubayd Allah, see N. Abbott, ‘A new papyrus and a review of the administration of ‘Ubayd Allah b. al Ḥabḥab’, in G. Makdisi (ed.), *Arabic and Islamic studies in honor of Hamilton A. R. Gibb* (Cambridge, MA, 1965). On the ‘alms tax’ levied on Muslim lands to cope with fiscal shortfalls, see Sijpesteijn, ‘Shaping a Muslim state’, pp. 119–88.

27 As stressed in H. Kennedy, ‘Egypt as a province in the Islamic caliphate, 641–868’, in C. F. Petry (ed.), *The Cambridge history of Egypt*, vol. I: *Islamic Egypt, 640–1517* (Cambridge, 1998). For a revision of the strict centralisation model based on papyri from the Fayyum, see Sijpesteijn, ‘Shaping a Muslim state’, pp. 92–118.

shaharija (the local gentry) to do their administrative dirty work.²⁸ And Iraq, with its Syrian occupying forces and recently demobilised tribes in the *amṣar*, had its own unique challenges for its governors. Here, men such as al Ḥajjaj and Yusuf ibn ‘Umar al Thaqafī kept an eye on the east, and on Kufa in particular. The Ḥijaz and Yemen were excluded from the superprovinces (eastern Arabia fell under al Baṣra’s control), no doubt because they lacked any active military fronts or waves of settlement. Only the prestige of the Holy Cities of Mecca and Medina obliged the Marwanids to keep the region within the control of the family circle. In other aspects the region had become a backwater: major roads were not even built until the reign of the ‘Abbasid caliph al Maḥdī.

Beyond these core regions dominated by the ruling family lay a periphery of distant frontier provinces where the authority of the Marwanid dynasty was felt less directly.²⁹ To the west, the authority of the caliph weakened as it spread further from Syria, filtered first through Egypt, and then through Ifrīqiya, so as to be in al Andalus more of an ideal than a reality. On the caliphate’s eastern flank, Iraq might be governed by loyal Thaqafī strongmen, but in Iraq’s eastern dependencies such as Khurasan the men chosen to govern often did so with little input from the caliph. If al Andalus and the west barely felt the authority of the caliphs, Khurasan and the east toed the line only slightly better, oscillating between local autonomy and direct Syrian rule. Finally, compared with the western and eastern flanks, the northern provinces governed from al Jazīra Armenia, Arran and Azerbaijan were long the preferred arenas of Marwanid kinsmen, perhaps reflecting the gravity of the Khazar and Byzantine threats. With this one possible exception in the north, as much as the Marwanids could rely upon relatively easy administration of their core territories, the imposition of authority in the periphery was never a given.

Settlement and economy

The economic forces that undergirded Syria’s role as the centre of empire remain poorly understood. That said, the two most significant forces shaping

28 On Mosul and al Jazīra in Marwanid times, see C. F. Robinson, *Empire and elites after the Muslim conquest: The transformation of northern Mesopotamia* (Cambridge, 2000).

29 What follows can be easily seen by comparing appointments to provincial governorates. See Eduard von Zambaur, *Manuel de généalogie et de chronologie pour l’histoire de l’Islam*, 2nd edn (Bad Pyrmont, 1955). For the Maghrib, see Hicham Djait, ‘Le Wilaya d’Ifriqiya au IIe/VIIIe siècle’, *SI*, 27 (1967); Salvador Vilá Hernández, ‘El nombramiento de los walīes de al Andalus’, *al Andalus*, 4 (1936–9).

the economy in this period are undeniable, and have already been discussed: imperial expansion and administrative centralising. Along with these two forces were a number of associated trends, most of which have their roots in Late Antiquity, and the Sasanian economy in particular, but which underwent greater intensification during the early and middle eighth century.³⁰

The monetarised economies of Late Antiquity continued unabated under Islam, and here we are best informed about the core areas of the caliphate.³¹ In Egypt, Iraq, Iran and Syria, for example, copper coins continued to be minted locally throughout the Umayyad period. Although gold and silver coins were not minted in Egypt until the 'Abbasid period, there is abundant evidence in the papyri and in glass weights of foreign gold and silver being used in commercial and fiscal transactions.³² In Syria, Iraq and the east, reformed gold and silver issues are well documented for the Marwanid period.³³ Nevertheless, we should imagine that a customary economy revolving around barter and payments in kind existed to some degree alongside the monetarised economy. This can be documented in Egypt, and was undoubtedly true of other regions as well.³⁴

The Late Antique tendency for large estates, worked by tenant farmers, to proliferate in the hands of the powerful – and to grow ever larger – also continued in Marwanid times. 'And if you are able to, obtain for me the land of Bilatus ibn Bihawīh's which you mentioned, if you think it a good idea. Or tell Yuhannis ibn Sawirus to give it to me, for he has already promised me ten

30 For the broader context, see Chris Wickham, *Framing the early Middle Ages: Europe and the Mediterranean, 400–800* (Oxford, 2005). For a synthetic sketch, see Alan Walmsley, 'Production, exchange and regional trade in the Islamic East Mediterranean: Old structures, new systems?', in Inge Lyse Hansen and Chris Wickham (eds.), *The long eighth century* (Leiden, 2000). Specific trends have been identified in greatest detail by Michael G. Morony, 'Economic boundaries? Late Antiquity and early Islam', *JESHO*, 47 (2004).

31 Morony, 'Economic boundaries', pp. 170–2.

32 Michael L. Bates, 'Coins and money in the Arabic papyri', in Y. Ragib (ed.), *Documents de l'Islam médiéval: Nouvelles perspectives de recherche* (Cairo, 1991). On the continued monetisation of Egypt throughout the eighth century, see Jairus Banaji, *Agrarian change in Late Antiquity: Gold, labour, and aristocratic dominance* (Oxford, 2001), p. 188. On the copper coinage of Syria, see Shraga Qedar, 'Copper coinage of Syria in the seventh and eighth century AD', *Israel Numismatic Journal*, 10 (1988–9).

33 John Walker, *A catalogue of the Muhammadan coins in the British Museum*, vol. I: *A catalogue of the Arab Sassanian coins* (London, 1941); vol. II: *A catalogue of the Arab Byzantine and post reform Umayyad coins* (London, 1956). Michael L. Bates, 'The coinage of Syria under the Umayyads, 692–750 AD', in M. A. Bakhit and R. Schick (eds.), *The history of Bilad al Sham during the Umayyad period: Proceedings of the third symposium* (Amman, 1989), vol. II.

34 On the mixed economy of Egypt, see Sijpesteijn, 'Shaping a Muslim state', pp. 71–2, n. 141.

feddans.' These were the orders issued in 735 from one such landlord to his estate manager in the Fayyum, preserved in a papyrus letter that testifies to the brisk business of land grabbing in Egypt and, incidentally, one of the first attested Muslim large estate holders known to the documentary record.³⁵ Large estates are likewise attested in Iraq and North Africa, but the situation was mixed in Syria and Mesopotamia, where, on the whole, small farms and villages seem to dominate the literary and archaeological record. The proliferation and growth of large estates are related to another trend: the spread of irrigated agriculture. Under the Marwanids some areas of the caliphate came under cultivation that had either never been cultivated, or that had at least been neglected for generations.³⁶

What all this implies, of course, is a market in agricultural produce and, one should add, specialised processed goods such as oil and wine, and industrial goods such as pottery and glass. 'Make sure, O Abu 'l Ḥarith, that you help out for my sake Yuḥannis ... the old man, with the mill wheat and sift it and take it. And when each one is done, send Zayd and have him measure each one, and order Sanba not to forget to improve the field.' Thus ran more advice from our over anxious Fayyumī landlord, himself miles away from the estate, selling part of his wheat harvest in Alexandria (he also made wine). These were the classic consumer goods of the ancient world, of course, but now available by Marwanid times in greater volume and variety.³⁷

And what all this commercial activity implies is building, and lots of it. From their new cities and their markets to their new estates and their irrigation works, the Marwanids were the great builders of the early Islamic period, and there is fortunately abundant record of this in Syria alone. For what Egypt is to Umayyad documents, Syria is to Umayyad monuments. The

35 The letter (slightly amended here) is edited and translated in Petra M. Sijpesteijn, 'Travel and trade on the river', in P. Sijpesteijn and L. Sundelin (eds.), *Papyrology and the history of early Islamic Egypt* (Leiden, 2004), esp. pp. 135–6.

36 On the broader phenomenon of large estates and agricultural expansion, see Banaji, *Agrarian change*; and Morony, 'Economic boundaries?', pp. 168–70. On continuities in elite incomes from land from Umayyad to 'Abbasid times, see Hugh Kennedy, 'Elite incomes in the early Islamic state', in John Haldon and L. I. Conrad (eds.), *The Byzantine and early Islamic Near East*, vol. VI: *Elites old and new in the Byzantine and early Islamic Near East* (Princeton, 2004).

37 On commercialised agriculture and specialisation of certain industries, see Morony, 'Economic boundaries?', pp. 172–8 and the introductions to two volumes edited by him: *Production and the exploitation of resources*, *The Formation of the Classical Islamic World* 11 (Princeton and Aldershot, 2002) and *Manufacturing and labour* (Aldershot, 2003); Rebecca M. Foote, 'Commerce, industrial expansion, and orthogonal planning: Mutually compatible terms in settlements of Bilad al Sham during the Umayyad period', *Mediterranean Archaeology*, 13 (2000). On the Fayyumī letter, see note 35.

most famous of these are the ‘desert castles’, which is rather a misnomer since many of these structures are neither castles nor located in the desert. The Arabic term for them *qusur* is a vague one that denotes form more than anything else,³⁸ but is suitably flexible to describe the many uses to which these buildings were put, as hunting lodges, defensive strongholds, urban cores, spas, palaces and, especially for present purposes, country estates: these are sites of the farmer’s life as much as they are of *la dolce vita*.³⁹ The diversity of the *qusur* is readily apparent even to the untrained eye, ranging as they do from the massive structure(s) at the complex known as Qaṣr al Ḥayr al Sharqī in the Syrian desert to the many others that, by comparison, seem like mere hovels, as at Khan al Zabīb, near Qatrania in Jordan.

But for all the diversity of form and function, the location of the Umayyad *qusur* in the economic trends discussed above cannot be denied.⁴⁰ Surely at Qaṣr al Ḥayr al Sharqī we are looking at the sort of thing that the historians mean when they refer to ‘the growth of large estates’. Here, in a cultivable seam in the desert midway between Palmyra and the Euphrates, two fine stone chateaux and other outbuildings (including an olive press) were built in 727 in the reign of Hisham, surrounded by a village of mud brick dwellings, as well as a circuitous enclosure wall that marked off an immense area of cultivated land served by dams, canals and cisterns. Other humbler brick *qusur* were later added to the ensemble. Many similar arrangements can be found throughout Syria, as at al Bakhra’, where al Walīd II was assassinated in 744, and where the surrounding village extends for some 40 hectares (at least).⁴¹

38 Lawrence I. Conrad, ‘The *qusur* of medieval Islam: Some implications for the social history of the Near East’, *al-Abḥāth*, 29 (1981).

39 And possibly the traveller’s life, too: see G. R. D. King, ‘The distribution of sites and routes in the Jordanian and Syrian deserts in the early Islamic period’, *Proceedings of the Seminar for Arabian Studies*, 17 (1987), which posits a connection between the *qusur* (at least some of them) and the Umayyad road network.

40 The literature on the *qusur* is dauntingly large and diffuse. A definitive inventory and analysis of the dozens of structures that can claim to be Umayyad *qusur* has yet to be written. Older starting points include Jean Sauvaget, ‘Châteaux umayyades de Syrie: Contribution à l’étude de la colonisation arabe aux Ier et IIe siècles de l’Hégire’, *REI*, 35 (1967); and Fawwaz Tuqān, *al-Ḥa’ir: Baḥṭh fī al-qusur al-umawiyya fī al-badiya* (Amman, 1979). More recently, see Jere L. Bacharach, ‘Marwanid building activities: Speculations on patronage’, *Muqarnas*, 13 (1996) (not limited to the *qusur* alone); and the summary reports of Denis Genequand’s project ‘Implantations umayyades de Syrie et de Jordanie’, for the Schweizerische Liechtensteinische Stiftung für archäologische Forschungen im Ausland (SLSA) in the *SLSA Jahrsbericht 2001* (Zürich, 2001) and *SLSA Jahresbericht 2002* (Zürich, 2003).

41 Oleg Grabar, R. Holod, J. Knustad and W. Trousedale, *City in the desert: Qasr al Hayr East*, 2 vols. (Cambridge, MA, 1978). But cf. Denis Genequand, ‘Rapport préliminaire de la campagne de fouille 2002 à Qasr al Hayr al Sharqi (Syrie)’, in *SLSA Jahresbericht 2002*

But for all the attention that they lavished on cultivating the rural landscapes of their core lands, the Marwanids and their servants were really thinking in the end about their cities, where their surplus could be brought to market, and their income and rents spent.⁴² Here too the monuments can help us, revealing a vigorous commercial and industrial economy. This is evident in both Antique urban landscapes that were maintained or retooled and in *de novo* foundations. Examples of the former include Baysan in Palestine, where Hisham ordered the construction of a complex of some twenty shops and a notable covered walkway on the site of a ruined Byzantine basilica; or Palmyra (Tadmur), where an impressive new market, some 200 metres long and containing some fifty stalls, was inserted into the colonnade of the old Roman *decumanus*. Examples of the latter include 'Anjar in the Biqa' valley of Lebanon, probably built by al Walīd I's son, 'Abbas, to house his troops. It was built from scratch in the style of a Roman legionary camp, but is unambiguously Umayyad, with its palaces, mosque, Syrian style houses, baths and shops; or al Ramla, capital of the *jund* of Filastīn, built by the future caliph Sulayman, though its original plan is unknown. So identified with city building were the Marwanids that at Mosul the family cut new canals, developed the land and added some new buildings, but were nevertheless held by tradition to have founded the city itself.⁴³ When we add to these examples in the core areas the propensity of Marwanid governors in the provinces for agricultural development and urban expansion,⁴⁴ we can begin to appreciate that we are dealing with a society and an elite committed to urban living.

Whether there were enough people to keep the economy going is a debatable question. The demographic trends of the early Islamic period are really only the subject of clever guesswork. Conventional wisdom suggests that a recovery from the demographic downturn caused by the plagues, famines, deportations and wars of Late Antiquity was in the offing, but

(Zurich, 2003); Denis Ganequand, 'Rapport préliminaire de la campagne de fouille 2003 à Qasr al Hayr al Sharqi et al Bakhra' (Syrie)', in *SLSA Jahresbericht 2003* (Zurich, 2004).

42 On Marwanid urbanism in Syria, see Alastair Northedge, 'Archaeology and new urban settlement patterns in early Islamic Syria and Iraq', in G. R. D. King and A. Cameron (eds.), *The Byzantine and early Islamic Near East*, vol. II: *Land use and settlement patterns* (Princeton, 1994); Bacharach, 'Speculations'; and, esp. Foote, 'Commerce'.

43 Robinson, *Empire and elites*, pp. 86–9.

44 On settlement and development in the provinces, see Ira M. Lapidus, 'Arab settlement and economic development of Iraq and Iran in the age of the Umayyad and early Abbasid caliphs', in A. L. Udovitch (ed.), *The Islamic Middle East, 700–1900: Studies in economic and social history* (Princeton, 1981); Khalil 'Athamina, 'Arab settlement during the Umayyad caliphate', *JSAI*, 8 (1986).

would have to wait until after the Marwanids had left the scene.⁴⁵ Certainly, Marwanid investment in this labour intensive economy of farming, building, mining and so on created a demand for labour, either in the form of slaves or *corvée*, which may suggest that economy was outstripping demography. It also suggests a certain mobility, at least for labourers, such as the Ḥimṣīs sent by Hisham to build Qaṣr al Ḥayr al Sharqī, the Iraqi Christians and Copts enlisted to build ‘Anjar, or the Zutt peoples, captured in Sind and resettled on the Syrian coast in the reign of al Walīd I, presumably as labourers and not as sailors.

The mobility of certain populations (to which we should add the well travelled troops, scholars and administrators of the period), the integration of regional markets and merchant communities, and the administrative centralising of this period also led to a greater regional interdependence. But one should not exaggerate such a process. We are dealing principally with small scale local economies that were only beginning to connect to one another and to a broader world. Nevertheless, the increasingly integrated economies of the Marwanid caliphate would set the stage for the increasingly integrated Islamic civilisation of later periods. In sum, even if the economic history of the period is patchy and resistant to synthesis, the confluence of trends is clearly recognisable: urbanism and economic expansion were as much a part of the Marwanid programme as were monotheism, centralisation and empire.

Elite culture and the Marwanid transformation

As has already been noted, the Marwanid caliphs who ruled over this spreading and centralising empire were holders of imperial might – latter day avatars of Khusrau and Caesar – and also religious guidance – signposts and lodestars. But the caliphs were also sources of wealth and patronage. Their cash parched poets eulogised them in panegyric as storm clouds, rivers and falling rain. They were, in their munificence, elemental. The *ashraf* – the Arab elite who served the caliphs as commanders, soldiers and, increasingly, administrators – will have felt the same, even if they expressed it in less mellifluous terms. The entire system of Marwanid loyalty hinged upon patronage emanating from the caliph filtered through networks of patronage headed by the *ashraf* on down to their tribal constituents. The caliphs were always the head of this system, the fount of any benefits that might accrue to the populace. But on the

⁴⁵ Morony, ‘Economic boundaries?’, pp. 181–3. On Late Antique economic trends more generally, see chapter 1 in this volume.

basis of their wealth and noble ancestry the *ashraf*, the descendants of Islam's early conquest elite, could aspire too to be rivers to their people.

Nowhere can the aspirations of the Marwanid elites be better glimpsed than in the *quṣur* built by caliphs and *ashraf* throughout the caliphate. Some of these were quite humble, but others were clearly sites dedicated to elite distraction and self representation. A particularly well preserved case, Quṣayr 'Amra, can serve as a convenient example, though other equally lavish *quṣur*, such as those at Khirbat al Maḡjar near Jericho or Qaṣr al Ḥayr al Gharbī south west of Palmyra, would do as well. Located in the Jordanian steppe south east of 'Amman, Quṣayr 'Amra is perhaps to be attributed to al Walīd II. And, while the decoration of the structure can certainly tell us much about the ideals of caliphs, it is also revealing of the broader world of the *ashraf* who served them.⁴⁶ The site itself consists of a small hall attached to a bath house, with a nearby well and cistern. The ruins of other structures, including a mosque and a residence of some kind, are located in the vicinity. What the site lacks in external appeal, it makes up for in interior decoration.

In Quṣayr 'Amra's frescoes we see the cultural world of the Marwanid elite as its putative caliphal patron wanted it to be represented to his household, clients, allies and rivals. In an alcove directly opposite the entrance one confronts an image of a prince enthroned, in a style evocative of Late Antique representations of Adam. The rest of the hall is given over to images that call forth the pastimes of the men who frequented it: hunting scenes, musicians, workers, acrobats, dancers, scores of voluptuous women and, lest one get jaded, personifications of Philosophy, History and Poetry, identified by Greek inscriptions. Similar frescoes can be found in the adjoining bath house, where the *caldarium* is crowned by a zodiacal dome. Amidst the general riot, one is drawn to three panels in the western aisle, which may be taken to represent three concurrent scenes. In the centre, a nearly naked woman emerges Venus like from her bath while attendants (and a peeping Tom) look on. In the panel to the right, and thus outside the building in which the bathing woman is busied, acrobats perform in celebration. Finally, to the left, a dour delegation awaits entry: six kings humbled by the might of the caliph and the *ashraf*, identified in matching Greek and Arabic inscriptions: the Byzantine Caesar; the Visigoth Roderic; the Persian Khusrāu; the Abyssinian negus; and

⁴⁶ For a study of the messages conveyed by the decoration of Quṣayr 'Amra, to which most of the following discussion is indebted, see Garth Fowden, *Quṣayr 'Amra: Art and the Umayyad elite in Late Antique Syria* (Berkeley, 2004). On the elite cultural world associated with the *quṣur*, see also Robert Hillenbrand, 'La dolce vita in early Islamic Syria: The evidence of later Umayyad palaces', *Art History*, 5 (1982).

two unidentified monarchs, probably a Turkish or Khazar *khaqan* and an Indian *raja*. These are expressions of an elite that embraced the finer things of Antiquity, that valued manliness, genealogy, ostentatious display, power over nature and dominion over foes on every horizon. Such artistic expressions are not, as in the coins and monuments of ‘Abd al Malik, the loud clamourings of a newcomer to the dance of empire, but rather the subtler gestures of the heirs of conquerors, supremely confident of their place in history.

In this sense, Quṣayr ‘Amra is a testament to the blinkers worn by Syria’s elite. For by the time the workers who are depicted in its frescoes were mixing its mortar, the political horizons of the *ashraf*, like the conquest society that they created, had undergone a radical transformation.⁴⁷ The close knit conquest society of earlier days, in which a small tribal elite of Arab Muslims sequestered themselves in the *amṣar*, was now disintegrating. There were two principal mechanisms of this momentous social change. The first was conversion to Islam. What little we know about this process suggests that, other than simple opportunism, such conversion as happened at this early date occurred primarily by two means: conversion due to voluntary religious conviction; and conversion through enslavement, the result of being taken captive in war and brought into Muslim households. There slaves learned some Arabic, encountered and accepted Islam and, in the ideal, were freed, entering the ever growing (and, to the *ashraf*, ignoble) stratum of non Arab converts (*mawālī*). Muslims became more and more common, in every sense of the word.

The second mechanism was the professionalisation of the army. Under ‘Abd al Malik and his successors the role of imperial army now went to a loyal, professional body of troops from Syria and al Jazīra, who were sent to various hot spots when needed and to replenish garrisons on active frontiers.⁴⁸ This meant that the old tribal armies of the *amṣar* and the old style *ashraf* who led them were effectively demobilised, and many (though not all) of the once proud families of the conquests settled down and took to civilian pursuits such as trading, landownership and scholarship. Garrison towns became cities and soldiers became civilians. Having assimilated into this emergent civilian

47 On the Marwanid transformation and the development of factionalism, see Patricia Crone, *Slaves on horses: The evolution of the Islamic polity* (Cambridge, 1980); Patricia Crone, ‘Were the Qays and Yemen of the Umayyad period political parties?’, *Der Islam*, 71 (1994).

48 On the military reforms of ‘Abd al Malik, see Chase F. Robinson’s discussion in chapter 5 of this volume.

society, there was now little beside their genealogies that distinguished the *ashraf* from the *mawālī* so many of them had scorned.

None of these changes boded well for the Marwanids. Given that non Muslim subjects and non Arab Muslims carried the bulk of the tax burden of the caliphate, conversion theoretically meant a reduction in revenues, precisely in an era when building projects, urbanism and military expansion demanded more, not less, returns from the peasantry. Indeed, it is said that al Ḥajjaj, a man ever attentive to fiscal matters, was obliged to send back to their villages the peasant cultivators who if only for the tax break flocked to the towns clamouring for conversion to Islam. Such practices will only have angered the populace: the *mawālī* of course, but also a growing number who worried that their caliphs had become better at collecting taxes than at offering God's guidance. Among these concerned civilians were scholars, and it is surely no accident that it is, so far as one can tell, in these late Umayyad times that scholars with clear claims to religious authority emerge. Significantly, it was especially in Iraq, not metropolitan Syria, that such scholars began to delve into the lore of other monotheisms and start policing the perimeters of right guidance themselves, in *ḥadīth* and in theological disputation (*kalam*); it is also the time when the first chronicles – among them a *History of the caliphs* – were composed, a sign perhaps of contested caliphal legitimacy.⁴⁹

Meanwhile, in Syria, the caliphs, their kinsmen and the old Syrian *ashraf* dominated political affairs until just before the collapse of the dynasty, no doubt working out their alliances and shared political goals through meetings arranged at places just like Quṣayr 'Amra.⁵⁰ But outside the metropole, the old noble families of Sufyanid times, replaced by the Syro Jazīran imperial troops, were now merely the children of conquerors, not conquerors themselves. Those members of the old style *ashraf* who remained involved in the military did so primarily as local troops in garrisons on active frontiers such as Khurasan. As a result, the Syro Jazīran troops were bitterly resented by old Arab families and their *mawālī* in the provinces, who came to see them as an

49 For two examples from the world of Marwanid scholars, see Alfred Louis de Prémare, 'Wahb b. Munabbih, une figure singulière du premier islam', *Annales HSS*, (2005); and Gerhard Conrad, *Die Quḍāt Dimasq und der Madhab al Auza'i: Materialien zur syrischen Rechtsgeschichte* (Beirut, 1994). See also Christian Décobert, 'L'autorité religieuse aux premiers siècles de l'islam', *Archives de Sciences Sociales des Religions*, 125 (2004). On early history writing, see Fred M. Donner, *Narratives of Islamic origins: The beginnings of Islamic historical writing* (Princeton, 1998).

50 On the role of the *qasr* in Umayyad tribal politics, see the suggestive study by Heinz Gaube, 'Die syrischen Wüstenschlösser: Einige wirtschaftliche und politische Gesichtspunkte zu ihrer Entstehung', *Zeitschrift der Deutschen Palästina Vereins*, 95 (1979).

occupation force, and an insult to their honourable past service. It also meant that, for those few groups of *ashraf* who still held on to positions of power and privilege in the provinces, old style tribal politics had given way to the new style factional politics that had become endemic in the army, what the sources call tribal partisanship or *‘aṣabiyya*.

‘Aṣabiyya was the defining feature of political life in the provinces. In the course of governing a province, governors were inclined to rely upon their own kinsmen and allies for their sub governors or other positions. As a result, various groups – Syro-Jazīran troops, local Arabs, *mawālī* – competed for access to the power and patronage that a given governor might offer to his kinsmen in return for loyal service. Although it was usually the case for South Arabian tribes to line up with the Yaman faction and North Arabian tribes to align with Qays/Muḍar, this was not always the case, and it is not uncommon to find genealogically ‘southern’ tribesmen supporting Qays and ‘northerners’ supporting Yaman in their rivalries against one another and feuding over provincial appointments. For example, the revolt in 720 of the former governor of Khurasan, Yazīd ibn al Muhallab, was backed by Qaysīs and Yamanīs alike. But because the Muhallabids were of Azd/Yaman and his revolt was crushed by largely Qaysī troops under Maslama ibn ‘Abd al Malik, it became part of a Yamanī narrative of Umayyad oppression that they would later exploit. Indeed, as only one faction can be on top, such partisanship quickly became polarised and, as resentment at the Syro-Jazīran troops and the caliphs who sent them grew, factional complaints, especially by the out of favour, became increasingly shrill. In the end, as the musicians played on at Quṣayr ‘Amra, factional politics in the provinces would finally boil over into Syria and bring civil war with it.

Rebellion and the alternatives to Marwanid imperium

For the growing crowd who resented Umayyad rule, it helped that other groups – Kharijites and Shī‘a – had been organised against the dynasty since the battle of Ṣiffīn and remained steadfast in their opposition. However, since the second *fitna*, Kharijites and Shī‘a were in a tighter spot than they had ever been before. Under ‘Abd al Malik Kharijite rebellions had threatened Marwanid control over southern Iraq at a moment when the dust of the civil war had barely begun settling. However, the rebellions were soon subdued when ‘Abd al Malik stationed Syrian troops under al-Ḥajjaj in Iraq. With this new aggressive stance Kharijites were obliged to move further

afield, to Iran and, in particular, to Mosul and al Jazīra. This latter region was the scene of some Kharijite activity in the last decades of Marwanid rule, but even in these cases rebellion for the moment involved small numbers and little hope for success. When a son of the old Kharijite leader Shabīb ibn Yazīd rose in revolt, he could only raise a few score men for an unsuccessful raid on one of the governor's country estates. Only during the third *fitna* would Kharijism regain its power to contest the caliphate.⁵¹

Before the third *fitna*, Shī'ite movements faced the same situation, and the same odds. None of the Shī'ite revolts in southern Iraq in Marwanid times came close to the threat posed by al Mukhtar's rebellion during the second *fitna*. However, they did adopt some of its ideas, a testament to the popularity in the Iraqi *amṣar* of radical expressions of Shī'ism spiked with gnostic concepts, and these movements were duly dismissed by later observers as extremists (*ghulat*).⁵² And if the specific creeds of the *ghulat* are hard to piece together from the hostile and patchy sources that relate them, their gnostic flavour and focus on the Banu Hashim as imams are clear.⁵³ Thus, Bayan al Nahdī, who rebelled in Kufa and was executed some time in the 730s, is said to have claimed to have worked for Abu Hashim, the son of Muḥammad ibn al Ḥanafiyya, himself a son of 'Alī by a concubine, though he is also said to have claimed to be the emissary of Muḥammad al Baqir, from the Ḥusaynid branch of 'Alī's descendants. To these figures all manner of beliefs were attributed, including the doctrine of continuous prophecy, transmigration of souls, the divinity of 'Alī and his sons and the belief in a pair of Gods – an earthly and a heavenly one.⁵⁴

In comparison with the small scale political agitation of the *ghulat*, the revolt in 740 led by a grandson of al Ḥusayn, Zayd ibn 'Alī, seemed to hold

51 On Jazīran Kharijite activities after the second *fitna*, see Julius Wellhausen, *Die religiös politischen Oppositionsparteien im alten Islam* (Berlin, 1901), trans. R. C. Ostle as *The religious political factions in early Islam* (Amsterdam, 1975), pp. 79–80; Robinson, *Empire and elites*, pp. 125–6, 147–8.

52 On the term, see Wadād al Qaḍī, 'The development of the term *ghulat* in Muslim literature with special reference to the Kaysaniyya', in A. Dietrich (ed.), *Akten des VII. Kongresses für Arabistik und Islamwissenschaft* (Göttingen, 1976). On the gnostic influence see Patricia Crone, *God's rule: Government and Islam: Six centuries of medieval Islamic political thought* (New York, 2004), pp. 80–2.

53 Though, as Crone notes, the imams of the *ghulat* were not expected by their followers to be politicians: Crone, *God's rule*, pp. 82–4.

54 On these rebellions and other Umayyad *ghulat* movements, see M. G. S. Hodgson, 'Ghulat', *ELZ*, vol. II, pp. 1093–5; M. G. S. Hodgson, 'Bayan b. Sam'an al Tamīmī', *ELZ*, vol. I, pp. 1116–17; and the series of articles by William F. Tucker, 'Bayan ibn Sam'an and the Bayaniyya: Shī'ite extremists of Umayyad Iraq', *MW*, 65 (1975); 'Rebels and gnostics: al Muḡīra Ibn Sa'īd and the Muḡīriyya', *Arabica*, 22 (1975); 'Abu Maṣṣur al 'Ijlī and the Maṣṣuriyya: A study in medieval terrorism', *Der Islam*, 54 (1977).

more promise for those seeking an ‘Alid imam.⁵⁵ He is said to have called his followers in Kufa to ‘the Book of God and the *sunna* of His Prophet, holy war against the tyrants, defending the oppressed, giving pensions to those deprived of them, distributing plunder (*fay*)’ equitably amongst those entitled to it, restitution to those who have been wronged, recall of those detained on the frontiers, and help the household of the Prophet against those who oppose us and disregard our cause’, a fairly generic appeal to settle old Kufan grievances.⁵⁶ Syrian troops quashed Zayd’s revolt, and he was killed. His son Yahya survived, and fled to Khurasan, where he too was tracked down and killed. Given the ease with which the Marwanids suppressed their revolt, the cause of Zayd and his son posed no real danger, and it is the claims made later upon them for which they are remembered. Zayd was claimed as the founder of a small but flourishing Shī‘ite sect, the Zaydiyya. And some sources relate that Yahya – or rather, vengeance for his murder – moved into action one Shī‘ite partisan in Khurasan: Abu Muslim, chief missionary for the Hashimiyya, a Shī‘ite movement that would, very soon, topple the Marwanid house.

Fitna and dawla: the end of Syrian centrality

The maelstrom that toppled the Umayyad dynasty from power and replaced them with an ‘Abbasid dynasty, and ultimately ended Syria’s short lived role as the centre of empire, is best conceived of in three closely connected phases: the conflict that broke out over disputes about the succession of al Walid II; the *dawla* or revolution of the Hashimiyya movement, which joined the fray of the third *fitna* under its own candidate for imam; and the Maṣṣurid victory, by which, on the heels of a Hashimī victory, the ‘Abbasid notable Abu Ja‘far al Maṣṣur consolidated ‘Abbasid power, neutralised his rivals within the revolution and secured the succession to rule in his own line. It is the first two phases that principally concern us here.

The third fitna

Upon the succession of al Walid II (r. 743–4), the prognosis for Marwanid rule was not good. True, the territory controlled by the caliph was vastly larger than it had been at the death of ‘Abd al Malik. But all indications suggested

55 On this revolt, see al Ṭabarī, *Ta’rīkh*, series II, pp. 1676–8, 1698–1711; Aḥmad ibn Abī Ya‘qub al Ya‘qubī, *Ta’rīkh al Ya‘qubī*, ed. M. T. Houtsma, 2 vols. (Leiden, 1883), vol. II, pp. 391–2; Wellhausen, *Religio political factions*, pp. 161–4.

56 Al Ṭabarī, *Ta’rīkh*, series II, p. 1687.

that the caliphate had overreached itself, and that the ideals of Marwanid rule were unable to extend to its furthest borders. The fissures were everywhere: in the stark disconnect between provincial administrative practice and central administrative demands; in the exhaustion of the Syrian troops; and in the growth of tribal factionalism. To Kharijites, Shī'a and others who sought an imam who better represented their understanding of God's plan for the faithful, it was equally clear that Marwanid style Islam had reached its limits, too. Taxation, the military, factionalism and Islamic alternatives were all at work behind the overthrow of al Walīd II and, ultimately, of the Umayyad dynasty itself.

Al Walīd II's father, Yazīd II, had named Hisham as heir, but he had specified that al Walīd II was to succeed Hisham in turn. Hisham had tried to overturn this arrangement and keep the caliphate within the line of his own sons, but was unable to do so. It was little comfort to the sons of Hisham that when al Walīd finally did succeed, he showed little talent or love for his job. An accomplished poet, the sources also describe him as a bit of a *debauché* who liked to pass his time as he pleased, generally ignoring his duties amidst the *otium* of one of his *quṣur*.⁵⁷ Yet for all his alleged disdain for caliphal responsibilities, al Walīd seemed determined to remain in power, and he swiftly acted against any who opposed him. Some of the tribal notables who resented his succession he had killed. His main Marwanid rival, Sulayman ibn Hisham, he had beaten and imprisoned. And when he named his two minor sons as his heirs, and Hisham's beloved governor of Iraq and the east, the pro Yamanī Khalid al Qasrī, refused to recognise them, al Walīd handed Khalid over to his enemy and successor as governor, who had him tortured and killed. The rift between al Walīd II, on the one hand, and the Yamanī faction and the rest of the Marwanid house, on the other, was complete.

Al Walīd's cousin, the future Yazīd III, backed by disgruntled Umayyads such as Sulayman ibn Hisham and members of the infuriated Yamanī faction, led the charge against him. Most of Yazīd's Yamanī followers were seasoned veterans, many of them with connections to the deeply factionalised armies. Still others came from the villages surrounding Damascus, especially al Mizza, a town noted as a centre of Yamanī settlement and a hotbed of a heretical doctrine called Qadarism. As a result of this association, elements of Yazīd's

57 For a whimsical sampling, see Robert Hamilton, *Walid and his friends: An Umayyad tragedy*, Oxford Studies in Islamic Art 6 (Oxford, 1988). On al Walīd's literary shaping, see Steven Judd, 'Narratives and character development: al Ṭabarī and al Baladhurī on late Umayyad history', in Sebastian Guenther (ed.), *Ideas, images, and methods of portrayal: Insights into classical Arabic literature and Islam* (Leiden, 2005).

supporters are referred to as belonging to the Qadariyya or, less frequently, the Ghaylaniyya. While later sources use the term Qadarī to refer to Muslims who uphold human free will in contrast to the prevailing Muslim doctrine of predestination, it is not entirely clear what being a Qadarī meant in the middle of the eighth century. Free will does not necessarily breed rebels, and the political content of Yazīd's programme and the claims of his followers seem fairly limited (see below). As for the Ghaylaniyya, these were the disciples of the rebel Ghaylan al Dimashqī, a *mawla* and Marwanid bureaucrat who was executed by Hisham. Although little is known about his teachings, Ghaylan, too, is later named as a Qadarī. Whatever their exact political and theological claims, it was their military support and their loathing of al Walīd II that most mattered to Yazīd.⁵⁸ With the Yamaniyya behind him, Yazīd entered Damascus, neutralised any sources of resistance in the city, was proclaimed caliph in the Umayyad Mosque and received the oath of allegiance from the troops. He then sent a detachment of men to intercept al Walīd who had, in the meantime, relocated to the *qaṣr* of a loyal supporter of his at al Bakhra', not far from Palmyra. Al Walīd was apprehended and executed.

The resistance on the part of the old *ashraf* of Syria was immediate. Despite the fact that many of them hailed from genealogically Yamani tribes, they and their troops from the *ajnad* had every reason to fear for their future under a rebel caliph and the upstart Yamaniyya faction. In both Ḥimṣ and Filasṭīn, loyalist *ashraf* and local troops rebelled against Yazīd III in the name of the sons and heirs of al Walīd II, whom Yazīd III had thrown into prison. Yazīd, aided by Sulayman ibn Hisham, crushed the revolt in Filasṭīn (led by a son of the caliph Sulayman), and apprehended the leader of the Ḥimṣīs (a descendant of Mu'awiya). Further north, the grizzled general Marwan ibn Muḥammad (a grandson of Marwan I) had prepared to march from Armenia to support the cause of al Walīd II's heirs against the rebel Yazīd III, but the Yamani troops with him on the frontier deserted, and he was forced to interrupt his plans. He further mollified the troops by retaining some of their *ashraf* in power and paying their stipends.

With most of the immediate threats to his power neutralised, Yazīd could focus on his duties as caliph. His first duty, of course, was to his factional

58 On the events of this phase of the *fitna* and the reign of Yazīd III see al Ṭabarī, *Ta'rikh*, series II, pp. 1775–875, esp. pp. 1784–836; 1870–4; Josef van Ess, 'Les Qadarites et la Gailaniyya de Yazīd III', *SI*, 31 (1970); Crone, *Slaves on horses*, pp. 46–8; Paul M. Cobb, *White banners: Contention in 'Abbasid Syria*, 750–880 (Albany, 2001), pp. 71–5. On the later literary shaping of Ghaylan al Dimashqī, see Steven Judd, 'Ghaylan al Dimashqī: The isolation of a heretic in Islamic heresiography', *IJMES*, 31 (1999).

following and, sure enough, Yamanīs came to dominate provincial affairs under Yazīd III, notably in Iraq. But was Yazīd's revolt just a Yamanī coup? Certainly the references to the Qadariyya or Ghaylaniyya suggest some kind of ideological basis to his actions. But if a Qadarī programme was behind Yazīd's rebellion, it seems to have more to do with concerns about the imamate than with free will. In a speech he gave upon seizing power in 744,⁵⁹ Yazīd claimed to be rebelling in righteous anger in the name of God, His Book, and the *sunna* of His Prophet. The wicked al Walīd II had forfeited his rights through his tyrannical conduct, and by extinguishing 'the light of pious folk'. On a more practical level, Yazīd pledged that he would 'not place stone upon stone nor brick upon brick' or cut any canals, an evident gripe against the profligate building projects of the Marwanids. The rest of his speech addresses grievances common to much of the Umayyad period involving taxation, military service and justice. As it happens, Yazīd was unable to keep any of these promises, as he died after ruling only a few months.

The coup of Marwan II

Yazīd had named his brother Ibrahīm (r. c. September–November 744) to succeed him but, given the context, the people's allegiance to him wavered. As a result, he barely gets a notice in the sources.⁶⁰ As under Yazīd III, the troops of Ḥimṣ refused to recognise this new caliph at first, and Ibrahīm was beset with rivals almost from the moment he took power. Chief of these was his kinsman Marwan ibn Muḥammad, who now saw his moment to renew his plan to march on Damascus in the name of the two young heirs of al Walīd II, who were still locked away in prison. Marwan and his Qaysī troops were intercepted on their way to Damascus by a Yamanī army under Sulayman ibn Hisham. Marwan's battle-hardened frontier troops easily held the day, and Sulayman's forces were routed. Sulayman himself fled to Damascus and, it is said, arranged with a cabal of Yamanī leaders to murder al Walīd II's young heirs. Not long afterwards Marwan arrived in Damascus and received the oath of allegiance as caliph from the troops and *ashraf*, who were happy to be rid of a caliphal line associated with the odious Yazīd and his Yamaniyya. The reigning caliph, Ibrahīm ibn al Walīd, followed suit and joined Marwan's retinue.

59 Al Ṭabarī, *Ta'riḫh*, series II, pp. 1834–5; *Fragmenta historicorum arabicorum*, ed. M. J. de Goeje, 2 vols. (Leiden, 1869), vol. I, pp. 150–1; Khalīfa ibn Khayyāt, *al Ta'riḫh*, ed. Akram al 'Umarī, 2 vols. (Najaf, 1967), vol. II, pp. 382–3.

60 On Ibrahīm ibn al Walīd and the coup of Marwan, see al Ṭabarī, *Ta'riḫh*, series II, pp. 1876–9; *Fragmenta*, vol. I, pp. 154–6; Ibn Khayyāt, *Ta'riḫh*, vol. II, pp. 391–3.

As in Yazīd III's revolt, which resulted in the Yamaniyya faction acquiring a new position of authority, Marwan II (r. 744–50) owed his rise to power to the factional loyalties of the Qaysī troops of the frontier. Marwan was thus as obliged, as Yazīd had been, to reward his factional supporters. In some provinces Qaysīs did come to dominate positions of power. But in Syria itself the Qaysīs made only slight headway. This might have been enough to mollify the army and *ashraf* of Syria, had Marwan not made the decision to move, with the treasury, from Syria to Ḥarran in al-Jazīra. For Marwan this was a sensible move back to familiar territory long associated with his kinsmen and the homeland of his Qaysī supporters. But for other Umayyads and the *ashraf* and armies of Syria it was a further sign of their growing irrelevance in the new political landscape. The result was predictable, and the *ashraf* and the Syrian *ajnad* (most of them Yamanīs) revolted in concert against this new caliph. Marwan thus spent much of 745 pacifying Syria, subduing revolts in Filasṭīn, Tiberias, Ḥims, Palmyra, and even Damascus. Syria's old guard rallied behind Sulayman ibn Hisham, who had recently been pardoned by Marwan for his association with the regime of Yazīd III. Together with two other sons of Hisham, Sulayman received the allegiance of a host of Yamanī troops, and attempted to seize cities throughout Syria. In the end Marwan was just able to counter the uprising of the sons of Hisham, razing the walls of the cities that had dared to revolt; but Sulayman managed to escape and flee to Iraq.

At this point the Syrian troops garrisoned in Iraq were divided between Yamanīs loyal to Yazīd III and his governor (a son of the caliph 'Umar II) and Qaysīs loyal to Marwan and his governor. This situation should have made Marwan's subjugation of the province an easy one, but it was complicated by a Kharijite uprising among the Rabī'a tribes, traditional rivals of Qays despite their 'northern' origins. They were led by Shaybanīs of northern Mesopotamia under al-Ḍaḥḥak ibn Qays.⁶¹ But this was a Kharijite uprising quite unlike the recent raids by small bands of Shaybanī bandits. Al-Ḍaḥḥak's men (and women, who joined them in battle) numbered in the thousands, were well paid and included seasoned veterans of the frontier. Al-Ḍaḥḥak marched into Iraq and overwhelmed the Syrian troops. The Qaysīs fled but the Yamanīs, under their noble governor, submitted to the Kharijites, recognising al-Ḍaḥḥak as their caliph with authority in Iraq, western Persia and Mosul. It was a unique sight, even for a civil war: 'A Qurayshite of the ruling family now prayed behind a Kharijite of Bakr ibn Wa'il!' as Wellhausen

61 On this revolt, see al-Ṭabarī, *Ta'rikh*, series II, pp. 1897–916, 1938–49; Wellhausen, *Religio political factions*, pp. 80–2. Robinson, *Empire and elites*, pp. 110–13, 125–6.

exclaimed, echoing the amazement of a contemporary poet at how badly fragmented Islam's ruling dynasty had become.⁶² At Mosul, the mendicant Umayyad Sulayman ibn Hisham also joined al Ḍaḥḥak's cause. Marwan first sent his son 'Abd Allah to pen in al Ḍaḥḥak in al Jazīra, but the caliph was soon obliged to join the fray himself, and he ultimately triumphed, killing al Ḍaḥḥak and scattering his forces. By 746 the remnants had crossed over the Tigris, and were forced to flee into the mountains to the east. Iraq submitted to Marwan's authority.

Perhaps inspired by these events, Kharijites in the Hijaz seized control of Mecca and Medina.⁶³ This group recognised as caliph a Kharijite judge in the Hadramawt who took the sobriquet 'the Seeker of Justice' (*ṭalib al ḥaqq*), but were led locally by a Baṣran troublemaker named Abu Ḥamza ibn 'Awf. With a small group of followers, Abu Ḥamza took over Mecca during the pilgrimage, railed against the iniquities of the Marwanids – Marwan II in particular – and convinced the city's governor to flee. A lieutenant then took charge of Medina. Without delay Marwan sent an army under a trusted commander to take charge of the situation in Arabia. Abu Ḥamza's forces were overcome, and Medina and Mecca were secured. The army then proceeded into Yemen, where they captured the Kharijite leader, sending his head back to Marwan.

With Egypt only recently subjugated and the Maghrib still reeling from the effects of the Berber revolt, Iran and the east next drew Marwan's attentions. The focus of opposition here was the Shī'ite rebel 'Abd Allah ibn Mu'awiya, a descendant of 'Alī's brother Ja'far.⁶⁴ In 744, after the death of Yazīd III, he had rebelled in Kufa against the governor and his garrison, but was forced to flee to western Iran. He was joined by Zaydī Shī'a, a disgruntled *mawālī*, even the remnants of the Kharijite followers of al Ḍaḥḥak ibn Qays (among them the Umayyad Sulayman ibn Hisham), who had fled Marwan II's armies into Ibn Mu'awiya's domains. His following even included a few members of the 'Abbasid family, a notable lineage of the Banu Hashim who were only now beginning to manifest their opposition to generations of Umayyad rule. At its height the dominion of Ibn Mu'awiya included most of south western Iran, but it was short lived. In 746 7 the bulk of his forces were on the run and

62 Wellhausen, *Arab kingdom*, p. 390.

63 On this revolt, see al Ṭabarī, *Ta'rikh*, series II, pp. 1942–3, 1981–3, 2005–15; Wellhausen, *Religio political factions*, pp. 85–8; C. Pellat, 'al Mukhtar ibn 'Awf al Azdī', *El2*, vol. VII, p. 524.

64 On the revolt of 'Abd Allah ibn Mu'awiya, see al Ṭabarī, *Ta'rikh*, series II, pp. 1879–88; Wellhausen, *Religio political factions*, pp. 164–5; William Tucker, 'Abd Allah b. Mu'awiya and the Janāḥiyya: Rebels and ideologues of the late Umayyad period', *SI*, 51 (1980).

defeated by Marwan's troops near Marw. The rebel Umayyad Sulayman ibn Hisham managed to escape with a few men to Sind, the very margins of the Islamic world, where death caught up with him. Ibn Mu'awiya himself escaped and fled into Khurasan, where Abu Muslim, the leader of another Shī'ite revolt, had him captured and executed as a rival.

Hashimiyya and 'Abbasids

It is traditional at this point in medieval and modern narratives of the fall of the Umayyads to pick up our story in Khurasan, whence Abu Muslim's Shī'ite movement, called the Hashimiyya, exploded, defeating Marwan and his badly overstretched armies, overturning the Umayyad dynasty and replacing it, after some sleight of hand, with a line of caliphs from the 'Abbasid family. It is this sequence of events that modern historians usually call 'the 'Abbasid revolution'. But there are good reasons for questioning the precise role of the 'Abbasids in all this – and, furthermore, just how revolutionary it all was.⁶⁵

We may consider first whether the revolution was really 'Abbasid. Given that the movement began with a clandestine phase (called the *da'wa*), puzzling out what really happened before the public uprising (called the *dawla*) of the Hashimiyya is a fraught pursuit. A few points can be taken as relatively certain, however.⁶⁶ The Hashimiyya movement, as its name suggests, was a Shī'ite opposition group originating in Kufa whose members believed that the leadership of the Muslim community should be drawn solely from the Banu Hashim, the Prophet's clan, which they also called variously the *ahl al bayt* (People of the Household) or simply the *al Muḥammad* (the Family of Muḥammad). The goals of the Hashimiyya thus automatically excluded an imam/caliph drawn from the broader pool of Quraysh such as the earliest caliphs, Abu Bakr and 'Umar. More to the point, it considered the current line of Umayyad caliphs a terrible deviation, an iniquitous dynasty that should

65 There is a large and diverse body of scholarship devoted to the 'Abbasid revolution. For a convenient summary discussion, see R. Stephen Humphreys, *Islamic history: A framework for inquiry*, rev. edn (Princeton, 1991), pp. 104–27, with the addition of Saleh Said Agha, *The revolution which toppled the Umayyads: Neither Arab nor 'Abbasid* (Leiden, 2003).

66 On the *da'wa*, see Moshe Sharon, *Black banners from the east* (Jerusalem, 1983); Moshe Sharon, *Revolt: The social and military aspects of the 'Abbasid revolution* (Jerusalem, 1990); Hugh Kennedy, *The early Abbasid caliphate: A political history* (London, 1981); Tilman Nagel, *Untersuchungen zur Entstehung des abbasidischen Kalifates* (Bonn, 1972); Patricia Crone, 'On the meaning of the 'Abbasid call to al Riḍa', in C. E. Bosworth *et al.* (eds.), *The Islamic world from classical to modern times: Essays in honor of Bernard Lewis* (Princeton, 1989), pp. 95–111; and most recently, Agha, *Revolution*.

never have come to rule. For the Hashimiyya, restoring the imamate to the family of the Prophet was a clear solution to the error of Marwanid rule.

The Hashimiyya thus revolted to vindicate the claims of a clan, not an individual. They referred to their future unspecified leader as *al riḍa min al Muḥammad* ('the one selected from the family of Muḥammad'), which suggests that, like so many rebel movements before them, they considered selection by *shura* (electoral council) to be the mechanism that would determine their imams. As the pool was limited to the Banu Hashim, the new imams could be either 'Abbasid or 'Alid. During the clandestine phase of the revolution, and even afterwards, many may well have assumed this really meant an 'Alid imamate, but others seem to have supported the claims of the 'Abbasid Ibrahīm ibn Muḥammad (dutifully called Ibrahīm al Imam in the sources) as being the most worthy of the Banu Hashim.

Strictly speaking, this is not how the 'Abbasids themselves came to remember their role in the *da'wa*.⁶⁷ In the 'Abbasid version of these events it is the Imam Ibrahīm's father, Muḥammad ibn 'Alī, who was the first 'Abbasid to become involved in the Hashimiyya. And he was no mere disgruntled notable, but rather the chosen heir of Abu Hashim, the son of the 'Alid imam Muḥammad ibn al Ḥanafīyya (this last is the same 'Alid to whom al Mukhtar had tied his fortunes back in the second *fitna*). From the 'Abbasid family *qaṣr* at Ḥumayma in southern Transjordan, Muḥammad ibn 'Alī directed the growing network of propagandists who spread his claims in Kufa and elsewhere, above all Khurasan. When he died in 743, his son Imam Ibrahīm took over as head of the movement, and it was he who, in response to demands from the Khurasanīs, appointed a mysterious *mawla* of his, Abu Muslim, as chief propagandist there. As it happens, Marwan II seems to have caught on to what the 'Abbasids were up to, and he had Ibrahīm dragged in chains from Ḥumayma and thrown into prison in Ḥarran, where, in 749, he died. By then the revolution was in full swing, and claims about old caliphs took a back seat to struggles with current ones.

The 'Abbasid story of their origins thus posits an early connection with the *da'wa* of the Hashimiyya and irrefutable Shī'ite credentials through the 'testament' of Abu Hashim. And if it provides as many problems for us as it did solutions for 'Abbasids worried about legitimacy, it is nevertheless the official version of events and worthy of note in that respect. But an unproblematic

67 I base my paraphrase of the 'official version' here on the anonymous *Akhbar al dawla al 'Abbasiyya wa fīhi akhbar al 'Abbas wa wuldihi*, ed. 'Abd al 'Azīz al Durī and A. J. al Muṭṭalibī (Beirut, 1971), on which see Elton Daniel, 'The anonymous history of the Abbasid family and its place in Islamic historiography', *IJMES*, 14 (1982), pp. 419–34.

direct line between the ‘Abbasid caliphs and Muḥammad ibn al-Ḥanafīyya certainly sounds more like post revolutionary wishful thinking than a straight forward guide to what transpired in the last days of the Marwanids. Unfortunately, the evidence does not offer us much with which to construct an alternative. For both historiographical and political reasons ‘the relationship between the ‘Abbasids and the revolution customarily named after them is nothing if not problematic’.⁶⁸

Although Kufan in origin, the Hashimiyya found its most ardent supporters in Khurasan. It was an ideal place to start a revolution.⁶⁹ While Marwan II was stamping out the fires of rebellion in Egypt, Arabia, Syria and Iraq, Khurasan was governed almost autonomously by Naṣr ibn Sayyar, Hisham’s octogenarian governor, who had steadfastly refused all attempts to replace him. Naṣr faced two principal local challenges. On one hand, there was the civilian population, comprising both non Arabs and Arabs, who had created an ‘archipelago’ of settlement in the towns and villages of the province.⁷⁰ In the aftermath of the early waves of conquest the traditional barriers between Arab settlers and Iranian *mawālī* were breaking down and, as both sides intermarried and commingled, their interests began to converge. One of these interests was taxation. For decades the Arab settlers had complained that local non Muslim elites in charge of tax collection were favouring their fellow natives and co religionists, which meant that Muslims paid more than their share of the taxes. Naṣr attempted to resolve these issues by making some significant tax reforms, but these seem to have arrived too late to quell all opposition to him.

On the other hand, there was the army, based most prominently in Marw. As in other provinces, the army was divided by factional disputes between Yaman and Qays. Naṣr here also tried to resolve differences, but to no avail. A dispute over pay led one Yamanī commander to revolt and gather his kinsmen and factional followers in opposition to Naṣr, whom he was able to oust from Marw. Naṣr’s appeals to Marwan II for help went unanswered but, gathering Qaysī supporters from other settlements, he camped before Marw in the summer of 747. It was at this juncture that, in the nearby village of Sikadanj, the Hashimiyya under Abu Muslim proclaimed a new turn of fortune’s favour

68 Crone, ‘al-Riḍa’, p. 103, which also treats the political reasons. The evidence for historiographical re-shaping is discussed in Jacob Lassner, *Islamic revolution and historical memory: Abbasid apologetics and the art of historical writing* (New Haven, 1986).

69 On the public manifestation of the revolution, Wellhausen, *Arab kingdom*, is fundamental. See also Shaban, *‘Abbasid revolution*; Sharon, *Revolt*.


70 The allusion is to Agha, *Revolution*, pp. 185–6.

(*dawla*) to replace the loathsome Umayyads, and prayers were said on behalf of Imam Ibrāhīm. By adopting such techniques as using black banners as their insignia, and later giving their caliphs apocalyptic sounding epithets, the Hashimiyya tapped into a strain of apocalyptic expectation that had never really died down among Muslims or, for that matter, non Muslims in the region.⁷¹ Naṣr briefly came to terms with the Yamanī opposition, and was able to retake Marw, but Abu Muslim was too deft an intriguer for Naṣr and, in early 748, with overwhelming Yamanī and even Qaysī support, he and his Hashimī followers, Arabs and *mawālī*, took the city. Naṣr once again took flight.

Abu Muslim's commander in chief in Khurasan was a Yamanī soldier named Qaḥṭaba ibn Shabīb. It was Qaḥṭaba who pursued Naṣr and his men westward across Iran, dislodging him from Nishapur and Qumis, and penning him in at Hamadhan, where Naṣr finally fell. Iraq was in reach. Qaḥṭaba made for Kufa, but was forced to contend with the Umayyad garrison at Wasīṭ, where he himself fell in August 749. His son al Ḥasan now took command and proceeded to Kufa, which was already in the midst of a Yamanī led pro-ʿAbbasid revolt, perhaps by prior arrangement. It was in this period, the early autumn of 749, that several members of the ʿAbbasid family made their way to Kufa. Among them was the man whom, it is said, Imam Ibrāhīm named as his successor: his brother Abu al ʿAbbas. Although some members of the Hashimiyya were reluctant to accept these claims, when Abu al ʿAbbas was proclaimed caliph on 28 November 749 in the main mosque of Kufa his opponents in the movement could do little but acquiesce, and thereby transformed the Hashimī revolution into an ʿAbbasid *coup d'état*.

Acquiescence was not an option for Marwan II, however. In al Jazīra he was convinced to take to the field against a Khurasanī army that had been sent to take Mosul, under the command of Abu al ʿAbbas's uncle, ʿAbd Allah ibn ʿAlī. Marwan's exhausted force of Syro Jazīran troops had little hope against the Khurasanī army under ʿAbd Allah ibn ʿAlī and, in January 750, on the banks of a flooded tributary of the Tigris called the Greater Zab, the last Umayyad caliph's army was broken, and Marwan fled. He fled first into Syria, where, after years of revolt, nearly every city closed what was left of their ruined gates to him. Passing through Palestine, he reached Egypt where, in August 750, ʿAbbasid troops caught up with him at Buṣīr, where he had taken refuge in a

71 ʿAbd al ʿAzīz al Durī, 'al Fikra al mahdiyya bayna al da'wa al 'abbasiyya wa al 'asr al 'abbasi al awwal', in W. al Qaḍī (ed.), *Studia arabica et islamica: Festschrift for Ihsan ʿAbbas* (Beirut, 1981); H. Suermann, 'Notes concernant l'apocalypse copte de Daniel et la chute des Omayyades', *Parole de l'Orient*, 11 (1983).



5. The Shi'ite imams.

After Ira M. Lapidus, *A history of Islamic societies*, 2nd edn, 2002, pp. 96f., fig. 4. Copyright Cambridge University Press, reproduced with permission.

church.⁷² Although Marwan's men reportedly outnumbered his pursuers, in a short skirmish under cover of night, the Khurasanīs prevailed. At first unrecognised in the midst of the mêlée, Marwan, a soldier to the end, was killed fighting alongside his men. Back in Syria, city after city surrendered almost without incident to 'Abd Allāh ibn 'Alī and his Khurasanī troops. At Damascus, where Mu'awiya had built his green domed palace and al Walīd I his sublime mosque, Yamanī townsmen enthusiastically opened the gates to an 'Abbasid general bearing black banners from the east.

72 On the contested location of Buṣīr, see G. Wiet, 'Buṣīr', *El2*, vol. I, p. 1343.

Conclusion: 750 and all that

If the 'Abbasids played a minor part in the planning and execution of the Hashimiyya's activities and only later claimed a central, starring role, then the 'Abbasid revolution can only be said to be 'Abbasid in hindsight. But was it really a revolution? Even if the passing of authority from one branch of Qurashī caliphs to another hardly seems revolutionary, the question is about more than semantics. In considering the 'Abbasid dynasty's role in the passing of Syria's moment as the heart of empire we would do well to recall that the 'Abbasid revolution was, after all, merely the final fillip to an Umayyad civil war rooted in Syria, and to remember that, from a Syrian point of view, the battle for the caliphate was far from over even in 750.

Abu al 'Abbas (r. 749–54) staked his claim to be caliph with the suitably apocalyptic tinged title *al Saffaḥ* ('the blood letter'), thanks to his role (rather exaggerated in the sources) in the massacre and collective desanguination of the Umayyad family. Yet even under a caliph whose name was so literally made in Umayyad misfortune, Syrians had varied options.⁷³ Many members of the Marwanid army, of course, simply surrendered, hoping for a continued future under the 'Abbasids. Others, however, were more pessimistic about their future under the new regime, and so continued to fight so long as there were suitable Umayyad claimants with good odds. Umayyad kinsmen with factional followings continued to fight throughout the reign of *al Saffaḥ*, proof that the question of 'Abbasid sovereignty was still an open one. In Palestine, Damascus, Ḥims, Qinnasrīn, Aleppo and on the Syrian frontier, garrisons fought behind members of the Umayyad family (Sufyanid and Marwanid) to stake their claims. In the end all of them were subdued by Khurasanī armies.

That Syria could not yet be written off as a centre of power was amply demonstrated early in the reign of *al Saffaḥ*'s successor, his brother Abu Ja'far al Maṣṣur (r. 754–75). Al Maṣṣur's succession was disputed by his powerful uncle 'Abd Allah ibn 'Alī, who was *al Saffaḥ*'s governor of Syria, and who claimed he had been named to succeed *al Saffaḥ* in return for his duties in overthrowing Marwan II. To back up his claim he convinced prominent commanders of the Syro-Jazīran army to join with his Khurasanī troops

⁷³ On the reactions of Syrians and surviving Umayyads to the coming of the 'Abbasids and their diverse fates thereafter, see Cobb, *White banners*.

(i.e. the very men responsible for their downfall) and march with him to confront his upstart nephew in Iraq. In the end, thanks to dissension within his ranks, ‘Abd Allah was defeated and al Manṣur was secure as caliph. The Syrians involved in the action sent a delegation to the new caliph, who pardoned them. From al Manṣur’s time onward the Syro Jazīran troops were assured a continued role in the new ‘Abbasid empire, but it would be an increasingly limited one. Outside Spain (where a grandson of Hisham managed to flee and set up his own caliphate) the descendants of the Umayyad dynasts who survived the unpleasantness of 750 settled in as courtiers and comfortable, if not privileged, members of ‘Abbasid society.⁷⁴

From the early eighth century and, arguably, even before, the region of Syria and its populace broke from its prevailing historical role as a province of empire and became instead the heartland of a burgeoning Umayyad caliphate, making manifest what had been only a potential future created by the reforms of ‘Abd al Malik. Syria’s rise to prominence was made possible principally for one reason: it was Syria’s tribal armies that manned the machinery of Marwanid imperium. As a result, Syria became a clearing house for commerce and tribute from France to Farghana and, as such, Syria suited the ruling dynasty. As much as Umayyad elites lived and served throughout the caliphate, only Syria offered the dynasty room for its penchant for settlement, frontier warfare, urban consumption and the pastimes of the steppe. But it was the Syrians, not the Umayyads, who elevated the region. For, as we have seen, Syria’s peculiar imperial moment ended not when Marwan II was cut down in 750, but only when al Manṣur, who would root his empire in Baghdad, accorded the Syrians an honourable but circumscribed place in the new regime. In so doing, he ensured that when the Syrians revolted it would be not to overturn the ‘Abbasid state, but to grumble over better treatment within it, and that when surviving Umayyads revolted in Syria they did so not as caliphal rivals, but as bandits, messiahs and madmen.

The revolutionary deed of the ‘Abbasids in these events was therefore not so much in replacing the Umayyads, for there is little in ‘Abbasid statecraft that is not recognisably Marwanid in precedent, but in providing answers to some of the problems that the Marwanid experiment posed and by meeting the needs of a growing populace that was increasingly Muslim and increasingly non Arab. The Umayyads never stopped depicting themselves as God’s

⁷⁴ Specific cases of Umayyad elites in ‘Abbasid times have been studied in Amikam Elad, ‘Aspects of the transition from the Umayyad to the ‘Abbasid caliphate’, *JSAI*, 19 (1995). On the second Umayyad caliphate of Spain, see chapter 14.

caliphs and as figures of immense Islamic sacrality.⁷⁵ But they could never avoid the fact that they were Islamic rulers who came to power when being Muslim was almost identical with being Arab, and they simply could not – or would not – provide legitimacy to the newfangled political unity required in the 740s. With its origins as an Arab kingdom in a practical sense, the Umayyad state fell short of a caliphate in a symbolic sense. It was symbolism of what was viewed as Islamic rule as opposed to Arab rule that the ‘Abbasids, as members of the sacred lineage of the Prophet, backed by their devoted Khurasani troops and ‘Sons of the Revolution’, could provide, and it is this that stands as their earliest and most durable achievement.

⁷⁵ Wadad al Qaḍī, ‘The religious foundation of late Umayyad ideology and practice’, in *Saber religioso y poder político en el Islam: Actas del simposio internacional (Granada, 15-18 octubre 1991)* (Madrid, 1994).

The empire in Iraq, 763–861


TAYEB EL-HIBRI

The consolidation of power

Although the Umayyad dynasty fell rapidly in the face of the Hashimite Khurasanī revolution in 132/750, the ‘Abbasid dynasty’s hold on power took until 145/762 to become firmly established. The second ‘Abbasid caliph, Abu Ja‘far al Manṣur (r. 136–58/754–75), rightly recognised by historians as the real founder of the ‘Abbasid state, was well aware, immediately after his accession to power, that he had to subdue a range of the revolution’s heroes if the caliphate was to remain in his family line. His first political move in 754 was to force the allegiance of his uncle, ‘Abd Allah ibn ‘Alī, thereby redefining the hierarchy within the ‘Abbasid house. This step was quickly followed by the overthrow of Abu Muslim al Khurasanī. In spite of his outward loyalty to the Hashimite family, Abu Muslim commanded popular support in Khurasan as an Iranian political leader, and to some he resembled a messianic figure. The latter aspect became apparent only after his downfall, when a series of rural rebellions, collectively known as the ‘Abu Muslimiyya’ revolts, sprang up in Khurasan, challenging ‘Abbasid rule. Although these heterodox (*ghulat*) rebels did not seriously threaten the ‘Abbasid state, they did point to both the lingering hope for an Iranian revival and a syncretistic belief in continuous prophecy, which at that juncture included such beliefs as Abu Muslim’s occultation, reincarnation and future return.¹

By far the greatest potential threat that al Manṣur expected, however, came from the ‘Alid branch of the Hashimite family, which had the closest kin ties to the Prophet, and was thus viewed by Hashimite sympathisers as the most legitimate inheritor of the caliphate. The ‘Abbasids had long sensed the prestige of the ‘Alid imams, and contented themselves during the propaganda

¹ E. Daniel, *The political and social history of Khurasan under Abbasid rule, 747–820* (Minneapolis and Chicago, 1979), pp. 125–47.



6. The 'Abbasids.

After Ira M. Lapidus, *A history of Islamic societies*, 2nd edn, 2002, p. 55, fig. 3. Copyright Cambridge University Press, reproduced with permission.

phase of the revolution with generalising the aim of the anti Umayyad opposition for a Hashimite leader rather than specifying a candidate branch for the caliphate (whether 'Abbasid or 'Alid). The name of the 'Hashimiyya' movement reflected this by pointing to the wider Banu Hashim clan, thereby

allowing the ‘Abbasids to share with the ‘Alids the image of religious mystique and pretension to esoteric religious knowledge. Meanwhile, the leadership objective of the revolution was also kept general in the slogan that called for eventual rule by ‘the one agreed upon or satisfactory from the family of Muḥammad’ (*al riḍa min al Muḥammad*).²

The main ‘Alid challenger to al Manṣur was Muḥammad al Nafs al Zakiyya, an illustrious scion to the Ḥasanid branch of the ‘Alid family, who was born the year the *da‘wa* began and was surrounded with a measure of reverence in the wider clan, such that some reports assert that he was given a *bay‘a* in Medina by the leading Hashimites during the early phase of the *da‘wa*. Whatever the truth behind his claims, Muḥammad al Nafs al Zakiyya seems to have garnered enough support to declare his rebellion in 145/762 not only in Medina, but also in Baṣra, where an uprising was led by his brother Ibrāhīm ibn ‘Abd Allāh, and was to find support in traditional religious circles that included the renowned scholars Malik ibn Anas and Abu Ḥanīfa as sympathisers. An exchange of letters between caliph and pretender before the outbreak of conflict may have been significantly embellished in the chronicle of al Ṭabarī, but it sufficiently summarises the crux of the competing arguments between the two Hashimite branches. Muḥammad al Nafs al Zakiyya stressed the primacy of his direct descent from Faṭīma, the Prophet’s daughter, while al Manṣur pointed to pre Islamic patriarchal tradition that stressed the priority of the uncle – in this case al ‘Abbas – inheriting from a man who left no male offspring. The ‘Alid rebel also stressed that his campaign was a return to the simple society and government of early Islam, in contrast to the imperialistic – even heretical – pretensions of the new caliph.

While the ‘Alids were in full command of the rhetoric of opposition and sentimental memory, the ‘Abbasids ultimately controlled the battlefield and strategic policies. In spite of its important religious symbolism, Medina was a non strategic centre for rebellion, a fact that quickly became evident when al Manṣur disrupted the grain supplies from Egypt on which the Ḥijaz depended. The second rebellion in Baṣra, led by Ibrāhīm ibn ‘Abd Allāh, met with greater success, but even there the ‘Alids stood no chance against al Manṣur’s ability to muster troops from Khurasan. Matters were further complicated for the ‘Alids by division within their family, reflected by the lack of support from

2 P. Crone, ‘On the meaning of the ‘Abbasid call to al Riḍa’, in C. E. Bosworth *et al.* (eds.), *The classical and medieval Islamic world: Essays in honor of Bernard Lewis* (Princeton, 1990), pp. 98–9.

Ja'far al Ṣādiq and much of the Ḥusaynid branch of the 'Alids for what was largely viewed as the Ḥasanid rebellion of Muḥammad al Nafs al Zakiyya.

Although the rebellion did not last long, it did signal the beginning of a new phase of rivalry between the 'Alid imams and the 'Abbasids, which would erupt intermittently over the next century, even while the caliphs tried to bring it under control through a mix of coaxing and coercive policies. The 'Alid revolt of 145/762 did also have the important effect of influencing some changes in religious attitudes and policies. Sunnī religious scholars, for example, who had previously supported al Nafs al Zakiyya's political bid, thereafter renounced millennial activism altogether in favour of political quietism, and began distancing themselves from the 'Alid cause as a sectarian Shi'ite movement. Also at around the same time, the 'Abbasid caliphs, probably reacting to the resonance of the 'Alid claim for the imamate, began cultivating their own rival conception of an 'Abbasid imamate, which centred on the caliphs and had its own claims for ideas of *'ilm* (gnosis), *wasiyya* (official succession designation) and reference to early Hashimite ('Abbasid) patriarchs.

The foundation of Baghdad

Having consolidated his political leadership against his two main rivals, the 'Alids and the Persian sympathisers of Abu Muslim, al Manṣur set about laying the foundations of the new 'Abbasid state, the most prominent signal of which was the establishment of a new capital: Baghdad, or Madīnat al Salam (the city of peace), as it was known in its time. After initial experiments to establish a capital named 'al Hashimiyya' in the environs of Kufa, al Manṣur finally decided on a location for the new capital in the heart of Mesopotamia, at the point where the Tigris and Euphrates rivers came closest, some fifteen miles north of the former Sasanid capital of Ctesiphon. Baghdad was meant to be the fortress of the new dynasty in times of crisis, as well as a strategically situated city in times of peace in economic and political terms. Its river surroundings permitted rapid communication with distant provinces of the empire through the Persian Gulf, and its central location made it a vital link for merchant traffic between Syria and Iran. Later medieval geographers, such as al Ya'qubī (d. 284/897) and Ibn Khurdadbeh (d. 272/885), marvelled not only at the wealth of the city's markets, but also at its ideal climate, which they related to the brilliance and good nature of its people.

The foundation of Baghdad did more than provide control over the wealthiest agricultural province of the empire and facilitate tax collection; it provided the 'Abbasids with a new space for inventing their own political mythology

and religious pretensions. The original kernel of the city, founded in 145/762, was the Round City of Baghdad, which housed the adjoining complex of the caliph's palace and mosque at its centre and was lined around its perimeter with the military barracks of the 'Abbasid troops and administrative buildings. With its circular design, and the caliph's palace and mosque standing at its centre, the Round City was meant to mirror the cosmological disc of the heavens, while its four main gates (Kufa, Baṣra, Khurasan and Damascus) pointed towards the cardinal directions, symbolising the varied directions of 'Abbasid control. The overall message was clear: the caliph's authority was divinely sanctioned, and the new caliphate seemed to lay a universal claim of succession to previous Near Eastern empires. Astrologers predicted that no caliph would meet death while living in the Round City, and a free turning statue towering over the palace pointed to where the caliph's enemies could come from next.

The new Islamic capital resonated with new ideological pretensions about the position of the 'Abbasid caliphs as imams and representatives of divine rule. Iranian notions about the divine right of kings were fused with Islamic messianic expectations centred on the family of the Prophet, or a utopian community ruler, to shape the 'Abbasid political institution. This mixture was best reflected in the messianic titles that various caliphs were given as successors even before they assumed caliphal authority. The caliphs ruled as blessed members of the Prophet's family, as guardians of the Islamic faith, and as just rulers who were faithful to the Persian monarchal ideal. The strength of the caliphal institution thus lay in its universality and ability to communicate different things to different subjects of the empire, an achievement that surpassed all the particular shades of previous Near Eastern empires.³

Within this milieu of competing religious expectations, al Manṣūr crafted the path of his successor when he designated his son, Muḥammad, as heir to the throne and gave him the more formally suggestive title 'al Mahdī' (the rightly guided one) in 141/758. At the time, al Mahdī was just being readied to depart to Rayy to rule as viceroy of the eastern provinces and confront the challenges of the Khurasanī rebellion (led by 'Abd al Jabbar al Azdī). In that climate the title 'al Mahdī' was clearly meant to bring a closure to all hopes of millennial change, both Arab and Iranian. Over the next decade al Mahdī's governorship gave a certain stability to the 'Abbasid image in this context. His provincial capital, Rayy, was renamed 'al Muḥammadiyya' in his honour, and

3 J. Lassner, *The shaping of 'Abbasid rule* (Princeton, 1980), pp. 169–75; C. Wendell, 'Baghdad: *Imago Mundi* and other foundation lore', *IJMES*, 2 (1971).

the city's fortunes quickly grew in the second half of the eighth century, as it became both a trading hub for the Caspian region and a monetary centre that issued a volume of 'Abbasid coinage that rivalled Baghdad's.⁴

Aside from crafting the charismatic image of the new state, al Manṣur was a methodical planner of centralising policies, a quality that was reflected in his military and provincial organisation. While the institution of the vizierate had not yet assumed a significant role, a range of advisers (Abu Ayyub al Muryanī, Khalid ibn Barmak and al Rabī' ibn Yunus) helped facilitate policies planned by the caliph. Al Manṣur's primary reliance on the Khurasanī troops who brought the 'Abbasids to power during the revolution remained his main policy. Various commanders who had formed the nucleus of lieutenants (*nuqaba'*) of the early revolutionary summons (*da'wa*) now assumed leading roles as commanders (*quwwad*) in the new state, holding positions of governorship and heading important campaigns. The most prominent in this group included Khazim ibn Khuzayma al Tamīmī, Malik ibn al Haytham al Khuza'i, Muḥammad ibn al Ash'ath al Khuza'i, Mu'adh ibn Muslim al Dhuhli, 'Uthman ibn Nahik al 'Akkī, al Musayyab ibn Zuhayr al Ḍabbī and kin relations of the famous Qaḥṭaba ibn Shabīb al Ṭa'i. This was a formidable circle of commanders, who commanded support both in their land of Arabian origin and in the Khurasanī settlements they had inhabited in the late Umayyad period. The caliph often called on them in situations of crisis, and they invariably proved successful in defending the 'Abbasid cause. In honour of their role in founding the 'Abbasid regime, the caliphs bestowed on them the honorary title 'al Abna', an abbreviation of *abna' al da'wa* or *abna' al dawla* ('the sons of the state') which gradually was applied to their descendants who served in a similar capacity as well. The Abna' formed both a social and a military solidarity group drawn from the larger army of the Khurasaniyya, and they became the crack troops of the caliphs for a period of half a century. Their unique identification with the historical moment of the revolution was only strengthened with their settlement in Baghdad and their acquisition of landed estates in Iraq (*qaṭa'i*).⁵

Another group that al Manṣur relied on extensively was the 'Abbasid family itself. Al Manṣur's succession coup, in which he claimed the succession for himself and his son at the expense of 'Abd Allah ibn 'Alī, did not prevent him from relying on his other uncles to govern important provinces. These individuals often included Sulayman ibn 'Alī (in Baṣra), Ṣalīḥ ibn 'Alī (Syria),

4 Thomas Noonan, 'The 'Abbasid mint output', *JESHO*, 29 (1986), pp. 150–3.

5 H. Kennedy, *The early Abbasid caliphate: A political history* (London, 1981), pp. 78–85.

Ismaʿīl ibn ʿAlī (Mosul) and ʿIsa ibn Musa (in Kufa). Their children often occupied government positions as well, albeit not necessarily in the same town or for a significant length of time. A key pattern of the early ʿAbbasid state was that, whereas the Abnaʾ and the Khurasanī commanders often served in distant provinces (al Jibal, Fars, Khurasan or North Africa), members of the ʿAbbasid family took appointments in regions closer to Baghdad (Kufa, Baṣra, Syria, Egypt and the Ḥijaz).⁶ Ceremonial functions such as leading the pilgrimage caravan to Mecca were also entrusted to members of the ʿAbbasid family.

Beyond these two groups of officials, al Manṣūr tried to reach out to veteran commanders of the Umayyad period, including those who had once fought against him during the revolution. In this group one finds commanders such as Salm ibn Qūṭayba ibn Muslim, Maʿn ibn Zaʿida al Shaybanī and a slew of Muhallabī commanders (Sufyan ibn Muʿawiya ibn Yazīd ibn al Muhallab, governor of Baṣra; Rawḥ ibn Ḥatim ibn Qabīsa ibn al Muhallab; Yazīd ibn Ḥatim al Muhallabī; and Muḥammad ibn ʿAbbad). These commanders did not always thoroughly defend the ʿAbbasid interest, such as in the wavering role Sufyan ibn Muʿawiya assumed in Baṣra during the ʿAlid revolt of Ibrahīm ibn ʿAbd Allah, but al Manṣūr seems to have been willing to forgive some lapses. It appears that, while religiously his propaganda addressed an eastern constituency, politically and militarily his focus was on the Arab tribal elite, even if this sometimes meant rehabilitating former Umayyad commanders.⁷ This trend towards an accommodation with Syria was best reflected in 154/771, when al Manṣūr ordered the building of the garrison city of al Rafīqa, modelled after Baghdad, adjacent to the town of al Raqqā as the ʿAbbasid base in Syria. Al Raqqā and Rafīqa would quickly surpass Damascus as the largest urban centre in Syria, and Harun al Rashīd would later choose al Raqqā as his political centre and residence during the period 180–92/796–808.

There is less information about the economic organisation of the ʿAbbasid empire in those decades than its political and military order. Iraq was the wealthiest province of the empire, and had been undergoing a process of agricultural development since the Umayyad period. Al Manṣūr continued the practice of allocating various revenue generating projects to his supporters;

6 D. Nicol, 'Early ʿAbbasid administration in the central and eastern provinces, AH132–218/AD750–833', Ph.D. thesis, University of Washington (1979), pp. 208, 211, 271.

7 On the continuity in some governmental patterns from the Umayyad to the ʿAbbasid period, see I. Bligh Abramski, 'Evolution vs. revolution: Umayyad elements in the ʿAbbasid regime 133/75–32/932', *Der Islam*, 65 (1988); A. Elad, 'Aspects of the transition from the Umayyad to the ʿAbbasid caliphate', *JSAI*, 19 (1995).

however, this time the main share went to members of the ruling family. These were encouraged to reclaim lands in the marsh area (the territory known as al Baṭa'ih) for agricultural use, to develop irrigation in the area, and were granted commissions for canals initiated by the caliph in the region.⁸ The tax regime in Iraq seems to have been flexible, and even light, favouring the continued satisfaction of the ruling elite over fiscal control from the central government. In a region that was historically the breeding ground for 'Alid rebellion, this policy was partly intended to sway political sympathies towards the ruling dynasty. Information about taxation in other provinces is not abundant, but anecdotal evidence from an important source such as al Baladhurī's *Futuḥ al buldan* also shows a trend of government flexibility whereby caliphs sometimes modified the taxation rate of particular towns upon petition from the populace.⁹ This flexibility was to change in the reign of al Ma'mun, who demanded greater revenues from the provinces, and this resulted in famous rebellions, in Egypt in 217/832 and in some Iranian towns (at Qumm in 210/825).

Al Manṣur's image in the sources is that of a thoroughly authoritarian ruler, consistently centralising but never arbitrary. He is said to have compared himself with the Umayyad caliph 'Abd al Malik ibn Marwan as a consolidator of caliphal power, and he probably went further in keeping track of his governors' policies through a network of provincial agents (*ṣaḥib al khabar*), although this may well be exaggerated as a political exemplum in the sources.¹⁰ Various accounts also give a vivid picture of al Manṣur's pragmatism and his parsimony, which built the 'Abbasid treasury. When he decided to build a wall enclosure and a moat around Kufa, he reportedly offered residents of the town, who participated in the project, five *dirhams* each before the work began. But then, using this to establish a population census, he later ordered that each resident of the town be taxed forty *dirhams*.¹¹ Poets and courtly visitors found little patronage at al Manṣur's court, but he left behind a rich

8 Aḥmad ibn Yahya Baladhurī, *Futuḥ al buldan*, ed. S. al Munajjid, 3 vols. (Cairo, 1957), vol. I, pp. 445, 451, 453 4; Michael Morony, 'Landholding and social change: Lower al 'Iraq in the early Islamic period', in Tarif Khalidi (ed.), *Land tenure and social transformation in the Middle East* (Beirut, 1984).

9 This happened mainly during the reign of al Rashīd: Baladhurī, *Futuḥ al buldan*, vol. I, p. 182, vol. II, p. 456: Qudama ibn Ja'far, *Kitab al kharaj wa šina'at al kitaba*, ed. M. H. al Zubaydi (Baghdad, 1981), p. 377; Yaqut al Ḥamawī, *Mu'jam al buldan*, 5 vols. (Beirut, 1957), vol. IV, p. 343.

10 A similar policy of monitoring governors is attributed to 'Umar ibn al Khaṭṭab earlier: al Jahiz (attrib.), *Kitab al taj fi akhlaq al muluk*, ed. A. Zaki (Cairo, 1914) p. 168.

11 Abu Ja'far Muḥammad ibn Jarīr al Ṭabarī, *Ta'rikh al rusul wa'l muluk*, ed. M. J. de Goeje, 15 vols. in 3 series (Leiden, 1879–1901), series III, p. 374.

treasury and a stable empire for his successor. It was left to al Mahdī to decide on a new direction in official policy.

Al-Mahdī, al-Hadī and al-Rashīd

Al Mahdī's decade long reign was by all accounts a prosperous time for the caliphate. Al Maṣṣūr's efforts to build the name of the dynasty and its treasury allowed his successor to explore new paths for developing 'Abbasid authority, especially in the religious sphere and in foreign policy towards the Byzantines. Al Mahdī's policies aimed at making the caliphate more popular with its subjects. He began his reign with an amnesty for political prisoners and established a high court that examined public grievances (*maḥalim*), and sought to lessen the tax burden in Iraq by establishing the system of *muqasama*, a tax ratio that was established in proportion to the agricultural yield, in place of the existing fixed tax rate (*miṣaḥa*).¹² Messianic rebellions against the caliphate greatly diminished (especially from the 'Alids, with whom the caliph established some measure of reconciliation), with the important exception of the Iranian revolt initiated in 159/776 by the famous 'veiled prophet' (al Muqanna'). This revolt, which began in the town of Kish in Khurasan, eventually spread to Samarqand, and lasted for three years before it was defeated, thus showing the continued resilience of the millennial message in the east.

Al Mahdī's more immediate response after al Muqanna's revolt was to draw a clearer boundary between Islam and *zandaqa* (heresy),¹³ as well as to foster a greater affinity between the caliphate and traditional Islam. Toward this effort, he invested heavily in the upkeep of Mecca, the pilgrimage road and charities associated with the *ḥajj*. In 161/778 he refurbished the Ka'ba (removing previous layers of veiling piled up since the time of Hisham ibn 'Abd al Malik), and undertook an expansion of its mosque that included the adding of significant decorative mosaics. He improved the pilgrimage road from Iraq to Mecca by building better travel stations along the way, lavished charities on the Meccan inhabitants, and in 166/782 added a postal network

12 The switch in tax regimes was in part due to reduced expectations of revenues from Iraq's agricultural lands after the area was affected by war in the last decades of Umayyad rule. The system of *muqasama* also varied according to amount of cultivated land, irrigation methods being used, types of crops and proximity to the market: 'Abd al 'Aziz al Duri, *al 'Aṣr al 'Abbāsī al awwal* (Baghdad, 1945), pp. 85, 204–6; R. Le Tourneau, 'Bayt al Mal', *EL*2, vol. I, pp. 1141–9.

13 The charge of *zandaqa* had previously been applied by the Zoroastrians to the Manichaeans.

between Mecca, Medina and Yemen.¹⁴ All this attention came in addition to the already established practice of the 'Abbasid caliphs of making frequent pilgrimage trips to Mecca (or assigning a member of the family to lead the ceremony in their place), as well as making occasional visits to Jerusalem and devoting resources to its preservation.¹⁵ Al Mahdī is noted for having completely rebuilt al Aqṣa Mosque after it was damaged by an earthquake in 130/747.¹⁶

There was also from this period a greater turning at the 'Abbasid court towards the traditionist culture of *jama'ī sunnī* practices, dicta and customs of Medina. Sunnī Islam, as later generations came to know it from the canonical *ḥadīth* texts of the ninth century and the Ḥanbalī responses to the Mu'tazila, had not yet flowered, but the key trends of *jama'ī* beliefs and practices, as well as the method for reasoning legal opinion, were already in place. Malik ibn Anas (d. 179/795) and Abu Ḥanīfa (d. 150/767) were the two leading exponents of normative religious practice. The first contributed his classic compilation *al Muwaṭṭa'*, which preserved the sayings and practices of the Prophet and the early Medinan community as a code of religious practice, and the second introduced the use of reasoned argument (*al ra'y*) to adduce jurisprudential opinion. Unlike the Umayyads, the 'Abbasids displayed an interest in the activities of religious scholars and tried to have them serve in official capacities. Al Maṣṣūr did not make much progress in this, but his successors, especially al Rashīd, later did, and attracted a diverse circle of traditionalist scholars to their court.¹⁷ Among these individuals were sages, such as 'Abd Allah ibn al Mubarak (d. 181/797), Qur'an scholars, such as al Kisa'ī (d. 189/805), and jurists, such as Abu Yusuf (d. 182/798), a student of Abu Ḥanīfa who became the chief *qaḍī* of Baghdad.

But perhaps the most public sign of the 'Abbasid rediscovery of Islamic symbols was the revival of the Arab Byzantine *jihad*. Arab campaigns in Asia Minor, which had been a major pillar of Umayyad imperial expansion, had come to a halt during the period of the dynastic transition. In place of official

14 Al Ṭabarī, *Ta'rikh*, series III, p. 483. 'Izz al Dīn 'Alī ibn Aḥmad ibn al Athīr, *al Kamil fī'l ta'rikh*, 13 vols. (Beirut, 1965-7), vol. VI, pp. 55, 76.

15 Al Maṣṣūr had already introduced the custom of caliphal visits to Jerusalem, after his pilgrimage in 140/757, and al Mahdī made a similar journey in 163/779. Al Maṣṣūr also journeyed from Baghdad as far as Jerusalem in 154/771, accompanying the army of Yazīd ibn Ḥatīm al Muhallabī, which was heading to North Africa: Baladhurī, *Futuh al buldan*, vol. I, p. 275.

16 Shams al Dīn Muḥammad ibn Aḥmad al Muqaddasī, *Aḥsan al taqasīm fī ma'rifat al aqalim*, ed. M. J. de Goeje (Leiden, 1906), p. 168; R. W. Hamilton, *The structural history of the Aqsa Mosque* (Jerusalem, 1949), pp. 71-3.

17 Muḥammad Q. Zaman, *Religion and politics under the early 'Abbasids: The emergence of the pro Sunnī elite* (Leiden, 1997), pp. 147-62.

campaigns, during the early ‘Abbasid period the frontier became open to local warlords, who were occasionally joined by religious volunteers who took up residence in improvised *ribaṭs* (frontier forts).¹⁸ Starting with al Mahdī, the caliphate began to reassert its presence in organising campaigns, which on occasion the caliph led in person, such as in 163/780, when he was accompanied by his twenty year old son Harun. Two years later Harun was put in command of his own army, which mounted a daring expedition that reached as far as the coastline opposite Constantinople and forced the Byzantine empress Irene to pay a heavy tribute of 160,000 *dīnars* for the next three years.¹⁹ It was probably in light of Harun’s savvy strategy in this campaign that he was given the title ‘al Rashīd’ the following year and designated as second successor, after al Hadī.

Al Mahdī’s attention to the Arab–Byzantine conflict formed a major pillar in his religious propaganda on behalf of the caliphate. These expeditions set in place the image of the ‘*ghazī* caliph’ who was resuming the unfinished mission of the early Islamic conquests, and reviving the potential for conquering Constantinople. Aside from its religious significance, the increased ‘Abbasid attention to the Byzantine frontier underscored the policy of restoring a military role for former tribal sources of support in Syria. As such, the Byzantine front helped bridge differences between the Iraqi and Syrian military elite, and the situation was reinforced in a new administrative context when in 189/805 al Rashīd established the new frontier province of al ‘Awaṣim, which ran along the southern side of the Taurus mountains in northern Syria. The new unit was placed under the leadership of a prominent member of the ‘Abbasid house, Harun’s nominee for the third succession, al Mu’taman, who from then on became responsible for commanding annual raids, supervising conscription and ransoming prisoners of war.

Al Mahdī died suddenly in 169/785 from eating a poisoned pear, according to one account, or in a hunting accident, according to another. The sources give little biographical information about him in comparison with al Maṣṣur or al Rashīd, which may indicate a redaction in the extant early medieval chronicles from a once larger collection of narratives. Al Mahdī was succeeded by al Hadī, who ruled for one year and died in mysterious circumstances. The main event of his reign was another attempt at revolt by an ‘Alid leader from the Ḥasanid line, al Ḥusayn ibn ‘Alī, who chose Mecca as his base

18 Michael Bonner, ‘Some observations concerning the early development of jihad on the Arab–Byzantine frontier’, *SI*, 75 (1992), p. 30.

19 Warren Treadgold, *The Byzantine revival 780–842* (Stanford, 1988), pp. 67–70.

this time. The revolt was a dismal failure and ended with the tragic death of its leader, which the caliph reportedly deeply regretted and claimed had happened against his will. A more important result of this rebellion was the escape of two of al Ḥusayn's 'Alid supporters, Idrīs ibn 'Abd Allah and Yaḥya ibn 'Abd Allah, brothers of Muḥammad al Nafs al Zakīyya, to distant provinces where they set up 'Alid bases away from 'Abbasid control. Idrīs fled to the Maghrib, where he succeeded in rallying Berber support in establishing the first 'Alid dynasty in Islamic history, while Yaḥya fled to Daylam, where he found refuge with Persian princes of the area before he was captured during al Rashīd's reign.

When the 'Abbasid succession passed on to Harun al Rashīd, it was finally the anticipated moment which different factions wanted. The 'Abbasid family, the Barmakid viziers and the army had all favoured al Rashīd for his achievements in al Mahdī's time, and he appeared ready to take the 'Abbasid state to a new height. While al Ma'nūr had established the concept of the 'Abbasid caliphate, it was Harun al Rashīd who came to establish the character of its monarchy. His relatively long (twenty three year) rule helped institutionalise the image of the 'Abbasid court at home and abroad. Through numerous anecdotal accounts set during his reign, the medieval sources describe patterns of courtly order and ceremony that were surely new to the caliphate and that probably reflected a revival of Persian Sasanid principles of a ruler's behaviour and conduct.

The 'Abbasids went even further than the Umayyads in announcing their political absolutism and its religious foundation, claiming titles such as 'imam' and 'God's caliph' (especially from al Ma'mūn's time onwards). But whereas Umayyad absolutism was characterised negatively by Islamic texts as *mulk* (kingship), the 'Abbasids were accommodated by *jama'ī sunnī* writers, mainly because the new caliphs postured as guardians of Islamic law and ritual. More than any previous caliph, al Rashīd cultivated a public image of piety, often leading the pilgrimage to Mecca and just as frequently leading an expedition across the Byzantine frontier. Following al Mahdī's policy, he established generous endowments at Mecca and Medina, and he went further by welcoming a range of *ḥadīth* and *fiqh* scholars and ascetics at his court.²⁰ Al Rashīd's

20 Harun's times in general were a period when important religious sciences were undergoing critical systematisation and contributing to the shaping of orthodox principles. After an earlier generation of mentors, such as Abu Ḥanīfa, Malik ibn Anas and Ibn Ishāq, a diverse cadre of successors contributed to the shaping of detail in the grammar and message of the Islamic text. This included the jurist Shafī'ī (d. 204/819); Abu Ḥanīfa's student Muḥammad ibn al Ḥasan al Shaybānī (d. 189/804), the grammarians al Khafīl ibn Aḥmad al Farahīdī (d. 175/791) and Sībawayhi (d. 183/799), and Qur'an reciters such as Warsh (d. 197/812) and Ḥafṣ (d. 189/805).

wife, Zubayda, also earns a wide reputation in the sources for funding the construction of the water stations (the famous Darb Zubayda) between Kufa and Mecca, to facilitate the *ḥajj* journey and bring water to pilgrims in Mecca.

On the international stage, Harun also devoted considerable effort to projecting an image of 'Abbasid power. The story of Charlemagne's embassies to Baghdad in 797 and 802, and the arrival of envoys from the caliph in Aachen, is well known from Western medieval sources and, although never mentioned in the Arabic chronicles, does seem historically genuine.²¹ The aim of these ties was primarily to build on the mutual hostility of the two leaders to the Spanish Umayyad emirate in Cordoba and the Byzantine empress Irene and her successor, Nicephorus. In studying 'Abbasid Carolingian relations, F. W. Buckler has argued that at a crucial moment, around 803, with simultaneous pressures on the Byzantine empire in Venice and the Dalmatian region as well as in Asia Minor, Nicephorus was forced to recognise Charlemagne as emperor in the west.²² Even more important to 'Abbasid foreign policy were relations with the Khazar kingdom, situated north of the Caucasus. The Khazars, a people of mixed Altaic and Turkic background, had generally harboured a pro Byzantine policy. They had helped them turn back the tide of Sasanid conquest in the reign of Heraclius (610–41), and were later to intervene in similar contexts (their invasion of the Caucasus in 183/799 helped distract al Rashīd from his campaign against the Byzantines). Al Manṣur had tried to improve relations with the Khazars in 760 when he ordered his governor of Armenia, Yazīd ibn Usayd al Sulamī, to betroth himself to the daughter of the Khazar *khaqan*, but an alliance failed to materialise after the accidental death of the Khazar princess, which led to the initiation of raids against the caliphate. Al Rashīd seems to have also tried, albeit unsuccessfully, to improve ties with the Khazars.²³

In internal government, an important innovation by al Rashīd was to develop the powers of the vizierate, which promoted a new class of bureaucrats (the *kuttāb*), who mediated political control in the provinces. Among the *kuttāb*, the Barmakid family rose to unprecedented prominence for a period of nearly two decades. Khalid ibn Barmak, the family's chief representative during the revolution, was a trusted adviser to the caliph al Manṣur, but it was in Harun's time that the fortunes of Khalid's son, Yahya, and grandsons,

21 Among the well known Western accounts of these embassies are those by Einhard and Notker Stammerer, *Two lives of Charlemagne*, trans. L. Thorpe (Penguin, 1969), pp. 70, 145–9.

22 F. W. Buckler, *Harun al Rashid and Charles the Great* (Cambridge, MA, 1931), p. 27.

23 W. Barthold and P. Golden, 'Khazars', *EL2*, vol. IV, pp. 1172–8.

al Faḍl and Ja'far, became increasingly dominant. The 'Abbasids had probably long appreciated the elite Persian roots of the Barmakid family, as former priests of the Buddhist temple of Balkh, and their ties with princely families in Khurasan, and tried to establish a closer link with them through a milk brotherhood, which was repeated in two generations such that it made Harun al Rashīd and al Faḍl ibn Yahya milk brothers, and Yahya a kind of foster parent for the caliph.

During their tenure as viziers the Barmakids succeeded not only in reducing Iranian revolts, but also in garnering a more realistic share of Khurasan's tax revenues for the central government, and were able to defuse 'Alid revolts as well. It was clear that Harun relied on the Barmakids to give an Iranian character to the caliphate in the east, and that through the vizierate he sought to project an image of partnership between the Arab and Iranian elements in ruling the empire.²⁴ The energetic Barmakids played a key role in making this equilibrium between east and west work, and it seems they may have pushed to translate it to the sphere of dynastic succession as well. After designating his son al Amīn to the caliphal succession in 175/791, Harun assigned al Ma'mun as second successor in 183/799. The maternal ties of the two successors were influential in these decisions, since al Amīn was born to Zubayda and her illustrious Arab line of descent from al Manṣur, while al Ma'mun was the son of a Persian concubine from the region of Badhghīs. Selecting a second successor with Khurasanī ties was clearly symbolically important for future government, and was undoubtedly an evolution of the policy of relying on the Barmakids. The culmination of this symbolic refinement of administration came in 186/802 with Harun's famous plan to 'divide' the empire between his two successors upon his death. Thus, while al Amīn was to reign as caliph in Baghdad, he would rule effectively only in the western provinces (west of Iraq), while al Ma'mun would be the autonomous ruler of the eastern provinces until he succeeded al Amīn, when he would reign as caliph over a reunited empire.

The details of this plan are described in a covenant of succession included in al Ṭabarī's chronicle. There is, however, reason to doubt the full authenticity of this document, since it often sounds like an apologetic text written in the aftermath of the civil war to defend al Ma'mun's counterclaims against al Amīn during the succession conflict in 195 8/811 13. The assertions in the

²⁴ The story of the influential Barmakids remains mired in a mix of historical fact and literary legend. For a traditional survey of their prosperous career and sudden downfall from power in 187/803, see D. Sourdel, *Le vizirat abbasside de 749 à 936*, 2 vols. (Damascus, 1959 60), vol. I, pp. 127 81.

succession covenant of 186/802 about full independence for al Ma'mun in the east may well be an exaggeration of an earlier attempt by Harun to give al Ma'mun a position of governorship that would remain under the central rule of Baghdad. While keeping Khurasan under the central rule of Baghdad, however, Harun did envisage a unique, new image for 'Abbasid governorship in the east that would replace the crucial role previously played there by al Faḍl ibn Yahya.

Within a year of establishing the covenant of succession Harun ordered the sacking of the Barmakids. Whether the caliph believed that the 'Abbasid dynasty had become self-sufficient with the new succession arrangement, and that the Barmakids had served their purpose of coopting the loyalty of the east, or whether he feared that this family of ministers had become too powerful, cannot easily be determined. However, the years that followed were marked by the return of 'Abbasid government to the centralising policies of al Maṣṣur. The caliph now relied increasingly on the *Abna'* to enforce provincial control. 'Alī ibn 'Isa ibn Mahan, one of the more assertive members of the *Abna'*, though not their most experienced, was dispatched to Khurasan to control the province. His policies alienated the population, however, and it did not take long before rebellion broke out. Provincial disaffection surfaced this time in the garb of a rebellion by the governor of Samarqand, Rafī' ibn al Layth, grandson of the last Umayyad governor in Khurasan, Naṣr ibn Sayyar. Al Rashīd's previous options, using the *quwwad* and the Barmakids, had now been exhausted, and he resorted to a new strategy altogether, which was to head to Khurasan in person, accompanied by al Ma'mun. This was the first time a caliph had journeyed to Khurasan, and the gesture was intended as much to introduce 'Abbasid charismatic presence on the Khurasanī arena as to subdue the challenge of Rafī' ibn al Layth. A chain of army command was established between the caliph in Ṭus, al Ma'mun in Marw and the commander, Harthama ibn A'yan, in Samarqand.

Not long afterwards Harun died in Ṭus from a lingering illness he had contracted before leaving Baghdad, and the stage was set for rivalry between his sons, al Amīn in Baghdad and al Ma'mun in Marw. This ended the famous 'golden prime' of the 'Abbasid caliphate. Harun's relatively stable reign became a reference point for nostalgia by later Muslim chroniclers who wrote after the civil war. For Sunnī writers his reign symbolised a time of harmony within the *jama'a* before the onset of *fitna* (conflict), while for literary writers it represented the last days of a prosperous time. Religious writers saw in him a loyal champion of *ḥadīth*, unlike the innovative al Ma'mun, while literary writers depicted his court as the purveyor of massive

wealth and patronage for poets and all those with talent. And yet, notwithstanding an element of myth, the prosperity of the caliph's time does appear to have been real. The archaeological evidence of pottery and numismatic finds outside the caliphate in the Baltic Sea region, the coast of East Africa and China point to a wide network of long distance trade in which Baghdad stood as the most important metropolis.²⁵ The cooperative relation between the 'Abbasids and the Tang dynasty (r. 618–907) in China facilitated not only overland trade through Transoxania, but also helped establish a commercial presence for Muslim traders in the Indian Ocean, which contributed in time to the emergence of a Muslim community in South Asia.²⁶ In the absence of reliable literary accounts about al Rashīd, the main image of the caliph remains the popular, romantic one of the *Thousand and one nights*. There, Harun remains the caliph who would journey the streets of Baghdad at night in disguise, accompanied by his minister Ja'far, mingling with the ordinary population in search of mystery and adventure while being attentive to his subjects' well being.

The succession crisis

The formal agreement that Harun drafted between his two sons mainly established a line of first and second succession. This had become necessary, as previous political experience showed that a ruling caliph often tried to change the path of succession from a relative (often a brother) to his own son. Al Manşur did this when he pushed away 'Isa ibn Musa from the succession in favour of al Mahdī, and al Hadī tried to do the same when he sought to place his son Ja'far ahead of al Rashīd. The document of 186/802 helped to formalise the succession through covenants. However, the gubernatorial role given to al Ma'mun in the east, combined with the unrest in Khurasan at the time of Harun's death in 193/809, made the situation open for ambitious contention. Almost immediately al Ma'mun became a political magnet for Iranian sympathisers (in place of Rafī' ibn al Layth), who saw in him a national representative against the central government. Meanwhile, al Amīn's hasty attempt to

25 Richard Hodges and David Whitehouse, *Mohammed, Charlemagne and the origins of Europe: Archaeology and the Pirenne thesis* (Ithaca, 1983), p. 158.

26 Philip Curtin, *Cross cultural trade in world history* (Cambridge, 1984), p. 107. G. Hourani, *Arab seafaring in the Indian Ocean in ancient and early medieval times* (Princeton, 1951), pp. 68–73. Remarkably, the most convenient path for trade between the caliphate and Europe through the Mediterranean was blocked by the Byzantine navy, which tried to thwart contacts between Charlemagne and the 'Abbasids.

exert a traditional centralising policy by recalling his brother from the east in favour of leaving the Abna' commanders to handle the situation further strengthened the polarisation between al Amīn and al Ma'mun.

Each side was advised by a capable minister who sought to protect a privilege or an ambition at the cost of war. Al Faḍl ibn al Rabi', who had replaced the Barmakid family in the vizierate, strengthened the bias against Khurasan by pushing to have al Amīn drop al Ma'mun from the succession altogether, while in Khurasan al Faḍl ibn Sahl, a Khurasanī aristocrat and a protégé of the Barmakids, urged al Ma'mun to remain in the east, and set about organising a local army under the command of Ṭahir ibn al Ḥusayn. Ṭahir's family, although Iranian (from the town of Bushanj near Herat), had joined 'Abbasid service since the revolution, but they had been eclipsed by bigger stars among the Abna'. Al Ma'mun thus represented to diverse groups (the Sahlids, the Farrkhusraws and the Ṭahirids) an opportunity for changing the status quo. When al Amīn finally summoned his brother to the capital and the latter refused, al Amīn dropped al Ma'mun's name from coinage as successor in favour of his own son, Musa, 'al Naṭiq bi'l Ḥaqq', and the situation became one of open war from 196/812 onwards.

During the next two years the succession conflict between al Amīn and al Ma'mun translated into a myriad of regional conflicts across the Islamic empire as local leaders championed the cause of one 'Abbasid leader against the other. The central military confrontation between al Amīn's armies, which were led by 'Alī ibn 'Isa ibn Mahan, and al Ma'mun's troops, who were led by Ṭahir ibn al Ḥusayn, happened at the town of Rayy, where, after a clear victory, al Ma'mun's army advanced on to Baghdad in 198/813. After a siege that lasted over a year, al Ma'mun's forces finally broke through the defences of the city, and in the chaos that followed the caliph was captured and quickly put to death. This resolution must have gone against the strategy of al Faḍl ibn Sahl, who then feared a backlash against al Ma'mun and sought to alleviate the crisis by transferring Ṭahir to a relatively inferior military command in al Jazīra soon afterwards. The regicide of al Amīn was the first time that an 'Abbasid caliph had been violently overthrown, and this was something that no doubt shook the credibility of the 'Abbasid monarchical institution and altered how it was perceived by an Islamic and Persian public.

Far from providing stability, Ṭahir's conquest of Baghdad triggered a new phase of turmoil, as local vigilante groups took control of the city and ousted the new governor of Iraq, al Ḥasan ibn Sahl. A rebellion in southern Iraq on behalf of an 'Alid imam, led by a former army commander Abu 'l Saraya, further added to the chaos. Iraqi resentment was further enhanced by

al Ma'mun's curious policies during the next four years. Instead of returning to Baghdad after his victory he remained in Marw after 198/813, and allowed al Faḍl ibn Sahl a free hand in ruling the empire, after having bestowed on him the title of *Dhu 'l Riyasatayn*. To the Iraqi populace, attached to the primacy of their province in the empire, this was a subversive Iranian action, designed by the Sahlids to undermine the Arab caliphate. When al Ma'mun decided in 201/816 to enhance his religious authority by assuming the title 'God's caliph' and simultaneously nominating the 'Alid imam 'Alī ibn Musa al Riḍa to the caliphal succession and changing the official colour of the 'Abbasid state from black to green, the Baghdadīs decided to respond by putting forward their own nominee for the caliphate, Ibrahīm ibn al Mahdī, and dismissed al Ma'mun as a prince manipulated by the Persians.

However, when the situation in Baghdad spiralled completely into chaos al Ma'mun's priorities now shifted to the west, and he resolved to return to Baghdad and reduce his partisan association with Khurasan. His journey west, which took a whole year to complete, began conveniently with the death of 'Alī ibn Musa al Riḍa (who died poisoned in mysterious circumstances). Al Ma'mun's political rapprochement with the Baghdad opposition was helped even more when al Faḍl ibn Sahl was assassinated soon after in the town of Sarakhs, again possibly at the caliph's instigation. He had been the architect of al Ma'mun's bid for power from the beginning, but had also come to be viewed as the reason for the 'Abbasid civil war, and had alienated both the *Abna'* and his own Ṭahirid military base. When the new caliph finally arrived in Baghdad in 204/819, all disturbances in the city subsided. The populace was now eager for a return to more peaceful days and for the restoration of Harun's legacy.

The age of reunification and transition

(204–18/819–33)

When al Ma'mun began the new phase of his rule from Baghdad, only the eastern provinces of the empire were politically stable. Nearly all the others had lapsed, in varying degrees of autonomy, from 'Abbasid rule. Egypt had broken up into two districts ruled by competing commanders, 'Ubayd Allah ibn al Sariyy in the south and 'Alī al Jarawiyy in the north. Syria had fallen to local tribal rivalries in which a Qaysī strongman, 'Abd Allah ibn Bayhas, emerged as a leader. Al Jazīra had fallen under the sway of another ambitious Qaysī chief, Naṣr ibn Shabath al 'Uqaylī, while Yemen drifted under various 'Alid rebellions, first led by Ibrahīm ibn Musa ibn Ja'far al Ṣādiq in 199–202/814–17,

and later resumed by another 'Alid rebel, 'Abd al Raḥman ibn Aḥmad, in 206/821. Most dangerous of all was the heterodox movement of Babak al Khurramī, who, starting in 201/816, took control of the mountainous region of Azerbaijan and Armenia and declared an open war against Islam and Arab rule. Reunifying these diverse provinces demanded a kind of military force that was not available to al Ma'mun at that time, so for the next decade he used a mix of diplomacy and incremental conquest to restore his control of the empire.

The cornerstone of al Ma'mun's new government was a continued reliance on the Ṭahirid family that had brought him to power. Now, under the command of 'Abd Allah ibn Ṭahir, a new and more Iranian nucleus of the 'Abbasid army set about achieving provincial centralisation. After achieving reconciliation with the 'Abbasid family and granting amnesty to former opponents in Baghdad, al Ma'mun dispatched 'Abd Allah ibn Ṭahir on the mission of reunification. This began first in 209/824 with a move north against Naṣr ibn Shabath, who was brought to submission after difficult negotiations, and the same 'Abbasid army then moved south west into Syria, gaining the allegiance of Ibn Bayhas along the way, and then marched towards Egypt. Although the two Egyptian commanders were not directly hostile to al Ma'mun's leadership as caliph they were clearly interested in autonomy, and had succeeded in rebuffing an earlier army sent by al Ma'mun in 209/824, led by Khalid ibn Yazīd ibn Mazyad. 'Abd Allah ibn Ṭahir must have shown a distinct military talent on his campaign, since through tactical manoeuvring and negotiation he was able to outmatch the two experienced governors. When he returned to Baghdad in 212/827 with news of the submission of Egypt, Ibn Ṭahir was received with a parade and a hero's welcome, and was soon afterwards designated the new governor of Khurasan, thus beginning the most prosperous phase of Ṭahirid rule in the east (213 30/828–45).

The caliph's success in the west was not matched in the north, where a series of armies sent out against the Khurramiyya met with catastrophic failure. Several key 'Abbasid commanders of these campaigns were killed during these wars including, al Sayyid ibn Anas, governor of Mosul, and Muḥammad ibn Ḥumayd al Ṭusī, governor of Azerbaijan. The persistence of the Khurramiyya revolt was partly due to their knowledge of the region's difficult terrain and their alliance with the Byzantines, but over time, and from the perspective of the central government in Baghdad, the situation provided a sharp reminder of the empire's shortage of military resources, which had reached a crisis point with the defeat of Muḥammad ibn Ḥumayd in 214/829.

It is therefore not a coincidence that the first significant appearance of the new Turkish slave military units – when Abu Ishāq (al Mu‘taṣim) is reported to have commanded an army of 4,000 Turkish troops – happened around this time.²⁷ This military development signalled a new strategy by al Ma’mun for dealing with the crisis on the northern front. The Ṭahirids and the Samanids, while aware of the increased military demands of the caliphate, appear to have been reluctant to join in such intractable wars.²⁸

At the same time that he sought to achieve political centralisation in the empire, the caliph also undertook other steps that reflected administrative changes. The most salient of these was perhaps the coinage reform for the empire, which changed both the fineness and the style of *dirhams* and *dīnars*. In place of the varied inscriptions on Islamic coinage, which previously included names of local governors and officials as well as the caliph, al Ma’mun ordered the removal of all names, including his own, from the coinage. This trend towards anonymity was perhaps meant to simplify the test of political control in the provinces and the continuity of the minting process. A remarkable artistic feature of the new coinage was a marked refinement in the style of Arabic Kufic script. This change in script mirrored accounts in the sources about the caliph’s command to scribes and chanceries at around the same time, when he reportedly ordered an improvement in the styles of calligraphy. These monetary reforms came at a time when al Ma’mun was also reorganising tax assessments in Iraq and making some changes to systems of measuring the agricultural harvest.²⁹

By 215/830 al Ma’mun had restored control over most of the empire, and essentially turned a new leaf in ‘Abbasid government, moving away from the traditional system of al Maṣṣur and al Rashīd. Provinces were now organised into larger administrative units than those that had prevailed before. The province of al Jibal, for instance, was now subsumed under Khurasan, and smaller town governorships, such as Kufa and Baṣra, were merged into Iraq. The principle of hereditary and family centred gubernatorial appointment was introduced in provincial administration. The Ṭahirids were the first and most prominent example of this new pattern of administration: Ṭahir ibn al Ḥusayn was appointed governor of Khurasan in 205/820, and his family continued as governors in the province until 259/873. Their domain was vast (from the outskirts of Baghdad to the border of Transoxania), and they had control over

27 Muḥammad ibn Yusuf al Kindī, *Wulat Miṣr*, ed. H. Nassar (Beirut, 1959), p. 212.

28 ‘Abd Allah ibn Ṭahir declined the offer to assume command of the war against the Khurramiyya in 212/827.

29 Al Ṭabarī, *Ta’rīkh*, series III, p. 1039.

the tax revenues. They were also in charge of providing security in Baghdad, a task that would become even more important when the capital shifted to Samarra'. The Persian identity of the Ṭahirids greatly helped them to gain local political support. In cultural terms, however, they made every effort to identify with Arab culture, inviting eminent poets from Baghdad to come to their court and publicising their ancestral clientage to the tribe of Khuza'a (purportedly this began with the clientage of the family's ancestor, Ruzayq, to Ṭalḥa ibn 'Abd Allah al Khuza'i, who was governor of Sistan (624/681–3)). Khuza'a was especially important because in pre-Islamic times it had been considered a host and protector for the tribe of Quraysh; as such this helped enhance the symbolism of Ṭahirid support for al Ma'mun.³⁰ Various strands in their image as just rulers, loyal governors to the caliph and their affinity to Arab culture were strengthened further by their religious policy, which favoured the *jama'i sunnī*. As such, they succeeded in distancing themselves from the previous stigma of religious syncretism, especially in its messianic aspects, which had previously characterised and often undermined Iranian political movements in Khurasan.

Across the Oxus river, the Samanids provided what proved to be an even more important example of family government, as al Ma'mun put various children of Asad ibn Saman khuda (Nuḥ, Yahya and Ahmad) in charge of the important provinces in Transoxania (Samarqand, Shash and Farghana). The early history of the Samanids, when they first supported al Ma'mun's cause against Rafi' ibn al Layth, and later, during the civil war, is less known than that of the Ṭahirids, but the key fact about them is that they had an aristocratic background – priestly, and probably princely as well – that resembled the background of the Barmakids. Unlike the Ṭahirids, the Samanids identified strongly with Persian culture, even though they were also ardent Sunnīs who attracted *ḥadīth* scholars to their capital, Bukhara, and essentially set the standard for the non-Arab Sunnī emirate. While the Ṭahirids were in power the Samanids were dependent on their support, receiving investitures of governorate from Nishapur rather than from Baghdad. The Samanids were not alone in their dependence on Ṭahirid political approval. The same applied to Mazyar, the Iranian ruler of Ṭabaristan, and possibly to Afshīn in Ushrusana. Accustomed to longstanding independence, particularly in Ushrusana, which only cooperated with the caliphate during the governorate of al Faḍl al Barmakī, the two leaders would later rebel against al Mu'taṣim

30 C. E. Bosworth, 'The Ṭahirids and Arabic culture', *JSS*, 14 (1969).

because of his insistence that they continue to report to the Ṭahirid governor of Khurasan.

With this reshaping of the provincial administration in favour of a new Iranian elite, al Ma'mun had essentially pushed aside the two key groups that had previously served as governors, the 'Abbasid family and the Abna'. The power of the Abna' was also deliberately reduced as a response to their previous support for al Amin. Their political influence, however, may have already been on the decline for some time, with their increasing attachment to their economic interests and landed estates in Iraq. Still, for all the loyalty of the eastern governors to al Ma'mun, the caliph gradually became wary of Baghdad's singular dependency on the Iranian political element, and to counterbalance this he presided over the organisation of two other wings of the military. The first of these was the newly created Turkish military slave corps, which was put under the direction of the future al Mu'tasim, who became the caliph's viceroy in the western provinces of Syria and Egypt and a likely candidate for succession. And the second was the grouping of a tribal army under the direction of the caliph's son, al 'Abbas, who became the governor of al Jazira and was put in charge of organising campaigns against the Byzantines.

This new tripartite structure of the 'Abbasid army allowed the caliph to balance his diverse troops (Arab, Iranian and Turkish) and preserve the autonomy of caliphal decisions. With these and other administrative changes in place, al Ma'mun began to pursue a systematic strategy of confrontation with the Byzantine empire. The beginning of these hostilities can be dated to 215/830, when relations between the 'Abbasids and the Byzantines rapidly deteriorated. Byzantine attempts to restore their military pride in Asia Minor, along with 'Abbasid suspicion of Byzantine support for the revolt of the Khurramiyya, were key factors in igniting cross border raids. Unlike previous caliphs, whose conflicts with Byzantines tended to stabilise after a momentous confrontation, such as al Rashid's conquest of Heraclea in 190/806, al Ma'mun showed a surprising determination to escalate the war to the extent of showing an ambition to subdue the entire empire. This can partly be gauged from the impossible conditions he put on Theophilus in 218/830 (that all his subjects convert to Islam or all, including the emperor, pay the poll tax), and from the extra military recruitments the governors ordered in the regions of Syria, Jordan, Palestine, al Jazira, Baghdad and Egypt.³¹

31 Al Ṭabarī, *Ta'rikh*, series III, p. 1112; Abu Zakariya Yazid ibn Muḥammad al Azdī, *Ta'rikh al Mawṣil*, ed. 'Alī Ḥabība (Cairo 1967), pp. 410, 412.

For all its religious appearances, al Ma'mun's ambitious thrust against the Byzantines may have also had secular components that rested on a cultural and civilisational rivalry between Baghdad and Constantinople. Al Ma'mun was most famous among the caliphs for his interest in retrieving the classical heritage of the ancient Greeks from the Byzantines and for his patronage of the translation of classical texts. In his reign Iraq became renowned not only for gathering specialists in different fields, but also for synthesising knowledge from diverse cultures: Persia, India and the Byzantine domains. In the light of this, it is not unlikely that the caliph viewed his political ambitions in synchrony with his scientific ones, and considered regional dominance a catalyst for the acquisition of knowledge in various fields. Whatever his exact motives were, however, al Ma'mun's campaign ended with his sudden death after his armies had assembled in Tarsus. He was accompanied by his brother Abu Ishaq (al Mu'tasim) and his son al 'Abbas, and there are conflicting reports about whether the caliph had intended to transfer the succession to the throne from al 'Abbas to al Mu'tasim, who in fact assumed the caliphal title soon after.

Intellectual life: the religious policy of al-Ma'mun

Just as al Ma'mun's political achievements radically transformed the 'Abbasid government, his religious policies were equally new and daring. Unlike previous caliphs who had tried to ally themselves with existing systems of religious authority, al Ma'mun challenged *ḥadīth* and *fiqh* scholars directly. His adoption of the title *imam al huda* ('the guide to righteousness') in 195/811 and of 'God's caliph' in 201/816 gave an early sign of his ambition for a dominant religious authority. However, the more wide ranging plan for religious influence surfaced later, when he showed favour for the Mu'tazilī religious movement over other traditional sects. The Mu'tazila school of speculative theology had branched off some time in the early 'Abbasid period from the rationally oriented approach to forming legal opinion, the *ahl al ra'y*. Whereas the latter were concerned with practical juristic problems and solutions, however, the Mu'tazila debated sophisticated questions that dealt with the meaning of the divine word, the concept of divine justice, individual free will and predestination.³² Al Ma'mun's first clear patronage of the Mu'tazila occurred in 212/827, when he proclaimed as official doctrine the Mu'tazilī creed concerning the 'createdness' of the Qur'an.

32 M. Watt, *Islamic philosophy and theology* (Edinburgh, 1962), p. 42.

The idea of the createdness of the Qur'an was a Mu'tazilī refinement of the traditional religious belief in the Qur'an as the speech of God. This issue was controversial because it had a bearing on how orthodox belief ought to interpret the attributes of God, their eternity and the definition of an absolute monotheism. The Mu'tazilī logic behind the refinement considered that mere assertions about the Qur'an as the speech of God risked making the word of God something that existed outside the frame of time and therefore co-eternal with the Creator. Philosophical belief in a Prime Mover demanded that all contingent events be viewed as created in time (*muḥdath*). Ḥadīth scholars, however, who were dubious about any discussion of revelation and prophecy in relation to philosophy and linguistic detail, rejected this interpretation and abided by the letter of the text without attempts at redefinition. The Qur'an, to the traditionalists, was simply the 'Word' of God that cannot be characterised further.

When al Ma'mun first declared the official adoption of the createdness creed in 212/827, he remained tolerant of other *jama'ī* opinions on this issue for a period of six years. During that time he experimented with other official declarations that had diverse religious implications, including declaring the superiority of 'Alī's merits over those of other Companions of the Prophet, rejecting the merits of Mu'awiya, adding the *takbīr* ritual after the prayer and prohibiting puritanical zealotry as per the slogan *al amr bi'l ma'ruf wa'l nahy 'an al munkar* (commanding right and forbidding wrong). Then, in 218/833, the caliph returned to the issue of the createdness creed when he decided to impose this interpretation, along with other Mu'tazilī opinions, on traditional ḥadīth scholars in a programme known as the *miḥna* (lit., 'ordeal' or 'inquisition').

Why the creed issue interested al Ma'mun to the point of making it official doctrine, and why the ḥadīth scholars stood so solidly against it, is still not clear. Although it may seem that, by contextualising the Qur'an as 'created' in time, al Ma'mun was trying to override the text's authority, there is no evidence that the caliph was trying to override the authority of the Qur'an as a source of religious law. Rather, the confrontation with the 'ulama' probably related indirectly, but more importantly, to the authority of ḥadīth.³³ Ḥadīth had long been the primary field of specialty among traditionalists, who professed knowledge not only about the authority of ḥadīth content but also about those who narrated it. This exclusive exercise, which had grown to govern a variety of topics, including interpreting the law, Qur'anic exegesis, and narrating an authoritative

33 M. Hinds, 'Miḥna', *ELI*, vol. VII, pp. 2–6.

version of early Islamic history (the *sīra* and biographies of the Companions), gave the ‘*ulama*’ a religious authority that surpassed that of the caliph. The *miḥna* sought to change this by applying scrutiny to the content of selected examples of religious commentary: the createdness creed; the controversy over the attributes of God (the issue of *tashbīḥ*, anthropomorphism); the beatific vision; and stories about Final Judgement. The ensuing debates quickly showed that these issues needed *ḥadīth* to be interpreted in the way the ‘*ulama*’ demanded, and it was in this sphere that al Ma’mun probably perceived the conflict to be truly happening. By forcing the ‘*ulama*’ to abide by a new official policy, the caliph was making state approval (and the logical system that the Mu‘tazila demanded) – and not the books of *ḥadīth* – the source of final authority. Had he succeeded in enforcing the case of the ‘createdness creed’, al Ma’mun would have been on his way to creating a formal religious hierarchy tied to the court that would have been instrumental in centralising the process of legal and theological interpretation in the empire.³⁴

In some sense this was not the first attempt by the ‘Abbasid state to centralise religious authority. As early as the reign of al Maṣṣūr, the palace counsellor Ibn al Muqaffa‘ had advised of the need for the caliph to codify a law for the empire that would eliminate provincial variations in religious custom and interpretative practices.³⁵ At the time (during the 750s) the concept of Medinan and Prophetic *sunna* was just beginning to gain popularity as an authoritative source of law alongside the Qur’an. Al Maṣṣūr’s times, however, were still secure enough for the caliphate to maintain its religious authority on the basis of its connection to the Prophet’s family. It was not until al Ma’mun’s time that a caliph would attempt to define the system of religious authority in a new way. That he sought to achieve it on a philosophical ground only partly explains his failure to dominate prevailing currents of popular piety. More importantly perhaps, al Ma’mun’s religious programme came too late. For, during the time he was in Khurasan, a process of systematisation of legal and doctrinal principles had already been pioneered by Muḥammad ibn Idrīs al Shafī‘ī (d. 204/819) in his famous *Risala*, which established a synthesis between the two main currents of religious interpretation: the ‘*ḥadīth* folk’ (*ahl al ḥadīth*), who followed Prophetic sayings and established Medinan customs as precedents; and the group that favoured rationalist interpretation (*ahl al ra’y*). This synthesis was to bridge different

34 John Nawas, ‘A reexamination of three current explanations for al Ma’mun’s introduction of the *miḥna*’, *IJMES*, 26 (1994).

35 A. Lambton, *State and government in medieval Islam: An introduction to Islamic political theory* (Oxford, 1981), pp. 53–4.

regional religious cultures as well, since the *ḥadīth* method was predominant in the Hijaz, while the rationalist approach was predominant in Iraq. Shafīʿī's contributions were of a wide ranging scope, and he had essentially invented the science of Islamic jurisprudence (*fiqh*). His achievement strengthened the concept of *sunna* by associating it with *ḥadīth* sayings, universalised the legal authority of Medinan *sunna* to the exclusion of other customs attributed to the Companions in the provinces, and toned down the range of rationalist interpretation to something that needed to be grounded in the texts of the Qur'an and the *ḥadīth* rather than drawing on other interpretations and customs. *Ra'y* therefore became more a matter of *qiyas* and *ijtihad* (interpretation through analogy and a limited degree of interpretation) that is grounded on a set basis of religious texts, rather than being a free exercise of rationalism and the incorporation of provincial customs that pre dated the advent of Islam. And in the event of a remaining controversy among religious scholars on addressing a certain case, al Shafīʿī established the principle of *ijma'*, a kind of collective agreement in the community on interpreting outstanding issues, and this ultimately meant a scholarly circle of *ḥadīth* and *fiqh* scholars.³⁶ With a system in place that favoured the *ḥadīth* text to the degree of giving it a near infallible authority, it was no wonder that al Ma'mun would face overwhelming opposition.

Thus al Ma'mun's programme of imposing the Mu'tazilī interpretation was doomed to be unsuccessful. For about eight years various kinds of pressure were applied by al Ma'mun and his successors, al Mu'tasim and al Wathiq, particularly in the western provinces of Iraq, Syria and Egypt, to make the 'ulama' abide by the 'createdness creed'. Scholars who refused to follow the official doctrine were not allowed to serve in an official capacity as judges, prayer leaders or teachers; nor was their word in court testimony considered bona fide. In Egypt there are stories about some scholars being prevented from praying in the main mosque because they were in the opposition group.³⁷ The creed of the 'created Qur'an' itself was given great publicity when al Ma'mun commanded that it be included in inscriptions at the entrances of some mosques.

In the end, however, the campaign not only failed, but also had a negative effect on the image of the caliphate as a source of religious authority and increased the popularity of *ḥadīth* scholars. It was not so much the arguments

36 N. J. Coulson, *A history of Islamic law* (Edinburgh, 1964), pp. 53–60.

37 Abu 'Umar Muḥammad ibn Yusuf al Kindī, *Kitab al wulat wa'l quḍat*, ed. R. Guest (Leiden and London, 1912), p. 446.

of the ‘*ulama*’ that won them support as their principled stance against political authority and their seeming devotion to simple belief.³⁸ Aḥmad ibn Ḥanbal (d. 241/855), whose name later became a lightning rod for traditionalist Islamic movements, became famous primarily as one of the few scholars who held out against the *miḥna* till the very end. When the caliph al Mutawakkil finally decided to lift the *miḥna* in 233/848, the *ḥadīth* group emerged as a stronger and more cohesive network that commanded not just scholastic allegiance across the provinces, but the loyalty of a Baghdad commune as well. The Ḥanbalīs (named after Ibn Ḥanbal) became the spearhead of *jama‘ī sunnī* Islam, resistant to mixing philosophy with religion, wary of the esoteric path of Sufism and hostile to Shī‘ite Islam and to People of the Book. By the third quarter of the ninth century *ḥadīth* became more rigid than it had ever been, codified in canonical texts, and its authority was matched only in importance by the reputations of its narrators.

Al Ma’mun’s reign can easily be misperceived as a time of decline in the fortunes of Islam, in light of the *miḥna* and the rise in provincial decentralisation in Khurasan. In reality, however, his reign marks a watershed moment of growth in the social history of Islam, as it was a time of acceleration in the pace of conversion to Islam.³⁹ An entire period of religious rebellions in Khurasan and Transoxania, which had been unknown in the Umayyad period but had littered the landscape of the early ‘Abbasid period, came to an end with al Ma’mun’s rise to power. The caliph’s Persian identity, his long residence in Marw, his reliance on Khurasan’s local elites and his eventual tolerance for the autonomy of these groups were all factors that increasingly made Islam appear less the political emblem of outside conquerors and more the new domestic cultural identity. The Sahlids, Ṭahirids, Samanids, Mazyar of Ṭabaristan and Afshīn of Ushrusana were all groups and leaders who either converted to Islam in al Ma’mun’s reign or brokered the dissemination of the traditional tenets of the faith while serving as governors. The effect of this was to make Islam the defining culture for political change and social mobility to a much greater extent than had been the case in the Umayyad or early ‘Abbasid periods. In time this development represented a prelude to the emergence of autonomous provincial dynasties in the east, which would relate to the caliphal centre in nominal terms of loyalty only.

38 Michael Cooperson, *Classical Arabic biography: The heirs of the Prophet in the age of al Ma’mun* (Cambridge, 2000), p. 40.

39 Richard Bulliet, *Conversion to Islam in the medieval period: An essay in quantitative history* (Cambridge, MA, 1979), p. 47.

The caliphate at Samarra'

Soon after al Ma'mun's death al Mu'taṣim seized control of the caliphate, called a halt to the invasion of Asia Minor, and returned to Baghdad. With the accession of al Mu'taṣim there began a clear and decisive shift in the political and military foundations of the empire towards a new regime that was militaristic and centred on the Turkish corps. Whereas al Ma'mun had created a coalition of Arab, Iranian and Turkic Transoxanian troops that balanced one another, al Mu'taṣim relied almost exclusively on the newly recruited Turkish troops. The exact nature of his military power base is difficult to know precisely, and has been the subject of debate. Some of the new commanders who became his chief lieutenants were probably of aristocratic Transoxanian or Central Asian background, such as Afshīn, prince of Ushrusana, Khaqan 'Urtuj and al 'Abbas ibn Bukhara Khuda, who brought with them their personal military retinues (*chakars*). In these situations the loyalty of these troops to the caliph was mediated through a princely figure for some time before it became direct to the caliph.⁴⁰ The majority in the rank and file of the new army, however, were slave troops who were dispatched from beyond the Oxus river by the Samanid governor to al Mu'taṣim.⁴¹ Little is known about these latter recruits, who are collectively labelled 'Turks', a term that referred to diverse people in a wide region stretching from the Khazar domain in the Caucasus to the Central Asian steppes. Be that as it may, al Mu'taṣim's Samarran troops were both ethnically and linguistically and probably for some time religiously different from the mainstream of the Perso Arab society of the empire, which created the first paradigm of a political rift between a ruling elite and Islamic society.

It was not long before al Mu'taṣim realised both the need for new quarters for his fledgling army and the problems the latter had in mixing with the Baghdad population. After considering places in the suburbs of Baghdad as locations for a new military encampment, he finally decided to reach further out. At a distance of some 60 miles north of Baghdad, and with enough good portents from astrologers and soothsayers, he decided to build his new capital of Samarra' in a lightly settled area, mostly steppe land, on the eastern bank of the Tigris. The name of the capital probably derived from a more ancient toponym (*Souma* in Greek, *Sumere* in Latin), but soon a clever play on words in

40 C. I. Beckwith, 'Aspects of the early history of the Central Asian guard corps in Islam', *Archivum Eurasiae Medii Aevi*, 4 (1984), p. 39.

41 Matthew Gordon, *The breaking of a thousand swords: A history of the Turkish military community of Samarra' (AH 200 275/815 889 CE)* (Albany, 2001), p. 8.

Arabic established its more widely famous name: *Surra man Ra'a* ('he who sees it is pleased').⁴² For the next fifty years the new city not only became the centre of the empire, but also witnessed a rapid and astonishingly ambitious wave of construction. Samarra' served not only the practical purpose of providing lodging for al Mu'taṣim's army, but, just as importantly, it enhanced the prestige of the 'Abbasid dynasty. The ruling authority was now set at a distance from the populace of Baghdad and protected by a new guard of foreign troops, and amid a new royal culture revolving around sprawling palatial grounds, public spectacle and a seemingly ceaseless quest for leisurely indulgence. The relationship between Samarra' and the metropolis of Baghdad, as Oleg Grabar has noted, became like that between Versailles and Paris during the seventeenth and eighteenth centuries.⁴³ Different caliphs competed in building their own palaces. Al Mu'taṣim's al Jawsaq, al Wathiq's Harunī and al Mutawakkil's al 'Arus provide a few such examples – as does the occasional palace for an heir apparent, such as the palace of Bulkawara built for al Mu'tazz. Eventually al Mutawakkil, still unsatisfied, went on to build his own city, al Ja'fariyya (also known as *Madīnat al Mutawakkiliyya*) to the north of Samarra'.

Unlike in Baghdad, where the city began with the Round City and then developed around this nucleus, Samarra' was laid out on a vertical plan along the east bank of the Tigris, which allowed more spacious development in a mostly grid street design. The key features of the new town included the separation of residential areas from the markets and the organisation of its military residents in a series of large cantonments. Under the ordinances of al Mu'taṣim these military personnel were not encouraged to mix with the local population. In addition, each community had its exclusive neighbourhood (the Turks, the Faraghina, the Shakiriyya and the Maghariba), while more established commanders such as Afshīn, Ashnas and Khaqan 'Urṭuj had their own *qaṭa'i'* (large estates) and mansions. The city's grand mosque, built by al Mutawakkil between 848 and 852, probably as a statement of his orthodox piety after the lifting of the *miḥna*, remains to this day something of a legend as the largest mosque in the Islamic world, with its massive dimensions (240 × 156 m), bastioned walls, and famous spiral minaret (the *malwiya*), reminiscent of ancient ziggurats at Babylon. The minaret rises to a height of 60 metres, and has thus far defied explanations of function. Samarra' quickly came to influence provincial

⁴² Alastair Northedge, 'Samarra', *El2*, vol. VIII, pp. 1039–41.

⁴³ Oleg Grabar, *The formation of Islamic art* (New Haven, 1973), p. 166.

styles in architecture (the Mosque of Ibn Ṭulun in Egypt, for example, shows a similar design), and set a new artistic style and sensibility. A famous decorative pattern emerged in Samarra' that favoured naturalistic representation, albeit in abstract terms (the so called 'bevelled' style), which appeared in stucco building panels as well as in wooden doors, and glass design. This predominant pattern, however, did not entirely overshadow pictorial representation, which remained evident in interior palace murals.

In Samarra' the greatest emphasis was placed on its palaces, which represented a distinct break in style from the famous Umayyad summer palaces. Here, al Mu'taṣim's palace of al Jawsaq (also known as Dar al Khilafa) set the standard for the new designs and later Samarran architecture. Whereas the Umayyad palaces tended to have a clear linear axis of courtly progression, along with adjoining apartments (at Mshatta and even Ukhayḍir), al Jawsaq shows more complexity with its sprawling clusters of courts, gardens, public and private assembly rooms, and tunnels. The overall design showed a strong concern with security as much as an aesthetic that valued mystery. Outside, al Jawsaq's palace grounds, covering an area of 71 hectares, boasted a range of space types, including review stands, hunting reserves, a polo maydan and various pools.⁴⁴ The caliphs were increasingly kept at a distance from the public, and the caliph's public appearances became carefully staged events. Whether it was al Mutawakkil's trip to the mosque on a holiday festival or the event of announcing the designation of his three sons (al Muntaṣir, al Mu'tazz and al Mu'ayyad) for succession in 236/850, the court went to great effort and expense to mount a parade spectacle that went on for miles.⁴⁵

In spite of their focus on Samarra', the concerns of the first three caliphs who built the city were very different. Al Mu'taṣim was a military personality, whereas his son al Wathiq was more concerned with literary matters, and seems to have been little interested in government.⁴⁶ Al Mu'taṣim tried to invest greater authority in the office of the chief judge, most notably Aḥmad ibn Abī Du'ad, in place of the vizierate, while al Mutawakkil tried to consolidate more power with himself and dealt directly with the military. Perhaps

44 A. Northedge, 'The palaces of the 'Abbasids at Samarra', in C. F. Robinson (ed.), *A medieval Islamic city reconsidered: A multidisciplinary approach to Samarra*, Oxford Studies in Islamic Art 14 (Oxford, 2001).

45 Muḥammad ibn 'Alī ibn al 'Imrānī, *al Inba' fī ta'rīkh al khulafā'*, ed. Q. al Samarra'i (Leiden, 1973), pp. 117–18.

46 *Kitab al aghani* preserves many anecdotes related to al Wathiq and his interests in poetry and song: Abu'l Faraj al Iṣfahānī, *Kitab al aghani*, ed. A. Muhanna, 27 vols. (Beirut, 1992), vol. IX, pp. 315–35.

the most important difference, however, was the reversal in caliphal religious policy that al Mutawakkil introduced when he abandoned the pro Mu'tazila programme and the *miḥna*, and instead began backing the Ḥanbalī and *ḥadīth* scholars as the propagators of orthodoxy. This was a crucial turning point in Islamic history, since it signalled the triumph of Sunnī ideology and its ability from that time onwards to shape not only orthodox religious doctrine but the whole narrative of the Islamic past in a way that legitimised the primacy of the *jama'a*. And part of the fallout of the new policy had polemical dimensions as well, as boundaries were now drawn more rigidly between Sunnīs and Shī'a, Muslims and non Muslims (Christians and Jews), and some restrictions were placed on the latter to stress the supremacy of Islam. These restrictions were probably projected on the past as the 'ordinances of the caliph 'Umar' during that time.

Al Mutawakkil inherited a caliphate that was greatly strengthened by the military triumphs of al Mu'taṣim and the sustained loyalty of the new military system. This allowed his reign to be characterised by stability and prosperity. With the exception of a revolt in Armenia in 236/850, there is little evidence of regional disaffection. All political and financial power was consolidated at the centre in Samarra', in the army, its officers and a class of palace ministers. Al Mutawakkil tried to scale back the influence of these groups by sacking their main leaders, Itakh in the army and Ibn al Zayyat, the chief minister; but the limits on the caliph's ability to form new and independent policies did not radically change. This became evident in 244/858, when the caliph's attempt to shift the capital to Damascus was strongly resisted by the Turkish corps and had to be abandoned. Al Mutawakkil's possible expectation that his orthodox religious policy would garner popular social and military support for the caliphate and counter the influence of the Turks did not materialise either, leaving him still reliant on the Turkish military.

The critical factor that ultimately undermined al Mutawakkil's caliphate, however, was probably financial, and related to his extravagant lifestyle. It is not difficult to establish an image of al Mutawakkil's personality from anecdotal literature and the vast archaeological remains of Samarra'. He appears to have been anxious to leave a significant legacy in 'Abbasid history, which led him to try to outdo the achievements of his predecessors (especially al Rashīd, al Ma'mun and al Mu'taṣim). This he set out to do in a palace building spree, through extravagant festivals for commemorative events, and with the construction of the new city of al Ja'fariyya, where he built his most magnificent palace, Qaṣr al Ja'farī. Several medieval sources give a lengthy list of the palaces that al Mutawakkil built, sometimes providing the cost of each in an

effort to highlight their exorbitant cost and perhaps to signal a reason for the eventual decline of the 'Abbasid government after him.⁴⁷

Less than a year after he moved into the new city of al Ja'fariyya, al Mutawakkil was assassinated by a clique of palace commanders working in league with al Mutawakkil's eldest son, al Muntaṣir, who apparently feared that his father was about to shift the succession to his other son, al Mu'tazz. After a reign of nearly two decades, this was a momentous event. Up until then the idea of military intervention in politics had been successfully suppressed (with the downfall of al 'Abbas ibn al Ma'mun, Afshīn and Itakh, all suspected of seeking to foment such conspiracies). With al Muntaṣir the plan had finally succeeded, and it set in place the paradigm of palace coups for later Turkish commanders. Al Muntaṣir himself died suddenly only six months after his accession. He was succeeded by several short lived caliphs (al Musta'in, al Mu'tazz and al Muhtadī), who were installed and deposed through the domination of one faction of Turkish commanders or another. Caliphal authority underwent a dramatic collapse during this period, and with it came a general decline in the fortunes of Samarra' (and the total abandonment of al Ja'fariyya) until the capital eventually was moved back to Baghdad in 279/892. Modern historians, following the the opinion of medieval chroniclers, are prone to blame al Mutawakkil for the decline of the caliphate at Samarra'. The famous remark that 'what al Ma'mun, al Mu'taṣim and al Wathiq had accumulated [in wealth], al Mutawakkil spent completely'⁴⁸ finds support in the amounts he spent building palaces.

But the reasons for the decline of the 'Abbasid caliphate at Samarra' are not exclusively al Mutawakkil's policies. They also have to do with the choice of Samarra' as a new capital, as well as the policy of reliance on the Turkish troops. From its very beginning Samarra' was an artificial city, where life revolved more around palatial construction and imperial display than its urban population or commerce. Unlike Baghdad, Samarra' lacked the necessary resources for cohesive growth or steady communication. The built up area was entirely on the east bank, where the land was arid, fresh water scarce and its canals were few and flawed in their original levelling and construction. Whatever resources existed were channelled primarily to the palace and, with its regimented military and social divisions, the city could not have been an inviting place for commerce. Samarra' could only survive as long as the caliphs

47 Yaqut, *Mu'jam al buldan*, vol. III, p. 175.

48 Abu Maṣṣur 'Abd al Malik ibn Muḥammad Tha'alibī, *Laṭa'if al ma'arif*, ed. P. de Jong (Leiden, 1867), p. 71.

poured wealth into its upkeep, which reached a point of culmination with al Mutawakkil's excessive palace building.⁴⁹

The relationship between the Turkish military and the court had also undergone some important changes. In al Mu'taṣim's reign the loyalty of the leading commanders, such as Ashnas, Bugha and Itakh, to the caliph was strong because they had been dependent on the success of his faction, and probably because of their own rivalries with the Transoxanian leaders, such as Afshīn. In al Mutawakkil's reign, however, a generational turn must have occurred that brought in younger, more ambitious generals who felt little obligation to the caliphal office. The radical switch in caliphal religious policy probably played a role in shaping this change as well. Al Mutawakkil's lifting of the *miḥna* and abidance by the *ḥadīth* and *jama'ī sunnī* principles of the traditional 'ulama' constituted an admission that the caliph derived his legitimacy from defending *ḥadīth* principles and was no longer himself the anchor of religious and political authority, as had been the case in al Ma'mun's time. In this new environment the roads of Islamic legitimacy had diversified, reaching to any credible authority figure (the Ṭahirids, the Samanids or the Turks), so long as such a group kept *sunnī* and *ḥadīth* interests paramount. After al Mutawakkil the locus of political power in the Islamic empire shifted decisively to the provinces, even though the economic and cultural fortunes of Baghdad continued to ascend.

The twilight of the high caliphate after the end of al Mutawakkil's reign invites a comparison with the earlier conditions of the Umayyad empire. As early as the ninth century Muslims began comparing the two dynasties, such as when the famous essayist al Jahīz (d. 255/869) remarked that the main difference was that whereas the Umayyad state was Arab, the 'Abbasid state was Iranian and Khurasanī ('*ajamiyya khurasaniyya*').⁵⁰ While this juxtaposition is valid for the period after al Ma'mun's caliphate, the situation during the period before (132–98/750–813) is more complex. It may be true that the early 'Abbasids surrounded themselves with Persian courtly culture and bureaucratic arrangements, but they also, as noted earlier, invested heavily in coopting Arab tribal support and used Syria (al Raqqa) as much as Baghdad as their base for government and military preparation. Indeed, it was their continuous attempt to reconcile the Arab tribal armies (of the central lands) with the Khurasanī troops (the emigre Arabs of Khurasan and non Arabs) that

49 J. M. Rogers, 'Samarra: A study in medieval town planning', in A. Hourani and S. M. Stern (eds.), *The Islamic city: A colloquium* (Oxford, 1970), pp. 140–2, 152–4.

50 'Amr ibn Bahr al Jahīz, *al Bayan wa'l tabyīn*, ed. A. H. Harun, 4 vols. (Cairo, 1960), vol. III, p. 366.

eventually resulted in tensions. The system could work only through a combination of religious/ideological propaganda and under a leadership of proven skill, such as al Maṣṣūr, or charisma, such as al Rashīd. In the absence of a uniting force the 'Abbasid armies were prone to division and conflict, as occurred in al Amīn's reign.

A more glaring difference between the two empires, however, was territorial, and was reflected in the rapid loss of 'Abbasid control over Spain and North Africa and the cessation of the tide of conquest on virtually every front (and with this, one should add, ended any further mention of tribal tensions between Qaysiyya and Yamaniyya). With the exception of al Ma'mun's attempt to revive full scale campaigns against the Byzantines, official 'Abbasid wars were generally fought out of necessity, either to deter and impress or to protect a vital interest. Al Mu'taṣim's spectacular campaign against 'Ammuriya in 223/838 is an example of the former, while al Mutawakkil's expedition against a tribal grouping called al Beja in Nubia in 241/855 illustrates a retaliatory measure after this group attacked the gold and mineral mines in southern Egypt. The 'Abbasids never built up a significant navy, nor did they attempt to take Constantinople. They seem to have had a sense of territorial or civilisational self sufficiency in their control over the central lands, and a belief in Islamic fulfilment with the establishment of their rule as the Hashimite caliphs. All of their efforts were devoted to consolidating control over the existing empire, which eventually they accomplished through a variety of arrangements.

Still, for all their chiliastic pretensions and political confidence, the early 'Abbasids faced a continuous trend of populist, religious rebellions from 750 onwards, and in this lies a major difference with the Umayyad experience. In Umayyad times political challenges were often counter claims to the caliphate or more commonly mutinies over taxation, which targeted the Umayyads in the provinces as much as it did their regional allies, such as the *dihqans* in Khurasan. Rebellions against the 'Abbasids, however, were often modelled after the *da'wa* of the revolution. They were little concerned with economic issues, but were rather centred around a compelling religious belief, either in a revivalist prophecy or imamate or in an imminent redemptive moment. The syncretistic rebellions in Khurasan during 136–60/754–75 were examples of this philosophy, and these were eventually brought under control when the caliphate stood as the defender of Islamic orthodoxy and in alliance with the Iranian aristocracy (the Barmakids). However, in North Africa the 'Abbasid cause proved more vulnerable, and soon lost ground there for good. There it was the Kharijites who made inroads among the local Berber tribes and

succeeded in creating a rival imamate. From their remote bases in Tahert and Sijilmasa the Kharijites launched attacks that battered the isolated 'Abbasid garrison city of Qayrawan starting in 141/758. The caliphate was, with difficulty, able for a time to regain the initiative, such as during the successful governorship of Yazīd ibn Ḥatim al Muhallabī, who arrived in 154/771 with a massive army of 60,000 troops. But the province suffered from additional problems which had to do with the restive situation within the provincial army of Qayrawan over issues of pay and promotion. Eventually, the problems of security and managing the province were solved when the 'Abbasids finally conceded provincial authority to an experienced, permanently resident local governor, Ibrahīm ibn al Aghlab, who established the hereditary governorship of the Aghlabids in Tunisia starting in 184/800.

The Kharijites were not the only competitors for the 'Abbasids in the west. Spain had already drifted from the authority of the caliphate in 138/756 when an adventurous member of the Umayyad family, 'Abd al Raḥman ibn Mu'awiya ibn Hisham (r. 138–72/756–88), escaped the dynasty's downfall in Syria and succeeded in establishing an Umayyad emirate in Spain with Cordoba as its capital. 'Abd al Raḥman's rule had to contend for some time with various challenges, including a pro 'Abbasid attempted coup encouraged by al Manṣur, a resistance movement from the local governor, Yusuf al Fihri, who led a Qaysī tribal coalition against 'Abd al Raḥman in 141/748, and a challenge from Charlemagne to control the northern cities of Saragossa and Barcelona in 162/778. Eventually the Umayyad emirate of Spain stabilised as a hereditary dynasty, and although its *amīrs* did not assume the title 'caliph' (which would happen in the early tenth century), they were able to cultivate a strong image of their rule as orthodox Sunnī leaders who were defending the western Islamic frontier. The legitimacy of their authority was strengthened further when they adopted the Malikī school of law during the reign of Hisham ibn 'Abd al Raḥman (r. 172–80/788–96), which allowed them to connect with the most popular current of Sunnī Islam at the time. Although they remained politically hostile to the 'Abbasids for some time, the Umayyads kept up an avid interest in cultural and intellectual developments in Baghdad, and succeeded in attracting talented luminaries from the east. This happened particularly during the reign of 'Abd al Raḥman II (206–38/822–52), who presided over what can be termed the first golden age of Islamic Spain.

Another, more politically challenging, rival to 'Abbasid authority was Idrīs ibn 'Abd Allah, a prominent Hashimite descendant, who arrived in the western extremity of the Maghrib in 173/788. After an odyssey of escape from the Hijaz following the failed 'Alid rebellion in Mecca in 171/786, Idrīs represented

the quintessential 'Alid victim of 'Abbasid persecution, and quickly succeeded in rallying the sympathy and support of the largest Berber confederation of the Walila in Morocco, who saw in him both a patron saint and a political leader for their autonomous aspirations. The rise of the Idrīsīd dynasty, which became the first 'Alid state in Islamic history, represented the counter image to al Ma'mun's organisation of a Khurasanī movement during the civil war with Baghdad. Both leaders, Idrīs and al Ma'mun, provided examples of a Hashimite leadership with important religious pretensions that attached itself to a movement of regional particularism. The long standing restiveness of the Berbers against central caliphal rule came to an end, as in Khurasan, after the establishment of a local religious and political leadership.

As the 'Abbasid state turned increasingly to a decentralised system of government in the ninth century, the North African principalities, which included the Idrīsids (r. 188 305/804 917), the Rustamids (r. 161 296/778 909) and the Aghlabids (r. 184 296/800 909), blended well with the picture of the semi autonomous eastern governorates of the Ṭahirids (r. 206 59/821 73) and Samanids (r. 204 389/819 999) in the east, the Ziyadids in the Yemen (r. 202 371/817 981) and the Ṭulunids (r. 253 93/868 906) in Egypt. Although these states emerged in different contexts and varied in their degrees of autonomy, they all inherited key patterns of the caliphal government in the mid ninth century and (with the exception of the Kharijite Rustamids) adopted its orthodox ideology. Provincial cities, such as Bukhara, Nishapur, Fustāṭ, Qayrawan and Fez grew into important centres of religious learning and commerce, and the provincial states sometimes projected an Islamic assertiveness, such as in the conquests of the Aghlabids, that had previously been a key prerogative of the caliphate. In this environment, the caliphate in Baghdad increasingly became mainly a cultural symbol for Islamic society, rather than being a politically dominant institution as it had been in the seventh and eighth centuries. In spite of all the political upheavals that it endured, however, Baghdad remained the pre eminent city in the Islamic world, favoured as it was by its ideal location, commercial importance and historical memory as the last capital of the great caliphs.

The waning of empire, 861–945

MICHAEL BONNER

The assassination of al-Mutawakkil

On a winter night in Samarra' in 247/861, the caliph Ja'far al Mutawakkil held a carousing session with some companions and courtiers. The caliph had a fondness for wine, as well as for the foolery of clowns and other entertainments,¹ and we are told that on this occasion, after openly insulting his son and heir apparent, al Muntaşir, he proceeded to drink himself into a stupor. By this time al Muntaşir had already made his way out of the door, but the courtiers and servants who remained in the caliph's presence were reluctant to leave. However, the Turkish commander Bugha the Younger ordered most of them to go since, he said, the caliph's womenfolk were within hearing distance. Soon afterwards al Mutawakkil was awakened, as a band of armed men took up positions before him. He asked who these were, and Bugha replied that they were merely the night guard. But now the band, led by Bugha himself, rushed with drawn swords against the caliph and his confidant, al Fath ibn Khaqan. Al Fath threw himself over the caliph in a desperate attempt to defend him and then, after receiving a fatal wound, cried out 'Death!' (*al mawt*). The others dispersed as the assassins hacked the caliph into pieces. The *bay'a*, or oath of accession, was offered that same night to al Muntaşir, who accepted immediately. Al Muntaşir's involvement in the plot seemed even more certain when he put out the patent lie that it had been al Fath who had killed his father and that he, al Muntaşir, had then ordered the killing of al Fath.

¹ Julia Bray, 'Samarra in ninth century Arabic letters', in Chase F. Robinson (ed.), *A medieval Islamic city reconsidered: An interdisciplinary approach to Samarra*, Oxford Studies in Islamic Art 14 (Oxford, 2001), p. 24.

This dark scene² marked a low point for the 'Abbasid caliphate. Since the days of the Rashidun (632–61) several caliphs had been deposed³ and a few had met violent deaths, but only after civil wars or other open conflicts.⁴ Al Mutawakkil's assassination was all the more shocking for having been carried out by men of servile origin: as one court poet put it, 'The Commander of the Faithful has been killed by his slaves, / Slaves, who are always the bane of kings.'⁵ Finally, and most terribly, we have the implication of al Muntaṣir in the plot, indicated in most versions of the story that we have.⁶

The Islamic world in 861 still had a palpable sense of its own unity, which it projected squarely onto the figure of its caliph. But now, literally overnight, the humiliation or murder of a caliph became thinkable, and before long it would be unremarkable. And as the ruler proved vulnerable and fragile, so too did the empire. In 861 the 'Abbasids still controlled most of Iraq, Syria, the Byzantine frontier district in Anatolia (the Thughur), Egypt, Arabia and Iran, even if they had to share some of their authority with local dynastic rulers such as the Ṭahirids and Dulafids. But over the next several years, as internal struggles raged at the empire's heart, the provinces were largely left to fend for themselves, in a variety of ways that this chapter will seek to chart. Meanwhile, the loss of control over the provinces aggravated the crisis at the centre. As a result, a number of transformations now became visible. These included changes in the ownership and taxation of agricultural lands, in the role of the military in the administration and government, and in several other areas. Thus when a new generation of caliphs, commanders and administrators began, only a decade later, to assemble a reformed 'Abbasid caliphate, this enterprise stood on a different basis from the old 'classical' caliphate of Harun al Rashīd and the

2 The version described here is found in Abu Ja'far Muḥammad ibn Jarīr al Ṭabarī, *Ta'rikh al rusul wa'l muluk*, ed. M. J. de Goeje *et al.*, 15 vols. in 3 series (Leiden, 1879–1901), series III, pp. 1471–84; see also vol. XXXIV, trans. Joel L. Kraemer as *Incipient decline* (Albany, 1989), pp. 170–84.

3 Franz Christoph Muth, "'Entsetzte" Kalifen, Depositionsverfahren im mittelalterlichen Islam', *Der Islam*, 75 (1998).

4 Including the 'Abbasid revolution and the fourth *fitna* or civil war between al Amīn and al Ma'mun. Suspicions about al Ḥadī's death in 170/786 may have had some basis but were never proved: see Michael Bonner, 'al Khalīfa al Marḍī: The accession of Harun al Rashīd', *JAOS*, 109, 1 (1988); and Richard Kimber, 'The succession to the caliph Musa al Ḥadī', *JAOS*, 121, 3 (2001).

5 'Alī ibn al Jahm, quoted by 'Izz al Dīn ibn al Athīr, *al Kamil fī l ta'rikh*, 11 vols. (Beirut, 1418/1998), vol. VI, p. 140. Contempt for the 'slaves' is underlined by the verb in the feminine plural.

6 Samer Ali, 'Praise for murder? Two odes by al Buḥturī surrounding an 'Abbasid patricide', in Beatrice Gruendler and Louise Marlow (eds.), *Writers and rulers* (Wiesbaden, 2004).

Barmakids. Now many people would look back with nostalgia to that lost era, regarding it as a golden age of unity and prosperity.

For these and other reasons, political disenchantment prevailed in many places. We may detect some of this in our historical sources, which change markedly during the eight decades covered in this chapter. The unitary caliphate of the Rashidun, Umayyads and earlier ‘Abbasids received its greatest memorial in the *History* of al Ṭabarī (d. 310/923), who settled in Baghdad around nine years after the death of al Mutawakkil. As he looked back over nearly three centuries of the history of the caliphate, this office, even in its most difficult moments, still inspired respect and awe, evoked in the phrase *hadha l amr*, ‘this [caliphal] authority’. As al Ṭabarī left off and other historians took up the story after him, the caliphate remained an important fact; now, however, the phrase *hadha l amr* could connote political ambition and instrumentality, at times verging on cynicism.⁷

By the end of this chapter we shall find that some people remained loyal to the ‘Abbasid caliphate, even though they understood that its authority was symbolic or even fictitious. Others sought new sources of charismatic authority, in ways that the following pages will attempt to chart. At the same time, values were now projected and interests advanced through networks of associations and groups, and through the leadership that these networks generated. The practices of negotiation were never far away and, one way or another, the old unity was gone. A new, more complex, world was emerging, a world whose contours were still not quite clear.

If these were the lessons of al Mutawakkil’s murder, they were not yet apparent. What was clear was that during his lifetime al Mutawakkil had pursued dangerous policies. By reversing the *miḥna* he had renounced the prerogative of caliphs to pronounce on matters of right belief. By instituting measures against Shī‘a, Christians and Jews he had risked alienating large groups. One reason for these moves may have been a desire to cultivate new constituencies, such as the budding Ḥanbalī movement in Baghdad. However, the caliph’s isolation in Samarra’ made such constituencies unreachable. For despite Samarra’s building boom, its population still did not approach Baghdad’s. And while Samarra’ attracted soldiers, courtiers, poets, craftsmen and builders, for men of religious learning it remained merely a passing destination.⁸

⁷ E.g. ‘Arīb ibn Sa’d al Katib al Qurṭubī, *Ṣīlat ta’rīkh al Ṭabarī* (Leiden, 1897), pp. 20–1.

⁸ Samarra’ has no biographical literature of its own: Bray, ‘Samarra in ninth century Arabic literature’, p. 22.

Al Mutawakkil brought down several powerful figures, including the administrator Ibn al Zayyat, the *qaḍī* Ibn Abī Duʿad and the commander Itakh. The men who took their places did not lack ability, but some of them lacked clear places in the hierarchy. The crucial post of *ḥajib* (chamberlain) was typically held by several men simultaneously.⁹ Of all the caliph's courtiers, the one closest to him was al Faṭḥ ibn Khaqan, who apparently held no formal position at all. Al Mutawakkil went further than most of his predecessors in this matter of having his highest officials answer to him personally and almost informally. In the matter of lavish spending he may have outdone all his predecessors, with his mind numbing expenditures on palaces, gardens, ceremonies, and gifts to poets and other courtiers.¹⁰

We may also detect a gambler's instinct in al Mutawakkil's handling of the succession to himself. Early in his reign he set up three of his sons, al Muntaṣir, al Muʿtazz and al Muʿayyad, as successors to one another, in a manner reminiscent of Harun al Rashīd's arrangement in 803. As in that earlier instance, the politics of succession intermeshed with other matters, chief among which was al Mutawakkil's desire to get free of the Turkish officers who surrounded him. In this he proceeded imprudently, without establishing an alternative base of support, which, as we have seen, was just about unachievable in any case. Only three years before his death al Mutawakkil had to renounce his plan for establishing his capital at Damascus.¹¹ He then returned to Samarra' and built himself yet another costly palace. Meanwhile, we are told that he sought to remove al Muntaṣir from the position of heir apparent and to elevate al Muʿtazz, who thus became associated with an 'anti Turkish' policy. Despite all this manoeuvring, al Mutawakkil remained isolated and vulnerable, as everyone learned on that dismal winter night.

Samarra' and civil war

At the outset of this chapter on the waning of empire we may affirm that we are, in fact, dealing with an empire. Imperial structures in the western Mediterranean had collapsed long before, and while they survived in the eastern Mediterranean and Near East, it was a colossal task to maintain

⁹ Matthew Gordon, *The breaking of a thousand swords: A history of the Turkish military of Samarra (AH 200 275/815 889 CE)* (Albany, 2001), pp. 79–80.

¹⁰ Ibid., p. 88; Chase F. Robinson, introduction to Chase F. Robinson (ed.), *A medieval city reconsidered: An interdisciplinary approach to Samarra*, Oxford Studies in Islamic Art 14 (Oxford, 2001), pp. 10–12; chapter 7 above.

¹¹ Paul Cobb, 'al Mutawakkil's Damascus: A new 'Abbasid capital?', *JNES*, 58 (1999).

them. The caliphate inherited this task from its Byzantine and Sasanian predecessors. At the same time, however, the Islamic caliphate went in new directions in the matter of religion, and also in the recruitment and organisation of its armies. Eventually it took quite a new path when it established its capital in Samarra'. This militarisation of the empire's centre resulted in the dominance of a military elite and the isolation of the ruler. Al Mutawakkil tried to reverse all this; the result was the plot against him. After his death came a decade long crisis, which we often call 'the anarchy of Samarra'. Here the structures of empire were shaken so severely that afterwards they only recovered in part, and then not for very long.

The Turkish rank and file soldiers were, in their origins, slaves from the eastern steppes, whereas their commanders were generally free men of aristocratic or royal lineage. There were also units of free soldiers from the Islamic west (Maghariba) and Central Asia (Faraghina). This was the situation when Samarra' was first built, and it remained broadly so during the next decades.¹² Relations between commanders and rank and file were thus far from easy. The commanders, moreover, did not constitute a unified group among themselves. However, the most powerful figures among them provided at least passive support for the conspiracy against al Mutawakkil. The *wazīr* 'Ubayd Allah ibn Yahya ibn Khaqan (not related to al Fath) immediately organised resistance against the conspirators. This meant supporting al Mu'tazz, next in line to the succession after al Muntasir. 'Ubayd Allah gathered many soldiers (by some reports, as many as 20,000), but the attempt fizzled. Backing al Muntasir was the chamberlain Waṣīf, who had provided tacit support for the plot against al Mutawakkil, and who now emerged as the leader of the ruling elite within the palace.

Al Muntasir's caliphate lasted only six months, during which he completed his parricidal work by razing his father's palace.¹³ Al Muntasir tried to establish his footing in an increasingly slippery Samarra', now dominated by the Turkish commanders, especially Waṣīf, and by the new *wazīr*, Ibn al Khaṣīb. Al Muntasir's brothers al Mu'tazz and al Mu'ayyad were compelled to abdicate their places as heirs. Meanwhile Waṣīf fell foul of Ibn al Khaṣīb and was sent off to the Byzantine frontier. Then, when al Muntasir died under suspicious circumstances, the most powerful commanders selected a new

¹² See chapter 7 above.

¹³ Al Ṭabarī, *Ta'riḥ*, series III, p. 1439, and vol. XXXIV, trans. Kraemer as *Incipient decline*, p. 156; Julie Scott Meisami, 'The palace complex as emblem: Some Samarran *qasidas*', in Chase F. Robinson (ed.), *A medieval Islamic city reconsidered: An interdisciplinary approach to Samarra* (Oxford, 2001), p. 69.

caliph, Abu 'l 'Abbas, a grandson of al Mu'taṣim, who took the regnal title al Musta'in. This time, however, conflict broke out and led gradually to a war, sometimes known as the fifth *fitna*, which took up all of 251 (865–6) and culminated in a siege of the city of Baghdad.

This conflict had several parties. The ruling elite of Turkish officers included Waṣīf, Utamish, Bugha the Younger and Bugha the Elder, who, when he died in 248/862, was replaced by his son, Musa ibn Bugha. These men consolidated their position by ridding themselves of the *wazīr* Ibn al Khaṣīb. However, there was rivalry among them, while their relations with their own soldiers and lower ranking officers were far from harmonious. For in the caliphate's declining fiscal circumstances,¹⁴ it was becoming impossible to keep these men paid and equipped. Any new caliph and anyone who wished to manipulate the caliph and the government would have to deliver arrears of pay, as well as the special grants or donatives that the soldiers expected on the occasion of a new reign. As resources grew scarcer the soldiers felt increasing resentment against their own commanders. Their fears were exacerbated by the hostility of the civilian population. This hostility now emerged in the Turks' home base of Samarra', but it remained, as before, most intense in Baghdad. It was accordingly in Baghdad that Muḥammad ibn 'Abd Allah ibn Ṭahir, commander of the *shurṭa*, or security forces in the city, led the fight against the Samarran Turkish ruling elite.

As civil war loomed, and then broke out in earnest in 251/865, al Musta'in transferred to the old capital of Baghdad, where he allied himself with Waṣīf, Bugha the Younger and the Ṭahirid Ibn 'Abd Allah. The opposing commanders, who remained in Samarra', reclaimed their supremacy by proclaiming al Mu'tazz as caliph. Al Mutawakkil, at the end of his life, had favoured al Mu'tazz over al Muntaṣir as part of his anti Turkish policy. However, the fight that now erupted was not a contest of Turks against non Turks: al Mu'tazz's partisans included both Turks and Maghariba (men from the western Islamic world), and the situation was much the same for al Musta'in's side in Baghdad. But al Musta'in made a fatal error when he spoke in public about his lower ranking Turkish officers as 'uncouth foreigners' (*qawm 'ajam*) and sent these off to Samarra' where, not surprisingly, they went over to the

¹⁴ Abu l Qasim 'Ubaydallah ibn Khurradadhbih, *al Masalik wal mamalik* (Leiden, 1889), pp. 8–14, reports budget figures for the Sawad of Iraq during the time of al Mutawakkil and just following. The yearly revenue here is 94 million *dirhams*, a loss of 18.5 million since the budget for 204/819 (reign of al Ma'mun), reported by Qudama ibn Ja'far, *Kitab al kharaj wa shina'at al kitaba*, ed. M. H. al Zubaydi (Baghdad, 1981), pp. 162–7; cf. D. Waines, 'The third century internal crisis of the 'Abbasids', *JESHO*, 20 (1977), p. 286.

other side. The struggle acquired yet more of an ethnic character as ragtag irregulars (*ṣaʿalīk*) took part in the fighting in Baghdad, seeking Turkish heads, for which Ibn ʿAbd Allāh had promised to pay bounty. All this recalled the siege of Baghdad of a half century earlier, as did the devastation wrought on the city and the land around it. Waṣīf and Bugha, cut off from their sources of wealth and authority in Samarraʾ, yielded leadership in the fight to Ibn ʿAbd Allāh who had, in turn, to confront angry crowds shouting ‘Hunger!’ before his palace. In the end, the Samarran leadership held and al Mustafīn abdicated in favour of al Muʿtazz. Shortly afterwards a young officer named Aḥmad ibn Ṭulun conveyed al Mustafīn to Wasīṭ, conspicuously showing him honour and politeness. Some days later the deposed caliph was found dead.

The four and a half years of al Muʿtazz’s caliphate were consumed by violence and intrigue. Waṣīf and Bugha the Younger were reinstated in Samarraʾ, but Waṣīf was killed in 253/867 by soldiers angry over delays in their pay, while Bugha, after a long, deadly dance with the caliph, finally knelt on the executioner’s mat in 254/868. The new generation of officers who emerged, led by Ṣalīḥ, the son of Waṣīf, and Musa, the son of Bugha the Elder, faced fiscal collapse. To meet the army’s demands for its pay, Ṣalīḥ tried to extort large sums from administrators in Iraq, but to no avail. As soldiers marched on the palace, Ṣalīḥ and his fellow officers directed their wrath against al Muʿtazz, who was tortured and killed.

During the brief reign of al Muhtadī (255–6/869–70), in al Ṭabarī’s words, ‘the entire Islamic realm was engulfed in civil strife’.¹⁵ Ṣalīḥ ibn Waṣīf held as much effective control as there was, until Musa ibn Bugha arrived in Samarraʾ, sent out search parties for Ṣalīḥ, found him and put him to death. Musa also came into conflict with al Muhtadī, who insisted on recovering some of the dignity of his office. The quarrel turned into an armed confrontation, which the caliph naturally lost; and so al Muhtadī became the latest in the series of caliphs killed by mobs of angry soldiers. Meanwhile, however, negotiations had begun between the caliph and the rank and file of the army, apparently circumventing the high commanders. An opportunity now presented itself for the assertion of caliphal authority, and this time the ‘Abbasid house proved equal to the challenge. The accession of al Muʿtamid in 257/870 marked an end to the nightmare of the ‘the anarchy of Samarraʾ’.

In their negotiations with al Muhtadī in 256/869f. the soldiers are reported to have demanded that their Turkish commanders be replaced by the caliph’s brothers, and that guilty commanders and officials be punished

15 Al Ṭabarī, *Taʾrīkh*, series III, p. 1739; Gordon, *The breaking of a thousand swords*, p. 101.

for looting the treasury.¹⁶ The call for restoration of the tried and true order extended also to tax revenues, as the soldiers demanded the abolition of abuses that had damaged the *kharaj* lands and estates (*ḍiyaʿ*), ‘as a result of the awarding of concessions (*iqṭaʿat*) to their officers’.¹⁷ This may be the first evidence that we have for the new type of *iqṭaʿ* that would later become widespread in Iraq under Buyid rule, and eventually throughout the Islamic world. The evidence is sketchy, but here we can perceive crisis and change in both the land regime and the army.

The *kharaj* or land tax was the staple element of the fiscal system of early Islam, both in theory and practice. In the later Umayyad and early ‘Abbasid periods it was assessed and levied according to a centralised model, with taxpayers dealing directly with the fiscal agents of the state. This system must have proved unwieldy, for the fiscal authorities resorted to contracts of tax farming (*ḍaman*) at least from the early ninth century onward.¹⁸ In the course of the century other, related, arrangements became widespread, including *muqāṭaʿa*, the contracting out of a rural district (that owed *kharaj*) to an individual in return for payment to the treasury of a specified sum; and *īghar*, fiscal immunity, amounting to much the same thing.¹⁹ At the same time, ever since the arrival of Islam there had been lands classified as estates (*ḍiyaʿ*), which did not owe the heavy *kharaj*, but only the lighter tithe or ‘*ushr*. Caliphs often made grants of such estates to their entourages and family members. This, according to the late ninth century writer al Yaʿqubī, is how Samarraʾ was first built: al Muʿtaṣim distributed grants (*qaṭaʿ*’i, sing. *qaṭiʿa*) to his commanders and ordered them to build up the city and its environs, applying their names and patronage to the new urban quarters and rural districts.²⁰

From al Ṭabarī’s report of the negotiations between al Muṭadī and the soldiers in 256/870, we see that high ranking officers were benefiting from the revenues of estates (*ḍiyaʿ*) and *kharaj* lands. Again, modern scholars have looked here for the beginnings of the new *iqṭaʿ*, but this is looking ahead to the end of

16 Al Ṭabarī, *Taʾrīkh*, series III, p. 1824; Gordon, *The breaking of a thousand swords*, p. 104.

The demand for ‘Abbasid commanders may be related to the subsequent rise of Abu Aḥmad al Muwaffaq; see Gordon, *The breaking of a thousand swords*, p. 142.

17 Al Ṭabarī, *Taʾrīkh*, series III, pp. 1798–9; Gordon, *The breaking of a thousand swords*, pp. 125–7.

18 M. Brett, ‘The way of the peasant’, *BSOAS*, 47, 1 (1984), pp. 49–50, referring to Egypt but broadly applicable to Iraq as well.

19 C. Cahen, ‘L’évolution de l’*iqṭaʿ* du IXe au XIIIe siècle: Contribution à une histoire comparée des sociétés médiévales’, in C. Cahen, *Les peuples musulmans dans l’histoire médiévale* (Damascus, 1977).

20 Aḥmad ibn Abī Yaʿqub ibn Waḍiḥ al Yaʿqubī, *Kitab al buldan* (Leiden, 1892), pp. 256–64.

this chapter and beyond.²¹ The point to keep in mind here is that revenues coming not only from estate lands, but now also from *kharaj* lands, were being directed towards the high ranking officers, and away from the control of the fiscal agents of the 'Abbasid caliphate. One result was a deterioration of the caliphate's cash flow, especially since the rank and file soldiers still depended upon the central treasury for their pay. Another result was change in the countryside itself. Here the fate of individual landowners is difficult to follow: no doubt there were cases of outright expropriation, but more often we detect small landholders seeking to lighten their burden of taxes (or rents) by taking refuge (*ilja'*) with powerful individuals who then consolidated these properties with what they already held. The result, of course, was the disappearance of the weak and the enhancement of the strong.

Together with this turmoil on the land came what we may call the privatisation and factionalisation of the army, trends that had been perceptible at least since the foundation of Samarra'. Even if the commanders grew rich from their holdings, in the end they had to rely on the support of soldiers who were, as we have seen, prone to anger and alienation. The 'decade of anarchy' in Samarra' was not a case of domination by a group of men united in solidarity by their Turkish ethnicity, military function and non free status over free civilians and soldiers. It was rather a series of manoeuvres by desperate individuals looking for leaders whom they could safely follow, or followers whom they could safely lead.

Periphery and centre

With Samarra' and Baghdad absorbed by inner conflict in the 860s and trying to recover from it during the following decades, most of the empire fell apart. We are best able to perceive this process when it takes the form of the emergence of new dynastic states on the periphery. These were remembered afterwards as the wilful expression of military men who carved out territories for themselves and their descendants within the physical and moral space of the 'Abbasid caliphate. At the same time, several of these successor states were also built out of the principles and practices of warfare against the enemies of Islam, which is to say, the *jihad*. In other words, these were frontier societies, negotiating new Islamic identities for individuals and groups.

21 Gordon, *The breaking of a thousand swords*, pp. 118–24. Cahen, 'L'évolution de l'*iqta'*', pp. 236–8, argued that the new *iqta'* did not derive from the estates, but rather from the *muqata'a* and *ighar* arrangements imposed on lands that owed *kharaj*: see below, p. 353.

We may well ask whether the inhabitants of these provinces really wished to renegotiate their relations with the caliphate. In general, however, relief from 'Abbasid fiscal pressure was welcome, and in some places a measure of local identity began to emerge. These were, after all, the years in which Islam became the majority religion in most places,²² which meant that a local or provincial identity, expressed in Islamic (or even religiously neutral) terms, no longer had to pose a threat to the governing authorities. So while the Samarran crisis of 861–70 precipitated the expression of these local identities, they would doubtless have emerged sooner or later.

When al Mu'tamid, a son of al Mutawakkil, succeeded to the caliphate in 256/870, he was compelled to make a special place for his brother Abu Aḥmad, who received a regnal title of his own, al Muwaffaq. Abu Aḥmad, like his grandfather al Mu'taṣim, was a military man through and through. Having acted as chief commander for al Mu'tazz's side during the civil war of 865, he enjoyed the respect of the soldiers. And so, after a chaotic decade during which Turkish commanders had intrigued against one another and deposed or killed at least four caliphs, the solution arose of putting the army under the command of an 'Abbasid prince with a general's résumé. In the event, al Muwaffaq's decisive leadership was to save the 'Abbasid caliphate from destruction on more than one occasion. Not surprisingly, however, al Mu'tamid chafed at this arrangement.

Under these circumstances it became clear that the ties between periphery and centre were severely frayed. Nothing illustrates this so well as the vicissitudes of the Ṭahirid dynasty. Now well into their third generation of high office, the Ṭahirids remained firmly rooted in their native Khurasan, where the leading member of their family held the office of governor or *amīr*. At the same time, ever since the days of Ṭahir ibn al Ḥusayn (d. 822) the Ṭahirids had governed in conjunction with the 'Abbasids. In Baghdad the crucial job of *ṣaḥīb al shurṭa* (chief of the security force) was theirs by hereditary right. They also held other positions, in addition to estate properties in Iraq and elsewhere. Their relations with the caliphs were not easy: the transfer of the capital to Samarra' had never suited them, and may have been made, in part, to diminish their importance. Nonetheless, the Ṭahirids maintained their position securely in Khurasan and Baghdad, astride the great route known now as the Silk Route, enjoying the support of the Khurasanian landholding classes. In the eyes of modern historians, even

22 R. Bulliet, *Conversion to Islam in the medieval period: An essay in quantitative history* (Cambridge, MA, 1979).

though the Ṭahirids come first in the well known sequence of ninth and tenth century ‘eastern dynasties’, they appear different from the dynastic rulers who come after them in Iran: ‘not a separate dynasty, but merely the hereditary governors of Khurasan, always as servants of the commander of the faithful in Baghdad’, their true fame resting ‘in their cultural patronage’, especially of Arabic letters.²³

It may be useful to think of the Ṭahirid phenomenon as a remnant of the centripetal politics of the Umayyad and early ‘Abbasid periods, from a time when provincial ambition, especially in the all important frontier province of Khurasan, looked obsessively to the centre of the Islamic world. The Ṭahirids loyally held the eastern frontiers against external enemies. However, it was not this activity that defined them as much as their stable place within the political system of the caliphate and their embodiment of the aristocratic cultural values expressed, in Arabic, at the ‘Abbasid court in Samarra’ and the Ṭahirid court in Nishapur.²⁴

With Samarra’ in deep crisis, a centrifugal pattern set in that, as much as anything else, comes near to defining this entire period of Islamic history. Now we find ambitious military commanders (most often social upstarts) establishing themselves in the provinces through forcible conquest, and through peaceful alliance with local elites. In their relations with the caliphal government, these new men were mostly content with formal recognition of their status as provincial *amīrs*. Only one of them, in the third/ninth century, made a serious attempt against the heart of the ‘Abbasid empire (see following paragraphs). This change from a centripetal to a centrifugal pattern²⁵ became visible rather suddenly, in the east, with the rapid decline of the Ṭahirids. (The west is a different story, to be discussed below.) Thus Muḥammad ibn ‘Abd Allah ibn Ṭahir’s defeat in Baghdad in 865 (see above) was followed in 873 by the ousting of his brother Ṭahir ibn ‘Abd Allah from the governorship of Khurasan, at the hands of Ya‘qub ibn al Layth al Ṣaffār (‘the Coppersmith’ in Arabic, from which comes the name of the dynasty he founded, the Ṣaffarids). Now visibly out of date, the Ṭahirid enterprise was reduced, though not yet swept aside.

This Ya‘qub ibn al Layth, a charismatic soldier of humble origins, had emerged as the major power in the eastern Islamic world during the decade

23 Richard N. Frye, *The golden age of Persia: The Arabs in the east* (London, 1975), pp. 191–2.

24 C. E. Bosworth, ‘The Ṭahirids and Arabic culture’, *JSS*, 14 (1969); see chapter 7 above.

25 This distinction was stated in a conference paper by Michael Cook in 1984. See now Patricia Crone, *God’s rule: Government and Islam* (New York, 2004), esp. pp. 36–9.

of strife in Samarra'. His home was the eastern Iranian province of Sistan (Sijistan), a marginal region which had never come under the firm control of the caliphate. But now Sistan was destined to enjoy the limelight for a while, for three main reasons. The first of these was its position as a frontier province, connecting to the mountains of present day Afghanistan and the fringes of India. The second reason was Sistan's internal condition. For generations it had harboured Kharijite rebels who had, under Ḥamza ibn Ādharak (d. 213/828), controlled much of it. The Ṭahirid governors did not seriously try to control the countryside, but limited themselves to the large towns of Bust and Zaranj. But there too central authority suffered, as bands of local urban roughnecks ('*ayyarun*') set out to fight the Kharijites.

The third reason for Sistan's sudden fame was Ya'qub's rare combination of ability and ambition. Ya'qub and his brothers joined the '*ayyarun*' in Bust, fighting hard and rising quickly. In 247/861, the year of al Mutawakkil's murder, Ya'qub gained control over Zaranj and, in the next four years, over all of Sistan. He then turned eastward to lead armies against the frontier regions of Zabulistan, Kabul and Badhghīs, acquiring plunder and prestige. During these operations many Kharijites joined his side, an early sign of the waning of Kharijism. After opening hostilities against the Ṭahirids in Herat, Ya'qub began to look westward. In the early 870s he invaded Kirman and Fars, receiving reluctant acknowledgement as governor from the caliph al Mu'tamid. In 259/873 he turned north, invaded Khurasan and seized Nishapur, thus toppling the Ṭahirids, as we have seen. Now al Mu'tamid declared that Ya'qub had gone too far. In 262/876 Ya'qub replied by marching into Iraq, but there, near Dayr al 'Āqul, some 50 miles from Baghdad, an 'Abbasid army defeated him, to everyone's surprise. Ya'qub with drew, retaining control over most of Iran, but three years later he died and was succeeded by his brother 'Amr.

The brilliant, though uneven, career of the Coppersmith has provoked much interest. Two questions emerge in particular. First, what did Ya'qub have in mind when he assaulted the 'Abbasid caliphate at its seat? (Though still based in Samarra', the caliphate was already repositioning itself to Baghdad.) Perhaps this question has no answer, other than Ya'qub's fury against the 'Abbasids and their rejection of his claim. It was generally understood during this era that a provincial governor would indicate his loyalty to the caliphate through two symbolically loaded acts: by including the caliph's name on coins struck in the provincial mint (*al sikka*); and by making an invocation in the caliph's name during the sermon (*al khuṭba*) pronounced on the occasion of the Friday prayer. Now Ya'qub did try to secede from caliphal rule in some way. However, he remained within these limits of *sikka* and *khuṭba*: even

during his campaign against the ‘Abbasids he proposed no alternative to the caliphate, and may have intended merely to replace al Mu‘tamid with another ‘Abbasid prince.²⁶ He rejected overtures from the most important rebels in southern Iraq at the time, the Zanj (see below). Above all, his rebellion carried no religious message – Kharijite, Shī‘ite, Zoroastrian or anything else.

The second question regards the reasons for Ya‘qub’s success. These included a superb military organisation,²⁷ and also an appeal to Iranian group feeling or, more precisely, to memories of the traditions of Persian kingship.²⁸ Ya‘qub was notorious for his ignorance of Arabic, as well as his rough manners and lowly birth. But what is the meaning of his rise to prominence as a leader of ‘*ayyarun* in Bust and Zaranj? These groups were utterly local in character: something more was necessary if they were to become the vehicle for the formation of a new state and regional power. Deborah Tor has argued that Ya‘qub, and the Ṣaffarid dynasty as a whole, lived and breathed for one purpose only, which was performance of holy war against infidels and heretics. If so, then the bands of ‘*ayyarun* were actually *mutaṭawwi‘a* (volunteers) and *ghazīs* (warriors for the faith). By remaining true to the ascetic ideals of these *ghazī* bands, Ya‘qub and his successor ‘Amr would have won justification for their wars of conquest.²⁹ In particular, they won the support of religious learned groups in the cities in this way,³⁰ although here the evidence remains slim. This view of Ya‘qub and ‘Amr as frontier fighters for the faith provides welcome relief from the views that have often prevailed of them, as well as of other *amīrs* of the ‘eastern dynasties’, as either overambitious soldiers of fortune, or else as Iranian patriots and nationalists *avant la lettre*. On the other hand, it may be too much to ascribe the entire Ṣaffarid enterprise to a single motivating principle of holy war.³¹ Be that as it may, we can see in the rise and expansion of the

26 Deborah G. Tor, ‘A numismatic history of the first Ṣaffarid dynasty (AH 247–300/AD 861–911)’, *Numismatic Chronicle*, 162 (2002) p. 298; C. E. Bosworth, *The history of the Ṣaffarids of Sistan and the Maliks of Nimruz (247/861 to 949/1542)* (Costa Mesa and New York, 1994), pp. 153, 156–7.

27 C. E. Bosworth, ‘The armies of the Ṣaffarids’, *BSOAS*, 31 (1968); Bosworth, *History of the Ṣaffarids*, pp. 341–57.

28 Samuel Miklos Stern, ‘Ya‘qub the Coppersmith and Persian national sentiment’, in C. E. Bosworth (ed.), *Iran and Islam, in memory of Vladimir Minorsky* (Edinburgh, 1971); Bosworth, *History of the Ṣaffarids*, pp. 160–80.

29 At least until 287/900, when ‘Amr went soft and ‘betrayed his original ‘*ayyar* ideals of *ghazw* and ascetic zeal’, as a result of which his army handed him over to the Samanids, who sent him on to Baghdad for execution: Tor, ‘A numismatic history’, p. 309.

30 *Ibid.*, pp. 304–5.

31 As was done by Paul Wittek, *The rise of the Ottoman empire* (London, 1938). By advancing *jihad* or, in Wittek’s case, *ghaza* as an explanatory principle or cause, we risk falling into a circular argument, just as when we advance Islam itself.

Šaffarids a drama of state formation, with stage and backdrop provided by the eastern frontier. Unlike the Kharijites, they did not accuse other Muslims of unbelief, but rather sought to expand the territory of Islam, as they gathered legitimacy and strength along the eastern frontier.

Centrifugal forces had become noticeable earlier on in the other, western, end of the Islamic world, where the caliphal authorities had yielded to them much sooner. This was especially true of al Andalus, or Islamic Spain, which had precociously dropped out of the 'Abbasid caliphate in the 750s. As the country grew more prosperous, the Umayyad *amīrs* of al Andalus consolidated their position and then, after 852, lost ground to internal opposition and anarchy. Meanwhile, al Andalus lived in a condition of low density warfare against the Christian kingdoms on its northern borders. This meant that it developed as a frontier society, where the performance of *jihad* against external enemies was critical not only for territorial defence and expansion, but also for upholding the legitimacy of rulers, and for articulating the claims to leadership made by various legal and religious authorities.³²

More important in the eyes of the caliphal government was the province of Ifrīqiya, corresponding to modern day Tunisia and parts of Algeria and Libya. Here, since 184/800, the *amīrs* of the Aghlabid dynasty enjoyed substantial autonomy, including the right to transfer the emirate within their bloodline. The Aghlabids showed formal loyalty to the 'Abbasids as they conducted religious quarrels with Kharijites, especially the Berber Ibaḍīs of the Rustamid state which formed the western border of Aghlabid Ifrīqiya.³³ At the same time, the Aghlabids faced internal opposition from the Arab fighters of the *jund* (army), and also from urban men of religious learning, above all those of the Malikī *madhhab* (school of law), which was establishing its dominant position in Muslim North Africa in the course of the century.

In 827 the Aghlabids began the conquest of Byzantine Sicily. This operation, which required three quarters of a century to complete, met with enthusiastic support. Mass participation in the Sicilian campaigns, together with frequent turmoil among the Muslim fighters there, provided the Aghlabids with an escape valve for tensions building up among the soldiers

32 Hugh Kennedy, *Muslim Spain and Portugal: A political history of al Andalus* (London and New York, 1996), pp. 30–62; Cristina de la Puente, 'El Yihad en el califato omeya de al Andalus y su colminación bajo Hišam II', in Fernando Valdés Fernández (ed.), *Almanzor y los terrores del Milenio* (Aguilar de Campoo, 1999).

33 Elizabeth Savage, *A gateway to hell, a gateway to paradise: The North African response to the Arab conquest* (Princeton, 1997).

of the *jund* and the scholars of the Maliki *madhhab*.³⁴ Meanwhile the coasts of Ifrīqiya itself remained exposed to attack. The Aghlabids and their subjects devoted considerable resources to defensive structures, known as *ribaṭs*, where volunteer garrisons could reside. It was, however, in its project of conquest in Sicily that Aghlabid Ifrīqiya revealed its character as yet another provincial frontier society. This was in some ways the last of the early Islamic conquests, performed largely by volunteers fighting for religious reward and the promise of plunder.³⁵ Operations began successfully with the fall of Palermo in 216/831, but were soon bogged down in quarrels that reflected the conflicts of Ifrīqiya itself, between Arabs and Berbers and between the Aghlabid ruling house and its unruly subjects. With the accession of Ibrāhīm II in 261/875, the Muslims had a series of successes, culminating in the fall of Syracuse in 264/878. Otherwise an unpopular ruler, Ibrāhīm found in the *jihad* an activity to his liking, and later he relinquished the emirate and devoted himself to the Sicilian war, achieving the conquest of Taormina in 289/902. This was precisely when the Faṭimid *daʿī* (missionary) Abu ʿAbd Allah al-Shīʿī began to lead his Kutama Berber force against the Aghlabid state from its western edge. It now turned out that the Aghlabids had made a fatal error by concentrating upon Sicily and neglecting their land frontiers.

Egypt, despite its economic and political problems earlier in the ninth century, now enjoyed prosperity, with its borders secure and its commerce increasing in the Red Sea and the Mediterranean.³⁶ However, it still played a subordinate role as provider of foodstuffs and cash. Indeed, as Iraq became beset by economic difficulties, Baghdad and Samarra' depended all the more on the Egyptian revenues that in centuries past had gone to their imperial predecessors (Byzantine Constantinople, Medina under the Rashidun, Umayyad Damascus). Now, however, an Islamic Egyptian voice was emerging, audible in Arabic among scholars such as the Ibn ʿAbd al-Ḥakam family, authors of major works on history and law. And the country was about to acquire, for the first time, a front rank place in the politics of the Islamic world, with the arrival of Aḥmad ibn Ṭulun and the founding of the Ṭulunid dynasty.

³⁴ Michael Brett, *The rise of the Fatimids: The world of the Mediterranean and the Middle East in the fourth century of the hijra, tenth century CE* (Leiden, 2000), p. 80.

³⁵ R. Traini, 'Sikilliyya', *Elz*, vol. IX, pp. 582–9.

³⁶ Thierry Bianquis, 'Autonomous Egypt from Ibn Ṭulun to Kafur, 868–969', in Carl F. Petry (ed.), *The Cambridge history of Egypt*, vol. I: *Islamic Egypt, 640–1517* (Cambridge, 1998), pp. 87–8.

We have already met Aḥmad ibn Ṭulun as he conveyed the deposed caliph al Mustaʿīn to his doom in Wasīṭ at the end of the civil war in 865.³⁷ The freeborn son of a Turkish father, Ibn Ṭulun had grown up in Baghdad and Samarraʾ, and received a literary and religious, as well as a military, education. His youthful experience also included military service on the Arab-Byzantine frontier, where he received instruction from the *ḥadīth* scholars and pious men (*zuhhad*) of Tarsus.³⁸ In 254/868 he was appointed deputy governor of Egypt by his patron Bayakbak (or Bakbak), a member of the ruling elite in Samarraʾ who had been granted control over the province. At this point Ibn Ṭulun was just one of several junior officers under the patronage of high ranking men such as Bayakbak, Ṣāliḥ ibn Waṣīf and Musa ibn Bugha. Indeed, Bayakbak was in competition against Ṣāliḥ, who around this time named Abu ʿl Saj – another capable officer who would soon make a name for himself – as his proxy in northern Syria.³⁹ Ibn Ṭulun arrived in Egypt to find the fiscal administration under the control of Ibn al Mudabbir, a wily bureaucrat with long experience. Four years went by before Ibn Ṭulun succeeded in getting rid of him, during which time he also faced local opposition in several parts of Egypt. But now, with the administration (both military and fiscal) of the entire country finally under his control and with his Samarran patron, Bayakbak, removed from the scene, Ibn Ṭulun found himself in a position of strength and autonomy. He maintained this position in part by timely interventions and gift giving at the caliphal court in Samarraʾ, and in part by building a powerful army of slave soldiers at home in Egypt. In the manner of all rulers of Egypt before and since, Ibn Ṭulun paid special attention to the situation along the country's north eastern border.

We have seen that the caliph al Muʿtamid was compelled to share power with his brother al Muwaffaq, and Ibn Ṭulun now found himself in the midst of the quarrel. He began by favouring al Muʿtamid, sending him the lion's share of the Egyptian tribute in 263/876⁴⁰ and assuming, after 265/878, the title *mawla amīr al muʿminīn* ('client of the commander of the faithful'). Meanwhile al Muʿtamid, like several of his predecessors, divided his realm into two regions, each assigned to a viceregent who was also a prince of the ʿAbbasid house. In 875 he assigned

37 Al Balawī, the author of an encomiastic biography of Ibn Ṭulun, absolves his hero from involvement in the crime: *Ṣīrat Aḥmad ibn Ṭulun* (Damascus, 1939), pp. 40–1.

38 Ibid., pp. 34–5; Bianquis, 'Autonomous Egypt', p. 91; Gordon, *The breaking of a thousand swords*, pp. 99f., 117, 226.

39 Gordon, *The breaking of a thousand swords*, p. 100; al Ṭabarī, *Taʾrīkh*, series III, p. 1697.

40 1.2 million *dinars* to Muwaffaq and 2.2 million to Muʿtamid: Bianquis, 'Autonomous Egypt', p. 95.

the western provinces to his son and heir Ja'far, while the eastern provinces went to al Muwaffaq. However, al Muwaffaq held the real power and did not feel constrained to operate in the eastern provinces only. With al Muwaffaq threatening both Syria and Egypt, Ibn Ṭulun asked al Mu'tamid for the command over the Arab–Byzantine frontier district of the Thughur. He moved against Āmajur, the 'Abbasid governor in Damascus, who then died in 264/877f. As Ibn Ṭulun occupied the great cities of Syria, al Muwaffaq named Musa ibn Bugha governor of Egypt and sent him to Syria; lacking funds, however, Musa's expedition collapsed and he returned to Iraq.

Ibn Ṭulun then marched on Tarsus, chief stronghold of the frontier district of the Thughur. This move had much in common with Ya'qub ibn al Layth's activity, in the 860s, on the eastern frontiers. Ibn Ṭulun already had credentials as a participant in the Byzantine wars, as well as in the learned and pious activities characteristic of Tarsus. However, Ya'qub had built up the Ṣaffarid state by commanding *ghazīs* on the eastern frontiers, whereas the Ṭulunid project of state formation was now already substantially complete. The residents of Tarsus, for their part, felt no desire for an Egyptian occupation. Ibn Ṭulun withdrew, but left his lieutenant Lu'lu' in command in Aleppo. In this way he combined control over Syria, Palestine and some of al Jazīra (northern Mesopotamia), in addition to Egypt, briefly anticipating the later pattern of the Ayyubid and Mamluk sultanates.⁴¹

It was in Egypt that Ibn Ṭulun's achievement was most lasting, as is apparent today to anyone who stands in the courtyard of the great Ibn Ṭulun Mosque in Cairo. This mosque was completed in 266/880 and was soon accompanied by a palace for the *amīr* and residential quarters for the army, called al Qaṭa'i' ('the land grants'). While these buildings announced Egypt's arrival as a military and political power, many things about them, including the Mesopotamian architectural idiom of the mosque, also recalled Samarra'. Just as al Mu'taṣim had done in Samarra' a half century earlier, Ibn Ṭulun now settled his army in al Qaṭa'i', assigning a land grant to each unit. Thenceforth these slave soldiers formed the backbone of Ṭulunid power, and much of Egypt's wealth would be spent on a standing army which, in the year of Ibn Ṭulun's death, included 24,000 Turks and 42,000 black Africans, both slave and free.⁴²

In 269/881 Ibn Ṭulun's deputy in Syria, Lu'lu', was summoned by al Muwaffaq to serve against the Zanj in Iraq (see below). Ibn Ṭulun departed

⁴¹ Ibid., p. 96.

⁴² Ibid., p. 98.

for Syria, where again he found trouble in Tarsus. There the governor, the eunuch Yazman, refused to acknowledge his authority. As Ibn Ṭulun passed through Syria in 882 he received a message from the caliph al Mu'tamid, saying that he had secretly left Samarra' and was on his way to Syria. Ibn Ṭulun waited for al Mu'tamid in Damascus, hoping to escort him to Fustaṭ; in this way Egypt might become the centre of a restored 'Abbasid caliphate, under Ṭulunid protectorate. However, al Muwaffaq's agents got wind of the scheme and a commander loyal to him, Ishaq ibn Kundaj, encountered al Mu'tamid near Ḥaditha, in western Iraq, and forced him to return to Samarra'.

In Damascus Ibn Ṭulun now convened an assembly of religious scholars and judges from all the territories under his control. *Khuṭba* (Friday sermon) after *khuṭba* denounced al Mu'tamid's imprisonment and al Muwaffaq's arrogance. However, there was some disagreement among the judges and scholars, and when Ibn Ṭulun demanded a declaration of *jihad* against al Muwaffaq, the assembly refused to go that far. All the same, the event was the first of its kind, an indication of the ties that Ibn Ṭulun cultivated among the learned classes. Al Muwaffaq replied by having curses against Ibn Ṭulun pronounced from the pulpits of the territories under direct 'Abbasid control.⁴³ Meanwhile, Ibn Ṭulun tried unsuccessfully to dislodge Yazman from Tarsus in 270/883. He fell ill during the campaign and returned to Fustaṭ, where he died in 270/884.

Opposition

For the 'Abbasid leadership these new dynastic enterprises were ultimately manageable. An adroit player of the game such as al Muwaffaq could even use them to his own advantage. During these years, however, new threats arose that can only be described as existential. A series of movements and groups made religious and ideological claims that left no room for the 'Abbasid caliphate and empire. Some of these sought autonomy, resistance and revenge. Others aimed to restore the caliphate, in a reformed and purified version. Questions relating to universal dominion and just rule were debated constantly and passionately. These questions were at once historical, relating to the Islamic past and its interpretations, and theological, relating to God's plan for the world and the community of believers. Our historical sources for these movements and groups are largely absorbed by

43 Al Balawī, *Sīrat Aḥmad ibn Ṭulun*, pp. 298–300; Bianquis, 'Autonomous Egypt', pp. 101–2.

these arguments. Accordingly, the study of what has been called ‘the revolt of Islam’⁴⁴ requires attention to some historiographical problems.

At the beleaguered centre of the Islamic empire, al Mu‘tamid and his brother al Muwaffaq began to share power in 870, as we have seen. Despite the conflict between them, this arrangement worked reasonably well, since it allowed al Muwaffaq to maintain the loyalty of the armies and to meet military challenges. Thus it was al Muwaffaq, together with Musa ibn Bugha, who commanded the force that stopped Ya‘qub the Coppersmith in 876 at Dayr al ‘Āqul. Meanwhile, as the Samarran crisis of the 860s abated and the officers loosened their grip on the caliphal administration, the scribes (*kuttab*) gained in visibility and influence. Al Mu‘tamid began by appointing as his *wazīr* ‘Ubayd Allah ibn Yahya ibn Khaqan, who had held the office at the time of al Mutawakkil’s death. This allowed al Mu‘tamid to maintain some independence; but, after ‘Ubayd Allah’s death in 262/877, al Muwaffaq intervened by appointing men of his own choice as al Mu‘tamid’s *wazīrs*. Al Mu‘tamid’s position grew weaker, and after his failed attempt to escape to Egypt in 882 he found himself under house arrest. Meanwhile, as the administrators became more powerful, the factional divisions among them grew. This bureaucratic factionalism would prove characteristic of the coming decades, as would the chronic lack of money in the treasury.

The great crisis of the era of al Mu‘tamid and al Muwaffaq was the revolt of the Zanj. This Arabic word denotes blacks originating from the East African coast. Large numbers of East African slaves had, in the later first/seventh century, been brought to work in southern Iraq under harsh conditions.⁴⁵ In the third/ninth century we find gangs of Zanj kept in conditions of acute hardship and misery and working in the marshlands (*al baṭa’ih*) of lower Iraq, removing the nitrous topsoil (*sibakh*) to reclaim the land for cultivation. This swampy region was ideally suited to guerrilla warfare, as everyone would soon know. Our information here comes almost exclusively from al Ṭabarī, who does not tell us all we would like to know about the ownership and management of these lands. It appears, in any case, that the owners were concentrated in the nearby city of Baṣra, and that they availed themselves of the provision in Islamic law for ‘reviving dead lands’ (*iḥya’ al mawat*) under fiscally advantageous terms. We know of no other instances of plantation style slavery of this kind in the early Islamic world – as opposed to domestic and military slavery, which were widespread.

44 Bernard Lewis, *The Arabs in history* (London, 1958).

45 Alexandre Popovic, *The revolt of African slaves in Iraq in the 3rd/9th century* (Princeton, 1998), pp. 22–3.

The revolt got under way in 255/869 with the arrival of one 'Alī ibn Muḥammad, whom al Ṭabarī describes as an adventurer and jack of all trades, but who had considerable charisma and leadership skills.⁴⁶ 'Alī's appeal to the Zanj had a markedly Shī'ite character, although it was not until around two years later, after the destruction of Baṣra, that he actually claimed membership, through Zayd ibn 'Alī, in the Prophet's family.⁴⁷ 'Alī ibn Muḥammad promised the Zanj revenge against their oppressors, riches and slaves of their own, and in the next few years he made good on these promises to a remarkable extent. The local and caliphal authorities were unable to defend against the Zanj, who moved swiftly on interior lines, hidden by the swamps. They seized the main cities of lower Iraq and neighbouring Khuzistan, including Baṣra, Wasit, 'Abbadan and Ahwaz. They slaughtered many inhabitants, but did not occupy these cities permanently: all the 'Abbasid forces could do was to enter these ruined centres of early Islamic civilisation and survey the devastation. Meanwhile, 'Alī ibn Muḥammad established himself in al Mukhtara, a fortress town astride several canals to the east of Baṣra, where he minted coins and tried to create alliances with the Ṣaffarids and the Qaramiṭa (see below). The 'Abbasid authorities, led by al Muwaffaq, did not mobilise effectively against the Zanj until 266/879, the year of Ya'qub the Coppersmith's death. But now they moved resolutely, driving the Zanj back into the swamps and canals. Command of the armies was shared between al Muwaffaq and his son Abu 'l 'Abbas, the future caliph al Mu'taḍid. The 'Abbasid forces pressed slowly through the canals, forcing the Zanj to concentrate their forces and to undergo a siege at al Mukhtara. Finally, in 893, when al Mu'taḍid had already succeeded to the caliphate, the Zanj were defeated, their leader killed and his chief companions taken for execution to Baghdad.

If the revolt of the Zanj had begun only a few years earlier, it probably would have brought an end to the 'Abbasid caliphate. As is, it stands out as the greatest slave rebellion in the history of Islam. At the same time, its appeal went beyond the slaves of the swamp region. Its commanders, including 'Alī ibn Muḥammad himself, seem to have been of Arab origin – in any case, not Zanj. The movement's Shī'ite character may seem rather vague, although this may be a result of the hostility of al Ṭabarī and his sources. Of special interest is the fact that Arab nomads or semi nomads (*a'rab*) are described as fighting

46 Al Ṭabarī, *Ta'riḫ*, series III, pp. 1742–6, vol. XXXVI trans. D. Waines as *The revolt of the Zanj*, (Albany, 1992), pp. 30–3; Popovic, *Revolt*, pp. 33–43.

47 Al Ṭabarī, *Ta'riḫ*, series III, p. 1857; vol. XXXVI, trans. Waines as *The revolt of the Zanj*, p. 133.

side by side with the Zanj, especially in the early phase of the rebellion when cities such as Baṣra were targeted and destroyed.⁴⁸

Until this time Kharijism was the form of Islam preferred by many dissidents who inhabited the borderlands between the desert and the sown. In earlier times there had been Kharijites (notably al-Ḍaḥḥāk ibn Qays al-Shaybānī, d. 128/746) who attempted to take over the entire Islamic polity. But in the 'Abbasid period Kharijism was more often the creed of people who wanted nothing to do with the centre of empire except, where convenient, to do it harm. Kharijites sought to establish virtuous polities in fringe provinces, as Ḥamza ibn Ādharak had done in Sīstan (see above).

We have seen that in the later ninth century provinces were falling into the hands of local *amīrs* who desired autonomy from the imperial centre. In doctrinal terms these new rulers tended to remain Sunnī (if it is not too early to use this word), although some of them, notably Ya'qub the Coppersmith, mounted political and cultural resistance against the hegemony of Samarra' and Baghdad. Meanwhile, Shī'ism provided the structure and idiom for a wide and, in many ways, new range of opposition movements. At least in some areas (such as North Africa and northern Syria), where formerly we found Kharijites, we now find more adherents of Isma'īlism and other forms of radical Shī'ism. But though radical Shī'ism now spread widely, it had its beginnings at the heart of the 'Abbasid empire, in the fertile farmland of southern and central Iraq and in the marginal lands – whether desert or marsh – that surrounded it. In this way the revolt of the Zanj was a harbinger of what was to come.

Our literary sources for these Shī'ite movements of the later third/ninth century present difficulties. Many of these sources are heresiographical in character: their purpose is to identify false belief (whether from a Shī'ite, Sunnī or other perspective) and to refute it. The historical chronicles also show sectarian disagreement. Sunnī chronicles, such as the *History* of al-Ṭabarī, often have an anti-Isma'īlī viewpoint. On the other hand, there is also an Isma'īlī historiography which connects these events to the rise of the Faṭimid dynasty, the major manifestation of Isma'īlism in this period. In recent decades a large body of scholarship has emerged regarding these questions of Isma'īlī and Faṭimid origins. Before we discuss this, however, we may quickly review the situation of Shī'ism in the later ninth century.

⁴⁸ Al-Ṭabarī, *Ta'rikh*, series III, pp. 1850–1; vol. XXXVI, trans. Waines as *The revolt of the Zanj*, pp. 127–8.

Most Shī'a agreed that rightful authority – the true imamate and caliphate – belonged, after the Prophet, to a series of imams, beginning with the Prophet's son in law and cousin 'Alī ibn Abī Ṭalib. With the exception of 'Alī himself, who ruled as caliph from 35/656 to 40/661, these imams did not actually command armies and governments on earth. Nonetheless, they held rightful authority, and all the Umayyads and 'Abbasids were mere usurpers. In this view each imam inherited his rank both through ties of blood and through designation by the current imam or his heir.

In the later ninth century the Shī'a of Iraq underwent a crisis of leadership, coinciding with the crisis of the 'Abbasid caliphate – of which, whether they liked it or not, they were subjects. They disagreed over several matters, one of which regarded events over a century old. The sixth in the line of imams had been the highly respected Ja'far al Ṣādiq (d. 148/765). According to some Shī'a, Ja'far had designated as his heir his son Isma'īl who, however, predeceased him; the imamate then went to Ja'far's grandson, Muḥammad the son of Isma'īl. Shī'a of this persuasion became known as Isma'īlīs or Seveners.⁴⁹ Many of them believed that Muḥammad ibn Isma'īl, the last of their imams, had not died but had disappeared into occultation (*ghayba*), from which he would return one day to rule the earth.

Other Shī'a disagreed, claiming that Ja'far al Ṣādiq had been followed in the imamate not by Isma'īl, but by another son, Musa al Kazim. For people of this persuasion the series ended with the death of the eleventh imam, al Ḥasan al 'Askarī, in Samarra' in 260/874, early in the reign of al Mu'tamid. Some of al Ḥasan's followers held further that a son of his, Muḥammad ibn al Ḥasan, was the rightful twelfth imam, even though he had disappeared at around the same time. Agreement on all this was not achieved until some time afterwards, with the consolidation of what we know as Imāmī or Twelver Shī'ism. Shī'a of this persuasion believed (and believe) that the twelfth imam, Muḥammad ibn al Ḥasan the Mahdī, the 'rightly guided', had entered a state of occultation (*ghayba*) from which he will emerge eventually to rule the world. It is important to remember, in any case, that it was during the later ninth century that these doctrines were taking form; and that many Shī'a, and Isma'īlīs in particular, expected that their imam would return from occultation very soon.

Isma'īlīs were not the only political activists during these years. Zaydī Shī'a, concentrated in Kufa and elsewhere, had already been involved in a long series of revolts against the 'Abbasid caliphate, especially in its early decades. Their

49 For the arithmetic leading to seven, see Heinz Halm, *The empire of the Madhi: The rise of the Fatimids*, trans. Michael Bonner (Leiden, 1996), p. 19.

doctrine achieved maturity in the work of the imam al Qasim ibn Ibrāhīm al Rassī (d. 246/860). Now, in the later ninth century, Zaydīs emerged in force in two peripheral areas. In Ṭabaristan, south of the Caspian, a Zaydī state was established in 250/864 by the Ḥasanid al Ḥasan ibn Zayd, followed by his brother Muḥammad. External resistance and internal turmoil overcame this enterprise, but a renewed Zaydī state was established by a Ḥusaynid, al Naṣir ila 'l Ḥaqq (d. 304/917). This Zaydī presence in the southern Caspian provided a constant challenge to the 'Abbasid governors and other rulers of this turbulent region. Meanwhile in Yemen a Zaydī state emerged in 284/897, led by a grandson of al Qasim ibn Ibrāhīm, al Ḥadī ila 'l Ḥaqq, followed by a long line of imams. From their capital in Ṣa'da the Zaydīs achieved a remarkable level of stability, maintaining distance from the politics of the larger Islamic world.⁵⁰

Regarding the rise of Isma'īlism and the Faṭimid caliphate, recent research on the literary sources⁵¹ points to a sequence of events that may be sketched as follows. The doctrine and sect first became visible in the early 870s, in the activity of 'Abd Allah the Elder ('Abd Allah al Akbar) who lived in 'Askar Mukram in Khuzistan. 'Abd Allah preached that Muḥammad ibn Isma'īl was *al mahdī*, 'the truly guided one' and *al qa'im*, 'the one who appears', destined to return and to rule the world; he was also the seventh and last within an Islamic cycle of imams, itself the last within a larger series of cycles. Upon his arrival Muḥammad ibn Isma'īl would reveal the 'true religion', known until then only to small circles of the initiated. This revelation would result in the abolition of Islamic law (*raf' al shar'ī'a*), together with a renewal of the Edenic religion of Adam, without any rites, commandments or prohibitions.⁵² In this way 'Abd Allah the Elder combined Shī'ite principles regarding the imamate with gnostic teachings and secret rites of initiation. (The Neoplatonism that we associate with Isma'īlism did not enter the picture until afterwards.) 'Abd Allah and his family established themselves quietly in Salamiyya (or Salamya) in eastern Syria on the desert's edge. There, acting as chief *da'īs* (callers) for Muḥammad ibn Isma'īl, they sent out other *da'īs* who created a network of communities in northern Iran, the Gulf, Yemen and elsewhere. They scored an early success in the Sawad of Iraq.

50 W. Madelung, 'al Rassī, al Qasim b. Ibrāhīm', *EL*2, vol. VIII, pp. 453–4; W. Madelung, 'Zaydiyya', *EL*2, vol. XI, pp. 477–81 with bibliography; W. Madelung, 'The minor dynasties of northern Iran', in R. N. Frye (ed.), *Cambridge history of Iran*, vol. IV: *The period from the Arab invasion to the Saljuqs*, (Cambridge, 1975).

51 Recent summaries of this approach can be found in Halm, *Empire of the Mahdi*; Paul Walker, 'The Isma'īlī da'wa and the Fatimid caliphate', in Carl F. Petry (ed.), *The Cambridge history of Egypt*, vol. I: *Islamic Egypt, 640–1517* (1998); and Paul Walker, *Exploring an Islamic empire: Fatimid history and its sources* (London and New York, 2002).

52 Halm, *Empire of the Mahdi*, p. 21.

It has already been mentioned that al Ḥusayn al Ahwāzī was sent to the Sawād of Kufa as a *dā'ī* ... Along the way he met a man called Ḥamdān ibn al Ash'ath, who was known as Qarmaṭ, since he was short and had short legs ... [Qarmaṭ] had with him an ox, on which he was carrying goods. Al Ḥusayn asked him, 'Which is the way to Quss Bahram?' 'That's my village,' replied Qarmaṭ ... After they had gone for a while, Ḥamdān said to him, 'I suppose you've had a long journey, since you're exhausted. Come sit on this ox of mine!' Al Ḥusayn replied, 'I have not been instructed to do that.' [Ḥamdān Qarmaṭ's interest is aroused, and al Ḥusayn continues:] 'A sack has been entrusted to me which contains the knowledge of one of God's secrets. I have been instructed to cure the people of this village, to make them rich, to save them, and to take the kingdoms of the world out of the hands of those who now control them, and to place them under their rule.'⁵³

Ḥamdān Qarmaṭ takes the vow 'which God took from his prophets and messengers'. He and his brother in law 'Abdan become zealous partisans of the *mahdī*. The *dā'ī* lives in their village until his death, when Ḥamdān Qarmaṭ takes his place. This Iraqi mission recognises the authority of Salamiyya, where the entire network is directed by a series of descendants of 'Abd Allah the Elder, each bearing the title of *ḥujja*, or 'proof'.

It is rare for medieval Arabic historical writing to carry us so deep into the countryside, riding on the back of an ox. For a while the narrative carries in the village, as the community shares its possessions and contributes to the *mahdī*'s cause. Soon, however, we find 'Abdan preaching to the Bedouin around Kufa.⁵⁴ Within a few years these nomads and semi nomads were threatening the cities of Iraq and Syria, where the 'Abbasid authorities referred to them by the (abusive) term Qarmaṭīs, or Qaramiṭa. However, if the Qaramiṭa were now predominantly Bedouin, their leadership came from the settled lands of the Sawad,⁵⁵ just as the leadership of the Zanj had not come from the Zanj themselves.

Another brilliant success was reserved for the resourceful Abu 'Abd Allah al Shī'ī, originally from Kufa, who was recruited and sent to Egypt and Yemen in 891. While on the pilgrimage Abu 'Abd Allah met a group of Kutama Berbers from what today is north eastern Algeria. Sensing an opportunity, he plied his new acquaintances with questions.

53 Ibid., pp. 28–9, combining several sources that rely ultimately on the anti Isma'īlī polemicist Ibn Rizām. A readily accessible version of the story is in Aḥmad ibn 'Alī al Maqrīzī, *Itti'āz al ḥunafa' bi akhbar al a'imma al faṭimiyyīn al khulafa'* (Cairo, 1967), pp. 151–8.

54 Halm, *Empire of the Mahdi*, pp. 48, 64.

55 Hugh Kennedy, *The Prophet and the age of the caliphates*, 2nd edn (Harlow, 2004), p. 286.

He asked them whether the [Aghlabid] rulers of Ifrīqiya had any governors [in the region where they lived], and they said they did not. There were individual men who ruled alone over the various cities, but these had nothing to do with the rulers, beyond having the prayer said for them in the pulpits ... ‘Then do you owe them obedience?’ ‘Not at all; they rather fawn on those of us who go to them, for we are superior to them in strength.’ Then who rules over you?’ ‘Each of us has power over himself’ ... ‘How large is your country?’ ‘Five days’ journey in length and three in width.’ And are you a single tribe?’ ‘The name Kutāma unites us, but we are divided into tribes, subtribes and clans.’ ‘Then are you unified among yourselves?’ ‘No, we fight one another, and after someone has gained the victory, we join together again’ ... ‘But if a stranger tries to force his way in among you, do you hold together?’ ‘No one has yet tried that.’ ‘And why not?’ ‘Because we are many and our country is impassable.’ ‘How many are you then?’ ‘No one, neither from among us, nor so far as we know from outside, has ever counted us.’ ‘Do you have horses and weapons?’ ‘They are our most important possessions and all our pride; we collect these things because we need them in our fights against one another.’ ... [Abū ‘Abd Allāh] retained everything and got them to report everything he wanted to know. For he had high expectations and hopes in them, whereas they had no inkling of what he wanted ... He was content with everything he heard and thought that with them he would arrive at his goal.⁵⁶

Abu ‘Abd Allah travelled to the Kutama homeland and established himself there. The Kutama admired him for his knowledge of the law and his ascetic way of life, and soon most of them were enthusiastic converts to the cause of Muḥammad ibn Isma‘īl.

In Salamiyya in 899 the leadership of the *da‘wa* or ‘summoning’ devolved upon a descendant of ‘Abd Allah the Elder named Sa‘īd ibn al Ḥusayn. This Sa‘īd now declared that he was not merely the ‘Proof’ and the leader of the *da‘wa*, but the actual imam himself. He claimed to be a direct descendant of Muḥammad ibn Isma‘īl and, through him, of ‘Alī and the Prophet Muḥammad. In this view the imamate would have been passed on continuously within this family, instead of ending with the disappearance of the seventh imam. Sa‘īd’s claim, which was sorely contested on genealogical grounds, roiled the Isma‘īlī movement. Some, including Abu ‘Abd Allah al Shī‘ī in the west, accepted the imamate of Sa‘īd, who now took the name ‘Abd Allah (and thereby became known to his enemies as ‘Ubayd Allah, ‘little

⁵⁶ Halm, *Empire of the Mahdi*, pp. 40–1, quoting Qaḍī Nu‘man, *Ifṭitāḥ al dawla wa btida’ al da‘wa*, ed. F. Dachraoui [Dashrawī] (Tunis, 1975), paragraphs 31 ff.; ed. W. al Qaḍī (Beirut, 1970), pp. 54–8.

‘Abd Allah’), and the title al Mahdī. Others, including the followers of ‘Abdan and Ḥamdan Qarmaṭ in Iraq, rejected it, insisting on the imamate of Muḥammad ibn Isma‘īl. Meanwhile, Sa‘īd/‘Abd Allah escaped to Egypt and from there to North Africa. He did not join Abu ‘Abd Allah and the Kutama, but pushed ahead to the western fringe of the Islamic world in Sijilmasa, where he tried to remain anonymous.

Abu ‘Abd Allah emerged with a Kutama fighting force in 902 and attacked the Aghlabid emirate. We have already seen that the Aghlabids had made a fatal error in committing most of their resources to the war in Sicily, while leaving their western borderlands in the hands of Berber tribesmen and a few Arab warlords in the cities (as the Kutama informed Abu ‘Abd Allah). The enthusiastic Kutama overcame the demoralised Aghlabid force. In 297/909 Abu ‘Abd Allah took the Aghlabid capital, al Raqqada, near Qayrawan, as well as Qayrawan itself. In the same year the Rustamid state also fell victim to Abu ‘Abd Allah and the Kutama, who destroyed their capital, Tahert. As Ziyadat Allah III, the last of the Aghlabid *amīrs*, escaped from Ifrīqiya to Egypt, Abu ‘Abd Allah led a rescue expedition westward to Sijilmasa. When ‘Abd Allah the Mahdī arrived in Ifrīqiya in 297/909f., he formally assumed the imamate and caliphate. Here we have the beginning of what we know as the Faṭimid caliphate of North Africa and (from 358/969 onwards) of Egypt.

Counter caliphs and Shī‘ite rebellions had risen before, but since the ‘Abbasid revolution none of them had come so far. For whatever one thought of his credentials, the Faṭimid *mahdī* ruled over a large part of the Islamic world, at a time when the ‘Abbasid caliphate was ill equipped for the challenge. However, the *da‘wa* network that the *mahdī*’s ancestors had knit together now came unravelled. In Iraq we hear nothing more of Ḥamdan Qarmaṭ,⁵⁷ but, as we have seen, the ‘Abbasid authorities applied the term ‘Qarmaṭī’ to Bedouin movements that threatened them much as the Zanj had done earlier, but now over a wider area. These ‘Qarmaṭīs’ of Syria, Iraq and al Baḥrayn were sworn enemies not only of the ‘Abbasids, but also of the Faṭimid *mahdī*.

In Ifrīqiya, however, the *mahdī* set about establishing a state that broadly resembled its Umayyad and ‘Abbasid predecessors. Again we have an imperial centre deriving the bulk of its revenues from a land tax levied directly upon

57 There is, however, the interesting (and solitary) passage in Ibn Ḥawqal, *Surat al ard* (Leiden, 1938), p. 96, which identifies a Faṭimid supporter and courtier named Abu ‘Alī as none other than Ḥamdan Qarmaṭ. According to Walker, ‘The Isma‘īlī *da‘wa* and the Fatimid caliphate’, pp. 126–7, Abu ‘Alī/Ḥamdan would have been responsible for the conversion of Abu ‘Abd Allah al Shī‘ī and his brother Abu ‘l ‘Abbas in Kufa.

the taxpayers. The bureaucracy resembled its 'Abbasid counterpart, with the lack of a formal office of *wazīr* amounting to an archaic trait. And, like the earliest Islamic state, the Faṭimid enterprise owed its success to a tribal army, the Kutama, who remained eager for further conquest. Before long, however, the Faṭimids brought their state into line with prevailing trends, by resorting to tax farming⁵⁸ and already in the reign of al Mahdī by bringing slave soldiers into their armies. On the other hand, the Faṭimids had a different theory of succession to the imamate.⁵⁹ Their imam was a charismatic figure, surrounded by an ever more complex processional and ceremonial, rising above the religious and social divisions of the Islamic world over which he reigned.⁶⁰

This sketch of Ismaʿīlī and Faṭimid origins is based on the analysis of modern scholars who have used a rich and growing collection of medieval sources. However, it is important to mention other approaches, especially that of Michael Brett.⁶¹ Brett sees ninth century Ismaʿīlism as part of a larger brew of oppositional trends, the 'sectarian milieu' which John Wansbrough described as the religious and doctrinal environment of early Islam.⁶² Thus, when the Faṭimid dynasty came to power in North Africa in 909, and again when it conquered Egypt in 969, its historians and other advocates including the Qaḍī al Nu'mān (d. 975), a brilliant jurist and gifted writer retrospectively cast a view of unity over the entire Ismaʿīlī past. More precisely, these pro-Faṭimid writers presented a story of a united origin followed by sectarian division: those who believed in the imamate of the Faṭimids were the trunk of the Ismaʿīlī tree, the followers of the authentic teaching, whereas the various dissenting groups were branches that had diverged into wrong belief. In Brett's view it is likely that the so called Qarmaṭīs of Iraq and Baḥrayn were not even part of the original Ismaʿīlī movement, but became associated with it later on.⁶³ At the same time, the idea of an unbroken connection between the beginning of Ismaʿīlī doctrine and the foundation of the Faṭimid caliphate also suited the purposes of anti Ismaʿīlī writers who sought, all at once, to

58 Halm, *Empire of the Mahdi*, pp. 358–60.

59 Though not entirely different from the Umayyad doctrine, if we follow Patricia Crone and Martin Hinds, *God's caliph: Religious authority in the first centuries of Islam* (Cambridge, 1986).

60 Brett, *Rise of the Fatimids*, pp. 176–99.

61 Brett, 'The Mīm, the 'Ayn, and the making of Ismaʿīlism', *BSOAS*, 57 (1994), repr. in Michael Brett, *Ibn Khaldun and the medieval Maghrib* (Aldershot, 1999); Brett, *Rise of the Fatimids*, esp. pp. 29–47, 176–218.

62 John Wansbrough, *The sectarian milieu: Content and composition of Islamic salvation history* (Oxford, 1978).

63 Brett, *Rise of the Fatimids*, pp. 46–7.

denounce Ismaʿīlī doctrines as heresy, and to discredit Faṭimid claims to legitimacy as genealogical lies. Accordingly, in Brett's view, the fact that pro and anti Ismaʿīlī sources often agree in their description of events does not constitute proof for the historicity of these events: the two camps, each for its own reasons, embraced a similar (unitary) view of Faṭimid and Ismaʿīlī origins.

Restoration

Before and during this challenge from a vigorous rival, the 'Abbasids, together with their soldiers and administrators, worked hard to rebuild their own caliphate, and for a time they achieved considerable success. Here, in a world of reduced resources and proliferating red tape, technocrats and bureaucrats held the key. Soldiers, though needed at every turn, were mainly content to follow the caliph, a military man like themselves. At the same time, this restored 'Abbasid caliphate imitated some of the practices of its neighbours, especially in the search for legitimisation through performance of *jihad* and through control of the frontiers against the enemies of Islam.

When al Muwaffaq died in 278/891 his son Abu 'l 'Abbas inherited his position as high commander and strongman. In the following year al Mu'tamid died, and Abu 'l 'Abbas pushed aside his cousin, Ja'far ibn al Mu'tamid, to become caliph in his own right, assuming the regnal title al Mu'taḍid. Al Mu'taḍid cut a figure similar to his father's: an energetic military man, respected by the troops. Unlike his father, however, he now enjoyed sole control over the caliphate and, with the defeat of the Zanj in 280/893, a generally improved situation. He achieved a reputation and popularity that went beyond the army, and his reign (279 89/892 902) constituted the high point of what is known as the 'Abbasid restoration'.

This restored caliphate was militarised in a way that the old caliphate of al Manṣur and al Rashīd had not been. This did not mean that the soldiers could simply have their way: the Samarran crisis of the 860s had made everyone averse to such a situation. The bureaucracy, meanwhile, saw a net gain in its power and influence. Al Mu'taḍid's *wazīr*, 'Ubayd Allah ibn Sulayman ibn Wahb, held wide power over both civil administration and military affairs. But in a situation where both caliph and *wazīr* were often preoccupied with military affairs, the leading bureaucrats learned to impose themselves. After all, the army could not live (let alone fight) unless it received its pay from the *diwan al jaysh*, the Bureau of the Army. The caliphate was reduced in territory and could rely on regular income from only a few areas,

apart from the Iraqi heartland of the Sawad. Al Mu‘taḍid set about remedying this situation by bringing the *amīrs* of remote provinces into line and, where possible, by reconquering territory for the caliphate to administer directly. However, these expeditions cost large amounts of money, which the bureaucrats had to exert all their skills to provide.

By this time the ‘Abbasid bureaucracy had achieved a high level of technical proficiency and complexity. It provided the very model for Islamic administration, a model that would be imitated by, among others, the Samanids (see below), who would then transmit these procedures, together with the cultural styles associated with them, to later dynastic states in the east. Employment in the *dīwans* (bureaux) required an array of accomplishments which included, on the humanistic side, mastery of the Arabic language together with poetry, history, calligraphy and many other subjects. On the technical side, scribes needed expertise in arithmetic, accounting and surveying, together with familiarity with the fiscal districts and the procedures governing them; this technical work seems especially daunting because what we now call the ‘Arabic numerals’ were not yet in everyday use. The skills required for the *dīwans* were thus quite demanding, but educational networks, including the practices of apprenticeship within the *dīwans* themselves, produced them in abundance, and there were more than enough qualified scribes available for the jobs.

The *dīwans* became ever more complex, hierarchical and costly. And as they grew larger the fiscal districts grew smaller, to allow the officials to exercise closer oversight. Under al Mu‘taḍid the *dīwans* of all the provinces were united in one central location in Baghdad, the *dīwan al dar*, or Bureau of the Palace. Afterwards these were divided again into the *dīwans* of the west, the east and the Sawad, while the *dīwan al dar* became an accounting or records office for the others.⁶⁴

The reign of al Mu‘taḍid saw a growth of factionalism within this bureaucracy, observable also in the army and in urban civilian life.⁶⁵ A leading role in financial administration was played by two brothers of the Banu al Furat family, Aḥmad and ‘Alī, until 286/899, when their place was taken by the Banu al Jarrah, led by Muḥammad ibn Dawud and his nephew ‘Alī ibn ‘Isa. In the following decades ‘Abbasid administration would be largely dominated by

64 R. Mottahedeh, ‘The ‘Abbasid caliphate in Iran’, in R. N. Frye (ed.), *The Cambridge history of Iran*, vol. IV: *The period from the Arab invasion to the Saljuqs* (Cambridge, 1975), pp. 79–84.

65 R. Mottahedeh, *Loyalty and leadership in an early Islamic society* (Princeton, 1980; repr. 2001), esp. pp. 158–68 (factions).

these two clans, the Furatids and Jarrahids; employees of the bureaucracy had little choice but to establish ties of patronage with one or the other. Thus whenever the man at the top was dismissed, his network would collapse and be replaced by the rival network. The scribes were usually civil and restrained in their dealings with members of the opposing faction, since they knew well that the situation could turn against them at any moment. At times we find them taking indirect action against each other, as in a caliphal decree (issued under al Muqtadir, in 296/909) that Jews and Christians must not be hired for administrative work;⁶⁶ this seems to have been a Furatid measure directed against the Jarrahids, recent converts to Islam whose rank and file still included numbers of unconverted Christians.

However, things could become uncivil and worse during the investigative and confiscatory procedure known as *muṣadara*, in existence since the days of the Umayyads. It was common, whenever a *wazīr* or other high official fell from power, for his successor in the office, with approval of the caliph, to 'encourage' the fallen official to hand over the properties and funds that he had supposedly embezzled during his term of office. The mulcting procedure involved imprisonment and torture, sometimes extended to the victim's family. One result was that a holder of high office had no choice but to stow away large amounts of property and cash, so as to avoid being tortured to death when the moment arrived. At the same time, it was necessary not to give everything away at once, which would lead the investigators to suspect the existence of even more. We may view all this as a routinised combination of embezzlement and extortion: at least since the days of al Ma'mun there had been a *dīwan al muṣadarat*, a 'Bureau of Mulcted Properties'.⁶⁷ Confiscations could also be directed against a wider range of targets, and not only former office holders. It seems, moreover, that the confiscated wealth was turned over to the caliph's 'private' treasury or privy purse, the *bayt mal al khaṣṣa*.⁶⁸ During this period of the restored 'Abbasid caliphate and the precipitate decline that followed it, this caliphal treasury frequently held more money than the 'public treasury', the *bayt mal al 'amma*. Thus, on the accession of al Muqtadir in 295/908, the 'private' treasury held 15 million *dīnars*, the 'public' treasury only 600,000.⁶⁹ The privy purse had its own *dīwans* and a cohort of bureaucrats to administer them, a source of frustration for those who tried to make the entire machine work more efficiently.

66 Sibṭ Ibn al Jawzī, *Mir'at al zaman*, British Museum, OR 4169, vol. 2, 42b.

67 C. E. Bosworth, 'Muṣadara', *EL*, vol. VII, pp. 652–3.

68 A. K. Lambton, 'Ṣaḥī', *EL*, vol. VIII, pp. 798–800.

69 Al Ṭabarī, *Ta'rikh*, series III, p. 228r; 'Arīb, *Ṣīla*, pp. 22–3.

The balance among competing factions of bureaucrats and soldiers was precarious. One thing that held it all together under al Muwaffaq and al Mu'taḍid was the example set by the ruler, especially in his personal involvement in the wars. The role of 'ghazī caliph', invented by Harun al Rashīd⁷⁰ and enhanced by al Mu'tasim, now had its greatest performance, in al Mu'taḍid's tireless campaigning. This allowed him to foster ties of patronage among the army, so that many soldiers proudly called themselves 'al Mu'taḍidī' ('so and so the client or follower of al Mu'taḍid') for their entire lives. Al Mu'taḍid also enjoyed popularity among civilians, which made it easier for him to transfer the capital from Samarra to Baghdad. This move had begun decades earlier, when al Muwaffaq made Baghdad a base of operations against the Zanj. But now al Mu'taḍid established himself in what became Baghdad's centre of gravity, on the east bank of the Tigris downstream from the Round City of al Manṣūr.⁷¹

At the outset of his reign al Mu'taḍid did not control much territory beyond Iraq. His project of restoration would succeed only if he could gain control over the revenues of other provinces. He proceeded accordingly and, where he could not achieve this goal directly, he sought the formal allegiance of the rulers in question. He chose his targets shrewdly, alternating diplomacy with the use of force. His accomplishments now seem all the more remarkable when we consider how unwieldy and expensive the 'Abbasid army and bureaucracy had become.

In Egypt, upon the death of Ibn Ṭulun in 270/884 the emirate had been taken over by his son Khumarawayh. Al Muwaffaq opposed this move and mounted a challenge, which Khumarawayh fended off in 271/885. Khumarawayh managed to extend Ṭulunid power over most of al Jazīra, and he even compelled Yazman, the strongman of Tarsus, to acknowledge him as overlord. In 273/886 al Muwaffaq made peace with Khumarawayh, granting to the Ṭulunid line the right to govern Egypt for the next thirty years. Thus, even though Khumarawayh lacked his father's charisma and energy, he achieved a measure of success. He also seems to have made a good choice by entrusting the country's finances to the Madhara'īs, a family of administrators who would maintain fiscal continuity in Egypt for decades to come, over several changes of regime.

When al Mu'taḍid became caliph he tolerated the Ṭulunid position in Syria, al Jazīra and the Thughur. In 280/893 he made a new accord with Khumarawayh, this one more favourable to the 'Abbasid side. The Ṭulunids

⁷⁰ Michael Bonner, *Aristocratic violence and holy war: Studies in the jihad and the Arab Byzantine frontier* (New Haven, 1996), pp. 99–106.

⁷¹ Kennedy, *The Prophet and the age of the caliphates*, p. 181.

were to pay an annual tribute of 300,000 *dīnars*, with 200,000 *dīnars* of arrears to be provided forthwith. Khumarawayh also agreed to hand over the Jazīran provinces of Diyar Rabī'a and Diyar Muḍar. Al Mu'taḍid was prepared to coexist with the Ṭulunids: this is evident in his marriage to Khumarawayh's daughter Qaṭr al Nada, who brought a record breaking dowry of a million *dīnars*.⁷² However, the young bride did not live long afterwards, nor did her father: Khumarawayh was assassinated in Damascus in 282/896, by his court eunuchs. He was followed by his fourteen year old son Jaysh, who was soon deposed, and then by another son, Harun. With the Ṭulunids disabled, Tarsus and the Arab Byzantine frontier district opted for al Mu'taḍid, who then assumed, after a long hiatus, the old caliphal prerogative of commanding the annual summer expedition and arranging the defence against the Byzantine empire. The crumbling Ṭulunid state then had to face the onslaught of the Qaramiṭa, who defeated the Ṭulunid commander, Ṭughj ibn Juff, near al Raqqa in 289/902, and then besieged Damascus. Now many Ṭulunid officers left to join the more promising enterprise of the 'Abbasids.

Al Mu'taḍid also devoted attention to al Jibal, in west central Iran. Since the days of Harun al Rashīd this had been the home of the Dulafids, descendants of the poet and commander Abu Dulaf (d. c. 225/840), centred on Karaj, between Hamadhan and Iṣfahan.⁷³ The Dulafids enjoyed a hereditary position within the 'Abbasid caliphate, rather like that of the Ṭahirids. Now, with the death of Aḥmad ibn 'Abd al 'Azīz ibn Abī Dulaf in 280/893, al Mu'taḍid saw an opening. He went to the province and imposed his son 'Alī al Muktafi as governor of Rayy, Qazvīn, Qumm and Hamadhan, and in 283/896 he stripped the last Dulafid *amīr* of his remaining lands.⁷⁴ However, the affairs of the province remained turbulent, in part because of the Zaydī 'Alid mini state lodged in the lowlands of nearby Ṭabaristan.

The Ṣaffarids remained the dominant power in the Persian speaking world. After the death in 265/879 of Ya'qub ibn al Layth, his brother, 'Amr ibn al Layth, proved a shrewd leader. Though mainly active in the east, 'Amr still held Fars in south western Iran, a province that the 'Abbasids coveted for themselves. However, al Mu'taḍid chose the path of cooperation here (since 'Amr was clearly too big to take on), recognising 'Amr's position in Fars as well as in Khurasan. In 285/898 al Mu'taḍid allowed 'Amr to go one step further, when he appointed him governor of Transoxania. This province was

72 Bianquis, 'Autonomous Egypt', p. 106.

73 C. E. Bosworth, *The new Islamic dynasties: A chronological and genealogical manual* (New York, 1996), p. 153.

74 Kennedy, *The Prophet and the age of the caliphates*, pp. 183–4.

already in the possession of the Samanid *amīr* Ismaʿīl ibn Aḥmad, whose brother Naṣr had previously been recognised as governor by al Muʿtaḍid. With these conflicting investitures, al Muʿtaḍid may have thought it in his own best interest to let ʿAmr and Ismaʿīl fight it out. When the decisive battle occurred, ʿAmr met utter defeat.⁷⁵ Ismaʿīl sent him as a prisoner to Baghdad, where he was executed soon after the death of al Muʿtaḍid in 289/902. However, this did not mark the end of the Ṣaffarids. In Fars, still an object of desire for the ʿAbbasids, a grandson of ʿAmr ibn al Layth named Ṭahir ibn Muḥammad held out against armies sent by al Muʿtaḍid. The province would not fall to the ʿAbbasids until 910; later the Ṣaffarids would reappear as local rulers in Sīstan and adjoining regions, beginning in 923.

Al Muʿtaḍid died in 289/902, after a reign of ten years. If he had ruled as long as his ancestors al Maṣṣur and al Rashīd, things might have turned out differently for the ʿAbbasid caliphate, which now found itself in an improved but still precarious position. The new caliph was ʿAlī al Muktafi, a son of al Muʿtaḍid who already had experience of governing in Rayy and Qazvīn. In his policies al Muktafi provided continuity, but in his character and comportment he did not, being a sedentary figure who did not instill much loyalty, let alone inspiration, in the soldiers. However, loyalty and inspiration were now sorely needed, as the ʿAbbasid caliphate faced the gravest threat it had seen since the days of the Zanġ.

The Ismaʿīlī network of the late ninth century included a community in north eastern Arabia, in the region known as al Baḥrayn (corresponding broadly to the modern Saudi province of al Ḥasa, not the island known nowadays as Bahrain). Here, in the last years of the caliphate of al Muʿtaḍid, Abu Saʿīd al Jannabī established himself at the head of this community and challenged the caliph's forces in Iraq, with considerable success. The ʿAbbasid authorities called these Arabian sectarians Qaramiṭa or Qarmaṭīs, as we have seen. Having previously encountered this threat from the south east, the authorities were unprepared for the Qarmaṭī threat that now erupted in the west.

In the turmoil that followed the announcement by Saʿīd/ʿAbd Allah of his own status as *mahdī* and imam, the Ismaʿīlīs in Iraq found themselves divided. Some, led by Ḥamdan Qarmaṭ's brother in law ʿAbdan, denied the claim, as we have seen. Others, who supported it, arranged for ʿAbdan to be treacherously murdered. Implicated in the deed was one Zikrawayh or Zikroye, a former protégé of ʿAbdan who now went into hiding. In Syria, Zikrawayh's

⁷⁵ See above, n. 29.

son Yahya emerged at the head of a force of Bedouin from the tribal confederation of the Kalb. Yahya read from a book containing divine instructions, he wore a veil which left only his eyes uncovered, and he rode a camel mare (*naqa*) which provided a rallying point (and totemic emblem) for the warriors. Accordingly, Yahya became known as *ṣaḥīb al naqa* (the ‘man with the she camel’).⁷⁶ In 289/902 he defeated a Ṭulunid force, sacked al Ruṣafa and besieged Damascus, as we have seen. Meanwhile ‘Abd Allah the *mahdī* began his westward flight. Yahya pressed on with the siege of Damascus, but in the summer of 290/903 he died before the city walls, and the siege was lifted. However, his brother al Ḥusayn, known as *ṣaḥīb al shama* (the ‘man with the birthmark’ (or mole)), took over, briefly establishing the *mahdī*’s rule in several Syrian towns. Awkwardly, the *mahdī* himself did not arrive, though he sent messages promising he would do so.

Meanwhile, al Muktafi sent an army to Syria, commanded by Muḥammad ibn Sulayman, who bore the title ‘scribe of the Bureau of the Army’ (*katib dīwan al jaysh*). (Significantly, Ibn Sulayman had risen in the bureaucracy, and not the army.) Ibn Sulayman encountered the Bedouin fighters, now referred to as ‘Faṭimids’ (*Faṭimiyyun*, *Fawaṭim*), and routed them. ‘Abd Allah the *mahdī* still maintained a prudent distance, and the ‘man with the birthmark’, in his rage, slaughtered those members of the *mahdī*’s household who still remained in Salamiyya. This atrocity did not endear him to the surviving Bedouin ‘Faṭimids’, who returned to their pasturages. Ibn Sulayman tracked him down and delivered him to Baghdad where, in an elaborate public spectacle in the winter of 291/904, the ‘man with the birthmark’ was maimed and tortured to death, together with over 300 of his followers and some common criminals. The gruesome show gave vent to the fear that the ‘Qarmaṭīs’ inspired among the population. But although al Muktafi could claim victory this time, this fear would return many times in the coming decades.

The other notable success of al Muktafi’s five year reign involved the end of the Ṭulunid state. Ṭughj ibn Juff, who had been the Ṭulunid commander against the sons of Zikrawayh before the arrival of the Iraqi army commanded by Ibn Sulayman, now came to an understanding with the ‘Abbasid forces. Fustaṭ surrendered in 292/905, the Ṭulunid complex of al Qaṭa’i’ was razed to the ground, except for the great mosque, and a train of prisoners was dispatched to Baghdad. Nonetheless, the restoration of ‘Abbasid rule did not bring an improvement in Egypt’s fortunes. Having to send large sums to Iraq every year, and saddled with an expensive military

⁷⁶ Al Ṭabarī, *Ta’rīkh* II, series III, p. 2224; Halm, *Empire of the Mahdi*, pp. 71–2.

establishment at home, the Egyptian administrators apportioned *iqṭaʿat* (concessions of revenues from fiscal districts), as had happened in Iraq perhaps as early as the 860s. Lands were assigned to soldiers and administrators, and periodically confiscated. This practice immobilised a large proportion of Egyptian lands and properties, and reduced the ability of rulers and administrators to take effective action.⁷⁷

Not surprisingly, direct ʿAbbasid rule in Egypt did not last long. After several governors had come and gone, a Turkish commander named Takīn gained control and received confirmation from Baghdad in 301/913f. Takīn then had to confront the first attack against Egypt launched by the Faṭimids in North Africa. He was removed in the following year, and in the end it was Muʿnis, a general from the court of the caliph al Muqtadir, who came from Iraq and repelled the invasion. A second Faṭimid invasion followed five years later; Takīn took control, only to see Muʿnis enter Egypt again with a force of 3,000, defeating the Faṭimids in 922. Takīn was reappointed a third time in 924, in a time of turmoil and insecurity. After he died in 933 a struggle took place over the leadership; and now the ʿAbbasid authorities were unable to intervene. The winner was Muḥammad ibn Ṭughj, son of that Ṭughj ibn Juff who had fought the sons of Zikrawayh and brought about the collapse of the Ṭulunid state. Ibn Tughj staved off a third Faṭimid invasion in 323/935, this time without outside help. He received confirmation of his governorship, and in 327/939 the caliph al Raḍī granted him the right to be called *ikhshīd*, a princely title harking back to the land of his ancestors, Farghana in Central Asia. The *ikhshīd*'s position resembled that of the Ṭulunids before him, even if he lacked their brilliance. Egypt in the Ikhshīdid period (until 968) was a major power within the new configuration of politics in the Mediterranean, which included a revived Byzantine empire, a Holy Roman empire occupying much of southern Italy, and two new Islamic caliphates in the west, those of the Faṭimids (from 909) and the Spanish Umayyads (from 929).

New centres of power

As the ʿAbbasid caliphate in Baghdad collapsed during the first half of the tenth century, in other places – especially along the edges of the Islamic world – new rulers achieved successes and new states emerged.

⁷⁷ Bianquis, 'Autonomous Egypt', p. 109.

Faṭimid North Africa

The Faṭimid *dawla*, or dynastic state, that emerged in Ifrīqiya in 909 harked back, in many ways, to the Umayyad and early ‘Abbasid caliphates, as we have seen. Of course it was built on the foundations of the Aghlabid emirate.⁷⁸ At the same time, this new *dawla* was the achievement of one man, the austere Abu ‘Abd Allah al Shī‘ī. But now, for Abu ‘Abd Allah and some of his fellow *da’īs*, the new reality proved disappointing. The *mahdī* whom they had placed on the throne did not lead an exemplary life, let alone usher in a new age. A measure of messianic expectation can be seen in the name and title of his son and heir, Abu ‘l Qasim Muḥammad ibn ‘Abd Allah al Qa’im (where the genealogically ordered name is precisely that of the Prophet Muḥammad, and the title, ‘the present one’, is millennarian), but for the most part the new ruler was concerned with establishing a state and army in conventional ways. Within two years matters came to a head. The *mahdī* found out about a plot against him, and he executed Abu ‘Abd Allah together with several other *da’īs* and Kutama commanders. The similarity to the execution of Abu Muslim, a century and a half previously, has often been noted: like Abu Muslim, Abu ‘Abd Allah had become a burden to the ruler he had placed on the throne. And like the ‘Abbasid caliph al Maṣṣur, the Faṭimid *mahdī* had to struggle afterwards to maintain the loyalty of his base; but in the end he prevailed.

The history of the Faṭimid caliphs in North Africa conveys a sense of movement towards a great consummation: not the End of Days, but rather the worldly conquest of Egypt. This great province, whose revenues dwarfed those of Ifrīqiya, was the first step on the way to dominion over the entire Muslim world, which the Faṭimid claim to imamate and caliphate entailed. Moreover, Egypt was vulnerable following the Ṭulunid collapse and ‘Abbasid takeover. To exploit the situation, the *mahdī* sent an expedition in 301/914. His son and heir Abu ‘l Qasim took part, holding Alexandria, Giza and the Fayyum before yielding to the ‘Abbasid commander Mu’nīs, as we have seen. Five years later another expedition was sent, nominally under Abu ‘l Qasim’s command. This expedition included a fleet of around eighty ships, which the ‘Abbasids destroyed. Meanwhile, Abu ‘l Qasim occupied much of the country before he became trapped, in 922, in the Fayyum and was forced to escape with heavy losses. Afterwards, early in his own reign, Abu ‘l Qasim al Qa’im made a last attempt to take Egypt. Despite the failure of these

⁷⁸ The basic work on the Aghlabid emirate is still Mohamed Talbi, *L’émirat aghlabide* (184–296/800–909): *Histoire politique* (Paris, 1966). Much of the recent work relating to the Aghlabids has dealt with their operations in Sicily.

expeditions, they are a testimony to Faṭimid power. Egypt is nearly impregnable from its western side: the Faṭimid expedition that ultimately succeeded, that of Jawhar in 969, met little opposition, and the only serious invasion from the west since then has been that of Rommel, which came to grief in 1942 at El Alamein.

Ismaʿīlīs were probably not as scarce in the Faṭimid domains as we often think: proselytising ‘sessions of wisdom’ (*majalis al ḥikma*) were held, at first under Abu ‘Abd Allah al Shīʿī himself, and from a later time we hear, from the Qaḍī al Nuʿman, that the audiences for these sessions were eager and large.⁷⁹ However, there is no denying that the ruling elite was a religious minority. Al Mahdī built himself a new capital, al Mahdiyya, a fortified stronghold on a spit of land jutting into the Mediterranean, thus isolating himself from the hostile Sunnī and Malikī populace of Qayrawan. In fact, his Aghlabid predecessors had done much the same, in establishing themselves at al Raqqada (near Qayrawan) and Tunis (like al Mahdiyya, looking out to sea); afterwards the Faṭimids would return inland, to a new foundation in al Manṣuriyya. However, even if the Faṭimid caliphs maintained a degree of physical separation from the population, their relations with non Ismaʿīlīs were not uniformly hostile. Malikī biographical works with a hagiographical character lament the oppression inflicted by the heretical rulers, but they do not name a single victim who suffered martyrdom at their hands.⁸⁰ There were confrontations over matters of ritual, along Sunnī–Shīʿite lines, but the Faṭimids learned to leave other religious groups considerable latitude in their religious practice and communal organisation. Like the Aghlabids before them, the Faṭimids found that the campaigns in Sicily and southern Italy, together with the activity of volunteers in the *ribaṭs*, or fortresses guarding the North African coastlines, provided a minimal measure of solidarity between rulers and ruled. Above all, this was a time of prosperity for North Africa. Trade with western Europe was on the rise. The naval technology of the time required frequent stops, which worked to the advantage of the North African and Sicilian ports. In this way the Faṭimids benefited from the conquest of Sicily, and Palermo became one of the largest cities of Islam. This did not, by itself, quell opposition to the Faṭimids, but many North Africans must have noticed the relative increase in prosperity that came with their rule.⁸¹

79 Halm, *Empire of the Mahdī*, pp. 374–6, citing Qaḍī al Nuʿman, *al Majalis wal musayarat* (Tunis, 1978), paragraphs 201, 224, 467, 487.

80 Halm, *Empire of the Mahdī*, pp. 221–47, citing the *Riyaḍ al nufus* of Abu Bakr al Malikī (Beirut, 1981).

81 Brett, *Rise of the Fatimids*, pp. 247–66.

Effective and deadly opposition to the Faṭimids came from another direction. Many North African Muslims remained loyal to Kharijism, especially along the fringes of the Sahara and among Berber tribal confederations that were rivals of the Kutama. It was among one of these, the Zanata, that the great enemy of the Faṭimids arose: Abu Yazīd Makhlad ibn Kaydad, known as the *ṣaḥīb al ḥimar* (the ‘man with the donkey’). Abu Yazīd set out in 943 and quickly swept over most of Ifrīqiya, including Qayrawan. He besieged the caliph al Qa’im (r. 322 34/934 46) in al Mahdiyya where, some said afterwards, it had been prophesied that the entire Faṭimid realm would become reduced to a single narrow space. Things looked all the worse for the Faṭimid cause because of al Qa’im’s reclusiveness and passivity, which contrasted strangely with the energy he had shown in his youth. However, Abu Yazīd and his back country followers severely alienated the urban Malikī population when they occupied Qayrawan. The Faṭimids and the Kutama managed to regroup and to drive the Kharijites back. The hero of the encounter was al Qa’im’s son, the future caliph Isma‘īl al Maṣṣūr (r. 334 41/946 53). After years of hard campaigning he defeated the Kharijites and finally got hold of the ‘man with the donkey’ himself, whose corpse, flayed and stuffed with straw, was then paraded throughout the Faṭimid domains. Al Maṣṣūr is alone among the Faṭimid caliphs, Egyptian as well as North African, in being a military figure, a ‘*ghazī* caliph’, through and through. This, together with his early death, contributed to the favourable image he had among his subjects, including and beyond his fellow Isma‘īlis.⁸²

Al-Andalus

The arrival of a new caliphate in North Africa in 909 was followed, two decades later, by yet another one, this one in al Andalus or Islamic Spain. We have seen that in the second half of the ninth century al Andalus suffered from internal strife. Meanwhile, it remained a frontier society, in constant low density warfare against the small Christian kingdoms to its north.⁸³ All this changed with the Umayyad *amīr* ‘Abd al Raḥman III, who, from the beginning of his rule in 300/912, campaigned energetically against local lords installed in cities, mountain redoubts and frontier posts. ‘Abd al Raḥman also looked to the north, where Christians from León had advanced to the Duero and were raiding Muslim territory. ‘Abd al Raḥman personally led campaigns of *jihad* five times. In 924 he arrived in the Ebro valley, sacking Pamplona and

⁸² Halm, *Empire of the Mahdi*, p. 337.

⁸³ Above, p. 318.

burning its cathedral. In this way he extended Umayyad power to the north, including the Mediterranean coast.

‘Abd al Raḥman also faced a challenge in the south, from the Faṭimid al Maḥdī and his successors. Isma‘ilism on its own never gained ground in al Andalus, but, with the rise of the new caliphal power, rebels against ‘Abd al Raḥman could compel the mosques in the territory under their control to say the *khutba* in favour of the Faṭimid.⁸⁴ Fighting between Umayyads and Faṭimids did not take the form of direct conflict and invasion. Instead, the two sides acted against each other through proxies in the western reaches of North Africa. There the earlier division of territory, with the Midrarids based in Sijilmasa, the Idrīsids in Fez and the Rustamids in Tahert, had already been upset by the arrival of the Faṭimids. In 921 a Faṭimid campaign took Fez (though the Faṭimids did not hold it for long), bringing an end to what remained of the Idrīsīd dynasty. Meanwhile ‘Abd al Raḥman fortified his ports and sought bases on the North African coast near Spain.⁸⁵

Encouraged by his successes and seeking to counter the Faṭimid threat to his south, ‘Abd al Raḥman made a bold move in 929, by assuming the title commander of the faithful, with the regnal title al Naṣir (‘the victorious’). The Umayyads of Spain had never claimed the caliphate before, but now they had good reasons for trying. The decline of ‘Abbasid power was felt throughout the Islamic world. The Umayyads had a plausible claim to the caliphate, based on their simply being Umayyads: for them the usurping, butchering ‘Abbasids had deprived all generations of Umayyads of their rightful place. The decisive reason, however, must have been rivalry with the Faṭimids. ‘Abd al Raḥman made contact with Byzantium and the German emperor Otto I (r. 938–73), with the goal of restraining a common enemy. A new configuration of power in the Mediterranean was emerging, as we have already seen.

This new or renewed Umayyad caliphate constituted a high point of prosperity and cultural production for al Andalus. However, there was turbulence, some of it caused by the caliph’s slave soldiers, many of whom were Slavs or Europeans (*ṣaqaliba*). Holding this prosperous but fractious enterprise together required energy and determination. In this ‘Abd al Raḥman resembled the ‘Abbasid al Mu‘taḍid, and here too the restored caliphate of al Andalus did not long survive the disappearance of its ‘*ghazī* caliph’ from the scene.

84 As was done in 909 by the rebel Ibn Hafsūn, who also sent an embassy to Qayrawan and received a return visit of Isma‘īlī *da‘īs* bearing robes of honour from al Maḥdī.

85 Kennedy, *Muslim Spain and Portugal*, pp. 95–7; Halm, *Empire of the Maḥdī*, pp. 264–74.

The Samanid emirate in Khurasan and Transoxania

In the east, the family that we know as the Samanids first rose to prominence as sub governors in the service of the Ṭahirids in Khurasan and Transoxania, in the early third/ninth century.⁸⁶ In 875, after the fall of Nishapur and the collapse of the Ṭahirids, the Samanid Naṣr ibn Aḥmad, already de facto governor of Transoxania, received confirmation from the caliph al Mu'tamid. Rather like al Mu'tamid in those same years, Naṣr found himself under the domination of an ambitious brother, Isma'īl, who assumed sole control when Naṣr died in 279/892. As we have seen, Isma'īl defeated the Ṣaffarid 'Amr ibn al Layth in 287/900, after which al Mu'tamid awarded him the governorship of Khurasan and Transoxania. These two provinces together then constituted the core of the Samanid emirate. Though Nishapur, in Khurasan, remained a great city, the Samanids maintained their court and capital on the other side of the Oxus river, in Bukhara.

This choice of capital guaranteed that the Samanid emirate would be a frontier state. Isma'īl inaugurated his reign with an expedition into the steppe in 280/893, defeating the Qarluq Turks and capturing Talas, far to the north east. In addition to ruling directly over their core provinces, Isma'īl and his successors asserted overlordship over the rulers of Ushrusana and Farghana to the east, Khwarazm to the north, and other regions. This position on the frontier brought prosperity to the Samanids and at least some of their subjects: in an age when Turkish slaves were in high demand, the Samanids had a monopolistic control over the supply. Their raiding expeditions took captives who either went on to the slave markets further west or remained in the Samanids' service. Meanwhile, like the Ṭahirid *amīrs* before them, the Samanids constructed systems of defensive fortresses, as well as walls and ramparts for the cities. Under Isma'īl these were so effective that the fortifications of Bukhara and Samarqand became neglected, unfortunately for later generations.⁸⁷ Large numbers of 'volunteers' served in these frontier posts, known here, as in Aghlabid North Africa, as *ribāṭs*, while many religious scholars took part in the affairs of the emirate. Their role consisted largely of preaching and exhorting, but there is also evidence for men of learning at the head of units of *ghazīs* (fighters for the faith), apparently not organised directly by the Samanid state.⁸⁸ This participation of 'volunteers' in defence of the frontiers may be

⁸⁶ See chapter 7.

⁸⁷ R. N. Frye, 'The Samanids', in R. N. Frye (ed.), *The Cambridge history of Iran*, vol. IV: *The period from the Arab invasion to the Saljuqs* (Cambridge, 1975), p. 140.

⁸⁸ Jürgen Paul, 'The histories of Samarqand', *Studia Iranica*, 22 (1993), esp. pp. 82–7; Jürgen Paul, *The state and the military: The Samanid case*, *Papers on Inner Asia* 26 (Bloomington, 1994); Jürgen Paul, *Herrscher, Gemeinwesen, Vermittler: Ostiran und Transoxanien in vormongolischer Zeit* (Beirut and Stuttgart, 1996), esp. pp. 93–139.

connected to the social peace that prevailed under Samanid rule: the Samanids, who may have been descendants of petty landowners from near Balkh, enjoyed good relations with the *dihqans*, or landed gentry.

The high regard for scholarship at the Samanid court appears in an anecdote in which the *amīr* Ismaʿīl ibn Aḥmad rises publicly before a man of learning, and is then chided by his brother: ‘You are the ruler of Khurasan, and you rise before one of your subjects when he enters your presence? This is the end of statecraft and good policy!’ Ismaʿīl’s comportment then receives approval in a dream in which the Prophet announces the confirmation of Ismaʿīl’s rule and that of his descendants, and the end of his brother’s rule. In this way the theme of respect for scholars is related to the rivalry between the brothers Ismaʿīl and Naṣr at the beginning of the independent Samanid emirate.⁸⁹

During the long reign of Naṣr II ibn Aḥmad ibn Ismaʿīl (301–31/914–43), the Samanid court took the lead in a remarkable flourishing of the arts and sciences. Two of Naṣr’s *wazīrs*, al Jayhanī (302–10/914–22 and 327–31/938–41), and Abu ʿl Faḍl al Balʿamī (310–27/922–38), had leading roles in this activity, which may be further described, in general terms, as bilingual.⁹⁰ The Ṭahirids had made scant use of Persian, though the Ṣaffarids used it considerably more. But under the Samanids Persian emerged as a full fledged language of literature and (to a lesser extent) administration. Court patronage was extended to Persian poets, including the great Rudakī (d. c. 940). Meanwhile Arabic continued to be used abundantly, for administration and for scientific, theological and philosophical discourse.

Relations with the ‘Abbasid caliphate tended to be correct but cool. Although the names of the caliphs duly appeared on their coins, the Samanids did not forward these coins to Baghdad in the form of tribute or tax. Of course the ‘Abbasids were far away and increasingly powerless. In some ways, however, the Samanids paid them the compliment of imitation: their well ordered administration was modelled largely on ‘Abbasid precedent. Afterwards it provided the model for administrative structures and

‘Fighting scholars’ are discussed also by Michael Bonner, *Jihad in Islamic history: Doctrines and practices* (Princeton, 2006), pp. 97–117; and in Deborah Tor’s *The ‘Ayyars: A study in holy warfare, chivalry and violence* (forthcoming).

89 Abu Bakr Aḥmad al Khaṭīb al Baghdādī, *Taʾriḫ Baghdad*, 14 vols. (Cairo, 1931), vol. III, p. 318, entry for Abu ‘Abdallāh Muḥammad ibn Naṣr al Marwazī, d. 295. This date of death indicates that the losing brother must be Naṣr ibn Aḥmad (d. 279/892), and not Ishaq, who is named in the story. This Ishaq ibn Aḥmad was another brother of Ismaʿīl and Naṣr who revolted later on, after the accession of the underage *amīr* Naṣr II ibn Aḥmad ibn Ismaʿīl (r. 301–31/914–43). The narrator of the story, Abu ʿl Faḍl al Balʿamī, was *wazīr* for Naṣr II from 310/922 to 327/938.

90 Frye, ‘The Samanids’, pp. 142–3, 145–6.

techniques for, among others, the Ghaznavid and Saljuq states; the Saljuq *wazīr* Nizām al Mulk (d. 485/1092) admired the Samanid example beyond all others.

The Samanids were Sunnī in their religious doctrine and Ḥanafī in their legal affiliation. However, the Ismaʿīlī *daʿwa* achieved some success in their domains, and in the reign of Naṣr II it attracted converts at the court and in adjacent circles. The *amīr* himself tolerated and even, to some extent, adopted this Ismaʿilism, which here, in the Samanid north east, took on a markedly philosophical (Neoplatonic) character. The response came in 331/943, when a *coup d'état* brought Naṣr II down and elevated his son Nuḥ to the throne. One result was an affirmation of the Sunnism and anti Shīʿism of the Samanid state, especially since its chief rival was now the pro Shīʿite Buyid emirate of Iraq and western Iran.

Like the Faṭimids and the Spanish Umayyads, and indeed like most of the political formations that emerged during these decades, the Samanids relied on units of slave soldiers, to the point where Turkish commanders came to outweigh the Samanid *amīrs* and bureaucrats. This resulted in a crisis that had some points in common with that of the 'Abbasid caliphate in Samarra' in the 860s; however, since it came a good century later than that crisis, it lies beyond the scope of this chapter.

Daylam and the rise of the Buyids

This tour of the edges of the Islamic world ends with mountainous Daylam, at the south western end of the Caspian Sea.⁹¹ Because of its difficult terrain, Daylam had never been integrated into the unitary caliphate. Islam also arrived late, and then often in the form of Zaydī Shīʿism. Daylam might have remained obscure and marginal, but for the fact that in the early tenth century it began to export soldiers throughout northern Iran, and then to much of the Islamic world. The phenomenon seems difficult to explain. In a military scene dominated by cavalry, the Daylamīs were infantry, known for their use of the javelin and tall shield. The most sought after units consisted of Turkish slaves who had been born outside the Islamic world and then converted to Islam; the Daylamīs were free born Iranians. One reason for their popularity was their reputation for endurance and strength. Another reason must have been that unlike slave soldiers they did not have to be bought and cared for, and unlike tribal levies – such as the Kutama in North

⁹¹ 'Daylam' in the sources for this period often refers to the entire southern Caspian region, including Jurjan, Ṭabaristan and Gilan, in addition to Daylam proper.

Africa or the Arab tribal confederacies of the Syrian desert – they were largely immune to what Ibn Khaldun would later call *‘aṣabiyya*, the passion of group feeling. Despite their Zaydism they did not usually fight out of religious or ideological passion. In a world where loyalties were under negotiation, where military needs were often short term, but where religious and ethnic identity had sharp edges, the Daylamīs had the potential for being truly effective mercenaries, and thus in great demand.

The Daylamī commanders, often compared to the *condottieri* of the Italian Renaissance, sought power and fame, and some of them became rulers of fledgling dynastic enterprises. Daylam and the neighbouring areas lay between the spheres of control of the Samanids to the east and the ‘Abbasids to the west. In the early tenth century there was another power on the scene, Ibn Abi ‘l Saj, the ruler of Azerbaijan, whose departure for Iraq in 314/926, to fight the Qaramiṭa, left an opening. Several commanders fought one another, and one of these, Makan ibn Kākī, became master of Ṭabaristan, Jurjan and even of Nishapur in Khurasan in 318/930. Meanwhile, the fierce and extravagant Mardavīj ibn Ziyar, who had risen in the service of yet another commander, Asfar ibn Shirawayh, rebelled against his master in 319/931 and killed him. Mardavīj then captured some of the cities of western Iran from the ‘Abbasids, before seizing Ṭabaristan and attacking Makan ibn Kākī. However, the Samanid Naṣr II intervened, and Mardavīj agreed to a peace settlement.⁹² It was at around this time that three Daylamī brothers in Makan’s service, ‘Alī, Ḥasan and Aḥmad, sons of a Caspian fisherman named Buya (or Buwayh), transferred their allegiance from Makan to Mardavīj. ‘Alī, the eldest, received an appointment as governor over the old Dulafid capital, Karaj. Later on, Mardavīj made threats against Baghdad and the caliphate, declaring his intention to restore the Iranian monarchy and the Zoroastrian religion. Before he could do this, however, he was murdered by his own Turkish slaves in Iṣfahan in 323/935. His brother Wushmgīr held on to the Caspian regions of Ṭabaristan and Jurjan, where the Ziyarid line continued afterwards.⁹³ These Daylamī commanders, Mardavīj above all, are interesting as players of the rough game of military politics in the post caliphal Islamic world, and also as seekers of new kinds of local and Iranian identity. However, it was the three sons of Buya, whom we know as the Buyids (or Buwayhids), who were going to leave a profound mark on the history of Islam.

92 C. E. Bosworth, ‘Makan b. Kākī’, *EL*, vol. VI, pp. 115–16; W. Madelung, ‘Mardawīdj b. Ziyar b. Wardanshah’, *EL*, vol. VI, p. 539.

93 Madelung, ‘The minor dynasties of northern Iran’.

Well before Mardavīj's death 'Alī ibn Buya found an independent base in the south western Iranian province of Fars. The 'Abbasid caliphate had previously won Fars back from the Ṣaffarids, but now, with general anarchy threatening, some local magnates there invited 'Alī to provide them with protection. Backed by this alliance, 'Alī settled in with his soldiers and sought recognition of his position from Baghdad. Mardavīj's death then allowed 'Alī to avoid a confrontation with his former master and to recruit some of his troops. The power void in west central Iran eventually enabled 'Alī to place his brother Ḥasan over a large region, including the cities of Rayy and Iṣfahan, in 335/947. Meanwhile the third brother, Aḥmad, had an unsuccessful adventure in the province of Kirman, just to the east. Now, however, he looked westward to Iraq and joined the military commanders who were competing there for the new position of *amīr al umara'* (chief commander), circling like vultures over an 'Abbasid caliphate that had nearly come to its end.

End of the independent 'Abbasid caliphate

During the four decades between the accession of al Muqtadir in 295/908 and the arrival of Aḥmad ibn Buya in Baghdad in 334/945, all of the 'Abbasid caliphate's hard won gains of the previous decades vanished. We know a good deal about these events because of the coverage provided by several historians who wrote in Arabic during the tenth and eleventh centuries.⁹⁴ These historians valued eyewitness testimony, and while they were acutely aware of the legacy of al Ṭabarī, who died in the middle of this period in 310/923, they also went in directions that the master had not taken, as some of them displayed intimate knowledge of the protocol and inner life of the court, while one of them, the philosopher historian Miskawayh, proved to be a world class observer and analyst of politics. For readers accustomed to the work of al Ṭabarī and his predecessors, this historical writing can have a bracing effect.⁹⁵ Nowadays, however, historians often neglect the history of the first half of the tenth century, perhaps because they see it as a painful transition between effective 'Abbasid rule and the ensuing period of Buyid domination in Iraq and western Iran, famous for its 'renaissance of Islam'.⁹⁶

94 There are summaries of the historiographical 'succession to al Ṭabarī' in Kennedy, *The Prophet and the age of the caliphates*, pp. 362–5; and Franz Rosenthal, *A history of Muslim historiography* (Leiden, 1968), pp. 81–3.

95 See the beginning of this chapter.

96 Joel L. Kraemer, *Humanism in the Renaissance of Islam: The cultural revival during the Buyid age* (Leiden, 1993).

When al Muktafi, still in his early thirties, died of an intestinal disorder in 295/908, the situation of the caliphate seemed favourable, with Egypt recently conquered from the Tulunids, the Qaramiṭa repelled, and the treasuries reporting a modest surplus.⁹⁷ At this point the bureaucrats had matters in hand as never before, and the group that gathered to choose a new caliph included only administrators, but no soldiers or princes of the blood. The reports of this meeting are filled with refined calculation of political interest. The *wazīr* at the time, al ‘Abbas ibn Ḥasan, backed by ‘Alī ibn al Furat and his faction, desired to keep power for himself, as he had grown accustomed to exercising it during al Muktafi’s illness. This led him to declare for al Muktafi’s brother Ja‘far, a child of thirteen. The meeting concluded in agreement and Ja‘far was acclaimed as caliph, with the regnal title al Muqtadir. Much of the money in the treasury went into donatives for the army and other gifts, as was customary on these occasions. The boy caliph immediately lived up to ‘Abbas’s expectation, being naive, gullible and open to manipulation.

There is nothing so dangerous as the fulfilment of one’s dearest wish, and in the following year the ambitious *wazīr* fell victim to a *coup d’état*. This was organised by administrators of the Jarraḥid faction and by officers led by the dashing Arab commander al Ḥusayn ibn Ḥamdan, who deposed al Muqtadir and replaced him with ‘Abd Allah ibn al Mu‘tazz.⁹⁸ At the time Ibn al Mu‘tazz seemed a plausible candidate, notwithstanding (or because of?) his reputation as a poet and man of letters. However, a group of officers and administrators closed ranks around al Muqtadir, while Ibn al Mu‘tazz’s partisans disintegrated because of their inept planning. Ibn al Mu‘tazz and several of his followers were put to death and others suffered prison or exile, while the ruling faction saw its power confirmed. Now it was necessary to distribute yet another round of donatives and gifts, eliminating whatever surplus still remained in the treasury.

Bureaucratic factions dominated the long reign of al Muqtadir. One soldier kept the remnants of the army together and saved the caliphate on several occasions: this was Mu‘nis al Khadim (‘the eunuch’), who had been in the ‘Abbasid service since the days of al Mu‘taḍid and who, after his first triumph over the Fatimids in Egypt in 301/914 (see above) received the honorific title al Muza‘ffar (‘the Victorious’). Meanwhile, a long string of *wazīrs* came and went, facing the impossible task of maintaining the caliphate’s finances and

⁹⁷ See above, p. 334.

⁹⁸ Son of that al Mu‘tazz who was declared caliph in a failed *coup d’état* after the murder of his father al Mutawakkil, and later became counter caliph against al Musta‘īn in 865, and then caliph until his miserable death in 869 (see above).

periodically undergoing the ordeal of *muṣādara* (see above). Most prominent of these were the two rivals, 'Alī ibn 'Isa and 'Alī ibn al Furat, who each served as *wazīr* three times. 'Alī ibn 'Isa, allied with Mu'nis, was known for piety, efficiency and attempts at limiting expenditure.⁹⁹ 'Alī ibn al Furat, also admired for his knowledge and skill, was given to displays of generosity, which led him to accumulate large sums for himself. Like other members of his clan Ibn al Furat favoured Imamī Shī'ism, though not quite openly. It was still possible for a high ranking official to have such a sympathy, though it could provide Ibn al Furat's enemies with a weapon when they wanted one.

The precarious balance among factions in the administration and court suffered damage during the tumult of the trial and execution of the mystic al Ḥusayn ibn Manṣūr al Ḥallaj. Born in 244/857f., al Ḥallaj ('the carder') travelled widely, including stints on the eastern frontiers and in India. When he came to Baghdad during the reign of al Muktafi he resumed the impassioned preaching that had made him famous as 'the carder of hearts' (*ḥallaj al qulub*). A first trial of al Ḥallaj ended in his release since, as one jurist said, the authorities had no jurisdiction in the matter. Already, however, al Ḥallaj had friends and enemies at court. The failed *coup d'état* in favour of Ibn al Mu'tazz was a debacle for al Ḥallaj's supporters the Jarrahids, and he fled into exile. He was brought back, however, and made to stand trial a second time. Now 'Alī ibn 'Isa was the *wazīr*, and he managed to end this trial in 301/912. For a long time afterwards al Ḥallaj was kept at the palace, with the factions swirling around him. The third and final trial took place in 308 9/921 2. The *wazīr* at the time, Ḥamid ibn al 'Abbas, went to great lengths to destroy al Ḥallaj. The mystic, who had been accused of claiming to have achieved substantial union with God (*ḥulul*, as in the saying that his enemies attributed to him, 'ana 'l ḥaqq', 'I am the Truth'), was now accused, somewhat improbably, of being a Qarmaṭī. Finally a conclave of jurists, under prodding, signed a death warrant. Al Muqtadir concurred, and al Ḥallaj was gibbeted, tortured and dispatched. It is noteworthy that this death warrant included signatures from representatives of different *madhabs*, or schools of law. The Ḥanbalīs, however, took al Ḥallaj's side, aggravating the urban unrest that was already brewing. Angry mobs threatened the jurist and historian al Ṭabarī, now near death, who had declared against al Ḥallaj.

The episode of al Ḥallaj illustrated many things, beginning with the precariousness of life at court and of 'Abbasid rule itself. It revealed the very

99 Harold Bowen, *The life and times of 'Alī ibn 'Isa, the 'Good Vizier'* (Cambridge, 1928), still the most gripping account (in a European language) of this period.

palpable importance of the *madhhabs*, which had been growing as juridical and intellectual affiliations for a long time, but were thenceforth a major element of identity for large urban groups, and often for angry mobs. Not least of all, the episode shows that Sufism was becoming more and more noticeable within urban life, as the central authority of the caliphate declined. Sufism of the ‘Baghdad school’ had flourished in the previous century as a set of moral and intellectual doctrines with, for example, the introspective teachings of al Muḥasibī enjoying popularity among many of the townspeople. But now, with the growing division between the followers of the so called ‘drunken’ al Ḥallaj and their more ‘sober’ rivals, Sufism offered an enormous range of doctrines and experiences, as well as new styles of leadership. Together with other forms of mystical and ascetic expression it spread far beyond Baghdad, especially in the Samanid east, and became a major element of social aggregation.¹⁰⁰

Al Ḥallaj’s death brought little advantage to ‘Alī ibn al Furat who, in his third wazirate, struggled to sustain the failing machine of government. In his rage at the situation he faced, and having recently endured a long imprisonment himself, Ibn al Furat, together with his son al Muḥassin, extorted and tortured beyond the customary limits of *muṣadara*. Father and son fell from power and were executed in 312/924. ‘Alī ibn ‘Isa returned to the wazirate, but when he was brought down in 317/929, the loyal Mu’nis finally turned against al Muqtadir and attempted a *coup d’état*. A brother of al Muqtadir, Muḥammad al Qahir, was briefly installed on the throne, before al Muqtadir was restored and Mu’nis driven away. In 320/932, however, Mu’nis returned, and in the ensuing fight al Muqtadir was killed. Now al Qahir became caliph and Mu’nis, as kingmaker and head of the army, held the reins of power.

During the decade before al Muqtadir’s death the situation was severely aggravated by the renewed attacks of the Qaramiṭa of Baḥrayn. Under their leader, Abu Ṭahir Sulayman, the Qaramiṭa sacked Baṣra in 311/923, and in 315/927 they nearly took Baghdad itself. Qarmaṭī bands repeatedly attacked the Meccan caravans. In 317/930 they stormed Mecca and, amid great slaughter, they removed the Black Stone and brought it to their capital, where it would remain for some years.¹⁰¹ Unable to meet this challenge with its own resources, the government offered Ibn Abi ‘l Saj, the *amīr* of Azerbaijan and Armenia, a splendid reward for fighting the Qaramiṭa in 314/926. He accepted

100 Jacqueline Chabbi, ‘Remarques sur le développement historique des mouvements ascétiques et mystiques au Khurasan’, *SI*, 46 (1977).

101 C. E. Bosworth, ‘Šanawbarī’s elegy on the pilgrims slain in the Carmathian attack on Mecca (317/930): A literary historical study’, *Arabica*, 19, 3 (1972).

the offer and proceeded to attack the enemy, but was defeated and killed. Factional divisions within the government aggravated differences over policy, as 'Alī ibn 'Isa advocated the unpopular view that it was better to appease the Qaramiṭa than to endure their attacks.

Although the Qarmaṭī threat subsided after 930, it was clear that if the 'Abbasid state was to survive it would have to resolve its military crisis. In fact, al Muqtadir's violent death marked a new domination of the government by the military, as was widely noted at the time. As in Samarra' in the 860s, the factional fighting became intense. Its early victims included Mu'nis, killed in 321/933 by al Qahir, whom he himself had placed in power. Once again the provinces fell away, this time including al Jazīra, now in the hands of the Ḥamdanids (see below). Only the Sawad of Iraq remained, and even this was compromised, as the Barīdī family held sway around Ahwaz, in Khuzistan to the south. Though the Barīdīs were administrators rather than soldiers, they interacted skilfully with the soldiers by allocating revenues and lands. For these were now at stake, as the fiscal system of the caliphate fell to pieces.

In these years, together with the following period of Buyid domination, the land regime emerges that we sometimes call the 'new' *iqta'*. The term *iqta'* means the act of apportioning a land grant or *qaṭī'a*, but it can also refer to the land grant itself. As we have seen, perhaps as early as the 860s such grants were made to army commanders not only out of 'estate' lands (*ḍiyya'*), but also out of *kharaj* lands, supposedly under direct control of the administration (see above, p. 312). The evidence for this is slender. By 945, however, *iqta'* clearly referred to the allocation of the revenues of a district, made directly to an individual – most often a high ranking officer – who received these revenues in lieu of regular pay from the central treasury.

There are two ways of conceptualising this 'new' *iqta'*. The first is at the level of the provincial governor, a military man who could be granted the right to all the revenues of his province, with the stipulation that he would forward a specified sum to the central treasury. An example is the deal made with Ibn Abi 'l Saj in 314/926. In this instance, Ibn Abi 'l Saj died in combat against the Qaramiṭa and the deal was never completed. However, there was only one step from this 'provincial' *iqta'* to employing the same procedure in the Sawad of Iraq itself. This meant, in effect, militarising the central administration and, indeed, the lands.

The second way of conceptualising the 'new' *iqta'* involves considering the administration of all the lands within a particular province – here, the Sawad of Iraq. We have already seen that the land regime of the 'classical' caliphate included two main categories, lands paying the heavy *kharaj* (land tax) directly

to the central treasury; and *ḍiyya* ('estates'), lands in the possession of privileged individuals who paid only the lighter *'ushr* (tithe). The holders of *ḍiyya*, or estate lands, would collect their revenues (or rents) from the taxpayers (or tenants) who resided on their lands; these revenues (or rents) were assessed at the same (high) rate as the *kharaj*. The estate holders would then forward to the central treasury a smaller amount, assessed according to the *'ushr*. They would keep the difference between the two – a very tidy sum – for themselves.

As for the *kharaj* lands, we have seen that throughout the third/ninth century the work of levying taxes from them was often not performed directly by the fiscal authorities of the 'Abbasid state, but instead by intermediaries. The legal instruments of these transactions were contracts of tax farming (*ḍaman*), and then also of *muqata'a* and *ighar* (see above, p. 312). Here the contracting party collected the taxes from the taxpayers at the *kharaj* rate, paid a stipulated amount to the central treasury, and kept the rest for himself as a fee.

Now, beginning in the later third/ninth century, came a further step, which we identify with the 'new' *iqta'*. A military officer would no longer draw his pay directly from the central treasury, but instead would be assigned the revenues from a particular district in the Sawad. He was expected to forward a stipulated amount to the treasury (though in reality he often sent less than that amount, or nothing at all). On the one hand, the position of this *muqta'*, or recipient of *iqta'*, resembled that of someone who had signed a contract of tax farming (*muqata'a* or *ighar*). On the other hand, the *muqta'* was still a soldier, and not a professional administrator. And the officers who found themselves in this position apparently felt a strong – even proprietary – interest in their assigned districts, beyond that of a functionary or tax collector. As in the case of the 'provincial' *iqta'* (see above), the result was the militarisation of what had previously been a civilian contract or arrangement. And now the entire countryside became open, at least potentially, to this new regime: not only *ḍiyya*, but even *kharaj* lands, which were theoretically the property of the civilian owners who held title to them, became open to the domination of military landholders.

Unlike the *iqta'* of the later Saljuq, Ayyubid and other periods, which was partly the result of planning, the *iqta'* of this period emerged out of crisis mode improvisation. With the treasury empty and the soldiers constantly demanding their pay, it offered liquidity and security: once assured of a comfortable income, the officers would presumably remain loyal. On the negative side, however, the soldiers of the rank and file still had to be paid out of the central

treasury.¹⁰² And together with the new *iqta'* came a decline in the professional standards of the bureaucrats, whose main task became (or so they complained) the demarcation of districts for *iqta'*. Since an *iqta'* assignment was, in principle and largely in fact, for a fixed time only, the officers sought upgrades, and competed avidly for the desirable holdings. However, they had little motivation and no expertise for maintaining the lands in good condition and performing vitally needed infrastructural work. The decline of the agricultural lands is painfully visible in budget data: in the century between 204/819 (in the reign of al Ma'mun) and 303/915 (in the reign of al Muqtadir) the revenues of the Sawad shrank from 112,416,000 *dirhams* to 22,500,000, with most of the loss occurring from the reign of al Mutawakkil.¹⁰³ The historian Miskawayh describes these converging processes in a Thucydidean passage that is remarkable for its analytic power and economy of expression.¹⁰⁴

While civilian administrators such as the Barīdīs could participate in this competition for revenues and lands, the big players were the military commanders. After Mu'nis's death, the next powerful figure to emerge was Muḥammad ibn Ra'iq, military governor in Baghdad, Baṣra and then Wasīṭ. The caliph was now al Raḍī (r. 322 9/934 40), a son of al Muqtadir, who in 324/936 reluctantly agreed to appoint Ibn Ra'iq as *amīr al umara'* ('chief commander'), with control over the civilian administration (or what remained of it) as well as the military. However, the violent competition among the officers did not let up. Ibn Ra'iq killed al Raḍī's household troops, and then, in the following year, seeking a momentary advantage over his opponents, he destroyed the Nahrawan canal, undoing the work of generations and causing untold ecological damage. Meanwhile, new soldiers arrived from the east, following the assassination of Mardavīj ibn Ziyar (see above). These included the Turks Bajkam and Tuzun, who afterward held the new office of *amīr al umara'*. Ibn Ra'iq himself was assassinated in 942 by Ḥasan ibn Abī al Hayja', who then briefly held the office of *amīr al umara'* himself.

This Ḥasan was a member of the family known as the Ḥamdanids. Unusually for high level players in the military politics of this age the Ḥamdanids were Arabs, of the tribe of Taghlib. In the late third/ninth century they had changed their affiliation from Kharijism to mild Shī'ism, not

102 Cahen, 'L'évolution de l'*iqta'*', pp. 244 5.

103 Budget data are collected by Waines, 'Internal crisis', pp. 286 7.

104 Miskawayh, *Tajarib al umam*, ed. A. Emami (Tehran, 2001), vol. VI, pp. 129 32, trans. D. S. Margoliouth in *The eclipse of the 'Abbasid caliphate: Original chronicles of the fourth Islamic century*, vol. V (Oxford, 1921), pp. 100 5.

uncommon for inhabitants of the borderlands between desert and sown at the time (see above, p. 325). We have already met al Ḥusayn ibn Ḥamdan, a leader in the failed coup in favour of Ibn al Mu‘tazz in 296/909. Afterwards al Ḥusayn came in and out of ‘Abbasid service, before ending on the executioner’s mat in 306/918. Meanwhile his brother Abu al Hayja’ performed brilliantly in the expeditions against the Dulafids, the Qaramiṭa (including ‘the man with the birthmark’) and the Ṭulunids. Loyal to Mu’nis al Khadim, he died defending al Qahir during the abortive attempt at overthrowing al Muqtadir in 317/929. By then, however, Abu al Hayja’ had established a foothold in the province of Mosul. His son al Ḥasan took his place there, holding several provinces as *iqṭa’*s, and playing a role in the murderous intrigue of the following years. Al Ḥasan was thus all at once a provincial ruler ensconced in Mosul, and a product of the power politics of Baghdad. He acquired the honorific title Naṣir al Dawla (‘helper of the dynasty’) while his younger brother ‘Alī received the title Sayf al Dawla (‘sword of the dynasty’).

In the end it was the younger brother who brought lasting fame to the Ḥamdanid line. From 944 onwards Sayf al Dawla became established in northern Syria and the district of the Byzantine frontier, a position which made him a *‘ghazī amīr’*, which is to say, a provincial ruler who gloried in his role of fighter for the faith. The Ḥamdanid emirate of Aleppo was accordingly a frontier state, like so many we have seen in this chapter. Although Sayf al Dawla did not succeed in the end, his dynastic enterprise achieved renown because of its Arabism, because of the unparalleled collection of literary talent that Sayf al Dawla assembled to sing his praises, and because of the stand that the Ḥamdanids took against the onslaught of a restored and strengthened Byzantine empire. All this, however, belongs to a later chapter.

When al Raḍī died in 329/940, several candidates for the caliphate declined to be considered since, they are reported to have said, ‘the executive power belonged to someone else [other than the caliph]’.¹⁰⁵ Finally the choice fell upon al Raḍī’s brother Abu Ishaq, who chose the regnal title al Muttaqī. The *amīr al umara’* was now Bajkam, who died soon afterwards. Turks and Daylamīs in the army began to quarrel, as the Barīdis threatened Baghdad and Ibn Ra’iq tried to get back his old job of *amīr al umara’*. Al Muttaqī tried to save himself through an alliance with Naṣir al Dawla, who did away with Ibn Ra’iq, as we have seen. However, Naṣir al Dawla’s stint as *amīr al umara’* ended when the Turkish commander Tuzun occupied Baghdad in 331/943.

¹⁰⁵ Abu Bakr Muḥammad al Shatranjī al Ṣulī, *Akhbar al Raḍī wal Muttaqī* (London, 1935), p. 186, ‘wal tadbīr li ghayrihi’.

Al Muttaqī then tried to form an alliance with the *ikhshīd*, the ruler of Egypt who also controlled Syria at the time. When this attempt failed, al Muttaqī received assurances and oaths from Tuzun that he could come back and resume his place in Baghdad. However, when al Muttaqī did return in 333/944, Tuzun had him blinded and then deposed, an act that deeply shocked the Islamic world.¹⁰⁶ Tuzun himself died within the year, an act of divine justice in the eyes of many observers.

Now it was the turn of Aḥmad ibn Buya. As we have already seen, Aḥmad had been previously in Fars and Kirman. He came to Khuzistan to ally himself with the Barīdīs, but then turned against them and ruled Khuzistan on behalf of his brother ‘Alī, from 330/941 onward. In 334/December 945 Aḥmad seized his opportunity and entered Baghdad with his troops. He assumed the position of *amīr al umara*’ and the honorific title Mu‘izz al Dawla (‘strengthener of the [‘Abbasid] dynasty’). Despite this title, when Aḥmad found the current caliph (al Mustakfi, since 333/944) not to his liking, he cast him aside and appointed a new one (al Muṭī‘illah, r. 334 63/946 74).

The arrival of Mu‘izz al Dawla in Baghdad marks a turning point. Now the Buyids ruled over Baghdad and the Sawad, centre of the caliphate and the old Islamic empire, together with their holdings in western and central Iran. It is reported that Mu‘izz al Dawla considered doing away with the ‘Abbasids like other Daylamīs, the Buyids were sympathetic to Zaydī Shī‘ism but thought better of it. A powerless ‘Abbasid caliphate was still indispensable to the Buyids for several reasons, including their need for formal legitimacy. Thus began a century of unhappy cohabitation between Buyid *amīrs* and enfeebled ‘Abbasid caliphs.

Conclusion

With Tuzun’s treacherous blinding of al Muttaqī we seem to have come full circle since the assassination of al Mutawakkil, as once again an outrage against a caliph’s body reveals the fragility of dynasty, empire and state. Now, however, the ‘Abbasid empire and state no longer exist, except as a legal or sentimental fiction. People feel horror over Tuzun’s perjury, but not because of damage done to the sacred office of the caliphate and the community of believers so much as because oaths and vows are now the essential way of making binding arrangements for the long and the short term. The

¹⁰⁶ Mottahedeh, *Loyalty and leadership*, pp. 46–8.

caliph's body is no longer the focal point of unity, but merely a visible patch within the great fabric of loyalties and associations.

During the eight decades between the assassination of al Mutawakkil and the blinding of al Muttaqī, people came to identify themselves more completely with the associations they were born into or entered into voluntarily, in their religious activities, professions, legal affiliations, urban neighbourhoods and other things. More than before, life was a matter of negotiation and renegotiation among groups and individuals, at all levels of society including that of high politics. The rulers now acted as mediators among these formations and groups, understanding full well that they could not govern without the approval of the civilian elites.¹⁰⁷

We often think of corruption as a component of the fall of empire, and this period of Islamic history has its share of conspicuous overconsumption, bribery, fraud, embezzlement and extortion. However, many of these practices were routinised, as in the *muṣadara* (see above). The rules and expectations were complex, as we see in a report from the courtier and historian al Ṣulī describing how, in 329/940, he drew up a list of possible regnal titles for the new caliph, one of which, al Muttaqī, was eventually selected.

On Tuesday evening al Tarjumān said to me, 'Choose a name [regnal title] for the caliph.' I wrote out thirty names on a piece of paper and then did the same on another piece. I sent one to him and the other to Aḥmad ibn Muḥammad ibn Maymūn. They assured me that I would receive a consideration for having chosen the names (*wa ḍaminā lī ikhrāj ḥaqq al tasmiya*). However, they did not keep their word in the least, they did not intercede with anyone on my behalf, and they did not lead anyone else to think favourably of me.¹⁰⁸

Al Ṣulī expects a monetary reward or tip for his exertions.¹⁰⁹ He is furious over his patrons' failure to extend protection during the perilous time of an interregnum. It might be argued that during the earlier, 'classical', caliphate of Harun al Rashīd and the Barmakids, the machinery of government had been constantly and systematically greased with gifts and bribes. Now, however, with the caliphate at its end and the bureaucracy in disrepair, these costs increase disproportionately. It is likely that 'considerations', such as the one that al Ṣulī expected here for a small, discrete piece of work, were exacted

107 Ibid., esp. pp. 175–90; Michael Chamberlain, *Knowledge and social practice in medieval Damascus, 1190–1350* (Cambridge, 1994).

108 Ṣulī, *Akhbar al Raḍī wal Muttaqī*, p. 187; trans. Marius Canard as *Histoire de la dynastie abbaside de 322 à 333/933 à 944*, 2 vols. (Algiers, 1950), vol. II, p. 6. I follow Canard in reading Ṣulī's interlocutor as 'al Tarjuman', and not 'al Barjmalī(?)'.

109 In fairness to Ṣulī, it has to be remembered that he was a *nadīm*, a courtier, and not a salaried bureaucrat.

constantly and routinely, thereby increasing the hidden expense of government and aggravating the decline that we see in the budget figures and elsewhere. The great fabric of loyalties and associations came, quite literally, at a cost.

The decline and fall of the 'Abbasid empire coincided with the rise and flourishing of many new successor states. Among these we have seen three basic types which we may quickly review here, bearing in mind that any real life example can combine characteristics of more than one type.

The first is the dynastic state pure and simple, resulting from the activity of a military adventurer who seizes control over a territory and then tries to make his rule palatable to the local population (which does not actually have much say in the matter), to rival centres of power and to the central authorities of the empire. Though rough and unpredictable, the state that forms in this way still belongs to the older value system of the caliphate: the new dynasty does not aspire to overthrow the imperial centre, but needs that centre to provide confirmation of his own authority. The Buyids are a good example of this, ironically enough since they came to occupy the physical space of the 'Abbasid caliphs themselves.

The second type, which forms along the frontier, applies to such dynastic states as the Saffarids, Samanids and Ḥamdanids. These are frontier societies not only because they emerge and grow on the physical periphery, but also because they are constantly discovering and testing the inner limits and meanings of Islamic society. Their characteristics include lots of movement, as volunteer fighters, ascetics and men of religious learning come to these borderlands to take part in the fight against the infidel.¹¹⁰

The third and final type is the state that forms out of a volatile combination of tribal group feeling and the propagation of a new religious message. This is the process familiar to us from Ibn Khaldun, and which is often discussed as the most common or even normal mode of state formation in Islam. In this period the notable examples of state formation of this type involve radical Shī'ite states, especially those of the Faṭimids in North Africa and the Qaramiṭa in Baḥrayn. The Faṭimids are, at the same time, the outstanding instance of a restoration of the caliphate and a revival of the old, battered structures of empire.

How can we set this shifting grid of new dynastic states together with the all pervasive fabric of loyalties and associations mentioned just before,

¹¹⁰ Bonner, *Jihad in Islamic history*, chapters 7 ('Embattled scholars') and 8 ('Empires, armies and frontiers').

in such a way as to obtain an accurate, three dimensional picture of the Islamic world in 334/945? We may well think of this world as an Islamic commonwealth, as some have done. We should also remember that some of the best writers of this age were interested in the problem of how to name and portray the Islamic world they lived in. We have seen that al Ṭabarī recorded the history of the old unitary caliphate in loving detail, but showed reticence and discomfort when he arrived at his own troubled times. Younger writers, however, were willing to take on the problem, and we may single out two of these. Qudama ibn Jaʿfar was a scribe in the ʿAbbasid service in Baghdad during the first half of the tenth century, and the author of a comprehensive work on ‘the land tax and the secretary’s art’. Abu Ishāq Ibrāhīm al Iṣṭakhrī was a lifelong traveller and geographical writer; we do not know how he actually made his living. Both Qudama and al Iṣṭakhrī describe the late or post caliphate world as *mamlakat al islam*, ‘the realm of Islam’. In their books this is an enormous space traversed by itineraries, trade routes, religious and cultural affinities, frontiers, shared administrative practices and other affiliations.¹¹¹ The realm of Islam is thus an idealised, intensely networked geographical and political entity which, strictly speaking, happens to lack a head. Later geographical writers would take up the idea, but already we see what a varied and interesting place this post imperial Islamic world has become.

¹¹¹ André Miquel, *La géographie humaine du monde musulman*, 4 vols. (Paris and the Hague, 1967), vol. I, pp. 271–5.

The late 'Abbāsid pattern, 945–1050

HUGH KENNEDY

The decline and fall of the 'Abbasid caliphate in the first half of the fourth/tenth century led to the emergence of a new political order. The most fundamental change was the collapse of the resource base and fiscal system that had sustained the caliphate. The 'Abbasid caliphate had owed its wealth and hence its political survival to the revenues derived from the rich agricultural lands of the Sawad of Iraq. A rough calculation suggests that during the reign of Harun al Rashīd this area produced a large proportion of the gross revenue of the caliphate, four times as much as the next most productive area, Egypt.¹ During the course of the third/ninth and fourth/tenth centuries this happy state of affairs changed forever. The once rich landscapes of the alluvial plain of southern Iraq were ruined and impoverished by a mixture of maladministration, military campaigning and lack of investment. Such meagre revenues as they continued to yield had been appropriated by the military nominally serving the government in Baghdad or by independent adventurers, and no longer filled the coffers of the state.

This economic decline profoundly affected the political geography of the Islamic world. Even under the Umayyads, whose courts were predominantly to the west in Syria, Iraq had been the resource base of the caliphate, and this status had been reinforced under the early 'Abbasids by investment in agricultural infrastructure. By the mid fourth/tenth century, however, Iraq was probably no more productive than many other areas.² This fiscal realignment was the prelude to a political shift that resulted in the centrifugal dispersal of power; polities based in Fars, Khurasan or Egypt could be just as wealthy and powerful as those based in the old heartland. With the collapse of the centre, power passed to new regimes in the provinces.

¹ See David Waines, 'The third century internal crisis of the 'Abbasids', *JESHO*, 20 (1977).

² Hugh Kennedy, 'The decline and fall of the first Muslim empire', *Der Islam*, 81 (2004), repr. in H. Kennedy, *The Byzantine and Islamic Near East* (Aldershot, 2006).

Social and religious changes were also in progress. In the first century and a half of Islam the caliphate was inhabited largely by non Muslims ruled over by an elite class of Muslims, most of whom were or claimed to be of Arab descent. By the third and fourth centuries, however, this had changed. The central administration of the Middle 'Abbasid caliphate was increasingly dominated by men of non Arab – usually Turkish or eastern Iranian – origin. One effect of this was to alienate the Bedouin tribes of the Arabian and Syrian deserts from the formal government, as can be seen from the increasing level of nomad attacks on the *hajj* in the late third/ninth and early fourth/tenth centuries. At the same time, increasing conversion to Islam in provinces and outlying regions meant that these areas produced native Muslim elites, whether landowners in Fars or the chiefs of transhumant Kurdish tribes. They were all Muslims, but saw no need to show any deference or obedience to the authorities in Baghdad and Iraq. It is a striking fact that, with one exception, none of the dynasts and warlords who took power in the lands that the 'Abbasids had ruled made any attempt to reject Islam or establish Christian or Zoroastrian states.

The lands that had once formed the domains of the 'Abbasid caliphate became a commonwealth in the sense that they were linked by many ties: by the shared elite religion, Islam; the use of Arabic as the language of administration and high culture; and by patterns of trade and pilgrimage which brought together people from all over the area. Baghdad itself remained a centre of scholarship that attracted seekers of knowledge from all parts of the Muslim world. But these links no longer provided the basis for political unity. In place of the caliphate, numerous different ruling polities emerged, each striving to maintain itself in its chosen area.

That the only man who tried to reverse the tide of Islamic rule, the Daylamite warlord Mardavīj ibn Ziyar, had little success speaks to the degree of Islam's entrenchment in the culture of Iran.³ Mardavīj (d. 323/935) was one of the most remarkable personalities of his age. Brutal and aggressive as he was, he had a vision of a restored Iranian monarchy, ordering that the old Sasanian palaces at Ctesiphon (al Mada'in, near Baghdad) should be restored to await his arrival. He rejected the authority of the 'Abbasid caliphate entirely, and sought to displace Islam as the dominant religion and restore the old Zoroastrian faith, ostentatiously reviving the old ceremonies of fire

³ The Daylamites inhabited the mountainous province of Daylam at the south west corner of the Caspian Sea. They were to be the military foundation of Buyid power: see below.

worship. It is therefore with some satisfaction that Muslim writers record his death at the hands of some disillusioned Turkish troops in 323/935. Despite his personal power, his efforts to revive the old faith seem to have met with little popular support.

Apart from Mardavīj, all the dynasties that emerged to fill the power vacuum caused by the collapse of 'Abbasid power were, despite their differing geographical and ethnic affinities, Muslim. The post 'Abbasid history of the central Islamic lands is usually presented in dynastic terms (e.g. the Buyids, Ghaznavids etc.), the names of the dynasties often being distinct from those of the tribes that supported them: thus the Banu Mazyad or Mazyadids were chiefs of the Asad tribe, the Mirdasids of the Kilab etc., the name of the ruling dynasty usually being derived from that of the father or grandfather of the first important ruler. This may seem somewhat arbitrary and show cavalier disregard for regional identities and economic realities; it can certainly result in a bewildering multitude of unmemorable names. It does, however, reflect the terminology of the sources on which we depend and the reality of political power, and these conventional dynastic divisions are probably the most satisfactory way of presenting these developments. And if the modern reader is confused, we can imagine that many people at the time were equally perplexed about what was going on around them.

Typology of successor regimes

The 'Abbasid caliphate did not disappear. The three caliphs who succeeded the unfortunate al Muttaqī,⁴ al Mustakfī (r. 333 4/944 6), al Muṭī' (r. 334 68/946 74) and al Ṭa'ī (r. 363 81/974 91), were effectively powerless puppets confined to their palace in Baghdad, without any possibility of independent action. All three were deposed, al Mustakfī and al Ṭa'ī because they were felt to be resisting the demands of the Buyids. Al Muṭī' was paid a pension of 2,000 *dirhams* per day by the Buyid Mu'izz al Dawla, who insisted on choosing the members of the caliph's household himself. However powerless and impoverished they were in reality, their continued existence did, however, provide a constitutional façade for the different dynasts who did control the Muslim world and their survival meant that the 'Abbasids could take on a new and important role as leaders of the Sunnī community from the time of al Qadir (r. 381 422/991 1031).

4 See chapter 8 above, for the 'Abbasid caliphs of the early fourth/tenth century.

The regimes that took over effective political power from the 'Abbasids can be divided, very simply, according to the type of fiscal and military structure on which they based their power. In one group were the polities based on the employment of the *ghulam*, and in the second those based on the support of fellow tribesmen. The term *ghulam* (pl. *ghilman*), originally meaning 'young man', is used in Arabic sources of this period to describe professional soldiers, usually but not always of Turkish origin. From the fifth/eleventh century such soldiers would come to be known in Arabic speaking countries as *mamluks*. Legally, the *ghilman* were unfree, but in practice this made little difference to their ability to further their own financial and political interests and, unlike true slaves, they were paid for their work. During the third/ninth century the *ghilman* had emerged as the undisputed elite soldiers of their time, fighting as cavalry and often as mounted archers.⁵ They were efficient, usually loyal and always very expensive. Many of the post 'Abbasid regimes attempted to continue the old system and employ *ghilman*, with their salaries being paid out of the receipts of taxation. With the exception of the Ghaznavids, who acquired additional resources out of the proceeds of *jihad* in India, regional regimes such as the Buyids mostly encountered major financial problems, and their precious *ghilman* went looking elsewhere for paid employment or mutinied to try to extort their pay.

On the other hand, regional dynasts who based their power on the services of their fellow tribesmen were not under this constant financial pressure, since their followers were interested in access to good pastures and occasional booty rather than regular cash salaries. But tribal supporters brought other sorts of problems. They were often difficult to discipline, and unwilling to accept commands from a chief whom they regarded as no more than *primus inter pares*. Among these states were the 'Uqaylids of Mosul, whose support was based on Arab Bedouin; another was the Marwanids of Mayyafariqin, and their transhumant Kurds.⁶

In *ghulam* based states the traditions of 'Abbasid bureaucracy were continued, with greater or lesser success: revenues still had to be collected and salaries paid. The Ghaznavids on the far eastern frontiers of the Muslim world developed an administrative system which was ultimately based on those that had been developed by the 'Abbasids in Baghdad and Samarra'. Tribal polities needed no such infrastructure: their rulers were often on the move and their viziers served not as heads of a complex bureaucratic structure, but rather as

⁵ See chapter 7 above for the emergence of this new army.

⁶ On these dynasties see below.

intermediaries with local peoples and to compose such diplomatic correspondence as was required.

Almost without exception the rulers of these polities looked to 'Abbasid structures to provide a form of legitimisation. They took titles that claimed them to be supporters of the *dawla* – that is, the 'Abbasid dynasty – so we find 'Imad al Dawla ('support of the *dawla*'), Rukn al Dawla ('pillar of the *dawla*') and so on. In fact, this allegiance rarely impinged on their independence, nor did it provide any support against their enemies; but it did allow some dynasts, most notably the Ghaznavids, to claim a legitimacy within the Muslim commonwealth which these newly converted Turkish ex slaves would otherwise have lacked.

The Buyid confederation

The Buyids⁷ were the dynasts who took over the lands in Iraq and western Iran that had formed the core of the 'Abbasid caliphate in the ninth and early tenth centuries. They also took over some, at least, of the administrative traditions of the 'Abbasids and dominated the caliphate itself as 'protectors' of the 'Abbasid caliphs, who remained in their palace in Baghdad, powerless in all practical ways but still important as legitimising figureheads. The Buyids themselves came originally from Daylam, at the south western corner of the Caspian Sea. They were complete outsiders – descendants, it was said, of a simple fisherman called Buya from an area that had never produced important figures in the politics of the Islamic world. The local inhabitants, the Daylamites, fought as foot soldiers, taking service with military leaders in Iran and Iraq as mercenaries. This meant that they had to find allies – usually Turks, sometimes Kurds – who could provide the cavalry to make up a balanced fighting unit. Family ties were very important to the Buyids, and much of Buyid politics was family politics.

The Buyids' initial success was due to their military abilities. In 320/932 'Alī ibn Buya, with a force of just 400 men, made himself master of the rich and comparatively peaceful province of Fars. In 315/927 the province had been

⁷ On the Buyids, see H. Busse, *Chalif und Grosskönig: Die Buyiden im Iraq (945–1055)* (Beirut, 1969); John J. Donohue, *The Buwayhid dynasty in Iraq 334H/945 to 403H/1012: Shaping institutions for the future* (Leiden, 2003); R. Mottahedeh, *Loyalty and leadership in an early Islamic society*, 2nd edn (Princeton, 2001). On the cultural achievements of the period, Adam Mez, *The Renaissance of Islam*, trans. Khuda Bakhsh (London, 1937; repr. New York, 1975) is still valuable. See also chapter 8 above.


taken over by a Turkish soldier called Yaqut, who made himself unpopular with the local people by his misgovernment and oppressive taxation. 'Alī achieved power by allying with important landowners in the area, some of whom claimed 'Alid descent. They provided the revenues, while 'Alī and his Buyid followers supplied the military power to maintain law and order and protect the province from outside invasions. It was an arrangement that generally worked well until the coming of the Saljuqs in the 1050s, and during this period Fars was one of the most stable and agriculturally prosperous areas of the Muslim world.

'Alī ibn Buyā's brother al Ḥasan was able to establish himself as ruler of central Iran, from Rayy to Iṣfahan, in 335/947, and Aḥmad, the third brother, turned to Iraq. In 332/944 he attempted to take Baghdad for the first time, but was beaten off by the Turkish *amīr al umara'* ('commander of commanders', the title adopted by the military rulers of the 'Abbasid caliphate), Tuzun. A year and a half later, however, Tuzun was dead, and so Aḥmad easily occupied the city with his forces and was accepted by the caliph al Mustakfi as *amīr al umara'* in 334/945. By 335/946 the brothers were rulers of Fars, Iraq and Rayy, and their descendants were able to maintain themselves in most of those areas until the coming of the Saljuqs a hundred years later.

In theory, the Buyid brothers exercised authority as governors for the 'Abbasid caliphs. Aḥmad was appointed *amīr al umara'* by the 'Abbasid caliph in Baghdad. His brothers were 'appointed' to provincial governorates, and both the structures of 'Abbasid government and the old provincial boundaries remained largely unchanged. The brothers took titles that expressed their support of the 'Abbasid *dawla* (dynasty): 'Alī was to become 'Imad al Dawla ('support of the state'), al Ḥasan, Rukn al Dawla ('pillar of the state'), while Aḥmad was to be Mu'izz al Dawla ('glorifier of the state'). Some Buyids also revived the old Sasanian title of *shahanshah* (king of kings).⁸ By this they intended to establish their legitimacy with their Iranian subjects and, above all, with their fellow Daylamites.

The Buyid lands formed a family federation, not a centralised empire, and family concerns and rivalries remained central to their political outlook. The possessions of the family were always considered as the property of the whole kin, rather than of individual branches, and relatives felt that they had the right – even the duty – to interfere in times of trouble. The Buyids never

⁸ See W. Madelung, 'The assumption of the title shahanshah by the Buyids and "the reign of the Daylam (*dawlat al Daylam*)"', *JNES*, 28 (1969).



7. The Buyids.

After Hugh Kennedy, *The Prophet and the age of the caliphates*, 2004, p. 405. Copyright Longman, reproduced with permission.

developed a clearly defined system of inheritance; each powerful ruler sought to provide a suitable inheritance for all his sons, even if it had to be done at the expense of his cousins. The tensions between the traditional Daylamite clannishness and the needs of settled government were a continuing source of conflict.

The major political units were the principalities centred on Fars, with its capital at Shīraz, al Jibal, based on Rayy, and Iraq, including Baghdad, Baṣra and, very briefly, Mosul. After the death of the last of the original Buyid brothers, Rukn al Dawla al Ḥasan, in 366/977, the western half of the principality of al Jibal was detached to form a new unit based on Hamadhan and Iṣfahan, while from time to time Kirman in the east enjoyed independence from Fars, an independence which became permanent after the death of Baha' al Dawla in 403/1012. Of these principalities, Fars was the most important, maintaining its power and prosperity well into the fifth/eleventh century. Baghdad enjoyed prestige as the seat of the caliphate, and remained a cultural and intellectual centre of great importance. Politically and economically, however, it was very weak, and after the death of its first Buyid ruler, Mu'izz al Dawla, in 356/967 it became apparent that the only Buyid rulers

who could exercise power effectively in Baghdad were those like 'Aḍud al Dawla and Baha' al Dawla, who also ruled Fars. The fortunes of the rulers of Shīraz and Baghdad were therefore closely linked. The principality of Rayy, on the other hand, remained somewhat separate, never being ruled by the same prince as Fars and facing different problems, notably the danger of attack from the east by the Samanids⁹ and later the Ghaznavids.

On some occasions, especially in the second half of the Buyid century after the death of 'Aḍud al Dawla in 372/983, princes were persuaded or obliged to take the offensive against other members of the family by different groups of their followers. After 'Aḍud al Dawla's death a group of wealthy Iraqis, whom he had sent into exile in Fars, persuaded his son Sharaf al Dawla, against the advice of his Farsī counsellors and his own better judgement, to attack Iraq so that they could be restored to their possessions. It was Fakhr al Dawla's vizier, the Ṣaḥīb ('the master') Ibn 'Abbad, who induced him to attack Iraq in 379/989. The most serious and lasting source of such quarrels was the rich lands of southern Iraq and Khuzistan whose lush *iqṭa*'s (the rights to revenues from lands and districts given to troops as payment) were the envy of troops from less favoured areas. With the ravaged lands around Baghdad almost useless as a source of revenue, the lands of Khuzistan and Wasīṭ were now vital for the support of the largely Turkish garrison of Baghdad; at the same time, they were also coveted by the Daylamite troops from Fars. No Buyid prince could afford to ignore demands from his soldiers that he should seize these areas, and they were a continuing source of conflict between the princes of Baghdad and Shīraz until Baha' al Dawla's administrators worked out a careful division of the territories around the turn of the fifth/eleventh century.

Buyid rule in Baghdad was always precarious. The first problem that faced Mu'izz al Dawla after he took over the city in 334/945 was that of relations with the Ḥamdanids, who were now firmly in control of Mosul and northern Iraq. Naṣir al Dawla had been *amīr al umara'* before, and sought to regain his position by launching an attack on Baghdad which was only beaten off with difficulty. From then on, Mu'izz al Dawla's relations with the Ḥamdanids were based on an uneasy balance of forces, tested from time to time when the Buyids tried to take the Ḥamdanid base at Mosul. Naṣir al Dawla was able to maintain his independence by withdrawing to his mountain forresses when attacked, but was obliged to promise tribute, only intermittently paid. The failure to subdue al Jazīra (the lands between the middle

⁹ For the Samanids see chapter 8 above.

Tigris and Euphrates rivers) had important consequences in Baghdad since the area had been a major source of grain for the city, and its loss was one of the reasons for the repeated famines which caused much misery in Buyid times.

Mu'izz al Dawla had taken Baghdad by peaceful agreement, and had had to reach an accommodation with existing forces in the city. He brought with him his own Daylamite followers, but was also obliged to employ the troops, most of them Turks, who were already there. These arrangements seem to have meant that he had a military establishment that was much larger and more expensive than the country could support, and as soon as he arrived he was faced with a major economic crisis, resulting in famine and appalling hardship for the civilian population. It also became clear that the revenues were totally inadequate to pay regular salaries to the inflated numbers of soldiers, and he was forced to grant out much of Iraq as *iqta's* to his Daylamite and Turkish soldiers. This meant that much of the tax revenue from Iraq never reached the Buyid government, which became increasingly impoverished. In any case these measures merely postponed the problem, however, since the troops soon complained that their revenues were inadequate, while it became very difficult for the government to recover its financial and political power because the tax base was now so small.

The granting of *iqta's* did not solve the problems of military discontent. This was in part because the *iqta'* holders were often cheated by the agents they employed to collect their revenues, or because the lands they relied on had been ruined by war. The problem was made worse by the fact that the Turkish cavalry were paid more than the Daylamite infantry, and there was constant tension between the two groups as each struggled to obtain a share of the diminishing resources of the state.

Until the end of the fourth/tenth century Buyid administration was vigorous and moderately successful. The high point of their power in Iraq was under the rule of the great 'Aḍud al Dawla (366 72/977 83). He was already ruler of Fars, and brought the resources of that province to the government of Baghdad. He also succeeded in taking control of Mosul, expelling Abu Taghlib, the last of the Ḥamdanids, in 369/979 and so bringing al Jazīra back under the control of Baghdad. 'Aḍud al Dawla took effective measures to discourage violence between Sunnīs and Shī'a, to revive the economy of Iraq, and to keep the restless Bedouin away; but when he died in 372/983 his possessions were divided up. Constant rivalries among his heirs and the continuous financial crises meant that Buyid rule in Baghdad became increasingly enfeebled. Under Jalal al Dawla (416 35/1025 44) the city became a

lawless environment made up of fortified and mutually hostile villages presided over by a powerless *amīr* who could not afford to pay his servants or feed his horses. The Saljuq conquest of 1055 must have come as a relief to many of the city's inhabitants.

The Buyid emirate of Rayy was less bureaucratic and more financially secure than Iraq. This was not because the country was richer, but rather because the *amīrs* never recruited Turkish *ghilman*, relying instead on Daylamite troops. They kept on good terms with the leading families of Daylam, with whom they made marriage alliances, and with the Ḥasanwayhid Kurds of the Zagros mountains, who provided some cavalry in exchange for being allowed effective independence in their own lands. The Buyids of Rayy were served by a series of viziers who made an enormous contribution to Arabic literature. Rukn al Dawla relied from the beginning of his reign on the services of his great vizier, Ibn al 'Amīd, who served him loyally until his death in 360/970 when he was succeeded by his son, also known as Ibn al 'Amīd. The most famous of all Buyid viziers was Isma'īl ibn 'Abbad, known as the Ṣaḥīb, who served the Buyids of Rayy for a quarter of a century from 360/970f. to 385/995.

The viziers of the Buyids were prominent patrons of the Arabic literature of the period, and it is as patrons of culture, rather than for their administrative achievements, that they are chiefly remembered.¹⁰ The elder Ibn al 'Amīd was renowned for his knowledge of classical Arabic poetry, while Ibn 'Abbad was the patron of Abu 'l Faraj al Iṣfahanī, whose *Kitāb al aghānī* (Book of songs) is the most important record we have of early Arabic poetry and poets; he was also an accomplished Arabic stylist himself. The most important Muslim intellectual of his generation, Abu 'Alī ibn Sīna (d. 428/1037), known in the West as Avicenna, served for the last nine years of his life as vizier to a member of the Buyid clan, the Kakwayyid ruler of Iṣfahan and Hamadhan. Despite the Iranian origins of the dynasty, the high culture of the Buyid courts was almost entirely Arabic, in contrast to both the Samanids and the Ghaznavids further east, who patronised the emerging new Persian literature.

The Buyid period can be seen as a confusing and unimpressive period in Islamic history. The Shī'ite religious affiliations of the dynasty¹¹ also meant that they were the victims of hostile reports among contemporaries and later historians. This is not really fair. It is true that the dynasty did not supply the strong centralised government historians tend to admire, but the way local

¹⁰ For the literary and philosophical milieu of the Buyid period see J. L. Kraemer, *Humanism in the renaissance of Islam: The cultural revival of the Buyid age* (Leiden, 1992).

¹¹ On which see below pp. 387–90.

urban elites and tribes worked out a measure of autonomy within the general framework of Buyid rule may actually have benefited most people much more than strong government and the fierce taxation that inevitably went with it. A study of the small Iranian city of Qazvīn has shown how authority was divided between members of two prominent local families: on the one hand, the 'Ijlīs of Arab tribal origin and the Ja'farīs, descended from Ja'far, brother of 'Alī ibn Abī Ṭalib, who held the unofficial but important title of *ra'īs*; and, on the other, the *amīr*, effectively the military governor appointed by the Buyid rulers in Rayy. The *qaḍīs* were appointed by the rulers in Rayy but were almost always chosen from prominent local Qazvīnī families. Far from exercising absolute power, the Buyids of Rayy, like many contemporary rulers, had to negotiate authority with local elites and respect the interests of the urban community in such matters as curbing the factionalism that was such a destructive feature of the life of many towns in this period.¹² It is also true that there were many wars, but it must be remembered that armies were small, much smaller than those of the early 'Abbasid period or of the Saljuq Turks, and the campaigns were seldom very destructive. The great failure of the dynasty was the failure to secure the prosperity and stability of Iraq, but this was a problem whose origins went back before Buyid times and whose solution was probably beyond the powers of any contemporary government. In central Iran, and above all in Fars, their rule seems to have been an era of prosperity and development, an era brought to a premature close by the influx of the Ghuzz Turkmen in the middle of the fifth/eleventh century.

The Ghaznavids

From the beginning of the fifth/eleventh century the position of the Buyids on the Iranian plateau was threatened by the rise of the Ghaznavids.¹³ Like the Buyids, the Ghaznavids were rulers who followed the middle 'Abbasid practice of recruiting an army of Turkish *ghilman* and collecting taxes to pay them. In other ways, however, they were very different. The Ghaznavids sought to challenge the legitimacy of the Buyids by proclaiming themselves militant Sunnīs, supporters and avengers of the 'Abbasid caliphs. They also claimed legitimacy because of their role as *ghazīs*, leaders of the Muslims in their struggle to conquer India from the infidels.

12 See R. Mottahedeh, 'Administration in Buyid Qazwīn', in D. S. Richards (ed.), *Islamic civilisation 950–1150* (Oxford, 1975).

13 For the Ghaznavids see C. E. Bosworth, *The Ghaznavids: Their empire in Afghanistan and eastern Iran* (Edinburgh, 1963).

The establishment of the Ghaznavid dynasty as rulers in Khurasan in 389/999 marks the moment when the *ghulam* system came of age in the eastern Islamic world. For the first time in the history of the Islamic world, a group of Turkish *ghilman* took power in their own right. Rather than being the elite soldiers and servants of dynasties of Arab or Iranian origin, they were independent sovereigns, exercising authority in their own names. The authority of the Ghaznavids was not based on tribal connections, claims to tribal leadership or the complicated family alliances of the Buyids. They were very much part of the post 'Abbāsid pattern in that they used the proceeds of taxation to pay a professional army. The dynasty owed its power to the ability of the rulers to attract and above all pay enough *ghilman* and other soldiers to ensure that their army was the strongest in the region. Financial strength and military success were essential to Ghaznavid power, and when these began to falter there were no wider or more ancient loyalties on which they could call.

The Ghaznavid state was thus based firmly on the power of the army. For any *amīr*, the most important concern was to raise enough money to make sure that the military were regularly paid. The collection of revenues was the responsibility of the civil bureaucracy with the vizier at its head. This bureaucracy differed from the military in recruitment and ethnic background. While the leading *ghulam* soldiers were all Turks, the bureaucrats all came from Persian backgrounds and used New Persian (the Persian language written in Arabic script with many Arabic loanwords which became the lingua franca of the Iranian world from the third/ninth century on) as the language of administration. In the first years many of them had previously worked for the Samanids in Khurasan and had been trained in the traditions of Iranian bureaucracy. The revenues came from royal lands, regular land tax (*kharaj*) and war plunder. When these proved insufficient, Ghaznavid rulers and their agents resorted to illegal taxes (that is, taxes not sanctioned by Islamic law) and the confiscation of the possessions of disgraced subjects.

The founder of the dynasty, Sebüktegin, was born on the southern shores of the Issyk Kul, the vast freshwater lake surrounded by snow capped mountains in what is now Kyrgyzstan. It seems he was captured when young by members of a rival tribe and sold in the slave markets of Transoxania. Here he was purchased by Alptegin, the chief *ghulam* of the Samanid rulers of Bukhara. The young *ghulam* soon showed his talents, and rose rapidly in his master's favour. In 350/961 Alptegin attempted to intervene in a succession dispute at the Samanid court and, finding himself on the losing side, he set out with his *ghilman*, perhaps heading for India. In the event, he took the frontier town of Ghazna, hitherto a comparatively unimportant agricultural and trading centre

on the road from Kabul to Kandahar. Sebüktegin accompanied his master, and even at this early age he commanded a small body of *ghilman*. In Ghazna, Alptegin became ruler with an ambiguous relationship with his erstwhile masters, the Samanids, for whom Ghazna was a small and remote frontier town of no great value. He established his Turkish followers in ‘*iqta*’s in the countryside around Ghazna and set up what was essentially a small, independent state.

Alptegin designated one of his sons as his heir, but he died shortly afterwards and the attempt to start a dynasty failed. For a while Ghazna was ruled by Alptegin’s *ghilman*, who continued to acknowledge Samanid overlordship until in 366/977 when they chose Sebüktegin as their new ruler. He then set about consolidating his position. In 367/977f. he took Bust from its Turkish *ghulam* rulers and so came to control most of what is now southern and eastern Afghanistan. He also reformed the simple administration of his realm, setting up three *dīwans* to ensure that all his Turkish followers were properly rewarded. He also minted his own, rough and ready, coins.

The continuing decline of the power of the Samanids gave Sebüktegin further opportunities. In 383/993 he went to Khurasan at the invitation of the Samanid *amīr*, Nuḥ ibn Naṣr, who was faced by a rebellion of his military commander Fa’iq, supported by a powerful noble, Abu ‘Alī Sīmjuṛī. When Sebüktegin defeated the rebels the next year he was rewarded with the governorships of Balkh, Ṭukharistan, Bamyān, Ghur and Gharchistan – that is, almost all of modern Afghanistan – and was given the title of Naṣir al Dīn wa al Dawla. His able son Maḥmud was made commander of the Samanid army in Khurasan and given his own title, Sayf al Dawla.

Sebüktegin died in 387/997 as a loyal, though very powerful, subject of the Samanids. He divided his possessions between his brother and three of his sons. His brother, Bughračuq, was to be governor of Herat; his son Naṣr of Bust; and his youngest adult son, Isma‘īl, was given the homelands around Ghazna – perhaps because he alone was a grandson of Alptegin through his mother, and hence was felt to have a firmer claim. Meanwhile, his most able and experienced son, Maḥmud, inherited his position as head of the Samanid army in Khurasan. Sebüktegin’s succession arrangements mark the first time in Islamic history that *ghilman* were able to establish a dynastic succession, and he treated his possessions like a Bedouin or Kurdish tribal chief, making sure that all his family had shares.

Meanwhile the power of the Samanid dynasty was failing rapidly. The last *amīr*, Abu’l Ḥarith Maṣṣūr, was faced by the opposition of many of the leading magnates, including the Sīmjurids of Khurasan and the Turkish

Qarakhanids, who were already in control of the Jaxartes river valley. Maḥmud, who had by this time deposed his brother Isma'īl and taken control of Ghazna, was determined to secure for himself effective control of Khurasan and make himself protector of the enfeebled Samanids. In 389/999 Maṣṣur was deposed and blinded by the leading figures in his army, who were afraid that he would make an agreement with Maḥmud that would exclude them. They appointed the deposed *amīr*'s brother, but the fate of Maṣṣur gave Maḥmud the chance to pose as his avenger. After the failure of negotiations Maḥmud quickly defeated the opposition and became the effective ruler of Khurasan.

He moved now from being the most successful military commander of his generation to being an independent sovereign. He repudiated the Samanid dynasty entirely and proclaimed himself the loyal subject of the 'Abbasid caliph al Qadir (r. 381–422/991–1031). The letter he wrote to the caliph offering his allegiance claimed that he had only acted because of the Samanids' disobedience to the 'Abbasid dynasty. The argument may well have been specious, but the acceptance of 'Abbasid sovereignty was to prove of great importance. In return for his profession of obedience Maḥmud received formal investiture with the governorate of Khurasan, a crown and the two titles of Yamīn al Dawla and Amīn al Milla ('right hand of the dynasty' and 'trustworthy supporter of the faith'). This endorsement gave legitimacy to Maḥmud's position, which no previous Turkish *ghulam* had ever achieved. At the same time it bound Maḥmud firmly to the Sunnī cause. At this time al Qadir was consistently asserting his role as leader of the Sunnīs, in opposition to the Faṭimids of Egypt and Isma'īlī groups throughout Iran. In this way Maḥmud began the association of Turkish rule with Sunnī Islam that was to be inherited by the Saljuqs and later by the Ottomans. In everyday usage Maḥmud was often referred to as *sulṭan*. In early Islamic usage this term was an abstract noun meaning 'the authorities', but in the fifth/eleventh century it was increasingly used to refer to an individual, much in the same way as the abstract noun 'majesty' in English comes to refer to the person of the monarch ('Her Majesty'). The term also distinguished its bearer from the largely powerless caliph.

Maḥmud made the persecution of Shī'a in general and Isma'īlīs in particular a central part of his policy. By claiming to rid his lands of these 'heretics' he justified his often brutal repressions in his own lands and interventions in neighbouring areas. This opposition to the Shī'a was especially useful when he began to intervene in the Buyid kingdom of Rayy after 419/1028.

It remained for Maḥmud to come to a *modus vivendi* with his neighbours to the north and east. Shortly after he became ruler he made peace with the

Qarakhanids who had occupied the eastern parts of the former Samanid lands. It was agreed that the Oxus should form the frontier between the two domains, and the peace was sealed by a marriage alliance when Maḥmud married the daughter of the Qarakhanid ruler. Peace did not last long. In 1006, when Maḥmud was in India, Qarakhanid troops crossed the river and took Balkh and Nīshapur. Maḥmud hurried back and drove them out. According to the defeated Qarakhanid commanders, Maḥmud's elephants had played an important part in his victory. In 1008 the Qarakhanids made a last attempt on Khurasan, recruiting allies from Khotan, far to the east. Again Maḥmud's military ability and the 500 elephants in his army ensured victory, and Qarakhanid power was soon paralysed by internal feuds.

Maḥmud was never able to reunite the lands once ruled by the Samanids in Iran and Central Asia. Transoxania and the great cities of Bukhara and Samarqand remained in the hands of the Qarakhanids. He did, however, establish control over the rich and fertile lands of Khwarazm. The pretext was the marriage of his sister to the brother of the ruling *amīr* in 406/1015f. When he attempted to exploit this connection by demanding that he be recognised in the *khuṭba* (the Friday sermon in the main mosque at which the ruler's name was invoked) his brother in law was assassinated by the angry Khwarazmians. This gave Maḥmud the excuse for direct military intervention; the country was conquered by the Ghaznavid army and the Ma'munid dynasty replaced by a Turkish *ghulam*.

On his western frontiers, Maḥmud was for most of his reign content to accept Buyid control over Rayy. It was not until 1028, when the Buyid ruler Majd al Dawla asked Maḥmud to support him against his own Daylamī followers, that he intervened. Using the excuse that he was cleansing the area of 'Baṭinis' (literally those who believe in the hidden meaning of the Qur'an; the term is used as a disparaging description of Shī'a) and other heretics, he invaded, sacked Rayy and established Ghaznavid rule over the city.

In the south, Maḥmud invaded Sistan in 1002 and deposed the last of the Ṣaffarids.¹⁴ The Hindus in his army behaved with great savagery, destroying both the great mosque and the church in the capital Zaranj, and Ghaznavid rule was harsh and rapacious. The province, with its vast deserts and scattered settlements, was never an easy place to govern, and there was continuous guerrilla activity against the Ghaznavid governors. When the Turkmen appeared in the area in 427/1036 local people welcomed them and offered them their support.

¹⁴ For Sistan in this period see chapter 8 above.

Maḥmud's authority was enforced by what was probably the largest and most formidable army in the Islamic world at the time. Essentially this was a *ghulam* based state, but on a much larger scale than the Buyids or other contemporaries in western Iran and the Fertile Crescent. Sebüktegin had been a *ghulam* himself, and the Ghaznavids had no tribe on which they could call for support. At the heart of the army there was a comparatively small force of some 4,000 *ghilman*, mostly Turks of slave origin. In addition to this full time professional nucleus there were numerous other troops: in 414/1023 Maḥmud is said to have reviewed 54,000 men and 1,500 elephants at Ghazna, though this was probably exceptional.¹⁵

As with later 'Abbasid administration, which it imitated in many ways, the Ghaznavid civil administration was sharply differentiated from the military. It was staffed by Persians steeped in the traditions of Persian bureaucracy and Arabic literary culture. At the same time, Ghaznavid administration seems to have been more systematic and developed than that of most contemporary regimes in the Middle East. There were five main *dīwans*, the most important of which were the *dīwan i risalat* dealing with correspondence and the *dīwan i 'arīd* concerned with the military. In many ways, as Niẓām al Mulk recognised, the administration of the Ghaznavids laid the foundations for later Saljuq systems but, like Saljuq administration, it was fairly fluid, with different officials exercising the same offices in many different ways. Like the Samanids who preceded them, but unlike their Buyid contemporaries in western Iran, the Ghaznavid court used Persian as the language of administration and culture. The leading court poet al 'Unṣurī (d. 431/1039f.) wrote in Persian and the court of the Ghaznavids was chronicled in Persian by Abu 'l Faḍl Bayhaqī (d. 470/1077), while his older contemporary Abu 'Alī Miskawayh (d. 421/1030) wrote the history of the Buyids in Arabic.

Much of this splendour was financed by Maḥmud's most famous military exploits, his raids into India, which became almost annual winter expeditions. The object of the military forays was not permanent conquest, or even the spread of Islam among the conquered populations. The element of prestige was certainly important: being a *ghazī* (warrior for the faith) prince and leading the Muslim armies against the Hindu idolators was an important way for Maḥmud to assert his legitimacy as a Muslim ruler and answer the claims of critics and rebels within the Muslim world. News of his victories was always sent to Baghdad, where it was publicised and new honorific titles were

¹⁵ For the numbers of troops in the Ghaznavid armies, see Bosworth, *The Ghaznavids*, pp. 126–8.

awarded in return. Like his older contemporary in al Andalus, al Maṣṣur ibn Abī ‘Āmir, he used the *jihad* as a way to legitimise political authority acquired by brute force. But it was above all the constant need for money to pay the army and maintain the court that drove Maḥmud. The Ghaznavids paid their armies in cash, and the need for funds usually seems to have dominated Maḥmud’s actions. In areas such as Khurasan, already under Ghaznavid control, this took the form of sweating their assets ruthlessly by imposing heavy and oppressive taxation, to the great distress of their inhabitants. The plains of Hindustan (today Pakistan and northern India) and its rich temples offered the possibility of plunder and of serving the cause of Islam.

Muslim penetration of the Indus Valley had begun in Umayyad times with the expedition of Muḥammad ibn Qasim al Thaqafī in 90 2/709 11. These early Muslim attacks had come by sea or by the long desert route through Makran. The Ghaznavids were the first Muslims to exploit the northern route through the Khyber Pass, and the fact that their bases in Afghanistan were so much closer meant that their attacks were much more devastating. One of Maḥmud’s first objectives was the main Muslim city of Multan, first settled in the second/eighth century. The presence of a substantial Isma‘īlī community in the city meant that Maḥmud could justify his aggression as a campaign against ‘heretics’, and in 401/1010 he deposed the local ruler, Abu ‘l Fath Da‘ud. The Ghaznavid takeover of the city was followed by a massacre of the Isma‘īlīs.

Winter was the campaigning season, and Ghaznavid armies, along with volunteer *ghazīs* attracted from all over the Muslim world, would descend. The next targets were the Hindushahid rulers of the kingdom of Wayhind in the Punjab. Since their domains lay at the foot of the Khyber Pass, they bore the brunt of Maḥmud’s aggression. In 392/1001 Maḥmud won his first great victory when he defeated and captured the *raja* Jaipal in a battle near Peshawar. The struggle was continued by his son Ānandpal, but he too was defeated in 399/1009. Resistance continued until the death of the last Hindushahid, Bhīmpal, in 417/1026, after which virtually all the Punjab was in Ghaznavid hands.

The great Hindu temples were especially attractive because not only did they contain enormous stores of wealth, but Hindus were not People of the Book and could not claim the status of *dhimmīs*, so pillaging their shrines was a religious duty as well as an economic opportunity. In 405/1014 the temple at Thanesar just north of Delhi was sacked, but his most celebrated triumph was the expedition to Somnath on the coast of Gujarat in 416 17/1025 6. When the temple was taken and burned to the ground, the loot is said to have amounted

to the vast sum of 20 million *dīnars*. News of the sack of Somnath spread throughout the eastern Islamic world, and the 'Abbasid caliph sent his congratulations and more honorific titles to Maḥmud. Along with the money and the prestige, the campaigns in India brought back large numbers of captives 53,000 from the expedition of 409/1018 alone, we are told – and they were sold to merchants from all over the Middle East. Others were incorporated into the Ghaznavid armies. Unlike Turkish *ghilman* they were not required to convert to Islam, and in some difficult areas such as Sīstan the Ghaznavids used them against their own Muslim subjects.

Maḥmud's expeditions to India are an interesting example of the use of *jihad* as an instrument of state policy. The campaigns provided legitimacy for Ghaznavid rule, and the sultan became a hero of Islam. It is probable that the booty provided the resources to maintain the army and build mosques in Ghazna and the vast palace at Lashkar i Bazar on the Helmand river in southern Afghanistan. The campaigns, however, did little to spread Islam or Muslim power in the Indian subcontinent. The Ghaznavids made no effort to hold onto the areas they raided, and there is no evidence for widespread conversion of the local population to Islam.¹⁶

Maḥmud died in 421/1030. The obvious successor was his son Mas'ud, who had had considerable military experience, having recently distinguished himself in the struggle against the Buyids, and was governor of Herat. However, Maḥmud passed him over in favour of another son, Muḥammad, who was in Ghazna at the time of his father's death. Mas'ud had the advantages of experience and reputation and, with the support of senior members of the family and commanders of the army, he was able to seize power from his hapless brother. Like his father, the new sultan was an energetic warrior, but he was also a suspicious and difficult man, surrounding himself with cronies and unwilling to accept unpalatable advice.

The account of his reign by the historian Abu 'l Faḍl Bayhaqī casts a clear and often cruel light on the sultan and his court, but he also describes the splendour with which Mas'ud used to dazzle his subjects. The historian describes him at one great *majlis* (formal reception) on his golden throne, with his crown suspended on a golden chain above his head and wearing a cloak of crimson so heavily embroidered with gold that almost nothing of the original material could be glimpsed. 'All around the hall, standing against the panels, were the household *ghilman* with robes of Saqlaṭunī [apparently

¹⁶ For the early history of Islam in India see A. Wink, *Al Hind: The making of the Indo Islamic world*, 3 vols. (Leiden, 1990–2004).

of unknown origin] Baghdādī and Iṣfahānī cloth, two pointed caps, gold mounted waist sashes, pendants and golden maces in their hands. On the dais itself, to both left and right of the throne, were ten *ghilman*, with four sectioned caps on their heads, heavy, bejewelled waist sashes and bejewelled sword belts.' After describing more groups of *ghilman* and their golden bejewelled accoutrements, he describes the celebrations.

The great men of state and the holders of high ranks came forward. Enormous quantities of largesse were distributed. The prominent people, governors and great men were invited to sit on that dais and the Amīr [Mas'ūd] held court, seated on his throne, until morning when the *nadīms* [boon companions] came in, and distributed largesses. Then the Amīr rose, mounted and made off to the garden. He changed his robes, rode back and sat down to feast in the splendidly adorned hall. The nobles and great men of the state came forward to the table too. Other tablecloths were spread outside the hall, to one side of the palace and groups of the army sat down there and began to eat. Musicians struck up and wine flowed like water so that, gradually, those who had become drunk left the tables. The Amīr rose up from the table in a mood of great joy, mounted and rode off to the garden.¹⁷

Such were the pleasures of wealthy monarchy, and it is worth remembering that his Buyid contemporary in Baghdad, Jalal al Dawla, was so poor that he could not pay his servants or feed his horses. No wonder the courts of the Ghaznavids achieved such fame in the Muslim world.

In the early years of his reign Mas'ūd was able to pursue the same aggressive policies as his father had done. Further conquests were made in India, and in 429/1037f. he personally led an expedition which took the fortress of Hansī near Delhi. But all was not well with the Ghaznavid army in India. Aḥmad Inal Tagīn, whom he had appointed to command the Ghaznavid garrisons, led a rebellion among the Turkish *ghilman* stationed in the Punjab. Mas'ūd was obliged to rely on an Indian commander called Tilak to crush the rebellion in 425/1034.

While Mas'ūd was able to continue an aggressive policy in India, the position was very different in Khurasan. Already by Maḥmud's time, Ghaznavid rule had been resented for its brutality and harsh taxation. Furthermore, even Maḥmud had been unable to take the Transoxanian cities of Bukhara and Samarqand and the Farghana valley from the Qarakhanids, who always provided a focus for rivalry and opposition. Maḥmud's conquest of Khwarazm had helped to neutralise this threat, but under the strong rule of 'Alī Tegīn the Qarakhanids

17 Bayhaqī, *Ta'rīkh i Mas'ūdi*, in Bosworth, *The Ghaznavids*, pp. 136 7 (slightly abridged).

once again became a real threat to Ghaznavid power. Mas'ud's problems were compounded by his own suspicious nature. The *khwarazmshah*, Altuntash, appointed by his father, had always proved a loyal ally against the Qarakhanids, but Mas'ud resented his semi independent power and large army, and made an attempt to assassinate him. When Altuntash was killed in 423/1032, still fighting for the Ghaznavids against 'Alī Tegīn, his son Harun swiftly changed sides, allying himself with the Qarakhanids against the Ghaznavids. In 425/1034 Harun and 'Alī Tegīn launched a joint campaign to drive the Ghaznavid forces out of Transoxania. Mas'ud had Harun assassinated and 'Alī Tegīn died in the same year of natural causes, but Harun's brother and 'Alī Tegīn's sons continued the fight, and the lands of the lower Oxus were lost to the Ghaznavids for ever.

If they had only had to contend with the Qarakhanids, the well equipped Ghaznavid armies might have prevailed, but there was a new, much less conventional, threat that they had to face. This is not the place to give a full account of the origins and growth of Saljuq power, but we need to recount the stages by which these bands of impoverished and apparently disorganised nomads effectively defeated the most powerful army in the eastern Islamic world.

The Ghuzz tribesmen, who formed the foundation of Saljuq power, first entered Ghaznavid territory in 416/1025 when the men of 4,000 tents asked to be able to use the pastures in the areas of Sarakhs and Abīvard, in return for which they would guard the frontiers against other nomads. Inevitably friction arose between the nomads and the people of the towns and villages in the area, and just three years later Mas'ud had to lead in person an expedition to disperse them. Some fled west where they entered into service with the Buyids and other western Iranian dynasts, while others went back across the Oxus to join the Saljuq leaders, Tughril Beg and Chaghri Beg, now allies of the Qarakhanids. After the death of 'Alī Tegīn the Saljuqs were threatened by the power of another Ghuzz leader, Shah Malik, from the steppes around the lower reaches of the Jaxartes river. Defeated and destitute, some 10,000 of them petitioned Mas'ud to be allowed to enter his lands and, once more, to take service as frontier guards. This time Mas'ud was resolute in his refusal, determined to crush the unruly Turkmen once and for all; but the armies he sent against them were defeated, and by 428/1037 the Saljuqs were demanding that Sarakhs and the great city of Marw itself should be granted to them. The Turkmen became increasingly bold, pasturing their flocks throughout the settled lands of Khurasan as far west as Nishapur, which they occupied in 429/1038.

The Saljuqs did not take these great cities by siege or by force; they did not have the forces to do that. Local elites chose to make agreements with the

Saljuq leaders rather than rely on the sporadic and ineffective protection offered by Mas'ud in distant Ghazna. At this time both Marw and Nishapur were prosperous cities, and the new suburbs that had sprung up since the Muslim conquests were unwallled. There were no local military forces and, in the absence of the sultan's army, making peace was the only sensible option.

Mas'ud remained determined to crush the nomads. In 430/1039 his armies defeated the Turkmen at Sarakhs and retook Nishapur. The next year he mounted another campaign with the intention of driving the Turkmen from the steppes around Marw. A large army, including elephants, set out across the semi desert from Sarakhs, but at the isolated desert city of Dandanqan they met a group of some 16,000 Turkmen. The Ghaznavid army, weakened by thirst and exhaustion, was cut to pieces, the survivors fleeing back towards Ghazna in complete disarray. Mas'ud himself retired to his capital, where he carried out a purge of all those whom he blamed for his defeat. He then seems to have decided to abandon Iran altogether and retreat to India, but his troops mutinied and he was killed in 432/1040.

Mas'ud was succeeded by his son Mawdud who took over in Ghazna, and the dynasty survived for the next 130 years in eastern Afghanistan and the Punjab. Nonetheless, the battle of Dandanqan marked a major turning point in the history of Iran. The Ghaznavids could not hope to retrieve their position in Khurasan, and the Saljuqs were accepted, even welcomed, by the towns people of the cities they had once ruled.

The Kurdish dynasties

Kurds had inhabited much of the area of the Zagros mountains and the uplands to the north of Mosul for many centuries before the coming of Islam.¹⁸ Like the Daylamites, however, they had only played a marginal part in the politics of the Islamic state until the fourth/tenth century, being mentioned as rebels or mercenaries in the chronicles. The failure of centralised 'Abbasid government, coinciding with the spread of Islam among the Kurdish tribes, however, allowed the emergence of a number of independent Kurdish principalities alongside, and sometimes in competition with, the Daylamite ones. This Kurdish efflorescence survived until the coming in the

¹⁸ On the geography of Kurdish settlement in this period, see I. C. Vanly, 'Le déplacement du pays kurde vers l'ouest', *RSO*, 50 (1976); for a general political history, see Hugh Kennedy, *The Prophet and the age of the caliphates*, 2nd edn (London, 2004), pp. 248–64.

430s/1040s of the Ghuzz Turkmen, who sought to take over their pastures and effectively squeezed them out of many of their traditional areas.

The main Kurdish dynasties which emerged in the second half of the fourth/tenth century were the Ḥasanwayhids and 'Annazids of the central Zagros, the Rawwadids and Shaddadids of Azerbaijan and the Marwanids of south eastern Anatolia. They were based in different areas and never developed any common political ties, but they had much in common. All emerged in mountainous regions, the natural pasture grounds of the Kurdish tribes, and many were based on the great transhumance routes between summer and winter pastures. On the whole their administrations were primitive; some, such as the 'Annazids in southern Kurdistan and Luristan (381/991 to c. 500/1107), seem to have lacked any bureaucratic structures at all. But the picture is not one of chaos and anarchy, as might at first appear. Some of the Kurdish rulers, notably Badr ibn Ḥasanwayh (r. 370–404/980–1013 in the Central Zagros around Qarmaṣīn/Kīrmanshah) and Naṣr al Dawla the Marwanid (r. 401–53/1011–61 in Amida and Mayyafariqīn), left reputations for good government which few of their contemporaries could match. Equally telling are the good relations Kurdish leaders frequently developed with leading citizens of the towns in their domains, frequently working in partnership with them. The collapse of 'Abbasid rule allowed local elites to emerge, and it is fascinating to see how the people of each area developed their own political solutions, a pattern of variety and local autonomy soon to be extinguished by the coming of the Turks. At Amida (Diyarbakr) for example, real power in the city was exercised by the *qaḍī* Ibn Damna, a member of a prominent local family who agreed to pay a tribute to the Marwanid ruler in exchange for effective autonomy for the city and its inhabitants. Even after his death in a domestic intrigue in 415/1024f., the Marwanids were obliged to accept the authority of his successor as *qaḍī*, Ibn Baghl.

In the mid fourth/tenth century the Kurds were distributed all along the Zagros chain from Fars in the south to Azerbaijan and the Araxes river in the north. They were also influential in south east Anatolia as far west as Amida and northern Syria. They were largely sheep rearers who exploited the pastures of the high Zagros and eastern Anatolia in the summer and the warm plains of Iraq and al Jazīra in the winter. The Hadhbānī Kurds, one of the most powerful tribes in the period, are described as spending the summer in Azerbaijan around the area of Salmas, north east of Lake Urmīyya, and the winter on the plains along the Greater and Lesser Zab rivers east of Mosul. Not all Kurds, however, were transhumant shepherds, and their leaders often seem to have maintained fortresses along the migration routes where their

valuables were kept and where they could take refuge in time of danger. There were Kurdish populations in many of the small towns of the mountain area such as Shahrazur and Salmas, and there were also Kurds who lived in villages; the Marwanid rulers of Mayyafariqīn came from a family who were headmen of a village near Sī'ird (modern Siirt). With the decline of 'Abbasid power, leaders of the Kurdish tribes came to assume military control in the areas they moved through and became effectively independent rulers while still acknowledging the theoretical overlordship of the caliph.

The Kurdish dynasts all based their power on the military prowess of the Kurdish tribesmen. They never needed to employ Turkish *ghilman*, as the Buyids did, because they provided mounted soldiers from their own ranks. The rise to power of the Kurdish dynasties also changed the political geography of the area: the 'Abbasid, Buyid and Ḥamdānid states were all based on cities and their surrounding agricultural land. By contrast, the power of the Kurdish rulers (with the possible exception of the Shaddadids (340–468/951–1075 in Ganja and Dvin in Armenia) was based on their control of the transhumance routes, and it was the valleys of the Zagros and anti Taurus that formed the nucleus of these states. This was not because they were especially rich and fertile and thus produced high tax yields, but because it was there that the tribesmen passed on their biannual migrations. The relationship of the Ḥasanwayhids with the town of Hamadnan, like the relationship of the Marwanids with Amida or the Shaddadids with Dvin and Ganja, was based on indirect influence rather than direct control; the Shaddadids and the Marwanids especially established close links with local, non Kurdish urban elites. The administration of the Kurdish states tended to be very basic; the Marwanids employed viziers, but there is no indication that the other groups employed any bureaucrats at all: the cities paid an agreed tribute, and for the rest, the traditional mechanisms of tribal authority were sufficient. The *ḥimaya* (protection agreement) was the underlying basis of government.

This Kurdish ascendancy was soon threatened, as elsewhere in the Zagros and southern Anatolia. As early as 420/1029 these pasture hungry nomads had reached Maragha and killed a number of Kurds. Thereafter the pressure from Turkish tribes was almost continuous. The Turks, by the arrival of the Ghuzz Turkmen tribes, precursors of the Saljuqs, were much more of a threat to the Kurds than their traditional rivals, the Daylamites or the Armenians, had been. Daylamites and Armenians, being settled farmers, could coexist with transhumant pastoralists such as the Kurds; clearly there were sometimes clashes of interests when flocks strayed into cultivated fields, for example but these could be adjudicated. The Turks, on the other hand, were sheep rearing

nomads, in direct competition for the rich summer grazing on the mountain uplands, and the days of Kurdish dominance were accordingly numbered. The Saljuqs took control of the 'Annazid lands in the Central Zagros in 447/1055, and the Rawwadid capital at Tabriz in 463/1071. In 468/1075 they took control of Shaddadid lands in Azerbaijan, and the Marwanids of Diyarbakr were extinguished by the armies of Malik Shah in 478/1085.

The Bedouin dynasties¹⁹

The Muslim world had come into being because lands from Central Asia to North Africa had been conquered by armies largely made up of Arab Bedouin tribesmen. In the first century and a half of Muslim rule, Bedouin – or at least the descendants of men who had been Bedouin – formed an important part of the ruling class. There had always been Bedouin who had refused to pay taxes or accept the authority of the caliphs, both Umayyad and 'Abbasid, and formed themselves into Kharijite bands. From the third/ninth century, however, the Bedouin were increasingly excluded from the rewards of being part of the ruling elite. No longer receiving military salaries or government subsidies, some began to resort to more ancient methods of extracting revenues from settled populations. We begin to hear of Bedouin disturbances in the Hijaz during the reign of al Muqtadir, suppressed by Turkish soldiers sent from Baghdad. At the same time, the Bedouin also began to attack pilgrim caravans crossing Arabia from Iraq to Mecca and Medina, a clear sign that they felt they were not benefiting from this traffic. In the early fourth/tenth century many of them joined the religio political movement known as the Qaramiṭa (Carmathians)²⁰ and launched devastating attacks on the pilgrim caravans and even on important Iraqi cities such as Baṣra (sacked in 311/923). By the end of al Muqtadir's reign (320/932) they were a real threat to the existence of the 'Abbasid caliphate. The alienation of many Bedouin from the Islamic state their ancestors had helped to create was virtually complete.

With the collapse of the Qaramiṭa in the 350s/960s and the weakening of Buyid and Ḥamdanid power in the 370s and 380s/980s and 990s, the chiefs of the larger Bedouin tribes began to establish themselves as independent rulers. A number of dynastic polities were founded in which the ruling families were chiefly by lineages of Bedouin tribes, and the tribesmen provided the military muscle. The important cities of Mosul and Aleppo were

¹⁹ For a general account see Kennedy, *Prophet and the age of the caliphates*, pp. 283–306.

²⁰ See chapter 8 above.

ruled by men such as Ṣāliḥ ibn Mirdas al Kilabī (d. 415/1024) and Qirwash ibn al Muqallad al ‘Uqaylī (d. 442/1050), whose power ultimately derived from their status as tribal chiefs, a position usually inherited from their fathers or other members of their kin. In other areas of the Fertile Crescent, from southern Iraq to Palestine, we find Bedouin tribes and their leaders establishing or attempting to establish small independent states. The Banu ‘Uqayl of Mosul (c. 380–478/c. 990–1093), the Banu Mirdas of Aleppo (415–72/1024–80), the Banu Asad (Mazyadids) in the Kufa area from around 350/961 to 558/1163 and the Numayrīs in Ḥarran (380–c. 474/1081) are all examples of tribes that came to dominate important towns and establish independent dynastic polities. Other large and influential tribes such as the Banu Kalb in the Damascus area and the Banu Ṭayy in southern Palestine failed to achieve control over major urban centres, largely as a result of Faṭimid military intervention, and never established settled states.

The Qaramiṭa had profoundly affected the balance of power among the tribes in the north Arabian and Syrian deserts, and in the main it was tribes that had been involved in the movement that came to dominate the area. Now, however, they did not do so in the name of a religious ideal but for their own tribal interests, and they were led not by missionaries from the settled peoples but by their own tribal shaykhs. Kilab and ‘Uqayl had been the leading supporters of the Qaramiṭa of Baḥrayn, and it seems that in the second half of the fourth/tenth century many of them, disillusioned with the decline of the power of the movement, drifted north to join fellow tribesmen already established in the hinterlands of Mosul and Aleppo. The influence of the Kalb in central Syria had probably been consolidated by their leading role in the rebellion of the Syrian Qaramiṭa, while the Ṭayy seem to have moved from northern Arabia to Palestine during the last waves of Qaramiṭi attacks on the area. Of the tribes that founded Bedouin states at this period, only the Asadīs in the Kufa area had played no part in the movement.

The founders of these Bedouin states all owed something to the patronage of rulers of settled states. The Mirdasid chiefs of Kilab owed much of their predominance in northern Syria to the support given them by Sayf al Dawla the Ḥamdanid (d. 381/991). The primacy of the ruling clan of the ‘Uqayl was greatly aided by the Buyid ‘Aḍud al Dawla, who made them responsible for the disciplining of their fellow tribesmen. It was the attempts of the last Ḥamdanids to counter the influence of the Kurds in the Mosul area by granting lands to the ‘Uqaylids that ensured their control of northern Iraq. Equally, the Mazyadid leaders of the Asad tribe owed much to the patronage of Bakhtiyar (d. 367/978) and later contenders for power in Buyid Baghdad.

who sought their support, while Ibn Ustadh hurmuz (Buyid governor of Baghdad, 392–401/1002–10) was to rely on them to discipline the Bedouin of the area. None of the dynasties would have achieved power without the patronage of settled rulers.

The dynasties that prospered were only able to do so because they had access to the revenues of towns and settled areas with which to reward their followers. The power of 'Uqaylid rulers lay in their tribal following, but it was control of Mosul that brought them the wealth these followers needed. Ṣaliḥ ibn Mirdas was simply one of a number of Kilabī chiefs until he took possession of Aleppo, a position which assured his primacy in the tribe. In the desert a nomad state was impossible since no chief could command absolute authority. Contact with settled powers and peoples enabled some ruling clans to establish themselves as effective dynasts, even while retaining a nomad lifestyle. The possession of the revenues of settled lands also helped the chiefs to increase their tribal following. The dominant position of the 'Uqayl in northern Iraq looks at first glance to have been the product of a vast influx of tribesmen from Arabia, and there certainly were new immigrants from northern Arabia at this time; but it may also be, although it is hard to find specific examples, that many of the members of these newly dominant tribes in fact came from other groups and had attached themselves to the successful tribe, adopting their names and thenceforward being counted among the 'Uqayl or Kilab.

In economic terms, the changing relationships between the nomads and the settled population can be seen in the laments of numerous sources about the decline of settled agriculture and the occupation of farmland by the Bedouin. The areas worst affected were probably Transjordan, where almost all urban and much village life seems to have come to an end at this time, the Ḥawran, south of Damascus, and the northern Jazīra, where Ibn Ḥawqal describes the process most clearly. It is probable that other areas on the desert margins of Syria and Iraq were also affected. There can be no doubt that the century 950–1050 saw a vast increase in the area used for nomad pasture and the collapse of the agricultural economy in districts that had once been the granaries of the 'Abbasid caliphate.²¹ It would be wrong to present a purely negative view of these changes. There were cities that benefited from the Bedouin ascendancy; Aleppo seems to have been more prosperous under the Kilabī Mirdasids than

²¹ See for example the collapse of the irrigation systems of the middle Euphrates valley described in Sophie Berthier, *Peuplement rural et aménagements hydroagricoles dans la moyenne vallée de l'Euphrate, fin VIIe–XIX siècle* (Damascus, 2001), esp. pp. 161–70.

it had been under the Ḥamdanids. It may have been that tax levels were lower under Bedouin rule than under regimes such as the Buyids or Ḥamdanids with their expensive *ghilman* to pay. Certainly the city that suffered the best documented urban crisis in this period, Baghdad, was never under Bedouin control, while nearby Ḥilla, 'the camp' of the Mazyadid clan of the Banu Asad, developed into a flourishing city which has remained one of the main towns of central Iraq to the present day.²²

The rise and fall of a Bedouin dynasty can be observed in the history of the 'Uqaylids of Mosul.²³ The Banu 'Uqayl are found in al Jazīra from Umayyad times, but until the death of the Buyid 'Aḍud al Dawla in 372/983 they were subject to the authority of the Ḥamdanids or the Buyids. In the confusion that followed the great man's death, the 'Uqaylī chief Muḥammad ibn al Musayyab was able to make himself master of the city of Mosul in 386/996. The chiefs did not, however, live in the city but exercised power from the nomad camps. An attempt by one member of the ruling family, al Muqallad ibn Muḥammad, to establish himself in the city and recruit Turkish *ghilman* in fact, to make the 'Uqaylids into a settled dynasty like the Ḥamdanids or Buyids met with failure in the face of opposition from his fellow tribesmen. In 391/1001 leadership of the tribe was assumed by Qirwash ibn al Muqallad, who was to reign until 441/1049. During this half century his main priorities were to preserve his political independence and ensure access to sufficient summer and winter pastures for his tribesmen. He lived in his camp and seldom visited Mosul or any of the other towns that paid him tribute. The most dangerous and persistent of his enemies were the rival Bedouin chiefs of the Khafaja and Asad tribes to the south, who challenged 'Uqaylid access to winter grazing. In contrast, the 'Uqaylids had generally good relations with the Kurds in the mountains to the north, with whom they were not in competition for resources.

The 'Uqaylids are sometimes described as a Shī'ite dynasty, but this gives a rather misleading impression. In fact, Qirwash and his followers seem to have paid little attention to the demands of formal religion. It is true that in 401/1010 Qirwash had his allegiance to the Faṭimid caliph al Ḥakim proclaimed in the mosques of the cities under his control, which at that time included Mosul, Anbar, Kufa and al Mada'in. However, in the absence of any military support from Cairo he soon abandoned this attempt at independence and reverted to his allegiance to the 'Abbasids.

22 G. Makdisi, 'Notes on Ḥilla and the Mazyadids in medieval Islam', *JAOS*, 74 (1954).

23 On whom see H. Kennedy, 'The Uqaylids of Mosul: The origins and structure of a nomad dynasty', *Actas del XII Congreso de la UELI* (Madrid, 1986), repr. in H. Kennedy, *The Byzantine and Islamic Near East* (Aldershot, 2006), XIII.

Like all the other states in the area, the 'Uqaylids were challenged by the arrival of the Ghuzz Turks. At first things went badly for the 'Uqaylids, and in 433/1041f. the Turks took Mosul. However, the newcomers were in direct competition for pasture with both Kurds and Arabs, and Qirwash was able to put together a coalition which inflicted a major defeat on the Turks in Ramaḍān 435/April 1044, a victory which effectively ensured that the plains of northern Iraq should remain in Arab, rather than Turkish, hands. Qirwash's most important successor, Muslim ibn Quraysh (453–78/1061–85), was able to maintain his independence for a while by playing off Fāṭimids and Saljuqs, but after his death in battle the Saljuqs gradually asserted their authority, and in 486/1093 the city was taken by Tutush ibn Alp Arslan.

Sunnism and Shī'ism

The period from 945 to 1050, which we can call that of the Muslim commonwealth, was in some ways a period of dissolution and disintegration, and the elaborate and powerful state structures so admired by many historians collapsed. But at the same time it was like fifteenth century Italy, in that great political diversity went along with immense cultural achievement. It was also a time when many provincial centres acquired their own Muslim identity for the first time.

It was also a period when religious divisions within the Islamic community hardened. Perhaps the most important and long lasting development within the Islamic *umma* during this period was the formalisation of the divisions between Sunnī and Shī'ite branches in the Muslim world. It would be fair to say that in 900 many Muslims did not consider themselves either Shī'ite or Sunnī. It is true that many Muslims venerated the house of 'Alī, and that some fervently believed that only with the accession to power of a member of that house could a truly just Muslim society be established. There was no body of Shī'ite ritual, however, which distinguished its adherents from other Muslims, and no distinctively Shī'ite festivals.

It was in Baghdad during the period of Buyid rule (945–1055) that 'Twelver' Shī'ism developed more distinctive religious practices and a clearer sense of communal identity.²⁴ The last of the widely acknowledged imams of the house of 'Alī, al-Ḥasan al-'Askarī, died in Samarra' in 260/874, leaving no

²⁴ For the history of Shī'ism in general, see H. Halm, *The Shi'ites*, 2nd edn (Princeton, 2007). On the history of early Shī'ism, S. H. M. Jafri, *The origins and early development of Shi'a Islam* (London, 1979).

generally accepted heir. During the course of the fourth/tenth century, however, it came to be believed among the Shī'a that he had left a son who had remained hidden and never died, but would come again to establish the rule of true Islam. Meanwhile, he had left representatives in the world to guide the faithful in his absence. Acceptance of the imam remained, however, fundamental to true belief, since he was the *ḥujja*, the proof of God, without whom there could be no Islam. This theory of the imamate was developed in Baghdad by such scholars as al Kulaynī (d. 329/940f.) and above all al Shaykh al Mufīd (d. 413/1022), who produced the view of the imamate generally held by Twelvers down to the present day. Despite the violence and the economic problems of the former capital city, this intellectual activity was centred on Baghdad, especially on the old commercial quarter of al Karkh, which became the main stronghold of the Shī'a, and scholars from all over the Muslim world, such as the famous Muḥammad ibn al Ḥasan al Ṭūsī (d. 460/1067) from Khurasan, were attracted to the city.

This newly emerging Shī'ism was not formally the state religion of the Buyids (in the sense that Isma'īlī Shī'ism was in the Faṭimid caliphate). Remote Daylam, the original homeland of the dynasty, was an area in which members of the 'Alid family had sought refuge and made converts, and the Buyids were, in some sense, Shī'a. They made no attempt, however, to replace the 'Abbasid caliphs with rulers from the house of 'Alī. There were good practical reasons for this. Such a move would have alienated many in Iraq and western Iran who were otherwise prepared to accept Buyid rule in exchange for a measure of peace and security. It would also have meant finding an imam from the house of 'Alī, and such an imam might well have wanted to take real power in his own name. However, Shī'ite scholars were given some support by figures at the Buyid court, such as the vizier, Sabur ibn Ardashīr, who established a major Shī'ite library in al Karkh in 381/991f. The scholars were also patronised by rich local families of 'Alid descent who were in many cases close to the Buyid court, such as the *sharīfs* al Raḍiyy (d. 406/1015) and al Murtaḍa (d. 436/1044). While some Buyid rulers, notably 'Aḍud al Dawla (d. 372/982), seem to have discouraged speculation that might divide the Muslim community, others at least tolerated it and allowed their courtiers to provide patronage for the needy intellectuals involved.

New elements distinguished the Shī'a from other sects, specifically its distinctive and exclusive religious observances. These included the public denigration of the first two caliphs (Abu Bakr and 'Umar), who were held to have usurped the rights of 'Alī, and the development of certain particularly Shī'ite public festivals. The most important of these festivals was the

mourning for al Ḥusayn on 10 Muḥarram and the celebration of Ghadīr Khumm on 18 Dhu al Ḥijja, in commemoration of the event when the Prophet was said to have acknowledged 'Alī as his successor during the Farewell Pilgrimage in 10/632. There also took place the development of the tombs of members of the 'Alid family as centres of pilgrimage. These three elements characterise the development of the mature Shī'ism of the fourth/tenth century as distinct from the reverence for 'Alī or support of 'Alid pretenders to the caliphate which had been common in previous centuries. This Shī'ism was basically quietist in that its adherents did not demand the immediate installation of an 'Alid as caliph, nor did they feel that they had to take up arms to achieve this. The three distinguishing features of the new Shī'ism described above were all essentially public acts, and at least two were exclusive; while any Muslim could accept the veneration of the tomb of 'Alī, if not those of all his descendants, no one could accept the celebration of Ghadīr Khumm or the cursing of the first two caliphs without cutting himself off from a large number of other Muslims. Sectarian tension between supporters and opponents of the house of 'Alī had been increasing in Baghdad before the coming of the Buyids, but the policies of Mu'izz al Dawla (d. 356/967) and Bakhtiyar (d. 367/978) escalated the situation by taking deliberately provocative positions on the three elements outlined above. From the time of their arrival in Baghdad, the Daylamites became associated with the Shī'ite point of view, and allowed and encouraged the development of a Shī'ite party in the capital, partly to secure the support of at least one constituency among the Baghdad populace. In 351/962 Mu'izz al Dawla provoked public anger by having curses of the first two caliphs painted on walls in Baghdad. In the end his astute vizier, al Muhallabī, persuaded him that only the first Umayyad caliph, Mu'awiya, who had few admirers in Iraq, should be condemned, and so Abu Bakr and 'Umar were spared. In 353/964 Mu'izz al Dawla encouraged the public celebration of the important Shī'ite festivals of 10 Muḥarram and Ghadīr Khumm, to the intense annoyance of many in Baghdad. In the same period the Shī'ite shrines of Iraq and Iran were increasingly revered, and they came to replace Mecca and Medina, increasingly difficult to reach because of the lawless conditions in the Arabian Peninsula, as the goal of pilgrimage for many Shī'a. In 342/953 an officer from Baṣra requested to be buried beside al Ḥusayn at Karbala', and the practice of Shī'ite burial *ad sanctos* soon grew in popularity. On his death in 399/1009, Aḥmad ibn Ibrāhīm al Ḍabbī, the vizier of the Buyid rulers of Rayy, instructed that his body be taken to Karbala' for burial, as

did al Ḥusayn ibn al Maghribī (d. 418/1027), vizier of the Marwanid ruler of Mayyafariqīn. Under Buyid patronage most of the famous Shī'ite shrines were embellished – not only the tombs of 'Alī and al Ḥusayn, but also that of Faṭīma in Qumm and of 'Alī al Riḍa near Ṭus (now known as Mashhad).

A further step in the differentiation of sects within Islam came with the establishment of the Faṭimid caliphate in Egypt in 358/969.²⁵ As long as the Faṭimids, with their claims to be imams directly descended from 'Alī and Isma'īl, were confined to the Maghrib, they did not constitute a serious threat and could be dismissed as provincial dissidents. When they took over Egypt, began to move into southern Palestine and to send missionaries throughout the Middle East, it became essential for the Shī'a of Baghdad to distinguish themselves from these newcomers. The Faṭimids claimed to be caliphs of the entire Islamic world, so it was important for the Buyids too that the Shī'ite ideology they espoused did not accept Faṭimid claims to the imamate.

The tensions between the Sunnī and Shī'ite parties in Baghdad came to a head during the reign of the feeble Buyid ruler Bakhtiyar from 361/972 onwards. A powerful Turkish leader in Buyid service, Sebüktegin,²⁶ diverted the enthusiasm of the Baghdadīs for the *jihad* against the Byzantines into attacking the Buyids and their Daylamite and Baghdadī supporters on the grounds that they were heretics and so legitimate targets for holy war. The Shī'a were fewer in number, and their centre, the al Karkh area, was burned down twice during this period. Miskawayh, a contemporary observer, is quite specific about the nature of the change that resulted: 'the dispute between the two factions [Sunnī and Shī'ite], which had formerly been on religious questions, now became political as well, as the Shī'a adopted the watchword of Bakhtiyar and the Daylamites while the Sunnīs adopted that of Sebüktegin and the Turks'.²⁷ The fighting resulted in the arming of both factions and the increasing division of the city into fortified quarters, each with its own sectarian character. These divisions persisted after the immediate political quarrel was over, and in the end became permanent.

It was also at this time that the Turks became identified with the anti Shī'ite party. There is no evidence that the Turks of Samarra' in the third/ninth

25 See Yaacov Lev, 'The Fatimid caliphate (358 567/969 1171) and the Ayyubids in Egypt (567 648/1171 1250)', in Maribel Fierro (ed.), *The new Cambridge history of Islam*, vol. II (2010).

26 Not to be confused with the Sebüktegin who founded the Ghaznavid dynasty.

27 Ibn Miskawayh, *Tajarib al umam*, ed. and trans. H. Amedroz and D. S. Margoliouth in *The eclipse of the 'Abbasid caliphate*, 7 vols. (London, 1920 1), vol. II, p. 328.

century had shown any hostility at all to the house of 'Alī, and many of them had supported the Mu'tazilite movement. From Bakhtiyār's reign, however, they became associated with the Sunnī cause, a development which became firmly established in the next century when Turkish rulers such as Maḥmūd of Ghazna and the Saljuqs emphasised their role as champions of Sunnism. The identification of Turkish rulers with Sunnism was to persist throughout the Saljuq and Ottoman periods, outside Ṣafavid Iran.

Throughout the second half of the Buyid period, processions on sectarian feast days and the writing of inflammatory slogans, particularly the cursing of the Companions of the Prophet and the first three caliphs, were to provide flash points for continuing violence. Despite the efforts of determined rulers of Baghdad such as 'Aḍud al Dawla to put an end to the growth of sectarian tension, the divide between the Shī'a and their opponents continued to harden. In the years after the death of 'Aḍud al Dawla in 372/983 those who can now confidently be described as Sunnīs who opposed the claims of the Shī'a were developing their own festivals, notably the feast of the Cave, just eight days after Ghadīr Khumm; in this way the Sunnīs memorialised how the Prophet and Abu Bakr had taken refuge together in a cave during the *hijra* from Mecca to Medina, emphasising the unique closeness of the first caliph to Muḥammad. Again the processions and public festivities were an occasion for violence.

In the early fifth/eleventh century a new element was added to the deepening divisions between the sects when the 'Abbasid caliphs assumed the role of champion of the Sunnī community. As Buyid power in Baghdad decayed, so the 'Abbasids began to explore ways of increasing their power and status. The 'Abbasid caliphs became firmly attached to the Sunnī cause, and they were encouraged in this by the rising power of Maḥmūd of Ghazna, who linked himself firmly to the Sunnī, anti Buyid position.

The last decades of Buyid rule in Baghdad, despite the political chaos, witnessed a religious development which was to affect the whole subsequent history of Islam: the so called Sunnī revival.²⁸ This was not, in fact, so much of a revival as the formulation and definition of Sunnism in response to the contemporary emergence of Imamī (Twelver) Shī'ism. The new Sunnism was based on the ideas of the *muḥaddithun* (Traditionists), first developed in the third/ninth centuries. They had held that the traditions of the Prophet (his *sunna*) were the only true foundation of Islamic law and religious practice, and

²⁸ See G. Makdisi, *Ibn 'Aqīl et la résurgence de l'Islam traditionaliste au XI siècle* (Damascus, 1962).

that no imam, whether descended from 'Alī or not, should presume to interfere. In Baghdad this division was intensified by political strife: while Shī'ism was intermittently patronised by the Buyids and their representatives in Baghdad, the lead in the elaboration of Sunnism was taken by the 'Abbasid caliph.

The caliph al Qadīr (r. 381/422–991/1031) worked to codify a Sunnī doctrinal and ritual position to counter that of the Shī'a and to strengthen his position against the absent Buyid ruler of Baghdad, Baha' al Dawla. His first opportunity came in 394/1003 when Baha' al Dawla was rash enough to propose a leading member of the family of 'Alī, Abu Aḥmad al Musawī, as chief *qaḍī* in Baghdad. For the first time the 'Abbasid caliph put himself at the head of the popular protest and, successfully, refused to accept the nomination. Thereafter he began to defend the cause of the Traditionists against the claims of Twelver Shī'ism. He did, however, find common ground with the Buyids in his opposition to the claims of the Faṭimids, and so established himself as spokesman for both Sunnīs and Twelver Shī'a.

The death of Baha' al Dawla allowed him more scope. In 409/1018 he took a major step, issuing a decree which condemned Mu'tazilism and Shī'ism and asserted that the Companions of the Prophet and all the first four caliphs should be venerated by 'true' Muslims. These doctrines were repeated and elaborated in 420/1029 when the doctrine of the createdness of the Qur'an was explicitly condemned. This creed, the so called *al Risalat al Qadiriyya*, marks a fundamental development for two reasons. The first was because Sunnism was defined explicitly and positively. Hitherto, the supporters of the *sunna* had largely been defined by their opposition to the claims of the Twelver Shī'a; now there was a body of positive belief which had to be accepted by anyone claiming to be a Sunnī. Like the Twelver doctrines developed during the previous century, it was exclusive; the acceptance of the veneration of the first four caliphs meant rejecting the claims of the Twelvers that 'Alī had been unjustly deprived of the caliphate. It was no longer possible to be simply a Muslim: one was either Sunnī or Shī'ite.

The second important development was that the 'Abbasid caliph had emerged as spokesman for the Sunnīs. The early 'Abbasid caliphs were not, in the classical sense, Sunnī; an important part of the 'Abbasid claim to the caliphate was dependent on a recognition that the family of the Prophet, of which they could claim to be a branch, had a unique claim to leadership. They usually opposed the claims of the 'Alids to political power, but that did not make them Sunnīs. As part of their attempted rapprochement with the 'Alids, al Ma'mun and his immediate successors had espoused or sympathised with

the Mu'tazilite doctrines which al Qadir explicitly condemned. By his action al Qadir had become the champion of the Sunnīs and Traditionists against the claims of Twelver Shī'a and Faṭimids alike. He had also created a new and lasting role for the 'Abbasid caliphate. As Ja'far al Ṣādiq had shown in the second/eighth century, it was possible to be an imam from the house of 'Alī without taking an active role in politics or making claims to the caliphate, so al Qadir showed that there was a religious role for the 'Abbasid caliphs, a role which they could fulfil despite the fact that their temporal power was non-existent.

Al Qadir was able to take this position because he had more political independence. To begin with, the Buyid emirate of Baghdad had become so weak that it could not afford to take action against the caliph. He could also count on a large body of support in Baghdad itself; the people might not fight to restore the political power of the 'Abbasid caliph, but many of them would support the Sunnī cause against the pretensions of the Shī'a. In addition he received powerful moral support from Maḥmud of Ghazna. He was a fierce opponent of the Buyids on a political level, but he also gave a religious dimension to the conflict by accusing them of being heretics and claiming that he was the champion of Sunnī Islam. He established himself as protector of the *hajj*, a role traditionally played by the caliphs as leaders of the Muslim community. This moral support from the east enabled al Qadir to distance himself from the Buyids. But this did not lead to direct political power. By the time of his death al Qadir had established his moral and religious authority, but the 'Abbasid caliph had no troops to command and no land to call his own beyond the gates of his palace.

By this time Baghdad was firmly divided between the adherents of the two rival religious groups, each armed and defending its own areas. The divisions soon spread to other Iraqi towns such as Wasīṭ and to other parts of the Islamic world. It is probable that the divisions between Sunnī and Shī'ite would have hardened in this period in any case, partly because of the establishment of the Faṭimid caliphate, but there can be no doubt that the political rivalries in Baghdad accelerated and defined the process, not just because sectarian differences were encouraged for local political reasons but because Baghdad remained such an important intellectual centre for Sunnī and Shī'ite alike.

PART III

★

REGIONALISM

Arabia

ELLA LANDAU-TASSERON

The history of the Arabian Peninsula after the shift of the capital of the empire to Damascus is largely neglected by the universal histories. For example, al Ṭabarī mentions in one line the conquest of Oman in 280/893, completely ignoring the major civil war that had led to it. Local sources for certain regions, such as Oman, Ḥaḍramawt and Najd, are very deficient as well.¹ This fact is perhaps the reason for the assumptions sometimes voiced by modern scholars: that the central government was not interested in the Peninsula (except in the holy places), and that its history was largely tribal, cyclical and trivial. As will be shown below, these assumptions may be correct when applied to certain regions, such as Najd and Ḥaḍramawt, but not to others, such as Oman, Baḥrayn and the main parts of the Yemen.

Only a few generalisations may be made. The Peninsula never constituted one province, or one political unit, and its internal administrative and political divisions often changed. From the second/eighth century independent and semi independent polities appeared, and regions underwent cycles of unification and fragmentation. Broadly speaking, society in Arabia, both settled and nomad, remained tribal, and ruling dynasties usually never became full fledged states. The Peninsula in general lacked the features characteristic of other parts of the Islamic world, namely, court society, sophisticated central bureaucracy, highly developed civilisation and a fixed system of raising standing armies. Apart from that, there were great differences between the various regions.

This chapter is divided into four sections, following a certain division into regions: the Ḥijaz, the Yemen, Oman, and Central and Eastern Arabia. Each section opens

¹ Abu Ja'far Muḥammad ibn Jarīr al Ṭabarī, *Ta'riḫ al rusul wa l muluk*, ed. M. A. Ibrāhīm, 10 vols. (Cairo, 1960), vol. X, p. 33; Sa'īd 'Awāḍ Bawazīr, *Ṣafāḥat min al ta'riḫ al ḥaḍramī* (Aden, n.d.), pp. 76, 79; R. B. Serjeant, 'Historians and historiography of Ḥaḍramawt', in R. B. Serjeant, *Studies in Arabian history and civilization*, Variorum Collected Studies X (Aldershot and Vermont, 1981), pp. 241–7; R. B. Serjeant, 'Materials for South Arabian history', *BSOAS*, 13 (1950), pp. 283–4, 289–302; M. A. Cook, 'The historians of pre Wahabī Najd', *SI*, 76 (1992), pp. 163–76. For Oman see below.

with an overview, followed by more detailed information arranged chronologically. When the chronological arrangement was not adequate, it has been complemented by thematic arrangement. The outline of the chapter is therefore the following:

- (1) The Ḥijaz
 - Outline of Ḥijazī history in the first/seventh and second/eighth centuries
 - Administration from the first/seventh to the third/ninth century
 - The special status of Mecca and Medina
 - Sanctity violated: rebellions and disorders in the holy cities
- (2) The Yemen
 - The Yemen from the first/seventh to the end of the second/eighth century
 - Non sectarian dynasties
 - Religious activity and sectarian states
- (3) Oman
 - Oman from the first/seventh to the third/ninth century
 - Oman from the third/ninth to the fifth/eleventh century
- (4) Central and Eastern Arabia: Najd, Yamama and medieval Baḥrayn
 - Central and Eastern Arabia from the first/seventh to the third/ninth century
 - The Qarmaṭīs

Finally, two points should be made. First, there is much more material about the Ḥijaz and the Yemen than about Oman and Eastern Arabia. The sections of the chapter are therefore of varying length. Second, contradictory information is not explicitly discussed in the chapter, but contradictory reports are included in the references.

The Ḥijaz

The Ḥijaz, which lies between the plateau of Najd and the Red Sea coast, is the heart of Arabia, for it is the cradle of Islam and contains the holy cities of Mecca and Medina. Information about these cities in the period discussed here is better than information about other places in the Ḥijaz.²

The Ḥijaz is varied in landscape, containing desert as well as oases of various sizes.³ Accordingly, its population on the eve of Islam was made up of sedentary, nomadic and semi nomadic tribes, most of them pagan but some Jewish and

2 Hamad al Jasir, 'Mu'allafat fī ta'rīkh Makka', *al 'Arab*, 4 (1970); Ḥamad al Jasir, 'Mu'allafat fī ta'rīkh al Madīna', *al 'Arab*, 4 (1969); 'A. 'A. Drees, 'A critical edition of *Ta'rīkh al Madīna* by al Shaykh Qutb al Dīn', Ph.D. thesis, University of Edinburgh (1985), part I, pp. 12–23; Ṣalīḥ Aḥmad al 'Alī, *al Ḥijaz fī ṣadr al Islam: dirasat fī aḥwālīhi al 'umrāniyya wa l idariyya* (Beirut, 1990/1410), pp. 568–91.

3 Detailed geographical description: 'Alī, *al Ḥijaz*, pp. 61–156.

Christian. The main settlements were the three towns, Mecca, Ṭaʿif and Yathrib, and the oases of Khaybar and Fadak to the north of Yathrib. Mecca, which was ruled by the Quraysh tribe, thrived on international or at least trans peninsular trade, whereas the other towns lived off agriculture and local trade. Each of these towns had an array of nomadic and semi nomadic tribal groups attached to it in one way or another. Political, economic and religious leadership lay in the towns, in particular Mecca, and not in the nomadic tribes, even though, generally speaking, the latter were militarily superior.

*Outline of Ḥijazī history in the first/seventh and
second/eighth centuries*

Yathrib was the base of the Prophet's activity after he had migrated there in 622, and it came to be known as Medina. Mecca surrendered to the Prophet in 8/630, and soon Ṭaʿif followed suit. The Prophet recognised the high status traditionally accorded to the dominant sedentary tribes, the Quraysh of Mecca and the Ṭhaqīf of Ṭaʿif. This attitude helped many of the Ḥijazī satellite tribal groups to decide to convert.⁴ The extent of the Prophet's rule in the Ḥijaz cannot be established, but winning the Ḥijaz over to his side was certainly his greatest political achievement. It was mainly Ḥijazī tribes that coalesced around Abu Bakr after Muḥammad's death in 11/632 and that helped him subdue the whole of the Arabian Peninsula; and it was mainly the elite of the Ḥijazī towns, in particular Mecca, that led Islam to become a world religion and that continued for a long time to assume the roles of political and economic leadership in the empire.

In spite of tribal emigration to the conquered territories, the cities of the Ḥijaz were not depleted or relegated to a marginal position during the Rashidun period (11 40/632–61). Medina in particular attracted many new inhabitants, being the political capital of the new empire. Great wealth flowed into the Ḥijaz, and the standard of living rose considerably. As early as 'Umar's reign (r. 13 23/634–44) food supplies from Egypt arrived in Medina and Mecca through the ports of al Jar and al Shuʿayba. 'Uthman (r. 23 35/644–56) reportedly abandoned the port of al Shuʿayba and chose Judda instead.⁵

4 See chapter 6 in this volume. For details about the tribes see 'Alī, *al Ḥijaz*, pp. 177–90; M. F. von Oppenheim, *Die Beduinen*, vol. II, ed. E. Bräunlich and W. Caskel (Leipzig, 1943), pp. 314–16 and *passim*.

5 Ahmad ibn Abī Yaʿqub al Yaʿqubī, *Taʾrīkh*, 2 vols. (Beirut, 1379/1960), vol. II, p. 154; 'Abd al Qadir ibn Muḥammad ibn Muḥammad ibn Faraj al Juddī al Ḥijazī, *al Silaḥ wa l 'udda fī taʾrīkh Judda*, ed. M. al Hudrī (Damascus, Beirut and Medina, 1988), pp. 25–6; Ḥamad al Jasir, *Fī shimal gharb al Jazīra* (Riyadh, 1981), pp. 167–214; 'Alī, *al Ḥijaz*, pp. 429–32. A. Dietrich, 'al Djar', *EL2*, vol. II, p. 454; R. Hartmann and Phebe Ann Marr, 'Djudda', *EL2*, vol. II, p. 571; G. F. Hourani, *Arab seafaring in the Indian Ocean in ancient and medieval times*, (Princeton, 1951), pp. 60–82.

As a result of the assassination of the third caliph, 'Uthman, the capital shifted, first to Kufa (under 'Alī, r. 35 41/656 61), and then to Damascus (under the Umayyads, 40 132/660 750). The Ḥijaz nevertheless remained prosperous. Provisions continued to arrive from Egypt, and the local agriculture was greatly developed as well, being based on the labour of war prisoners sent from the conquered territories. Existing settlements grew and new villages and towns came into being, such as al Rabadha. New crops were introduced, dams were constructed and wells were dug by the government and by private entrepreneurs. Roads were improved, milestones and way marks were set up, and road stations were built. As a result administration, tax collecting, pilgrimage and commerce were facilitated. Economic prosperity, which was occasionally interrupted by crises (for instance during the time of Hisham, r. 105 25/724 43), was accompanied by both intellectual and leisure activities in Mecca and Medina. Such activities are usually associated with courts, but here they developed after the court had moved away. Descendants of Companions of the Prophet, among others, took it upon themselves to hand down his heritage. Thus, Islamic law, theology, tradition (*ḥadīth*), Islamic history and the Prophet's biography (*sīra*) began to develop in the holy cities. Among the most famous Ḥijazī scholars of the first two centuries of Islam were 'Urwa ibn al Zubayr, Ibn Shihab al Zuhri, Ibn Jurayj, Ibn Ishaq, al Waqidī, Nafi' and Malik ibn Anas. At the same time the high standard of living contributed to the growth of social gatherings, poetry and music.

The shift of the court to Iraq in the middle of the second/eighth century did not at first affect the Ḥijaz. The main political, economic and intellectual activities now took place in Iraq, but the first 'Abbasids continued to give their attention to the Ḥijaz, because of its holy places, its political significance and the status of its city dwellers (see below). Heavy damage was sometimes inflicted on Ḥijazī settlements as a result of rebellions, but recovery usually followed. The prosperity of the towns was due not only to the attention of the government but also to the fact that they were largely free of Bedouin pressures. By this time many Ḥijazī tribal groups had migrated, either on their own initiative or because ordered or encouraged to do so by the government. It was only after the middle of the third/ninth century that conditions in the Ḥijaz really deteriorated, as detailed below.⁶

6 Drees, 'A critical edition', part II, pp. 64 93; Juddī, *al Silah wa l 'udda*, p. 26; Ḥamad al Jasir, 'al Rabadha fī kutub al mutaqaḍdimīn', *al 'Arab*, 1 (1966); 'Alī, *al Ḥijaz*, pp. 199 206, 379 434, 441 5, 479 81, for the crops see pp. 157 76; Oppenheim, *Beduinen*, vol. II, pp. 317 20; Sa'd al Rashid, *al Rabadha: A portrait of early Islamic civilization in Saudi Arabia* (Riyadh, 1986).

*Administration from the first/seventh
to the third/ninth century*

Information about the administrative status and divisions of the Ḥijaz is contradictory. Various men are mentioned as governors for the Prophet, for the Rashidun and for Mu'awiya (r. 41 60/661 80) in each of the three towns. Sometimes Mecca and Ṭa'if had one governor, Medina another, and at other times all three cities constituted one jurisdiction, but the Ḥijaz as such does not generally figure as a single administrative unit. The great number of governors indicates frequent replacements, although it may also reflect various versions of historians.⁷ The logic of the various divisions is not always clear. For example, it is reported that the whole of the Peninsula, excepting Mecca and Yemen, was attached to Medina, until Mu'awiya removed Baḥrayn and Oman from the jurisdiction of the Ḥijaz and attached them to Iraq. Yet the area of al Ṭaff, to the west of Kufa (and closer to Kufa than to the Ḥijaz), is said to have paid its taxes to Medina until the time of al Mutawakkil (r. 232 47/847 61). According to other reports Mecca and Medina, and sometimes also Ṭa'if, were joined together with Yamama, or the Yemen.⁸ The different administrative divisions of the Ḥijaz reflect in part changes over time, in part a hierarchy of governors and sub-governors, and perhaps also confusion in the sources. All this is difficult to follow, but some facts seem to emerge out of the plethora of contradictory details. First, Mecca and Medina constituted separate governorships in the early period. Second, the early caliphs attached great importance to the holy cities. Until the middle of the third/ninth century most of the governors were members of the royal family or other people of high standing, mainly Qurashīs. Third, Medina remained an important economic and administrative centre throughout the Umayyad period. The governors often served the private interests of the Umayyad caliphs in agriculture and in business.

Economic crises: Muḥammad ibn Aḥmad al Fasī, *Shifa' al gharam bi akhbar al balad al ḥaram*, vol. II, ed. 'U. 'A. Tadmuri (Beirut, 1405/1985), pp. 429 31; Ibn Zahrā, *al Jami' al latīf*, in F. Wüstenfeld, *Akhbar Makka al musharrafā*, 3 vols. (Göttingen, 1274/1857), vol. II, pp. 309 11. Scholars of the first two centuries: Muḥammad ibn Aḥmad al Fasī, *al 'Iqd al thamin fī ta'rīkh al balad al amin*, ed. M. Ḥ. al Faqī, F. Sayyid and M. M. al Ṭanaḥī, 8 vols. (Cairo, 1378 88/1958 69), *passim*; S. Muṣṭafa, *al Ta'rīkh al 'arabi wa l mu'arrikhun*, vol. I (Beirut, 1979), pp. 149 68; J. Horowitz, *The earliest biographies of the Prophet and their authors*, ed. L. Conrad (Princeton, 2002); H. Motzki, *The origins of Islamic jurisprudence: Meccan fiqh before the classical schools* (Leiden, 2002). Poetry and social life: A. Arazi, 'Sukayna', *ELZ*, vol. IX, p. 802.

- 7 'Izz al Dīn 'Abd al 'Azīz ibn 'Umar Ibn Fahd, *Ghayat al muram bi akhbar saltanat al balad al ḥaram*, vol. I, ed. Fahīm Muḥammad Shaltut (Mecca, 1406/1986), pp. 35 114, 127; 'Alī, *al Ḥijaz*, pp. 61 2; 'A. 'Abd al Ghani, *Umara' al Madīna al munawwara* (Damascus, n.d.), pp. 25 58, 492 4.
- 8 Al Ṭabari, *Ta'rīkh*, vol. VIII, p. 40; 'Alī ibn Taj al Dīn al Sinjarī, *Mana'iḥ al karam fī akhbar Makka wa l bayt wa wulat al ḥaram*, ed. J. 'A. Muḥammad al Miṣrī, 6 vols. (Mecca, 1998/1419), vol. II, p. 150, read Ḥamdawayh for 'Ḥamdun' (see on him below).

It was Mu'awiya or his son Yazīd (r. 60 4/680 3) who first combined Mecca and Medina; or Medina and the Ḥijaz; or Mecca, Medina and Ṭa'if under one governor. Such arrangements were more common subsequently, but were never followed on a regular basis.⁹ In the early 'Abbasid period the office was occasionally only a nominal one. So, for example, al Ma'mun (r. 198 218/813 33) appointed his minister al Ḥasan b. Sahl to 'the Ḥijaz, the Yemen, Fars, al Ahwaz and Iraq'. Obviously this was a delegation of general authority, and not a nomination to specific governorship. Such an appointee would assign governors to govern the provinces directly. A remarkable fact is that, although seemingly people worthy of the caliphs' trust, most governors served only short terms.¹⁰ The pilgrimage was usually led by the governor of the holy cities, unless the caliph himself performed it, or appointed a person for the task (*amīr al ḥajj*), or unless a rebel took over.¹¹ The office of *amīr al ḥajj* had great political significance, as illustrated by the choice of the caliph al Qadir (r. 381 422/991 1031) who appointed the Alid Shī'ī leader, the *sharīf* al Raḍiyy, to this office, and, when necessary, reminded him and his relatives of this favour.¹² This appointment was meant to conciliate the Shī'ites and to counter the influence of the Faṭimids in the Ḥijaz (see below).

Outside of the towns, the tribes were apparently left to their own devices, except that they had to pay the alms tax (*ṣadaqa*) to the governor of Medina. There is hardly any information about tax collectors sent to the tribes, or indeed about their tribal daily life and about their contacts with the government.¹³

'Abbasid governors in the Ḥijaz are still mentioned in the sixties of the third/ninth century. Some of the governors of this period served long

9 Fasī, *Shifa'*, pp. 259, 261, 266, 273 5; Fasī, *Iqd*, vol. III, p. 419; Ibn Fahd, *Ghaya*, pp. 82, 108, 116, cf. pp. 91, 315 16, 318.

10 Muḥammad ibn Aḥmad al Fasī, *al Zuhur al muqtatafa min ta'rīkh Makka al musharrafā*, ed. A. M. al Ghazawī (Beirut, 2000), pp. 208 24; Fasī, *Shifa'*, pp. 251 303; Sinjarī, *Mana'ih*, vol. I, pp. 513 29, vol. II, pp. 8, 11 14, 37, 39, 47 8, 50, 55 61, 69 70, 72, 77, 79, 86, 90 5, 98, 100 3, 109 10, 119 20, 127 8, 142, 150 1, 155, 157 60, 164 5, 168 9, 171, 175; Ibn Fahd, *Ghaya*, pp. 191 389, 408 64; 'Alī, *al Ḥijaz*, pp. 282 315, 322 37; 'Abd al Ghani, *Madīna*, pp. 107 90 (al Ḥasan ibn Sahl, pp. 160, 164; other examples, pp. 174, 182, 185, 193); Edward von Zambauer, *Mu'jam al ansab wa l usarat al ḥakima fī al ta'rīkh al Islāmī* (Beirut, 1980), pp. 27 9, 35 7.

11 E.g. al Ṭabarī, *Ta'rīkh*, vol. VIII, pp. 238 9, 254, 272; Sinjarī, *Mana'ih*, vol. II, p. 148; Ibn Fahd, *Ghaya*, pp. 318, 325; 'Abd al Ghani, *Madīna*, p. 174.

12 Taqī al Dīn Aḥmad ibn 'Alī al Maqrīzī, *Itti'az al ḥunafa' bi akhbar al a'emma al Faṭimiyyīn al khulafa'*, ed. Jamal al Dīn al Shayyal (Cairo, 1368/1948), p. 39.

13 See e.g. 'Abd al Ghani, *Madīna*, p. 129; 'Alī, *al Ḥijaz*, pp. 292 3, 316 17, 339 57; Oppenheim, *Beduinen*, vol. II, pp. 320 1.

terms, a fact that gives the wrong impression of stability in the Hijaz.¹⁴ As a matter of fact, the central government had lost its grip on the region by this time.

The special status of Mecca and Medina

The holy cities had great political significance, not only as symbols of a faith that was also a polity, but also as cultic centres regularly visited by Muslims from all over the empire. This explains why the caliphs reserved for themselves, as long as they were able, the power to appoint governors to the Hijaz. It also explains the huge investments made by the caliphs and other rulers, not only in public but also in private property. In addition to renovations of mosques and infrastructure, caliphs and high officials built and purchased houses for themselves in Mecca, preferably near the Ka'ba.¹⁵

It appears that, in the early period, the caliphs' willingness to invest was the result of genuine concern for the believers' welfare. 'Umar established a food storehouse in Medina, and watering places on the road between Mecca and Medina, for the benefit of pilgrims. He also enlarged the mosques since they could no longer accommodate the growing numbers of believers. 'Uthman bought and demolished houses adjacent to the Ka'ba in order to enlarge the mosque there.¹⁶ Attention to decoration began with Mu'awiya, who sent from Damascus incense, candles, a cover (*kiswa*), and slaves to serve in the Ka'ba. 'Abd Allah ibn al Zubayr, who ruled from Mecca in the years 64/73/683/92, enlarged the mosque of the Ka'ba and repaired the damages inflicted on it during the Syrian siege of 64/683. Having defeated Ibn al Zubayr in 73/692, the general and governor al Hajjaj b. Yusuf returned the building to its previous state.¹⁷ The caliph al Walid (r. 86/96/705/15) invested not only in the Ka'ba but also carried out extensive works in the central mosque in Medina, turning it into a magnificently decorated edifice; a special militia was assigned to guard it (*haras al masjid*). In addition, al Walid ordered that a mosque be built at every place

14 E.g. Sinjarī, *Mana'ih*, vol. II, p. 157. See further 'A. 'Abd al Ghani, *Ta'rikh umara' Makka al mukarrama* (Damascus, 1413/1992), pp. 85–440.

15 See e.g. Muḥammad ibn Ishāq al Fakihi, *Ta'rikh Makka*, in Wüstenfeld, *Akhbar Makka*, vol. II, pp. 13–17.

16 Qutb al Dīn al Nahrawālī, *al 'Iḥām bi a'lam bayt allah al ḥaram*, in Wüstenfeld, *Akhbar Makka*, vol. III, pp. 74–9; Sinjarī, *Mana'ih*, vol. I, p. 529; Drees, 'A critical edition', part II, pp. 169–70, 173–4; 'Alī, *al Hijaz*, pp. 204–5.

17 Sinjarī, *Mana'ih*, vol. II, pp. 17–26, 30–1, 45–51; Fasī, *Zuhur*, pp. 60–2, 68–9, 91, 104–5; Ibn Fahd, *Ghaya*, p. 188; Nahrawālī, *I'lam*, in Wüstenfeld, *Akhbar Makka*, vol. III, pp. 73–86; 'Alī, *al Hijaz*, pp. 596–610.

where the Prophet had prayed. From the Marwanid period (beginning in 65/684) onwards, the caliphs donated gold, silver, ivory and mosaics to decorate the two cities' mosques. Renovations sometimes aroused opposition. Some refused to give up their homes, which had to be pulled down in order to enlarge the mosques. Others objected to adornments, which they associated with luxury and which they considered as deviation from the Prophet's custom. The protests had no effect, and they soon disappeared. Moreover, the inhabitants came to realise that they could benefit from the government's attention, and started to appeal directly to the authorities outside the Hijaz for help in repairing, for instance, the damage caused by floods, and their requests were usually granted. Such appeals, however, were not generally necessary, for the caliphs and governors often took the initiative in making repairs.¹⁸ It appears, however, that after the Rashidun, investments were meant to enhance the rulers' authority and to earn them legitimacy and prestige rather than merely to contribute towards the welfare of the Muslims. From the third/ninth century such investments served as a major tool in the competition between rival Muslim states. Destruction of renovations carried out by a political rival was rare,¹⁹ but its occurrence points yet again to the political significance of maintenance works in the holy cities.

Governors occasionally engaged not merely in renovations but also in innovations. In the Marwanid period Khalid al Qasrī, for example, enforced the separation of men from women during the circumambulation (*ṭawaf*) of the Ka'ba. This particular innovation was accepted, but others were resented or rejected.²⁰ Innovations, like renovations, had political significance, as illustrations of sovereignty.

The fact that the Hijaz had been the seat of the Prophet's rule and the centre of the new empire not only led to its development but also meant that its people, in particular the dwellers of the holy cities, claimed a special status. Some of the closest Companions of the Prophet and other important personalities remained in the Hijaz, profiting from their high status and from lands that had been granted them by the Prophet. Some of them further purchased

18 Fasī, *Shifā'*, pp. 267–8; Sinjarī, *Manā'ih*, vol. I, pp. 7–8, vol. II, pp. 92–3, 109–15, 122–3, 151–8, 161–3, 170, 178, 182–4, 186; Nahrawālī, *ʿIlām*, in Wüstenfeld, *Akhbar Makka*, vol. III, pp. 86–162; Ibn Fahd, *Ghaya*, pp. 204, 212–13, 231, 300, 309, 335, 370, 410–13, 424–5, 443; Drees, 'A critical edition', part II, pp. 128–42, 155–7, 181–2, 201, 203–6, 217, 234, 323–6; 'Alī, *al-Hijaz*, pp. 205, 306–7.

19 E.g. Ibn Fahd, *Ghaya*, p. 300.

20 Fasī, *ʿIqd*, vol. IV, p. 272; Ibn Fahd, *Ghaya*, pp. 194–200, see also pp. 409, 414, 426, 431, 444, 448.

lands and invested great sums of money in agricultural enterprises. Chief among them were the Prophet's cousin and son in law 'Alī b. Abī Ṭalib, al Zubayr b. al 'Awwam, Ṭalḥa b. 'Ubayd Allah and 'Abd al Raḥman b. 'Awf, all Qurashīs. It is perhaps no accident that the 'Alids and the Zubayrids were the greatest opponents of the Umayyads, who competed with them over the economic opportunities of the Ḥijaz, in addition to usurping their position as leaders of the Muslims.²¹ In the early period actual rebellions were few, but the Meccans and Medinans did defy the caliphs in various ways, and kept their dignity and status in the local arena even after their defeat in the second civil war (*fitna*, 61 73/680 92). Umayyad and early 'Abbasid caliphs tried to reconcile the members of the elite (e.g. by giving them generous gifts and pensions, '*aṭa*', by granting their requests, sometimes by the choice of governors), while at the same time keeping an eye on them. The caliphs did not hesitate to suppress rebellions, nor, when they saw fit, to confiscate lands, to deprive the Ḥijazī notables of their pensions and to humiliate them.²²

Of the two local families just mentioned, the Zubayrids came to prominence first, but it was the 'Alids, descendants of the Prophet, who had the more enduring influence. They were mainly based in the area of Yanbu', to the west of Medina, and in Fadak, to the north, where they owned large tracts of land. Yanbu' occasionally suffered from destruction as a result of 'Alid revolts, yet in the fourth/tenth century it was even more prosperous than Medina. The property, among other things, became a cause of quarrel between the various groups of the family of the Prophet.²³ It may also partly explain why the 'Alids never constituted a united front against any government.

21 Details of land ownership: Ḥamad al Jasir, *Bilād Yanbu'* (Riyadh, n.d.), pp. 23 4, 139; 'Alī, *al Ḥijaz*, pp. 304, 445 80; S. A. al 'Alī, 'Mulkiyyat al arḍ fī al Ḥijaz fī al qarn al awwal al hijrī', *al 'Arab*, 3 (1969). See also M. J. Kister, 'The battle of the Ḥarra: Some socio economic aspects', in M. Rosen Ayalon (ed.), *Studies in memory of Gaston Wiet* (Jerusalem, 1977).

22 Ibn Fahd, *Ghaya*, p. 187; 'Alī ibn Aḥmad ibn Ḥazm, *Jamharat ansab al 'Arab*, ed. 'A. M. Harun (Cairo, 1382/1962), p. 39 (al Maṣṣūr appoints an 'Alid as governor of Medina); Jasir, *Yanbu'*, p. 24; 'Alī, *al Ḥijaz*, pp. 301 4, 379 434, note that after Harun no state pensions are mentioned (p. 411); Kister, 'Ḥarra'. Defiance of caliphal authority (short of rebellion): Aḥmad ibn Yahya al Baladhurī, *Ansab al ashraf*, vol. V, ed. S. D. Goitein (Jerusalem, 1936), pp. 28 9, 41; Ya'qubī, *Ta'rikh*, vol. II, p. 250; Muṣ'ab ibn 'Abd Allah al Zubayrī, *Nasab Quraysh*, ed. E. Levi Provençal (Cairo, n.d.), p. 154; Ibn Fahd, *Ghaya*, pp. 201, 282, 284; Sinjarī, *Mana'ih*, vol. II, pp. 62, 68 9. Generosity of caliphs: *ibid.*, pp. 90, 111, 119, 123; Fasī, *Shifa'*, pp. 342 3, cf. p. 353; Drees, 'A critical edition', part II, p. 156.

23 Yanbu': Jasir, *Yanbu'*, pp. 13 16, 19 28. Disputes among 'Alids over property: al Ṭabarī, *Ta'rikh*, vol. VII, pp. 161 3, cf. Ibn Fahd, *Ghaya*, p. 120.

Sanctity violated: rebellions and disorder in the holy cities

The Ḥijaz was rarely a target for attacks by non Muslims, though this did occur – for example, in 173/790 and 183/799, when Ethiopians landed on the coast.²⁴ As a rule it was Muslims who stirred up violence, despite the prohibition on spilling blood in the holy places. Rebels, both local and others, did not hesitate to clash in Mecca, usually during the holiest of times, the pilgrimage. Robbery of pilgrim caravans, and even of the Ka'ba itself, became ever more common from the third/ninth century onwards. It was not only Bedouin who committed such acts, but also local leaders descending from the Prophet's family (*ashraf*). The caliphs themselves sometimes ignored the sanctity of Mecca and Medina, even when it was not absolutely necessary, for example, the first 'Abbasid governor of the region executed the Umayyads in Mecca, paying no heed to protests.²⁵

The first civil war (*fitna*) started with the assassination of the caliph 'Uthman in Medina (in 35/656), but subsequent events took place outside of the Peninsula, and those who remained in the Ḥijaz were not involved. Hostilities almost broke out in Mecca in 39/660 between supporters of 'Alī and a representative sent by Mu'awiya, but the parties avoided it and reached an agreement.²⁶ During Mu'awiya's reign (41 60/661 80), which followed that war, resentment in the Ḥijaz grew, and after his death many refused to recognise his son Yazīd as caliph. Al Ḥusayn b. 'Alī left for Kufa as a claimant to the throne, to be killed at Karbala' (61/680); 'Abd Allah ibn al Zubayr demanded that a caliph be elected by consultation, but claimed the throne himself after Yazīd's death (64/683); the Medinans acted under their own leadership and drove the Umayyads out of their town, but were defeated by a Syrian army at the battle of al Ḥarra (64/683).²⁷ The Ḥijazī opposition was not united until after al Ḥarra. Thereafter it was the Zubayrid family that gained prominence. Between the years 64 and 73/683 and 692 hegemony in the Ḥijaz (and in fact in most of the Islamic lands) was in the hands of 'Abd Allah ibn al Zubayr, but he was eventually defeated by the Umayyads. The Zubayrids remained in the Ḥijaz and continued to own lands there, and even to serve as

24 Sinjarī, *Mana'ih*, vol. II, pp. 121, 126.

25 Ibn Fahd, *Ghaya*, pp. 300 1. For Bedouin violence across the centuries, see al Ṭabarī, *Ta'rikh*, vol. IX, p. 553; Fasī, *Shifa'*, pp. 344 5, 352, 364; Sinjarī, *Mana'ih*, vol. II, pp. 147, 174, 204; Ibn Fahd, *Ghaya*, pp. 174, 399, 433; 'Abd al Ghani, *Madīna*, pp. 175 7, on the *ashraf* see below.

26 Fasī, *Shifa'*, pp. 338 9.

27 Al Ṭabarī, *Ta'rikh*, vol. V, pp. 381 467, 479 81; Ibn Fahd, *Ghaya*, pp. 122 6; Kister, 'Ḥarra'.

governors of Medina for the early 'Abbasids, but their political role was minor.²⁸ The stage in the Ḥijaz was thenceforth occupied by 'Alids and by non local forces.

The first non local rebel to take Mecca and Medina, in 129/746, was the Yemenī Kharijite al Mukhtar Abu Ḥamza. He was acting on behalf of 'Abd Allah b. Yahya Ṭalib al Ḥaqq, who had seized the Yemen shortly before. The caliph Marwan II (r. 127 32/744 50) dispatched troops from Syria, which suppressed the movement in both Mecca and the Yemen.²⁹

The local 'Alids first rebelled in 144/762 led by Muḥammad al Nafs al Zakiyya, who was a Ḥasanid (namely, a descendant of al Ḥasan b. 'Alī). Battles took place in Mecca and Medina, and the revolt was suppressed.³⁰ Another 'Alid Ḥasanid revolt, led by al Ḥusayn b. 'Alī, 'the man of Fakhkh', occurred in 169/786 and was suppressed during the Pilgrimage, its leader killed while being in the state of *iḥram*.³¹ The caliph al Amīn (r. 193 8/809 13) violated the sanctity of the Ka'ba, albeit not by spilling blood. In 196/811 he removed from it the document regulating the succession to the caliphate that had been drawn up by his father Harun. He then burnt it, an action that marked the beginning of yet another civil war. The Ḥijazīs rejected al Amīn and gave their allegiance to his brother Ma'mun. But they did not take to arms, and the actual civil war took place outside the Ḥijaz.³² Rarely did a governor refrain from fighting a rebel in order to avoid bloodshed in Mecca, the holy city. Thus al Ma'mun's governor preferred to leave Mecca (in 199/815) rather than to fight the 'Alid rebel al Ḥusayn al Aftas.

The latter took control of Mecca and its port Judda on behalf of Abu al Saraya, who had rebelled in Iraq in 199/815. Abu al Saraya gained control not only of Mecca but Medina too, through another agent, the Ḥasanid

28 Baladhurī, *Ansab*, pp. 150 9, 188 204, 355 78; Ibn Fahd, *Ghaya*, pp. 139 87; G. Rotter, *Die Umayyaden und der zweite Bürgerkrieg* (680 692) (Wiesbaden, 1982). Zubayrids as governors: 'Abd al Ghani, *Madīna*, pp. 154 5.

29 Fasī, *Iqd*, vol. V, pp. 511 12; Sinjarī, *Mana'ih*, vol. II, pp. 73 7; Ibn Fahd, *Ghaya*, pp. 282 97; Salim b. Hamud al Sayyabī, *al Ḥaqq wa l majaz fī ta'rikh al Ibaḍiyya bi l Yaman wa l Ḥijaz* (Muscat, 1400/1980), pp. 81, 99 125 (note the author's strong penchant for Ibaḍism); 'Abd al Ghani, *Madīna*, pp. 104 7. Ṭalib al Ḥaqq and the Syrian army: see below.

30 A. Elad, 'The rebellion of Muḥammad b. 'Abdallah b. al Ḥasan (known as al Nafs al Zakiyya) in 145/762', in J. E. Montgomery (ed.), *'Abbasid Studies: Occasional papers of the School of 'Abbasid Studies*, 6 10 July 2002 (Leuven, Paris and Dudley, MA, 2004).

31 Sinjarī, *Mana'ih*, vol. II, pp. 115 19; Ibn Fahd, *Ghaya*, pp. 349 55; Abu al Faraj al Iṣfahānī, *Maqatil al Ṭalibiyyin*, ed. Aḥmad Ṣaqr (Beirut, n.d.), pp. 435 60.

32 Al Ṭabarī, *Ta'rikh*, vol. VIII, pp. 438 40; Fasī, *Shifa'*, pp. 284 5.

Muḥammad b. Sulayman b. Da'ud. After Abu al Saraya had been killed in 200/816, al Ḥusayn al Aftas looked for another leader. He turned to the local Ḥusaynid (namely, a descendant of al Ḥusayn b. 'Alī), Muḥammad b. Ja'far al Ṣadiq, and persuaded him to declare himself caliph. Muḥammad mustered support among Ḥijazī Bedouins and defeated an 'Abbasid army, but he was eventually defeated (in 200/816) by a coalition of Meccans, Medinans and the 'Abbasids. His nephew, Ibrahīm b. Musa al Kazīm (brother of the well known 'Alī al Riḍa), was involved as well, but the reports about his career are contradictory.³³

Despite the turbulent events, the 'Abbasids did not change their policy towards the Ḥijaz during the first half of the third/ninth century. They continued to appoint governors (again from their own family), but their control of the region grew ever weaker. This was due partly to their general decline and the rise of other forces, partly to the arrival of new Bedouin groups from the south and the east to the vicinity of Mecca and Medina, and partly to the disturbances caused by 'Alids inside the cities. The general picture is that of a growing number of forces trying to gain control of the Ḥijaz.

In about 230/845 the caliph al Wathīq (r. 227 32/842 7) had to dispatch an army to fight the Sulaym and other tribes which were troubling Ḥijazī cities. The Turkish general who led this expedition, Bugha al Kabīr, acted against tribes in Najd as well, and emerged victorious, though only after several defeats.³⁴

The other threat to the caliphs, the 'Alids, was growing more menacing. Some early 'Abbasid caliphs tried to conciliate them, but Mutawakkil (r. 232 47/847 61) reversed this policy.³⁵ Perhaps in response to this pressure, the Ḥasanid Isma'īl b. Yusuf rebelled in 251/865 or 252/866 and wreaked havoc in Mecca, Medina and Judda. He robbed the Ka'ba, starved the Meccans under siege, and killed more than a thousand pilgrims. The governor used gold taken from the Ka'ba to finance the struggle against the rebel, but he also needed reinforcements from Baghdad. Eventually Isma'īl died of the

33 Al Tabarī, *Ta'riḫ*, vol. VIII, pp. 531 3, 536 40; Isfahānī, *Maqatil*, pp. 533, 537 41; Fasī, *Shifa'*, pp. 285 8, 289 90, a confused version on p. 344; Fasī, *Iqd*, vol. III, pp. 264 5, vol. VII, p. 466; Sinjarī, *Mana'ih*, vol. II, pp. 142 50; Ibn Fahd, *Ghaya*, pp. 376 8, 389 400, 405 7; Juddī, *al Silah wa l 'udda*, p. 30; 'Abd al Ghanī, *Madīna*, pp. 161 4. On Ibrahīm see also below.

34 Al Tabarī, *Ta'riḫ*, vol. IX, pp. 129 35, 146 50; Oppenheim, *Beduinen*, vol. II, p. 318; see also note 25 above (refs. to Bedouin violence), and below.

35 See e.g. Isfahānī, *Maqatil*, p. 599.

plague. His brother succeeded him, but was forced out of Mecca into Yamama, where he established the long lasting Ukhayḍir dynasty. One of the results of Ismaʿīl's revolt was economic decline, which forced many Meccans to leave their city.³⁶ In Medina, other 'Alid claimants rose in the second half of the third/ninth century – some Ḥasanids, some Ḥusaynids and some Ja'farids (namely descendants of Ja'far b. Abī Ṭalib). Muslim sources vilify some of these claimants for their sinful conduct. They sometimes turned against one another, as well as against the cityfolk and the pilgrims. The Shī'a ideology does not seem to have meant much to the Ḥijazī 'Alids of this period.³⁷

In addition to the various 'Alid groups, there is mention of other local notables, members of the ancient aristocratic Makhzum clan, who fought against one another (or against the governor) over Mecca and Judda (in 262/876 and 266/880). One of these notables may have been acting on behalf of the leader of the Zanj, whose rebellion in Iraq (254 69/868 83) deeply shook the caliphate.³⁸ To add to the confusion, non local Muslim rulers intervened in the Ḥijaz, namely Ibn Ṭulun, ruler of Egypt and Syria (254 70/868 884) and Ya'qub b. Layth al Ṣaffar, ruler of Sīstan (253 65/867 79).³⁹ The latter appointed (in 266/880) a governor to the holy cities, Muḥammad b. Abī al Saj al Afshīn, who in turn appointed his own representatives. Forces of Ibn Ṭulun and al Ṣaffar clashed in Mecca in 269/882, and the battle ended with Ibn Ṭulun's defeat.⁴⁰ During the same period, there is mention also of representatives sent directly by the government in Iraq, both to Mecca and to Medina; naturally, clashes occurred between the various appointees. Amazingly, one functionary, Harun b. Muḥammad of the 'Abbasid family, led the pilgrimage through the many vicissitudes of the period, for sixteen successive years (264 79/878 93). Certain sources call

36 Al Ṭabarī, *Ta'rikh*, vol. IX, pp. 436 7; Fasī, *Shifa'*, pp. 294 6, 298; Sinjarī, *Mana'ih*, vol. II, pp. 165 7; Shams al Dīn al Sakhawī, *al Tuḥfa al laṭīfa fī ta'rikh al Madīna al sharīfa*, 3 vols. (Cairo, 1376/1957), vol. I, pp. 308 9; Ibn Fahd, *Ghaya*, pp. 434 7, 443; 'Abd al Ghanī, *Madīna*, pp. 186 7.

37 Al Ṭabarī, *Ta'rikh*, vol. IX, pp. 552 3, 621, vol. X, p. 7; Iṣfahanī, *Maqatil*, pp. 716 20; Ibn Ḥazm, *Jamhara*, p. 39; 'Abd al Ghanī, *Madīna*, pp. 189 (feuds in 255/868), 192 (in 271/884), 194 (in 265 6/878 9), 197 203 (several rivals, all in 271/884), 206 8.

38 Fasī, *Shifa'*, pp. 300 1; Sinjarī, *Mana'ih*, vol. II, pp. 172 4; Ibn Fahd, *Ghaya*, pp. 456 62, 464; Juddī, *al Silāḥ wa l 'udda*, p. 32.

39 Sinjarī, *Mana'ih*, vol. II, p. 172; Ibn Fahd, *Ghaya*, pp. 450, 456 7; 'Abd al Ghanī, *Madīna*, pp. 194 6.

40 Al Ṭabarī, *Ta'rikh*, vol. IX, pp. 652 3; Sinjarī, *Mana'ih*, vol. II, pp. 172, 175 7; Ibn Fahd, *Ghaya*, pp. 450, 454 7; 'Abd al Ghanī, *Madīna*, pp. 194 6.

him 'governor of Mecca, Medina and Ṭa'if', but he did not occupy this post during all these years.⁴¹

Events in the Ḥijaz at the beginning of the fourth/tenth century are obscure, and certain sources admit their bewilderment. References are made to governors; to army commanders sent to fight Bedouins; to Ja'farids who took Medina; and to a claimant to the throne, the Ḥasanid Muḥammad b. Sulayman, who proclaimed himself imam in Mecca in 301/913. It appears that the caliphs had only nominal control. This is indicated by the facts that they distributed huge sums of money in the holy cities, and that they entrusted the Ḥijaz to Turkish generals.⁴² In 300/912 Mu'nis al Muẓaffar was in charge of the 'two holy cities and the frontiers', which means that conditions in the Ḥijaz were unstable, to the point that not a governor, but a general was needed to handle them.

In 317/930 the Qarmaṭīs of Baḥrayn entered Mecca during the pilgrimage, massacred thousands of people, wreaked destruction on the holy places and stole the black stone; it was only returned in 339/951. The pilgrimage ceased for a number of years, and anarchy prevailed.⁴³ Under these circumstances, it is not surprising that in 331/943 the caliph agreed that Mecca and Medina should be brought under the nominal jurisdiction of the Ikhshīdids, the semi independent dynasty that ruled Egypt and Syria (325 58/935 69). Nevertheless, the caliphs continued to contribute towards renovations in the holy places, and the actual governors, as far as anything is known of them, were still drawn from the 'Abbasid family. These caliphs' policies did not prevent clashes in Mecca between representatives of the Ikhshīdids on the one hand, and on the other, the Buwayhids. 'Alid leaders also played a part in local political and military events.⁴⁴

41 'Abbasid governors after al Ma'mun and until the end of the third/ninth century: Ibn Fahd, *Ghaya*, pp. 419 67; Fasī, *Shifa'*, pp. 277 305; Sinjarī, *Mana'ih*, vol. II, pp. 177, 179; 'Abd al Ghani, *Madīna*, pp. 190, 201, 203, 204 5, 211; Zambauer, *Mu'jam al ansab*, pp. 28 9, 37; Harun ibn Muḥammad: al Ṭabarī, *Ta'rikh*, vol. X, p. 31; Ibn Fahd, *Ghaya*, pp. 453 4; 'Abd al Ghani, *Madīna*, pp. 204 5. Clashes between various appointees: Fasī, *Shifa'*, pp. 299 301, 303 4.

42 Fasī, *Shifa'*, p. 303; Sinjarī, *Mana'ih*, vol. II, pp. 179 81, 185, cf. Isma'īl ibn 'Umar ibn Kathīr, *al Bidāya wa l nihaya*, 14 vols. (Beirut, n.d.), vol. XI, p. 200; 'Abd al Ghani, *Madīna*, pp. 208 17. The systematised lists of rulers in *Mir'at* do not match the information given in the other sources: see A. Ṣabrī Basha, *Mir'at jazirat al 'Arab*, trans. A. F. Mutawallī and A. al Mursī (Cairo, 1419/1999), pp. 93 7, 101.

43 Sinjarī, *Mana'ih*, vol. II, pp. 187 95, 198, and see below. The pilgrimage was suspended many times: see Fasī, *Shifa'*, pp. 346 9, 351 2, 354 7, 359 60, 364.

44 Fasī, *Iqd*, vol. II, pp. 31, 33 4; Fasī, *Shifa'*, pp. 305 6, 349 50; Sinjarī, *Mana'ih*, vol. II, pp. 181 2, 192, and on renovations 198 202; Ibn Fahd, *Ghaya*, pp. 470, 474 9. On the Buwayhids, who were the actual rulers behind the caliphs in the years 946 1055, see chapter 9 in this volume.

Some time before 329/940 the Ḥusaynid ‘Ubayd Allah b. Ṭahir founded in Medina the Banu Muhanna dynasty, which lasted until the end of the tenth/sixteenth century. It is not known precisely how he came to power, and whether he wrested the city from Ja‘farids or from an appointed governor. Mecca followed suit, and after (or shortly before) the death of Kafur the Ikhshīd in 356/967, the Ḥasanid Ja‘far b. Muḥammad established a dynasty that lasted until 453/1061. Henceforth Ḥasanid and Ḥusaynid families ruled Mecca and Medina respectively, fighting one another, the Ja‘farids, Bedouins and non Hijazī Muslim powers.⁴⁵ These descendants of the Prophet (*ashraf*) were closer in spirit to the Bedouin of the Peninsula than to the sophisticated urban Islamic elites elsewhere. Not only were they often engaged in internal wars, but they also treated the Hijaz, its people and the pilgrims mainly as a source of income. Whereas rulers of other provinces often expressed their status in grand architecture and by acting as patrons of art and science, the *ashraf* of the Hijaz paid no heed to such matters, and they sometimes even robbed the Ka‘ba themselves.⁴⁶ It is no accident that the renovations of the holy places were as a rule carried out by one of the competing Islamic states that flourished outside the Peninsula. The *ashraf* for their part were under constant pressure to choose between the competitors, whether the Western ones like the Ikhshīdīs and the Faṭimids after them, or the Eastern ones, namely, the ‘Abbasid caliphs, the Buwayhids and later the Saljuqs, and even the distant Ghaznavids. Competing rulers would offer to support one of the rival *ashraf* against another, and would also intervene directly, attempting to gain their allegiance by a variety of means: military force, lavish gifts and food supplies (the last being sent from Egypt). The *ashraf* not only transferred their loyalty from one power to another (as tribal leaders would), but also occasionally played an active role in the political struggles of the Islamic world. Muḥammad b. ‘Ubayd Allah, son of the founder of the Banu Muhanna (Ḥusaynid) dynasty of Medina, may have played a part in the Faṭimid takeover of Egypt in 359/969.⁴⁷ That same year the founder of the dynasty

45 Fasī, *Shifa’*, pp. 306–7; Sinjarī, *Mana’ih*, vol. II, pp. 211–16; Ibn Fahd, *Ghaya*, pp. 480–500; Ibn Ḥazm, *Jamhara*, p. 47; Maqrīzī, *Itti‘āz*, pp. 145–6; ‘Abd al Ghānī, *Madīna*, pp. 217ff.

46 E.g. Fasī, *Shifa’*, pp. 310, 312.

47 Sinjarī, *Mana’ih*, vol. II, pp. 203, 206–7, 221 (siege, and gifts), 230–1, 236 (gifts); Fasī, *Shifa’*, p. 353. There is a confusion regarding the relations of ‘Ubayd Allah ibn Ṭahir and his sons with the Ikhshīdīs and the Faṭimids: see Ibn Kathīr, *Bidayya*, vol. XI, pp. 310–11; ‘Abd al Ghānī, *Madīna*, pp. 222–3, 226–7. Contacts with the Ghaznavids: *ibid.*, pp. 228–9, with the Saljuqs, p. 236. See also Oppenheim, *Beduinen*, vol. II, pp. 321–2.

in Mecca, Ja'far b. Muḥammad, was already paying allegiance to the Faṭimids, perhaps as gratitude to the Faṭimid caliph al Mu'izz, who reportedly mediated in the 348/959 feud between the Ḥasanids and Ja'farids.⁴⁸ Ja'far's son and successor, Ḥasan b. Ja'far Abu al Futuḥ, paid allegiance to the Faṭimids as well, and took Medina from the Ḥusaynids (in 390/1000) on their command. For part of his long rule (384 430/994 1038) he became disaffected with the Faṭimids and proclaimed himself caliph under the name al Rashid bi Allah. He was even acknowledged as caliph by the Bedouins of Syria, who were anxious to free themselves of the Faṭimids. Eventually, however, Abu al Futuḥ renounced the caliphal title and returned to pay homage, first to the Faṭimid al Ḥakim (r. 386 411/996 1021) and later to the 'Abbasid caliph, al Qadir (r. 381 422/991 1031).⁴⁹ Abu al Futuḥ's son and successor (from 430/1039), Shukr, re conquered Medina, but he was embroiled in wars with his own relatives, and he had no offspring. Various 'Alid branches fought one another upon Shukr's death in 453/1061, and anarchy prevailed. Peace returned when 'Alī b. Muḥammad al Ṣulayḥī, the Faṭimids' agent in the Yemen, entered Mecca in 455/1053. The sources describe al Ṣulayḥī as just and considerate. At the request of some of the Ḥasanid leaders 'Alī al Ṣulayḥī left the city after he had chosen a representative, the Ḥasanid Muḥammad b. Ja'far Abu Hashim (son in law of the former ruler, Shukr). Muḥammad was thus the founder of a new Ḥasanid dynasty, the Hawashim, which lasted until 597/1201. He was temporarily expelled from Mecca by his rivals, but eventually regained his position and held it for thirty three years. He also succeeded in temporarily wresting Medina from the Ḥusaynid Banu al Muhanna.⁵⁰ The Saljuqs, acting on behalf of the 'Abbasids, and the Faṭimids continued to exert pressure on the *ashraf*, the Ḥasanid Hawashim in Mecca and the Ḥusaynid Banu al Muhanna in Medina. Even Muḥammad b. Ja'far, who had been appointed by the Faṭimid agent al Ṣulayḥī, vacillated between the two powers. Other *ashraf* followed the same pattern and also transferred their allegiance from

48 Fasī, *Shifa'*, p. 351; al Mu'izz: Maqrīzī, *Itti'az*, pp. 145 6 (Maqrīzī's dates differ from those given in other sources).

49 Very different versions of the events are given: see Fasī, *Shifa'*, pp. 307 9; Sinjarī, *Mana'ih*, vol. II, pp. 208 9, 216 20, 221 2; Ibn Fahd, *Ghaya*, pp. 485 94; Ibn Kathīr, *Bidaya*, vol. XI, pp. 309 10; 'Abd al Ghani, *Madīna*, pp. 230 1; Oppenheim, *Beduinen*, vol. II, p. 322.

50 Fasī, *Shifa'*, pp. 310 12, note the confusion about the identity of Banu Abī al Ṭayyib; 'Imad al Dīn, *Uyun al akhbar wa funun al athar*, vol. VII, ed. A. F. Sayyid (London, 2002), pp. 22 36; Sinjarī, *Mana'ih*, vol. II, pp. 222 34, 242 66, note the confusion regarding the names of the petty dynasties; Ibn Fahd, *Ghaya*, pp. 500 2, 509 10; 'Abd al Ghani, *Madīna*, pp. 236, 238, 240ff, 505, note the confusion about the years 390 469/999 1076 on pp. 230 7.

one power to the other, sometimes in return for huge gifts, at other times under pressure. For example, in 484/1091, and again in 486/1093 or 487/1094, Saljuq forces conquered Mecca, and plundered it. In addition, attacks by the *ashraf* themselves on pilgrims and merchants were not uncommon, and the same applies to clashes between pilgrims representing competing dynasties or rival ideologies.⁵¹ It is remarkable that in the early days of Islam, no one had dared to rob the pilgrims, and enemies performed the pilgrimage side by side, deliberately avoiding clashes in Mecca during the pilgrimage.⁵²

The political instability that started in the third/ninth century had a devastating effect. Some of the land still prospered in the fourth/tenth century, but in general, agriculture declined, settlements were deserted and the Bedouin way of life spread and affected the towns and their rulers. According to the traveller Naṣir i Khusraw (middle of the fifth/eleventh century), many edifices in Mecca had fallen in ruin and the population was only 2,500 people (one fifth of whom were temporary residents, *mujawirun*). The population of Judda was 5,000, and Ṭa'if was 'a wretched little town'. No central authority was recognised, and, he says, 'the people were robbers and murderers'.⁵³ The unstable conditions also influenced intellectual activity and the creativity of the first two centuries disappeared. It is mainly from the fifth/eleventh century onwards that pilgrims in increasing numbers resided in Mecca or in Medina, for shorter or longer periods. Many received and transmitted religious knowledge, namely *ḥadīth*, *fiqh* and various readings of the Qur'an (*qira'at*). Among the famous scholars who settled temporarily in Mecca were Juwaynī (d. 478/1085) and Zamakhsharī (d. 538/1144). It may be noted that of the historians who lived there, only ten were active from the third/ninth to the fifth/eleventh century. The remaining 177 were active from the sixth/twelfth to the thirteenth/nineteenth century.⁵⁴

After the fall of the Faṭimids in 566/1171, the Hijaz was generally under the patronage of whoever held power in Egypt.

51 Faṣī, *Shifā'*, pp. 311 13, 357 8, 362 4; Sinjarī, *Mana'ih*, vol. II, pp. 231, 234 43; Ibn Fahd, *Ghaya*, pp. 510 23; 'Abd al Ghani, *Madīna*, pp. 238 43.

52 Faṣī, *Shifā'*, pp. 338 9, 340 1 (first and second civil wars, the 'Abbasid revolution); Sinjarī, *Mana'ih*, vol. II, pp. 73 7 (Abu Ḥamza's revolt).

53 Naṣir e Khosraw, *Book of travels (Safarnama)*, trans. W. M. Thackston Jr., Bibliotheca Persica (Albany, 1986), pp. 67, 69, 82 3.

54 Faṣī, *'Iqd, passim*; Muḥammad al Ḥabīb al Hayla, *al Ta'rīkh wa l mu'arrikhun bi Makka min al qarn al thalith al hijrī ila al qarn al thalith 'ashar* (Mecca, 1994). Prosperity in Yanbu' in the fourth/tenth century: Jasir, *Yanbu'*, pp. 27 8.

The Yemen

The Yemen is characterised by the great variety of landscapes and tribes. Its topography effected a division into a great number of administrative provinces, tribal territories, domains of warlords and dynasties, and strongholds of ideological groups.⁵⁵ The boundaries of all of these were constantly shifting, as were the loyalties of the tribal groups. Furthermore, because of its remoteness, on the one hand, and its proximity to the holy cities in the Ḥijaz, on the other, the Yemen served as a haven for many rebels. Among those were Kharijites, Shī'ites and many other claimants who vied for power and for the local resources, including international maritime trade. The history of the Yemen is largely made of the struggles between all these groups and dynasties, on the one hand, and, on the other, the interaction between them and the pre Islamic Yemenite social structures and institutions that survived the advent of Islam. Certain modern scholars have noted that, broadly speaking, the north tended to remain anarchic throughout the centuries, whereas the southern parts tended to be more manageable to governments. This distinction is somewhat schematic. Ḥaḍramawt, in the south, was certainly anarchic, perhaps even more so than the north.⁵⁶

The early tenth century historian and geographer al Ya'qubī (d. 284/897) lists eighty four provinces, and 'a multitude of tribes'. Often, however, only a few main geographical divisions are mentioned, for example, from west to east: (1) the coastal plain (Tihama), a region of great importance, due to its seaports; (2) the highlands, called Najd of Yemen; (3) al Jawf and Ma'rib; (4) Ḥaḍramawt, which lies along the southern coast. There are other ways of division, for example: Ṣan'a' and its provinces; Ḥaḍramawt and its provinces; al Janad and its provinces (which include the coastal plain).⁵⁷ The whole of the

55 'Umara al Yamani, *al mufīd fī akhbar Ṣan'a' wa Zabīd wa shu'ara' mulukiha wa a'yanika wa udaba'iha*, ed. Muḥammad b. 'Alī al Akwa' (Ṣan'a', 1985), pp. 77–83; Ayman Fu'ad Sayyid, *Ta'rikh al madhahib al dīniyya fī bilad al Yaman* (Cairo, 1988/1408), pp. 57, 78–81; R. W. Stookey, *Yemen: The politics of the Yemen Arab Republic* (Boulder, 1978), pp. 96–7.

56 Stookey, *Yemen*, p. 50; D. T. Gochenour, 'The penetration of Zaydī Islam into early medieval Yemen', Ph.D. thesis, Harvard University (1984), pp. 10–26, see also pp. 35–8, 90–147, for the persistence of ancient structures. Local resources: see e.g. Ṣalīḥ al Ḥamid, *Ta'rikh Ḥaḍramawt* (Jiddah, 1968), pp. 93–5. International trade: Hourani, *Arab seafaring*, pp. 69–84. Conditions in Ḥaḍramawt: Bawazīr, *Ṣafāḥat*, pp. 78–80. See also G. R. Smith, 'Yemenite history: Problems and misconceptions', in G. R. Smith, *Studies in the medieval history of the Yemen and Arabia Felix* (Aldershot and Brookfield, VT, 1997), II, pp. 131–9.

57 Ya'qubī, *Ta'rikh*, vol. I, p. 201; 'Abd al Muḥsin Mad'aj M. al Mad'aj, *The Yemen in early Islam 9 233/630–847: A political history* (London, 1988), p. 5; Gochenour, 'Penetration', pp. 1–10. Detailed geographical description: Ḥasan ibn Aḥmad al Hamdanī, *Ṣifat jazirat al 'Arab*, ed. M. ibn 'Alī al Akwa' (Beirut and Ṣan'a', 1403/1983), pp. 90ff.

Yemen was rarely, if ever, unified, and the political frameworks often did not overlap any of the geographical divisions.

*The Yemen from the first/seventh to the end of the second/
eighth century*

The main large tribal confederations in the Yemen on the eve of Islam were Ḥimyar, Hamdan, Madhḥij, Kinda, Ḥashid, Bakīl and Azd. In addition, an aristocratic group of Persian origin, the Abna', was scattered throughout the country, and prominent in Ṣan'a'.⁵⁸ The Abna' presumably adhered to Zoroastrianism, but throughout the Yemen, Christianity and Judaism were widespread. At the time of the Prophet Ṣan'a' was ruled by the Abna' whereas the rest of the country was divided among local kings and chiefs, power struggles being a constant feature. Islam was thus introduced into the Yemen, and became yet another factor in the struggles between local leaders and groups. Yemenite delegations to the Prophet are reported, as well as the names of tax collectors, judges and instructors who were sent by the Prophet to Yemenite regions and tribes.⁵⁹ The extent of conversion during the Prophet's time cannot be determined. The sources are tendentious, reflecting the efforts made by each group to prove its early conversion and its contribution to Islam. It should also be noted that the sources are in the habit of applying the names of whole confederations to mere parts thereof. Thus, a report that the Prophet sent someone over Madhḥij, for instance, should not be taken literally: the person may have been appointed over merely a small group pertaining to Madhḥij. Finally, the sources tend to ignore the fact that although formally part of the Islamic domain, much of the Yemen remained as it had been in pre Islamic times.

Islam initially contributed to the local struggles rather than to the unity of the Yemen and its tribes. As elsewhere in the Peninsula, certain tribal chiefs adhered to Islam to enhance their status against other chiefs. Rivals were branded as apostates even if the rivalry did not revolve around religion. The

58 Ya'qubī, *Ta'riḫ*, vol. I, p. 201; S. 'A. al Kaf, *Ḥaḍramawt 'abra arba'at 'ashar qarnan* (Beirut, 1990/1410), pp. 26 30; Ḥamid, *Ta'riḫ Ḥaḍramawt*, pp. 13 53; Maḍ'aj, *Yemen*, pp. 6 7; Gochenour, 'Penetration', pp. 10 26.

59 Al Ṭabarī, *Ta'riḫ*, vol. III, pp. 120 2, 126 38, 147, 227; Aḥmad ibn 'Abd Allah al Rāzī, *Ta'riḫ madīnat Ṣan'a'*, ed. Ḥ. ibn 'Abd Allah al 'Amrī (Ṣan'a', 1401/1981), pp. 140, 249, 255, 293; 'Abd al Raḥman ibn 'Alī ibn al Dayba', *Qurraṭ al 'uyun bi akhbar al Yaman al maymun*, ed. M. ibn 'Alī al Akwa' al Ḥiwālī (Cairo, n.d.), pp. 36 75; Ḥusayn ibn 'Abd al Raḥman al Ahdal, *Tuḥfāt al zaman fi ta'riḫ al Yaman*, ed. 'A. M. al Ḥibshī (Beirut, 1407/1986), pp. 124 7; Ḥamid, *Ta'riḫ Ḥaḍramawt*, pp. 113 34; al Kaf, *Ḥaḍramawt*, pp. 30 1; Maḍ'aj, *Yemen*, pp. 10 15; Stookey, *Yemen*, p. 29.

most prominent among the 'apostates' was al Aswad al 'Ansī, who reportedly claimed to be a prophet and mustered large support in 10/632. The fact that he conquered Ṣan'a' has led some scholars to believe that his efforts were mainly directed against the foreign Abna', some of whom may have been Muslim by this time. Be that as it may, a coalition of members of the Abna' and deserters from al Aswad's own camp succeeded in killing him that same year.⁶⁰ The role of Islam and the Prophet in this so called apostasy was apparently minor. The Prophet's successor, Abu Bakr, played a more active role in establishing Muslim authority in the Yemen. He recruited local forces, reinforced them with troops sent from Medina, and eventually succeeded in adding the Yemen to the domains of Islam, at least formally. The most important foci of his military activity were in Ṣan'a', Ḥaḍramawt and the Tihama. Leaders of the 'apostates', such as Qays b. al Makshuḥ, 'Amr b. Ma'dikarib and the Kindī al Ash'ath b. Qays, repented, were pardoned and played important roles in the subsequent Islamic conquests.⁶¹ Thereafter, Yemenites left their homeland by the thousands to participate in the conquests and to settle in the new provinces. They played increasingly important roles in the army and in politics.⁶² Despite the fact that it was depleted of much of its manpower, the Yemen in general did not become a deserted backwater, as is sometimes assumed.⁶³

The Rashidun sent governors to the Yemen. Occasionally the sources specify the assignments as Ṣan'a', or Ḥaḍramawt, or al Janad, but even if the assignment is given as 'the Yemen', these governors never controlled the whole country. Nevertheless, Ṣan'a' was sometimes the base of a governor who controlled some junior officials in other regions. The appointees were mostly Companions of high status, such as Aban b. Sa'īd b. al 'Āṣ, al Mughīra b. Shu'ba and Ya'la b. Umayya. The last governed Ṣan'a' for twenty four years, serving the first three caliphs, and was dismissed by the fourth. 'Umar is said to have intervened in affairs in Ṣan'a', and to have called the governor to

60 Al Ṭabarī, *Ta'rikh*, vol. III, pp. 228–40; Sulayman ibn Musa al Kala'ī, *al Iktifa' bi ma taḍammanahu min maghazi rasul allah wa l thalatha al khulafa'*, ed. M. K. 'Alī, 4 vols. (Beirut, 1417/1997), vol. III, pp. 95–8; Mad'aj, *Yemen*, pp. 25–32; Stookey, *Yemen*, pp. 30–1.

61 Kala'ī, *Iktifa'*, vol. III, pp. 99–108; Ḥamid, *Ta'rikh Ḥaḍramawt*, pp. 149–61; al Kaf, *Ḥaḍramawt*, pp. 32–7; Mad'aj, *Yemen*, pp. 41–55; Stookey, *Yemen*, p. 32.

62 Details in Mad'aj, *Yemen*, pp. 64–101.

63 E.g. by *ibid.*, pp. 156, 159, and Stookey, *Yemen*, p. 42. Ḥaḍramawt was an exception: see Ḥamid, *Ta'rikh Ḥaḍramawt*, pp. 166–80, 197–200, 227, 245–6; A. Shalabī, *Mawsu'at al ta'rikh al Islāmī wa l ḥaḍara al Islamiyya*, vol. VII (Cairo, 1982), pp. 299–301.

account when necessary. The Rashidun also reportedly appointed judges and Qur'an instructors.⁶⁴ All this indicates that they attached importance to the Yemen, although in the tribal territories, pre Islamic chiefs often retained their positions, with or without the recognition of the caliphs. Special measures were taken by 'Umar against the powerful Christian tribes of Najran. In spite of previous treaties that they had with the Prophet and Abu Bakr, 'Umar evicted them from the area. Jews, however, were allowed to remain in return for the payment of poll tax.⁶⁵

The main events of the first civil war (36 41/656 61) took place outside the Arabian Peninsula, but those Yemenites who remained in their home land were divided, like the rest of the Muslims. Both 'Alī and Mu'awiya sent troops to the Yemen. For some time 'Alī's party had the upper hand, but opponents of his revolted against his governors in Ṣan'a' and al Janad. Eventually, Mu'awiya's general conquered Najran and Ṣan'a' in 40/660.⁶⁶

Like their predecessors, the Umayyads attached great importance to the Yemen, even though their capital shifted away from the Arabian Peninsula. Governors were appointed directly by the caliph, but the jurisdiction of the Yemen was sometimes attached to that of other regions. Thus 'Abd al Malik (r. 65 86/685 705) appointed al Ḥajjaj b. Yūsuf over Yamama, the Ḥijaz and the Yemen. Al Ḥajjaj remained in the Ḥijaz and sent his brother to represent him in the Yemen. As a rule the governors were high ranking individuals, whether they were outsiders or locals. One of the latter was Fayruz, a leader of the Abna', who served under Mu'awiya. How much each governor's control extended outside of the city that was his base is not clear, but the pre Islamic aristocracy certainly retained its status.⁶⁷

During the second civil war, the Meccan caliph, 'Abd Allah ibn al Zubayr (64 73/683 692), had control of Ṣan'a', but he constantly replaced his governors,

64 Razī, *Ta'rikh*, pp. 153, 158, 163 5, 294; Hamid, *Ta'rikh Ḥaḍramawt*, pp. 162 4; Mad'aj, *Yemen*, pp. 102 21; G. R. Smith, 'The political history of the Islamic Yemen down to the first Turkish invasion (1 945/622 1538)', in G. R. Smith, *Studies in the medieval history of the Yemen and Arabia Felix*, Variorum Collected Studies (Aldershot and Brookfield, VT, 1997), I, pp. 129 30.

65 Al Ṭabarī, *Ta'rikh*, vol. III, p. 446; Mad'aj, *Yemen*, pp. 111 13; W. Schmucker, 'Die Christliche Minderheit von Najran', *Studien zum Minderheitenproblem im Islam*, 1 (1973).

66 Al Ṭabarī, *Ta'rikh*, vol. V, pp. 139 40; Yahya ibn al Ḥusayn, *Ghayat al amanī fī akhbar al quṭr al yamanī*, ed. S. 'A. 'Āshur and M. M. Ziyada (Cairo, 1388/1968), pp. 95 8; Mad'aj, *Yemen*, pp. 123 49.

67 Hamid, *Ta'rikh Ḥaḍramawt*, pp. 201 2; Mad'aj, *Yemen*, pp. 156 60, 169 70; Stookey, *Yemen*, p. 41. Lists of governors: Ahdal, *Tuhfa*, pp. 134 40; Ibn al Dayba', *Qurrat*, pp. 89 114.

sometimes appointing locals to the post. This indicates, first, that he was not indifferent to the situation there, and, second, that his control was not firm. Lack of central control is also apparent in the events of 67/686 and 68/687. Challenged by Kharijites from Oman and Baḥrayn, the people of Ṣan‘a’ paid the invaders a large sum of money in the first case, and gave their allegiance to the invader, Najda b. ‘Āmir, in the second. In these reports there is no mention of a governor. It was the scholar Wabb b. Munabbih who tried, in vain, to incite the cityfolk to repel the invaders.⁶⁸ That Ibn al Zubayr did not enjoy strong Yemenite support was finally proven in 73/692, when Ṣan‘a’ offered no opposition to the Marwanid forces. After the re conquest of the Yemen the Umayyad caliphs continued to be directly involved in its affairs, and some invested great sums in its infrastructure, so that the country’s economy prospered.⁶⁹ Typically, ‘Umar b. ‘Abd al ‘Azīz (r. 99 101/717 20) took care to redress the wrongs done to the Yemenites by previous Umayyad caliphs and their governors. As elsewhere, ‘Umar became a model of justice, even for local Isma‘īlī and Zaydī historians.⁷⁰

The Yemen was not unified under the authority of the government, yet the sources do not report many revolts. Some Kharijites settled there directly after their defeat by ‘Alī in the battle of Nahrawan (38/658), but no open revolts are recorded. Kharijites from al Yamama invaded Ḥaḍramawt and Ṣan‘a’ in 67 8/687 8, but they did not stay to rule. A rebel named ‘Abbad al Ru‘aynī rose in 107/725 6, and the sources are divided as regards his precise identity and sectarian affiliation. Some say that he claimed to be the Ḥimyarite messiah, but others identify him as a Kharijite. The number of his supporters was 300.⁷¹ A much more serious revolt occurred in 128 30/745 7 during the caliphate of the last Umayyad, Marwan II. The Kindī ‘Abd Allah b. Yaḥya, the appointed judge of the Umayyad governor in Ḥaḍramawt, assumed the title Ṭalib al Ḥaqq (‘The One who Pursues the Truth’), and proclaimed himself caliph. Supported by the Ibaḍiyya Kharijites in Oman (see below), he succeeded in seizing Ḥaḍramawt, Ṣan‘a’ and even Mecca and Medina (through his agent Abu Ḥamza); the number of his followers is estimated by some sources at about thirty thousand (this number may of course be a topos, for it is recurrent, but it conveys large numbers). Allegiance was sworn to him in

68 ‘Izz al Dīn ibn al Athīr, *al Kamil fī al ta’rīkh*, 10 vols. (Beirut, 1415/1995), vol. IV, p. 21; M. ‘I. al Ḥarīrī, *Dirasat wa buḥūth fī ta’rīkh al Yaman al Islāmī* (Beirut, 1418/1998), pp. 19, 21; Muḥammad ibn Muḥammad Zabara al Ḥasanī, *al Inba’ ‘an dawlat Bilqīs wa Saba’* (Ṣan‘a’, 1404/1984), pp. 40 1.

69 Mad‘aj, *Yemen*, pp. 161 3, 170; Ḥarīrī, *Dirasat*, p. 31; see also Hamdanī, *Ṣifat*, p. 105.

70 ‘Umara, *Mufīd*, p. 66; Zabara, *Inba’*, pp. 41 3.

71 Yaḥya ibn al Husayn, *Ghayat*, p. 119; al Ṭabarī, *Ta’rīkh*, vol. VII, p. 40; Zabara, *Inba’*, p. 43; Mad‘aj, *Yemen*, pp. 161, 163 4.

Baṣra too, which is an indication not only of his power, but also of the fact that the Yemen was not politically isolated. Ṭalib al Ḥaqq was defeated in 130/747 by Marwan's general, 'Abd al Malik ibn 'Aṭiyya, who on that occasion suppressed yet other rebels in the region, Yahya b. 'Abd Allah al Sabbaq and Yahya b. Karib; both were Ḥimyarites who were active in their tribal territories, in al Janad and the coastal areas respectively. By order of the caliph, Ibn 'Aṭiyya left before completing his operation, to lead the pilgrimage in his name. Before leaving he reached a peace agreement with the Ibaḍiyya of Ḥaḍramawt, granting them the right to choose their own governors. Thus Ḥaḍramawt remained under local Ibaḍi rule until the reign of al Maṣṣur (136 58/754 75).⁷²

The early 'Abbasids continued their predecessors' policies. Again, some times the Yemen was attached to the jurisdiction of the governor of Ḥijaz, who would appoint a representative there. And again, people of high standing received governorships, and the caliphs sometimes replaced governors at the Yemenites' request. Members of the 'Abbasid family served as governors, as well as *mawālī* of the caliphs, members of the Arab Muslim aristocracy (occasionally Yemenite themselves), and even a member of the Barmakid family. At the time of the latter, who served under Harun (r. 170 93/786 809), Ṣan'a' prospered, yet it is reported that the number of poor people was great.⁷³

The Yemen remained fragmented, and pre Islamic local conflicts continued, sometimes intertwined with sectarian opposition to the government. For example, a governor of local origin, 'Abd Allah b. 'Abd al Maḍan, declared his independence in 142/759, which induced al Maṣṣur to send his general, Ma'n b. Za'ida, to restore order. During his nine years in office (142 51/759 68) Ma'n suppressed insurrections in various parts of the Yemen, including Ṣa'da, al Janad and Ḥaḍramawt, where Ibaḍi Kharījism was active. He applied harsh measures that resulted in thousands of casualties, and led to his assassination.⁷⁴ In this period the 'Abbasids also stationed a garrison in Ṣan'a', but it was not

72 Yahya ibn al Husayn, *Ghayat*, pp. 124 6; Ḥamid, *Ta'rikh Ḥaḍramawt*, pp. 203 13; Sayyabī, *al Ḥaqqīqa*, pp. 89 96, 125 30 (according to this source the Ḥimyarite chiefs were Ibaḍīs, and the Ibaḍiyya was suppressed as early as 132/750); Mad'aj, *Yemen*, pp. 164 7; E. Francesca, 'Ṭalib al Ḥakk', *El2*, vol XII, p. 785.

73 Hamdanī, *Ṣifāt*, pp. 108, 112 13; Ahdal, *Tuḥfa*, pp. 140 50; Razī, *Ta'rikh*, pp. 105 8, 111 12; Yahya ibn al Husayn, *Ghayat*, pp. 31 2, 141 2, 146 7; Ibn al Dayba', *Qurrat*, pp. 115 131; Ḥamid, *Ta'rikh Ḥaḍramawt*, pp. 214 24; Mad'aj, *Yemen*, pp. 180 2, 190 6, 220 3.

74 Ahdal, *Tuḥfa*, p. 143; Sayyabī, *al Ḥaqqīqa*, pp. 45 6; Ḥamid, *Ta'rikh Ḥaḍramawt*, pp. 214 19; Mad'aj, *Yemen*, pp. 183 5; Stookey, *Yemen*, p. 44.

always adequate. For example, around 184/800 a Ḥimyarite chief, al Ḥayṣam b. 'Abd al Ṣamad, stirred up a rebellion against Harun (reigned 170 93/786 809), which coincided with an insurrection in the Tihama. The caliph sent reinforcements headed by his trusted *mawla*, Ḥammad al Barbarī, to restore order. As a result of the activity of this governor (184 94/800 10) the trade routes between Ṣan'a', al Yamama and Mecca became relatively secure, and economic prosperity followed. Ḥammad's success, however, was achieved by treating the Yemenites harshly. Their complaints to the caliph al Amīn did not go unheeded, and Ḥammad was replaced in 194/810.⁷⁵ Nevertheless, the Yemenites did not remain loyal to al Amīn. During the struggle between him and his brother al Ma'mun (r. 193 8/809 13) the latter's general, Ṭahir b. al Ḥusayn, sent a representative to the Yemen, Yazīd b. Jarīr. Yazīd caused the Yemenites to transfer their allegiance to al Ma'mun by employing unorthodox means. For example, he forced the Yemenites of Persian origins to divorce their Arab wives. Another one of al Ma'mun's appointees acted against all things Ḥimyarite. Among other things, he is reported to have cut down all Ḥimyarite apricot trees.⁷⁶

Al Ma'mun appointed and replaced some 15 governors.⁷⁷ In 200/815 an 'Alid pretender from Mecca, Ibrahīm b. Musa al Kaẓīm (brother of the well known 'Alī al Riḍa), occupied Ṣan'a' and controlled much of the highlands to the north; it is not certain whether he did so on behalf of the 'Alid rebel in Kufa, Ibn Ṭabaṭaba, or on his own accord. However, *dīnars* were struck in Ṣan'a' in his name, he stirred up tribal conflicts, indulged in murder and robbery of Yemenites, and perhaps took Mecca as well. He clashed with 'Abbasid troops on the outskirts of Mecca during the pilgrimage of 200/815, and shortly afterwards he was defeated by al Ma'mun's army in Ṣan'a'. His fortunes changed, however, with al Ma'mun's change of policy. When in 201/817 the caliph decided to appoint the eighth Imamī imam, 'Alī al Riḍa, as his successor, he also appointed 'Alī's brother, Ibrahīm b. Musa, first to Mecca, then to the Yemen. Al Ma'mun's governor since 200/815, Ḥamdawayh (or Ibn Mahan), refused to step down and rebelled against the caliph. Armies sent

75 Ahdal, *Tuhfa*, pp. 146 7; Razī, *Ta'rikh*, pp. 108 9; Yahya ibn al Ḥusayn, *Ghayat*, pp. 143, 146; Ibn al Dayba', *Qurrat*, pp. 131 6 (here al Ḥayṣam's revolt is a response to Ḥammad's harsh treatment); Mad'aj, *Yemen*, pp. 186 8, 203.

76 Yahya ibn al Ḥusayn, *Ghayat*, pp. 146 7; al Ṭabarī, *Ta'rikh*, vol. VIII, p. 440 (cf. p. 593: harsh treatment by governors incurred an 'Alid revolt in 207/822); Ibn al Dayba', *Qurrat*, pp. 139 41; Stookey, *Yemen*, p. 44.

77 Ahdal, *Tuhfa*, pp. 147 9; Mad'aj, *Yemen*, pp. 220 2; Stookey, *Yemen*, p. 44. See the full list in Zambauer, *Mu'jam al ansab*, pp. 175 6.

from Baghdad defeated Ḥamdawayh in 205/820, and Ibrāhīm remained to represent al Ma'mun in the Yemen until 213/828.⁷⁸

Ṣan'a' was to remain under the caliphs' control for some time. By the end of the third/ninth century it was greatly reduced due to the struggles between Zaydīs, Isma'īlīs (see below) and local contenders.⁷⁹ In other parts of the Yemen independent dynasties were established as early as al Ma'mun's time. Some of them came into being out of mere personal ambition, whereas others were the expression of sectarian ideologies. As opposed to other parts of the empire, dynasties here often did not cause fragmentation, but rather unified parts of the country that had long been fragmented.

Non-sectarian dynasties

The first of these dynasties was of al Ma'mun's own making (just as was the case in Khurasan). In 202/817, faced with a continuous tribal rebellion in the coastal area, he appointed Muḥammad b. 'Abd Allah b. Ziyad, a descendant of the famous general Ziyad b. Abīhi, to restore order. Ibn Ziyad remained in the Yemen but he did not always live up to the task, and the caliph had to send him reinforcements. Nevertheless, Ibn Ziyad established the town of Zabīd in Tihama and the Ziyadī dynasty, that lasted until 409/1019. The dynasty retained its base there, at times extending its influence over most of the Yemen, including Ṣa'da, Najran, Ṣan'a', Aden, Shihṛ and Ḥaḍramawt. Ziyadī Zabīd is described as a prosperous city, deserving of the name 'Baghdad of the Yemen'. Even when effectively independent, the Sunni Ziyadīs remained loyal to the 'Abbasids in appearance, and to orthodox (Sunni) Islam. Consequently, they constantly fought the Zaydīs and the Isma'īlīs (see below). By the second half of the fourth/tenth century the Ziyadīs had lost most of their holdings and had become nominal rulers in their own court, with their black slaves holding the real power. In 407/1016 or 409/1018 the last of the Ziyadīs was assassinated and one of his slaves founded a new dynasty, the Najahīs. Like its predecessor this dynasty was loyal to the *sunna* and the 'Abbasids, and therefore it engaged in constant struggle with the Ṣulayḥī Isma'īlī state. During the fifth/eleventh century the Najahīs were vassals to the ruler of Aden, and they lost many of their territories – some of them to local and tribal rulers; others, including their capital, Zabīd, to the Ṣulayḥīs

78 Al Ṭabarī, *Ta'rikh*, vol. VIII, pp. 535–6; Ahdal, *Tuḥfa*, pp. 147–9; Yaḥya ibn al Ḥusayn, *Ghayat*, pp. 148–51; Ibn al Dayba', *Qurrat*, pp. 144–7; Ibn Fahd, *Ghaya*, pp. 399, 405–7; Mad'aj, *Yemen*, pp. 205–8; cf. Sayyid, *Ta'rikh*, p. 52. The reports of Ibrāhīm's career are contradictory, see also above.

79 Razī, *Ta'rikh*, pp. 112–15; Yaḥya ibn al Ḥusayn, *Ghayat*, pp. 151–4, 165–7, 219.

and the Zaydīs. The Najahīs reasserted their rule several times, and survived until the middle of the sixth/twelfth century, when they were brought down by ‘Alī b. Mahdī, founder of the Mahdī dynasty in Zabīd.⁸⁰

The Ziyādī dynasty in Tihama had the blessing of the caliphate from its inception. Other dynasties, however, were opposed to the caliphate. Thus the Ḥimyarī chiefs, the Manakhīs, seized the southern part of the highlands, where they held sway from 214/829 until they fell to the Isma‘īlī ‘Alī b. al Faḍl in 293/906. In the central and northern highlands another Ḥimyarī chief, Yu‘fir b. ‘Abd al Raḥman al Ḥiwālī, based in Shibam, challenged ‘Abbasid authority. The latter was represented by the governors of Ṣan‘a’, and was also supported by some local chiefs and tribes. The conflict between the two lasted some twenty years (214 33/829 47). In 247/861 the Yu‘firīs established control over Ṣan‘a’ and a large part of the highland, from Ṣa‘da in the north to al Janad in the south, and in 258/871 2 they conquered Ḥaḍramawt as well. Being Sunnī, however, the Yu‘firīs were recognised by the ‘Abbasids in 257/870, to make a Sunnī front against the Zaydīs and the Isma‘īlīs in the Yemen. They sometimes paid homage, and even taxes, to the stronger Sunnī state, the Ziyādīs of Tihama. Their state lasted until the end of the fourth/tenth century.⁸¹

Religious activity and sectarian states

The Yemen was the theatre of intense religious activity, both political and literary. From the religious political point of view it was the Shī‘a, both Zaydī and Isma‘īlī, who were the most active. Ibaḍism, suppressed in the early second/eighth century (see above), recovered in Ḥaḍramawt, and the community was largely autonomous under the aegis of the Ziyādīs. During the first half of the fourth/tenth century Ibaḍism in Ḥaḍramawt faltered, reportedly due to the activity of the Shī‘a. This activity was introduced by Aḥmad b. ‘Isa, a descendant of the ‘Alid imam Ja‘far al Ṣādiq. Aḥmad left Baṣra in 318/930 as a result of the Qarmaṭī attacks, and migrated to Ḥaḍramawt (subsequently

80 Ahdal, *Tuhfa*, pp. 150 1; ‘Umara, *Mufīd*, pp. 49 77, 154 84; Naṣer e Khosraw, *Travels*, p. 71; Shams al Dīn al Muqaddasī, *Aḥsan al taqasīm fī ma‘rifat al aqalīm*, ed. M. J. de Goeje (Leiden, 1906), pp. 85, 104; Ibn al Dayba‘, *Qurrat*, pp. 322 60; Ḥarīrī, *Dirasat*, pp. 179 213; Sayyid, *Ta’rikh*, pp. 82 3; Mad‘aj, *Yemen*, pp. 208 12; Smith, ‘Political history’, pp. 130 2; Stookey, *Yemen*, pp. 45, 65 6, 75 6, 98; Zambauer, *Mu‘jam al ansab*, pp. 179, 181 2.

81 Ahdal, *Tuhfa*, pp. 148 52; ‘Umara, *Mufīd*, pp. 55 9; Yahya ibn al Ḥusayn, *Ghayat*, pp. 155, 160, 164 7; Ibn al Dayba‘, *Qurrat*, pp. 154 77, 182, 200 12, 218 21; Ḥarīrī, *Dirasat*, pp. 96 7, 181 2; Sayyid, *Ta’rikh*, pp. 54 5; A. ibn A. al Muta‘, *Ta’rikh al Yaman al Islāmī min sanat arba‘ wa mi‘atayn ila sanat alf wa sitt*, ed. ‘A. M. al Ḥibshī (Beirut, 1986/1407), pp. 70 4; Mad‘aj, *Yemen*, pp. 213 18, 233; Gochenour, ‘Penetration’, pp. 38 46; Stookey, *Yemen*, p. 54; Smith, ‘Political history’, pp. 130 1; Zambauer, *Mu‘jam al ansab*, pp. 179 80.

the descendants of the Prophet in Ḥaḍramawt came to be known as ‘sayyids’). The Shī‘a started to gain supporters in Ḥaḍramawt, but Ibaḍism reasserted itself in the fifth/eleventh century. The proximity of Ḥaḍramawt to Ibaḍī Oman certainly encouraged the Ḥaḍramī Ibaḍīs, and in the fifth/eleventh century Ḥaḍramawt was incorporated into the Omanī Imamate. The collapse of the latter, and the conquest of Ḥaḍramawt by the Isma‘īlī al Ṣulayḥī (see below), brought an end to Ibaḍism there, so that it left no lasting imprint.⁸²

Religio political as well as spiritual activity sometimes blended into the pre Islamic Yemenite institutions. Traditionally, the arms bearing tribes were the dominant class and so they remained after the advent of Islam. It was such tribes that protected the *ḥawṭas* (sacred enclaves) in Ḥaḍramawt, and the *hajar/hjiras* (protected areas and protected status), in Northern Yemen. Under the aegis of these institutions many leaders, scholars and saintly people were active. Some of them were descended from the Prophet (or pretenders), whereas others were descended from ancient saintly local families.⁸³

From the literary point of view, the cultural achievements of the Yemen are quite impressive. There were many historians and poets, some astronomers and mathematicians; but, above all, there were scholars of the religious sciences. Qur’an exegesis, jurisprudence, *ḥadīth* and theology thrived throughout the Yemen from the first/seventh century onwards, and some Yemenite scholars acquired fame all over the Islamic world.⁸⁴ Theological debates were common from an early date, given the presence of scholars, on the one hand,

82 Al Kaf, *Ḥaḍramawt*, pp. 40 1, 44; Bawazīr, *Ṣafahat*, pp. 56 79; Ḥamid, *Ta’rīkh Ḥaḍramawt*, pp. 245 7, 250, 261 72, 296 336, 360 (the author is a Shī‘ite, and he plays down the Kharijite revival, while emphasising the role of Aḥmad ibn ‘Isa); Sayyabī, *al Ḥaqīqa*, pp. 130 51 (the author is an Ibaḍī and he emphasises the exploits of this sect); Stookey, *Yemen*, p. 42; Serjeant, ‘Historians’, p. 241; R. B. Serjeant, ‘The sayyids of Ḥaḍramawt’, in R. B. Serjeant, *Studies in Arabian history and civilization*, Variorum Collected Studies VIII (Aldershot and Brookfield, VT, 1981), p. 9.

83 Serjeant, ‘Sayyids’; R. B. Serjeant, ‘South Arabia’, in R. B. Serjeant, *Studies in Arabian history and civilization*, Variorum Collected Studies IX (Aldershot and Brookfield, VT, 1981); R. B. Serjeant, ‘The interplay between tribal affinities and religious (Zaydi) authority in the Yemen’, *al abḥath*, 30 (1982); Gochenour, ‘Penetration’, pp. 165 73, 295; W. Madelung, ‘The origin of the Yemenite *hijra*’, in A. Jones (ed.), *Arabic Felix: Luminosus Britannicus, essays in honour of A. F. L. Beeston on his eightieth birthday* (Oxford, 1991), pp. 25 44 (according to Madelung, the institution of *hijra* in the Yemen is not pre Islamic).

84 Hamdanī, *Ṣifat*, pp. 103 7; Harīrī, *Dirasat*, pp. 81 9. Full details: Razī, *Ta’rīkh*, pp. 294 454; Aḥmad ibn Muḥammad al Shamī, *Ta’rīkh al Yaman al fikrī fī al ‘aṣr al ‘Abbasī*, 4 vols. (Beirut, 1407/1987); ‘A. M. al Hibshī, *Maṣadīr al fikr al Islāmī fī al Yaman* (Beirut, 1408/1988); ‘A. M. al Hibshī, *Mu‘allafat ḥukkam al Yaman*, ed. Elke Niewoehner Eberhard (Wiesbaden, 1979); Sayyid, *Ta’rīkh*; Serjeant, ‘Historians’.

and the involvement of the Yemen in the empire's events, on the other.⁸⁵ It may be noted that both the Yemen and the Ḥijaz suffered from long periods of instability. But whereas in the Ḥijaz this (among other things) led to a depletion of cultural activity, in the Yemen the rivalry between the schools, sects and enclaves produced a vast literature.

Some sources report that during the Umayyad period the idea of *jabr* (predetermination) was widespread in the Yemen, and that the most popular schools of law until the third/ninth century were the Ḥanafī and the Malikī. Whether or not these statements are accurate, it is clear that the third/ninth century represents a turning point in Yemen's history. The Shafī'ī school of law was introduced, and it subsequently became increasingly prevalent. Zabīd became the main centre of Shafī'ism, but the school was popular also in al Janad, Ḥaḍramawt, Aden and Ṣan'a'.⁸⁶ Towards the end of the century Zaydism and Isma'īlism entered the Yemen simultaneously, against the background of political division: the Ziyādī state in the Tiḥama; the Ḥimyarite Yu'firīs in Ṣan'a' and part of the highland southwards to Janad; the Ḥimyarite Manakhīs in the southern highland; and the tribes of the north, who were busy fighting one another and paying allegiance to no central power. It was in the latter, fragmented area that the Zaydis established themselves, whereas the Isma'īlīs (called 'Qaramiṭa' by the Zaydis, to be distinguished from the real Qaramaṭīs of Baḥrayn) entered the south, as well as the western part of the central mountain ranges.⁸⁷

The Zaydis

In 284/897 Yaḥya b. al Ḥusayn al Ḥasanī, entitled al Ḥadī ila al Ḥaqq (the 'Leader to the Truth'), arrived in the northern highlands from the Ḥijaz. As a descendant of 'Alī and Faṭīma and a respected religious authority, he was invited by chiefs of quarrelling Yemenite tribes to restore peace and order. His mission in the area a few years earlier had ended in failure and his departure, but this time he remained and succeeded in establishing a Zaydī regime (*imama*) based in Ṣa'da. Striving to extend his influence he fought the Yu'firīs and other tribal chiefs over Ṣan'a', as well as the Isma'īlī claimant to

85 See e.g. Razī, *Ta'rīkh*, pp. 356, 387, 393, 401.

86 Yaḥya ibn al Ḥusayn, *Ghayat*, p. 203; Ḥarīrī, *Dirasat*, pp. 79–80; Sayyid, *Ta'rīkh*, pp. 44–69; Serjeant, 'Historians', p. 239.

87 Yaḥya ibn al Ḥusayn, *Ghayat*, p. 167; Sayyid, *Ta'rīkh*, p. 55; P. Dresch, *Tribes, government and history in Yemen* (Oxford, 1989), p. 167; Gochenour, 'Penetration', pp. 38–46; Stookey, *Yemen*, p. 45.

power, 'Alī b. al Faḍl. Having failed to gain firm control of Ṣan'a', al Ḥadī returned to Ṣa'da, where he died in 298/911.⁸⁸

The period between 284 444/897 1052 is sometimes called the first Zaydī Imamate, but Zaydī imams continued to rise after this date as well, although not consecutively. The initial purpose for which the founder, al Ḥadī, was invited to the Yemen was in general not achieved. Although some of the imams were strong enough to unify the northern region of the Yemen, the Imamate did not succeed in establishing permanent peace or unity. In fact, the Zaydī regime can hardly be considered a state. There was no formal administrative apparatus and no fixed pattern of succession. The main criterion for eligibility, in addition to 'Alid descent, was military activity aimed at establishing Zaydism. This had several consequences. First, there were many interregna. Second, Zaydī imams were constantly struggling against non Zaydīs occasionally also against their own tribal supporters, because the latter might oppose the imam's enforcement of the Qur'anic punishments (*ḥudud*) and the levying of *zakat* (alms tax). Indeed, Islamic law often clashed with the entrenched customary law. This explains why Zaydī imams are sometimes portrayed as fighting tribalism as such. Third, Zaydīs were also often at war among themselves. Members of the Prophet's family, backed by different tribal groups, fought one another over leadership. Imams often became entangled in tribal disputes that had nothing to do with Zaydism.

The Zaydī imams were associated with tribal protected status and sacred enclaves (*hajar* or *hijra*), but their influence usually extended beyond one tribe. This ancient Yemenite institution served to spread Zaydism in the northern Yemen (although it should be noted that not all enclaves were Zaydī). There were many enclaves throughout the tribal territories that may have been independent from one another, but were regarded by the Zaydī historiography as parts of a single Zaydī state. Although entangled in tribal life and politics, the imams, also called *sayyids*, differed from the tribal leaders (*shaykhs*), in that they called to *jihad*, practised the Commanding of Right and Forbidding Wrong (*al amr bi 'l ma'ruf wa 'l nahy 'an al munkar*), rendered educational and spiritual services, dispensed Islamic justice, and enforced Islamic law as far as they could. It is remarkable that, although considered holy by virtue of descent from the Prophet, Zaydī imams were

88 Yahya ibn al Ḥusayn, *Ghayat*, pp. 166 90; 'Alī ibn Muḥammad ibn 'Ubaydallah, *Sīrat al Ḥadī Yahya b. al Ḥusayn*, ed. Suhayl Zakkar (Beirut, 1972); al Muṭa', *Ta'rīkh al Yaman*, pp. 74 146; Gochenour, 'Penetration', pp. 46 56; Smith, 'Yemenite history', pp. 137 8; Stookey, *Yemen*, p. 79. On the turbulent events in Ṣan'a' during the late third/ninth and fourth/tenth centuries see also ibn al Dayba', *Qurrat*, pp. 218 42.

characterised by learning and knowledge of the law, rather than supernatural powers. They were nevertheless distinguished not only from tribal leaders but also from the religious elite that was not descended from the Prophet. Although highly regarded, and although they functioned as leaders of *jihād*, the Zaydī imams remained dependent on the tribes for protection. And therefore, although they served as mentors, judges, arbiters, political leaders and military commanders, they cannot be considered as the ruling elite.⁸⁹

The first Zaydī Imamate was active in Ṣa'da and Najran, occasionally in Ṣan'a' and the Jawf, but Tihama was generally out of its reach. The first half of the fifth/eleventh century was a period of deterioration and sectarian division. One major new sect, led by a Yemenite, Muṭarrif b. Shihab, became known as Muṭarrifiyya. Although originating as a schism, this sect was beneficial to Zaydism as a whole, and it upheld and spread the mission when the descendants of the Prophet were unable to do so. By the middle of the century the first Zaydī Imamate had come to an end at the hands of the Isma'īlī dynasty, the Ṣulayḥīs. The Zaydīs established their second Imamate in 532/1138, simultaneously with the demise of the Ṣulayḥīs; it lasted until 980/1585.⁹⁰

The Isma'īlīs

Isma'īlī activity (*da'wa*) in the Yemen started perhaps in the second half of the third/ninth century. There is a report about a missionary, al-Ḥasan b. Faraj al-Ṣanadiqī, who based himself in Mudhaykhira, acquired many followers and conquered the Yemen. He pretended to be a prophet, committed many atrocities, and was the cause of a massive emigration.⁹¹ Reports about all this are, however, sparse even in Yemenite sources. We have better information about the organised mission and military activity of the Isma'īlīs towards

89 Ḥarīrī, *Dirasat*, pp. 62–8; C. van Arendonck, *Les débuts de l'imamat zaidite du Yemen*, trans. J. Ryckmans (Leiden, 1960), pp. 127–255; Gochenour, 'Penetration', pp. 64–294 (list of enclaves on p. 172); Dresch, *Tribes*, pp. 136–97; Serjeant, 'Interplay'; E. Landau-Tasseron, 'Zaydī imams as restorers of religion: *lḥya*' and *tajdīd* in Zaydī literature', *JNES*, 49 (1990).

90 Stookey, *Yemen*, pp. 57, 61, 95, 98; Dresch, *Tribes*, pp. 171–2. On the Muṭarrifiyya see Gochenour, 'Penetration', pp. 186–201. Further details on Zaydī imams and their exploits: Yahya ibn al-Ḥusayn, *Ghayat*, pp. 204–52; al-Muṭa', *Ta'rīkh al-Yaman*, pp. 146–61, 179–233, 291–312; Muḥammad ibn Muḥammad Zabara al-Ḥasanī, *Ithāf al-muhtadīn bi-dhikr al-a'imma al-mujaddīdīn* (Ṣan'a', 1343/1925); Muḥammad ibn Muḥammad Zabara al-Ḥasanī, *Ta'rīkh al-Zaydiyya*, ed. M. Zaynahm (Cairo, n.d.).

91 Maqrīzī, *Itti'āz*, pp. 222–3, see also Muḥammad ibn Aḥmad al-Dhahabī, *Siyar a'lam al-nubala'*, ed. S. al-Arna'ut and M. N. al-Arqaṣuṣī, 23 vols. (Beirut, 1413/1993), vol. X, p. 285.

the end of the third/ninth century. Two Isma'īlī missionaries were sent to the region. One of them, Abu al Qasim ibn Ḥawshab, succeeded in conquering the entire Jabal Miswar massif (north west of Ṣan'a') and became known as 'Maṣṣur al Yaman' ('the God aided one from the Yemen'). The other, 'Alī b. al Faḍl, was active in the south, took the former Manakhī capital, Mudhaykhira, in 293/906, then went to Ṣan'a'. The city was contested for several years between the Yu'firīs, the Zaydī al Hadī ila al Ḥaqq and 'Alī b. al Faḍl, and finally fell to the latter in 298/911. Encouraged by his success, 'Alī defected from the Isma'īlī cause, became independent and turned to fight his former partner, Maṣṣur al Yaman. 'Alī was assassinated by an agent of the Yu'firīs in 303/915, whereupon his regime collapsed. Maṣṣur al Yaman remained loyal to the Isma'īliyya and to the Faṭimids who meanwhile had taken power in the Maghrib (in 297/909). He continued to send Isma'īlī missionaries to other regions, such as Oman, Yamama and Sind. His regime was brought to an end by the internal quarrels after his death in 302/914. One of his successors transferred his allegiance to the 'Abbasids, and the Isma'īliyya in the Yemen became mostly an underground movement until the rise of the Ṣulayḥīs, an aristocratic family of the tribe of Hamdan.⁹²

'Alī b. Muḥammad al Ṣulayḥī, son of a Sunnī judge from the Ḥaraz district (to the west of Ṣan'a'), was chosen as agent for the Faṭimids in the Yemen. During the first half of the fifth/eleventh century he engaged in clandestine activity, and acquired fame and support. Towards the middle of the century he received permission to act in public, and he based himself at the mountain of Masar in his native district. Having defeated the Zaydī imam of Ṣa'da and the local rulers of Ṣan'a' and the Ḥaḍur district to the north, 'Alī proceeded to consolidate his authority by military exploits, diplomacy and intrigue. After few clashes with the ruler of Zabīd, Najah, the latter died (in 452/1060), apparently of poisoning arranged by 'Alī himself. 'Alī thus gained control of the Tihama, whereupon he conquered the southern part of the Yemen, including Aden and Ḥaḍramawt. By 455/1063 he had unified the Yemen as it had been under the pre Islamic Ḥimyarites, although some anarchic tribal areas remained, as well as petty chiefdoms, such as Āl Qaḥṭan, Banu al Da'ar and Āl Faris in Ḥaḍramawt.⁹³ Based in Ṣan'a', 'Alī personally appointed governors to the provinces and supervised their work, as well as the work

92 Ahdal, *Tuhfa*, pp. 153 64, 168 71; 'Umar, *Mufīd*, pp. 59 63; Yahya ibn al Ḥusayn, *Ghayat*, pp. 191 209, 219; Ibn al Dayba', *Qurraṭ*, pp. 182 217; Ḥafīf, *Dirasat*, pp. 188 90; Stookey, *Yemen*, pp. 52 7; W. Madelung, 'Maṣṣur al Yaman', *EL*, vol. VI, p. 438.

93 Al Kaf, *Ḥaḍramawt*, pp. 45 8; Ḥamid, *Ta'rīkh Ḥaḍramawt*, pp. 403 28.

of the missionaries sent to spread the Ismaʿīlī ideology. He remained attached to the court in Cairo, received his orders from the caliph al Mustanṣir, and often appealed to him for advice and authorisation of his actions. ʿAlī al Ṣulayḥī acted in the Ḥijaz as well on behalf of his patrons, secured the allegiance of Mecca to Cairo, and carried out renovations in the holy places. However, his relations with the *sharīf* of Mecca sometimes necessitated the mediation of the Faṭimid caliph.⁹⁴

ʿAlī al Ṣulayḥī was constantly at war, whether against Ethiopian invasions or against numerous internal enemies, including tribal chiefs, rival dynasties and sects and Ismaʿīlīs who had gone astray. His staunchest enemies, however, were the Najahīs. The struggle between these two states continued, with Zabid frequently changing hands, until both dynasties came to a simultaneous end in the middle of the sixth/twelfth century. It appears that the issue in this struggle was not only Sunnism versus Ismaʿīlism, but also control of the Tihama, which ensured control of the trade via the Red Sea.

It was the Najahīs who killed ʿAlī al Ṣulayḥī in 460/1067, while he was on his way to perform the pilgrimage. His son al Mukarram took over, and successfully withstood both rebellions and attacks by traditional enemies, namely, the Zaydīs and the Najahīs. He avenged his father's death, rescued his mother from captivity in the hands of the Najahīs, and brought the Ṣulayḥī state to its peak. The extent of his power may be gauged from the fact that in 460/1068 he reportedly succeeded in defeating a tribal coalition numbering 30,000 men (this number may be a topos, but it conveys large numbers). Another indication of his eminence is that in 468/1075 the caliph entrusted him with conducting the Ismaʿīlī mission in India.⁹⁵ However, al Mukarram became too ill to conduct the affairs of the state, and the throne went to his wife Arwa even before his death (that occurred in 477/1094). The Free Lady (al Sayyida al Ḥurra) was recognised by the caliph in Cairo, moved her court to Dhu Jibla in the southern mountains and continued the struggles against the Najahīs and other opponents. She was also involved in the Ismaʿīlī movement at large. In the schism that broke out in 487/1094 she sided with the Egyptians who supported al Mustaʿlī bi Allah (as against his brother Nizar). Al Mustaʿlī in turn reconfirmed her position as both ruler and chief missionary.

94 See e.g. A. F. Sayyid, P. Walker M. A. and Pomerantz, *The Faṭimids and their successors in Yaman: The history of an Islamic community*, Arabic edn and English summary of Idrīs ʿImad al Dīn's *ʿUyun al akhbar*, vol. VII (London and New York, 2002) (henceforth ʿImad al Dīn, *ʿUyun*), p. 36.

95 *Ibid.*, pp. 117–27, 131–44, 152.

The Ismaʿīlī missionary ʿImad al Dīn (d. 872/1468) describes Arwa as a pious and learned woman who successfully implemented both her political and religious tasks.⁹⁶ But it appears that, being a woman, Arwa could not herself act as a missionary, just as she did not herself lead troops to battle. A chief judge sent from Cairo, Lamak b. Malik, and his son, acted by her side as auxiliary missionaries. Other major officials were Saba' b. Aḥmad, al Mufaḍḍal b. Abī al Barakat and Ibn Najīb al Dawla (the latter sent from Cairo in 513/1119, and sent back as a prisoner in 519/1125). Perhaps her gender was also one of the causes that led to the undermining of Arwa's authority by her own appointees (although ʿImad al Dīn expressly denies this). In addition, she was unable to retain Ṣulayḥī military superiority, and her armies were soundly defeated by a coalition of the Zaydīs and Najahīs in 479/1087. Ṣan'a', which had been changing hands between Ṣulayḥī governors and local Hamdanī rulers already in al Mukarram's time, fell to the Āl Ḥatim family in 493/1098.⁹⁷ In the Cairo crisis of 526/1130 Arwa remained loyal to the marginalised Faṭimid heir, al Ṭayyib, and refused to follow the regent (ʿAbd al Majīd al Ḥafīz). This crisis estranged her from the Faṭimid court and further weakened the Ṣulayḥī state, which shrank and deteriorated.⁹⁸ After Queen Arwa's death in 532/1137, the Banu Zuray' of Aden took over. This petty dynasty had ruled Aden (after having replaced the local Banu Ma'n) since 476/1083, under the patronage of the Ṣulayḥīs. Its relations with Arwa, however, were not always peaceful. Fifteen years after her death they bought the main castles and towns from al Maṣṣur b. al Mufaḍḍal, the son of her former official, became independent, and sided with the Egyptian Ismaʿīlī mission, which had been rejected by Arwa. The Zuray'īs fell to the Ayyubids with the rest of the Yemen in 569/1173.⁹⁹ Ismaʿīlī missionaries, however, with tribal backing from the Hamdan, continued their activities underground for centuries. They were

96 Ibid., pp. 278–9.

97 Ibid., pp. 304–9.

98 On the Ṣulayḥī dynasty from its foundation see *ibid.*, pp. 5–36, 98–177, 199–200, 213–15, 271–310; ʿUmara, *Mufaḍḍal*, pp. 83–138; Yahya ibn al Ḥusayn, *Ghayat*, pp. 253–301; Ibn al Daybaʿ, *Qurrat*, pp. 218–304; Ḥamid, *Taʾrīkh Ḥaḍramawt*, pp. 340–64; Ḥarīrī, *Dirasat*, pp. 190–211; Sayyid, *Taʾrīkh*, pp. 91–169; Stookey, *Yemen*, pp. 58–77; Smith, 'Political history', p. 132. The career of the founder, ʿAlī, is especially difficult to follow: see Gochenour, 'Penetration', pp. 307–16.

99 ʿImad al Dīn, *ʿUyun*, pp. 274–8, 310; ʿUmara, *Mufaḍḍal*, pp. 139–52; Ibn al Daybaʿ, *Qurrat*, pp. 304–20; Ḥamid, *Taʾrīkh Ḥaḍramawt*, pp. 345–53; Ḥarīrī, *Dirasat*, p. 105; Smith, 'Political history', p. 133; Zambauer, *Muʿjam al ansab*, p. 181. Al Mukarram, grandfather of Zuray', is not to be confused with al Mukarram, son of ʿAlī al Ṣulayḥī. See further on the Ismaʿīlīs in the Yemen and all their rivals: al Muṭaʿ, *Taʾrīkh al Yaman*, pp. 121–295.

mostly based in strongholds around Ṣan‘a’, monitoring the *da‘wa* not only in the Yemen but also in the Ḥijaz, Sind and Oman.

Oman

Oman had many peculiar features to its economy, its social organisation, its internal divisions and the patterns of authority and government. These were strongly affected by its location and by its geography and topography.¹⁰⁰

Oman lies on the south eastern corner of the Arabian Peninsula, and contains a coastal plain, mountain ranges and desert. The coastal area, known as the Baṭīna, is easily accessible from Iraq on the one hand, and from the Far East and Africa on the other. Its inhabitants on the eve of Islam were fishermen, sailors, pearl divers, traders, textile manufacturers and farmers. Many were Persian, and in the coastal town of Ṣuḥar the spoken language was Persian even in the fourth/tenth century. The interior, known as the Ṣāhira or Jawf, lies beyond the range of the Ḥajar and the al Akḥḍar mountains, and is much less accessible than the coast. Its inhabitants were settled and nomadic tribesmen. The Azd tribes, who were considered Southern Arabs, were dominant from ancient times, but many tribal groups from other parts of the Peninsula moved into the region before as well as after the advent of Islam. Among them were those from amongst the so called ‘Northern’ tribes, namely the Quraysh, Tamīm, ‘Āmir, ‘Abs and Dhubyān, to name but a few. These facts played a decisive role in Oman’s turbulent history. The coastal area with its capital, Ṣuḥar, took part in the international trade that brought much wealth and power. It was therefore a bone of contention between the coastal population, the inland tribes and foreign powers that attacked Oman recurrently. The inland tribes, thanks to their geographical position, were often able to retain their independence, even when the Baṭīna was occupied by foreign powers.

The details of Oman’s history are immensely confused due to incessant invasions, the division between the coast and the interior, the internal wars and the biases of the local historians. The latter were mainly religious scholars of the Kharijite Ibaḍī sect, and the scope of their interest in history was relatively limited. According to the Omanī historian Salīmī (d. 1332/1914), ‘the Omanis are not interested in history, so most of the reports about the [Ibaḍī] imams are lost, to say nothing of reports about others’. Indeed, Salīmī, among other historians, often points to lacunae in the historical

¹⁰⁰ See J. C. Wilkinson, *The imamate tradition of Oman* (Cambridge, 1987). Detailed geographical description in C. Holes, ‘Uman’, *EL2*, vol. X, p. 814.

information. To add to the difficulties, many of the Omanī sources are still in manuscript form.¹⁰¹

Oman from the first/seventh to the third/ninth century

At the beginning of the first/seventh century Oman was under Persian influence, and its internal affairs were run by a local family of the Azd tribe, the Julanda. Towards the end of the Prophet's lifetime the rulers, Jayfar and 'Abd (or 'Abbad), sons of al Julanda, were converted to Islam. After Muḥammad's death in 11/632 a movement of opposition to Islam and to the Julanda occurred, referred to in Islamic historiography as 'the apostasy of the Omanīs' (*riddat ahl 'Uman*). The Julanda overcame the revolt with the assistance of troops sent by Abu Bakr. It may be noted that the conversion of Oman to Islam was coupled with the expulsion of the Persians.¹⁰²

Universal histories record the names of several governors appointed by Abu Bakr (r. 11 13/632–4) and 'Umar (r. 13 23/634–44) to Oman. The region was usually attached to Baṣra, but occasionally it belonged to the same jurisdiction as Baḥrayn or Yamama. Governors sent from Medina were based in the coastal town of Ṣuḥar and had the tasks of collecting taxes and leading military expeditions eastwards.¹⁰³ The general sources, however, tend to ignore the role of Jayfar and 'Abd after the *ridda*. It appears from the local sources that the brothers remained in office, just as they had in the Prophet's time. During 'Umar's time the two Julanda brothers Jayfar and 'Abd died and were succeeded by the

101 Shalabī, *Mawsu'a*, pp. 11 24; 'A. 'A. al 'Ānī, *Ta'rikh 'Uman fī al 'uṣūr al Islamiyya al ula* (London, 1420/1999), pp. 44 53; J. C. Wilkinson, 'Bibliographical background to the crisis period in the Ibadī imamate (end of the ninth to end of the fourteenth century)', *Arabian Studies*, 3 (1976); Wilkinson, *The imamate*, pp. 364 72; Ḥasan M. Naboodah, 'Banu Nabhan in the Omani Sources', in G. R. Smith, J. R. Smart and B. R. Pridham (eds.), *New Arabian Studies*, 4 (Exeter, 1997), pp. 181 4. See also Salimī's remark: Nur al Dīn 'Abd Allah ibn Ḥumayd al Salimī, *Tuhfat al a'yan bi sirat ahl 'Uman*, vol. I (Cairo, 1380/1961), p. 353, see also pp. 338, 342. International trade: 'Ānī, *Ta'rikh*, pp. 79 81, 85; Hourani, *Arab seafaring*, pp. 61 83. Tribes: Salim ibn Ḥamud al Sayyabī, *Is'af al a'yan fī ansab ahl 'Uman* (Beirut, 1384/1965); 'Ānī, *Ta'rikh*, pp. 57 69.

102 Al Ṭabarī, *Ta'rikh*, vol. III, pp. 95, 314 16; Yaqut ibn 'Abd Allah, *Mu'jam al buldan*, 5 vols. (Beirut, n.d.), vol. III, p. 27; Ya'qubī, *Ta'rikh*, vol. II, p. 122; Salimī, *Tuhfa*, pp. 53 69; Anonymous, *Ta'rikh ahl 'Uman*, ed. S. 'A. 'Ashur (Oman, 1986), pp. 40 4; Kala'i, *Iktifa'*, vol. II, pp. 398 401, vol. III, pp. 92 4; 'Ānī, *Ta'rikh*, pp. 95 109; Shalabī, *Mawsu'a*, pp. 228 30; Wilkinson, *The imamate*, p. 205; J. C. Wilkinson, 'The Julanda of Oman', *Journal of Oman Studies*, 1 (1975); M. Kervran, 'Ṣuḥar', *EL2*, vol. IX, p. 774.

103 Al Ṭabarī, *Ta'rikh*, vol. III, pp. 479, 623; Yusuf ibn 'Abd Allah ibn 'Abd al Barr al Qurṭubī, *al Isti'ab fī ma'rifat al aṣḥab*, ed. 'A. M. al Bījawī, 4 vols. (Beirut, 1412/1992), vol. III, pp. 1035, 1082, 1187; Aḥmad ibn 'Alī ibn Ḥajar al 'Asqalanī, *al Iṣāba fī tamyiz al ṣaḥaba*, ed. A. M. al Bījawī, 8 vols. (Beirut, 1412/1992), vol. II, p. 44; Dhahabī, *Siyar*, vol. II, p. 374; Khalīfa b. Khayyāṭ al 'Uṣfurī, *Ta'rikh*, ed. A. Ḍ. al 'Umarī, 2 vols. (Beirut and Damascus, 1397/1976), vol. I, pp. 124, 278; 'Ānī, *Ta'rikh*, p. 116.

latter's son, 'Abbad b. 'Abd, who in turn was succeeded by his two sons, Sulayman and Sa'īd.¹⁰⁴

In addition to highlighting the role of the Julanda family, local sources tend to play down the *ridda* in Oman, and to emphasize the loyalty and support that the Omanīs gave to Medina at that difficult time, and later as well.¹⁰⁵ Indeed, in the Rashidun period many Omanīs departed for the conquered territories and played an important role in the conquests and settlement of Iran and territories further east. Omanī maritime expertise was of great service in launching military expeditions against the west coast of India. The Omanī Muhallabī family, among others, left a deep mark on both the military exploits and the politics of the Umayyad period. In addition, Oman gradually replaced coastal Baḥrayn as the main centre of maritime trade in the Persian Gulf.¹⁰⁶

Oman did not participate in the first civil war of 36 41/656 661. When this war ended with the Umayyads' victory, the Julanda brothers, Sulayman and Sa'īd, became independent. During the second civil war (61 73/680 92) Najda b. 'Āmir, leader of an extremist Kharijite faction, conquered Oman for a short period of time, but the Julanda brothers succeeded in re establishing their position.¹⁰⁷ Kharijite migration from Baṣra, however, which began after the first civil war, continued through the second half of the first/seventh century, turning Oman into a centre of Kharijite activity. The most prominent among the Kharijites in Oman were the Ibaḍīs, that is, the followers of Ibn Ibaḍ, who represented a moderate form of Kharijism.

It was only under the caliph 'Abd al Malik (r. 65 86/685 705) that the governor of Iraq, al Ḥajjaj b. Yusuf, dispatched troops that re conquered Oman, albeit with great difficulty. The Julanda brothers fled to East Africa, and governors representing the Umayyads were henceforth sent to Oman. The governor of Iraq shouldered the responsibility of appointing these, but when there were complaints about them, the caliph sometimes intervened.¹⁰⁸ There is no information about Omanī insurrections during the Marwanid period (64 132/684 749), but a certain report suggests that such

104 Sirḥan ibn Sa'īd ibn Sirḥan al Izkiwī (attrib.), *Annals of Oman to 1728*, trans. and annotated E. C. Ross (Cambridge and New York, 1984), p. 10; Anonymous, *Ta'riḥ*, pp. 45 7; 'Ānī, *Ta'riḥ*, pp. 113 17, 214.

105 E.g. Anonymous, *Ta'riḥ*, pp. 40 5; Izkiwī (attrib.), *Annals*, pp. 9 10; Salimī, *Tuhfa*, pp. 69 73.

106 Aḥmad ibn Yahya al Baladhuri, *Futuḥ al buldan*, ed. R. M. Riḍwan (Beirut, 1983/1403), p. 420; P. Casey Vine (ed.), *Oman in history* (London, 1995), pp. 136 60; 'Ānī, *Ta'riḥ*, pp. 140, 177 84. The Muhallabīs: M. Hinds, 'An early Islamic family from Oman: al 'Awtabī's account of the Muhallabids', *JSS*, Monograph 17 (Manchester, 1991).

107 Ibn al Athīr, *Kamil*, vol. IV, p. 21; 'Ānī, *Ta'riḥ*, pp. 117 19.

108 Khalīfa, *Ta'riḥ*, vol. I, pp. 297, 310, 319, 367; Abu Nu'aym al Iṣbahani, *Ḥilyat al awliya'*, 10 vols. (Beirut, 1405/1985), vol. V, p. 290, see also vol. IX, p. 31 (the caliph intervenes in

events did occur. It is related that 'Umar II (r. 99 101/717–20) issued a decree concerning Muslim Omanī captives.¹⁰⁹ These captives may have been rebels, supporters of Yazīd b. al Muhallab, one of the chiefs of the Omanī Aزد and governor of Khurasan and Iraq for 'Abd al Malik and Sulayman (r. 96 9/715–17) respectively. Yazīd b. al Muhallab made many enemies during his long career, including the caliph 'Umar II, who had him deposed and imprisoned in 99/717. In 101/720 Yazīd staged a revolt and succeeded in extending his control over Iraq, southern Iran and Oman. His revolt lasted only a few months, and after having defeated him, the Umayyads returned to control Oman.¹¹⁰

Despite Umayyad rule, the ancient local Julanda family remained powerful. Shortly after the advent of the 'Abbasids in 132/750, the Ibaḍiyya elected al Julanda b. Mas'ud as their ruler (imam), although his family did not support the sect. The 'Abbasids, on their part, appointed governors to Oman. The Ibaḍiyya seems to have taken over with the help of the second 'Abbasid governor, who sympathised with them. Al Julanda was powerful enough to repel an invasion by Ṣufrī Kharijites in 134/752, and to inflict heavy casualties on 'Abbasid troops sent to Oman. He was, however, eventually killed by these troops, reportedly together with 10,000 Omanīs. His rule was brief, but it is remembered in Omanī history as just and righteous, the precursor of the first Imamate, and al Julanda himself is lauded as the best of all the subsequent imams.¹¹¹ After his death a period of unrest ensued, characterised by fragmentation and constant feuds. Despite the 'Abbasid victory it seems that no governors were sent to Oman.¹¹² Two leaders of the Julanda family, Muḥammad ibn Za'ida and Rashid b. Shadhan (or al Naẓr), stand out in Ibaḍī historiography as oppressors, presumably because they acted as agents of the 'Abbasids.

the matter of the *ṣadaqa* tax); Muḥammad ibn Isma'īl al Bukharī, *al Ta'rikh al kabīr*, ed. H. al Nadwī, 8 vols. (Beirut, n.d.), vol. III, p. 79, vol. VI, p. 348; Salimī, *Tuhfa*, pp. 74–7; Sirḥan ibn Sa'īd ibn Sirḥan al Izkiwī (attrib.), *Kapitel XXXIII der anonymen arabischen Chronik Kaṣfal ġumma al ġami li ahbar al umma*, ed. and trans. Hedwig Klein (Hamburg, 1938), pp. 11–15; Izkiwī (attrib.), *Annals* pp. 10–12; Anonymous, *Ta'rikh*, pp. 47–51; 'Anī, *Ta'rikh*, pp. 120–2; Sayyabī, *Is'af*, pp. 74–6; Shalabī, *Mawsu'a*, pp. 231–2. On the Ibaḍiyya, see Lewicki, 'Ibaḍiyya', *EL*, vol. III, p. 648.

109 'Abd al Razzaq al Ṣan'anī, *Muṣannaf 'Abd al Razzaq*, ed. Ḥ. al A'zamī, 11 vols. (Beirut, 1403/1983), vol. X, p. 105.

110 'Anī, *Ta'rikh*, p. 121. On Yazīd see P. Crone, 'Muhallabids', *EL*, vol. VII, p. 358.

111 Al Ṭabarī, *Ta'rikh*, vol. VII, pp. 462–3, cf. p. 353; Ibn Kathīr, *Bidaya*, vol. X, p. 57 (Julanda is identified here as leader of the Ṣufriyya, instead of the Ibaḍiyya); Izkiwī (attrib.), *Annals*, pp. 12–13; Anonymous, *Ta'rikh*, pp. 54–5; Salimī, *Tuhfa*, pp. 88–102, 276; Casey Vine (ed.), *Oman*, pp. 164–5; Laura Vecchia Vaglieri, 'L'Imamato Ibaḍī dell'Oman', *Annali* (Istituto Universitario Orientale, Napoli), n.s. 3 (1949).

112 Only one governor is mentioned: see al Ṭabarī, *Ta'rikh*, vol. VIII, p. 204.

In 177/793 the Ibaḍīs succeeded in overcoming other powers and established a state. Their religious leaders elected a man of the Azdī Yaḥmad confederation as imam, and when he displeased them, they deposed him and chose another.¹¹³ This pattern of government was relatively stable for about a century. Imams, mostly Yaḥmadīs (from either the Kharuṣ or the Faḥl clan), ran a unified Imamate that extended from Baḥrayn to the Yemen, and that was also recognised by the Ibaḍī community of Ḥaḍramawt. Many imams reigned for long periods.¹¹⁴ In its structure and ideas the Imamate differed considerably from the Caliphate. There was no ruling family and no hereditary succession. It was a tribal community in which the leader was elected by a group of elders (namely, religious scholars), took his decisions by consultation, had no privileged position, and had only limited authority to compel military service. The Imamate was intertwined with the tribal concepts and cultures, yet the imams were not merely tribal leaders, and the latter did not disappear from the scene.¹¹⁵ Such a pattern of government would suggest instability and weakness, but the imams of the second/eighth and third/ninth century successfully repelled attacks by several enemies, among them invaders from India, and troops sent by Harun al Rashīd (r. 170 93/786 809). Oman prospered in this period, mainly due to the role it played in international maritime trade. Not only did it serve as a depot but its trade also expanded overseas, in the Indian Ocean as well as on the East African coast. But stability was not to last. Contenders for power and for wealth, among them descendants of the ancient ruling family, the Julanda, repeatedly challenged the imams.¹¹⁶ These internal struggles turned into a major civil war in the last third of the third/ninth century.

Oman from the third/ninth to the fifth/eleventh centuries

The civil war is usually portrayed simply as a struggle between the two factions that are known to have been rivals in many parts of the empire, namely the 'Southerners' ('Yaman') and the 'Northerners' (known variously as 'Qays', 'Muḍar' or 'Nizar'). In Oman the 'Southerners' meant in particular the Azd and the

113 Izkiwī (attrib.), *Annals*, pp. 13 14; Anonymous, *Ta'rikh*, pp. 56 8; Salimī, *Tuhfa*, pp. 107 17; Wilkinson, *The imamate*, p. 9. Casey Vine (ed.), *Oman*, pp. 165 6.

114 Ten, twelve, eighteen and even thirty five years: see Anonymous, *Ta'rikh*, pp. 60, 62, 63, 67; Wilkinson, *The imamate*, pp. 9 10; Wilkinson, 'Bibliographical background', p. 137.

115 Wilkinson, *The imamate*, pp. 91 212.

116 Izkiwī (attrib.), *Annals*, pp. 14 19; Izkiwī (attrib.), *Kapitel*, pp. 18 27; Anonymous, *Ta'rikh*, pp. 58 68; Wilkinson, 'Bibliographical background', p. 138; Casey Vine (ed.), *Oman*, pp. 168 9. For the attacks by Harun in 170/786 and 189/804, see Khalifa, *Ta'rikh*, vol. I, p. 447; al Ṭabarī, *Ta'rikh*, vol. VIII, p. 317; Salimī, *Tuhfa*, pp. 118 19.

'Northerners' meant in particular the Banu Sama group. In actuality, however, the conflict was a complex matter that involved not only tribes, but also regions (the Baṭīna and the eastern valleys of Jabal al Akhḍar as against the interior), as well as factions within the Ibaḍiyya. The caliph al Mu'taḍid and the governor of Baḥrayn were drawn into the struggle as well. The latter, Muḥammad b. Thawr (or Nur, or Bur), conquered Oman in 280/893, wreaked devastation and caused many Azdīs to emigrate.¹¹⁷ Thus 'Abbasid intervention in the civil war helped bring down the first Imamate of Oman.

The period that followed was extremely turbulent, and the sources are very confused. While tribal, ideological and regional motives stirred up internal conflicts, there was also a growing interest on the part of foreign powers in controlling the Gulf. The country was divided, the coastal area alternately occupied by the 'Abbasids, the Qarmaṭīs from Baḥrayn (who first invaded Oman in 318/930), the Ṣaffarids, the Buwayhids, and later the Saljuqs, while the inland tribes continued to elect imams or tribal chiefs, to fight one another, and to struggle against the foreign powers all at the same time. Imams and tribal chiefs were elected over various tribes and areas simultaneously, so that the authority of each was very limited and struggles continued incessantly. The Ibaḍiyya became increasingly divided between two schools, known as the Nizwa school and the Rustaq school, after their respective centres (Nizwa was the capital of the interior, Rustaq the capital of the Ghadaḥ, i.e. the eastern valleys of Jabal al Akhḍar). Ostensibly the major divide was the question of blame for the major civil war of the third/ninth century, a matter that was never resolved.¹¹⁸ An attempt to bridge the internal differences was made after 323/934 when the Ibaḍī scholars agreed to suspend further judgement and refrain from quarrelling among themselves. They then elected an imam, Rashid b. al Walīd of the Kinda tribal confederation (the majority of the imams were of the Azdī Kharuṣī group). Based in Nizwa, this imam is said to have gained wide recognition. However, he was subsequently deserted by his followers and

117 Izkiwī (attrib.), *Annals*, pp. 20–3; Izkiwī (attrib.), *Kapitel*, pp. 27–37; Anonymous, *Ta'rikh*, pp. 68–74; Salimī, *Tuhfa*, pp. 196–263; 'Ānī, *Ta'rikh*, pp. 137–8; Shalabī, *Mawsu'a*, pp. 741–2; Wilkinson, *The imamate*, pp. 9–10, 202–10; Wilkinson, 'Bibliographical background', p. 138; Casey Vine (ed.), *Oman*, pp. 170–1.

118 Izkiwī (attrib.), *Kapitel*, pp. 38, 40; Anonymous, *Ta'rikh*, pp. 75–91; Salimī, *Tuhfa*, pp. 263–78, 288–94, see also 349, 352; Wilkinson, *The imamate*, pp. 11, 166–8, 201, 209, 349 note 20; Casey Vine (ed.), *Oman*, pp. 171–2. See also ibn Kathīr, *Bidaya*, vol. XI, p. 120: 'Oman's ruler' (*ṣaḥīb*) sends presents to the 'Abbasid caliph, in 301/914, probably a token of submission. For a list of imams see Zambauer, *Mu'jam al ansab*, pp. 191–3 (they seem to be represented as a dynasty, which is misleading).

forced to capitulate to the sultan. The source mentions neither the date of these events nor the identity of the 'sultan'.¹¹⁹

In the fourth/tenth century there is mention of 'the ruler of Oman' (*ṣaḥīb 'Uman*), one Yusuf b. Wajīh, a non Ibaḍī who apparently controlled the coastal plain. Very little is known of him, although he almost conquered Baṣra in 331/943 and again in 340/951 (and perhaps also in 341/952).¹²⁰ In 354/965 Yusuf's assassin and successor, his black *mawla* Nafī', submitted to the Buwayhids, but the Omanīs rejected this move and turned to pay allegiance to the Qarmaṭīs of Hajar (Baḥrayn). Under nominal Qarmaṭī rule conflicts continued, among them clashes within the army between units of white soldiers against the black ones (Zanj, East African blacks who reportedly numbered 6,000 men).¹²¹

In 355/966 the Buwayhids conquered Oman, but they had to re conquer it subsequently. It appears that their main objective was to destroy the maritime strength of the port of Ṣuḥar and to secure for themselves the route from the Gulf into the Indian Ocean. A major battle occurred in 362/972, when Zanj (blacks, presumably from the Omanī army) killed the Buwayhids' appointee, 'Umar b. Nabhan, and appointed one Ibn Ḥallaj as a ruler. Buwayhid armies dispatched from Kirman defeated the Zanj on land and at sea. Another Buwayhid army, sent against the inland Ibaḍiyya, was victorious as well, and caused the Ibaḍī imam to flee Nizwa for Yemen. In 394/1003 Baha' al Dawla, then ruler of the Buwayhid confederacy, appointed his friend and father in law, Abu Muḥammad b. Mukram, as governor. Thereafter members of this family ruled Oman for about half a century. They kept close relations with the Buwayhids, and were sometimes embroiled in their quarrels.¹²² It appears,

119 Izkiwī (attrib.), *Annals*, pp. 26 30; Salimī, *Tuhfa*, pp. 279 85; Sayyabī, *Is'af*, p. 136; cf. Wilkinson, *The imamate*, pp. 210 12; Anonymous, *Ta'riḫh*, pp. 84 91.

120 Ibn al Athīr, *Kamil*, vol. VII, pp. 173, 241 (but on p. 185 he has Yusuf assassinated already in 332/943); Ibn Kathīr, *Bidaya*, vol. XI, pp. 224, 225; Muḥammad ibn 'Abd al Malik al Hamdanī, *Takmilat ta'riḫh al Ṭabarī*, ed. A. Y. Kan'an (Beirut, 1957), pp. 135, 165; Izkiwī (attrib.), *Kapitel*, p. 65 of the German text, Klein's note to p. 40.

121 Ibn al Athīr, *Kamil*, vol. VII, pp. 290 2; Salimī, *Tuhfa*, pp. 289 91; Casey Vine (ed.), *Oman*, pp. 174 5. See also Zambauer, *Mu'jam al ansab*, p. 193. The latter (p. 194) also mentions two rulers of Banu Sama between 300 and 316, based only on ibn Khaldun's *Ibar*.

122 Ibn al Athīr, *Kamil*, vol. VII, pp. 292 3, 348 9, 354 5, vol. VIII, pp. 14, 224, 233 4, 253; Salimī, *Tuhfa*, pp. 285 93, 318 20; Wilkinson, *The imamate*, pp. 10, 213, and p. 349 note 20. The latter seems to identify the Nabhanīs with the Mukramids. The Nabhanīs rose to power in the sixth/twelfth century, but Salimī, *Tuhfa*, p. 352 records an earlier phase of this dynasty (mentioning no dates), while omitting mention of the Mukramids. Zambauer omits mention of the Mukramids as well. Abu Muḥammad ibn Mukram also served the Buwayhids outside Oman, and was deeply involved in Buyid politics: see e.g. ibn al Athīr, *Kamil*, vol. VII, p. 496, vol. VIII, pp. 137, 144 5, 166. See also Casey Vine (ed.), *Oman*, pp. 175 6.

however, that the dynasty mainly controlled the coastal plain, while Ibaḍī imams continued to be elected in the interior.¹²³ It is remarkable that Oman continued to be a centre for maritime trade connecting the Far East and Africa with the caliphate despite the unstable political conditions of the third/ninth and the fourth/tenth centuries. Ṣuḥar, and to a lesser extent Maṣqaṭ, served as centres for this trade and enjoyed prosperity.¹²⁴

A special feature of the period from the end of the third/ninth to the middle of the sixth/twelfth century is the distinction made between different types of Ibaḍī imams. Some of them were recognised as leaders of offensives, in keeping with the Kharijī tradition (*imam 'ala al shira'*) which meant that they were expected to wage *jihād* on non Kharijites in order to spread the true faith. Others were not expected to engage in such activity, and pledged to lead only wars of defence (*imam 'ala al difa'*). It should also be noted that, although an imam's son would occasionally inherit his father's office, the Imamate was not hereditary in principle, and no dynasties were formed. The imams' authority was often contested by rivals from within, and challenged by outsiders too. Some regularly made themselves scarce whenever a representative of the real – that is, foreign – power happened to come to the country.¹²⁵

According to *al Kamil* (a general history of the Muslim world, written by Ibn al Athīr, d. 630/1233), by 442/1050 Oman was no longer ruled by the Mukramids, but by a Buwayhid governor, the son of Abu Kalījar, king of Faris. This governor was defeated by the Kharijites, led by 'Ibn Rashid'.¹²⁶ Ibn al Athīr here apparently refers to the imam Rashid b. Sa'īd, who was elected in Rustaq in 425/1033 (or later), remained in power until he died in 445/1053, and succeeded in driving the Buwayhids out of the coastal plain. The Imamate under him was a unified and powerful state that incorporated Ḥaḍramawt and expanded overseas as well, not only conducting trade but also propagating Ibaḍism.¹²⁷

123 Salimī, *Tuhfa*, pp. 295, 304; al Khalil ibn Shadhan and Rashid ibn Sa'īd were elected before 442/1050, while the Mukramids were still in power.

124 Muqaddasī, *Aḥsan al taqasīm*, p. 92; R. D. Bathurst, 'Maritime trade and imamate government: Two principal themes in the history of Oman to 1728', in D. Hopwood (ed.), *The Arabian Peninsula, society and politics* (London, 1972), pp. 92–3; on the traded commodities see 'Ānī, *Ta'rīkh*, pp. 147–68, on the extent of the trade pp. 178–208.

125 Izkiwī (attrib.), *Annals*, pp. 20–30; Izkiwī (attrib.), *Kapitel*, pp. 27–40; Anonymous, *Ta'rīkh*, pp. 75–91. Cf. the distinction made (for other reasons) between Zaydī imams who were both warriors and scholars, and those who were only warriors: Landau Tasserón, 'Zaydī imams'.

126 Ibn al Athīr, *Kamil*, vol. VIII, p. 295; Salimī, *Tuhfa*, pp. 293–4, 319 (quoting Ibn al Athīr).

127 Salimī, *Tuhfa*, pp. 304–14; Wilkinson, *The imamate*, p. 210; Wilkinson, 'Bibliographical background', p. 139. Ibn Kathīr, *Bidaya*, vol. XII, p. 61, refers in one sentence to the imam's success, among the events of the year 442/1050.

The Imamate collapsed under the pressures of both foreign powers and internal quarrels. In 455/1063 the coast came under the nominal rule of the Saljuqs. The Omanīs, however, remained largely independent in their activities overseas. More destructive than this occupation was the edict issued in 443/1052 by the Rustaq school which declared their opponents to be renegades, thus perpetuating the rift between the schools. As a result, many tribes abandoned the Ibaḍī creed, tribal and regional wars increased, and rival imams and local non Ibaḍī rulers constantly sought to establish their power.¹²⁸ The death of the imam Muḥammad b. Khanbash in 557/1161 marks the beginning of a period that is often considered an interregnum, but Ibaḍī imams continued to be elected, albeit intermittently, until the ninth/fifteenth century.¹²⁹ A non Ibaḍī local dynasty of the Azd tribe, the Nabhanīs, seized power at the end of the sixth/twelfth century.¹³⁰

Central and eastern Arabia: Najd, Yamama and medieval Baḥrayn

These three regions extended from the eastern border of the Ḥijaz, through the central plateau and as far as the Persian Gulf. Not only are they adjacent, but they also were often under the same regime or influence, and certain tribes, such as Banu ‘Āmir and Tamīm, were dispersed over all three. Yamama is in fact often considered to be geographically a part of Najd.¹³¹ It may be added that events in Islamic Baḥrayn are much better documented than those in Najd and Yamama.

Central and eastern Arabia from the first/seventh to the third/ninth century

Najd is the remotest and least known of these regions. At the beginning of the seventh century CE it was mainly populated by numerous nomadic and semi nomadic tribal groups. Most of these opposed the Prophet, but some joined him at various stages of his career, in particular after he had conquered Mecca in 8/630. Certain Najdī groups, including some that had been converted before Muḥammad’s death, participated in the so called ‘Wars of Apostasy’ of 11–12/632–3. After these events all the tribes

128 Salimī, *Tuhfa*, pp. 320–42; Wilkinson, *The imamate*, pp. 210–12; Wilkinson, ‘Bibliographical background’, pp. 139–40; Casey Vine (ed.), *Oman*, pp. 176–8.

129 Izkiwī (attrib.), *Kapitel*, pp. 15–18; Anonymous, *Ta’rīkh*, pp. 60–93; Shalabī, *Mawsu‘a*, pp. 234–6.

130 Casey Vine (ed.), *Oman*, pp. 178–81; Naboodah, ‘Banu Nabhan’; Zambauer, *Mu‘jam ansab*, p. 194.

131 A. Grohman, ‘Najd’, *El2*, vol. VII, p. 864; U. M. al Juhany, *Najd before the Salafī reform movement* (Reading and Riyadh, 2002), pp. 23ff.; Shalabī, *Mawsu‘a*, pp. 44–6, 80.

and their domains became part of the Muslim state. The sovereignty of the state in the area is perhaps best illustrated by the *ḥimas*, the large pasture areas that the state confiscated from Najdī tribes for its own use. The best known of these are Ḍariyya and al Rabadha. The system, established by ‘Umar b. al Khaṭṭab, only fell out of use in the middle of the second/eighth century, after the advent of the ‘Abbasids.¹³²

To the east of Najd lay Yamama, a densely populated, cultivated area. Its main towns were Ḥajr and al Jaww, also called al Khiḍrīma. The importance of pre Islamic Yamama lay in the fact that it supplied wheat to the Ḥijaz, and that trade routes from Iraq, the Yemen and Mecca ran through it. In the Prophet’s day the dominant tribe, Ḥanīfa, was ruled by Hawdha b. ‘Alī, a Christian loyal to Persia. After Hawdha’s death in 8/630, his successor, Musaylima, offered staunch opposition to Islam, both during the Prophet’s lifetime and after it. Yamama was conquered by the caliph’s armies in 11/632, though only with great difficulty.

The eastern part, extending as far as the western shores of the Persian Gulf, was known in medieval Islam as al Ḥasa, al Aḥsa’, Hajar and Baḥrayn (to be distinguished from the island of Baḥrayn). The precise meaning of these terms and the boundaries of the regions to which they refer cannot be determined. The names al Ḥasa and Hajar refer both to the entire region and to specific towns. Al Ḥasa sometimes designates the oases part of the region, but the southern part of these, which lies on the shores of the Persian Gulf, is known as al Qaṭīf.¹³³ For the sake of convenience I shall refer to the region by a single term, Baḥrayn.

At the time of the Prophet the inhabitants of Baḥrayn comprised mainly groups of the Arab confederations of ‘Abd al Qays, Bakr and Tamīm, most of whom lived off agriculture, fishing, textile production, pearl diving and trade. Many were Christians or Zoroastrians, and some were Jews. The region was under Persian rule, the Persians being represented by a local Tamīmī, al Mundhir b. Sawa. His clan was apparently under heavy Persian influence, and its members were known by the mysterious appellation *asbadhiyyun*, usually rendered as ‘horse worshippers’. Persian troops were stationed in al Qaṭīf, but they did not offer any resistance to Muḥammad. Reportedly the local ruler was converted to Islam after negotiations with the Prophet, and the

¹³² Al Rashid, *al Rabadha*, pp. 2–4, see also the references in note 139 below.

¹³³ Ḥamad al Jasir, *al Mu‘jam al jughrafī li l bilad al ‘Arabiyya al Su‘ūdiyya*, 3 vols. (Riyadh, 1399–1401/1979–81), vol. I, p. 31; F. S. Vidal, *The oasis of al Ḥasa* (Dhahran, 1955), pp. 4–9; F. S. Vidal, ‘al Ḥasa’, *ELZ*, vol. III, p. 237; G. Rentz, ‘Qaṭīf’, *ELZ*, vol. IV, p. 763.

inhabitants either followed suit or became subject to the poll tax. Al Mundhir retained his post until he died, shortly after the Prophet. Names of the Prophet's appointees to Baḥrayn are mentioned as well.¹³⁴

After the Prophet's death the 'Wars of Apostasy' encompassed almost every settlement in Baḥrayn. Troops sent by Abu Bakr, reinforced by loyal groups from Yamama, succeeded in suppressing them. Some Persian resistance persisted until about 19/640, but most Arab tribesmen converted and left for the conquests and the conquered areas.

The Rashidun appointed Companions of high standing as governors of Baḥrayn. The first of them, already appointed by the Prophet, was the Meccan al 'Ala' b. al Ḥaḍramī, who served until 16/637. Administrative divisions, however, were not rigid. Baḥrayn and Yamama sometimes constituted one division, and at other times Oman and Baḥrayn, or the Yemen and Baḥrayn, were joined under a single governor, who would reside in one place and appoint representatives to the others. Thus, although adjacent, the three regions were attached to different centres in this period. When Mu'awiya came to power in 40/661, Yamama was attached to Medina whereas Baḥrayn and Oman were administratively part of the Ḥijaz. Mu'awiya at first appointed to Baḥrayn one of his own relatives, but later he added it, as well as Oman, to the jurisdiction of his powerful governor in Iraq, Ziyad b. Abīhi. His reason for doing this was, perhaps, that it was easier to control eastern Arabia from Iraq than from western Arabia. Administration in Iraq was more developed, and military power stationed there was much superior to that present in Arabia. Henceforth the governors of Iraq often shouldered the responsibility of appointing representatives to Baḥrayn, or to Baḥrayn and Yamama, or to Baḥrayn and Oman.¹³⁵

The importance of Baḥrayn lay especially in its location: in the Rashidun period it was a convenient base for raids into Persia. Later it received attention as lying on the road from Iraq to the holy places in the Ḥijaz. It also played a part in the maritime trade with the Far East, although Oman's role in this trade

¹³⁴ References for all three regions: Ya'qubī, *Ta'rikh*, vol. II, pp. 76, 82; al Ṭabarī, *Ta'rikh*, vol. III, pp. 137, 147, 301; Yaqut, *Mu'jam al buldan*, vol. I, p. 172; Dhahabī, *Siyar*, vol. I, pp. 261, 263; Muḥammad ibn Mukram ibn Manẓūr, *Lisan al 'Arab*, 15 vols. (Beirut, n.d.), vol. III, p. 493; Jasir, *Mu'jam*, vol. I, pp. 48–52, 56–7; Shalabī, *Mawsu'a*, pp. 412–15; M. F. von Oppenheim, *Die Beduinen*, vol. III, ed. W. Caskel (Wiesbaden, 1952), pp. 7–10 and *passim*; Juhany, *Najd*, pp. 39–42.

¹³⁵ Ibn Hajar, *Iṣāba*, vol. I, p. 34 (s.v. al Aḥwaṣ ibn 'Abd), see also vol. II, p. 457; Baladhurī, *Ansab*, p. 126; al Ṭabarī, *Ta'rikh*, vol. V, p. 217; Ibn al Athīr, *Kamil*, vol. IV, p. 367; 'Alī, *Ḥijaz*, p. 293; Ḥamad al Jasir, 'Wulat al Ahsa' fī al 'ahd al Umawiyy', *al 'Arab*, 1 (1966–7). See also p. 401 above for contradictory information on administration.

increasingly superseded that of Baḥrayn. Yamama and Baḥrayn also supplied the Hijaz with grain, and were a source of revenue for the caliphate.¹³⁶ During Mu'awiya's reign Baḥrayn yielded 15 million *dirhams*, and benefited from investments in agriculture and infrastructure, as did Yamama and other parts of the Arabian Peninsula. Some such investments in Najd were made already by the Rashidun, mostly connected with the *ḥimas*.¹³⁷

Not much is known about central and eastern Arabia during the Umayyad period, except that it became the theatre of tribal hostilities, often under the Kharijite banner. According to one report, a local Tamīmī chief, 'Umayr b. Sulmiyy, took control of Yamama during the first civil war.¹³⁸ The Kharijite Najda b. 'Āmir rose in Yamama during the second civil war and, supported by the local tribes of Bakr, took control of Baḥrayn (as well as Ḥaḍramawt and Ṭa'if) from 67/686. Muṣ'ab b. al Zubayr, governor of Iraq for his brother 'Abd Allah (r. from Mecca 64 73/683 92), continually attacked Baḥrayn, but to no avail. Najda was killed in 72/691 by another Kharijite leader, Abu Fudayk. The latter's revolt was suppressed the next year by Umayyad troops from Iraq, with great difficulty and at the cost of 6,000 lives on the rebels' side. Further Kharijite revolts occurred in 79/698, 86/705 and 105/723. The leader of the revolt of 105/723, Mas'ud al 'Abdī, is said to have ruled Baḥrayn and Yamama for nineteen years, until the Umayyad representative to Yamama killed him and vanquished his followers. Throughout the Marwanid period Baḥrayn and Yamama remained under the jurisdiction of the governor of Iraq, who would appoint sub governors and send troops to combat rebels.¹³⁹

136 The Rashidun period in all three regions (including the *ridda*): Ya'qubī, *Ta'rikh*, vol. II, pp. 131, 134, 138, 153, 161, 201; Baladhurī, *Futuh*, pp. 90 5, 378, 420; al Ṭabarī, *Ta'rikh*, vol. III, pp. 301 13, 427, 479, vol. IV, pp. 39, 79, vol. V, p. 155; Yaqut, *Mu'jam al buldan*, vol. I, p. 430, vol. III, p. 113, vol. IV, pp. 227, 455; Jasir, *Mu'jam*, vol. I, pp. 69 75; Hamad al Jasir, *Madinat al Riyad 'abra atwar al ta'rikh* (Riyadh, 1386/1966), pp. 52 60; Shalabī, *Mawsu'a*, pp. 416 19; Oppenheim, *Beduinen*, vol. III, pp. 10 13; E. Shoufani, *al Riddah and the Muslim conquest of Arabia* (Toronto and Beirut, 1975), pp. 112 34; M. J. Kister, 'The struggle against Musaylima', *JSAL*, 27 (2002). The raids from Baḥrayn into Persia may have been initiated by the governor rather than the caliph: see Ibn Kathīr, *Bidaya*, vol. VII, p. 84. On maritime trade: Hourani, *Arab seafaring*, pp. 64 76; 'Ānī, *Ta'rikh*, pp. 175 9.

137 Ya'qubī, *Ta'rikh*, vol. II, p. 233; Jasir, *Mu'jam*, vol. I, pp. 75 6; Oppenheim, *Beduinen*, vol. III, p. 12; Juhany, *Najd*, p. 42.

138 Hamdanī, *Ṣifat*, p. 254, but see below note 140.

139 Ya'qubī, *Ta'rikh*, vol. II, pp. 272 3; Khalifa, *Ta'rikh*, vol. I, pp. 267, 278, 279, 313, 359, 336; al Ṭabarī, *Ta'rikh*, vol. V, p. 619, vol. VI, pp. 174, 913; Ibn al Athīr, *Kamil*, vol. IV, pp. 366, 491; Yusuf ibn al Taghribirdī, *al Nujum al zahira fī muluk Miṣr wa l Qahira*, 12 vols. (Cairo, n.d.), vol. I, p. 199; Jasir, *Mu'jam*, vol. I, pp. 76 7; Jasir, 'Wulat al Aḥsa'; Shalabī, *Mawsu'a*, pp. 420 4; Oppenheim, *Beduinen*, vol. III, p. 13.

Rebellions were not motivated only by religion. In 126/744 a rebel of the Banu Ḥanīfa in Yamama simply wanted his country back and expelled the Umayyad governor. Yamama was left to tribal feuds for a time, until another governor was sent from Iraq. As a result of these and other tribal feuds in the Umayyad period, the Banu Ḥanīfa completely lost their pre-Islamic eminence, a process already begun upon their defeat in the Wars of Apostasy. Najd was largely left to its own feuds, and was hardly involved in the major political struggles of the Islamic world.¹⁴⁰

With the shift of the capital to Iraq in 132/750, the pilgrim road to the Ḥijaz through eastern Arabia grew in importance and attracted large investments by the caliphs and members of their family. The pilgrim road from Kufa is named *Darb Zubayda* after al Rashīd's wife, who expended great effort and wealth on it. The eastern region of the Peninsula, which had been depleted by the migration of the tribes for the conquests, was now filled again with tribes coming from the south and the west. Villages along the route prospered, and some tribal groups became sedentarised through a long process that appears to have lasted into the third/ninth century.¹⁴¹ In contrast to Umayyad practice, the first 'Abbasid caliphs appointed the governors of the region themselves, often choosing their own family members. Baḥrayn still yielded considerable revenues, and occasionally it was administratively attached to provinces in southern Iraq and/or southern Persia, rather than to Yamama. However, a governor's jurisdiction would occasionally comprise Yamama, Mecca, Medina and Ṭa'īf (in the years 163 4/779 80), Yamama, Baḥrayn and the route to Mecca (in 236/850), or Yamama, Baḥrayn and Baṣra (in 252/866). The appointment of governors remained in the hands of the caliphs; but the fact that al Mutawakkil (r. 232 47/847 61) appointed to Baḥrayn (and Yamama) a poet who had praised him, perhaps indicates that he despaired of holding on to a region that had grown too difficult to control.¹⁴²

As early as 151/768 or 152/769 the people of Yamama and Baḥrayn killed al Maṣṣur's governor, and insurrections during al Maḥdī's reign (r. 158 69/775 85) are mentioned as well. These revolts were harshly suppressed, and the government apparently continued to have fairly firm

¹⁴⁰ Ibn al Athīr, *Kamil*, vol. IV, pp. 491 3; Jasir, *Madīnat*, pp. 65 7; Juhany, *Najd*, pp. 40, 42 3; Shalabī, *Mawsu'a*, p. 95. The name of the rebel in 126/743 is al Muhayr ibn Sulmiyy, so perhaps the unique report of Hamdanī (above note 138) is a distortion of this one.

¹⁴¹ Oppenheim, *Beduinen*, vol. III, pp. 13 14; Juhany, *Najd*, p. 42; Sa'd al Rashid, *Darb Zubayda: The pilgrim road from Kufa to Mecca* (Riyadh, 1980).

¹⁴² Al Ṭabarī, *Ta'rikh*, vol. VII, pp. 459, 465, vol. VIII, pp. 134, 149, 151, vol. IX, pp. 140, 183; Ibn al Athīr, *Kamil*, vol. IV, p. 493, vol. V, p. 199, vol. VI, pp. 140, 183; Sinjarī, *Manā'ih*, vol. II, pp. 86 7, 90 1; Juhany, *Najd*, p. 44; Shalabī, *Mawsu'a*, pp. 62 3; Jasir, *Mu'jam*, vol. I, pp. 79 81.

control until the third/ninth century. By this period Bedouin groups of the Banu ʿĀmir had replaced the once powerful Tamīm and Bakr in central and eastern Arabia. These newly arrived groups were continually disturbing the peace in these regions, and the caliph al Wathīq (r. 227 32/842 7) sent against them armies from Baghdad, headed by his Turkish general Bugha al Kabīr. He was soundly defeated in Najd in 230/845 and 232/847, but eventually had success against these tribes and others, in Najd as well as in the Ḥijaz.¹⁴³

Following these events the ʿAbbasids allowed Yamama and Baḥrayn to fragment and be ruled by several local tribal chiefs. An ʿAbbasid governor is still mentioned in Baḥrayn in 280/893 as involved in bringing down the imamate of Oman.¹⁴⁴ But, it was chiefs of the ancient local tribes who succeeded, albeit with great difficulty, in expelling the ʿAlid pretender who mustered support in the region in 249/863. This pretender, ʿAlī b. Muḥammad, started his mission in Baḥrayn, reportedly because 'its people were stupid and easily deceived'. After his defeat at the hand of the local chiefs he left for Baṣra to become the leader of the Zanj revolt that wreaked havoc in Iraq between 255 70/868 83.¹⁴⁵ In Yamama the local chiefs were marginalised by the Ukhayḍirs, an ʿAlid family that came from the Ḥijaz and ruled Yamama from the middle of the third/ninth century. The large emigration from Yamama that is reported in the third/ninth century is imputed by certain sources to the evil regime of this family.¹⁴⁶

The revolt of ʿAlī b. Muḥammad, 'Lord of the Zanj', was but a precursor to the other serious threat to the caliphate in Baghdad, namely, the extreme Shīʿī movement called the Qarmaṭī.

The Qarmaṭīs

The foundation of the Qarmaṭī state is shrouded in mystery. Some sources describe the founder, Abu Saʿīd al Jannabī, as a poor Baṣran corn measurer who staged a revolt at the head of the remnants of the Zanj. Others connect him with clandestine activity of extremist Shīʿīs begun in Baḥrayn a few years

¹⁴³ Yaʿqubī, *Taʾrīkh*, vol. II, pp. 385, 396; al Ṭabarī, *Taʾrīkh*, vol. VIII, p. 39, vol. IX, pp. 129 35, 146 50; Juhany, *Najd*, pp. 44 5; Oppenheim, *Beduinen*, vol. III, p. 14.

¹⁴⁴ See above.

¹⁴⁵ Dhahabī, *Siyar*, vol. XIII, pp. 132 6; Ibn al Athīr, *Kamil*, vol. VI, pp. 206 7; Shalabī, *Mawsuʿa*, pp. 431 2; Oppenheim, *Beduinen*, vol. III, p. 15. For the 'kings' of al Yamama see also Hamdanī, *Ṣifāt*, p. 276.

¹⁴⁶ Jasir, *Madīnat*, pp. 71 2. On the Ukhayḍirs see *ibid.*, pp. 69 78; Ibn Ḥazm, *Jamhara*, pp. 47 8; Sakhawī, *Tuhfā*, vol. I, p. 309; Juhany, *Najd*, pp. 45 7; Zambauer, *Muʿjam al ansab*, p. 177, records their end at the hand of the Qarmaṭīs, but see below and above (p. 409).

before his appearance.¹⁴⁷ He was probably a missionary sent by the extremist Shī'ite agent Ḥamdan Qarmaṭ. When the latter seceded from the Isma'īlī Faṭimids who came to power in North Africa in 296/909, Abu Sa'īd may have remained loyal to them, but the information about his conduct is contradictory. Be that as it may, Abu Sa'īd gained support among certain Bedouin tribes in Baḥrayn, mainly the 'Uqyal and other sections of the Banu 'Āmir, who had migrated there during the third/ninth century. Abu Sa'īd first conquered al Qaṭīf, then the other oases and towns of Baḥrayn, as well as Ṭa'if and a few oases in Najd. Troops sent by the caliph al Mu'taḍid could not rout him, and he continued his military activity after he had consolidated his reign. He raided Oman to extract tribute and booty, and extended Qarmaṭī influence (but not direct rule) to Yamama, which was ruled by the Ukhayḍirs. His rule, begun in 286/899, ended with his assassination in 301/913.¹⁴⁸

The great exploits of the Baḥrayn Qarmaṭīs were initiated by Abu Sa'īd's son, Abu Ṭahir, who took the reins of power in 305/918 or 310/923 and ruled until he died in 332/943. He subordinated the Ukhayḍirs of Yamama, then carried onto the heart of the caliphate, after years of peaceful relations with the 'Abbasids. He captured Baṣra in 311/923, raided Iraq and the pilgrim caravans repeatedly, conquered Kufa in 313/925 and almost reached Baghdad by 317/929, after having defeated a large 'Abbasid army. In these campaigns he was leading the nomads of the Arabian Peninsula into the Fertile Crescent to plunder in the traditional Bedouin way, but he also received support from Qarmaṭīs in southern Iraq, apparently on an ideological basis. The strength of his army is estimated at between 1,500 and 2,700 troops, but the 'Abbasid government failed in vanquishing it, and attempted to secure peace by other means. In 327/939 it was proposed that Abu Ṭahir act as the pilgrimage protector in exchange for tribute and a fee to be paid by the pilgrims. He accepted the offer, but did not refrain from raiding Iraq in subsequent years. After the mid fourth/tenth century, the Buwayhids avoided Qarmaṭī hostility by granting them extensive privileges in addition to those arising from their

147 'Abd al Ḥayy ibn al Aḥmad ibn al 'Imad, *Shadharat al dhahab fī akhbar man dhahab*, 4 vols. (Beirut, n.d.), vol. I, p. 192; Ibn al Athīr, *Kamil*, vol. VI, pp. 396 7; Muhammad al Khalīfa Mayy, *Min Sawād al Kufa ila al Baḥrayn* (Beirut, 1999), pp. 239 43; Suhayl Zakkar, *al Jami' fī akhbar al Qaramiṭa fī al Aḥsa'*, *al Sham, al Iraq, al Yaman* (Damascus, 1407/1987), p. 147.

148 Al Ṭabarī, *Ta'rīkh*, vol. X, pp. 71, 75, 104; Ibn al Athīr, *Kamil*, vol. VI, pp. 419, 482; Ibn Kathīr, *Bidaya*, vol. XI, p. 83; Yaqut, *Mu'jam al buldan*, vol. IV, p. 359; Maqrīzī, *Itti'āz*, pp. 214 21; Mayy, *Min Sawād al Kufa*, pp. 244 8, 265 8; Zakkar, *al Jami'*, pp. 460 8, 541 7; Oppenheim, *Beduinen*, vol. III, pp. 14, 15 17; W. Madelung, 'The Faṭimids and the Qarmaṭīs of Baḥrayn', in F. Daftary (ed.), *Medieval Isma'īlī history and thought* (Cambridge, 1996), pp. 22 9 (the last two references include discussions of the origins of the Qarmaṭī movement as a whole).

protection of the caravans. Among other things, the Qarmaṭīs received land holdings in southern Iraq and kept a permanent representative in Baghdad.¹⁴⁹

Abu Ṭahir's murderous and sacrilegious activities reached their peak in 317/929, when he conquered Mecca, massacred its population and removed the black stone from the Ka'ba. It was kept in the Qarmaṭī capital for twenty two years, and was only returned when the 'Abbasid caliph paid a large ransom. The raids on the pilgrims and the robbery of the black stone reflected Abu Ṭahir's belief that the end of the Islamic era was nearing with the imminent advent of the *mahdī*. In 319/931 this belief led him to transfer all powers to a Persian pseudo prophet, and even to deify him. This impostor reportedly committed murders and other atrocities, and tried to rid himself of the ruling family. Encouraged by his minister, Ibn Sanbar, Abu Ṭahir removed him and his influence from Baḥrayn, and re-established state control. In view of Abu Ṭahir's career it is not surprising that Muslim historians were not satisfied with reporting the shocking events, but imputed additional atrocities to him, such as making permissible homosexuality and intercourse between brothers and sisters. It is also reported that the Faṭimid caliph tried to induce him to burn mosques and Qur'an copies. Less hostile reports have it that the Qarmaṭī government failed to build mosques or hold Friday prayers.¹⁵⁰ In actuality, the order and justice that prevailed within the Qarmaṭī state have evoked the admiration, if not the envy, of non Qarmaṭīs. The state was run by descendants of the founder, Abu Sa'īd, either collectively or as a council acting at the ruler's side. The council included other dignitaries, chief among whom were the Sanbars, a local family, perhaps of humble origin, who had supported the Qarmaṭī state from its inception. The revenues were distributed with a view to the welfare of the inhabitants at large. The state took care of production, education, security and trade in a way that has led certain modern scholars to describe it as 'communist', and even to impute to it a liberal attitude towards women. It may also be noted that crises of succession, rebellions and civil wars were much less frequent than in other dynasties.¹⁵¹ This is proved not only by the sparsity of

149 Maqrīzī, *Itti'az*, pp. 239–46; Mayy, *Min Sawad al Kufa*, pp. 269–92; Zakkar, *al Jami'*, pp. 154, 403, 489–501, 517; W. Madelung, 'Qarmaṭī', *EL*, vol. IV, p. 660; Juhany, *Najd*, pp. 47–9.

150 Fasī, *Shifa'*, pp. 346–7; Ibn al 'Imad, *Shadharat al dhahab*, vol. I, p. 305; Yaqut, *Mu'jam al buldan*, vol. II, p. 224; Dhahabī, *Siyar*, vol. XV, pp. 320–5; Ibn al Taghribirdī, *Nujum*, vol. III, p. 287; Ahdal, *Tuhfa*, p. 165; Mayy, *Min Sawad al Kufa*, pp. 293–307; Zakkar, *al Jami'*, pp. 149, 152–3, 503–7, 595; Oppenheim, *Beduinen*, vol. III, p. 17; Madelung, 'The Faṭimids', pp. 21–2, 30–3, 37, 46–9.

151 Cases of internal division: Madelung, 'The Faṭimids', pp. 38–40; Zakkar, *al Jami'*, pp. 155–6, 225–6, cf. Shalabī, *Mawsu'a*, pp. 462, 465. Descriptions of the state: Nāser e Khosraw, *Travels*, pp. 86–90; Mayy, *Min Sawad al Kufa*, pp. 226–8, 245–58; Zakkar, *al Jami'*, pp. 148–51; Oppenheim, *Beduinen*, vol. III, p. 18; Madelung, 'Qarmaṭī'. List of rulers: Zambauer, *Mu'jam al ansab*, p. 180.

accounts about such crises, but also by the fact that the ruler and his army stayed away for long periods of time, presumably without fear of rebellion.

The Qarmaṭīs of Baḥrayn attacked not only Iraq but also Syria aided, and perhaps prompted to action, by local Bedouin. Al Ḥasan al Aʿṣam, a nephew of Abu Ṭahir who was leading the Qarmaṭī armies between 357/66/968–77, took Damascus from the Ikhshīdīs in 357/968 and extracted annual tribute of 300,000 *dīnars*. This payment was later stopped by the Faṭimids when they conquered parts of Syria in 359/970. Al Ḥasan al Aʿṣam then fought the Faṭimids in Syria, sometimes cooperating with the Ikhshīdīs, his former enemies. He also invaded Egypt, supported by the ʿAbbasid caliph, to whom he paid allegiance despite his own sectarian persuasion. The Faṭimids, however, wrested Syria from the Qarmaṭīs, and bought their peace in Egypt in 363/974. Hostilities between the Faṭimids and the Qarmaṭīs on Syrian soil were resumed on the death of the Faṭimid caliph al Muʿizz in 365/976. Al Ḥasan al Aʿṣam formed an alliance with the Turkish warlord Alftakīn, who had taken Damascus a few years earlier. After a few initial victories this coalition was defeated. Al Ḥasan died in 366/977, and his successor continued the struggle against the Faṭimids until a new peace treaty was signed in 368/978. This treaty secured Qarmaṭī allegiance to the Faṭimids in exchange for annual tribute.¹⁵²

Little is known of the Qarmaṭīs of Baḥrayn from the end of the fourth/tenth century. They may have vacillated between the ʿAbbasids and the Faṭimids, and attempted military adventures at the same time.¹⁵³ These adventures eventually cost them their influence in Iraq and their privilege of escorting the pilgrim caravans. In 373/983 they attacked Baṣra, and in 375/985 they occupied Kufa. The Buwayhid government in Iraq felt prompted to act, and defeated them. The Qarmaṭīs now began to lose the support of the Bedouins who had followed them to campaigns and to the gain of booty. Moreover, Baḥrayn itself fell prey to Bedouin attacks, and the Qarmaṭīs suffered defeats at their hands as well (as in 378/988, the raid of the ʿUqaylīs led by al Aṣfar). Much weakened, they remained to rule Baḥrayn until they began losing their domains to local rebels, from the first half of the fifth/eleventh century. In the 430s/1040s Abu al Bahlul, a chief of the local ʿAbd al Qays tribe, took the island of Uwal and destroyed the port of al ʿUqayr (on the mainland). The Qarmaṭīs suffered another major defeat at his hand in a naval battle off al Qaṭf, in 450/1058. By this time they had lost their influence in

152 Maqrīzī, *Ittiʿāz*, pp. 177–9, 181–2, 247–65; Mayy, *Min Sawad al Kufa*, pp. 307–20; Zakkar, *al Jamiʿ*, pp. 226–44, 401–2, 508–17, 528–32, 565–83, 595–8, 606; Shalabī, *Mawṣuʿa*, pp. 455–60; Madelung, 'Qarmaṭī'. Note the contradictory reports about al Aʿṣam's correspondence and relations with the Faṭimids.

153 Ibn Kathīr, *Bidayā*, vol. XI, p. 311; Madelung, 'Qarmaṭī'.

Yamama, and the Ukhayḍirs were completely independent of them. The traveller Naṣīr i Khusraw presumably refers to the Ukhayḍirs when he states (in the 440s/1050s) that Yamama was ruled by a strong dynasty that relied on three or four hundred mounted soldiers. Notwithstanding these events and processes, the same traveller describes Baḥrayn as a prosperous state run with equity and efficiency, based on the labour of 30,000 slaves and on military power of 20,000 soldiers.

The Qarmaṭī state came to an end in 470/1077, brought down by a tribal chief from the ‘Abd al Qays of Baḥrayn, ‘Abd Allah b. ‘Alī al ‘Uyunī. The new regime was formally subject to the Isma‘īlī Ṣulayḥīs of the Yemen, and stayed in power until the seventh/thirteenth century.¹⁵⁴

The policy and exploits of the Qarmaṭīs during the fourth fifth/tenth eleventh centuries boosted the wave of nomad migrations from the Peninsula into the Fertile Crescent and Egypt, apparently set in motion by droughts. No less importantly, they caused huge damage to settlements along the pilgrim routes and to agriculture in large areas of the Peninsula. Among other places, the town of al Rabadha was destroyed and deserted. Yamama under the Ukhayḍirs was still relatively prosperous in the fourth fifth/tenth eleventh centuries, but in general central and eastern Arabia did not recover with the waning of the Qarmaṭīs of Baḥrayn.¹⁵⁵ Events in Yamama and Najd between the fifth/eleventh and the eighth/fourteenth centuries are very poorly known. The regions appear to have been fragmented and constantly engaged in tribal feuds, mostly unattractive to external powers, save some times to the rulers of Baḥrayn.¹⁵⁶ It is also worthy of note that in general, eastern Arabia contributed very little, if anything, to Islamic scholarship.¹⁵⁷

The Arabian Peninsula of the first fifth/seventh eleventh centuries was a place of many variations. Its society both nomad and settled and its culture, were mostly tribal, yet the different regions followed various ideologies and various forms of political order. Sunnīs, Kharijites and Shī‘ites of many kinds, centralised regimes, petty dynasties and tribal polities, local and foreign powers, all contributed to the complex history of Arabia in this period.

154 Ibn al ‘Imad, *Shadharat al dhahab*, vol. II, p. 55; Maqrīzī, *Itti‘az*, p. 68; Ibn al Taghribirdī, *Nujum*, vol. IV, p. 74; Naṣīr e Khosraw, *Travels*, pp. 86–90; Mayy, *Min Sawad al Kufa*, pp. 321–3; Shalabī, *Mawsu‘a*, pp. 462–3, 468–9; Zakkar, *al Jami‘*, pp. 517, 583; Madelung, ‘Qarmaṭī’; Madelung, ‘The Fatimids’, pp. 34–5, the question of the Qarmaṭīs’ allegiance or otherwise to the Fatimids is discussed in detail throughout this article; Oppenheim, *Beduinen*, vol. III, pp. 17–19; M. Canard, ‘al Ḥasan al A‘ṣam’, *EL*, vol. III, p. 246.

155 Juhany, *Najd*, pp. 42, 47–9. On the damages to the pilgrim road see al Rashid, *Darb Zubayda*, pp. 47–52; al Rashid, *al Rabadha*, p. 11.

156 Shalabī, *Mawsu‘a*, pp. 48–59, 63, 81–3, 91; Jasir, *Madīnat*, p. 79.

157 See Hamad al Jasir, ‘al Ḥafṣī wa kitābuhu ‘an al Yamama’, *al ‘Arab*, 1 (1967); A. b. ‘A. Āl Mubarak, ‘‘Ulama’ al Aḥsa’ wa makanatuhum al ‘ilmiyya wa l adabiyya’, *al ‘Arab*, 17, 1 (1982–3), pp. 361–83; Cook, ‘The historians’.

The Islamic east

ELTON L. DANIEL

The concepts of both the 'Islamic east' and 'regionalism' are nebulous enough to require some definition for the purposes of this discussion. In the case of the 'Islamic east' there are two terms sometimes found in Muslim geographical and historical works that could be understood as referring to such an area: *al sharq* and *al mashriq*.¹ *Al sharq*, the east in general, should probably be understood, at least in the conceptual framework of most medieval Muslim geographers, as referring to everything to the east of Egypt. *Al mashriq*, the eastern lands, refers to a smaller and more distinct component of this territory; as a term, it was certainly in usage by 203/818f., as it appears on a coin of that date.² It was precisely defined by the geographer al Muqaddasī (d. c. 380/990) as encompassing Khurasan, Sīstan (Sijistan) and Transoxania (Ma Wara' al Nahr), an area which he saw as a unity but which his predecessor, Abu Zayd al Balkhī (d. 322/934) had regarded as a group of regions (*aqalīm*).³ Neither of these concepts is well suited for the present purpose: *al sharq* is much too broad, as it would include areas such as Syria, while *al mashriq* is perhaps too narrow, as it would exclude Ṭabaristan and other areas.

In a more practical sense for modern usage, 'Iran and the Islamic east' can be understood as referring to those parts of the Islamic oecumene that had formerly been part of the Sasanian empire and where Islam came to be the dominant religion, but where Arabic did not establish itself as the vernacular language of the majority of the population. Such a definition has the advantage of eliminating the need to discuss areas west of the Euphrates or even most of Iraq, which became Arabic speaking, as well as those such as Armenia, which remained Christian. Given the shadowy eastern boundaries of the Sasanian

1 See A. Miquel, 'Mashrik', *EL*2, vol. VI, p. 720.

2 G. C. Miles, 'Numismatics', in R. N. Frye (ed.), *The Cambridge history of Iran*, vol. IV: *The period from the Arab invasion to the Saljuqs* (Cambridge, 1975), p. 370.

3 Shams al Dīn Muḥammad ibn Aḥmad al Muqaddasī, *Aḥsan al taqasīm fī ma'rifat al aqalīm*, ed. M. J. de Goeje (Leiden, 1906), p. 260.

empire, it also reduces the need to consider all the remote principalities of Central Asia as well as the Indus and India, the subject of separate chapters elsewhere in this series.⁴ It is still not entirely satisfactory, however, as it leaves for consideration a large number of territories such as Arran, al Jibal or Quhistan, about which we are poorly and unevenly informed in the available sources and which would be difficult to treat in any comprehensive fashion. Moreover, defined in this way, the 'Islamic east' was a region only in the generic dictionary sense of 'a large and indefinite part of the surface of the earth'.⁵ If one assumes 'regionalism' to be based upon some criteria of geographical, political, administrative, economic, social and/or cultural unity, then the Islamic east was not 'a region' so much as a group of regions or, better still, a network of cities and their hinterlands with great variations in terms of relations both with each other and with the greater commonwealth of the caliphate.

Finally, 'regionalism' in the strict sense should be understood as a concept implying a high degree of political, economic and cultural autonomy. One can detect a great many examples of provincialism or localism or nativism in the Islamic east as defined above, but there are far fewer areas that can be said to have a truly regional culture and history in this way. Of these, the region par excellence of the Islamic east was *al mashriq* as understood by al Muqaddasī, i.e. Khurasan and adjacent territories. Tremendously important both as a critical frontier province and an avenue for trade, it developed into a centre of political and cultural development that rivalled the centre of the caliphate itself. Of necessity, it will be the primary focus of this chapter.

The conquest of the Islamic east

The history of the conquest of the Islamic east, like that of other phases of the Muslim wars of expansion, is difficult to reconstruct and to interpret.⁶ The extant sources provide often lengthy accounts, but they are also full of contradictions and inconsistencies when it comes to matters of chronology, the personalities involved and the course of events. They show a marked

4 See Edmund Bosworth, 'The steppe peoples in the Islamic world' and André Wink, 'The early expansion of Islam in India', in David Morgan and Anthony Reid (eds.), *The new Cambridge history of Islam*, vol. III: *The eastern Islamic world, eleventh to eighteenth centuries* (Cambridge, forthcoming).

5 Webster's new world dictionary of the American language (Cleveland and New York, 1974), p. 1196.

6 For a good overview of this problem, see Chase Robinson, 'The rise of Islam, 600–705', chapter 5 in this volume.

preference for repetitious *topoi* and moralising tales rather than any meticulous concern for historical detail or actual military tactics and strategy. Any modern description of the phenomenon must therefore be tentative and to some extent conjectural.

The opening phase of the conquest of the east apparently had its origins in the need to provide the newly established garrison city of Baṣra with a supporting agrarian hinterland, comparable to that available to its counterpart at Kufa, by expanding into the plains of Khuzistan.⁷ Skirmishing between Baṣran forces and those of the local Persian ruler of those areas, Hurmuzan (Hormizdan), began in AH 16 or 17 (637–38). Hurmuzan proved to be a wily and tenacious opponent, but was eventually forced to surrender. The districts around Ahwaz, Sus, Tustar and Ramhurmuz all came under Arab rule, either by force or capitulation.⁸

Having completed the detachment of the western provinces from the Sasanians and established a line of control all along the foothills of the Zagros, the caliph ‘Umar seems to have been reluctant to push further. He is said to have urged the Baṣrans to be content with the cultivated lands around Ahwaz and to have wished that ‘a mountain of fire’ would separate the Baṣrans and Kufans from the people of Fars and al Jibal, ‘through which they cannot get at us, nor we at them’.⁹ Whether this caution was due to the need to consolidate what had already been conquered, a shift in focus to the western campaigns, a fear of overextending his forces, or the realisation that further expansion would dilute the Arab character of the newly created empire is open to debate. In any case, ‘Umar’s hesitation was trumped by other factors. One was the eagerness of individual warriors to carry out raids on their own initiative, sometimes dragging the caliph into fights he might have wished to avoid. Thus al ‘Ala’ ibn al Ḥaḍramī reportedly disregarded the caliph’s instructions discouraging both further expansion and undertaking raids that required the use of ships in order to initiate a piratical attack of his own from Baḥrayn on Fars. He raided as far inland as the provincial capital at Iṣṭakhr, but his expedition turned into a near disaster when his troops were cut off from their ships. ‘Umar, though furious at this act of disobedience, felt

7 Abu Ja‘far Muḥammad ibn Jarīr al Ṭabarī, *Ta’rīkh al rusul wa’l muluk*, ed. M. J. de Goeje et al., 15 vols. in 3 series (Leiden, 1879–1901), series I, p. 2539.

8 See Chase Robinson, ‘The conquest of Khuzistan: A historiographical reassessment’, *BSOAS*, 67 (2004) for a detailed review of the problems regarding the conquest of these areas.

9 Al Ṭabarī, *Ta’rīkh*, series I, p. 2545. This may well be a kind of *topos* – ‘Umar, for example, makes a similar remark later about Khurasan – but probably reflects a genuine ambivalence about further expansion.

obliged to send a relief force to extricate al ‘Ala’, thereby becoming involved in the fighting in Fars.¹⁰

Another important consideration for ‘Umar was the possibility that the Sasanians might attempt to drive the Arabs back from the conquered territories. It is debatable whether the defeated Sasanian king, Yazdegerd III, was really engaged in trying to organise such a counter offensive, but it does seem that a number of Persian magnates in the Zagros principalities feared that the Arabs would not be content with what they had already conquered and would seek to expand further – in which case their territories, like those of Hurmuzan, might be lost. A number of these Persian commanders – their names are given differently in various sources – began to gather in the area of Nihawand, near a key pass through the central Zagros, but what they actually intended to do is not known. Reports about this supposed massing of forces persuaded ‘Umar to authorise a pre-emptive strike, drawing on troops from both Kufa and Baṣra. The date of the consequent battle of Nihawand is disputed in the sources (it was most likely in 21/642, though perhaps as early as 18/639), and the actual course of events is blurred by the intrusion of the colourful anecdotes to which those sources are prone. It does appear to have been a fierce fight extending over several days; both the Arab and Persian commanders are said to have been killed, but in the end the Persian forces were decisively defeated.

After the ‘Victory of Victories’ at Nihawand ‘Umar endorsed a comprehensive invasion of the remaining Sasanian territories¹¹ (at that point it is unlikely he could have restrained the armies in any case). This might better be described as an occupation rather than an invasion, since further Persian resistance was isolated and sporadic. Many places, or at least some local authorities anxious to preserve as much of their lands and privileges as possible, chose to capitulate and sign treaties rather than resist. As a result, the Arabs – who by now had been joined by many defectors such as some Iranian cavalrymen (the *asawira*) and other non-Iranian irregular forces that had been in Sasanian employ (such as the *Zutt*)¹² – were able to advance fairly rapidly to the east. Not long after Nihawand, the Fadhūsafan (*padhgospan*) of Iṣfahan agreed to surrender the area on terms to the Arabs. From there a mostly Kufan army moved along the northern rim of the central desert basin of the

10 See Martin Hinds, ‘The first Arab conquests in Fars’, *Iran*, 22 (1984) for a critique of the problems in accounts of these campaigns.

11 Al-Ṭabarī, *Ta’rīkh*, series I, p. 2643.

12 See, for example, Aḥmad ibn Yaḥyā al-Baladhurī, *Kitāb futuḥ al-buldan*, ed. M. J. de Goeje (Leiden, 1866), pp. 365–74.

Iranian plateau towards Rayy, while a mostly Baṣran army set out along the southern perimeter of the basin towards Fars, and perhaps Kirman.

In the northern campaign, the difficulty the Persians had in maintaining a united opposition against the Arabs was quite apparent. Hamadhan was besieged immediately after the battle of Nihawand, and the commanding general, Khusrawshunum, agreed to surrender on the usual terms of immunity in exchange for tribute. After the surrender of the city one of the local aristocrats, Dīnar, managed to pass himself off as the 'king' of Media in order to sign a treaty with the Arabs and thereby enhance his own authority in the area. Other leaders and perhaps the general population were not so submissive: Hamadhan had to be retaken and a force of 12,000 troops stationed there. They were challenged by a combined force of Persians from Daylam, Azerbaijan and Rayy that reportedly put up a significant fight at a place called Waj al Rudh but were defeated (c. 22/643). Thereafter, the Arabs established a number of small garrisons in fortresses throughout Media to pacify the area and serve as a frontier zone adjacent to unconquered Daylam. The overlord of Rayy, Siyawakhsh ibn Mihran, also tried to resist the Arab advance; he was, however, betrayed by one of his vassals, a *dihqan* (village landlord and minor military officer) named Zīnabī, who showed the Arabs a way into the city and then arranged a treaty with them.¹³ The Mihranids were removed from power and their estates demolished; Zīnabī and his family were recognised as the new *marzbans* (military governors) of the city. Treaties of capitulations with other cities and rulers soon followed: with Qumis, Ruzban Ṣul of Jurjan, Farrukhan of Ṭabaristan and the Jīl Jīlan, and Shahrbaraz at al Bab.

In the south, Baṣran forces were joined by Arabs from Baḥrayn and the Gulf who had renewed their assault on the coastal areas of Fars. In 23/643f. they took Tawwaj (an important town probably located near the confluence of the Shahpur and Dalaki rivers, just inland from what is today the port of Bushire) and made it into a permanent base of operations.¹⁴ Shahrak, the *marzban* of Fars, tried once again to cut the Arabs off from their lines of communication but was defeated and killed in what is described as a major battle near Rīshahr. Presumably leaderless, demoralised and facing the combined Arab armies, the people of most of the other major towns of Fars Sabur, Arrajan, Fasa, Darabjird, Iṣṭakhr made treaties of submission and agreed to pay tribute. Places that did resist, such as Jahram or the forts at Shabir and Jannaba, were

13 Al Tabarī, *Ta'rikh*, series I, pp. 2653–5.

14 Rather typically, al Ṭabarī's source (*Ta'rikh*, series I, p. 2694) attributes the conquest to the Baṣrans under Mujashi' ibn Mas'ud, and al Baladhurī (citing Abu Mikhnaf) (*Futuh*, p. 386) to the Gulf Arabs under 'Uthman ibn Abi 'l 'Āṣ.

soon subdued. An apparent uprising of Persians and Kurds at Birudh, to the rear of the Arab armies, was also suppressed.

Virtually all of the recently conquered areas from Azerbaijan to Fars revolted after hearing news of the caliph 'Umar's assassination in 644, and had to be pacified again. It was not until 29/649f., after meeting fierce resistance, that the new governor of Baṣra, 'Abd Allah ibn 'Āmir, was able to regain firm control of Iṣṭakhr. One of his lieutenants, Mujashi' ibn Ma'sud al Sulamī, reportedly went on to take Kirman and Sīrjan. Mujashi' also attempted to invade Sīstan, but most of his army perished near Bīmānd in a sudden blizzard.¹⁵ After raising another army he was able to take control of the area south of Kirman, including Bamm, Jiruft and Hormuz. A second attempt to conquer Sīstan was made under Rabī' ibn Ziyad al Ḥarithī. After sporadic fighting and the capture of several small towns, Rabī' besieged the capital, Zaranj. The *marzban*, Abarwīz (or according to the *Tarīkh i Sīstan*, the shah of Sīstan, Iran ibn Rustam ibn Āzadkhu, and the high priest), decided to capitulate, out of a mixture of respect for the religion of the invaders and shock at the barbarity of their actions.¹⁶ While this was going on, the bulk of Ibn 'Āmir's army moved into Quhistan as a prelude to the systematic conquest of Khurasan.

Accounts of the conquest of Khurasan and eastern Iran are usually connected to the pursuit of Yazdegerd, the last Sasanian shah. After the initial Arab victories he had supposedly tried to rally resistance from Rayy, Jur, Kirman, Sīstan, and finally Marw and Marw al Rudh, but in case after case he had been obliged to leave after disputes with the local governors – usually over access to funds from the treasury, but sometimes also due to fears his presence would be an invitation for the Arabs to attack. According to some of al Ṭabarī's sources, an effort to capture him began as early as 23/543f.: as the Baṣran forces advanced from Fars to Sīrjan, Kirman, Sīstan and Makran, a detachment under Aḥnaf ibn Qays crossed the desert directly from Iṣfahan to enter Khurasan at Ṭabasayn and proceeded to take Herat, Nīshapur, Sarakhs and Marw.¹⁷ If this expedition took place at all, however, it could hardly have been more than a passing raid. Other reports have Yazdegerd still in Fars, either having returned from Khurasan or perhaps not yet having left the area, at the time of the revolts and Ibn 'Āmir's campaign.

15 Al Ṭabarī, *Ta'rikh*, series I, p. 2863. The *Tarīkh i Sīstan* (ed. Malik al Shu'ara' Bahar, (Tehran, 1935), p. 63), however, says he was defeated in battle. Baladhurī, *Futuh*, p. 391 simply says that his army was wiped out.

16 *Tarīkh i Sīstan*, p. 81 (trans. Milton Gold as *The Tarikh e Sistan* (Rome, 1976), p. 64); cf. Baladhurī, *Futuh*, pp. 393–4.

17 Baladhurī, *Futuh*, p. 403 attributes the conquest of Ṭabasayn about this same time to 'Abd Allah ibn Budayl, who perhaps led an autonomous raid of his own.

Following the crushing defeat of the Persians at Iṣṭakhr he set out (again?) from Jur for Khurasan in 30/650f. Stories about his movements and activities are thus numerous, but differ greatly in their details; it is clear enough, however, that he had no success in organising any general resistance to the Arab advance, either among the local population or from the Hephthalites, Sogdians, Turks and Chinese, to whom he supposedly appealed for help. Even the armed forces remaining with him were destroyed, most likely because of a treacherous betrayal by the *marzban* of Marw, Mahuya; Yazdegerd himself was murdered in 31/651f., though by whom, how and why is much disputed.¹⁸

There are reports that an army under Qarin, apparently a scion of the famous noble family of Sasanian times, attempted to resist Aḥnaf's advance in 32/652f. but was defeated. There may also have been an effort at resistance in 655 by Yazdegerd's son, Fīruz, with some Chinese backing and the support of troops from Ṭukharistan; if so, it too failed.¹⁹ For the most part, the various towns and cities of Khurasan, without any semblance of coordinated resistance, fended for themselves with the various detachments of Ibn 'Āmir's army. Most of the smaller towns, such as Zam, Bayhaq or Baghgh, are said to have been conquered (one suspects they were attacked mostly because they lacked adequate fortifications and made easy targets). Larger cities, particularly those with military governors anxious to preserve their positions and privileges, generally agreed to capitulate on terms. Thus Nīshapur, Nasa, Abīvard, Herat, Marw and Marw al Rudh capitulated; the *kanarang* (the local ruler) of Ṭus apparently sought out a treaty arrangement even before his city came under attack. The most determined resistance came from the mostly Hephthalite areas of Ṭukharistan. That region was invaded by a detachment under Aḥnaf ibn Qays, who defeated a large opposing army, took the cities of Juzjan, Ṭalaqan, Faryab and Balkh, and even attempted to raid down the Oxus to Khwarazm.

Although virtually the whole of the former Sasanian empire was thus overrun, it was hardly subdued. Just as the agreements that had hastily been made in western Iran soon broke down and resulted in open rebellion, so too did those in eastern Iran. In most cases these 'revolts' were efforts to avoid the regular payment of taxes and tribute, taking advantage of the civil strife that had broken out among the Arabs after the murder of 'Uthman. This was represented, for example, in the revolt of Nīshapur in 37/657f. as well as in a major revolt in Fars and Kirman in 39/659f., when the inhabitants are said to

¹⁸ Al Ṭabarī, *Ta'rikh*, series I, pp. 2872–84.

¹⁹ H. A. R. Gibb, *The Arab conquests in Central Asia* (London and New York, 1923), p. 16.

have driven the tax collectors out of every district.²⁰ It would seem that agreeing to pay tribute to encourage a marauding army to move on was one thing, but actually having to pay them taxes year after year quite another. A major turning point in terms of alleviating this problem and consolidating the conquests apparently came with 'Alī's appointment of Ziyad ibn Abīhi as governor of Fars and Kirman to deal with the revolt there. Ziyad established a new fortress and treasury near Iṣṭakhr, restored order, and gradually won the support of the populace through what seems essentially to have been a policy of the carrot and the stick.²¹ Later, as governor of Baṣra under Mu'awiya, Ziyad also brought to an end a series of revolts in Khurasan, reorganised the administrative structure of the province, and established a large permanent garrison of Arab forces at Marw.

At the same time that so many areas were restive, other areas on the periphery of the conquests were only under nominal control, or were openly hostile. The 'conquests' in Ṭabaristan, for example, amounted to nothing more than the acceptance of mutual non aggression pacts by which the local hereditary rulers remained in place but paid some token tribute. The treaty was broken by a Kufan army under Sa'īd ibn al 'Āṣ in 30/650f. that attempted, with minimal success, to invade Ṭabaristan from Jurjan after it had failed in its effort to advance towards Khurasan. Arab armies sent against Ṭabaristan in 41/661 and 61/680 were both routed. In Jurjan itself the Arabs had to deal with the local Turkic ruler, the *ṣul*, until he was finally defeated in 98/716f. Even more troublesome were areas such as the principalities of Badhghīs and Ṭukharistan in the highlands of what today would be north west Afghanistan. The Arabs frequently raided these areas from their bases at Marw al Rudh or Balkh, but were fiercely resisted by the Hephthalite inhabitants, perhaps in coalition with Turkish, Sogdian and Tibetan allies. Nīzak Ṭarkhan, the Hephthalite ruler of Badhghīs, was the wiliest of these adversaries. An opportunist, he (or a predecessor with the same name/title) had supposedly been involved in the murder of Yazdegerd, campaigned against Rabī' ibn Ziyad in Quhistan in 51/671f., and alternately collaborated with or fought Arab commanders until he was finally killed in 91/710. A similar situation prevailed to the south in Sīstan. The Arabs were in relatively firm control of Zaranj, where, as noted earlier, the ruler and inhabitants had decided to capitulate. Their efforts to raid or control adjacent territories,

20 Al Ṭabarī, *Ta'rikh*, series I, p. 3449. Al Ṭabarī (ibid., pp. 3350, 3390) curiously attributes the revolt in Nishapur to the people's espousal of unbelief (*kufṛ*), but it hardly seems possible that they would have converted and apostatised at such an early date.

21 Ibid., pp. 3349–50.

however, were contested fiercely and mostly successfully by the existing rulers, notably the *zunbīl*²² of Rukhkhaj and Zamīndawar and the *kabulshah*, neither of whom could be subdued. For the better part of two centuries the *zunbīl* was 'a bone in the throat' of the Muslims.²³

Another, and essentially final, phase of the conquests in the Islamic east can be said to have begun after Ziyad's reforms in Khurasan and to have concluded in 751 with the great victory of Ziyad ibn Ṣalīḥ over a coalition of Central Asian forces at the battle of Talas. This expansion, which brought Transoxania as well as Sind under Muslim rule, appears rather different in character from the earlier phases of the conquests. It was made possible by Ziyad's administrative reforms and the settling of large, permanent Arab military garrisons in Khurasan, but it was also marked by a much greater degree of collaboration between the Arabs and local military forces in joint operations of mutual benefit. As a result, it soon acquired the features of a systematic war of expansion rather than the rather haphazard filling of a political vacuum by the disorganised raids that typified earlier periods.

The initial forays across the Oxus were aimed at Bukhara in 54/673f. and Samarqand in 56/675f. Details about both campaigns, the first led by 'Ubayd Allah ibn Ziyad and the latter by Sa'īd ibn 'Uthman, are sketchy, but they are said to have succeeded in extracting promises to pay tribute. An effort to follow up on these campaigns was apparently undertaken by Salm ibn Ziyad in 61/68 of., but it achieved little before being disrupted by the civil war that broke out during the reign of Yazīd I. As noted by H. A. R. Gibb, circumstances in Central Asia were at that time actually rather propitious for an Arab advance,²⁴ but the political upheavals of the late Sufyanid and early Marwanid periods resulted in a long hiatus of a quarter century in the campaigns and a reversal of many of the earlier successes. This changed dramatically with the appointment of Qutayba ibn Muslim as governor of Khurasan on behalf of al Ḥajjaj in 86/705.

Several important developments are noticeable in the period of Qutayba's administration. First of all, he was from a 'neutral' tribe, Bahila, and thus not beholden to the existing Arab factions in Khurasan while being in a good position to keep them united. Second, in his inaugural address in Khurasan he emphasised the importance of *jihad* and the struggle on the frontier²⁵ (typical

22 This term, which also appears in the sources in orthographical variants such as *rutbīl*, could have been a personal name but was most likely the hereditary title of a priest king who ruled over the upper Helmand valley: see e.g. G. Scarcia, 'Zunbīl or Zanbīl?', in *Yádnáme ye Jan Rypka: Collection of articles on Persian and Tajik literature* (Prague, 1967), pp. 41–5.

23 Al Ṭabarī, *Ta'rikh*, series I, p. 2706.

24 Gibb, *Arab conquests*, pp. 22–3.

25 Al Ṭabarī, *Ta'rikh*, series II, p. 1179.

of his religious policy but also a convenient means of keeping the tribal factions united and too busy for the internecine political rivalries that had proven so disruptive). Third, he left little room for doubt that the conquests carried out were meant to be permanent and treaty arrangements to be honoured accordingly; cities or people that revolted or reneged on the payment of tribute were severely punished,²⁶ in stark contrast to the milder renewal of terms that had earlier been the norm. Finally, he encouraged the fraternisation of Arabs and the local peoples (having Arab troops quartered in native houses in Bukhara, for example²⁷), and made extensive use of indigenous soldiers willing to help in his campaigns, both as auxiliaries and as members of the standing army. Taken together, these policies led to a decade of spectacular military successes in the Islamic east, which have been described in detail by Gibb:²⁸ the re establishment of control over the rebellious areas of Ṭukharistan in 86/705; the conquest of Bukhara and its suburbs, Samarqand and Khwarazm (over the period 87–93/706–12); and excursions across the Jaxartes and deep into the Farghana valley (where Qutayba was murdered during an army mutiny in 96/715 or 716). Qutayba also took a hand in the affairs of Sistan and helped direct a new campaign against the *zunbīl* in 92/711. Not exactly to his credit, he also had Nīzak Ṭarkhan murdered.

The expansion again lost momentum after Qutayba's murder, and it was not long before the Arabs were placed on the defensive by the emergence of a powerful alliance of Sogdian and Turkish (Türgesh) forces, backed by Chinese support. The Turkish counter offensive began with a surprise attack on the fortress of Qaşr al Bahilī in 102/720. In 106/724 the Turks routed an army in Farghana led by Muslim ibn Saʿīd al Kilabī, and by 110/728 they were threatening Samarqand. An infusion of reinforcements by Syrian troops eventually helped turn the tide: in 119/737 the Turks were able to cross the Oxus and invade Khurasan, but were defeated in a skirmish at Kharistan. The Turkish camp, including its flocks of sheep, was captured; not long afterwards the Turkish *khaqan* was murdered and his confederation collapsed. Under the governorship of Naṣr ibn Sayyar virtually all that the Arabs had lost was retaken by 123/741. The definitive victory marking the consolidation of the

26 For example, the severe punishment of the rebels in Bukhara or the execution of Nīzak.

27 Abu Bakr Muḥammad Narshakhī, *Tarīkh i Bukhara*, ed. Mudarris Raḍavī (Tehran, 1972), p. 66, ed. and trans. R. N. Frye as *The history of Bukhara* (Cambridge, MA, 1954), p. 48.

28 Gibb, *Arab conquests*, pp. 29–57.

Islamic east would come ten years later, after the 'Abbasid revolution, with Ziyad ibn Ṣalīḥ's defeat of a Chinese led army at Talas – an event of world historical significance, though one curiously neglected in works by the early Arab historians.

The conquests and the development of regionalism

The Arab conquests in what would become the Islamic east entailed a number of demographic, social, economic, political and cultural changes that would help determine the parameters for the development of this area. These changes are not easy to follow or to explain: even in the most obvious and important case the transition from a very diverse religious population to a predominantly Muslim one – the best available interpretations of the process of conversion still involve a considerable degree of conjecture. The early Arabic sources tend to deal with such matters only in incidental or anecdotal fashion, and provide little in the way of solid historical data. At the same time they are overwhelmingly interested in the affairs of the Arab conquering elite, while largely ignoring the vastly greater subject population, giving only minimal attention to non Arab Muslims and virtually none at all to non Muslims. Occasionally, though, there are bits of information that surface to suggest the broad outlines of regional developments. In addition, there have survived some provincial histories – works on areas such as Sīstan or Ṭabaristan and clearly written from the perspective of the periphery rather than the imperial centre – that can provide important correctives to the usual narratives; they are, however, generally in Persian and of a relatively late date, and consequently have often been discounted or ignored by modern historians.

In terms of demographic change, it is obvious that the conquests did lead to the intrusion of a substantial number of Arab settlers, either as occupying forces or outright colonists. Exactly how large this new Arab population was and where it was concentrated is more difficult to say. As noted earlier, accounts of the conquest often mention or imply the establishment of more or less permanent military garrisons in strategic locations such as Tawwaj, Iṣṭakhr, Kirman, Zaranj, Iṣfahan, Hamadhan, Qazvīn, Rayy, Ardabīl and Bab al Abwab; when numbers are mentioned, they are usually in the range of 4,000–8,000 per garrison (the number stationed at Bab al Abwab, a critical frontier post, was much larger). At least some of these forces remained in place, and several petty dynasties (such as the Rawwadids or Dulafids) that eventually emerged in western Iran could trace their origins back to early commanders of these garrisons. The same pattern was followed at first in

Jurjan and Khurasan, but military necessity there dictated settlement on a much larger scale. In 51/671 Rabīʿ ibn Ziyad is supposed to have settled 50,000 warriors and their families in Khurasan, and several thousand more were sent a few years later by Salm ibn Ziyad, perhaps to replace those who elected not to stay permanently. Al Baladhurī and Balʿamī give a similar number of 47,000 Arab troops in Khurasan at the time of Qutayba's governorship.²⁹ Most of these settlers seem to have resided in the Marw oasis, but groups of Arab settlers can also be identified in other cities of Khurasan such as Balkh and Marw al Rudh. These numbers can certainly be questioned but are not inherently unreasonable, and if the soldiers' families in fact came to settle with them, one could assume an immigrant population of approximately 150,000 Arabs in the area.³⁰

As is implied by the history of the conquests, three basic zones of Arab settlement in the Islamic east can be distinguished. The area to the north and west of a line from around Nihawand to Jurjan was conquered, for a while administered, and mostly colonised by Arab tribesmen from Kufa. The area to the south and west was similarly conquered, administered and settled by Arabs from Baṣra. Initially, Khurasan was also regarded as a predominantly Baṣran territory, but its emergence as a crucial frontier province soon dictated an expanded presence of Arab forces that included both Kufans and Baṣrans and, later, Syrians as well. These patterns of settlement had significant implications for regional political and religious development. Kufa was well known for its anti Umayyad and pro 'Alid sentiments, and its dissident tribesmen often found it convenient to remove themselves, apparently in rather substantial numbers, to more isolated areas of al Jibal. The area around Qumm was a particularly popular location for such immigrants, attracting former supporters of al Mukhtar, rebels against al Ḥajjaj and Shī'ite Ash'arī tribesmen. Likewise, dissidents from Baṣra tended to seek refuge in Khuzistan, Fars, Kirman and Sistan. These were mostly Kharijites: after failing to hold Baṣra, Kharijites led by Nafi' ibn al Azraq (perhaps a non Arab in origin) controlled Ahwaz down to 65/685,

29 Baladhurī, *Futuḥ*, p. 423; Abu 'l Faḍl Muḥammad Bal'amī, *Tarjamah yi Tarīkh i Tabarī*, ed. M. Rawshan as *Tarīkh namah ye Tabarī*, 3 vols. (Tehran, 1988), p. 873. Zotenberg's French translation of Bal'amī (*Chronique de Abou Djafar Mohammed ben Djarir ben Yezid Tabarī*, 4 vols. (Paris, 1867-74)) claims 40,000 Baṣran and 47,000 Kufan troops; although this figure has sometimes been accepted (e.g. P. Oberling, "Arab IV: Arab tribes of Iran", *Elr*, vol. II, p. 215), it is clearly erroneous and is given correctly as 40,000 Baṣran and 7,000 Kufan troops in the Rawshan edition.

30 Saleh Said Agha, *The revolution which toppled the Umayyads: Neither Arab nor 'Abbasid* (Leiden, 2003), pp. 177-85 reviews the evidence and concludes that the Arab population was at least 115,000 but no more than 175,000.

and Azraqī Kharijites virtually ruled Fars and Kirman until their 'caliph', Qatārī ibn al Fuja'a, was defeated and killed around 79/698f. In Khurasan and Transoxania, political problems developed not so much from 'unofficial' settlement by rebels and dissident sects as from factional disputes among the 'official' settlers – rivalries between Baṣran troops and settlers and the more recent Kufan arrivals and, later, friction between both of them and the new influx of Syrian troops. Perhaps as a result, religious trends there tended to develop almost as a reaction to the Shi'ism and Kharijism of other areas. Although they often seemed to express affection for the family of the Prophet and made pious calls for rule in accordance with the Qur'an and the *sunna*, they also attempted to defuse sectarian tensions and to foster better relations between Arab and non Arab Muslims. Thus two of the strongest religious trends in that part of the Islamic east were the theological school of the Murji'a, which emphasised avoiding contention over the relative merits of 'Uthman and 'Alī (but could also be quite critical of the Umayyad central government and was heavily involved in revolts against it),³¹ and the Ḥanafī school of law, which appealed greatly to non Arab Muslims – in its willingness, for example, to legitimise the uses of languages other than Arabic for religious purposes.

As for the overall impact of these demographic developments, it is probably safe to say that the conquests and subsequent influx of Arabs settlers did little to displace the existing population, or even to disrupt the existing social structure – at least initially. There are, of course, in non Muslim sources some allegations of destruction and persecution that contrast rather sharply with the much more benign picture of the conquests suggested by the Muslim historians. The 'Khuzistan Chronicle' claims that the Arabs 'shed blood there as if it were water' and killed a number of Christian religious notables.³² Various Zoroastrian texts such as the *Zand i Vohuman Yasht*, which claims the Arabs killed righteous men as easily as they would a fly, or the *Qīṣṣa i Sanjan*, which alludes to the persecutions that eventually caused the Parsees to flee to Gujarat, also raise this possibility. Even in Muslim accounts there are occasionally references, if of debatable reliability, to mass killings: Sa'īd ibn al 'Āṣ is supposed to have treacherously slaughtered all the defenders of a fortress in Ṭabaristan save one,³³ and Yazīd ibn al Muhallab to have murdered

31 See Wilferd Madelung, 'The early Murji'a in Khurasan and Transoxania and the spread of Ḥanafism', *Der Islam*, 59 (1982); Khalil Athamina, 'The early Murji'a: Some notes', *JSS*, 35 (1990).

32 Translation in Robinson, 'Conquest of Khuzistan', p. 18.

33 Al Ṭabarī, *Ta'rīkh*, series I, p. 2837; however, the story, like those in most of this section of the narrative, sound suspiciously like fables or folklore.

thousands of Turks in Jurjan, as their leader, Ruzban, had neglected to secure an amnesty for them.³⁴ The *Tarīkh i Qumm* claims that the defenders of Shustar (Ar. Tustar) killed their families and destroyed their belongings rather than surrender them to the Arabs, and it portrays the Arab and Iranian populations in Qumm as living in rather frosty isolation from each other for quite some time,³⁵ a pattern apparently followed in several other areas as well. Many Sogdians are also said to have fled, against the advice of their king, to more remote parts of Inner Asia out of fear of reprisals.³⁶ These probably represent extreme cases, however, and it is likely that the experience of the conquests by the population of south western Iran was rather different from that in areas such as Ṭabaristan or Sīstan, which were barely affected, or Khurasan, where circumstances really demanded cooperation between the Arab forces and their subjects.

The formation of a new Arab social elite in the Islamic east also had less of an impact on the existing social structure than one might think. Sasanian society was organised in a fairly rigid system of four classes (bureaucracy, military, clergy and subjects) and a hierarchy of officials: the monarch and great imperial officers (such as the commander general of the army, the *Iran-spahbad*); the de facto local rulers (*shahrdaran*); the military grandees (*waspuhragan*); the lesser nobility (*wuzurgan*); freemen (*azadan*); and ordinary subjects, mostly peasants.³⁷ A good deal of this structure is still apparent well into the conquest period, if in slightly modified form, under different names, with changes in personnel, and with the integration of the new Arab military elite into it. In the longer term, the most important changes probably derived from the stimulation of the urban environment in the form of more and larger cities, along with the commercial activities and social classes that accompanied them.

Obviously, the top of the old structure, the Sasanian monarchy and its attendant imperial institutions, was obliterated in the course of the conquests, culminating in the murder of Yazdegerd and the destruction of the retinue and praetorian guard he had with him. The supposed efforts of his son and

34 Baladhurī, *Futuḥ*, p. 336, trans. P. K. Hitti and F. C. Murgotten as *The origins of the Islamic state*, 2 vols. (New York, 1916–24), vol. II, p. 41.

35 Hasan ibn Muḥammad Qummī, *Kitāb i tarīkh i Qumm* (Tehran, 1353/1934), p. 300. It has been noted that this tendency to keep Arab and Zoroastrian populations physically separated may have been due to the important Zoroastrian beliefs regarding ritual purity and pollution; see Jamsheed K. Choksy, *Conflict and cooperation: Zoroastrian subalterns and Muslim elites in medieval Iranian society* (New York, 1997), p. 44.

36 Al Ṭabarī, *Ta'rikh*, series II, p. 1439.

37 For a survey of the Sasanian social hierarchy, see A. E. Christensen, *L'Iran sous les Sassanides*, 2nd edn (Copenhagen, 1944), pp. 97–113; see also Josef Wiesehöfer, 'The late Sasanian Near East', chapter 3 in this volume.

pretender to the throne to restore the regime came to nothing, as most of his help came from outside forces and received little support from within the conquered areas. The Zoroastrian clergy probably suffered almost as much as the monarchy; their popular support had been dwindling for some time, and they were heavily dependent on state support, which was now cut off. Some members of the aristocracy who had remained loyal were also eliminated: Hurmuzan was sent to Medina, where he narrowly escaped being executed, only to be murdered after the assassination of 'Umar. As noted earlier, the valiant *marzban* of Fars, Shahrak, fell in battle. The *marzban* of Kirman was killed, as was Zadhuya, the *marzban* of Sarakhs.³⁸ The whole sale slaughter that occurred at places such as Iṣṭakhr after the revolt of 29/649f. must also have done away with many members of the officer corps and other officials.

However, it is also clear that a very substantial number of aristocrats, military governors, prefects and administrators survived, and even thrived, by choosing to collaborate with the invaders. The notorious Mahuya of Marw is but the best known example; he was still in a position of authority as late as 36/656f., when he hastened after the assassination of 'Uthman to secure recognition of his position from 'Alī. Other provincial lords who managed to stay in place for some time included Mardanshah, the *mašmughan*³⁹ of Dunbawand; Ruzban Šul, the Turkish ruler of Jurjan; Farrukhan of Ṭabaristan; and the tenacious Nizak Ṭarkhan of lower Ṭukharistan.⁴⁰ Although less frequently mentioned in the sources, it is likely that a large percentage of lower ranking military nobles also remained: Shahrbaraz secured his position and the status of tax exempt auxiliaries for his troops at Darband, and he probably expressed a common sentiment when he told his Arab counterpart that they should cooperate since noblemen associate with noblemen and both were facing a common 'rabid enemy' and people of ignoble descent (i.e. the Khazars). Likewise, the letter 'Alī sent confirming Mahuya in office was addressed to the 'landlords of Marw, cavalry, and army officers (*dahaqīn, asawira, and jundsalarīn*)', which indicates that a significant section of the old military aristocratic hierarchy was still in existence in Khurasan.⁴¹ It is not uncommon to find mention of other lesser

38 Baladhurī, *Futuḥ*, p. 405.

39 Translated in Wilferd Madelung, 'The minor dynasties of northern Iran', in Frye (ed.), *The Cambridge history of Iran*, vol. IV, p. 199 as 'Great One of the Magians', perhaps suggesting here as in other places the existence of a kind of local priest king.

40 Al Ṭabarī, *Ta'rikh*, series I, pp. 2656, 2658, 2659; on Nizak, see E. Esin, 'Ṭarkhan Nizak or Ṭarkhan Tirek? An enquiry concerning the prince of Badhghīs ...', *JAOS*, 97 (1977).

41 Al Ṭabarī, *Ta'rikh*, series I, p. 3249.

officials who were still exercising authority after the conquests, such as Bahmana, administrator of Abīvard,⁴² or the *yazdanfadhār* of Abarishtjan, who provided land for the Ash‘arī colonists who came to Qumm.⁴³ As late as 61/680f. there was still in existence some kind of council of the ‘kings of Khurasan’ to coordinate their activities.⁴⁴ Finally, and most importantly, at the base of the old Sasanian social structure were the *dihqans*, the village landlords, who clearly survived as a class and were indispensable to the Arabs as tax collectors, auxiliaries and administrators. They also served as significant cultural interlocutors, both keeping alive old Iranian social traditions and using them to influence the customs and behaviour of the Arab conquerors. For example, ‘Abd Allah ibn al Zubayr, during his stay in Sistan, was reportedly given advice on how to govern by Rustam ibn Mihr Hurmuzd al Majusī in the form of proverbs known to the *dihqans*.⁴⁵ Likewise, the governor of Khurasan, Asad ibn ‘Abd Allah, attended a Mihrijan feast at Balkh in 120/737f. organised by the *dihqans* of Khurasan, who lavished gifts on him and praised him for his conduct (which they saw as in keeping with the Sasanian principle of justice in the sense that neither weak nor strong, rich nor poor, could be oppressed).⁴⁶

Finally, there is the key but most difficult issue of how the conquests and resulting demographic and social changes can be connected to the conversion of most of the population (previously a mix of Zoroastrians, Christians, Buddhists, Manichaeans, Jews and other faiths) to Islam. This turns on two basic questions: what were the motives for conversion; and at what rate did they proceed?

The problem of motivation (and along with it the matter of sincerity and exactly what it meant to ‘convert’) is particularly difficult to address. If one looks, for example, at the hagiographical literature (such as the collection of biographies of Sufi saints by Ḥujwīrī, d. c. 469/1072), it might be concluded that conversion was a largely random process that involved some kind of personal spiritual crisis and resolution leading to a profound faith. The historical literature, on the other hand, often implies much more mundane factors such as a desire to maintain social status or to avoid taxes. It also suggests that ‘conversion’ was, at least initially, a rather superficial change Narshakhī (*fl.* 332/943), for example, says that the people of Bukhara thrice

42 Baladhurī, *Futuḥ*, p. 404.

43 Qummī, *Tarīkh i Qumm*, p. 32.

44 Al Ṭabarī, *Ta’rīkh*, series II, p. 394.

45 *Tarīkh i Sistan*, p. 106 (trans. Gold as *The Tarikh e Sistan*, p. 85).

46 Al Ṭabarī, *Ta’rīkh*, series II, pp. 1635–8.

converted to Islam and then apostatised before Qutayba ibn Muslim 'planted Islam in their hearts', and even then they still worshipped idols in secret.⁴⁷ We can, however, be fairly sure that outright coercion – as opposed to various social pressures – was a factor of minimal importance in bringing about conversions: the best known evidence is probably the letter of Bishop Ishoyahb III of Rev Ardashir that complains about how quickly and readily the Christian population of Marw had decided to embrace Islam even without the threat of persecution.⁴⁸ We are also told that plans by Ziyad ibn Abīhi to execute Zoroastrian religious leaders and destroy fire temples in Sīstan were blocked by protests from the local Muslim population, who insisted on honouring the principle of tolerance embedded in the peace treaties they had concluded.⁴⁹ Proselytising and inducement as official policy, however, did play a role in converting the general population. There are several indications of this in, for example, the *Tarīkh i Sīstan*. 'Abd al Raḥman ibn Samura is supposed to have brought Ḥasan al Baṣrī to Sīstan in 43/663 to help reform the government and to teach Islam to the people, and many Zoroastrians converted because of their impression of the virtue and justice of the administration of Rabī' al Ḥarithī. A great adversary of al Ḥajjaj, 'Abd al Raḥman ibn Muḥammad ibn al Ash'ath, also courted the people of Sīstan (i.e. Zaranj), Bust, Zabul and other eastern lands, and used scholars and popular preachers 'to capture the minds of the people' there and 'to make Islam and the Shari'a attractive to them' while simultaneously complaining about al Ḥajjaj's oppression.⁵⁰ Proselytising also seems to have been a conscious and deliberate aspect of Qutayba ibn Muslim's strategy in Transoxania, as he not only founded new mosques there but subsidised attendance at the prayer services.⁵¹ It is well known that 'Umar II strongly endorsed efforts to promote conversion, inviting the 'kings of Transoxania' to accept Islam and ordering the governor of Khurasan, al Jarraḥ ibn 'Abd Allah al Ḥakamī, to make it easier for people to convert and to remit their taxes.⁵² Similarly, al Ḥarith ibn Surayj and the Murji'a in Khurasan encouraged conversion by championing the rights of non Arab Muslims while insisting that the non Muslims be held strictly to the payment of *dhimmī* taxes, and conversion was probably an important aspect of the 'Abbasid propaganda mission (*da'wa*) too.

47 Narshakhī, *Tarīkh i Bukhara*, p. 66, trans. Frye as *History*, pp. 47–8.

48 See Thomas Walker Arnold, *The preaching of Islam* (London, 1913), pp. 82–3.

49 *Tarīkh i Sīstan*, p. 92, trans. Gold as *The Tarikh e Sistan*, p. 74.

50 *Tarīkh i Sīstan*, pp. 83, 114–15, trans. Gold as *The Tarikh e Sistan*, pp. 66, 92.

51 Narshakhī, *Tarīkh i Bukhara*, pp. 67–8, trans. Frye as *History*, pp. 47–9.

52 Baladhurī, *Futuḥ*, p. 426; al Ṭabarī, *Ta'arīkh*, series II, p. 1354.

The most systematic effort thus far to trace the pace of conversion in the Islamic east has come from a quantitative analysis by Richard Bulliet of data in medieval Islamic biographical dictionaries.⁵³ It suggests that the conversion process proceeded slowly until about the time of the 'Abbasid revolution, and then accelerated rapidly until the mid third/tenth century, by which time 90 per cent of the population had become Muslim. Of course, the biographical data on which this study was based tend to be confined to a fairly narrow social class (religious scholars) and discrete urban environments; it is not entirely clear how far the results can be extrapolated to reflect the conversion process in general. There are at least a few indications in narrative sources that in some places early conversion, or at least nominal conversion, might have been more common than this scenario suggests: al Baladhurī, for example, reports that the people of Qazvīn, facing defeat, decided to become Muslims because they disliked the prospect of paying the poll tax; the *Tarīkh i Sīstan* says that many Zoroastrians became Muslims because they were impressed by the justice and equity of the administration of Rabī' al Ḥarithī; and the *Tarīkh i Bukhara* also claims that the people of that city converted very readily to Islam in the days of Qutayba ibn Muslim, who was flexible enough to allow prayer services to be conducted in Persian as well as to pay a dole for attendance at Friday prayers.⁵⁴ Conversion stories in the historical literature may be somewhat more common for the period before the 'Abbasid revolution, but this is probably due to their novelty (and the status of the converts) rather than their number. It may also be that some places resisted conversion much longer than others: there are reports that Fars still had a substantial Zoroastrian population even towards the end of the tenth century.⁵⁵ For the most part, however, Bulliet's results seem to track well both with anecdotal material about conversion and with what is known about overall historical developments. Reports about the size of the Muslim army in Khurasan just before the 'Abbasid revolution, for instance, suggest that non Arab Muslims (*mawālī*) made up about 15 per cent of the military forces, roughly the same percentage as the quantitative study indicates for the general population. If the pattern

53 Richard W. Bulliet, *Conversion to Islam in the medieval period: An essay in quantitative history* (Cambridge, MA, 1979), summarised in Richard W. Bulliet, *Islam: The view from the edge* (New York, 1994), pp. 38–9. An outdated but still useful study of anecdotal evidence about conversion in the Islamic East can be found in Arnold, *Preaching of Islam*, pp. 82–6, 209–20; more recent, but rather unsatisfactory in its handling of the source material, is Choksy, *Conflict and cooperation*.

54 Baladhurī, *Futuh*, p. 321; *Tarīkh i Sīstan*, p. 91, trans. Gold as *The Tarikh e Sistan*, p. 74; *Tarīkh i Bukhara*, pp. 67–8, trans. Frye as *History*, p. 48.

55 For example, Muqaddasī, *Aḥsan al taqasīm*, p. 429.

holds, the tipping point when the majority of the population became Muslim came during the mid second/ninth century; by the early third/tenth century the conversion process was largely complete. These, as will be seen, are also critical times in the political evolution of the Islamic east, corresponding to the periods when autonomous and then fully independent dynasties of regional rulers appeared. The implication would thus seem to be that a unified Islamic empire was viable as long as it involved a small Muslim elite ruling over a vast non Muslim population, but much harder to justify as that population converted: religious homogeneity magnified the importance of other differences. In that sense, ironically enough, conversion would seem to be an essential ingredient, not in consolidating and assimilating the population of an Islamic empire, but in the formation of regional identities in a Muslim oecumene. It is also particularly important to note that in the Islamic east, and virtually nowhere else during this period, conversion to Islam did not also produce a transition to Arabophone culture; vernacular languages and culture remained dominant.⁵⁶ This was of considerable significance since it helped ensure that Islam evolved into a multicultural world religion instead of remaining an essentially Arab religion.

The political development of the Islamic east

The classical Arabic historical sources, and a good many modern historians who follow them, generally tend to convey the impression of an Islamic east that was for some time a well integrated part of an imperial system, with the caliphs appointing and dismissing governors, directing wars and policy, and systematically collecting taxes and tribute. Nonetheless, it is unlikely that such a highly centralised empire actually existed for any substantial length of time, or even at all. As has already been indicated here, the conquered areas were riddled with largely autonomous enclaves. Numerous local rulers and nobles from the old order remained in place. The administration of the fiscal apparatus depended heavily on the same class that had played that role in Sasanian times. Even many of the governors designated by the caliph came from powerful families of the Arab elite in the provinces, and frequently used that local power base to rebel, so that it might be more accurate to say that they were 'recognised' rather than 'appointed'. In the century or so following

⁵⁶ On this phenomenon, see in particular Ehsan Yarshater, 'The Persian presence in the Islamic world', in R. G. Hovannisian and Georges Sabagh (eds.), *The Persian presence in the Islamic world* (Cambridge, 1998), pp. 4–125.

the conquest period, a tension between the forces of central authority and regional autonomy was quite noticeable before it was definitively resolved in favour of the latter; this transformation from empire to regional common wealth is perhaps the overarching theme of the history of the Islamic east during the period of the high caliphate.

At least in theory, the conquest of the Islamic east replaced the Sasanian administrative structure of the four 'quarters' and their subordinate *kuras* with a set of provinces connected to the central government via Kufa and Baṣra (or later as part of what has been called the 'superprovince' of Iraq⁵⁷). This network of provinces and sub provinces is familiar from the works of the medieval Arabic geographers, and has been comprehensively described in Guy LeStrange's classic *Lands of the eastern caliphate*. Leaving aside the Mesopotamian areas (parts of eastern Anatolia, al Jazīra, Iraq and Khuzistan) as well as those along or beyond the Indus, there were approximately twenty such provinces, most with many subdivisions, distributed among what we might regard as six or seven quite distinct geographical regions: the Caucasian provinces (Armenia, Arran, Shirwan), the Caspian provinces (Muqan, Jilan, Ṭabaristan, Jurjan), the provinces of the western Zagros (Azerbaijan, al Jibal), the provinces of southern Persia (Fars, Kirman), the provinces of north eastern Iran (Qumis, Quhistan, Khurasan), Chorasmia (Khwarazm), the Transoxanian provinces (Sogdia, Ushrusana, Shash), and the provinces of south eastern Iran (Sijistan/Sīstan and Makran).

The political history of these provinces – either individually or collectively – is not, however, a very satisfactory framework for discussing regionalism in the Islamic east, partly because we are told a great deal more about events in some provinces than others, and partly because the divisions themselves are somewhat arbitrary. Political economy, rather than fiscal administration, provides a better guide to distinguishing the various regions of the Islamic east and following their development. The key fact in this regard was the growing importance of Khurasan and Transoxania, *al mashriq* par excellence, as a frontier for expansion, as a centre of trade and commerce and as a hotbed for political upheaval – so important, indeed, that its history is virtually impossible to separate from that of the caliphate in general. Other areas, notably Azerbaijan and Sīstan, might have played comparable roles, but both became essentially static and defensive frontiers, rather than the dynamic type of frontier represented by Khurasan, and neither had a comparable place in the

57 Khalid Yahya Blankinship, *The end of the jihad state: The reign of Hisham Ibn 'Abd al Malik and the collapse of the Umayyads* (Albany, 1994), p. 57.

commercial networks of the time (the areas north of the Caucasus being of minor economic importance and maritime routes to South Asia providing alternates to transit via Sīstan). The relative importance of the various components of the Islamic east was also greatly affected by the opening of the 'Great Highway' to Khurasan via Rayy and Nishapur. Up until the time of Qutayba ibn Muslim, as al Ṭabarī notes in a particularly revealing incidental remark,⁵⁸ the most common route to Khurasan was from the south, from Baṣra and Ṣuḥar to Shīraz, Zaranj, Herat and Balkh – the route followed by the Baṣran invasion. The Kufans, moving along the northern rim of the desert basin, could advance no further than Jurjan, and failed to establish firm control even there. Qutayba managed to subdue the area around Qumis, probably by freeing it from Hepthalite marauders, and thereafter the northern route eclipsed the southern route. Naturally, the tendency was for the areas along the older southern route to become more isolated and to decline in importance, while those along the northern route increased in importance. Moreover, since there was generally no interior threat to the new line of communication between the metropolitan centre and its most important eastern province, there was little reason for either the government or historians to concern themselves much with the affairs of such areas. Were it not for the chance survival of sources such as the *Tarīkh i Sīstan*, the history of the southern areas in the early Islamic period would be very obscure indeed. Finally, the pacification of Jurjan opened up a venue for a new effort of expansion into the coastal plains south of the Caspian.

Taking all this into account, it is possible to suggest a framework for discussing the regional history of the Islamic east based not on individual provinces but three rather distinct areas: Khurasan and Transoxania, which are of the greatest importance and about which we are best informed; the secondary frontier areas, primarily Sīstan and Ṭabaristan, about which we are relatively well informed due to the survival of local histories dedicated to them; and the interior areas, including virtually all of western Iran, Fars, and Kirman, about which we know the least.⁵⁹ The last of these will not be treated in any detail here, partly because of the relative lack of information but also because its history is so closely tied to that of the successor states in Iraq.⁶⁰

58 Al Ṭabarī, *Ta'rikh*, series I, p. 2839.

59 There is a very comprehensive and authoritative survey of the available information about the numerous petty dynasties that flourished in this area in Madelung, 'Minor dynasties'.

60 See Michael Bonner, 'The waning of the empire, 861–945' and Hugh Kennedy, 'The late 'Abbasid pattern, 945–1050', chapters 8 and 9 in this volume.

Khurasan and Transoxania

As Khurasan became the most important component of the Islamic east, it also became the most politically volatile. Each change of governorship, each new infusion of troops, each change in fiscal and administrative policy carried the potential to touch off conflict among factions within the local elite or between the local elite and the central authorities. The severity of these disturbances tended to escalate whenever the momentum of the wars of expansion declined. The sources and many modern accounts generally depict them as conflicts between Arab tribal blocs (perhaps with links to geographic centres in Basra, Kufa and Syria), but tribal identity is neither an infallible guide to individual allegiances in the disputes nor a particularly informative indication of their motivation. In early cases, the disturbances may have been little more than quarrels over the division of political and economic spoils, but they soon came to represent much more than that. In the revolt of al Ḥarith ibn Surayj (beginning in 116/734), for example, questions of religion and ideology are apparent in his ties to the Murji'a, as are the issues of relations between the Arabs and the native and non Muslim population, and between both of them and the central government. These issues culminated in the great upheaval known as the 'Abbasid revolution.

The 'Abbasid revolution was clearly a pivotal event for both the Islamic east and the Islamic empire as a whole, but what is of key interest here is the regional dimension of this revolt and its consequences.⁶¹ The impression given in most of the traditional sources is of an externally organised and centrally directed movement, covert and conspiratorial in nature, which had as its secret goal the installation of a member of the 'Abbasid family as caliph. For over twenty five years this organisation conducted a campaign of propaganda and manipulation to undermine the Umayyad regime in Khurasan, and in 129/746f., under the leadership of a formerly obscure agent called Abu Muslim al Khurasanī, it launched an open revolt there that swept away Umayyad power, not only in Khurasan but the metropolitan centres of power as well. Unfortunately, few of the details of this story can be taken at face value, and many defy credibility. There is not much reason to doubt that the movement was conspiratorial in nature, but the notion that it was consistently run by an outside organisation working for the 'Abbasid family can be regarded as mostly a myth concocted by propagandists after the dynasty came to

61 For more details on these events and their background, see Tayeb El Hibri, 'The empire in Iraq', 763–861, chapter 7 in this volume.

power.⁶² Even the date at which the movement committed itself to the 'Abbasids is uncertain; the slogans on the earliest revolutionary coins could easily be interpreted as pro 'Alid, and some were actually minted in the name of 'Abd Allah ibn Mu'awiya.⁶³ The received tradition is quite obviously the result of much reworking and rewriting to accord with various political agendas, and it is anything but clear what the real nature and mechanics of the movement were. At least at the regional level, however, the vague slogans said to have been used by the revolutionary propagandists seem to suggest that the movement had two general goals: (1) to provide a thoroughly Islamised framework of government; and (2) to redefine the nature of the relationship between the local Arabo Persian Muslim elite and the caliphal authorities.

The implication of the first objective was that the mixed Muslim and non Muslim administrative structure of the conquest and early Umayyad period would be replaced by an exclusively Muslim one, but on the basis of an Islam that welcomed conversion and was open to all ethnicities equally. Controversies over these issues had been simmering for some time, and it seems highly probable that a crisis was precipitated by the policies of the governor Naṣr ibn Sayyar, such as switching the language of administration from Persian to Arabic, removing *dihqans* as tax agents, and bringing in more Syrian troops. These policies may well have been unwisely imposed on him by the central authorities against his own better judgement, but in any case they could hardly have been seen as anything other than an effort to Arabise the governing regime in the Islamic east. It was in reaction to this that the 'Abbasid movement was able to construct a popular coalition of anti Umayyad forces that cut across tribal loyalties and in which distinctions between Arab and non Arab became largely irrelevant. As long as non Arabs had converted, there would be no barrier to their participation in the governing elite, but the system by which a non Muslim such as Nizak could serve as a vassal lord or an unconverted *dihqan* could act as a tax agent would be dismantled. This principle was exemplified above all in the person of Abu Muslim al Khurasanī, who emerged as the leader of the overt revolution in Khurasan. As often noted, his very name (actually a deliberately chosen *nom de guerre*) proclaimed the fusion of religious and local identity. He is said to have made sure that those Iranians joining the revolutionary army were Muslims, but by the same token he insisted that those Iranian Muslims who did join should be welcomed

62. See especially Agha, *The revolution which toppled the Umayyads*.

63. See the very useful Miles, 'Numismatics', p. 369.

and treated well;⁶⁴ one of his first acts after seizing power was to establish a new army register which abolished the distinction between Arab and non Arab forces.

The second objective, the forging of a new centre periphery balance of power, is perhaps less obvious and more controversial to assert; indeed, it is likely that at least some of the factions involved in the revolution would not have agreed with it. It can be argued, however, that this message was implied in the call for rule by a chosen one from the family of the Prophet (*al riḍa min al Muḥammad*),⁶⁵ which was widely cited as a slogan of the revolutionaries. It was an invitation to replace the impious, despotic and increasingly intrusive rule of the worldly Umayyads with that of a charismatic holy man, chosen from the family of the Prophet in accordance with the will of the believers (or rather the elite leadership of the believers), who would give legitimacy to a system of government but would himself be uninvolved in secular affairs beyond perhaps mediating disputes between the regional components of the Islamic commonwealth. That there was to be some sort of deliberative and consensual process in the recognition of *al riḍa* is suggested by the substantial delay between the victory of the revolutionary army and the decision to install Abu al 'Abbas al Saffāḥ as caliph. The desire for the separation and recalibration of the powers of the caliph and the local authorities is best attested by the actual results of the revolution, namely the attempt to create a system in which there was an unrestrained exercise of independent authority conducted by Abu Salama al Khallal as *wazīr al Muḥammad* in the west and Abu Muslim al Khurasanī as *amīn* (or *amīr*) *al Muḥammad* in the Islamic east. That this was a strategic objective, and not just a temporary tactical necessity, is confirmed by the tenacious efforts Abu Muslim made to preserve his prerogatives as the leader of the Islamic east against caliphal demands. Indeed, so successful was he that the later 'Abbasid propaganda designed to demean his stature and minimise his importance could not succeed in effacing the memory of his all important role in the revolution and the foundation of the new regime.

From the regional perspective, however, and with this aspect in mind, the 'Abbasid revolution in fact turned out to be a *revolution manqué* that achieved at best only part of its agenda. The will of the believers may have played some role in the appointment of al Saffāḥ as caliph (though no doubt a good many of

64 *Akhbar al dawla al 'Abbasiyya wa fihi akhbar al 'Abbas wa wuldihi*, ed. 'Abd al 'Azīz al Durī and 'Abd al Jabbar al Muṭṭalibī (Beirut, 1971) (hereafter *Akhbar al 'Abbas*), p. 280.

65 On a possible interpretation of this slogan, see Patricia Crone, 'On the meaning of the 'Abbasid call to al Riḍa, in C. E. Bosworth *et al.* (eds.), *The Islamic world: Essays in honor of Bernard Lewis* (Princeton, 1989).

the revolutionaries were surprised to find that an 'Abbasid had been selected rather than a descendant of Muḥammad), but none at all in that of his successor, Abu Ja'far al Maṣṣur. Al Maṣṣur was not only the most forceful and overbearing personality in the 'Abbasid family, he was if anything even more absolutist in his conception of the caliphate than the Umayyads had been. He was clearly the leader of a reactionary faction perfectly willing to co opt elements of the former regime and to suppress the interests of those who had put him in power, and he was busily engaged in intrigues against the revolutionary agenda even before assuming office himself. Although it is true that a good many of the Khurasanīs, such as the Abna' expatriates who came to reside in Iraq or various social classes such as merchants who had a vested interest in a strong centralised administration to provide security and freedom of movement for trade, became firm supporters of al Maṣṣur and 'Abbasid rule, the sympathies of the Khurasanī population in general towards the 'Abbasids proved highly ambivalent. Indeed, there are many hints in the sources that a significant segment of the Khurasanī elite preferred another member of the 'Abbasid family, 'Isa ibn Musa, to al Maṣṣur and to his successors al Maḥdī and al Hadī, and that pro 'Alid sympathies were very strong among the general population.

In the case of the Islamic east, the most important and immediate aspect of al Maṣṣur's plans was the elimination of Abu Muslim. The sources are full of reports about the cat and mouse game that developed between the powerful king maker and his erstwhile 'Abbasid masters: an apparent attempt to implicate Abu Muslim in the murder of Abu Salama; Abu Muslim's interference with Abu Ja'far's efforts to secure a pardon for the Umayyad governor Ibn Hubayra; Abu Ja'far's resentment at Abu Muslim's perceived slights of him; efforts to stir up revolts against Abu Muslim in various parts of the Islamic east; and Abu Muslim's rejection of 'Abbasid attempts to assert suzerainty over him in matters pertaining to provincial administration and control of the army. In one particularly telling example, Abu Muslim's governor in Fars would not accept even the caliph's uncle as governor without a patent from Abu Muslim.⁶⁶ Finally though, Abu Muslim, perhaps overconfident of his position, was lured away from his power base in Khurasan and treacherously murdered in 137/755. With good reason, al Maṣṣur reckoned that day as the true beginning of his rule as caliph.

After Abu Muslim's death al Maṣṣur was able to move to affirm 'Abbasid control over the Islamic east, but with decidedly mixed results. In 140/757f. the

⁶⁶ Al Ṭabarī, *Ta'rīkh*, series III, pp. 71 2.

deputy Abu Muslim had left in Khurasan, Abu Dawud Khalid ibn Ibrahim, died – or, more likely, was murdered. This enabled the ‘Abbasids, for the first time, to make a direct appointment of a governor for the province. Al Manṣur’s choice for the job was ‘Abd al Jabbar ibn ‘Abd al Raḥman al Azdī, formerly the chief of his security forces. It is fairly clear from the sources that ‘Abd al Jabbar was given a mandate to root out any elements in Khurasan suspected of loyalty to the cause of Abu Muslim or the ‘Alids, but accounts of how he carried out his instructions differ wildly. According to some he was so overzealous in imposing new taxes and killing and arresting members of the local elite that he threatened to provoke an all out revolt and had to be recalled, at which point he himself decided to revolt. In others he is depicted as being secretly in league with anti ‘Abbasid elements in Khurasan before openly proclaiming his own revolt. In either case, it is obvious that caliphal authority in the Islamic east was not yet fully established. To suppress the revolt al Manṣur had to send out a substantial army under the nominal command of his son and heir, Muḥammad al Mahdī. ‘Abd al Jabbar was captured and executed no later than 143/761.⁶⁷

Among the string of ‘Abbasid governors who followed ‘Abd al Jabbar, the sources tend to distinguish between those who worked with the local elite and in the local interest, the exemplar among them being al Faḍl ibn Yahya al Barmakī (governor 178 9/794 5), and those who excessively taxed, oppressed, exploited and manipulated the population. Of the latter, the worst and most unpopular by far was the notorious ‘Alī ibn ‘Isa ibn Mahan, who was appointed in 180/796. By 189/804f. so many protests and revolts had broken out that the caliph Harun al Rashīd investigated his conduct; but instead of removing him, Harun confirmed him in office (largely because of the lavish bribes offered up by ‘Alī ibn ‘Isa). That touched off such a serious and massive revolt throughout the Islamic east – nominally under the banner of Rafī‘ ibn al Layth, an army officer in Samarqand (and reputed grandson of Naṣr ibn Sayyar), but one in which many different dissident groups joined – that Harun was finally obliged to dismiss and arrest ‘Alī ibn ‘Isa in 191/806 and come to Khurasan in person to try to restore order. To do so he not only had to correct the abusive policies of ‘Alī ibn ‘Isa, he had to rely on the support of key elements of the local elite, notably Ṭahir ibn al Ḥusayn, the chief landlord and de facto local ruler of Bushanj, to buttress the army he had brought with him under the command of Harthama ibn A‘yan. While engaged in this

⁶⁷ See E. Daniel, *The political and social history of Khurasan under Abbasid rule 747–820* (Minneapolis and Chicago, 1979), pp. 159–62.

campaign, Harun died at Ṭus in 193/808. Under the terms of the succession arrangement he had made in 186/802, one son, al Amīn, was to become caliph in Baghdad while another, al Ma'mun, would essentially become an autonomous vicegerent in the Islamic east.

Al Ma'mun, guided by the advice of his minister al Faḍl ibn Sahl (a recent convert and protégé of the Barmakids), managed to associate himself very closely with the local political, military and religious elites and their interests; in particular, he reversed the oppressive fiscal policies that 'Alī ibn 'Isa had followed and pledged to act in accordance with the principles of religious law. He behaved much as Abu Muslim had done in asserting his power on a regional basis and resisting any effort by the caliph and central government to interfere with it, and he was reportedly lionised by the local population, especially the *dihqans*, for his judicious conduct. When al Amīn challenged al Ma'mun's autonomy and attempted to reinstall the hated 'Alī ibn 'Isa as governor of the province, civil war was the inevitable result. The troops brought to the Islamic east by Harun al Rashīd and commanded by Harthama were conspicuous by their absence, apparently desiring to remain neutral in the initial phase of this conflict. Instead, al Ma'mun relied on a military force led by Ṭahir ibn al Ḥusayn and composed mainly of *dihqans* and their followers from Khurasan and especially Transoxania. Ṭahir routed the army of al Amīn at a great battle near Rayy in 195/811, in the course of which 'Alī ibn 'Isa was killed. Al Ma'mun was then proclaimed caliph in Khurasan, and al Faḍl ibn Sahl became governor of the whole of the Islamic east, with a huge salary and military and administrative authority from Hamadhan to the borders of China and from the Caspian Sea to the Persian Gulf.⁶⁸ Ṭahir, now joined by the regular forces (commanded by Harthama ibn A'yan and Zuhayr ibn al Musayyab), commenced a siege of Baghdad in 196/812. When it became clear that the city would fall, al Amīn attempted to surrender to Harthama, but was captured and murdered by troops loyal to Ṭahir in 198/813. Al Ma'mun then ruled from Marw as sole caliph and sent al Ḥasan ibn Sahl, brother of al Faḍl, to be governor of Baghdad and the central provinces.

The civil war thus did not end simply with a restoration of provincial autonomy: in effect, the Islamic east had suddenly become the locus of power and the former metropolitan centre its dependency – it is thus not surprising that it is just at this time that coins bearing the term *al mashriq* appeared. This generated its own set of problems, including continued resistance by supporters of the old regime in Baghdad, 'Alid revolts in Iraq and the

68 Al Ṭabarī, *Ta'rikh*, series III, p. 841.

fear of moderates in al Ma'mun's camp (notably Harthama) that events were getting out of hand. At first al Ma'mun appeared to be supporting the more radical aspects of Sahlid policy. Harthama was executed in 200/816, and in 201/816 al Ma'mun appointed an 'Alid, 'Alī ibn Musa al Riḍa, as his heir. This essentially revived the civil war and led to the declaration of a counter caliphate under Ibrahīm ibn al Mahdī in the west. In the face of these difficulties, al Ma'mun, supposedly with reluctance, left Marw in 202/818 to return to Baghdad. With so many issues occupying him there, from war with the Byzantines to theological disputes to local revolts, he entrusted the governorship of all the Islamic east to Ṭahir in 205/820. Ṭahir and his descendants would continue to rule the region on a hereditary and, for all practical purposes, autonomous basis down to 259/872.

Although it is fairly clear that the issue of central authority and regional autonomy was at the heart of these events, there are many difficulties in understanding exactly how this played itself out. Among them is the question of whether al Ma'mun was really the reluctant caliph and champion of the forces of regionalism he might appear to be from traditional accounts. If his actual goal was to preserve and enhance his position after al Amīn became caliph, he had no realistic alternative to cultivating the regional elites, and his actions can be interpreted as merely tactical moves towards that end. His appointment of 'Alī al Riḍa as heir, for example, served to shock his dynastic opponents in Baghdad and to blunt the appeal of pro 'Alid sentiments not only in Iraq but in the Islamic east as well. His return to Baghdad may have been much less forced by circumstances and reluctantly undertaken than is claimed; he certainly used the opportunity to shed past commitments by dispensing with both al Faḍl ibn Sahl and the need for an 'Alid heir. Exactly how and why he appointed Ṭahir as governor is even more obscure, and there is reason to think al Ma'mun was not happy with the arrangement; as will be discussed below, there are indications that the two were on a collision course averted only by Ṭahir's untimely, and rather suspicious, death in 207/822. All in all, however, an effective compromise had been struck through which regional elites could act without interference in return for nominal allegiance to the caliphs and cooperation with them when it was in their mutual interest, thus effectively achieving what appears to have been the abortive goal of the earlier 'Abbasid revolution. This was the political pattern that would hold thereafter.

The intra elite dispute over the balance of central and regional authority was by no means the only manifestation of turbulence in the post revolutionary Islamic east. Khurasan and much of the larger region were affected for several decades by a sequence of movements variously depicted as

heterodox, chiliastic and insurrectionary or revolutionary.⁶⁹ They are usually described as led by heresiarchs, charismatic figures teaching syncretistic religious doctrines who sometimes claimed to be prophets and employed various tricks to dupe the simple minded into following them. The sources often attribute low social origin to these heresiarchs, but on closer inspection they rather appear to have been wealthy and powerful local magnates. Most of the movements and revolts are said to have shared a common ideology of radical social egalitarianism (even wearing garments of the same colour) and thus to be directly related to each other in some way; several also supposedly connected themselves with the legacy of Abu Muslim and claimed to be avenging his murder (they are thus often referred to as the sects of the Khurramiyya, Abu Muslimiyya, Muḥammira, Mubayyiḍa, etc.). One, Bihafarīd, however, appeared in the rural districts of Nīshapur while Abu Muslim was establishing his administration at that city and was ruthlessly suppressed by him. In 138/755f. a certain Sunbadh the Magian declared a revolt to avenge the murder of Abu Muslim, and seized the treasury at Rayy to finance it before finally being defeated somewhere in the mountains of Ṭabaristan. Somewhat paradoxically, he is also said to have believed that Abu Muslim was not dead but in concealment with Mazdak and the *mahdī*, awaiting their messianic return. He supposedly called, among other things, for the slaughter of the nobles and aristocrats, for the overthrow of the empire of the Arabs, and for the restoration of a religion based on a form of sun worship. Whether he actually propounded any or all of these ideas is open to question; they may simply have been attributed to him in order to legitimise the suppression of the insurgency. Another large uprising, around 148/765, was led by Ustadhsīs and concentrated in the area around Badhghīs. Ustadhsīs reportedly cooperated with a contemporary Kharijite uprising (and is some times described as a Kharijite himself) but is also said to have taught his own doctrines based on the ideas of Bihafarīd (i.e. combining aspects of Islam and Zoroastrianism). His army, however, appears to have been composed primarily of peasants armed with hoes, shovels and axes. The revolt was brutally suppressed by the 'Abbasid general Khazim ibn Khuzayma, who is said to have slaughtered tens of thousands of the rebels. The sources disagree on the fate of Ustadhsīs himself; some suggest that he was taken captive at his mountain fortress and presumably executed, while others indicate that he

69 On these revolts, see G. H. Sadighi, *Les mouvements religieux iraniens* (Paris, 1938); B. S. Amoretti, 'Sects and heresies', in Frye (ed.), *The Cambridge history of Iran*, vol. IV; Daniel, *Khurasan*, pp. 125–47; R. N. Frye, *The golden age of Persia* (New York, 1963), pp. 126–49.

received a pardon, probably because he had earlier played a role in supporting the 'Abbasid revolution. (There are even claims that Marajil, the concubine of Harun al Rashīd and mother of the caliph al Ma'mun, was his daughter.⁷⁰) Yet another spectacular revolt around 159 63/776 80 was led by the so called 'veiled prophet of Khurasan', al Muqanna'. He and his followers, the 'wearers of white' (*mubayyiḍa* or *safid jamagan*), apparently controlled the whole of the Kashka Darya valley from their strongholds at Nasaf and Kish, and at times threatened Bukhara itself; they were also strong in areas around Samarqand and the upper Zarafshan valley. Muqanna' himself had a fortress near a place called Sanam (described as a lavish, almost paradisaal, enclosure reminiscent of those later attributed to the Assassins); he supposedly claimed to be not just a prophet but a god, taught a form of Mazdakism, and used tricks such as causing a false moon to rise from a well or using mirrors to focus sunlight on his person in order to overawe his sectarians. When it was clear that his fortress would fall, he, along with his wives and followers, committed suicide to avoid capture. A similar sectarian ideology is also attributed to the great insurrection led by Babak in Azerbaijan (201 22/816 37). These are by no means the only such movements and revolts, but simply the best known.

How should this phenomenon be interpreted? The source material is badly deficient since we have no documents from the movements themselves, only from writers who are generally hostile to them, and modern opinions about the nature of the movements – religious, political or social – vary greatly. Two basic features of these revolts, though, appear certain and must be taken into account: they occurred in a very discrete time period, the half century or so after the 'Abbasid revolution, and only in parts of the Islamic east (mostly in peripheral, rural areas). This makes it very difficult to accept the notion, as dear as it was to later polemicists such as Nizām al Mulk, that the revolts were the continuation – in thinly disguised form – of the Mazdakite and Manichaean traditions of earlier times as well as the precursors of subsequent Ismā'īlī heterodox movements. The idea, popular with nineteenth century European racial historians and twentieth century Iranian chauvinists, that they were part of some more generalised 'national' or 'anti Arab' insurgency can also safely be discarded. They would rather seem to be connected in some way with specific changes brought about by the 'Abbasid revolution and by the regional characteristics of the Islamic east.

If one emphasises the religious syncretism apparent in the revolts they might be explained as the product of the accelerating process of conversion to

70 Abu Sa'īd Gardīzī, *Zayn al akhbar*, ed. 'A. Ḥ. Ḥabībī (Tehran, 1347/1969), p. 125.

Islam brought about by the 'Abbasid revolution in the especially mixed religious environment of Khurasan and Transoxania. It is also possible that they grew out of popular disenchantment with the political and social results of the 'Abbasid revolution, crystallised and epitomised above all by the murder of Abu Muslim. Most revolutions attract coalitions of actors, some more radical than others, united only by their antipathy to the status quo; once the revolution succeeds these components clash, and the weakest are eliminated. In this regard, there are many indications that the 'Abbasid revolution stirred up the messianic and utopian dreams of the masses, especially the desire of the peasantry for social justice and an end to economic exploitation as well as the hopes of indigenous people to live free from outside interference. These sentiments and groups were not ones with which all the revolutionary leadership was comfortable, and efforts were made to suppress them even in the time of Abu Muslim; naturally, the early 'Abbasid caliphs tolerated them even less. A variation of this interpretation would place greater emphasis on the social aspects of the heterodox revolts: they may not have been literally and directly connected to earlier religious movements or to each other, but they did share an aversion to the imposition of a religious system favoured by the state and urban elites and the social injustices that went along with it. In this view, many of the religious doctrines attributed to these movements and the stories about their leaders may have been little more than myths, distortions and *topoi* used to discredit and justify suppressing the remaining autonomous peasant communities of the region. (For example, the allegations about al Muqanna's claim to divinity take on a different cast when one remembers that documents from Mount Mugh only a few decades earlier regularly referred to local rulers in that same region as 'god kings'.⁷¹)

Yet another interpretation, which has become popular in recent years, essentially sees all of these revolts as a last, desperate, and rather cynical effort by the vestiges of the pre Islamic aristocracy in certain sub regions to hold on to an autonomous position of privilege by deliberately manipulating and exploiting the religious sensibilities, superstitions and class hatreds of the masses.⁷² It should be noted, however, that some of these movements do seem to have been genuinely popular in character and to have achieved a

⁷¹ See R. N. Frye, 'Tarxun Türxün and Central Asian history', *Harvard Journal of Asiatic Studies*, 14 (1951), p. 127.

⁷² See, for example, Fuzuko Amabe, 'The lords of Khurasan and Ma wa'r'an Nahr', in Fuzuko Amabe, *The emergence of the 'Abbasid autocracy: The 'Abbasid army, Khurasan and Adharbayjan* (Kyoto, 1995), pp. 87–104; the same general approach has been applied to other revolts such as those of Babak and Mazyar (see below).

remarkable degree of communal solidarity. Women, peasants, tribesmen, and perhaps merchants and artisans as well, all appear to have joined in what could be regarded as a coherent guerrilla insurgency led by al Muqanna'.⁷³

Whatever particular interpretation one follows, it is difficult to escape the conclusion that these movements represented some kind of response to the imposition of a greater degree of political, economic and/or doctrinal control over the whole of the Islamic east in the aftermath of the 'Abbasid revolution. As the frontier stabilised and the expansion that characterised earlier periods came to an end, the focus of both the caliphal authorities and the local elites turned to internal expansion, i.e. tightening up their hold on previously isolated or neglected areas within the borders of the Islamic east, and the potential for conflict increased. All of the revolts just mentioned reflected a reaction to this intrusion; their suppression coincided with the destruction and subjection of the autonomous communities that had supported them.

The Caspian

As noted earlier, the Caspian region, shielded to the west and south by a formidable mountain barrier, was hardly touched by the early Arab conquests. Indeed, the Arab destruction of the Sasanian monarchy gave the local magnates an expanded opportunity to assert their authority. There is much confusion in the sources about the names, titles and relative positions in the hierarchy of these nobles. At the beginning of the Islamic era a dynasty of military governors (*iṣbahbadhs*) known as the Dabuyids claimed rule over everything from Jīlan in the west to Nishapur in the east, the contemporary ruler being a son of Dabuya named Farrukhan.⁷⁴ Rulers of this line are known to have minted their own coinage at least as early as 93/711 (year 60 in the Yazdegerdī era used by the coins), and they seem to have made a rather conscious effort to keep alive Zoroastrian and Iranian traditions and to isolate their subjects from contact with Arabs and Muslims. The control of the Dabuyids over Jīlan and Daylam was more nominal than real, and they also recognised as subordinate vassals various relatives and de facto local rulers of the mountainous areas of Ṭabaristan, of whom the most important were Bawandids and the Qarinids. The ruler of Damawand, the *mašmughan*, maintained his own independence and was in some ways a rival to the *iṣbahbadhs*. The main focus of the Arab efforts at conquest was a struggle with the Dabuyids for control of the coastal plain. None of the early

⁷³ See the perceptive comments of Amoretti, 'Sects and heresies', p. 502.

⁷⁴ Al Ṭabarī, *Ta'rikh*, series I, pp. 2659–60. There was apparently a later Dabuyid by the same name, who ruled 93–110/711–28; see W. Madelung, 'Dabuyids', *Elr*, vol. VI, pp. 541–4.

Arab raids made much progress, and even the major attempt at conquest launched in 98/716 by Yazīd ibn al Muhallab ultimately failed, although it did exact a new agreement to pay tribute.⁷⁵ Following the 'Abbasid revolution, Abu Muslim sought and received a pledge of allegiance from the *iṣbahbadh* Khurshīd.⁷⁶ After al Manṣūr had Abu Muslim murdered, Khurshīd seems to have thrown his support to Sunbadh, leader of the revolt in 137/754f. to avenge Abu Muslim and perhaps to bring about a restoration of Zoroastrianism (neither Sunbadh nor the Dabuyids had converted). One of his relatives, however, betrayed and murdered Sunbadh, supposedly because of a personal offence but perhaps also as part of an internal dynastic rivalry exploited by the 'Abbasids.⁷⁷

Khurshīd managed to remain in power by paying lavish tribute to al Manṣūr. Nonetheless, the accusation of support for Sunbadh, coupled with al Manṣūr's avarice and absolutist tendencies, sealed his fate. According to Ibn Isfandiyyar, Āmul was taken over as the 'Abbasid capital in 140/757f. and numerous small garrisons were established throughout the lowlands.⁷⁸ In 141/759 the caliph launched a major new invasion of Ṭabaristan. The *iṣbahbadh* and *maṣmughan*, warring with each other at the time, set aside their differences to resist the mutual threat, but they were worn down in what al Ṭabarī describes as a relentless war.⁷⁹ Judging from Ibn Isfandiyyar's account, the 'Abbasid offensive enjoyed two advantages over earlier efforts to subdue the region. First, the campaign was advised by 'Umar ibn al 'Ala', a man who had gained intimate knowledge of the area during a period when he lived as a political refugee under the protection of the *iṣbahbadh* (and who was appointed at the recommendation of Abarwīz, brother or son of the *maṣmughan*). Second, the *iṣbahbadh* had lost the support of much of the civilian population in the plains; thus, the people of Āmul are said to have tired of the *iṣbahbadh* and to have welcomed the opportunity to surrender and to convert to Islam after 'Umar ibn al 'Ala' had established a just administration there. The *iṣbahbadh* finally fled to Daylam, but after his family was captured he despaired and committed suicide in 144/761. The *maṣmughan* was also captured, and his principality collapsed into a state of anarchy.⁸⁰

75 Baladhurī, *Futuḥ*, p. 338.

76 *Akḥbar al 'Abbas*, p. 333, 'Izz al Dīn 'Alī ibn Aḥmad ibn al Athīr, *al Kamil fi 'l ta'rīkh*, 13 vols. (Beirut, 1965–7), vol. V, p. 397.

77 Al Manṣūr clearly exploited such rivalries to gain control over the area: not only did he try to supplant Khurshīd by recognising his brother(?) Wandaḍ as *iṣbahbadh*, he managed to win over one of the sons of the *maṣmughan* (al Ṭabarī, *Ta'rīkh*, series III, p. 131) who had quarrelled with his brother.

78 Ibn Isfandiyyar, *Tarīkh i Ṭabaristan*, ed. 'Abbas Iqbal (Tehran, 1944), pp. 175ff.

79 Al Ṭabarī, *Ta'rīkh*, series III, pp. 136–7.

80 *Ibid.*, p. 137.

Although the coastal plains of Ṭabaristan thus became integrated into the caliphal system of provinces, 'Abbasid authority over the rugged interior remained minimal; both Bawandids and Qarinids, along with lesser families, continued to hold power there. They were willing to make token obeisance to the 'Abbasids, but they firmly resisted any real encroachment (destroying, for example, the towns Khalid ibn Barmak had attempted to found in their territory). When people in the area under caliphal control tired of the onerous new tax regime they turned to the Qarinid ruler, Wandad Hurmuzd, for support. After rallying the other local princes Wandad Hurmuzd led an uprising around 165/781, beginning, according to Ibn Isfandiyyar, with a general massacre of the Arabs in Ṭabaristan. He repeatedly defeated the forces sent against him until, in 169/785, he was persuaded by Musa ibn al Maḥdī (the future caliph al Ḥadī and nominal leader of the 'Abbasid campaign) to surrender in return for a pardon. He was detained briefly in Baghdad but soon returned to resume his position in Ṭabaristan. In 189/805, after the murder of an 'Abbasid tax official, Harun al Rashīd obtained a more formal treaty arrangement with Wandad Hurmuzd and the vassal princes, spelling out the requirement for them to pay tribute and provide auxiliary troops to the caliph but recognising their autonomy in the highlands.

Both Wandad Hurmuzd and his Bawandid counterpart, Sharwīn, died during the reign of the caliph al Ma'mun (apparently at its outset, c. 198/813), and were succeeded by their sons, Qarin and Shahriyar. Qarin was a much less capable ruler than Wandad Hurmuzd had been, and the Bawandid Shahriyar became more and more powerful. After Qarin's death Shahriyar defeated his son and successor, Mazyar, and seized his lands. Mazyar was somehow able to make his way to al Ma'mun and win his assistance: the colourful account in Ibn Isfandiyyar claims he was imprisoned by his uncle, Wanda Umīd, but managed to escape, while al Ṭabarī suggests that the 'Abbasids had taken advantage of the internecine conflict to expand their presence in Ṭabaristan and took Mazyar as a captive or hostage in 201/816f.⁸¹ In any case, al Ma'mun decided to support Mazyar, but on condition he convert to Islam and become the caliph's *mawla* – something that had long been an objective of the caliphs but never accepted by the earlier local rulers. The caliph's motivation in this is not clear: Ibn Isfandiyyar attributes it in part to his appreciation of Mazyar's valour during a campaign against the Byzantines. However, he also saw an opportunity to use him to displace the new and unpopular Bawandid ruler, Shapur ibn Shahriyar, and he almost certainly saw

81 Ibn Isfandiyyar, *Ṭarīkh i Ṭabaristan*, pp. 206–7; al Ṭabarī, *Ta'rikh*, series III, p. 1015.

Mazyar as a valuable counterweight to the growing power of the Ṭahirids in Khurasan. Back in Ṭabaristan by 207/822f., technically as a co governor on behalf of the ‘Abbasids, he supposedly soon began acting in the same imperious manner as the earlier *iṣbahbadhs*. At least on the face of it, judging from sources that are universally hostile to him, Mazyar managed to alienate all the major groups of society. He carried out a purge of his former enemies and rivals, killing Wanda Umīd and Shapur, and the lesser nobility resented his increasing power and favour with the caliph. He outraged the urban Muslim elite, apparently by trying to impose taxes on them and restricting their efforts to gain control of agricultural lands, and they, led by the *qaḍī* of Āmul, reciprocated by accusing him of apostasy and collaboration with Babak and the Khurramdīn heretics of Azerbaijan. He also offended the Ṭahirids, who were trying to extend their influence over Ṭabaristan, by refusing to submit taxes to the caliph via their officials (which would have implied subordination to them) and by becoming embroiled in a plot with al Afshīn (a general, himself of Central Asian origin, who had commanded the forces of al Mu‘taṣim against Babak) to overthrow ‘Abd Allah ibn Ṭahir.

Mazyar’s relations with the peasantry are more ambiguous: on the one hand, he seems to have required them to provide corvée labour to construct forts and guard houses; yet he is also said to have encouraged them to carry out a jacquerie in which a number of landlords (presumably the new Muslim landlords, not the native nobility) were slaughtered. He supposedly deceived the caliph and resisted orders to appear at court by claiming he was engaged in warfare against Daylamites and ‘Alid pretenders. Some of these allegations are less than convincing. Mazyar certainly had enemies and rivals among the native elite, but others, including some very capable generals, remained loyal to him. Moreover, despite the numerous complaints and the reports of his own spies, al Ma’mun continued to support Mazyar, and even recognised him as sole governor. Indeed, al Ma’mun addressed Mazyar with the same grand titulature used by the ancient Dabuyid rulers: Jīl Jīlan, Iṣbahbadh i Iṣbahbadhan, Bishwar Jirshah (or Khurshah), and perhaps even Iṣbahbadh i Khurasan.⁸² Rather revealingly, Mazyar is said to have referred to himself not as the client (*mawla*) but as the ally (*muwalī*) of the caliph. It may well be that in tightening up the government, taxing the urban classes and challenging the Ṭahirids, Mazyar and the caliph were willing partners. It was not

82 Aḥmad ibn Abī Ya‘qub al Ya‘qubī, *Kitab al buldan*, ed. M. J. de Goeje (Leiden, 1892), p. 276; Aḥmad ibn Abī Ya‘qub al Ya‘qubī, *Ta’rīkh*, ed. M. Houtsma as *Ibn Wadhih qui dicitur al Ja‘qubī historiae*, 2 vols. (Leiden, 1883), vol. II, p. 582; al Ṭabarī, *Ta’rīkh*, series III, p. 1298.

until 224/838f. that ‘Abd Allah ibn Ṭahir succeeded in turning al Mu‘taṣim against Mazyar, provoking the latter to declare an open revolt and to cut off all payment of taxes. The forces arrayed against Mazyar were formidable, but he was ultimately defeated by exploitation of petty dynastic rivalries: his own brother Quhyar seized him and turned him over to the Ṭahirid general al Ḥasan ibn al Ḥusayn in the hope of assuming his position. Mazyar was sent to Samarra’, put on trial, and executed in 225/840. About the same time Quhyar was murdered by members of Mazyar’s former bodyguard, and the Qarinid dynasty effectively came to an end, although people said to be Qarinids continued to appear in minor positions of power for quite some time.

Despite its brevity, Mazyar’s revolt is by far the most extensively discussed of these events in the sources, and was certainly a key moment in the regional history of the Caspian component of the Islamic east. Its political, social and cultural implications have been much debated by modern historians, and those debates reflect some important questions in terms of the phenomenon of regionalism in the Islamic east that have already been noted in connection with the heterodox revolts in Khurasan and Transoxania. Thus, some older scholarship tended to see the revolt of Mazyar, like others, as a manifestation of ‘national’ anti Arab or anti Islamic sentiments; more recent studies see him as little more than a political opportunist who used whatever means were at hand to preserve his personal position.⁸³ Both views are probably exaggerated. Mazyar certainly did not hesitate to use conversion and caliphal support to hold on to his claim to authority, but in terms of regional dynamics he was also making a last ditch stand against the spread of a Muslim and commercial urbanism in the lowlands that was bringing agricultural land and the peasantry under the domination of urban elites and thereby disrupting the traditional social and economic structure of the region. He may not have been a neo Mazdakite in the way he is presented in some sources, but there is little reason to doubt that he used the Mazdakite technique of pitting peasants against rival aristocrats in his struggle. The irony is that the final collapse of the nativist resistance to the spread of Islamic urbanism and its political economy worked not to the benefit of a centralising caliphate but to another regional power, the Ṭahirids of Khurasan, who now acquired hegemony over the area.

The Bawandid Qarin ibn Shahriyar survived this last upheaval by throwing in his lot with the Ṭahirids and at last converting to Islam. This can be explained not only by political expediency but by the appearance of a new

83 See M. Rekaya, ‘Mazyar: Résistance ou intégration d’une province iranienne au monde musulman au milieu du IX^e siècle ap. JC’, *Studia Iranica*, 2 (1973).

and rather unexpected element in the development of the Caspian region: the emergence of Zaydī Shī'a as competitors to nativist, caliphal and Ṭahirid authorities alike.

The stronghold of Zaydism was in western Ṭabaristan, carried there, it seems, by survivors of the revolt of Yaḥya ibn 'Abd Allah, who had himself been given refuge in 176/792 by a local Daylamite ruler from a line known as the Justanids. Zaydism was then propagated to adjacent areas, especially by missionaries loyal to al Qasim ibn Ibrāhīm al Rassī (d. 246/860).⁸⁴ In an uprising against the Ṭahirids in 250/864 the people of Daylam and western Ṭabaristan invited a Ḥasanid, al Ḥasan ibn Zayd, then living in Rayy, to become their leader. Although he was not recognised as an imam, he was able to found a Zaydī state that expanded to control most of Ṭabaristan, with its capital at Āmul. Not only did the Zaydīs and their supporters oust the forces of the waning Ṭahirids, they repeatedly defeated and expelled local Bawandids who opposed them. The most effective of the Zaydī rulers was no doubt al Ḥasan ibn 'Alī al Uṭrush (d. 304/917), who successfully resisted challenges from both the Samanids of Khurasan and the local Bawandids and Justanids. Zaydism and Zaydīs continued to be the dominant forces in Ṭabaristan right down to the time of the rise of the Ziyarids, at which point the regional history of the Caspian begins to merge with that of western Iran and Iraq and is thus outside the range of this account. The question of exactly why Zaydism should have become such a fundamental element in Caspian regionalism is not easy to answer. To some extent it filled the void created by the erosion of sympathy among the population for either the local aristocracy or the outside powers trying to supplant them. It was perhaps a way of acceding to what seemed the inevitable spread of Islam while retaining some sense of local identity. It tapped into sentiments of affection for the 'Alids that appeared in the Kufan zone of conquest and the Islamic east in general. The appeal in the Caspian context of Zaydī theology and spirituality is difficult to explain, but there is testimony that there was an appreciation among the populace of the justice and ethical conduct of the Zaydī leaders,⁸⁵ and that may be the most basic factor in their success.

Sijistan/Sistan

Sistan and the Caspian are dramatically different places in many respects, but their local histories share a surprising number of similar features. Not the least

84 See W. Madelung, *Der Imam al Qasim b. Ibrāhīm und die Glaubenslehre der Zayditen* (Berlin, 1965).

85 Al Ṭabarī, *Ta'rikh*, series III, p. 2292.

of them is that we are fortunate to have available in both cases unique narrative texts that flesh out the sparse details about the history of these provinces found in the major chronicles. Ibn Isfandiyyar's *Tarīkh i Ṭabaristan*, however, seems to have been motivated by a simple antiquarian interest in the area, while the anonymous *Tarīkh i Sīstan* (a composite work, the bulk of which was probably written in the late eleventh century CE) reflects the author's sense of a distinct local identity and a pride in it as it moved from being little more than an appendage of Khurasan to the seat of the Ṣaffarid emirate and a regional power in its own right.

At least in the early conquest period the Arabs probably viewed Sīstan as a frontier province of prime importance, as it offered a prosperous urban and agrarian base in Zaranj and its hinterlands; prospects for raids and plunder in the still unsubdued marches of Zamīndawar, Rukhkhaj and Ghur; and the potential to serve as a springboard for further imperial expansion towards India. As time went on all these attractions must have lost their initial appeal, especially when contrasted to the opportunities developing in Khurasan.⁸⁶ The old trade routes, as noted earlier, were shifting dramatically, and settled agrarian life in Sīstan was hardly easy, as Qutayba ibn Muslim found out when he had crops planted at Zaranj but then could not harvest them because of the infestation of serpents.⁸⁷ The people of Zaranj and other cities that had accepted Arab rule displayed a remarkable streak of independence; they were known on occasion to shut their gates to newly appointed governors of whom they disapproved, or even to chase unpopular officials out of town. In these disputes the Arab tribes often wound up fighting each other rather than any local enemies.

Meanwhile, the *zunbīls* and *kabulshahs* proved to be formidable adversaries whose power could not be broken and whose lands were difficult to penetrate. Even when they agreed to pay tribute in exchange for the withdrawal of Arab armies, the amounts represented a rather poor return for the costs of the campaigns. One Arab general, having spurned an offer from the *zunbīl* to pay tribute of a million *dirhams*, had to accept an offer of 300,000 after a typically disastrous campaign, much to the disgust of the caliph, 'Abd

86 Ibid., series I, p. 2705 notes that the strategic importance of Sīstan was greater than that of Khurasan down to the time of Mu'awiya.

87 Baladhurī, *Futuḥ*, p. 400. It is interesting that the peace treaties concluded in Sīstan sometimes included the provision that weasels should not be killed, in the interest of helping to keep down the snake population! In general, there is good reason to think that agricultural productivity in Sīstan had already begun a downward spiral that eventually impoverished the area.

al Malik.⁸⁸ His successor fared even worse, and actually had to give tribute and hostages to the *zunbīl*; when a faction of the army protested and tried to continue to fight, it was annihilated.⁸⁹ The vigorous efforts of al Ḥajjaj to subjugate the area fared little better (he was eventually obliged to strike a bargain with the *zunbīl* in order to obtain his help against the rebel Ibn al Ash'ath), and we are told that after the death of al Ḥajjaj the *zunbīl* declined to pay any tribute at all.⁹⁰ A declining interest in Sīstan in the later Umayyad period can be detected in the rapid turnover of obscure governors there, as well as Khalid ibn Yazīd's frank advice to 'Abd al Malik to ignore any political troubles in Sīstan and worry about those in Khurasan.⁹¹

None of this was much changed by the 'Abbasid revolution. Judging from the *Tarīkh i Sīstan* (the text unfortunately has some lacunae at this point) the people of Zaranj were unenthusiastic about the regime change, and refused to hand over the Umayyad governor to the 'Abbasid forces sent by Abu Muslim until he was guaranteed safe conduct back to Syria. Abu Muslim's next governor, 'Umar ibn 'Abbas, stirred up so much controversy among both the townspeople and the tribesmen of Tamīm in Zaranj that his chief of police was murdered, and 'Umar had to flee to Bust. He was killed in subsequent fighting, and his successor, the prominent 'Abbasid propaganda chief (*da'ī*) Abu 'l Najm 'Imran ibn Isma'īl, was blocked by local forces led by a renegade from Bust named Abu 'Āṣim, who became the effective ruler of Sīstan for four years and even attempted, unsuccessfully, to invade Khurasan before being killed by a new 'Abbasid governor, Sulayman ibn 'Abd Allah al Kindī, in around 138/755. 'Abbasid authority was still quite tenuous: Sulayman himself rebelled when al Maṣṣur appointed a new governor in 140/757; that replacement, Hannad al Sarī, likewise rebelled when his term of office came to an end. Only under the governorship of Ma'n ibn Za'ida al Shaybanī was there some semblance of stability as well as some success against the *zunbīl*, but even Ma'n wound up being murdered by dissidents in 152/769. In sum, the appeal of caliphal authority in Sīstan to certain circles of the urban elite was more than offset by a general dislike of outside interference in local affairs – and especially the taxation that accompanied it – by most of the rest of the population.

One of the most powerful counteracting forces of localism in Sīstan was manifested in Kharijism, which played at least as important a role in the

88 Ibid., p. 399; cf. the apparently confused account in *Tarīkh i Sīstan*, pp. 105–6 (trans. Gold as *The Tarikh e Sistan*, pp. 86–97).

89 Baladhurī, *Futuḥ*, p. 399.

90 Ibid., p. 400.

91 Al Ṭabarī, *Ta'rikh*, series II, p. 1059.

history of that province as Zaydism did in the Caspian. Whatever may be said about the supposed Kharijite propensity for violence and divisiveness, the sect's indifference to ethnicity and its uncompromising insistence on virtue and justice could have great appeal, and certainly did in the case of Sīstan. The earliest Kharijite presence there was largely due to the collapse of the Azraḡī principality in Fars. Its last 'caliph', Qaṭarī ibn al Fuja'a, had once served with Muhallab ibn Abī Šufra in Sīstan, where, according to the *Tarīkh i Sīstan*, he was 'an illustrious man' (*buzurgwarī*) who won over many people as friends. He appealed to the Sīstanīs for help in his struggle against al Ḥajjaj, and was supported by them, both nobles and commoners.⁹² After his defeat and death (c. 79/698) surviving remnants of the movement sought refuge in Sīstan.⁹³ It is clear that these Kharijites were not long regarded as interlopers; they quickly established deep roots in Sīstanī society and found considerable support among the native population. In Sīstan, as C. E. Bosworth has noted, Kharijism managed to achieve a fusion of piety and politics that transformed it into a movement 'with some local foundations and with a concern about such grievances as excessive taxation and unjust tax collectors'.⁹⁴ As such, its main base was outside the urban areas and especially among the peasantry, but even people in the big cities might collude with them against an unpopular governor (as is probably exemplified, for example, in the ease with which Kharijites were able to penetrate into Zaranj to murder Ma'n ibn Za'ida in 152/769⁹⁵). At times the Kharijite disturbances in Sīstan could spill over into the countryside of adjacent provinces as well.

All of these trends are illustrated in the most important and climactic of the Kharijite revolts, led by Ḥamza ibn 'Abd Allah. He was himself of Iranian, and probably Zoroastrian, origin (other sources give his father's name as Ādharak and the *Tarīkh i Sīstan* says he was from the family of Zawtahmasb) but had many Arab followers. He is described in the *Tarīkh i Sīstan* as a pious man who first gained notoriety by killing an oppressive tax collector and then became

92 *Tarīkh i Sīstan*, pp. 109–10 (trans. Gold as *The Tarīkh e Sīstan*, p. 88).

93 It is interesting that the early peace treaty with the Sīstanīs, perhaps in conformity with traditional practices, specified that the wasteland areas served as a sanctuary for dissidents of various kinds and was regarded as off limits to the regular Muslim forces (al Ṭabarī, *Ta'rikh*, series I, p. 2705); this practice may well have provided an ideal refuge for the defeated Kharijites, who gradually banded together with the local inhabitants.

94 C. E. Bosworth, *Sīstan under the Arabs, from the Islamic conquest to the rise of the Šaffarids* (30–250/651–864) (Rome, 1968), p. 87.

95 *Tarīkh i Sīstan*, pp. 143–8 (trans. Gold as *The Tarīkh e Sīstan*, pp. 113–17); Ya'qubi, *Historiae*, vol. II, pp. 462–3; cf. Chase Robinson, *Empire and elites after the Muslim conquest: The transformation of northern Mesopotamia* (Cambridge, 2000), pp. 147–52.

the leader of a Kharijite sub sect in the vicinity of Uq, an obscure town that had become notorious as a bastion of brigands and Kharijites.⁹⁶ At first he was mostly engaged in fighting rival sects, but he soon became the champion of a much broader and more popular struggle against the policies of the governor 'Isa ibn 'Alī ibn 'Isa ibn Mahan, who was as hated in Sīstan as his father was in Khurasan. He defeated 'Isa in 182/798; spared the provincial capital, Zaranj; and abolished the land tax. According to the *Tarīkh i Sīstan*, the people of Zaranj negotiated a settlement with Ḥamza whereby they continued to recognise the caliph as ruler, but the payment of taxes and tribute to Baghdad ceased and was not resumed.⁹⁷ When 'Alī ibn 'Isa sent an 'Abbasid army to try to reclaim Sīstan in 186/802, Ḥamza simply moved his insurgency to Khurasan, killing tax collectors wherever he could.

At that point the struggle between the Kharijites and the 'Abbasids took a particularly brutal turn, with reports of devastation, mass slaughter and bloody reprisals carried out by both sides. Eventually the disturbances became so widespread and severe that the caliph Harun al Rashīd had to come in person to lead the campaign against Ḥamza. Harun sent an ultimatum to Ḥamza calling on him to submit, to which Ḥamza replied by using exactly the same titulature for himself as the caliph had employed and emphasising that he was fighting against the misconduct and oppression of government officials.⁹⁸ Harun's death in 193/809 averted the need for a decisive battle; Ḥamza apparently then dispersed his forces and returned to Sīstan, where he may have devoted himself to *jihad* against various non Muslim territories.⁹⁹ Al Ma'mun was, as we have seen, too preoccupied with larger problems to expend much effort in dealing with Sīstan. As the *Tarīkh i Sīstan* explains it, the governors sent by al Ma'mun governed lightly and did not demand much in the way of taxes, the Kharijites concentrated on raiding frontier areas, and the two sides generally left each other alone. That began to change after the Ṭahirids took over the administration of Sīstan in 206/821, in part because of feuding between some of the Ṭahirid officials and those sent to replace them.

96 C. E. Bosworth, *The history of the Saffarids of Sistan and the Maliks of Nimruz* (Costa Mesa, 1994), pp. 77–8 locates it north of Zaranj, probably near the earlier Zoroastrian cult centre of Karkuya.

97 *Tarīkh i Sīstan*, p. 158 (trans. Gold as *The Tarikh e Sistan*, pp. 124–5).

98 The exchange of letters is preserved in the *Tarīkh i Sīstan*, pp. 162–4 (trans. Gold as *The Tarikh e Sistan*, pp. 128–34); on them, see G. Scarcia, 'Lo scambio di lettere fra Harun al Rašīd e Ḥamza al Ḥarīḡi secondo il "Ta'riḡ i Sistan"', *Annali dell'Istituto Universitario Orientale di Napoli*, n.s. 14 (1964).

99 His supposed campaigns as far as India are part of the popular legends that make up the fabulous work known as the *Ḥamza namah*, followed also in part by the *Tarīkh i Sīstan*.

One of the governors named by Ṭalḥa ibn Ṭahir actually had to ally himself with Ḥamza to secure his office against his rivals. Ḥamza died in 213/218, not long after defeating a Ṭahirid army and driving the governor back to Khurasan. Inconclusive fighting between the Kharijites and Ṭahirid governors continued for quite some time.

The Ṭahirid intrusion into Sistan coincided with both the collapse of the last vestiges of caliphal authority in the area and the rise of the popular militia forces known as the *'ayyars*.¹⁰⁰ The origins and exact nature of these groups are uncertain and controversial. At least in the case of Sistan they have been well and succinctly described by C. E. Bosworth as 'anti Kharijite vigilantes'.¹⁰¹ There the *'ayyar* groups were fairly clearly, if paradoxically, composed of non sectarian brigands from the countryside and the lumpenproletariat (young, poor or unemployed, unmarried men) of the towns, especially Bust, under the sponsorship of an urban elite that, having despaired of the ability of the central government to maintain order, turned to these gangs to maintain some semblance of security. Although they were at first directed against the Kharijites, they soon became fierce opponents of Ṭahirid policies and methods in Sistan primarily fiscal oppression and the depredations of the Turks who were beginning to figure in the Ṭahirid military forces. One of the *'ayyar* leaders, Ṣaliḥ ibn Naḍr (or Naṣr), succeeding in driving out the last Ṭahirid governor in 239/854.

The great regional dynasties

Following al Ma'mun's accession to the caliphate and return to Baghdad, the history of the Islamic east becomes primarily that of largely autonomous, hereditary, regional dynasties: the Ṭahirids, Ṣaffarids, Samanids and Ghaznavids (leaving aside the plethora of petty local rulers and dynasties). To these one could add the Buyids as well, but the history of that dynasty is so closely interwoven with that of Iraq that it is best considered in the context of the caliphate's history. The purpose here is not to give anything like a systematic account of the eastern dynasties, for which many excellent studies

100 See Claude Cahen, 'Mouvements populaires et autonomisme urbain dans l'Asie musulmane du moyen âge', *Arabica*, 5 (1958), pp. 225–50, and 6 (1959), pp. 25–56, 233–65; F. Taeschner, 'Futuwwa: Eine gemeinschaftbildende Idee im mittelalterlichen Orient und ihre verschiedene Erscheinungsformen', *Schweizerisches Archiv für Volkskunde*, 52 (1956), pp. 122–58; Mohsen Zakeri, *Sasanid soldiers in early Muslim society: The origins of 'Ayyaran and Futuwwa* (Wiesbaden, 1995); Bosworth, *Saffarids of Sistan*, pp. 68 ff.

101 Bosworth, *Saffarids of Sistan*, p. 69.

are now available,¹⁰² but simply an overview of their significance for the development of regionalism.

The Ṭahirids

The appointment of Ṭahir ibn al Ḥusayn ibn Muṣ‘ab al Bushanjī as governor of Khurasan and the whole of the Islamic east in 205/821, the beginning of a governorship that would be held on a hereditary basis for some fifty years, can be regarded as a key turning point in the history of the region. Some modern historians downplay the importance of this event, emphasising that the Ṭahirids retained the status of governors and ‘faithfully acknowledged and fulfilled the constitutional rights of their overlords the caliphs’ or that they were ‘partners in the Abbasid state’ rather than ‘independent dynasts’.¹⁰³ There was indeed nothing novel about a powerful family dominating the province for a generation or more (much the same could be said about governors going as far back as Ziyad ibn Abīhi), and the relationship between the caliphs and the governors was no doubt correct in its adherence to the formalities of appointment. There was, however, a crucial difference. Up until the time of al Ma‘mun, a caliph might be obliged by circumstances to recognise an individual as governor, but he retained the ability to remove him, albeit with difficulty, or even – as we have seen – by military force. Beginning with the Ṭahirids, there is not the slightest reason to suppose that the caliphs had any such option or ability in the Islamic east – but plenty of hints that they wished they did.¹⁰⁴ There is also at least one case in which the caliph’s choice as governor was rejected by other members of the Ṭahirid family, and he was compelled to accede to their wishes.¹⁰⁵ The fact is that the Ṭahirids achieved a military power, political autonomy and fiscal independence beyond anything the caliphs could control; the caliphs were merely fortunate that on a good many matters their interests and those of the Ṭahirids happened to coincide.

102 Among them Munjī Ka‘bī, *Les Tahirides: Étude historico littéraire de la dynastie des Banu Ṭahir b. al Ḥusayn au Hurasan et en Iraq*, 2 vols. (Paris, 1983); Bosworth, *Saffarids of Sistan*; R. N. Frye, *Bukhara: The medieval achievement* (Norman, OK, 1965); W. Luke Treadwell, ‘The political history of the Samanid state’, D. Phil. thesis, Oxford (1991); C. E. Bosworth, *The Ghaznavids*, 2nd edn (Beirut, 1973).

103 C. E. Bosworth, ‘Tahirids’, *El2*, vol. IX, pp. 104–5; Hugh Kennedy, *The early Abbasid caliphate: A political history* (London, 1981), p. 167.

104 Al Ma‘mun was suspected of wanting to kill Ṭahir; al Mu‘taṣim is said to have detested ‘Abd Allah ibn Ṭahir; and al Musta‘in was relieved to hear of Ṭahir ibn ‘Abd Allah’s death since there was ‘no one he feared more’ (Ya‘qubī, *Historiae*, vol. II, p. 604).

105 The caliph al Wathīq reportedly attempted to install Ishaq ibn Ibrāhīm ibn Muṣ‘ab as governor but eventually had to recognise the succession arrangement that ‘Abd Allah ibn Ṭahir had specified, giving the office to Ṭahir ibn ‘Abd Allah.

It is certainly difficult to describe the relationship between Ṭahir and al Ma'mun as harmonious. Al Ma'mun had turned to Ṭahir mostly out of necessity, and it can be argued that he came to be as distrustful of Ṭahir as al Ma'nşur had been of Abu Muslim. In this case, the grievances went beyond resentment over being in debt to the kingmaker; much of what Ṭahir had done was decided entirely on his own, and al Ma'mun seems to have been genuinely disturbed by Ṭahir's role in the murder of al Amīn and perhaps also over having been manipulated by him into acceding to the execution of Harthama. Just as al Ma'nşur had endeavoured to keep Abu Muslim from returning to Khurasan by entangling him in the suppression of revolts and the managing of affairs in western provinces where he had no base of support, so al Ma'mun tried to keep Ṭahir in Iraq and gave him the task of fighting the rebel Naşr ibn Shabath in al Jazīra. There are likewise claims that he was plotting to kill Ṭahir (and that Ṭahir was aware of this).¹⁰⁶ However, the governors al Ma'mun had attempted to place in Khurasan had proven corrupt or ineffective or both, and disturbances there enabled Ṭahir to engineer his return as governor despite al Ma'mun's misgivings and the hostility of al Ḥasan ibn Sahl. Al Ma'mun could not risk an open breach with the regional elite that had put him in power, and he may well have been beginning to feel uneasy, after his return to Baghdad, with the prospect of living under the shadow of Ṭahir in the west. Conceding him the governorship of the Islamic east was an effective and necessary response to both realities.

It is equally difficult to think of Ṭahir as simply the faithful and loyal servant of the caliph. Indicative of his true attitude is the rebuke he gave al Ḥasan ibn Sahl when pressed to fight Naşr ibn Shabath: 'I made war on a caliph, and I handed over the caliphate to a caliph, and he gives me an order like this? He should send one of my subordinates for that!'¹⁰⁷ Obedience to the caliph figures hardly at all in the admonishments Ṭahir gave his son 'Abd Allah when the latter took over the job of fighting rebels in al Jazīra. While in Iraq he did not hesitate to rely on spies, and bribed officials to keep himself informed about the caliph's plans. Upon returning to Khurasan, he minted coins in his own name, and reportedly omitted the customary mention of the caliph's name in the Friday sermons. All indications are that an open break was prevented only by Ṭahir's sudden death in 207/822.

After Ṭahir's death his son Ṭalḥa took charge of the army and succeeded him as governor of Khurasan. It is not entirely clear whether his formal

¹⁰⁶ Al Ṭabarī, *Ta'rikh*, series III, p. 1042.

¹⁰⁷ *Ibid.*, p. 1043.

appointment was made by al Ma'mun, or whether he assumed the post as deputy of his brother 'Abd Allah, who inherited the post of governor of all the Islamic east but continued to conduct operations in the west. Not a great deal is known about Ṭalḥa's governorship (207 13/822 8), but he does not seem to have been a particularly capable ruler; he had to face at least two serious problems, the rebellion of another member of his family (al Ḥasan ibn al Ḥusayn ibn Muṣ'ab) and the Kharijite insurgency led by Ḥamza ibn 'Abd Allah. This gave al Ma'mun one last chance to assert some caliphal authority over the Islamic east by sending Aḥmad ibn Abī Khalid, ostensibly to direct campaigns against the Turks in Ushrusana and Farghana but more likely to spy on Ṭalḥa or even to try to replace him as governor. A huge bribe sufficed to defuse any trouble for Ṭalḥa that Aḥmad ibn Abī Khalid might have made.

Meanwhile, the far more talented and ambitious 'Abd Allah ibn Ṭahir had carved out a base of support in the central lands that rivalled that of the Ṭahirids in the east. He had proven himself indispensable by restoring order to al Jazīra and Egypt, and was preparing to attack the rebel Babak when Ṭalḥa died and he was supposedly given the choice of prosecuting the war or going to take over Khurasan. He had also acquired vast wealth, including lands and a palace in Baghdad that had the same status as a royal residence. Even after he returned to Khurasan he left a cousin in charge of the security forces in Baghdad, thereby keeping an important instrument of leverage vis à vis the caliph. Most sources (notably al Ya'qubī, who seems to have held a position in the late Ṭahirid administration) paint a glowing picture of 'Abd Allah's governorship of the Islamic east, and that is probably accurate from the point of view of the classes and interests it protected. What is known about it generally reflects the idealised form of government envisaged in the famous 'Epistle' addressed to 'Abd Allah by his father Ṭahir: the cultivation of an image of piety; close association with the religious scholars; adherence to religious law coupled with a sense of justice; maintenance of security and public order; a fair and scrupulous collection of taxes; and a paternalistic fiscal policy that promoted the welfare of the subjects.¹⁰⁸ Perhaps the most basic change was a shift in the primary role of the governor of the Islamic east from

108 The text is preserved in Abu 'l Fadl Aḥmad ibn Ṭahir ibn Abī Ṭahir Ṭayfur, *Baghdad fī ta'rīkh al khilāfa al 'abbasiyya* (Baghdad, 1968), pp. 19–28 and al Ṭabarī, *Ta'rīkh*, series III, pp. 1046–61; see C. E. Bosworth, 'An early Arabic mirror for princes: Ṭahir Dhu'l Yamīnain's epistle to his son 'Abdallah (206/821)', *JNES*, 29 (1970). Although Bosworth sees the ideas of the 'Epistle' as a reaction to 'new, Persian, hierarchic practices' that looks for 'a return to the simplicities of the Arab past', much of it actually seems in full accord with the values known to have been encouraged by the Iranian *dihqan* class to which the Ṭahirids had assimilated themselves.

being a marchlord and leader of wars of external expansion to a director of internal development. 'Abd Allah certainly retained an interest in the affairs of Inner Asia (not least because of the increasingly lucrative market for Turkish slaves) and carried out some campaigns there, but his general policy was to entrust the defence of the frontier to local lords, the best known being the Samanids. In keeping with this, he moved the capital from Marw to Nishapur and took a great interest in the promotion of agricultural development; among other things, he was responsible for a codification of law pertaining to canals and water rights.¹⁰⁹

The darker side of 'Abd Allah's policies and those of the Ṭahirids in general was the extent to which they wanted to dominate the whole of the Islamic east, not just Khurasan and Transoxania. As we have seen, their efforts to take control of Ṭabaristan certainly generated some friction with the caliphs. In both Ṭabaristan and Sistan they also produced a considerable amount of local resistance: obviously not everyone in those areas was as impressed with the benefits of Ṭahirid rule as people in their homelands supposedly were. The Ṭahirid hold on Sīstan was broken rather quickly by the 'ayyars, as we have seen, and this helped create the circumstances conducive to the rise of the next great dynasty of the Islamic east, the Ṣaffarids.

The Ṣaffarids

The Ṣaffarids represented in almost every conceivable way the antithesis of the Ṭahirid version of regionalism. The Ṭahirids were aristocrats with a distinguished lineage going back to the time of the 'Abbasid revolution; the first of the Ṣaffarids was a plebeian upstart and unabashed, even proud, of it (the fanciful genealogy ascribed to him in some texts notwithstanding¹¹⁰). The Ṭahirids maintained at least outwardly correct and respectful relations with the caliphs; the Ṣaffarid ruler made no secret of his disdain for the 'Abbasid caliphate (which he described as founded on treachery and deceit and not to be trusted), and may even have dreamed of overthrowing it. The caliphs may have resented the Ṭahirids, but they collaborated with them; they detested and distrusted the Ṣaffarids, and used every opportunity to undermine them.

¹⁰⁹ Gardīzī, *Zayn al akhbar*, p. 137.

¹¹⁰ The *Tarīkh i Sīstan*, pp. 200–2 (trans. Gold as *The Tarikh e Sistan*, pp. 159–60) gives an elaborate, and completely unbelievable, lineage for Ya'qub ibn al Layth going back to Ardashīr ibn Babak and Kayumarth; while the famous poem, most likely by Ibn Mamshadh, has him claiming to be a descendant of Jam: see S. M. Stern, 'Ya'qub the Coppersmith and Persian national sentiment', in C. E. Bosworth (ed.), *Iran and Islam* (Edinburgh, 1970). As noted by Bosworth, *Saffarids of Sistan*, p. 179, it is most improbable that Ya'qub would ever have taken such flattery seriously.

The regional character of the Ṭahirids was diluted by their territorial expansion and their vast holdings of property in the central lands; although the conquests of the Ṣaffarids were even more extensive, the dynasty remained distinctly Sīstānī in character and orientation. The Ṭahirids cultivated religious scholars and acted as defenders of orthodoxy; though pious in their own way, the Ṣaffarids had no perceptible sectarian biases, and welcomed support from groups such as the Kharijites. The Ṭahirids supported and participated in the high culture in Arabic of their time; the unpretentious Ṣaffarids viewed elite culture with contempt, and valued vernacular and popular culture instead.

Ya'qub ibn al Layth, the founder of the dynasty, was a coppersmith (*ṣaffar*) by profession. He emerged as one of the most popular and successful '*ayyar*' leaders after Ṣalīḥ ibn Naḍr had expelled the last of the Ṭahirid governors, distinguishing himself in several battles against the Kharijites. Thanks to what the *Tarīkh i Sīstan* calls his 'manliness, bravery, and splendor' (for which we might read his skilful exploitation of rivalries between '*ayyar*' factions and the cities of Zaranj and Bust), he was able in 247/861 to take control of Zaranj.¹¹¹ The following year he also displaced Ṣalīḥ ibn Naḍr, the '*ayyar*' commander of Bust. When Ṣalīḥ sought refuge with the *zunbīl*, Ya'qub responded by invading Zabulistan and accomplishing what no previous Muslim army had been able to do: decisively defeat and kill the *zunbīl* himself. Not only that, Ya'qub began to expand his army by co-opting and assimilating the very brigands and Kharijites the '*ayyar*' had been formed to resist. His great ideological tool in uniting such previously hostile groups appears to have been an appeal to Sīstānī nativist sensibilities; in a letter to one of the Kharijite leaders, for example, he emphasised the common task of fighting injustice by government officials (*aṣḥab i sulṭān*), resisting rule by 'foreigners' (*ghuraba'*) and a pledge not to surrender Sīstan to anyone (from outside).¹¹²

With a solid base in Sīstan, Ya'qub began to move into adjacent areas, consolidating his hold on Zabulistan and taking the area of Herat and Badghīs which, as mentioned earlier, had long been a centre of local resistance and Kharijite activity from the Ṭahirids. Around 254/868 (according to the *Tarīkh i Sīstan*) he occupied Kirman, and the following year captured Shīraz, the capital of Fars. Also in 255/869 (or 259/873 according to other sources) he was able to take Nīshapur without a battle, and imprisoned the last of the Ṭahirid governors of Khurasan, Muḥammad ibn Ṭahir. He also made a rather half-hearted effort to invade Jurjan and Ṭabaristan. The motivation

¹¹¹ *Tarīkh i Sīstan*, p. 199 (trans. Gold as *The Tarikh e Sistan*, p. 158).

¹¹² *Tarīkh i Sīstan*, p. 203 (trans. Gold as *The Tarikh e Sistan*, p. 160).

behind these spectacularly successful campaigns is open to debate. They were surely mercenary robber's raids, as Nöldeke puts it¹¹³ to some extent, especially given the hardships that had befallen Sistan because of recent droughts and famine. The attack on the Ṭahirids could be interpreted as striking back at those who had formerly dominated Sistan, as Ya'qub thought that it was his divine destiny 'to exterminate the Ṭahirids and end their tyranny over Muslims'.¹¹⁴ The conquests in Kirman and Fars and the great importance attached to them, however, also suggest a larger strategic interest of reviving the trade routes and consequent importance of Sistan that had prevailed in the early Islamic period.

The conquests in Fars, along with the overthrow of Muḥammad ibn Ṭahir, brought into the open the question of Ya'qub's relationship with the caliphate. To begin with, Ya'qub probably did not have a clear idea of the actual power possessed by the caliph, or his sentiments, and sought to appease him by sending rich tribute, including fifty 'gold and silver idols' seized at Kabul and the head of a Kharijite opponent who had posed as a counter caliph. For his part, the caliph al Mu'tamid was alarmed by Ya'qub's actions but responded politely to him since, as the *Tarikh i Sistan* bluntly states, he had no other choice.¹¹⁵ He indicated that he was willing to recognise Ya'qub's authority in Sistan on the basis of his claims to be restoring order there, but that his actions in Khurasan and Fars were unacceptable.¹¹⁶ When Ya'qub found that the people of Nishapur would not include his name in the Friday sermon (*khuṭba*) because he did not have a patent (letter) of investiture from the caliph, he derisively dismissed this as the charade that it was, making a display of his military might before the notables of the city and telling them that his authority, no less than the caliph's, was based on the sword: 'My patent and the caliph's are one and the same',¹¹⁷ If the *Tarikh i Sistan* is to be believed, he began acting much like a caliph himself, being addressed as 'king of the world' (*malik al dunya*), receiving embassies from foreign countries, and planning to lead a holy war against the Byzantines.¹¹⁸ In any case, a break between al Mu'tamid and Ya'qub was not long in coming. Neither efforts at appeasement nor inciting rebels in proxy wars against Ya'qub having produced satisfactory results, al Mu'tamid publicly repudiated Ya'qub's authority over Khurasan in 261/874,¹¹⁹ and Ya'qub responded by invading Iraq

113 Theodore Nöldeke, 'Yakub the Coppersmith and his dynasty', in Theodore Nöldeke *Sketches from eastern history*, trans. J. S. Black (London, 1892; repr. Beirut, 1963), p. 181.

114 *Tarikh i Sistan*, p. 220 (trans. Gold as *The Tarikh e Sistan*, p. 175).

115 *Tarikh i Sistan*, p. 225 (trans. Gold as *The Tarikh e Sistan*, p. 178).

116 Al Ṭabarī, *Ta'rikh*, series III, p. 1882.

117 *Tarikh i Sistan*, p. 223 (trans. Gold as *The Tarikh e Sistan*, p. 176).

118 *Tarikh i Sistan*, p. 234 (trans. Gold as *The Tarikh e Sistan*, pp. 182–3).

119 Al Ṭabarī, *Ta'rikh*, series III, p. 1887.

and marching on Baghdad, quite possibly with the intention of deposing al Mu'tamid.¹²⁰ Probably to everyone's surprise, the caliph's forces actually managed to stop 'the accursed renegade called Ya'qub b. al Layth'¹²¹ at a battle near Dayr al 'Āqul in Rajab 262/April 876. The *Tarīkh i Sīstān* seems to imply that Ya'qub had been lured into an ambush by a letter in which the caliph lavished praise on Ya'qub and invited him to visit the court;¹²² others attribute the defeat to Ya'qub's naive overconfidence that the caliph would capitulate. There is no doubt, however, that Ya'qub found himself fighting, quite uncharacteristically, with an inferior number of troops on unfamiliar terrain under disadvantageous circumstances. Despite this setback, Ya'qub retired in good order to Jundīshapur and continued to control Fars and Khuzistan until his death in 265/879.

Ya'qub was succeeded by his brother 'Amr ibn al Layth. 'Amr had earlier had a falling out with Ya'qub and they had only recently been reconciled, and he was acclaimed ruler by the army somewhat reluctantly; he may well have represented a minority faction in the Ṣaffarid regime that favoured a more conciliatory policy towards the caliphate.¹²³ Sistan remained firmly under his control, but he had to engage in a protracted and complicated struggle to suppress major revolts in Khurasan while simultaneously trying to hold on to the lucrative province of Fars in the face of 'Abbasid intrigues to recover it for the caliphate. Much like the Ṭahirids, 'Amr seemed perfectly willing to pay regular tribute to the caliph in return for patents of investiture, but the 'Abbasids granted them only reluctantly and grudgingly, and revoked them whenever an opportunity presented itself. Thus in 271/885 al Mu'tamid proclaimed that 'Amr was to be deposed from all his posts and publicly cursed in the prayer services. The caliph's brother (and effectively the co caliph) al Muwaffaq invaded Fars and drove 'Amr back to Zaranj in 274/887 before being obliged to renew the arrangement of recognising 'Amr in return for payment of tribute. In 276/890 al Muwaffaq again proclaimed 'Amr's deposition, but to no avail; he had to reconfirm 'Amr as governor of Khurasan in 279/892. After defeating his rivals in Khurasan 'Amr had managed to make himself master of most of the Islamic east by 283/896.

120 Gardīzī, *Zayn al akhbar*, p. 141.

121 The description in the caliph's victory letter, quoted in al Ṭabarī, *Ta'rikh*, series III, p. 1895.

122 *Tarikh i Sīstān*, pp. 231–2 (trans. Gold as *The Tarikh e Sistan*, p. 183).

123 See B. Skladanek, 'External policy and interdynastic relations under the Saffarids', *Rocznik Orientalistyczny*, 36 (1974).

As has been noted, the Ṭahirids had followed a policy of entrusting the defence of the frontier in Transoxania to a network of local lords as their subordinate governors. Of these the family known as the Samanids had emerged as the most important, becoming the rulers of Sogdia, with a capital at Samarqand. After the overthrow of the Ṭahirids the caliph al Mu'tamid had recognised one of them, Naṣr ibn Aḥmad, as governor of Transoxania in 261/875 (presumably as a counterweight to the Ṣaffarids; Ya'qub had defeated Naṣr's uncle Ilyas and removed him from the governorship of Herat, so relations between the Ṣaffarids and Samanids were likely to be hostile). As it happened, Ya'qub ibn al Layth showed little or no interest in challenging this system or adding Transoxania to his domains, so the Samanid family continued to rule there. But 'Amr, after his victory over the rebels in Khurasan, made the mistake of asserting a claim to Samanid territory. In 285/898 he induced al Mu'tamid to depose the Samanid Isma'īl ibn Aḥmad as governor of Transoxania and recognise him instead. Isma'īl reportedly pleaded with 'Amr to be content with the vast territories he already possessed and leave him in control of his frontier zone, but 'Amr refused. He apparently also ignored the warnings of his own military advisers about the difficulty of mounting a campaign across the Oxus.¹²⁴ Ironically, Transoxania had developed almost as strong a sense of local identity and resistance to outside interference as Sistan had, and 'Amr quickly found that he had overextended himself. Isma'īl rallied the *dihqans* and landlords of the area to resist him, defeated a Ṣaffarid army, and scornfully dismissed an offer from 'Amr to negotiate a settlement. In 287/900 he managed to surround and besiege 'Amr near Balkh, and finally to take him prisoner. Although some sources emphasise that Isma'īl treated 'Amr magnanimously, he was soon sent to Baghdad, where he was publicly humiliated, imprisoned, and most likely murdered in 289/902.

The unexpected and abrupt fall of 'Amr did not mean the end of the Ṣaffarid dynasty, but it did mark the beginning of its transformation from a great regional power to one of purely local significance. The Ṣaffarid army and administration were still largely intact and acclaimed 'Amr's grandson Ṭahir ibn Muḥammad as ruler. Ṭahir faced serious problems both in holding on to Fars against claims on it by the caliph and in managing factional strife within the Ṣaffarid regime, and he did not deal with either of them very satisfactorily. He was also threatened by Isma'īl ibn Aḥmad, who was now laying claim to

124 Al Ṭabarī, *Ta'rikh*, series III, p. 2194; cf. Abu 'l Faḍl Muḥammad Bayhaqī, *Tarikh i Bayhaqī*, ed. 'Alī Fayyād (Mashhad, 1350/1971), p. 615. The *Tarikh i Sistan*, pp. 254–5 (trans. Gold as *The Tarikh e Sistan*, p. 202) suggests that the caliph had approved 'Amr's request in order to lure him into just such a trap.

Sistan itself. In many ways the most important power in the Ṣaffarid realm was now the Turkish general Subkara, who was in control of Fars and its revenues, rather than Ṭahir. Not even the *Tarīkh i Sīstan* has much of a positive nature to say about Ṭahir, depicting him as a kind hearted but pleasure seeking and fiscally irresponsible ruler, who may also have been mentally unstable (some times spending days alone with pigeons and mules, which he regarded as his friends).¹²⁵ His various successors were not much better. In 298/910 the caliph al Muqtadir formally recognised a Samanid, Aḥmad ibn Ismaʿīl ibn Aḥmad, as governor of Sīstan, and within a year Samanid forces had captured Zaranj and brought the first line of Ṣaffarid rulers to an end. The Samanid occupation of Sīstan was not popular, however, and met with protracted resistance led by a collateral branch of the Ṣaffarid family, which was in power in the period 297 393/911 1002.

The Samanids

The Samanids, who now became the most important dynasty in the Islamic east, traced their origins back to one Saman khuda, a *dihqan*, probably from near Balkh, although this is uncertain (the claim that they were descended from the Sasanian general Wahram Chobin is intriguing but of course ultimately unverifiable). Saman khuda was among the many *dihqans* of that area who admired Asad ibn ʿAbd Allah for his administration of Khurasan. He presumably converted to Islam (his son was named after Asad and all his grandsons have Muslim names), but it is not clear whether he became Asad's *mawla*. It is also not clear how his association with Asad, a notorious persecutor of the ʿAbbasid propagandists, might have affected the family after the overthrow of the Umayyads. Asad ibn Saman khuda's sons reappeared in the time of Harun al Rashīd, when they provided valuable assistance against the rebel Rafīʿ ibn al Layth (perhaps inducing him to sign a peace accord). For this they were rewarded in 202/817f., when al Ma'mun had his governor of Khurasan, Ghassan ibn ʿAbbad, assign each of them districts to govern: Nuḥ at Samarqand, Aḥmad in Farghana, Yaḥya in Shash and Ilyas at Herat.¹²⁶ Eventually the line of Aḥmad became the most important branch of the family. His senior son, Naṣr, ruled at Samarqand and a younger son, Ismaʿīl, took over the administration of Bukhara. As noted earlier, it was Naṣr ibn

125 Bosworth, *Saffarids of Sistan*, pp. 243 59 attempts to rehabilitate Tahir's reputation somewhat, and it may be that he suffers in the sources from the wreckage that had been really been inflicted on the state by the more glamorous ʿAmr.

126 Following the detailed account of the family's origins in Narshakhī, *Tarīkh i Bukhara*, pp. 104 6 (trans. Frye as *History*, pp. 76 7).

Aḥmad whom al Mu'tamid recognised as governor of Transoxania in 261/875. Around 272/885 there was some kind of conflict between Naṣr and Isma'īl over the revenues from Bukhara. Isma'īl prevailed in the fighting and captured his brother in 275/888, but magnanimously arranged for him to continue in office at Samarqand. From then on, however, Isma'īl was the de facto Samanid ruler and Bukhara his capital. He was recognised as sole ruler after Naṣr's death in 279/892 and, as discussed earlier, successfully fended off the challenge posed by 'Amr ibn al Layth.

Clearly the caliphs felt more comfortable with the Samanids than the Ṣaffarids as the regional power in the Islamic east. The Samanid attitude towards the caliphs was somewhat less deferential than that of the Ṭahirids, but far less insolent than that of the Ṣaffarids. They followed the time honoured Iranian tradition of sending 'gifts' to a nominal sovereign, but there is no indication they ever paid regular taxes or tribute. They minted coins (in great abundance) in their own names. They usually honoured the tradition of obtaining patents of investiture from the caliphs, still something necessary for legitimacy at least in the eyes of the urban elites and '*ulama*', but it may be remembered that they also granted recognition of authority to the caliphs and on some occasions declined to do so. The complicating factor in the relationship was the rise of the Buyid rulers in western Iran and Iraq, particularly after their capture of Baghdad in 334/945, when the 'Abbasid caliphs became essentially Buyid puppets. Mu'izz al Dawla deposed al Mustakfi in 334/946, installed al Muṭi' as caliph, and pressured him to appoint Abu 'Alī al Ṣaghani governor of Khurasan, a clear affront to the Samanids (the issue was not so much his authority there as whether he received it from the Samanids or directly from the caliph). In consequence, the Samanids did not recognise al Muṭi' as caliph until 344/955. Similarly, when Baha' al Dawla deposed al Ṭa'i in 381/991, the Samanids withheld recognition until they were satisfied with the new caliph's policies (c. 390/1000). It is this tension that probably explains the reports that the Samanid *amīr* Naṣr ibn Aḥmad (r. 301–31/914–43) at least flirted with the possibility of switching his allegiance to Isma'īlī Islam and perhaps the Faṭimids. If the Ṭahirids can be described as only an autonomous hereditary dynasty, the Samanids were a fully independent one.

In his justification for resistance to 'Amr, Isma'īl ibn Aḥmad had pointed in particular to his role as a leader of *ghazīs*, protectors of a remote frontier and warriors for the faith in unconquered lands. This role provided a key prop for the maintenance of their legitimacy as rulers. Just as the Ṭahirid change of capital from Marw to Nīshapur had reflected a reorientation of policy towards internal expansion, the move of the capital from Nīshapur to

Bukhara symbolised a return of interest in external expansion. Sometimes this was done by encouraging peaceful missionary activities to convert the Turks of Inner Asia, sometimes through diplomacy, and sometimes through active warfare. Ismaʿīl's first major expedition as governor of the Islamic east came in 280/893, when he successfully conquered Ushrusana, ending the rule of a local dynasty there, and then invaded the lands of the Qarluq Turks in the steppes near Ṭaraz. When the Turkish tribes responded by attempting to invade Sogdia, Ismaʿīl proclaimed a *jihad* and soundly trounced them in a major battle around 292/904. These victories justified his boast that he would spare the people of Bukhara the trouble and expense of maintaining their defensive walls because 'while I live, I am the wall of the district of Bukhara'.¹²⁷ Not long afterwards the Turks began to convert in significant numbers to Islam. One perhaps unintended consequence of this was that the Samanid homeland began to be flooded with Turkish slaves and converts, fuelling the rise of Turks as slave soldiers in the armies of the Samanids and others and rather dramatically changing the demographics and then the politics of the Islamic east.

Of course, it was not only activities in the northern steppes that interested the Samanids. Like the Ṭahirids, they took their role as a regional power rather seriously, but their direct control over adjacent principalities was tenuous, and generally exercised by accepting the nominal vassalage of local rulers (not unlike the relation of the regional ruler himself to the caliph). This was the case, for example, in Khwarazm, where the Afrīghid *khwarazmshahs* remained in office; in Jurjanj, with the Ma'munids; and in Juzjan, governed by the Farīgunids. In the case of Sīstan, Aḥmad ibn Ismaʿīl (295 301/907 14) sent two armies into Sīstan and captured Zaranj in 298/911. As indicated earlier, Samanid rule was never very popular in Sīstan, thanks largely to its rapacious taxation policies and the rowdiness of the troops (now mostly Turkish) sent to occupy the province. There was a revolt and a short lived attempt to bring about a Ṣaffarid restoration in 299/912, and a more successful one that brought a collateral branch of the Ṣaffarid line to power in 311/923. Aḥmad ibn Ismaʿīl also attempted to assert authority over Ṭabaristan after a rebellion broke out there under Naṣir al Kabīr. He was murdered before accomplishing this, and the Zaydī imam al Uṭrush repelled Samanid invasions in 301 2/914 15. To the south west, however, Rayy was brought under Samanid rule in 314/926. Down to around 333/945 the Samanid military governor of Khurasan, Abu ʿAlī al Ṣaghānī, endeavoured to maintain some control over these areas; he

127 Narshakhī, *Tarīkh i Bukhara*, p. 48 (trans. Frye as *History*, p. 34).

contested parts of western Iran with the rising power of the Buyids and restored Samanid rule in Rayy. With the rise of the Buyids, however, the Samanids and some of the local rulers of northern Iran found it prudent to cooperate against a common rival. Thus the Ziyarids of Jurjan became nominal vassals of the Samanids in return for Samanid assistance against the Buyids; they secured an uneasy peace with Rukn al Dawla in 344/955. Thereafter the main thrust of Samanid policy seems to have been to avoid doing anything that might provoke the Buyids into attempting an invasion of Khurasan.

In the discussion thus far the focus has been on the political development of the Islamic east as a region, but with the Samanids the question of whether there was also a development of a cultural regionalism takes on special importance. There is no doubt that the cultural accomplishments of the Samanid period were prodigious, but many of them, like those of preceding periods, can be seen as part and parcel of general Islamic culture. In the case of figures such as the physician philosopher Ibn Sīna (d. 428/1037) or the polymath al Khwarazmī (d. c. 232/847), for example, it would seem pointless to try to distinguish their work as representative of regional rather than metropolitan culture. Likewise, the influence of the legal school of Abu Ḥanīfa and the theology of al Maturīdī were pervasive in the Samanid Islamic east, but were neither monolithic there nor absent elsewhere. The collection and compilation of traditions of the Prophet (*ḥadīths*) was carried out as enthusiastically in the Islamic east as anywhere else,¹²⁸ but this can hardly be regarded as regional culture. Nonetheless, the culture of the Samanid period did have a certain regional flavour, and some of its particular style and mannerisms in things such as speech, dress and social customs were identified by the geographer al Muqaddasī, who visited the area at that time.¹²⁹

In terms of high culture, it is also possible to identify some important tendencies that mark out a kind of regionalism. One, in keeping with the frontier location and spirit of the region, is a marked interest in geography, especially as it pertains to those areas outside the Islamic world that were of special importance to the Samanids: the northern steppes, China, Tibet and India. That interest is also notable in works from earlier periods, as in the history and geography of al Yaʿqubī, probably as the result of his work for the

¹²⁸ The remarkably extensive activity in this regard has been noted by R. Mottahedeh, 'The transmission of learning: The role of the Islamic northeast', in N. Grandin and M. Gaborieau (eds.), *Madrasa: La transmission du savoir dans le monde musulman* (Paris, 1997).

¹²⁹ Muqaddasī, *Aḥsan al taqasīm*, esp. pp. 327–40.

Ṭahirids, both of which give more attention to these areas than one normally finds in the conventional Arabic texts. It is quite apparent during the Samanid period in the patronage the Samanid rulers provided to Ibn Faḍlan during his journey (albeit on behalf of the caliph al Muqtadir) to the Bulghar lands (309 10/921 2)¹³⁰ and to Abu Dulaf in his travels among the Turks and Chinese (c. 331/943?).¹³¹ It was probably also characteristic of the unfortunately lost works of Abu 'Abd Allah al Jayhanī (fl. 310/922?) and Abu Zayd al Balkhī (d. 322/934), judging from what is said about them in later books by Gardīzī and Bīrunī. It may also be that in historiography there was now a more pronounced interest in a specifically regional history, exemplified in the (again, unfortunately no longer extant) *Ta'rikh wulat Khurasan* by al Sallamī (fl. fourth/tenth century).

Much more important for regional culture than any of these trends, however, was the emergence of Persian as a literary language, ending in the Islamic east the monopoly of Arabic in this regard. As a spoken vernacular language, recognisable dialects of Persian had been in use for some time, and had even been adopted by Arab settlers in the Islamic east: al Ṭabarī, for example, often quotes military commanders as giving orders or making comments in Persian, and records that the dying words of Ṭahir ibn al Ḥusayn were in Persian ('dar marg nīz mardī wayadh': 'one must be a man even in dying').¹³² Al Muqaddasī gives a fascinating overview of the various dialectical forms of this language spoken throughout the Islamic east and at the Samanid court (in the form called *darī*).¹³³ It was also adopted at various times as the language of the bureaucracy although this seems to have been a very contentious matter, as some factions pressed for the use of Arabic.¹³⁴ The issue was probably not so much the language itself, as most officials were certainly bilingual in Arabic and Persian, as the implications of using one or the other: was the Islamic east an autonomous region or part of a larger commonwealth? Would the interests of local groups, speaking languages such as Sogdian or Khwarazmian, be better served through the use of Arabic or Persian as an official language? Should the Turks now entering the Islamic east in great numbers be acculturated in Arabic or Persian? Exactly how all this played out is not clear, but the turning point

130 See A. Zeki Velidi Togan, *Ibn Faḍlan's Reisebericht* (Leipzig, 1939); A. P. Kovalevskii, *Kniga Akhmeda Ibn Fadlan o ego puteshestvii na Volgu* (Kharkov, 1956); M. Canard, *La relation du voyage d'Ibn Faḍlan chez les Bulgares de la Volga* (Algiers, 1958).

131 A. von Rohr Sauer, *Des Abu Dulaf Bericht über seine Reise nach Turkestan, China und Indien* (Bonn, 1939).

132 Al Ṭabarī, *Ta'rikh*, series II, p. 1063.

133 Muqaddasī, *Aḥsan al taqasim*, pp. 334–6.

134 See Treadwell, 'Samanid state', pp. 173–180.

would seem to be Aḥmad ibn Ismaʿīl's futile effort to reimpose Arabic as the language of administration; thereafter, Persian was dominant. The victory of Persian in the chancery was accompanied by the rise of literary Persian, sometimes under the patronage of the *dihqans* and local lords and eventually by the Samanid rulers themselves. In poetry, there may have been some tentative efforts under the Ṭahirids and Ṣaffarids to produce Persian verse; under the Samanids there was a galaxy of great Persian poets, including Rudakī (d. c. 329/940) and Daqīqī (d. c. 370/980?). For prose, a critical development was the decision of the Samanid *amīr* Maṣṣur ibn Nuḥ (350 65/961 76) to order Persian 'translations' (actually redactions) of al Ṭabarī's *Ta'rīkh* and *Tafsīr*, thereby extending Persian into realms of scholarship and religion that had always been the exclusive preserve of Arabic. The magnitude of the change in mindset that this required is indicated by the fact that he felt the need to secure a *fatwa* affirming that the use of Persian for such a purpose was legitimate. It served both to affirm the regional identity of the Islamic east under the Samanids and to assimilate sub regional identities into a common fabric: 'In this land, the language is Persian (*parsī*), and the kings of this realm are Persian kings (*muluk i 'ajam*).'¹³⁵

The downfall of the Samanids, ironically, was the product of their greatest success – their triumphs over the Turks – aggravated by disputes within the family itself. The acquisition of large numbers of Turkish slaves and their use as *ghulam* troops led to the eclipse of the Iranian *dihqan* forces which had been the backbone of earlier armies in the Islamic east. The Islamisation of the Turks and the appearance of Muslim Turkish states negated, at least in theory, the possibilities for *jihad* and enslavement. It was not long before the Samanids were under both internal pressure from their less than obedient *ghulams* and external pressure from the new Turkish state of the Qarakhanids. The problem is obvious at least as early as 301/914, when Aḥmad ibn Ismaʿīl was murdered by his own Turkish troops (supposedly because of his overly deferential attitude towards the religious scholars, although one suspects there was a good deal more than that behind the assassination). He was succeeded by his eight year old son Naṣr (301 31/914 43), and from then on it is difficult to avoid the impression that the Samanid rulers were mostly figureheads, with the real power behind the throne being Iranian ministers such as Jayhanī and Abu 'l Faḍl al Bal'amī and later Turkish generals such as Tash and Fa'iq. If Naṣr's encouragement of the Ismaʿīlīs was part of an attempt to reassert his independence and authority, it failed. He was compelled to

¹³⁵ *Tarjumah i Tafsīr i Ṭabarī*, ed. Ḥabīb Yaghma'i, 7 vols. in 4 (Tehran, 1961), vol. I, p. 5.

abdicate in 331/943 after the discovery of a plot in the army to overthrow him. Perhaps as part of this same conspiracy, his successor, Nuḥ ibn Naṣr (331 43/943 54), sought to install the Turkish general Ibrāhīm ibn Sīmjur as military governor of Khurasan, which provoked a rebellion by the previous Iranian commander, Abu 'Alī al Ṣaghānī. This continuing quarrel over Khurasan both weakened the dynasty and increased the dependency of the ruler on Turkish troops to stay in power (Nuḥ had to fend off an effort by Abu 'Alī to set up another member of the Samanid family as *amīr*). In the best known and most consequential case of Turkish insubordination, the governor of Khurasan, Alptegin, having failed in an effort to install a candidate of his choosing as the successor to 'Abd al Malik ibn Nuḥ in 350/961, went off with his supporters and seized control of Ghazna. There he acted ostensibly as a Samanid governor devoted to leading *jihād* in India while actually being in a state of semi rebellion, probably driving back at least one Samanid army sent against him.

The death pangs of the Samanid dynasty were protracted but inexorable. By the reign of Nuḥ ibn Maṣṣur (r. 365 87/976 97) the struggle between Iranian and Turkish elements in the army for control of Khurasan had become a competition between rival factions of Turks: on the one hand, the *amīr*'s nominal choice as governor, Abu 'l 'Abbas Tash; and on the other, a coalition of the chamberlain, Fa'iq, and the governor of Quhistan, Abu 'l Ḥasan Sīmjurī (who also took the opportunity to orchestrate the murder of the minister Abu 'l Ḥusayn al 'Utbi in 371/982). Tash, despite an appeal to the Buyids for help, was defeated in 377/987. Sīmjurī's son, Abu 'Alī, then defeated Fa'iq in 380/990. As a result, Samanid rule over Khurasan was completely lost. Meanwhile, the Qarakhanids were bearing down on the Samanids from the north, taking Isfijab in 370/980. In 381 2/991 2 Bughra Khan, the chief Qarakhanid ruler, attacked the Samanids and occupied Bukhara, probably at the instigation of Fa'iq or Abu 'Alī Sīmjurī or both of them. Nuḥ soon recovered his capital after Bughra Khan fell fatally ill and returned home. Fa'iq and Abu 'Alī then attempted to overthrow Nuḥ, but Samanid rule was saved by the intervention of Sebüktegin, who had become the chief of the Turkish troops at Ghazna; as a reward Sebüktegin's son, Maḥmud, was recognised by the Samanids as governor of Khurasan. Nuḥ also sought Sebüktegin's help against an invasion by the new Qarakhanid ruler, Ilik Naṣr, in 386/996. Sebüktegin, however, did not entirely trust the Samanid ruler and had little interest in becoming embroiled in a fight with the Qarakhanids. Consequently he negotiated a settlement with Ilik Naṣr that recognised Qarakhanid supremacy north of the Jaxartes and Sebüktegin's in Khurasan, leaving a Samanid principality now reduced to what had been its homeland areas around Samarqand and Bukhara

as a buffer between them. After Fa'iḳ, in league with the Turkish general Baktuzun, engineered yet another plot to put a puppet on the throne, even that was lost. Maḥmud ibn Sebüktegin reached an agreement with the Qarakhanids on the division of territory, confirming his supremacy south of the Oxus, and in 398/999 Ilik Naşr occupied Bukhara. Clearly the Samanid ruler was no longer a 'wall' for the city against the Turks or anyone else, and the religious leadership, which had invited a Samanid to rule in the first place, now declared that the dynasty was not worth fighting for since the Turks had become Muslims. There was eventually one last effort to bring about a Samanid restoration, but it ended with the death of Isma'īl ibn Nuḥ in 395/1005.

The fall of the Samanid dynasty marks an appropriate end for a history of the Islamic east in the classical period, although this is masked somewhat by the afterglow provided by the Ghaznavid rulers, especially during the reign of Maḥmud of Ghazna (388 421/998 1030). The Ghaznavid period was a transitional one, and it is certainly possible to regard it as the end rather than the beginning of an era. It is true that the Ghaznavids vigorously defended their hold on the former Samanid territories south of the Oxus before finally being driven out by the Saljuq Turks at the battle of Dandanqan in 431/1040. It is also true that many of the cultural trends of the Samanid period, such as the Persian literary revival, the reconstruction of the Iranian national epic, and the perfection of the Persian bureaucratic system, continued into early Ghaznavid times. Nonetheless, the Ghaznavids and the Qarakhanids represented the advent of a new Turkish political power unlike anything that had existed before. And, well before Dandanqan, the Ghaznavid vision was fixed on new conquests and new lands in Afghanistan and India, which is where the real significance of that dynasty resides.¹³⁶ The unity and shape of the Islamic east had fundamentally changed, but not before creating a synthesis of Islamic, Arab, Persian and Turkish culture that would prevail over a much larger area for many centuries to come.

¹³⁶ See Wink, 'The early expansion of Islam in India'.

Syria

R. STEPHEN HUMPHREYS

Syria is a name, not a country. It comprises a vast region whose boundaries, political or 'natural', cannot be defined with any precision. The Arabs called it (and still do) *al Sham* or *Bilad al Sham* – literally, 'the lands to the left', i.e. to the north for a person in the Arabian Peninsula facing east towards the rising sun. In its broadest sense it is simply the western half of the Fertile Crescent, reaching north to south from the foothills of the Taurus and Anti Taurus mountains to the Gulf of 'Aqaba and the Wādī Sirḥan, and east to west from the middle Euphrates to the Mediterranean. On the south, it fades imperceptibly into the great deserts of Sinai and the Arabian Peninsula. On the north, it adjoins the Cilician plain. The lands stretching from the Euphrates east and to the upper Tigris are both an extension of Syria and a separate entity. Usually called Mesopotamia or, in Arabic, *al Jazīra* – this region had, and still retains, a distinctive profile of its own, for it formed the frontier zone between Islam and Byzantium, and between the Kurdish and Armenian highlands on the north and the Arab dominated lowlands on the south. Even so, western Mesopotamia/*al Jazīra* is so deeply intertwined with Syria proper that it must be included in this chapter. Localism and political fragmentation were the inevitable consequence of Syria's geography. Even so, the interaction between the region's disparate elements was constant and intense. One could never regard Syria as a single unit, but on every level – political, economic, social, cultural – it certainly constituted a coherent system.

Syria falls into several geographical zones: a narrow plain that runs the length of the Mediterranean coast from Antioch to Jaffa; behind this plain, linked chains of hills and moderately high (but easily traversed) mountains; and finally, a vast interior steppe. The coastal plain north of Tyre receives extensive albeit seasonal rainfall, and northern Syria and the northern *Jazīra* typically see enough to support rainfed agriculture. With a few exceptions the centre and south are far more arid, and here agriculture is only possible with skilfully managed irrigation. Because of its complex geography Syria has

always possessed a diverse population and wide range of cultures. The coastal plain is dotted with major and minor seaports, and has been a hive of commercial and cultural exchange since the earliest times. The hills and mountains have generated an interwoven series of village based peasant societies, each jealously guarding its lands and way of life against its neighbours as well as any outside powers that might try to intrude. The western edge of the interior steppe is favoured by a series of oases and small rivers, and has been quite densely sprinkled with cities and villages for several millennia. In some ways this region, marked by famous names such as Damascus, Homs and Aleppo, seems the heart of Syria. The interior steppe, finally, has been dominated at least since the early first millennium BCE by tribally organised nomadic pastoralists, whose economy has been based largely (though never exclusively) on camel herding.¹

The demography of Syria, both now and in the past, does not permit a simple description. On the eve of the Arab conquest both the coastal and interior cities were dominated by a Greek speaking elite of landowners, imperial officials and senior ecclesiastics. However, the bulk of the urban population (at least in the interior cities and towns) spoke one or another dialect of Aramaic as their first language. Almost the entire village population, whether in the mountains or the western edge of the steppe, also spoke Aramaic, which was (in its Syriac form) already the predominant written language in al Jazīra. The steppe and desert were dominated by Arabic speakers, as they had been for many centuries past. The boundaries between language groups were hardly crisp: most towns men must have had some Greek, however rough and ungrammatical, and the Arab tribesmen on the western fringes of the steppe could move in and out of sedentarised modes of life.

When Heraclius entered Jerusalem in triumph in March 630, he retook possession of a region that was the most deeply Christianised part of his empire, and also one that Hellenistic and Roman culture had profoundly shaped in its own image over the course of more than nine centuries. Three centuries later, however, the changes in the region would have been striking even to a casual observer. Roman rule was now only a dim memory, recalled in the ruins of its monuments and in the resurgence of Byzantine military power along Syria's northern borderlands. Some districts, especially those on the western fringes of the interior steppe, were distinctly poorer and less populous than they had been in Roman times, though whether this was true

¹ The most systematic recent survey, with a strong historical dimension, is E. Wirth, *Syrien: Eine geographische Landeskunde* (Darmstadt, 1971).

of Syria as a whole is open to question. Greek had been supplanted by Arabic as the language of educated discourse throughout the region, and in most places Arabic was probably the main vehicle of everyday speech as well. In many areas (especially in Mount Lebanon, northern Syria and northern Mesopotamia) Christians surely still constituted a demographic majority, with their institutions and cultural life largely intact. However, Islam had sunk deep roots and was arguably a more dynamic force in the country's social and cultural life. In short, by the mid fourth/tenth century Syria was no longer a Roman Christian land, but rather one that was largely Arabic speaking and increasingly Muslim.

The late Roman milieu

In 630 no one could have imagined that such a thing might be possible. The imprint of *romanitas* and Christianity was obvious in every dimension of life. On the level of sheer visual grandeur, there were the impressive colonnaded streets, public basilicas, churches and agoras of major and lesser cities stretching from Antioch and Apamea in the north, to Beirut and Damascus in the centre, and finally to Caesarea Maritima and Gerasa in the south. By the end of the Persian war in 628 and perhaps well before that time the urban fabric of Greece, the Balkans and central Anatolia may have been seriously damaged, but even the smaller towns of Syria were still largely intact, though their surface areas (and presumably their populations) had shrunk somewhat since the third century.² Certainly their agricultural hinterlands seem to have been flourishing and highly developed. If the traditional organs of urban life temples, gymnasia and monumental public baths had been abandoned or converted to new uses, their loss was compensated by a host of churches thickly strewn across the landscape. Even remote mountain towns or settlements on the edge of the Jordanian steppe might have several churches, built and endowed by both private and official donors. Most were fairly small structures, but even these were beautifully constructed and richly decorated. A few imperial foundations, such as St Simeon Stylites in the limestone massif south west of Aleppo, St Sergius in Rusafa (al Ruṣafa) and of course the Church of the Holy Sepulchre in Jerusalem, were imposing indeed. Like churches, monasteries were everywhere always outside the city walls, but

2 J. H. G. Liebeschuetz, *Decline and fall of the Roman city* (Oxford, 2001), pp. 54–63, 295–317; C. Wickham, *Framing the early Middle Ages: Europe and the Mediterranean, 400–800* (Oxford, 2005), pp. 613–30.

often in rather close proximity to them. Beyond such formal institutions there was the dense network of holy men, living and dead, whose mighty deeds demonstrated God's ever present power and protection.³ In the realm of Greek thought and letters (both pagan and Christian), Syria had played an extraordinary role since Eusebius of Caesarea and Libanius of Antioch in the fourth century. In the early first/seventh century alone the monastery of Mar Sabas east of Jerusalem had produced such luminaries as John Moschos, Maximus the Confessor and Sophronius – and its great days were far from over. Greek was the language of law and administration everywhere. Even such marginal places as Petra (east of the Dead Sea) and Nessana (in the Negev) could produce complex legal and administrative documents written in serviceable Greek.

Looked at more closely, of course, the picture was more complicated. To begin with, not everyone shared in the region's cosmopolitan Graeco Roman culture. Indeed, except in imperial administrative centres such as Antioch or Caesarea the majority of townspeople, and the vast majority of country dwellers, spoke Greek as a second language, if at all. For the most part they relied on their ancestral Aramaic or (in the interior steppe) on Arabic. The peoples of Syria and Palestine were overwhelmingly Christian by this time, but in some areas – among the desert Arabs, for example – Christianity had only begun to take hold in the course of the sixth century, and Syria's many traditional cults must still have survived in patches that escaped the vigilance of imperial and ecclesiastical authorities. (The most striking case would be the astral religion of Harran, a substantial town in this period.) More important than such 'pagan' survivals was the presence of substantial Jewish communities (including the Samaritans), present in many places but especially concentrated in Jerusalem and northern Palestine. Certainly there were enough Jews to attract the unwelcome attention of Christian activists – not least the emperor Heraclius himself – who were embittered by the Jews' alleged treason during the Persian war (602–28), and fearful that their knowledge of the Old Testament might confuse ordinary Christians and tempt them away from the true faith.⁴

3 P. Brown, 'The holy man in Late Antiquity', *Journal of Roman Studies*, 61 (1971), pp. 80–101, repr. in P. Brown, *Society and the holy in Late Antiquity* (Berkeley and Los Angeles, 1979), pp. 103–52. On the spread of the cult of St Sergius of Rusafa, see E. Fowden, *The barbarian plain: Saint Sergius between Rome and Iran*, *Transformation of the Classical Heritage* 28 (Berkeley, 1999), maps 2–3, pp. 101–5 and *passim*.

4 G. Dagron, 'Judaïser', in G. Dagron (ed.), *Travaux et mémoires*, 11 (1991), pp. 359–80; survey of anti-Jewish tracts in V. Déroche, 'Polémique anti-judaïque au VI^e et au VII^e siècle', in G. Dagron (ed.), *Travaux et mémoires*, 11 (1991), pp. 275–84.

Christians themselves were not of one mind. Palestine, most of the coastal cities and the districts around Damascus followed the imperial Church with its Chalcedonian creed. The imperial Church was run by Greek speaking bishops and used a Greek liturgy, however, and this created a real barrier between clergy and laity. In Palestinian churches the Greek liturgy was typically interspersed with Aramaic paraphrases so that the congregation could follow along, and something like this must have been true elsewhere.⁵ However, among Christian Arabs (most notably the Ghassanid confederation which dominated the interior steppe from al Ruṣafa to the Ḥawran) and in the towns and countryside of northern Syria and Mesopotamia most people adhered to rival confessions, conveniently if somewhat misleadingly called Monophysite and Nestorian. In so far as they had the power to do so, imperial authorities strove to control the major bishoprics and enforce doctrinal and liturgical conformity, but for the most part they won for themselves only a reputation for brutal persecution. Even in the first/seventh century, to be sure, adherents of the Monophysite and Nestorian creeds did not regard themselves as a separate church; rather, like their Chalcedonian opponents, they were struggling for the soul of the one true Church. Even so, they dominated the monasteries in the north and tried to install bishops (or counter bishops) of their own wherever possible. Most important, they conducted their liturgy and wrote most of their theological, didactic and hagiographical works not in Greek but in Syriac i.e. Christian Aramaic. Their religious discourse was thus carried on in the most widely used spoken language more precisely, in a learned form of that language and this fact connected them more closely with their flocks than most Greek speaking clergy in Syria Palestine could ever hope to be.

None of this should lead us to suppose that Rome was widely viewed as an alien power, that Hellenism was only a veneer, or that the peoples and cultures of Syria were too divided against themselves to resist the Arab armies and their new religion. There is no good evidence that Syrians hailed the Arab armies as liberators from Roman oppression. On the contrary, our first/seventh century witnesses portray the coming of the Arabs as a divine chastisement, like the Assyrians and Chaldaeans of old, and they took it for granted that this chastisement would end as soon as the Christian people repented of their sins, or the emperor at last saw the light of the true faith. The new rulers

⁵ S. H. Griffith, 'The monks of Palestine and the growth of Christian literature in Arabic', *Muslim World*, 78 (1988), p. 5, repr. in S. H. Griffith, *Arabic Christianity in the monasteries of ninth century Palestine* (Aldershot, 1992).

themselves feared a Byzantine *revanche* down to the end of the first/seventh century, and not without reason. As for Islam, sophisticated Christian observers initially regarded it as little more than the inchoate cult of a few thousand barbarians; it could hardly threaten so deep rooted and richly elaborated a faith as Christianity.⁶

Whatever residual loyalties to Rome there might have been among Syrian Christians, however, the Arab Muslim conquest incontestably altered the balance of social forces in the country; it created an environment in which Arab political domination and the religion of Islam could take root. By the time Arab armies pushed into Syria in the early 630s there was much discontent with Byzantine rule, even if there was no active desire to overthrow it. Byzantine military and fiscal resources, drained by the long Persian war, were further depleted in the vain struggle against the Arabs in the 630s. After the grave defeat suffered by his forces at the Yarmuk river in 636 Heraclius was unable to raise a new army, and was compelled to leave the surviving Byzantine garrisons in Syria and Mesopotamia to their fate. Even Byzantium's powerful navy was sidelined for decades after the catastrophic battle of the Masts, which took place off the south western coast of Anatolia near Phoenix (modern Finike) in 655. Under these circumstances a serious Byzantine counter attack was more a phantom hope than a realistic possibility. Syrians might soon come to feel that a relatively stable and tolerant Arab Muslim government was no worse than the disruption and turmoil of the last decades of Byzantine rule. Islam in turn was a more formidable competitor than the earliest Christian commentators supposed. To begin with, it had the prestige of being the victors' religion a manifest sign of divine favour. With time, as Islam asserted a distinctive identity of its own and developed a more nuanced set of practices and teachings, it might well compete effectively with Christianity for the spiritual allegiance of Syrians. In short, the brilliant victories of the 630s opened the door to a new Arab Islamic order of things in Syria, but it was anyone's guess whether this new order would take root and endure.

The shape of early Islamic rule

The immediate changes brought to Syria and Mesopotamia by the Arab conquests were minimal on many levels. First of all, the degree of physical

6 B. Flusin, 'Démons et Sarrasins', in G. Dagron (ed.), *Travaux et mémoires*, 11 (1991), pp. 382–409, esp. pp. 407ff.; V. Déroches, 'Polémique anti judaïque et émergence de l'Islam (7e–8e siècles)', *Revue des études byzantines*, 57 (1999).

destruction was slight. Except for Caesarea Maritima (stormed and sacked in 638 or 640) almost all cities and towns surrendered on terms and were left undamaged. We have ample testimony from both Muslim and Christian sources that the countryside was scoured by Arab raiding parties; apart from the destruction of villages and crops, vast numbers of captives were seized in these raids. But crops could be replanted, and many captives were soon returned to their lands through ransom, exchange and manumission. These processes may have cost bishops and monasteries many of their treasures, but in aggregate terms that only represents a transfer of wealth from one owner to another. As for the goods carried off to Mecca and Medina, they were typically luxury fabrics or ceremonial objects – very costly, but not the kind of liquid wealth that fuelled everyday economic life. The battles of the 630s were sometimes very bloody; at Gaza, Fihl, Ajnadayn (all 634) and the Yarmuk (636) Arab forces gave no quarter. However, Byzantine armies were a mix of Anatolian, Armenian and Christian Arab troops. They were not recruited from Syrian peasants and townsmen, so the bloodshed had no significant impact on the indigenous sedentary population. It does seem that many high officials, great landowners and senior ecclesiastics (especially from the imperial Church) fled the country as Byzantine forces withdrew into Anatolia. However, enough experienced people remained to run things under the Arabs; there is no evidence of an administrative breakdown in either fiscal or ecclesiastical affairs. Finally, and perhaps most important, the conquest of Syria brought about no major Arab immigration and settlement. Long established Bedouin tribes – Judham in the south, Quḍā'a in the centre, Tanukh and Ṭayyī' in the north – continued to dominate the Syro Jordanian steppe. The Arab armies that had come from the Peninsula were not large, and most of the troops who remained in Syria – in particular their commanders, drawn largely from Quraysh – could be quartered in existing cities such as Damascus and Homs. The experiment of creating a separate garrison town in al Jabiya, the old Ghassanid encampment in the Ḥawran, was quickly abandoned due to a murderous outbreak of the plague there in 639. In sum, the Arab conquest of Syria and Mesopotamia was rather like a summer thunderstorm (to borrow an image proposed by Clive Foss) – terrifying while it lasted, but soon past and the damage promptly repaired.⁷

At the conclusion of the fighting in 639–40, Syria was exceptionally fortunate in its newly appointed governor, Mu'awiya ibn Abī Sufyan. In many ways

⁷ F. M. Donner, *The early Islamic conquests* (Princeton, 1981), pp. 91–155, 245–50; W. Kaegi, *Byzantium and the early Islamic conquests* (Cambridge, 1992).

Mu'awiya was not the obvious choice for this critical position. He belonged to the notorious Umayyad clan – fellow tribesmen of Muḥammad but (with a few important exceptions) bitterly hostile to his prophetic claims. His father, Abu Sufyan, had been one of Muḥammad's most obdurate opponents, and accepted Islam only on the eve of the latter's occupation of Mecca in 630. Mu'awiya himself was a late convert, though perhaps a bit in advance of his father, and many doubted the depth of his attachment to Islam. He began as an obscure mid level commander in the Syrian campaigns of 634, but by the end of the decade he had won his way to senior positions. The Plague of 'Amwas, which decimated the Arab forces gathered at al Jabiya, also killed the three leading Arab generals, including Mu'awiya's older brother Yazīd. The post of governor fell to him almost by default, and he retained it unchallenged for the next sixteen years, through the caliphates of 'Umar (r. 634–44) and 'Uthman (r. 644–56).⁸

His long governorship gave him the opportunity to build an unrivalled power base among the Arab tribes and Muslim notables of Syria – an opportunity he did not miss – but it also gave him a chance to develop his skills as a ruler. In contrast to his counterparts in Iraq and Egypt, Mu'awiya did not have to deal with a large influx of Arabian tribesmen from disparate lineages. Such newcomers needed to be settled and supervised, and they were easily filled with jealousy and resentment focused on the division of the spoils of the conquests. In contrast, the numerous tribes under his authority continued to live more or less in their traditional areas, and hence seldom fell into conflict with one another. He assiduously cultivated his connections with the old Syrian tribes, especially Kalb, the largest lineage in the Qudā'a group and the one that dominated the countryside around his capital, Damascus.⁹ These tribes in fact supplied the manpower for Mu'awiya's armies. Since they resided in the steppe and desert they required little bureaucratic oversight, but could rather be recruited and paid as needed. We know very little about military administration in Mu'awiya's Syria, but most likely it was done through subsidies to the tribal leaders rather than by centrally controlled stipends assigned to individual soldiers. No doubt all these factors, combined with his extraordinary political acumen, helped Mu'awiya make Syria and Mesopotamia into the most stable provinces in the emerging Islamic empire.

8 On Mu'awiya there is a surprisingly thin literature: for his early career, see Aḥmad ibn Yahya al Baladhurī, *Futuḥ al buldan*, ed. M. J. de Goeje, (Leiden, 1866), pp. 117–18, 126–9, 133–4, 139–42; R. S. Humphreys, *Mu'awiya ibn Abi Sufyan: From Arabia to empire* (Oxford, 2006), pp. 43–53.

9 J. Wellhausen, *The Arab kingdom and its fall*, trans. M. G. Weir (Calcutta, 1927), pp. 131–3; H. Lammens, *Le califat de Yazid Ier* (Beirut, 1921), pp. 5–6, 103.

Mu'awiya used his Syrian base to pursue the war with Byzantium, dispatching expeditions into central Anatolia and Armenia almost every summer (and often during the winter). These expeditions were not aimed at permanent conquest and occupation, but they should not be regarded merely as glorified raiding parties.¹⁰ Rather, they represented a strategy of attrition, grinding down Byzantine military resources until a strike could be mounted against Constantinople itself. In addition to overland expeditions Mu'awiya opened a new front on the sea, and indeed he must be regarded as the founder of the Muslim navy. Partly this was a defensive move, since the Syrian coast suffered repeatedly from Byzantine naval raids throughout the 640s. Mu'awiya may also have been impressed by the Byzantine naval expedition against Alexandria in 645. That effort enjoyed only a brief success, but it both demonstrated the danger of leaving Byzantine naval power unchecked and suggested the possibilities that command of the sea might offer. Mu'awiya's initiative bore fruit almost from the outset, with lucrative raids against Cyprus in 649–50 and Rhodes in 653, and a spectacular victory by a combined Syrian and Egyptian fleet against the Byzantine navy (under the personal command of the emperor Constans II) in the battle of the Masts (655). The Syrian littoral was henceforth secured, and this would ultimately open the way to a resettlement of the coastal towns in Mu'awiya's later years.¹¹

Mu'awiya's aggressive stance against Byzantium was not mirrored in his dealings with the Christian populations of Syria and Mesopotamia, who of course constituted the overwhelming majority of his subjects. Although we have no way of making any systematic comparison between Byzantine and early Islamic tax assessments, and the situation may well have differed between one province and another, the oldest Syriac sources imply that they were moderate and relatively stable. Churches and monasteries were left unmolested, and the archaeological evidence (admittedly very difficult to

10 Anatolian expeditions: Abu Ja'far Muḥammad ibn Jarīr al Ṭabarī, *Ta'rikh al rusul wa l muluk*, ed. M. J. de Goeje et al., 15 vols. in 3 series (Leiden, 1879–1901), series I, pp. 2806–9, 2907, series II, pp. 16, 27, 67, 82, 84, 85, 86, 87, III, 157, 158, 163, 171, 173, 180, 181, 188; Baladhurī, *Futuh*, pp. 163–5, 178, 183–5, 197–8, 204; Theophanes, *The Chronicle of Theophanes Confessor*, trans. C. Mango and R. Scott (Oxford, 1997), pp. 479–82, 484, 486–90, 492–6; J. Wellhausen, 'Arab wars with the Byzantines in the Umayyad period', in M. Bonner (ed.), *Arab Byzantine relations in early Islamic times* (Burlington, VT, 2005); Humphreys, *Mu'awiya*, pp. 50–3, 58–60, 104–10.

11 Naval expeditions, Cyprus: al Ṭabarī, *Ta'rikh*, series I, pp. 2820–7, 2865, 2867–71, 2888–9, series II, pp. 67, 85, 86, 87, 158, 163, 173, 181; Baladhurī, *Futuh*, pp. 128, 152–4; Theophanes, *Chronicle*, pp. 478–9, 481–2, 493–5; Dionysius of Tell Mahrē, trans. in A. Palmer, S. Brock and R. Hoyland, *The seventh century in the West Syrian chronicles* (Liverpool, 1993), pp. 73–5, 179–80; Humphreys, *Mu'awiya*, pp. 53–8.

date and interpret) suggests that they continued to be built and maintained. Indeed, an early Christian source tells us that Mu'awiya restored the great church of Edessa, one of the finest in the region, when it was damaged in an earthquake in 679. Public worship was mostly unhindered, and the bishoprics and major churches were left in the hands of the confessions that controlled them when the Byzantines withdrew.¹²

The Monophysite and Nestorian churches were indeed better off under the new order, since Mu'awiya was determined to keep peace between the rival sects and refused to favour one against the others. For the first time Monophysites and Nestorians were free to appoint their own bishops and teach their doctrines without hindrance. A policy of evenhandedness was not easy to bring off, since tolerance was a strange and unwelcome concept to most Christians, but to a remarkable degree Mu'awiya and his sub governors made it work. (Sometimes Muslim troops had to be posted during church services to keep the peace.) On balance, it is little wonder that Syrian church men did not worry much about the 'Saracen heresy' during the early decades of Muslim rule.

As benign as Mu'awiya's rule might have seemed, however, the churches were now operating in a radically changed environment, and over time this would have significant effects. On the material level, bishops and monasteries were no longer supported by public revenues and imperial benefactions. Thenceforth they had to live from private gifts and endowments, and in the long term, as taxes bit harder and conversion to Islam took hold, such gifts would be a declining resource. The former imperial (Chalcedonian) Church suffered a greater immediate loss than the Monophysites and Nestorians, to be sure, but on some level all the churches were affected. If not subject to slow starvation, they were at least living in reduced circumstances. The administrative and judicial authority of the bishops, which was very extensive in Byzantine times, was certainly altered, but it is impossible to be precise. We can at least be sure that conflicts between Muslims and Christians, which must have been numerous, were now handled by Muslim officials. The symbolic impact of Muslim rule may have been even greater, for the new regime was no longer a Christian commonwealth, a providential vehicle of salvation. In a sense, as in the Roman empire before Constantine, Christians were again

12. S. Brock, 'North Mesopotamia in the late seventh century: Book xv of John Bar Penkaye's *Riṣ Melle'*, *JSAI*, 9 (1987), p. 61; Dionysius of Tell Mahré, trans. in Palmer, Brock and Hoyland, *Seventh century*, pp. 186–7, 195. Archaeological evidence reviewed in R. Schick, *The Christian communities of Palestine from Byzantine to Islamic rule: A historical and archaeological study*, *Studies in Late Antiquity and Early Islam* 2 (Princeton, 1995).

strangers in a strange land. Under such circumstances the goal of the Church was not to infuse the state with a divine purpose, but simply to survive.

In 656 Syria ceased to be just another province within the vast Islamic empire. For the next five years it would be, along with Iraq, one of the two axes of the great civil war that brought the nascent Islamic empire to the verge of ruin. When the caliph 'Uthman was killed by mutinous Egyptian troops in his own residence in Medina, his second cousin Mu'awiya was inevitably implicated in the crisis. Though at first he made no claims on his own behalf, he demanded justice for his murdered kinsman, and used this demand to manoeuvre 'Alī ibn Abī Ṭalib out of the caliphate in spite of initial support from the Kufan and Egyptian garrisons and many Medinan Companions. By July 660 Mu'awiya was in a position to advance his own claim to the caliphate. His adherents swore the oath of obedience to him in Jerusalem, where he visited the Holy Sepulchre and the grave of St Mary the Virgin – a striking act whose real purpose is a matter of conjecture, but which must have been meant to reassure his Christian subjects that he was not only head of the Muslim community, but their emperor and protector as well.¹³ His grip on the office was assured the following year when 'Alī was assassinated by a Kharijite, and even the Iraqis were at last compelled to recognise him as caliph.

Mu'awiya is commonly regarded as the founder of the first hereditary dynasty in Islam, the Umayyads. More important, however, was his decision bitterly but ineffectually resented by many Medinans – to remain in Syria, with Damascus as his administrative centre. Syria thus became the metropolis of a great empire for the first time since the Seleucids a millennium before. Mu'awiya acted partly for pragmatic reasons, since his power rested on the Arab tribes of Syria – in particular the Kalb, whom he had cultivated and nurtured for two decades. He could not possibly recreate such a support network in the Ḥijaz or anywhere else in the Islamic empire. But his decision not to return to Medina, the traditional and religiously sanctified capital, rested on broader calculations as well. He recognised that an empire spanning the entire Nile to Oxus region could not be governed from a remote oasis in the Arabian Peninsula, but only from within the urban agrarian heartland, where the main lines of commerce and communication intersected and where experienced administrators could be found. In many respects Damascus filled the bill admirably. It was close to the critical Byzantine frontier and centrally located between Iraq, Egypt, the Ḥijaz and the Mediterranean ports. Its

¹³ Mu'awiya's accession to the caliphate: Wellhausen, *Arab kingdom*, pp. 101–2, 134; Humphreys, *Mu'awiya*, pp. 83–4.

drawback was that it was only a medium sized city with limited resources in its immediate hinterland. Syria was a prosperous region, but it did not produce anything remotely approaching the tax revenues of Iraq and Egypt. Syria's structural limitations would only gradually come into play, however; whatever the causes of the fall of the Umayyads, a lack of adequate Syrian financial resources was not among them.

As caliph Mu'awiya largely continued the same policies in Syria that he had followed as governor, albeit on a larger scale. His central administration was of the most rudimentary kind – essentially a mechanism for maintaining communications with (and control over) the powerful provincial governors of Iraq, Egypt and the Hijaz. He almost certainly received some surplus revenues from Iraq and Egypt, but to a large degree he ran Syria (including payments to the nomadic tribesmen who constituted the core of his army) on the basis of its own resources. Syria was in a sense his personal domain, but it was divided into sub provinces (the famous *ajnad*, lit., 'army commands': originally Filastīn, al Urdunn, Dimashq and Ḥimṣ, with Qinnasrīn added in the north under his son Yazīd I), and these in turn into sub districts. No doubt there was some sort of centralised fiscal apparatus, but the only direct evidence from his reign (a few papyri from the Negev town of Nessana) suggests a highly localised system of tax assessment and collection: bi monthly requisitions issued by the district sub governor to indigenous local officials, ordering them to send specified provisions to troops under his command. In Syria the fiscal system as well as everyday economic life continued to rely on Byzantine (or imitation Byzantine) gold and bronze coinage. According to a contemporary Christian source Mu'awiya endeavoured to introduce a gold and silver coinage of his own early in his reign, but his coins were rejected because they lacked a cross – striking evidence both of the continuing prestige of Byzantium in Syria and of the strong Christian identity of its people.¹⁴

Perhaps Mu'awiya's main innovation was a systematic effort to repopulate the almost abandoned coastal cities through a mix of incentives (e.g. hereditary land grants) and compulsory population transfers. As governor he had established a community of Jews or Persians in Tripoli shortly after its conquest during 'Uthman's caliphate. Now he brought Persians, Malays and Djats from Iraq (especially the port city of Baṣra) to Antioch, Tyre and Acre. His decision to look so far afield for appropriate settlers is intriguing but hard to interpret.

¹⁴ C. J. Kraemer, *Excavations at Nessana*, vol. III: *The non literary papyri* (Princeton, 1958); Maronite Chronicle, in Palmer, Brock and Hoyland, *Seventh century*, p. 32; C. Foss, 'A Syrian coinage of Mu'awiya?', *Revue numismatique*, 158 (2002).

Possibly the indigenous population of Syria was too decimated by a century of violent turmoil to provide the needed colonists, or perhaps they simply refused to return to places that still seemed insecure. More likely, Mu'awiya simply did not trust them; as Christians they were all too likely to collaborate with Byzantine naval raids. Outsiders would be more reliable and easier to control. Whatever Mu'awiya's thinking, his resettlement policy represents the beginnings of an Umayyad effort to restore and develop the Syrian economy.

Ambitious in many ways, Mu'awiya was not a builder of monuments: his palace in Damascus elicited derisory remarks from a Byzantine embassy, he erected no major mosques, and only one or two rural residences. He may have cleared the debris from the Temple esplanade in Jerusalem and enhanced a primitive mosque (the first al Masjid al Aqsa) erected there by 'Umar, but the evidence for this is terse and hard to interpret.¹⁵ His most important contribution to Syria and Mesopotamia was security and public order, a welcome respite after the turbulent century between Justinian's later years and the end of Islam's first civil war. According to John Bar Penkaye, a Nestorian monk of Sinjar: 'Justice flourished in his time and there was great peace in the regions under his control; he allowed everyone to live as they wanted ... Once M'away [sic] had come to the throne, the peace throughout the land was such that we have never heard, either from our fathers or grandfathers or seen that there had ever been any like it.'¹⁶ John's words, written about a decade after Mu'awiya's passing in 680 at the height of a bitter civil war, may be nostalgic rather than descriptive, but they surely reflect an authentic memory of better times.

The Pax Mu'awiya ended soon enough after his death. The reign of his son and successor Yazid I (r. 680–3) left Syria and al Jazīra undisturbed, despite serious revolts in Iraq and the Hijaz. But when he died things rapidly came unglued. Most disturbing perhaps was the emergence of a bitter rivalry between the two main tribal groups in the country, Kalb in the centre and the newly settled Qays in the north along the Byzantine frontier. The rivalry did not stem from some atavistic quarrel. Rather, it was rooted in a profound political crisis. With the death of Yazid, and that of his young son Mu'awiya II a few months later, there was no viable candidate for the succession in the Sufyanid branch of the Umayyad house. At the same time 'Abd Allah ibn al Zubayr in the Hijaz now revived his bid for the caliphate, which Yazid's

15 B. Flusin, 'L'esplanade du temple à l'arrivée des arabes, d'après deux récits byzantins', in J. Raby and J. Johns (eds.), *Bayt al Maqdis: 'Abd al Malik's Jerusalem*, Oxford Studies in Islamic Art 9, part 1 (Oxford, 1992), pp. 17–32.

16 Brock, 'North Mesopotamia', p. 61.

forces had all but crushed. As the son of a prestigious Companion who had been closely affiliated with Abu Bakr and 'Umar, Ibn al Zubayr could attract a wide spectrum of followers. Lacking an acceptable Umayyad candidate, the Qaysī tribes of northern Syria joined his cause. Umayyad rule was on the verge of extinction when Marwan ibn al Ḥakam, second cousin to Mu'awiya I and almost eighty years old, emerged to rally the Kalb. Marwan and the Kalb confronted the Qays at Marj Raḥiṭ near Damascus (684) and won a decisive but bloody victory. Umayyad hopes (now represented by the Marwanid branch of the family) were saved, though eight years of desperate struggle would pass before they at last vindicated their claim to the caliphate. The Kalb retained their pre eminent place in the Umayyad structure of power, but the Qays were humiliated and embittered. Successive Umayyad caliphs strove to reconcile the Qays and their allies in other regions of the empire, but it was a difficult task, all the more as excessive deference to Qays would inevitably alienate Kalb. In the 740s the delicate balancing act finally collapsed, as rival contenders for power within the Umayyad house lined up with different tribal factions. The manipulation of tribal politics, which had been the original foundation of Umayyad power, ended by destroying it.¹⁷

Marwan ruled for less than a year, but his victory at Marj Raḥiṭ at least bequeathed a relatively secure position within Syria to his son and successor, 'Abd al Malik (r. 685–705). Only in 692 did 'Abd al Malik at last crush Ibn al Zubayr and impose his authority throughout the caliphate although the struggle against the Kharijites in Iraq took many years more but he did not wait for the final outcome of the struggle to begin instituting important changes in the regions he did control. The Nessana papyri suggest a much stricter tax regime by the late 680s, with rates severe enough to provoke protest delegations. In part such changes may reflect 'Abd al Malik's urgent need for cash to pay his troops in a period of crisis and constant warfare, but they also reflect the temperament of a state builder. Like Mu'awiya, 'Abd al Malik had to reconstruct an empire on the verge of dissolution, but too much had changed for him to rely simply on his predecessor's tools of conciliation, patronage and personal loyalty.¹⁸

'Abd al Malik's fiscal reforms were certainly instituted wherever he established his government, and they were continued if not intensified under his son

17 Tribal conflicts: Wellhausen, *Arab kingdom*, pp. 180–2, 202–12, 397–491 and *passim*; G. L. Hawting, *The first dynasty of Islam: The Umayyad caliphate, AD 661–750* (London and Sydney, 1986), pp. 53–5, 73–6 and *passim*; P. Crone, 'Were the Qays and Yemen of the Umayyad period political parties?', *Der Islam*, 71 (1994).

18 On 'Abd al Malik, see most recently C. Robinson, *'Abd al Malik* (Oxford, 2005); for 'Abd al Malik as a state builder, pp. 59–80, 105–21.

al Walīd (r. 705–15). Dionysius of Tell Mahrē (d. 846) comments that ‘this Walīd was a learned man. But he raised the taxes and increased the general suffering more than any of his predecessors.’ He describes the policy of the caliph’s brother Maslama more concretely: ‘Maslama’s first action on coming to Mesopotamia and taking over the governorship of all the Jazīra was to commission a survey of the arable land and a census of vineyards, orchards, livestock and human beings. They hung a leaden seal on each person’s neck.’¹⁹

In the early Islamic state taxpayers were by definition non Muslims, so the policies of ‘Abd al Malik and al Walīd were clearly aimed at the Christians of Syria and Mesopotamia. In addition, the caliphs began eroding the position of their Christian subjects in symbolic ways. Michael the Syrian (d. 1199, probably paraphrasing Dionysius) states that in about 696–7 ‘the Arab king ‘Abd al Malik decreed that crosses should be taken down and pigs slaughtered’.²⁰ That is, the visible signs of a Christian society were to be removed from public view, and Muslim dietary taboos were to be enforced on everyone. We do not know just what circumstances occasioned these decrees – possibly ‘Abd al Malik was seeking to curry favour among the more rigorously minded Muslims, for example – nor do we know to what degree they were actually enforced. Nevertheless, there is a change of tone. The coinage reform, which replaced the sign of the cross with the Muslim *shahada*, and the gradual institution of Arabic as the sole language of official administration, tended in the same direction. That is, the key words and symbols of Christian identity were gradually being removed from public life.

‘Abd al Malik’s most spectacular gesture was no doubt the building of the Dome of the Rock in 692. On one level he was following in Mu‘awiya’s footsteps some thirty years earlier by recognising the special sanctity of Jerusalem. But on another level this act demonstrates the striking difference between the policies of the two men. Mu‘awiya, for whatever reason, went out of his way to honour two Christian shrines dedicated to key doctrines of the faith – the virgin birth, and the crucifixion and resurrection. ‘Abd al Malik, in contrast, revived the Temple Mount, the holiest of Jewish sites. Moreover, the inscriptions inside the Dome of the Rock quite explicitly denounce the doctrine of the Trinity and proclaim that Islam had supplanted all other religions. A more forthright statement of the religious identity and

19 *Chronicle of 819* and Dionysius, both in Palmer, Brock and Hoyland, *Seventh century*, pp. 79, 209; C. Robinson, ‘Neck sealing in early Islam’, *JESHO*, 48 (2005).

20 Michael the Syrian, *Chronique de Michel le Syrien, patriarche jacobite d’Antioche (1166–1199)*, ed. and trans. J. B. Chabot, 4 vols. (Paris, 1899–1924), vol. II, p. 475; G. R. D. King, ‘Islam, iconoclasm, and the declaration of doctrine’, *BSOAS*, 48 (1985).

purpose of his empire, or of the reduced status that non Muslims (and Christians in particular) would have in it, is hard to imagine.²¹

Apart from its general ideological import, the Dome of the Rock also marks the beginning of the Islamisation of the Syrian landscape. Until 'Abd al Malik, the public monuments of Syria marked it as a Christian country – a point noted by the geographer al Muqaddasī in the mid fourth/tenth century, when he asked his uncle why al Walīd had squandered such immense sums on the Umayyad Mosque in Damascus. His uncle spoke directly to the point:

Al Walīd was right, and he was prompted to a worthy work. For he saw that Syria was a country long occupied by the Christians, and he noted the beautiful churches still belonging to them, so enchanting and so renowned for their splendor, like the Church of the Holy Sepulchre and the churches of Lydda and Edessa. So he sought to build for the Muslims a mosque that would be unique and a wonder to the world. Likewise, is it not obvious that 'Abd al Malik, seeing the grandeur and magnificence of the Dome of the Holy Sepulchre, was concerned lest it dazzle the thoughts of the Muslims, and thus he erected above the Rock the Dome now seen there?²²

In following up his father's initiative, al Walīd was not content with the mosque in Damascus. He continued 'Abd al Malik's emphasis on the Temple esplanade with al Aqṣa Mosque, and he also launched a programme of great imperial mosques throughout the caliphate. (The mosque in Damascus had involved razing the Church of St John the Baptist, but such 'conversions' were very rare in Umayyad times.) Sulayman (r. 715–17) was mostly preoccupied with the siege of Constantinople, but he found time to undertake the Great Mosque in Aleppo. Thereafter there was a pause for a few years, but the construction of new mosques was energetically pursued by Hisham (r. 724–43). Though the ones he erected were on a more modest and practical scale than the grand monuments of al Walīd, there were certainly a great many of them. By the end of the Umayyad dynasty Islam had already left a deep imprint on Syria, even if Christian monuments still predominated.

At least in its earlier phases the policy of Islamisation set in motion by 'Abd al Malik probably did not aim at encouraging conversion to Islam. The Umayyad state still rested (as it had under Mu'awiya) on a sharp distinction between an Arab Muslim ruling class and non Muslim tax paying subjects, even though that distinction was becoming difficult to maintain even by the

21 O. Grabar, *The formation of Islamic art* (New Haven, 1973), pp. 61–7 (though he hedges his conclusions in the revised edn, 1987), O. Grabar, *The shape of the holy: Early Islamic Jerusalem* (Princeton, 1996).

22 Grabar, *Formation* (1973), pp. 64–5 (translation slightly revised).

mid 680s. However, the Islamising and Arabicising reforms of 'Abd al Malik and al Walid certainly encouraged an increasing flow of converts in Iraq, and it is fair to assume a similar situation in Syria, though in the present state of research we know very little about it.

These tendencies were reinforced and consolidated by the policy initiatives of 'Umar ibn 'Abd al 'Azīz (r. 717–20), the brevity of whose reign belies its tremendous importance. The oldest Christian sources characterise him as 'a good man and a king more merciful than all those who had preceded him',²³ and state that 'as much honor and praise is bestowed on him by all, even foreigners, as ever has been offered to anyone in his lifetime holding the reins of power'.²⁴ That fits with his reputation among Muslim writers, who praised his piety, justice and commitment to equality for the heretofore despised and maltreated *mawālī*, the non Arab converts to Islam. But the story is more complex. Michael the Syrian (d. 1199, but citing much earlier sources) concedes his personal piety and uprightness, but asserts that he was hostile to Christians and pressured them in every way to adopt Islam. To encourage this, converts were exempted from the poll tax. At the same time, Christians were not permitted to bear witness against Muslims, serve as government officials or pray with loud voices, along with many other restrictions. Theophanes even claims that Christians who would not convert were put to death, but this is certainly erroneous.²⁵ 'Umar's decrees represented a major shift in Umayyad policy, an effort to marginalise the practice of Christianity. In principle (though as yet seldom in reality) Christianity was to be enclosed within the walls of home, church and monastery; public space would belong to Islam.

This tendency was further confirmed by the Iconoclast decree of Yazīd II (r. 720–4), who commanded the destruction of all images of animate beings – first and foremost Christian icons, of course – throughout the caliphate. Yazīd apparently died before the decree could be enforced, but it set the stage for the parallel decree issued by the Byzantine emperor Leo III in 726. Obviously the two decrees struck a chord among many Christians, for the Iconoclast Controversy in Syria was a bitter one, to which the widespread defacing of mosaics in Jordanian churches, sometimes repaired with clumsily executed vegetal or geometric motifs, bears eloquent witness. St John of Damascus's

²³ *Chronicle of 819*, in Palmer, Brock and Hoyland, *Seventh century*, p. 80.

²⁴ *Hispano Arab Chronicle* (Anon. *Chronicle 741*), trans. in R. Hoyland, *Seeing Islam as others saw it: A survey and evaluation of Christian, Jewish, and Zoroastrian writings on early Islam* (Princeton, 1997), p. 625.

²⁵ Michael the Syrian, *Chronique*, vol. II, p. 489; Theophanes, *Chronicle*, p. 550.

famous defence of religious images reflects local conditions as much as it does the theological quarrels in distant Constantinople. In any case Iconoclasm in Syria was a matter between Christians, in which the Muslim authorities were involved only in minor ways.

We might speculate that the Iconoclast Controversy demoralised some Syrian Christians and hence did something to encourage conversion to Islam. We do know at least that by the late second/eighth century Christian discourse in Syria and Iraq had moved to an apologetic register, a defence of Christian truths against the attacks of Muslim critics, and these apologetics were composed in Arabic i.e. in a language strongly inflected by Islamic scripture and religious discourse. We know also that no Syrian bishops attended the Council of Nicaea (787), which restored the veneration of icons. The Syrian churches would no longer have any role in the debates and controversies that embroiled Byzantine and Roman Christianity. These facts do not necessarily imply isolation or intellectual stagnation, to be sure. Apart from their sheer numbers, Syro Jazīran Christians could draw on the great theological tradition of their region. Down through the fifth/eleventh century, at least, Christian apologetics were conducted with growing ingenuity and sophistication. By the late second/eighth century, however, Syrian and Mesopotamian Christians were on their own; they had to explain and defend their faith and practice within a world whose cultural and intellectual parameters were increasingly fixed by Islam.

The trends sketched above continued to evolve during the long reign of Hisham (724–43), though he seems to have had a more sympathetic attitude towards Christianity than his two immediate predecessors. Even if his policies represented in themselves no real innovation, however, he pushed them vigorously, and they ended up by bringing about some important changes. The most important of these concerned the caliphate as a whole, but their effects were strongly felt in Syria and Mesopotamia. Hisham strove (with reasonable success for most of his reign) to maintain the balance between the great tribal factions of Muḍar, Yaman and Rabīʿa – or, in Syro Mesopotamian terms, Qays and Yemen (i.e. Kalb and the other Qudaʿa tribes). He was notorious for his unrelenting efforts to squeeze more money from his subjects. More important, however, was his resolution of the fiscal dilemma created by ʿUmar II's reforms in favour of the *mawālī*. Finally, he strove to reignite the project of imperial expansion pursued with such brilliant success by his father ʿAbd al Malik and his brother al Walīd.

The last of these was critical on an ideological as well as a purely political level, since conducting the *jihad* was a foundation stone of Umayyad

legitimacy. Unfortunately Hisham's *jihad* was at best a stalemate. There were occasional victories, but just as many defeats, some of them extremely serious. Nineteen years of warfare ended with almost no changes in the caliphate's frontiers, and this at an enormous cost in money and manpower. Although these wars were usually waged in places remote from Syria and Mesopotamia (except on the Byzantine and Armenian frontiers), they had a serious impact on these two regions, because Syrian and Mesopotamian troops were by far the most reliable and effective forces available to Hisham. As one military crisis or revolt succeeded another, he was compelled to send expeditionary forces recruited in Syria to deal with the situation, and often to remain there, hundreds of miles from home, in order to keep things patched together when the immediate emergency was past. These measures both depleted military manpower in Syria to an alarming degree and eroded the Syrian tribes' morale and loyalty to the regime. In brief, Hisham's *jihad* policy ended by subverting the chief bulwark of Umayyad rule since the days of Mu'awiya.²⁶

It is very hard to know the numbers involved in all this. Blankinship has estimated that Syria and Mesopotamia supplied about 175,000 and 75,000 men respectively out of the roughly 400,000 that made up the caliphal armies as a whole. The total number of troops is a reasonable one given the vast size of the caliphate, and it is roughly similar to the nominal strength of the Roman army in the fourth century.²⁷ However, the estimates for Syria seem very high in view of that region's limited fiscal resources, all the more as Syrian and Jazīran troops were drawn from widely scattered tribes in the interior steppe, not from densely settled garrison cities such as Kufa and Baṣra. However, these numbers do include the Syrian garrisons that came to be posted all over the empire – in Iraq, Khurasan, North Africa, even distant al Andalus – and presumably these garrisons were paid from local revenues. Moreover, Egypt was easily controlled from Damascus. Since it had only a small standing garrison, a substantial proportion of its revenues (which totalled at least twice those of Syria) could have been used to support Syria's tribesmen. Likewise, as the Arab tribesmen quartered in Iraq were progressively reduced to second line status after the rebellion of Ibn al Ash'ath in 701, an increasing

26 K. Y. Blankinship, *The end of the jihad state: The reign of Hisham ibn 'Abd al Malik and the collapse of the Umayyads* (Albany, 1994), pp. 230–6.

27 Ibid., pp. 82, 303, n. 38. Cf. W. Treadgold, *Byzantium and its army, 284–1081* (Palo Alto, CA, 1995), pp. 44–59. The Saljuqid vizier Nizam al Mulk gives 400,000 as the total number of troops available to Malikshah, around 1080, in an empire that stretched from Syria to Transoxania.

proportion of Iraq's lucrative tax receipts might have been redirected to Syria. At the current stage of research, however, all this can only be speculation.

In Syria itself, Hisham directed his attention to two very disparate areas: (1) the sponsorship (and of course control) of Islamic learning and thought; and (2) an extensive construction programme, with an emphasis on the interior steppe of Syria. As to the former, a concerted effort to define the theological doctrines and moral obligations of Islam had been rapidly developing among pious circles in several centres, especially Mecca, Medina, Baṣra and Kufa, since the end of the great civil war in the early 690s. Since the Umayyad caliphs claimed to be God's vicegerents on earth and the authoritative spokesmen for Islam, they could not stand aside from this effort, all the more as the Ḥijaz and Iraq had often been staging grounds for rebellions against the regime and were never well reconciled to it.

Umayyad Syria has usually been regarded as only a secondary centre of Islamic thought, but that judgement may rest more on the surviving sources which are overwhelmingly Iraqi and Medinan than on second/eighth century realities. Both 'Abd al Malik and 'Umar ibn 'Abd al 'Azīz, both of whom had spent many years in the Ḥijaz, were regarded as highly learned, and serious theological discourse in Islam may have begun (though the matter is disputed) with 'Abd al Malik's assertion of the dogma of predestination. Hisham was both severe in temperament and personally observant, and he actively cultivated such eminent scholars as Ibn Shihab al Zuhri (d. 742), Ma'mar ibn Rashid (d. 750?) and several others. Apart from such prominent individuals, the great biographical compilations of Ibn 'Asakir (d. 1176) and Ibn al 'Adīm (d. 1262) contain entries for many hundreds of learned figures who resided in Syria during the Umayyad period. A substantial majority – some three quarters – of those whose occupation is recorded held political, military or administrative offices, but since scholars were only beginning to emerge as an identifiable group, that fact should not be surprising.

Hisham's construction programme reveals a different facet of his rulership. He certainly was no innovator in this area, although things seemed to reach their apogee during his reign. In some cases we are dealing with alternate capitals. Thus Qinnasrīn, near the Byzantine frontier, was the regular residence of the otherwise polar opposites Yazīd I and 'Umar ibn 'Abd al 'Azīz. Hisham himself spent hardly any time in Damascus. His principal residence was al Ruṣafa south of the Euphrates, adjacent to the great Byzantine shrine city dedicated to St Sergius. Both Qinnasrīn and al Ruṣafa were close to Mesopotamia and to the northern frontier, and were probably chosen in part for strategic reasons.

It is, however, the still puzzling ‘desert castles’ (*quṣur*) that have attracted most attention.²⁸ Again, Hisham was not doing anything essentially new; he simply acted on a larger scale than his predecessors. Even Mu‘awiya preferred to spend as much time as he could in a rural residence outside the formal capital, Damascus – he particularly favoured Sinnabra near the southern shore of Lake Tiberias – and later caliphs and princes enthusiastically followed his lead. They expended great sums to build an extremely varied group of structures in the countryside, some very simple and some extremely large and elaborate ensembles. A few of these were placed in pleasant, well watered areas, such as the new town of ‘Anjar in the southern Bīqā‘ valley, or Hisham’s own winter palace of Khirbat al Mafjar in the Jordan valley near Jericho. The majority, however, were located on the edge of the steppe, or even far within it. What drove the Umayyads to such a fever of construction? Few now believe that it stemmed from a romantic nostalgia for the life of the desert. On the other hand, an idea first put forth by Sauvaget – that these ensembles represented large scale economic development projects – has recently come in for serious criticism. Unfortunately the extant monuments have almost no inscriptions, and there are very few direct references in our textual sources.

As things stand, it is probably best to recognise that they were meant to serve many different purposes – though often we can only guess at just what the builders had in mind. Some, like Qaṣr al Kharana, were probably no more than way stations in the desert for soldiers and officials as they moved across the steppe from one locale to another. Others might have served as gathering places for the provincial governors or even the caliph to renew bonds of loyalty and negotiate terms of service with the tribal leaders, and to distribute pay and bonuses to the tribesmen who made up Syria’s armies. Qaṣr al Ḥallabat may be a case in point. Some were certainly retreats, where the princes and their entourages could get away from the health hazards, congestion and prying eyes of the cities and enjoy the princely pleasures of hunting, music, wine and the company of singing girls. Qaṣayr ‘Amra, with its small but wonderfully painted reception hall and bath, almost surely belongs in this group.

Finally, there were indeed some very ambitious ensembles that clearly did involve a major investment in irrigation, agriculture and horticulture, and even permanent settlement. The clearest and most impressive example is

28 G. Fowden, *Qaṣayr ‘Amra: Art and the Umayyad elite in Late Antique Syria* (Berkeley, 2004), pp. 1–30, reviews the large but uneven literature.

Qaṣr al Ḥayr al Sharqī, far out in the desert north east of Palmyra, and clearly built at Hisham's direction.²⁹ This complex encloses some 10 square kilometres. Two large and handsomely constructed walled enclosures – probably a palace and a vast residential compound – were embedded in the midst of numerous villages, elaborate irrigation works, agricultural and pasture lands, etc. The palace, one assumes, would have been occupied only when the caliph or governor was in residence. The residential compound, with its impressive mosque and carefully laid out apartment complexes, might have had a permanent garrison or police force, but space must have been reserved for the entourages accompanying the caliph or governor during their occasional visits. Whether Qaṣr al Ḥayr al Sharqī represented a serious economic investment, or whether it was chiefly meant to assert government control over the nomadic tribesmen in this remote part of the steppe, is still open to debate. Whatever questions there are in regard to specific structures, however, the 'desert castles' show that the Umayyads viewed the Syrian interior as a vital part of their domain. Their active engagement in the region on many levels ensured their cultural, political and economic ties with the tribesmen who were the foundation of their power.

The apparently abrupt collapse of the Umayyad regime after the death of Hisham in 743 was in part connected with antagonisms and fissures within the ruling house, in part with the last caliphs' failure to manage tensions between the Qays and Yaman tribal factions in Syria itself. In the end these tensions led to the total triumph of Qays under the leadership of the governor of Mesopotamia, Marwan ibn Muḥammad, and thus to the alienation of Kalb, the dynasty's traditional bulwark.³⁰ (As noted above, Kalb's loyalties may already have been severely eroded by Hisham's unending wars on the remote frontiers of the caliphate.) Marwan made Ḥarran his principal residence, and his caliphate was certainly not welcomed by the Syrian Arabs. He was compelled to reduce Homs and Damascus to obedience by force. When the 'Abbasid armies crossed the Euphrates into Syria in 750 after Marwan's forces were shattered at the Zab, they faced surprisingly feeble resistance from the Syrians, demoralised as they were by Marwan's harshness and the internal disintegration of the Umayyad family.

29 O. Grabar, R. Holod, J. Knustad and W. Trousedale, *City in the desert: Qasr al Hayr East*, 2 vols. (Cambridge, MA, 1978); D. Gènequand, 'The early Islamic settlement in the Syrian steppe: A new look at Umayyad and medieval Qasr al Hayr al Sharqi (Syria), *al 'Usur al Wusta*, 17 (2005).

30 Wellhausen, *Arab kingdom*, pp. 377–80.

‘Abbasid Syria

What changes did the new regime bring to Syria? It was long argued that the ‘Abbasid victory meant that Syria was reduced to the status of a minor, though sometimes troublesome, province. Various facts do seem to favour this interpretation. First of all, the capital was moved to Iraq, a far richer region than Syria, and the burgeoning new metropolis of Baghdad rapidly eclipsed Damascus in size and wealth. The great opportunities for land speculation and commercial agriculture were now in Iraq. Second, the ‘Abbasids took bloody vengeance on as many princes of the Umayyad house as they could reach. Though they did not succeed in liquidating them all, they did eradicate much of the propertied elite that had sustained Syrian prosperity during the first half of the second/eighth century. Third, the Syrian Arabs were progressively demobilised, beginning under al Maṣṣur (r. 754–75) and ending with the reign of al Ma’mun (813–33). As their names were struck off the army registers they lost an irreplaceable source of income, and were driven back into the traditional poverty of pastoral nomadism.

These arguments have merit, but they overlook some factors and exaggerate others. First of all, calls for a return to Umayyad rule evoked a very shallow response; the ‘Abbasids had no difficulty in suppressing a series of revolts by various Umayyad (or pseudo Umayyad) pretenders in the early 750s. Most of these revolts, however, should be seen as struggles by Yaman and Kalb tribesmen to reclaim lost military status and financial privileges, or even (as with the uprising led by Abu Ḥarb al Mubārqa’ in 841) as simple peasant revolts. In general, challenges to central power in ‘Abbasid Syria were no different from those in any other province of the caliphate; they stemmed from ambitious provincial governors, dissatisfied urban notables and tribal leaders, local factionalism, and rural banditry. A more serious cluster of revolts during the 810s displayed a brief outbreak of millenarianism and Umayyad legitimism, but these events reflected the crisis of ‘Abbasid authority during the civil war between al Amīn and al Ma’mun. None of these outbreaks posed a serious threat to ‘Abbasid rule.³¹

The ‘Abbasids in fact did not regard Syria as a minor province; for more than half a century at least major parts of it were held as an apanage by one branch of the new ruling house.³² The first governor was ‘Abd Allāh ibn ‘Alī,

31 P. M. Cobb, *White banners: Contention in Abbasid Syria, 750–880* (Albany, 2001), argument summarised pp. 125–36.

32 H. Kennedy, *The early Abbasid caliphate: A political history* (London and Sydney, 1981), pp. 48–50, 74–5, 168–9.

the powerful uncle of al Saffāḥ and al Maṣṣūr who had led the victorious 'Abbasid armies into Syria. When 'Abd Allah was removed from the picture after his failed *coup d'état* against al Maṣṣūr, Syria was assigned to another uncle, Ṣāliḥ ibn 'Alī, and remained in his descendants' hands until 803. Ṣāliḥ took over many of the Umayyad estates (including, no doubt, the desert castles), and apparently made new investments of his own in northern Syria. To legitimise his position he even married the widow of Marwan II, the last Umayyad caliph. Whatever her feelings about the matter may have been, the marriage was probably advantageous for her as well. His sons Faḍl and 'Abd al Malik (the latter's mother was Marwan's former wife) continued in the same way, and 'Abd al Malik ibn Ṣāliḥ was highly influential at Harun al Rashīd's court. Finally, Ṣāliḥ inherited the Umayyad mission of pursuing the *jihad* against Byzantium. In addition to leading numerous campaigns into Anatolia, he rebuilt a number of fortresses in Cilicia and the Taurus that had been lost or destroyed in the Byzantine counter offensives under Constantine V (r. 741–75): Mar'ash, al Maṣṣīṣa (Mopsuestia), Malatya (Melitene) and Adana.

The commitment of Ṣāliḥ ibn 'Alī and his family to the region was echoed in the career of Harun al Rashīd (r. 786–809), both before and after he became caliph. From 796 to 808 Harun resided mainly at Raqqa on the Euphrates, not far from Hisham's old capital of al Ruṣāfa, partly because he disliked Baghdad and partly because of his personal commitment to the Byzantine *jihad*. He strove to distinguish himself as the *ghazī* caliph – the first caliph to lead troops against the infidel. In this framing of his public persona we may well detect the influence of his Syrian cousins Faḍl and 'Abd al Malik.³³ Harun's interest in the Byzantine frontier was maintained at least sporadically by two of his sons. Al Ma'mun (r. 813–33) spent the last three years of his caliphate there, and died at Tarsus. Al Mu'taṣim (r. 833–42) devoted most of his reign to building his new capital at Samarra' and to quashing rebellions in Iraq and north western Iran, but in 838 he led a triumphant expedition against Amorion. However, this would be the last major offensive against the Byzantines by any Muslim ruler for more than a century.

Archaeological evidence supports the textual sources. Recent excavations and redatings of previously studied sites indicate that many Umayyad buildings and ensembles remained inhabited and economically active down into the early or mid third/ninth century, well over half a century after the fall of

33 M. Bonner, *Aristocratic violence and holy war: Studies in the jihad and the Arab Byzantine frontier* (New Haven, 1996), pp. 88–9, 99–106.

the Umayyads. Only then do we see clear signs of abandonment and impoverishment. Even some of the Christian churches in Jordan (most strikingly St Stephen's at Umm al Raṣaṣ near Ma'daba) show signs of embellishment and new construction in the first decades of 'Abbasid rule, though by this time a distinctly more hostile and restrictive attitude towards the old religion was growing up among Muslim officials and scholars.³⁴

In the struggle against Byzantium the 'Abbasids significantly reshaped the army in northern Syria and the Thughur (i.e. the military districts along the Byzantine frontier, established by Harun, and stretching from Tarsus in the west to Samosata in the east), by stationing there a substantial number of Khurasanī troops, the so called *abna' al dawla* who constituted the core of the caliphal army.³⁵ The Khurasanī forces supplemented rather than replaced the Arab tribesmen (mostly from Qays) who had been the mainstay of the Umayyad armies in the region. There is no basis on which to estimate the proportion of Khurasanī to Syrian troops, but it seems likely that the Syrian tribesmen (i.e. the former Umayyad army) remained in the majority. Nor did the new Khurasanī forces represent any fundamental ethnic change, since many were ethnic Arabs drawn by the Umayyads from the Iraqi and Syrian armies and stationed as garrison forces in north eastern Iran over a period of several decades. Still, they were newcomers to northern Syria and represented a new set of interests and ambitions. At the very least they kept the existing Syrian tribesmen under close surveillance, to ensure their loyalty to the new regime. The old Umayyad forces were still crucial to the job of maintaining the frontiers, but they were relegated to second line status and some were struck off the official registers. Likewise, the senior commanders in the region were now all drawn from the *abna' al dawla* as well.

These changes did not greatly affect 'Abbasid policy on the Byzantine frontier. After the catastrophic failure of the siege of Constantinople in 717–18 the Umayyads had been content to maintain a stalemate. They could launch very destructive raids deep into Anatolia during the summer expeditions, but they never tried to expand their holdings in a permanent way, or even resettle their side of the half abandoned frontier zone. The first three 'Abbasid caliphs followed the same pattern: the summer expeditions were regarded as important, but they were not expected to lead to permanent conquests. Moreover, under the emperor Constantine V the Byzantine army was tenacious and

34 J. Magness, *The archaeology of the early Islamic settlement in Palestine* (Winona Lake, IN, 2003).

35 The following paragraphs are based largely on Bonner, *Aristocratic violence*, pp. 56–68, 85–92, 107–9, 135–56.

effective. With Harun al Rashīd (r. 786–809) there was, as noted above, a new emphasis on the Byzantine frontier. Harun's motives are not certain. He too did not aim at permanent conquest (although his reign fell in a period of Byzantine political and military disarray) and so from a strategic point of view he was simply repeating a policy of limited war and stalemate. It has been argued that he was striving for legitimacy. He had after all come to the throne via the assassination of his elder brother, and even though he was not personally implicated in this event, he was inevitably tainted by it. He could thus demonstrate his right to rule the Muslims only by taking personal command of armies of Islam and leading them against the greatest infidel power, or at least symbolically the most important one.

The major social, religious and cultural changes on the Byzantine frontier during the period 750–861 resulted from a spontaneous flow of immigrants towards that frontier – immigrants motivated by the desire for *jihad*, in the conviction that full obedience to God's commandments required every believer to undertake the struggle against the infidel. The caliphs certainly attached themselves to this process and encouraged it; especially important was the restoration and refortification of Tarsus after 786. Still, it is hard to see it as a consciously planned policy. Even those immigrants who did not personally take up arms felt the need to live in a region where the confrontation between Belief and Infidelity was stark and immediate. In the century after 750 these immigrants created the first real Muslim community along the frontier, a community of merchants, artisans, scholars – people whose life was anchored in the mosque and marketplace, so to speak. Nothing of the sort existed there before that time. The indigenous populace of the towns and villages must still have been solidly Christian, albeit much diminished and impoverished by the endemic frontier warfare of the previous century. Muslims were present only as administrators and landowners (much the same thing), scattered fortress garrisons and nomadic tribes in the adjoining steppe. So for the Syrian and Cilician towns north of Antioch, the 'Abbasid revolution did bring about something truly new.

Where did these Muslim immigrants come from? Among those few whose origins we can identify with certainty, the great majority came from two regions: Iraq and Khurasan. Very few came from Egypt, the Hijaz, or even Damascus and central Syria. The Khurasanīs included the famous ascetic Ibrāhīm ibn Adham (d. 777), who developed a large following in northern Syria, and the scholar Ibn al Mubarak (d. 802), whose *Kitāb al-jihād* (more a collection of *ḥadīth* on martyrdom than a treatise on warfare) is the oldest extant work in this genre. Among the Iraqīs, Aḥmad ibn Ḥanbal is a crucial

figure, since he was imprisoned in Tarsus by al Ma'mun for refusing to agree that the Qur'an was created. The number of scholars in the Byzantine frontier who are presented as his followers or disciples is remarkable but of course his austerity, traditionalism, absolute commitment to principle and militant piety were a perfect match for the ethos of that region.

The Iraqi migration to the frontier seems more a puzzle than the Khurasanī migration. Iraq, after all, was not a frontier zone and presumably did not breed the same frontier ethos. However, we might surmise that many Iraqi scholars of a particularly ascetic, militant character wanted to get away from the stifling, corrupting presence of the 'Abbasid court, and perhaps from the 'hothouse' academic atmosphere of Baṣra and Kufa. Possibly the Islamic scholarship of the Byzantine frontier (with its emphasis on *ḥadīth* and *furu' al fiqh*) was rooted in Iraq both the migration of Iraqi scholars to the frontier and the travels of frontier scholars to Iraq for study. On the other hand, the peculiar militancy and austerity of Islam in the Thughur were largely owed to Khurasanī immigrants.

Developments in northern Syria and Mesopotamia can thus be seen as a natural outgrowth of processes already under way in Umayyad times. That is much less true of central Syria (Homs and Damascus) and Palestine, however. Especially by the mid third/ninth century, textual and archaeological evidence points to economic decline, some degree of cultural stagnation (especially after the death of the eminent jurist al Awza'ī in 777) and a climate of social tension, expressed in repeated revolts and social disturbances.³⁶

Although Christians probably remained a majority in the villages and small towns throughout Syria and Mesopotamia throughout the third/ninth century, and some major centres such as Edessa (Ar. Ruha) and Antioch were still predominantly Christian, Islam was now gaining converts rapidly and making its presence felt everywhere. By this time most of the once Christian Arab tribes – Kalb, Tanukh, even much of stubborn Taghlib – had gone over to Islam. As we have seen, the cities and fortresses of the Thughur were attracting a strong flow of ardently Muslim immigrants. In central Syria, as well as Palestine and Jordan, Muslims were an important part of the social and demographic landscape from the 630s on. They constituted the ruling elite in the major towns, especially the political administrative centres of Damascus and Homs, and they were densely interwoven with the native Christian

36 M. Abiad, *Culture et éducation arabo islamiques au Šam pendant les trois premiers siècles de l'Islam, d'après Ta'riḫ madīnat Dimasq d'Ibn 'Asakir (499/1105–571/1176)* (Damascus, 1981), pp. 155–207; Cobb, *White banners*, pp. 34–42, 92–102, 116–124.

populations in the villages and small towns along the edge of the interior steppe. Just from the fact of constant interaction they would exert a certain pressure and influence on Christian communities in those regions. By the second/eighth century, if not earlier, Muslims were permeating smaller cities such as Jerash. This close intermingling of Christian and Muslim populations, combined with the conversion of most nomadic tribesmen to Islam and the strongly pro Islamic policies of the later Marwanids and 'Abbasids, do much to explain the trend of conversion to Islam in the districts between Homs and the Negev. A further element would be the fact that this part of Syria Palestine was largely Chalcedonian. The Chalcedonian leadership had in effect been decapitated during the conquests, and the Church's official Greek language was unintelligible to most of the faithful. The capacity of the former imperial Church to shelter and nurture its flock was thus gravely weakened.

In the north the Thughur and the Jazīran Armenian borderlands east of the Euphrates things were quite different. The new Muslim settlers there were not much concerned with the established Christian populations and seem to have interacted with them only in limited, though rather destructive, ways e.g. foraging military expeditions, harsh tax collections etc. For that reason the old Christian communities, especially those that were somewhat out of the way of armies marching back and forth, could continue their life much as before. These districts were heavily Monophysite. Here the clergy and monks shared a language (Syriac or Armenian) and common ethnic origins with their flock, so the close knit ties of pre Islamic times were not broken or strained by the conquests. Likewise, Monophysite ecclesiastics might well feel liberated by the disappearance of Roman rule, as witnessed by the oft cited comment of Dionysius of Tell Mahré: 'When [God] saw that the measure of the Romans' sins was overflowing and that they were committing every sort of crime against our people and our churches ... He stirred up the Sons of Ishmael and enticed them hither from their southern land ... It was by bargaining with them that we secured our deliverance. This was no small gain, to be rescued from Roman imperial oppression.'³⁷ So long as the Muslim authorities were tolerant or indifferent, the position of Christianity seemed strong. As we have seen, however, Muslim tolerance grew narrower in late Umayyad and especially 'Abbasid times, and fiscal exactions grew more severe.

'Abbasid fiscal policy was initially moderate, and northern Mesopotamia seems to have been very prosperous during these years. However, in 773, near

³⁷ Dionysius, in Palmer, Brock and Hoyland, *Seventh century*, p. 141.

the end of al Manṣūr's reign, he named a new governor for the province, one Musa ibn Muṣ'ab, whose brutality, extreme demands and arbitrary assessments became a byword.³⁸ He was at least not discriminatory, since his agents pursued Arab Muslim landowners with almost the same ferocity as they did Christians. He held office only for a few years, so it is hard to know whether his actions did any long term damage. In any case, it must have been clear to the Christians of Mesopotamia how vulnerable they were to sudden shifts in government policy. From these things, and from a growing Muslim population, the churches could not insulate their people or even always protect their own interests. The trend of conversion to Islam would be much slower than in the south, the pockets of Christian believers would remain much larger. But here too a process was under way that would in the long run sap the churches of their vitality and erode the loyalty and confidence of their members, even though the full impact of that process would only be felt with the coming of the Turkomans in the fifth/eleventh century and the Crusades in the period following.

Some aspects of the problem are visible in the fate of the Greek and Syriac languages. Language change is a problem in its own right and does not explain the rise of Islam, since it was always perfectly possible to be a Muslim without speaking Arabic (as in Iran or the Berber highlands), or to become an Arabic speaker without becoming also a Muslim (as with the Christians and Jews of Egypt and the Fertile Crescent). Nevertheless, the processes of Arabicisation and Islamisation run in parallel, and language change may reveal important aspects of religious identity. It was the Chalcedonians (or Melkites) of central Syria and Palestine who first adopted Arabic as their primary vehicle of literary expression.³⁹ By the end of the second/eighth century Greek had almost disappeared as a literary, scientific and theological language in Syria and Palestine – an astonishing collapse in view of Syria's role in Patristic and Late Antique writing. Even in early Islamic times one finds such names as Anastasius of Sinai, St John of Damascus, George Syncellus and Theodore Abu Qurra. But the writings of this last figure tell a story: Theodore Abu Qurra was thoroughly at home in Greek, and yet by the 780s he found it more useful to

38 *Chronicle of Zuqnin*, parts 3 and 4, trans. Amir Harrak (Toronto, 1999), pp. 215, 223ff.; C. Cahen, 'Fiscalité, propriété, antagonismes sociaux en Haute Mésopotamie au temps des premiers 'Abbasides, d'après Denys de Tell Mahré', *Arabica*, 1 (1954); C. Robinson, *Empire and elites after the Muslim conquest: The transformation of northern Mesopotamia* (Cambridge, 2000), pp. 156–8.

39 S. Griffith, 'The Gospel in Arabic: An inquiry into its appearance in the first Abbasid century', *Oriens Christianus*, 69 (1985), pp. 160–7.

compose his theological treatises in Arabic. By that time the first language even of educated Christians in Palestine, including monks and lower clergy, was clearly Arabic. A similar process was under way in Iraq, as witnessed in the famous dialogue between the Nestorian Catholicos Timothy I and the caliph al Mahdī (r. 775–85).⁴⁰

Syriac enjoyed a much longer career, at least in Mesopotamia. But elsewhere it too began to fade quite early on. Central and northern Syria retained Aramaic speech somewhat longer than Palestine, but the appearance of Agapius of Manbij's chronicle in Arabic around 940 demonstrates that by then Arabic had become the language of literate Chalcedonians in that region as well. In Mesopotamia Syriac remained a living tongue on every level well into the third/ninth century, as witnessed by the great chronicle of Dionysius of Tell Mahré (d. 846), though some time thereafter it slowly began to fade. By the sixth/twelfth century Syriac had clearly fallen out of use outside the monasteries and the liturgy, save in isolated regions such as Ṭur 'Abdīn. The late sixth/twelfth and seventh/thirteenth centuries saw a brief literary renaissance, but the last flourish of literary production came from Gregory Abu al Faraj (Bar Hebraeus, d. 1283), a converted Jew for whom Syriac was clearly a grammar book language, and who also wrote in Arabic.

Later 'Abbasid Syria

In the late third/ninth century Syria suddenly entered on an era of sustained turbulence, in common with many parts of the Islamic world. The assassination of the caliph al Mutawakkil (r. 847–61) and the temporary seizure of power by the Turkish troops of Samarra' opened a period of political devolution, during which provincial governors or self-made warlords were able to assert control of broad territories within the caliphate. For the most part the new rulers maintained formal obeisance to the caliphs, but they had a free hand to run the territories they had seized. Thus in 868 Egypt fell into the hands of its governor, Aḥmad ibn Ṭulun (r. 868–84), himself one of the Samarra' Turks, and by 882 he had brought most of Syria under his control. In 890 his son and successor Khumarawayh (r. 884–96) occupied much of al Jazīra as well as the strategic frontier city of Tarsus. For the first time in Islam, but hardly the last, Syria was ruled (in a manner of speaking) from Egypt. The Ṭulunid interlude was a brief one, since 'Abbasid forces

⁴⁰ Dialogue of Timothy and al Mahdī: A. Mingana (ed. and trans.), 'The apology of Timothy the Patriarch before the caliph Mahdī', *Woodbrooke Studies*, 2 (Cambridge, 1928).

reoccupied Syria in 903 and Egypt two years later, and there is no reason to think that the Ṭulunids had attempted to alter established fiscal and administrative patterns there.

Far graver issues were posed by the Ismaʿīlī revolt at the beginning of the fourth/tenth century. During the 870s a clandestine revolutionary movement emerged in Iraq which aimed at overthrowing the ʿAbbasids and replacing them with an imam descended from ʿAlī ibn Abī Ṭalib through Muḥammad ibn Ismaʿīl ibn Jaʿfar al-Šādiq, a shadowy figure of whom we know nothing save his name, and who probably died some time around 800. The Ismaʿīlīs quickly gained followers in many parts of the Islamic world – Iraq, northern and eastern Iran, Yemen and Syria – but suffered a grave crisis in 899 when one of their leaders, ʿUbayd Allah (residing in the small Syrian town of Salamiyya) proclaimed that he himself was the awaited *imam*. His claims were accepted by some – enough to allow him to found the Faṭimid dynasty, which governed North Africa and then Egypt from 909 until 1171. But they were violently rejected by another Ismaʿīlī faction, the Qaramiṭa (also called Carmathians), so named after their chief, Ḥamdān Qarmāṭ. Although the Qaramiṭa had their greatest long term impact in southern Iraq and eastern Arabia, where they would be a major political and military force into the eleventh century, they first exploded onto the scene in Syria.⁴¹ Especially in its earlier years, the movement was extremely fluid, with cross cutting alliances and rivalries that are almost impossible to trace. The Qaramiṭa were in fact not a single sect, but rather a congeries of Ismaʿīlī factions who rejected the claims of ʿUbayd Allah and his Faṭimid successors.

One branch of the movement, directed by a man named Zikrawayh and variously connected both with ʿUbayd Allah and the Qaramiṭa, succeeded in converting several sections of the Kalb tribe to its cause. Zikrawayh himself remained in Iraq, but he sent his newly recruited forces to lay siege to Damascus in 903. They failed to capture it, but, nothing daunted, turned on the other cities of Syria. Aleppo also fended them off; however, they did seize Homs, Hama and several other towns, though they did not try to occupy them permanently. In 906 Adhriʿat and Bušra were sacked by Zikrawayh's men, who then attacked Damascus for a second time, again without success. At this point Zikrawayh turned his attention away from Syria and towards the more crucial arena of Iraq. Brief successes there, including the massacre of an Iranian pilgrimage caravan returning from Mecca, soon ended with

⁴¹ W. Madelung, 'Qarmāṭī', *El2*, vol. IV, pp. 660–5; W. Madelung, 'Fatimiden und Bahrainqarmaten', *Der Islam*, 34 (1959).

Zikrawayh's own death in battle in 907. With this event the Isma'īlī revolt in Syria faded away. The leadership of the revolt had lain with townsmen, largely Iraqi in origin, but (as in many areas) its followers were largely recruited among Bedouin tribesmen. It is impossible to gauge the depth and character of the latter's commitment to Isma'īlism. Only the Kalb seem to have been brought into the Isma'īlī orbit and, with two minor exceptions, none of the major tribal revolts of the mid fourth/tenth century can be linked to this movement.

The definitive collapse of 'Abbasid power in the 920s and 930s led to a new local dynasty centred in Egypt but with Syrian ambitions. The Ikhshīdīd era (935–69) was likewise brief and troubled, and they were never able to extend their control much beyond Damascus. Northern Syria (Homs and Aleppo), the Thughur and western Mesopotamia instead fell in 947 to Sayf al Dawla 'Alī ibn Abī al Hayja' ibn Ḥamdan, a brilliant young officer who had previously made his career in the maelstrom of caliphal politics in Iraq. By the mid 940s this vast region was in effect a power vacuum, and Sayf al Dawla had no difficulty in seizing it from the Ikhshīdīds. His elder brother Naṣir al Dawla had been trying (with uneven success) to establish his own principality in Mosul since the mid 930s, and to some degree Sayf al Dawla was able to draw on his brother's resources and position. But while Sayf al Dawla was in principle the junior partner in the Ḥamdanid enterprise, he quickly established himself as a far more effective and prestigious ruler.⁴² The extent of his territories led Sayf al Dawla to establish two capitals, Aleppo in the west and Mayyafariqīn (modern Silvan) in the north east. Until this time both had been minor cities; thenceforth both would become important political centres, and Aleppo the most prominent city in northern Syria. Sayf al Dawla devoted great efforts to fortifying and embellishing both towns, and a number of major monuments date from his reign. Given the nature of the times, he of course focused on the defences of the two cities, but a fine palace outside Aleppo, along with gardens and a new aqueduct, indicate his intentions to make a showpiece of his Syrian capital.

Sayf al Dawla's personal fame rests on two things: his indefatigable though ultimately disastrous warfare against the Byzantines; and the brilliant circle of poets, scholars and thinkers whom he brought to Aleppo. These were a remarkable group: the poets Abu Firas (Sayf al Dawla's cousin) and al Mutanabbī, the preacher and rhetorician Ibn Nubata, the philosopher

42 M. Canard, *Histoire de la dynastie des Ḥ'amdānides de Djazira et de Syrie* (Algiers, 1951); but now see T. Bianquis, 'Sayf al Dawla', *EL2*, vol. IX, pp. 103–10.

al Farabī (admittedly very late in his life) and many others of only moderately less attainment. Though a soldier by training and temperament, Sayf al Dawla enjoyed intellectual debates on all subjects as well as the verbal display of court poetry. In his time Aleppo could certainly have held its own with any court in Renaissance Italy.

Sayf al Dawla was himself a Shī'ite (of the Twelver school), and he encouraged Shī'ite observance in his domains, which had until this time been quite solidly Sunnī and traditionalist in outlook. Beginning in the mid fourth/tenth century, however, Shī'ism would strike root in northern Syria, and ultimately gain the wide popular following it had there by the sixth/twelfth century. Whether this is due largely to Sayf al Dawla's efforts, or can also be connected in some way with currents of revolutionary Isma'ilism in Syria during this period, is open to debate. Sayf al Dawla's religious initiatives seem broadly similar to those of the Buyids in Iraq during the same period, and Buyid patronage of Twelver Shī'ism unquestionably had an important long term impact on the development of this sect.

Sayf al Dawla had an unusual ethnic background in a period when most of the warlords of the Nile to Oxus region were of Turkish or Iranian descent, for he traced his ancestry to the Arab tribe of Taghlib in northern Iraq (though he may have had Kurdish connections as well). His background surely aided him in asserting control over the various Arab tribes of central and northern Syria and in establishing effective relations with them. On the other hand, it required a decade of negotiation and fighting, and the repression of a major revolt in 955, before this task was really completed. After 955 he was able to rely on the support of the Banu Kilab, the most powerful tribe still remaining in northern Syria. However, Sayf al Dawla did not use Bedouin tribesmen as the core of his army. Rather, he relied on the same mix as everyone else in this period: Daylamī infantry and Turkish mounted archers, along with Arab auxiliary cavalry and Sudanese spearmen.

Sayf al Dawla was a soldier of undoubted courage and skill, as well as a resourceful commander. Perhaps inspired by the *ghazī* mentality of northern Syria and the Thughur, he was deeply committed to the *jihad* against Byzantium. It was his misfortune to live in a time when the resurgent Byzantines were threatening the Muslims' hard won positions, not only in Cilicia and the Taurus mountains, but throughout all northern Syria. Sayf al Dawla's forces more than held their own in the early years of his reign. After 960, however, he had to face generals such as Nicephorus Phocas and John Tzimiskes. In 962 Nicephorus overwhelmed Sayf al Dawla's capital, Aleppo, and pillaged the city, though fortunately he did not try to retain it. In 963 the

ferocious John Tzimiskes obliterated Sayf al Dawla's army near Adana. Worst of all, in 964 5 al Maṣṣīṣa and Tarsus fell to the Byzantines, and the Muslim inhabitants of Cilicia were forced to evacuate the region. The geographer Ibn Ḥawqal, writing about 980, laments the perilous situation of the Muslims in northern Syria and the Thughur. Many, he points out, are now under Byzantine rule; compelled to live in humiliation and pay a heavy capitation, it cannot be long before they give up their religion and go over to Christianity.⁴³

Two years after the Byzantine conquest of Cilicia (967) Sayf al Dawla died, after suffering a long, debilitating illness. In spite of the dire circumstances, however, he was able to pass Aleppo on to his son Sa'd al Dawla Sharif. The dynasty endured another forty years, perhaps because its very weakness made it useful to its enemies, the Byzantines and the rising power of the Faṭimids.

The extraordinary political instability and periodic violence of fourth/tenth century Syria and Mesopotamia would naturally lead us to suppose that the negative economic trends of the third/ninth century must have continued, if not intensified. That is not necessarily the case, however, at least not everywhere. Travellers and geographers such as Ibn Ḥawqal and al Muqaddasi, who had detailed, first hand knowledge of this region, do not give us a bleak picture of the towns and countryside, apart from the war ravaged Byzantine frontier. In their portrayal the cities seem active and prosperous, while the land is actively cultivated with a wide range of crops. The nomadic Arab tribes do seem more in evidence than in the first/seventh and second/eighth centuries; they now dominated stretches of territory that had been devoted to agriculture in early Byzantine and Umayyad times – the Balqa' east of the Jordan river, parts of the upper Orontes basin, etc. On the other hand, much of this land was quite marginal and could only be brought under cultivation through extraordinary levels of investment. Pastoralism was not necessarily a less productive use of it. Moreover, some of the tribes were by now at least partly settled, either at their own initiative or that of the regional rulers. We should perhaps hypothesise a levelling off of third/ninth century trends, perhaps a consolidation of economic life within reduced but now stable parameters. However, any serious conclusions, either as to long term trends or underlying causes, must await further research.⁴⁴

43 Ibn Ḥawqal, *Kitab ṣurat al ard*, ed. M.J. de Goeje, rev. J. H. Kramers, BGA 2 (Leiden, 1938), pp. 187–9.

44 M. D. Yusuf, *Economic survey of Syria during the tenth and eleventh centuries*. (Berlin, 1985), pp. 177–82: well documented, but a more optimistic interpretation than most other scholars have given.

By 970 Syria and Mesopotamia had unquestionably changed greatly since Byzantine, and even Umayyad, times – on every level – but there was much continuity as well. Greek had disappeared and Arabic was now the dominant language both of high culture and everyday speech; on the other hand, Syriac continued to flourish in the monasteries and many of the villages and towns of Mesopotamia. Islam was clearly the paramount religion – not only politically privileged, but also the one that set the parameters for religious and philosophical discourse. However, Christianity still commanded a demographic majority in many areas, its institutions were still largely intact, and intellectually it was far from moribund. Indeed, the fourth/tenth century witnessed an unusually high level of serious debate between Muslim and Christian thinkers. On the level of material life, Syria and Mesopotamia were still highly urbanised; if some cities, such as Antioch, Apamea or Caesarea, had shrunk to a fraction of their former size, others such as Aleppo had risen to replace them. The balance between agriculture and pastoral nomadism had shifted somewhat in favour of the latter, but there is no evidence of agrarian crisis. A Byzantine official from the early seventh century might have had some trouble getting his bearings in tenth century Damascus or Aleppo, but he would surely sense that these places still had strong links to their Roman and Christian past.

Egypt

MICHAEL BRETT

Muslims and Christians

In Egypt the Arab conquest initiated a cultural transformation that left unchanged the constants of the country's history over the past three thousand years. The country itself was an anomaly, a vast oasis formed in the desert by the Valley and Delta of the Nile, a great tropical river bringing an immense amount of water to a rainless land. From the first cataract at Aswan to the sea, it made possible irrigated agriculture on a grand scale, a large agricultural population and a centralised state. To the north, the Delta or Lower Egypt looked to the Mediterranean and Near East; to the south, the Valley or Upper Egypt looked to Nubia, the Red Sea and the Indian Ocean. The arc became a full circle with Islam, which added the western and central Sudan, and a systematic relationship with North Africa. Politically, the state had the resources to expand north eastwards into Syria, westwards to (modern) Cyrenaica in Libya and southwards into Nubia, but the country was equally open to invasion and conquest, so that for the past fifteen hundred years it had alternated between the status of a province and a seat of empire ruled by immigrants. The history of the first four hundred years of Muslim rule is the history of its further progress from province to empire under the impulsion of fresh waves of conquest. The novel feature was the accompanying passage from Christianity, Coptic and Greek to Islam and Arabic.

The sources generated by this passage are twofold. The Muslim tradition begins with Ibn 'Abd al Ḥakam (d. 257/870) in the ninth century and al Kindī (d. 350/961) in the tenth, who celebrate the creation of an expanding Islamic community in the country.¹ On the other hand are those of the Christians: that of the Orthodox Melkites, compiled by Eutychius under his Arabic name of

¹ Ibn 'Abd al Ḥakam, *Kitab fūṭūḥ Miṣr wa 'l Maghrib*, ed. C. C. Torrey (New Haven, 1922); al Kindī, *Governors and judges of Egypt*, ed. R. Guest (Leiden and London, 1912).

Saʿīd ibn Baṭrīq (d. 328/940) in the tenth, and that of the Monophysite Copts in the eleventh century edition of *The history of the Coptic patriarchs of Alexandria*, which document the acceptance by the original majority of the population of an inferior status and numerical decline.² Apart from these literary sources, the archaeological evidence of settlement is matched by that of the papyri, a unique if fragmentary contemporary record, which for the first three centuries after the conquest supplements and controls the sectarian versions of events.³ Ibn ʿAbd al Ḥakam’s *Futuḥ Miṣr* (The conquests of Egypt) is a legal text that served to establish the legality of the conquerors in accordance with the criteria of the Islamic law some two hundred years after the event.⁴ Al Kindī’s *Wulat wa quḍat Miṣr* (Governors and judges of Egypt) brought the story down to his own time in notices of the two principal officers of the Muslim community: on the one hand, the governor responsible for obedience to the caliph; on the other, the judge responsible for obedience to the law.⁵ On the same principle the *History of the Coptic patriarchs of Alexandria* recounts the events of each ecclesiastical reign, confirming the dependence of the two religious communities upon the government of their respective pastors. In the case of the Muslims this was in effect the *qaḍī* or judge who, since his original appointment by the Umayyads to act on behalf of the caliph, had come to represent the supreme authority of the *sharʿa* or law of God. In consequence, although he depended for his appointment upon the governor or the caliph himself, he stood apart as the magistrate who met the supreme requirement of the community for government in accordance with the law. So too, on the principle of the apostolic succession, did the Coptic patriarch, who long before the Arab conquest had taken his stance in opposition to the Christian emperor on a point of doctrine, upholding the Monophysite view of the single divine nature of Christ against the Orthodox view of His duality, both human and

- 2 Saʿīd ibn Baṭrīq [Eutychius], *Eutychii Patriarchae Alexandrini Annales*, ed. L. Cheikho, CSCO, Scriptores Arabici, 3rd series, vols. VI, VII (Beirut, Paris and Leipzig, 1906, 1909); (Severus ibn al Muqaffaʿ), *History of the patriarchs of the Coptic Church of Alexandria/the Egyptian Church*, ed. and trans. B. T. A. Evetts, Y. ʿAbd al Masih, O. H. E. Burmester and A. Khater, 3 vols. (Paris, 1901; Cairo, 1943 59, 1968 70).
- 3 Most accessible in A. Grohmann (ed. and trans.), *Arabic papyri in the Egyptian Library*, 6 vols. (Cairo, 1934 62); see also J. Karabacek, *Papyrus Erzherzog Rainer: Führer durch die Ausstellung*, Vienna, 1892. Cf. L. Sundelin, ‘Papyrology and the study of early Islamic Egypt’, in P. M. Sijpesteijn and L. Sundelin (eds.), *Papyrology and the history of early Islamic Egypt* (Leiden, 2004), pp. 1 19.
- 4 See R. Brunschvig, ‘Ibn ʿAbdalḥʾakam et la conquête de l’Afrique du Nord par les Arabes’, in R. Brunschvig, *Études sur l’Islam classique et l’Afrique du Nord*, ed. A. M. Turki, Variorum Reprints XI (London, 1986).
- 5 For the list of governors, *qaḍīs* and other officers down to the arrival of Ibn Ṭulun, see S. Lane Poole, *A history of Egypt in the Middle Ages*, 4th edn (London, 1925), pp. 45 58.

divine. The conflict this had generated between Byzantine state and Coptic Church was a major factor in the success of the Arab invasion.

Arabs and Egyptians

Written more than a hundred and fifty years later than the events themselves, the account of that invasion in the extant Muslim sources begs many questions. The contemporary account in the *History of the Coptic patriarchs* is brief to the point of ignoring almost everything except the reappearance of the Coptic patriarch Benjamin I after years of hiding from Byzantine persecution directed by 'al Muqawqas'. In the Melkite account of Eutychius, on the other hand, 'al Muqawqas' figures not only as the financial controller of Egypt, but as a Jacobite, a heretical Copt who betrayed the country to the Arabs out of hatred of Byzantium. It was the late seventh century chronicle of John, Coptic bishop of Nikiu, which survives only in Ethiopic translation,⁶ that was largely used by Butler to settle the question of his identity, and establish a convincing account of the conquest.⁷ The mysterious Muqawqas was Cyrus, bishop of Phasis in Colchis, appointed by the emperor Heraclius not only as the Orthodox Melkite patriarch of Alexandria in the last of many attempts by Constantinople to recover the Church in Egypt from the Monophysite heresy, but also as the governor of the country. When the Arabs under 'Amr ibn al 'Āṣ invaded Egypt from Palestine in Dhu al Ḥijja 18/December 639, advancing up the eastern side of the Delta to besiege the fortress of Babylon at its head, he negotiated its surrender at Easter 641 (Rabī' II AH 20). When the Arabs advanced down the west side of the Delta to the siege of the capital Alexandria, he returned after a brief dismissal to negotiate in Dhu al Ḥijja 20/November 641 its evacuation by the Byzantines in Shawwal 21/September 642. The city was reoccupied by the Byzantines in 24/645, but finally relinquished the following year.

Between the Arabs, the Orthodox Greeks and the Monophysite Copts, however, there is no clear cut opposition. The conquest took two or three years of confused warfare in the Delta, in which it appears from John of Nikiu that the invaders found allies as well as enemies among both Greeks and

6 John of Nikiou, *Chronique de Jean, Evêque de Nikiou*, ed. and trans. A. Zotenberg (Paris, 1883), trans. R. M. Charles as *The Chronicle of John, Bishop of Nikiu* (Oxford, 1916).

7 A. J. Butler, *The Arab conquest of Egypt and the last thirty years of the Roman dominion*, 2nd edn, with critical bibliography by P. M. Fraser (Oxford, 1978). For Byzantine Egypt, see W. E. Kaegi, 'Egypt on the eve of the Muslim conquest', in C. F. Petry (ed.), *The Cambridge history of Egypt*, vol. I: *Islamic Egypt, 640–1517* (Cambridge, 1998).

Copts, and were not invariably successful.⁸ The situation was clarified by the Byzantine withdrawal, when Duke Sanutius (Shenute), prefect of the Rīf (coast), brought the Egyptian fleet over to 'Amr, and was instrumental in bringing the Coptic patriarch Benjamin out of hiding in 23/644, to be reinstated as the rightful successor to the see of St Mark. The Egyptian fleet, manned by Egyptians, is an important but neglected aspect of the country's history throughout the period of this chapter; in 24/645 it aided the Arab conquest of Cyrenaica and its annexation to Egypt as the province of Barqa.⁹ The Coptic Church regained possession of all the extensive ecclesiastical property in the country, which it held in trust under the Roman law of *piae causae*, with appropriate tax exemptions. In return for this patronage it helped to ensure a smooth transition to Arab rule. The initial levies of food and clothing were regularised as the Arabs took control of the state and its fiscal system, documented for this as for previous periods by the surviving papyri.¹⁰ Existing taxes were paid in tribute to the conquerors by the Christian population, categorised as *dhimmiyyun* or protected subjects. The land tax in particular remained as before, levied by village quota in accordance with an assessment of what the land would bear. Responsibility was for the most part left to the district administration or pagarchy, at the beginning of yet another phase in the age long conflict between peasant and state that characterised the history of the country down to the nineteenth century.¹¹

The conditions were laid down on the one hand by the Nile flood, and on the other by the fiscal demands of the state. Out of the flood had emerged the system of 'basin' irrigation, under which the floodwater was formed into artificial lakes by long earthen banks to allow it to soak into the soil.¹² A collective effort was required to build the banks, and to open and close the entrances each year. This effort called for collective organisation, not only to irrigate the land, but to allocate it each year to the villagers for cultivation,

8 See M. Brett, 'The Arab conquest and the rise of Islam in North Africa', in J. D. Fage and Roland Oliver (eds.), *The Cambridge history of Africa*, vol. II: *From c. 500 BC to AD 1050* (Cambridge, 1978), pp. 495–9.

9 See R. G. Goodchild, 'Byzantines, Berbers and Arabs in seventh century Libya', *Antiquity*, 51 (1967), repr. in R. G. Goodchild, *Libyan studies: Selected papers of the late R. G. Goodchild*, ed. J. Reynolds and Paul Elek, London, 1976; F. R. Trombley, 'Sawīrus ibn al Muqaffa' and the Christians of Umayyad Egypt: War and society in documentary context', in Sijpesteijn and Sundelin (eds.), *Papyrology*, pp. 199–226.

10 See Grohmann (ed. and trans.), *Arabic papyri*, vol. III. See also Sijpesteijn and Sundelin (eds.), *Papyrology*; and P. M. Sijpesteijn, 'The Muslim conquest and the first fifty years of Muslim rule in Egypt', in R. S. Bagnall (ed.), *Egypt in the Byzantine World, 300–700* (Cambridge, 2007).

11 See M. Brett, 'The way of the peasant', *BSOAS*, 47 (1984).

12 See H. E. Hurst, *The Nile* (London, 1952), pp. 38–46.

depending on the extent of the flood. Village custom was important for this purpose,¹³ but never independently of central government, which drew the bulk of its revenue from agriculture. While recording the area of land, the number of people and the amount due, the state went beyond the mere collection of taxes in its provision for the cultivation of the floodplain. Central control of the flood itself was not possible before the introduction of permanent irrigation through barrages and dams in the nineteenth and twentieth centuries, while central supervision of the task in each village was beyond the capacity of the pre modern state to sustain. The historical solution was a local manager responsible for ensuring the productivity of the land and its yield in taxation, somewhere between a landowner and an official. In Roman Egypt he had been a tax farmer. In Byzantine Egypt the nobility had moved in the direction of autonomy with their self governing estates or *autopracts*. With the Arab conquest, estates reappeared in the hands of the Arab nobility, but for most of the country the pendulum swung towards the opposite extreme in a uniform system of small administrative districts called *kuwar* (sing. *kura*), under pagarchs or governors appointed by the state.

The pagarchs were native Egyptians, drawn from a class of property owners described in the Aphroditto papyri as *proteuontes*, who were entrusted by the Arabs with responsibility for the collection of taxes and thereby for agricultural production, beginning with the management of the irrigation system through their subordinates, the village heads. The instrument of control was the list of cultivators in each village who were liable for tax. Upon the number of such cultivators depended the extent of the land under cultivation, and the size of the village tax quota.¹⁴ Peasants and pagarchs alike, however, belonged to the Coptic Christian community, while the administrative language was Greek. In the absence of expert supervision by the Arabs, this centralised system, which required the pagarchs to pay regular visits to the capital, served the purpose of their subjects, as peasants and pagarchs connived to keep the tax lists short and the quotas correspondingly low. Such profitable collusion between taxpayers and tax collectors, combined with the recognition of the Coptic Church as representative of the Christian population, went far to keep Egypt quiet under its new rulers down to the end of the seventh century.

13 See T. Sato, 'Irrigation in rural Egypt from the 12th to the 14th centuries', *Orient*, 8 (1972).

14 See D. C. Dennett, *Conversion and the poll tax in early Islam* (Cambridge, MA, 1950), pp. 81, 91–105; K. Morimoto, *The fiscal administration of Egypt in the early Islamic period* (Kyoto, 1981), pp. 96–104; Brett, 'Way of the peasant'.

The new rulers were the Arabs. Those who first conquered Egypt were Yemenites southern, as distinct from northern, Arabians whose commanders became a hereditary Arab aristocracy. They abandoned the Byzantine capital of Alexandria for Babylon, the fortress commanding the junction of the Nile Valley and Delta, which they incorporated into an army camp that rapidly became a city under the name of *Fuṣṭaṭ* (from Greek *phossaton*, '(defensive) ditch', which acquired the meaning of 'tent' in Arabic). Generically it was a *miṣr* (pl. *amṣar*), 'a garrison city', a common noun of Syriac origin homonymous with *Miṣr*, the Arabic name of Egypt. *Miṣr* in consequence became an alternative name of the city, so that it is often difficult to know whether the city or the whole country is intended. Situated on the right bank of the river, and centred on the Mosque of 'Amr, the new foundation was divided into *khiṭaṭ* (sing. *khiṭṭa*) quarters for the tribal regiments.¹⁵ The building up of these quarters in high rise blocks marked a change of character from military to civilian which corresponded to the evolution of the army of conquest into a cross section of the population. As it did so the exclusive Arab host of *mu'minun*, or faithful original followers of God and His Prophet, was gradually outnumbered in an eclectic community of *muslimun*, those who had submitted to the Arabs and been accepted into the ranks of believers. The factors were recruitment and reproduction, which by the end of the seventh century had turned the Arabs of the *jund* (army), warriors who received their pay out of the revenues of the state under the name of '*aṭa*' (gifts), into a dwindling minority of the religious community. Recruitment appears in the papyri as a distinction between *moagiritai* and *mauloi*, *muhajirun* and *mawālī*, Arab 'emigrants' and non Arab clients.¹⁶ Many of these were of slave origin, and many composed the armed retinues of the Arab aristocracy.¹⁷ Reproduction followed from the acquisition of women, again very often as slaves, and led to an increase in numbers far beyond what the state was prepared to support. This new, dynamic element in the population, Muslim and Arabic speaking, was in marked contrast to the native Christian, Coptic speaking majority. After the confusion of the conquest this mainly rural population was not liable to enslavement or eligible for recruitment, but was excluded from the ranks of conquerors and their burgeoning community as tax paying subjects locked into their own society and economy.

15 See W. Kubiak, *al Fustat: Its foundation and early urban development* (Cairo, 1987); S. Lane Poole, *The story of Cairo* (London, 1902); A. Raymond, *Le Caire* (Paris, 1993).

16 For *moagiritai*/*muhajirun*, see P. Crone and M. Cook, *Hagarism: The making of the Islamic world* (Cambridge, 1977), pp. 8–9.

17 For examples see Brett, 'Arab conquest', pp. 502–4.

Only as conscripts did Copts figure alongside the Muslim *mawālī* as *maqamiša* (Greek *machismoi*), ‘fighters’ called up for military service as one of the liturgies or labours they were obliged to perform.¹⁸

Between Syria and the west

While the Arab colonisation of Egypt was taking hold of its government and society, the country played a dual role in the development of the new Islamic empire. While serving as a base for the conquest of North Africa and Spain, it was active in the establishment and growth of the Umayyad caliphate at Damascus. The two roles emerged under ‘Abd Allah ibn Sa’d ibn Abī Sarḥ, governor of Egypt from 25/645 to 35/656, who made the country tributary to Medina while leading a successful raid into Byzantine Africa in 27/647f., and one to Nubia in 31/651f. The expedition to Christian Nubia resulted in the *baqt* (pact), a treaty which at least in its later recensions provided for a Nubian tribute of 360 slaves a year, and established a peaceable relationship across the frontier at Aswan.¹⁹ The raid into Byzantine Africa may have based itself on Tripoli; it was followed in the 650s by raids conducted by Mu’awiya ibn Ḥudayj, the principal Arab commander settled in Egypt. But permanent conquest was deferred until after the first civil war (*fitna*) that broke out after the murder of the caliph ‘Uthman in 35/656. Arabs from Egypt had a prominent hand in the assassination, which is evidence of the way in which local resentment at the amount sent each year to Medina flowed into the more general resentment of the growing inequalities within the community, splitting it into factions. As the affair developed into the contest between ‘Alī and Mu’awiya ibn Abī Sufyan for the caliphate, the protesters lost their battle when ‘Amr ibn al-‘Āṣ returned to Egypt in 38/658 to gain the country for Mu’awiya and the partisans of ‘Uthman. Their cause, however, was temporarily won when ‘Amr was left to govern on his own account, keeping the country’s revenues for his own and the army’s benefit.²⁰

At ‘Amr’s death in 43/664 the alliance between governors sent from Damascus and the Arab aristocracy of the province (*wujuh*) kept the peace with only a brief interruption in 64 5/683 4, in the course of the second civil war, when the proclamation of Ibn al Zubayr as caliph at Mecca briefly stirred

18 Ibid. Cf. M. A. Shaban, *Islamic history: A new interpretation*, 2 vols. (Cambridge, 1971 6), vol. I: AD 600 75 (AH 132), pp. 157 8.

19 See Y. F. Ḥasan, *The Arabs and the Sudan* (Edinburgh, 1967), pp. 20 4.

20 For the political history of this period, see H. Kennedy, ‘Egypt as a province of the Islamic caliphate, 641 868’, in Petry (ed.), *The Cambridge history of Egypt*, vol. I.

up opposition to the Umayyad establishment. His partisans, however, were defeated by the incoming Umayyad caliph Marwan, who left his son 'Abd al 'Azīz to rule the country while his other son, 'Abd al Malik, succeeded at his father's death to the caliphate at Damascus. In this family empire, Egypt was largely independent under a monarchical regime whose shift of government away from the *miṣr* (garrison city) to the princely court was a notable feature of the growth of the community out of a conquering army into a population of civilian subjects. While the Mosque of 'Amr was rebuilt, 'Abd al 'Azīz not only constructed a new palace, the Dar al Mudhahhab (Gilded hall), but a summer residence at Helwan to the south of Fuṣṭāṭ. Outside the city altogether, this became a seasonal capital in which the district governors were each required to build a house, while the Coptic patriarch erected a church for his regular visit from Alexandria. Meanwhile the conquest of Byzantine Africa, interrupted yet again by the warfare of the 680s, was resumed and eventually completed by 705. After the expeditions of Mu'awiya ibn Ḥudayj in the 650s and 660s this was no longer a specifically Egyptian initiative but, as the point of departure for subsequent expeditions, the province and its government supplied men, money and ships. 'Abd al 'Azīz was thus well placed to take over the conquest effected by his brother's nominee Ḥasan ibn al Nu'man. In 85/704 Ḥasan was dismissed and replaced with 'Abd al 'Azīz's own man, Musa ibn Nuṣayr, as governor of the new province of Ifrīqiya, which was thus annexed to his Egyptian dominion. As far as Egypt itself was concerned, the attraction of 'Abd al 'Azīz's court coupled with the ongoing conquest of Ifrīqiya made for a vigorous immigration which thrived on the opening up of the way to the west. While Fuṣṭāṭ flourished, however, the condition of the Coptic majority worsened as the state set out to increase its revenues to meet the demands of an ambitious regime. The imposition in 74/693f. of a poll tax on Coptic monks by al Aṣḡagh, the son of 'Abd al 'Azīz, marked the beginning of a major change.

Helwan was an echo of the palaces that the Umayyad caliphs had begun to construct in the Syrian desert in anticipation of the palace cities built by their 'Abbasid successors. But the evolution of monarchy in Egypt, and any pretension to an Egyptian empire, was halted by the death of 'Abd al 'Azīz in 86/705, preceded by that of his son and heir, al Aṣḡagh. 'Abd al 'Azīz was succeeded by 'Abd Allah, son of the caliph 'Abd al Malik; but after 'Abd al Malik's own death later in the year, 'Abd Allah himself was dismissed in 90/709 by his successor al Walīd, and an officer, Qurra ibn Sharīk, appointed to complete the return of the country to the status of a province under the direct authority of the caliph. Under the new regime the efforts of 'Abd al 'Azīz and

his son to take a tighter grip on the revenues developed into a systematic reform of the administration. A *dīwan* (register) of the Arabs eligible for pay as warriors of the *jund* was drawn up, clearly distinguishing between this residue of the original community of the faithful and the much larger Muslim population that had grown out of it over the past fifty years. At the same time Arabic was introduced as the official language of the administration in place of Greek, requiring its predominantly Coptic staff to work in the new language, and making possible a much closer supervision of their practice. For the first time monks were registered for tax, but the chief victims were the Coptic peasants, as the government attempted to match their numbers with the tax lists. Such an attempt was difficult at the best of times as new generations took the place of old,²¹ but in this case was aggravated by the perpetual migration of peasants, leaving the villages where they were registered for others where they were not. A practice previously condoned by the pagarchy, it became the principal form of resistance to taxation, and a major problem for the regime. The administration resorted to passports and the forcible return of peasants to their original villages; those who pretended to be monks without the iron ring with which monks were now branded had their hands cut off. With penalties for officials who failed to enforce these measures, the old complicity between the peasantry and the district administration was broken. Reform of the system itself culminated in the appointment in 105/724 of 'Ubayd Allah ibn al Ḥabḥab as *'amil* (head of the financial administration), directly responsible to the caliph Hisham. His appointment accelerated the substitution of Muslims for Christians in the administration, and the transfer of responsibility for local taxation from the pagarchs and village headmen to treasury officials. A land survey and a population census provided the basis for a revision of taxes and tax liabilities, which finally separated the poll tax under the name of *jizyat ra's* ('on the head') from the land tax under the name of *jizyat arḍ* ('on the land'): the first was to be paid by Christian subjects, the second by Muslims as well. The revision entailed a review of village and monastery quotas, and fresh lists of taxpayers and their dues; receipts were given for payment.²²

The entry of Muslims on the land tax lists is a sign that the growth of the Muslim community into a cross section of the population had extended into

21 The problem is well illustrated in Norman Sicily: see J. Johns, *Arabic administration in Norman Sicily: The royal diwan* (Cambridge, 2002), pp. 144–69.

22 See Morimoto, *Fiscal administration*, pp. 120–6. This is the standard history of the financial administration in the period of this chapter. Cf. C. Robinson, 'Neck sealing in early Islam', *JESHO*, 48, 3 (2005), pp. 409–41.

the countryside, helped by the policies of Ibn al Ḥabḥab, who established a colony of Syrian Bedouin around Bilbays to the north east of Fuṣṭaṭ in the eastern Ḥawf or margin of the Delta. Their appearance in the lists, however, was not a sign of growing conversion of the Coptic population, since to become Muslim Copts had to be accepted into the Muslim community as *mawālī* (clients), giving up their previous livelihood, including their land. With no escape from increasing fiscal control they turned to sporadic revolt, beginning in the Delta in 107/725f.; a second outbreak occurred in Upper Egypt in 121/739, after the departure of Ibn al Ḥabḥab for the Maghrib in 117/734, and the succession of his son al Qasim. Al Qasim's legendary severity during years of famine in Egypt was matched by the unpopularity of Ibn al Ḥabḥab and his other sons in North Africa, where their fiscal demands provoked the revolt of the Berbers that in 740 overthrew the Umayyad dominion in the west. Such discontent in Egypt, however, was overshadowed by the succession crisis of the dynasty that broke out on the death of Hisham in 125/743. The conflict that this brought into the open between northern and southern Arabians, and between Syria and the rest, was manifested in Egypt when the governor, Ḥafṣ ibn al Walīd al Ḥaḍramī, from a local Yemenī or southern Arabian family, created an Egyptian force out of the largely Yemenī Arab *jund*, the *mawālī* and the Coptic *maqamiṣa* (military conscripts) in opposition to the immigrant northern Arabian Syrians. In 128/745 the country was reconquered by a Syrian army sent by the new caliph, Marwan II, but its sentiments resurfaced in 131/749, when Marwan's governor Ḥawthara left to help combat the advance of Abu Muslim's revolutionary 'Abbasid armies from Khurasan. Both Arabs and Copts were in rebellion when Marwan himself arrived in flight from Syria in 132/750, only to be pursued and killed by the victors. Their messianic message of deliverance from tyranny was echoed in Egypt by John the Deacon, the contemporary author of the biography of the patriarch Michael I in the *History of the patriarchs*, where the kingmaker Abu Muslim comes under the sign of the Cross as a man sent from God to deliver His people, Christian and Muslim alike.

The end of Arab supremacy

John may have spoken for Egypt; he was certainly speaking for his Church and his people in his wary welcome of the new regime, whose distance from its new subjects was established with the building of a second *miṣr*, al 'Askar (the army), to house its Khurasanī troops and its government. The adherence of the Copts to the revolution was briefly rewarded with fiscal concessions but,

in accordance with the new egalitarianism, the Muslim community was opened up to Christian converts. The patriarchate was in a difficult position, responsible both to the infidel state and to its flock, a dilemma rendered all the more acute by the evolution of Arab practice into Islamic law. Evident in the establishment of the *jizya* as a poll tax, this converted the original subject status of the Christian into a legal condition by which he was categorically defined. In such circumstances, a Church that identified itself with the warrior St George, but which owed its liberties to its submission to rulers of a different faith, resisted extortionate demands but distanced itself from rebellion, counselling reluctant resignation. Over the next half century, as the hoped for deliverance failed to materialise, and the administrative reforms begun by the Umayyads were pursued by the 'Abbasids, the patriarchate was left to lament the renewed rebellion and repression of the Coptic peasantry, and the desertion of the Church by those tempted to escape the poll tax by conversion to Islam, while still retaining their land.

Administratively, the poll tax under the name of *jizya* was definitively separated from the land tax under the name of *kharaj*. Collection remained in the hands of an *'amil* (financial controller) responsible either to the governor or, between 152/769 and 161/778, to Baghdad; his collectors appear to have dealt directly with the village heads to the exclusion of the pagarchs.²³ But collection continued to be problematic when the tax concessions of 133/750 were abolished in 134/752. The Coptic peasant revolt that this precipitated was the beginning of a tale of growing resistance and rebellion down to the death of the caliph Harun al Rashīd in 193/809, in which the Coptic revolts of 150 2/767 9 and 156/773 blended by the end of the century into those of the Arabs settled in the eastern Ḥawf, and these in turn into the renewed opposition of the Arabs of Egypt to imperial government from abroad. For Baghdad as for Damascus, the problem lay in the rapid turnover of governors required to prevent the independence of the province under a viceroy such as 'Abd al 'Azīz, at the price of lack of support for a regime whose prime purpose was to raise revenue for Iraq. For the first twenty five years the balance was achieved between governors from the elite of the new regime and the members of the old elite of the province. Through the office of *ṣaḥīb al shurṭa* (prefect of police) the latter commanded the local *jund*, while the former were as much concerned with the protracted reconquest of Ifrīqiya from Arab and Kharijite Berber rebels as with Egypt: in 142/760 the governor Ibn al Ash'ath, and in 152/769 the governor Yazīd ibn Ḥatim al Muhallabī, were sent westwards

23 Morimoto, *Fiscal administration*, p. 150.

with their armies for the purpose. In the meantime a revolt in 145/762f. in favour of the 'Alid pretender to the caliphate, Muḥammad al Nafs al Zakiyya, was suppressed without difficulty. Not so that of the Umayyad pretender Dihya ibn Muṣab, a descendant of 'Abd al 'Azīz, who rebelled at Ahnas (Ihnasiyat al Maḍīna, ancient Herakleopolis) in the Valley to the south of the Fayyum in 167 9/783 5.

Yazīd was succeeded by governors from the local elite, but following the death of the caliph al Maṣṣur in 158/775, the accession of al Maḥdī and the renewed appointment of governors from Baghdad, the alliance with the Egyptians broke down over taxation. While Dihya took control of Upper Egypt, the Arabs of the eastern Ḥawf rose in revolt against a system that taxed their land at the same rate as the Copts, and included them in an attempt to increase the revenue of the province. With the compliance of the *jund* the governor, al Khath'amī, was killed in 784, and a major invasion was required to put down the two rebellions, with no clear victory for government. Over the next twenty years the strained relationship between a string of fleeting governors and recalcitrant Egyptian Arabs was punctuated by further revolt in the Ḥawf, in 178/794, 186/802 and 190 1/806 7. Copts as well as Arabs appear to have been involved, calling for further invasions in 178/794 and 191/807. On the death of the caliph Harun al Rashīd in 193/809, the conflict came to a head.

As the contest for the caliphate developed between al Amīn and al Ma'mun from 195/811 onwards, the army in Egypt divided into the *ahl Miṣr* (men of Egypt) and the Khurasanī regiments brought in from Iraq over the previous ten to fifteen years to stiffen the *jund*. While the Egyptians, including the Arabs of the Ḥawf, declared for al Amīn, the Khurasanians were enlisted on the side of al Ma'mun by Harthama ibn A'yan, one of his principal supporters, who had restored order in Egypt in 178/794, whose son Ḥatim had been appointed governor in 194/810, and who had at his disposal the wealth of his Egyptian estates for the purpose. Ḥatim, however, was dismissed in 196/812 and, following the death of al Amīn in 198/813, the claims of al Ma'mun and his nominees were effectively ignored by the leader of the Khurasanī faction, Sarī ibn al Ḥakam. Ruling the Valley and the southern Delta from Fuṣṭaṭ, he confronted the Arabs under ibn al Wazīr al Jarawī, who controlled the central and northern Delta from Tinnis on the coast to the north east. Sarī was finally recognised as governor in 202/817, but after both he and ibn al Wazīr died in 205/820 the division of the country was maintained by their sons, Muḥammad followed by his brother 'Ubayd Allah at Fuṣṭaṭ, and 'Alī at Tinnis. The picture was further complicated in 199/815 when Alexandria was captured by a fleet of Andalusians who allied themselves with a party of zealots called the Ṣufiyya to

seize the city and massacre the Banu Ḥudayj, the principal members of the old Arab nobility. As Kennedy remarks, what is surprising, and significant, is that this nobility, so essential to government under the Umayyads and early ‘Abbasids, failed to seize the opportunity of the civil war to take over the country.²⁴ While its wealth and patronage were doubtless offset by that of a new and for the most part absent nobility represented by Harthama and his son, in neither case were these sufficient to take control of the military whose commanders seized power.

The success of the two regimes, and especially that of ibn al Wazīr, which represented the interests of the rebels against taxation in the Delta, was evidently a consequence of their light hand. They survived, however, only until al Ma’mun was in a position to recover the country in 211/826 through the agency of ‘Abd Allah ibn Ṭahir, his viceroy of the western provinces of the empire. Ibn al Sarī and ibn al Jarawī both submitted, while the Andalusians were driven away from Alexandria to Crete in 212/827. But when ibn Ṭahir was replaced by the future caliph al Mu’taṣim in 213/828f. the Delta revolted, just as in 134/752, against the attempt of his nominees to reimpose the old level of taxation. In 214/829 al Mu’taṣim’s governor was killed; in 215/830 al Mu’taṣim himself put down the rising by both Arabs and Copts, but only briefly. In 216/831 it was systematically suppressed by al Mu’taṣim’s Turks under their commander al Afshīn; but only after the arrival of al Ma’mun himself in 217/832 were the Copts of the Basharud (the coastal marshes) finally put down after ignoring the appeal of the patriarch to submit. It was the culmination of a century of revolt. Provoked by the fiscality of the regime, the long series of rebellions was both the cause and the consequence of long term social and political change. While the original Arab supremacy, like that of the Greeks before them, was at an end, the appearance of Arabs in the peasant population, in contrast to the Greeks, signalled an alteration in the composition of the population as a whole.

Arabisation and Islamisation

The end of the Arab supremacy was complete when in 219/834 the Arabs were struck from the *dīwan*, the list of those entitled to pay as members of the *jund*, despite their protest that it was theirs by right. According to al Maqrīzī (d. 845/1442) it was matched by an end to the Coptic majority, when in the fifteenth century he said of the Copts that after the suppression of the revolt in the

²⁴ Kennedy, ‘Egypt as a province’, p. 81.

Basharud in 217/832: 'ghalabahum al Muslimun 'ala 'ammat al qura'.²⁵ Meaning either that the Muslims were in the majority or simply dominant in all the villages, the statement is ambiguous, made all the more questionable by the following statement that the Copts then turned from rebellion to plotting against the Muslims, notably by controlling the collection of taxes an attack upon the Coptic staff of the Mamluk treasury. While it may be doubtful as a statement of fact, it nevertheless points to the emergence of that tax paying Arab peasant population which by al Maqrīzī's time was indeed in the vast majority. As to when it attained that majority, his comment remains the basic ground for the contention that the corresponding passage of the Copts from the people of Egypt into the community of a minority came about in the course of the ninth century.²⁶ In support of this contention is the evidence from the province of Ashmunayn to the south of Fustaṭ for the destruction of small local churches dedicated to local saints with local, Coptic names, and their replacement by fewer, larger churches with dedications to major saints, most notably St George, in the course of the revolts of the late eighth and early ninth centuries.²⁷ In the course of that century, moreover, insecurity was such as to oblige the monasteries to turn themselves into fortresses.²⁸ The Coptic community was evidently hard hit, and felt threatened by desertion to Islam and the ways of the Arabs.²⁹ On the other hand, it survived, resisting conversion down to the present day. The tax lists of the ninth century contain numerous Christian names, as well, perhaps, as Arab names for Christians. In the tenth century ibn Ḥawqal considered the Qibṭ (Copts) to be the people of Egypt, noting their presence in the places he described.³⁰ So did al Muqaddasī, noting that they still spoke Coptic, still numerous enough to form a language community.³¹ Despite their undoubted retreat, the Copts may still have been in the majority.

25 Al Maqrīzī, *Kitab al mawa'iz wa 'l i'tibar fi dhikr al khiṭaṭ wa 'l athar (al Khiṭaṭ)*, ed. G. Wiet, 4 vols. only (Cairo, 1911), vol. II, pp. 1 3.

26 See e.g. I. M. Lapidus, 'The conversion of Egypt to Islam', *Israel Oriental Studies*, 2 (1972); S. I. Gellens, 'Egypt, Islamization of', in A. S. Atiya (gen. ed.), *The Coptic encyclopedia* (New York, 1991), vol. III, pp. 936 42.

27 See M. Martin, 'La province d'Ashmunayn', *Annales Islamologiques*, 23 (1987).

28 See C. C. Walters, *Monastic archaeology in Egypt* (Warminster, 1974), chs. 1 and 3.

29 See C. Décobert, 'Sur l'arabisation et l'islamisation de l'Égypte médiévale', in C. Décobert (ed.), *Itinéraires de l'Égypte: Mélanges offerts au père Maurice Martin, SJ*, (Cairo, 1992), pp. 288 300.

30 Ibn Ḥawqal, *Ṣurat al arḍ*, ed. J. H. Kramers, 2 vols. (Leiden, 1938 9), p. 153 and *passim*, trans. G. Wiet as *Configuration de la terre*, 2 vols. (Beirut and Paris, 1964), p. 151.

31 Al Muqaddasī, *Aḥsan al taqasīm fi ma'rifaṭ al aqalīm* (Damascus, 1980), p. 185; cf. A. Miquel, 'L'Égypte vue par un géographe arabe du IVe/Xe siècle: al Muqaddasī', *Annales Islamologiques*, 11 (1972), p. 124.

The explanation of the Copts' survival after the 'Abbasids had removed the barrier to conversion will have lain in the internal solidarity of their community as its members weighed the disadvantages of conversion against the obvious advantage of freedom from the poll tax. Long after the regime had broken the solidarity of pagarchy and peasantry, al Maqrīzī's denunciation of a Coptic conspiracy at the level of government takes a sour view of their continued operation in the fisc, an occupation in which their expertise gave employment up to the higher levels of the administration. The same was true of the Church, a still more reserved occupation which drew upon the same membership, socially as well as economically united through patronage and family connections. For such as these, the benefits of remaining Christian evidently outweighed any to be gained by conversion, all the more because the adoption of spoken and written Arabic to the point at which it became a native language included them in the dominant society and culture. In the same way, the traditional skills of the Coptic artisan, such as the textile workers of Tinnis, may have helped to preserve the religious community.³² At Fustāt, in the capital city founded by the Arabs, such factors certainly contributed to the actual growth of a Coptic community, whose festivals became a major feature of the calendar for centuries to come. Such occupational benefits will not have accrued to the illiterate Coptic peasant, progressively losing his monopoly of his traditional occupation, the cultivation of the soil. It is clear, however, that the advantages of conversion were similarly offset by reluctance to abandon a community which still maintained a hold upon the land, and the possibility of unemployment for any who left to make their way in the circle of the mosque. It would certainly seem that the desertions bemoaned in the time of troubles from the early eighth to the mid ninth century were countered by a closing of the ranks, which was rewarded with the return of a less oppressive regime from the end of the ninth century onwards. Given such solidarity, the explanation for the gradual attrition of the Coptic population must lie elsewhere.

It is most probably to be found in demography, to which al Maqrīzī referred when he spoke of the taking of Christian wives by Muslim men as a factor in the prevalence of Muslims over Christians after 832.³³ Despite the

32 See Y. Lev, 'Tinnīs: An industrial medieval town', in M. Barrucand (ed.), *L'Egypte fatimide: Son art et son histoire* (Paris, 1999).

33 See M. Brett, 'Population and conversion to Islam in the mediaeval period', in U. Vermeulen and J. Van Steenbergen (eds.), *Egypt and Syria in the Fatimid, Ayyubid*

famous fertility of the Nile Valley and Delta, the pre modern population of Egypt was small even if comparatively large for the period; in the absence of statistics the best estimate is that it fluctuated between two and six million around a norm of four to five.³⁴ It was kept low by high mortality attributable to poverty and disease associated with the precariousness of agriculture, at the mercy of the river, the climate and the state.³⁵ The land was in consequence undercultivated, certainly by the middle of the ninth century, when the lament of the financial controller ibn Mudabbir that only some 2 million *feddans*, a third to a half of the cultivable area, were down to crops reflects a shortage of labour, doubtless worsened by the insecurity of the previous hundred years.³⁶ By the eleventh century, when Issawi plausibly estimates the population at around four to five million, the situation had improved; but the ceiling on population growth remained, with important implications for its composition. In such a situation the growth of one sector can only have occurred to the detriment of another, in this case that of the Muslims vis à vis the Copts. The evident growth of the Muslim sector derived from immigration, which created the city of Fuṣṭaṭ, settled the Arab Bedouin on the land, and continued with a constant trickle of such settlement by Bedouin forced out of the desert. It was certainly assisted by conversion, but maintained by natural reproduction, which, if al Maqrīzī is correct, was at the expense of the Coptic population, which lost its women to its rival. The extent to which Muslim men did indeed take Christian wives may be unknown, but in an essentially static population differential fertility would have been all that was required to achieve a growing imbalance between the two communities from generation to generation. An added factor in the case of the Copts would have been the celibacy of the clergy with its monks and nuns. Whatever the weight of any one factor, the Islamisation of Egypt, accompanied by its Arabisation, is likely to have come about less by choice than by gradual substitution of the one community for the other.

and *Mamluk eras*, vol. IV (Leuven, 2005). The general question is discussed by T. Wilfong, 'The non Muslim communities: Christian communities', in Petry (ed.), *The Cambridge history of Egypt*, vol. I.

34 C. Issawi, 'The area and population of the Arab empire', in A. Udovitch (ed.), *The Islamic Middle East, 700 1900* (Princeton, 1981).

35 C. Issawi, *Egypt: An economic and social analysis* (London, New York and Toronto, 1948), pp. 45 6; H. H. Rabie, 'Technical aspects of agriculture in medieval Egypt', in Udovitch (ed.), *The Islamic Middle East*.

36 Ibn Ḥawqal, *Ṣurat al ard*, p. 135, trans. Wiet as *Configuration*, pp. 133 4.

From province to empire: the ʿTulunids

Population was certainly the underlying factor in the policies and politics of the regime after the restoration of caliphal control in 217/832. Under the system of provincial government introduced by al Ma'mun, Egypt was incorporated with Syria in the domain of a member or intimate of the dynasty – al Ma'mun's son and successor al Mu'taṣim, followed by the Turks Ashnas and Itakh, and finally by the son and successor of al Mutawakkil, al Muntaṣir. Their government was an exercise in patronage rather than administration, which was delegated to the governors they appointed. Revenues once again went to the capital, now Samarra'. But discontent was not in evidence for some thirty years, and the chief opposition to the regime came from the Arab bourgeoisie of Fustaṭ, who gave vent, perhaps, to their dissatisfaction with government from abroad in their resistance to the doctrine of the created Qur'an from 227/842 until its abandonment by al Mutawakkil in 235/850. Much more important was the attempt by the fisc to remedy the shortage of cultivators through the introduction of tax farming. This was in effect an admission of defeat, since it encouraged rather than forbade the migration of peasants when the farmer contracted for uncultivated land on favourable terms, and offered it for cultivation at a reduced rate of *kharaj* – rent or tax, depending on the point of view. The flight from the villages which had undermined the system instituted by the Arabs in the seventh century was not condoned in principle, but employed in practice as an essential feature of the new order. Tax farming itself remained central to the financial and eventually the political system of Egypt down to modern times.

The matter of population meanwhile took a different turn with the opening up of gold and emerald mines in the desert to the south east of Aswan. The gold rush that this provoked brought the Arab Bedouin tribes of Egypt southwards to the point at which they came to dominate Aswan, to push back the indigenous Beja nomads of the south eastern desert, and threaten Nubian control of the Maris, the valley to the south of Aswan. It was the beginning of a long migration which took the Arabs deep into the Sudan, and brought about the elimination of Christian Nubia by the fourteenth and fifteenth centuries.³⁷ As far as Egypt was concerned, the state rapidly lost control of the gold mining operation, together with much of its authority over the frontier at Aswan, a situation which remained a permanent feature of its history.

³⁷ See Ḥasan, *The Arabs and the Sudan*, pp. 50–62.

As the country settled down in this fashion there was little to suggest its spectacular rise to independence and empire following the murder of al Mutawakkil in 247/861, when the death or killing of the next four caliphs by the Turkish soldiery was followed by the rising of the Zanj in southern Iraq under the messianic leadership of the 'Alid pretender 'Alī ibn Muḥammad. Beginning in 255/869, the rising inaugurated a century of such revolutionary movements that looked for the coming of the *mahdī*, a second Muḥammad who would bring in the final, golden age of the world. These culminated exactly a hundred years later in the Faṭimid conquest of Egypt, after governing the course of its history from the outset. In the climate of revolutionary expectation building up to the rising of the Zanj, the revolt was preceded by persecution of the Shi'a, the party of 'Alī, around whose descendants such expectations centred. In Egypt, wealthy and influential members of the family were either deported to Iraq or forbidden to leave Fuṣṭāṭ, to own an estate or more than one slave, and to ride a horse. But in 252/866 the fragile peace of the country was broken by renewed rebellion, when one such 'Alid, ibn al Arqūṭ, was proclaimed by an alliance of militiamen and peasants, Muslims and Copts, under the leadership of one Jabir ibn al Walīd. These took over ibn al Wazīr al Jarawī's old lands in the Delta with the similar aim of collecting the taxes for themselves. Put down in 253/867, they reappeared in 254/868 to the west of Alexandria under a second 'Alid pretender, only to be followed in 255/869 by a third such pretender in Upper Egypt, ibn al Ṣufī, who massacred the inhabitants of Esna, and crucified the commander sent against him. Such rebellions reflected the persistence of popular discontent, but also the appeal of Islam, as the legalistic claims of the Arab *jund* to its pay faded into Islamic messianism on the part of a disenfranchised Muslim population. Whatever the relative size of that population, its creed had finally taken the place of Christianity as the ideology of political action.³⁸

This wave of rebellion was bracketed by two major appointments to the government, both in accordance with previous practice, but which combined in the circumstances to break decisively with the past. Al Muntaṣir's appointment of the experienced ibn al Mudabbir to the post of 'amil (financial controller) of Syria and subsequently Egypt was an attempt to bring the revenues of the two provinces under his direct control, first as their overlord and then as caliph. Recorded by al Maqrīzī in a diatribe against the 'cunning

38 See Brett, 'Arab conquest', pp. 589–91; M. Brett, *The rise of the Fatimids: The world of the Mediterranean and the Middle East in the fourth century of the hijra, tenth century CE* (Leiden, 2001), pp. 56–7.

devils of scribes' who oppressed the people with unjust taxes despite the efforts of enlightened rulers to bring the fiscal system into line with the Islamic law,³⁹ Ibn al Mudabbir's reputation for raising old and introducing new taxes presumably reflects his efficiency and determination, but also his partial responsibility for the revolts of the decade. Those revolts in turn contributed to the appointment in 254/868 of the Turk Bayakbak as overlord of the western provinces of the empire, followed by the appointment of Bayakbak's stepson Aḥmad ibn Ṭulun as governor at Fuṣṭaṭ. Al Muntaṣir's long serving governor Yazīd ibn 'Abd Allah al Turkī (242 53/856 67) had been unable to deal with ibn al Walīd and ibn al Arquṭ, and his successor Muzaḥim, who had put down the revolt, had died. Aḥmad's own captains were initially routed by ibn al Ṣufī and al 'Umarī, the adventurer who had established himself in the land of the mines and the valley to the south east and south of Aswan, and it was six or seven years before Upper Egypt was pacified. Meanwhile at Fuṣṭaṭ Aḥmad was confronted by Ibn al Mudabbir, in control of the revenue and answerable only to Samarra'. The situation, however, was favourable. The outbreak of the Zanj rebellion in 869 meant the preoccupation of the caliphate with the war in Iraq for the next fourteen years. In 256/870 Bayakbak was succeeded by Aḥmad's father in law Yarjukh, who in 257/871 extended his appointment to include Alexandria and Barqa in (modern) Cyrenaica. Ibn al Mudabbir was finally transferred back to Syria, and replaced as *'amil* in Egypt by Aḥmad himself. The accumulation of power was complete in 258/872, when Yarjukh died at Samarra' and was only nominally replaced by al Mufawwaḍ, the young son of the caliph al Mu'tamid.

By that time Aḥmad's ambition was apparent in the construction of a new palace city, beyond al 'Askar to the north east of Fuṣṭaṭ. Its name, al Qaṭa'i' (the wards), for the quartering of the various regiments of his army, reveals its military purpose in connection with the eclectic force of Turks, blacks (Sudan, 'Abīd) and probably Greeks which he was now able to afford. Blacks and Greeks are first mentioned in 256/870, the year of the foundation of al Qaṭa'i', when Aḥmad led a brief expedition into Palestine. The blacks probably came as slaves from both Nubia via Aswan and the central Sudan via Zawīla in the Fezzan; the origin and indeed identity of the Greeks (the Rum) is less clear. But the new city was palatial, with a royal residence and adjoining garden; recreational, with its *maydan* (hippodrome); governmental, housing the offices and officers of state; commercial, with its markets; and charitable, with its hospital. With the building of its great mosque, the Mosque of Ibn Ṭulun, it

39 Al Maqrīzī, *Khīṭaṭ*, vol. II, p. 81.

acquired a great fortress, and a crowning symbol of its status as a royal capital in the style of Samarra'. From the time the building was begun in 262/876, indeed, al Qaṭa'i' developed into a rival to Samarra', as Aḥmad's ambitions came into conflict with the effort of al Muwaffaq, brother of the caliph al Mu'tamid, to prosecute the Zanj war from his base at Baghdad. His ambitions centred on Syria under its governor at Damascus, Āmajur, and its 'amil, his old opponent Ibn al Mudabbir. The conflict stemmed from the unequal division between al Mu'tamid and his brother of the tribute that Aḥmad continued to send to Iraq, and more generally from al Muwaffaq's evident alarm at the liaison between Aḥmad and the caliph. In 263/877, while al Mu'tamid conferred upon Aḥmad the defence of the Thughur the northern border of Syria with Byzantium, and thus in effect the government of Syria al Muwaffaq attempted to depose him, entrusting to his senior general Musa ibn Bugha the task of installing Āmajur as governor at Fustaṭ. Musa, however, never got beyond al Raqqa on the Euphrates, Āmajur died, and in 264 5/878 Aḥmad marched through Syria to Cilicia, evicting Ibn al Mudabbir and taking over its government. He returned to Egypt to deal with the revolt of al 'Abbas, his son, heir and regent in his absence, who fled westwards in an unsuccessful attempt to displace the Aghlabids of Ifrīqiya, and was eventually captured and imprisoned by his father in 268/881. But in 266/879f. Aḥmad's name first appeared on the coinage in association with that of the caliph; and when in 269/882 the defection to al Muwaffaq of Lu'lu', his commander at al Raqqa, brought him back to Damascus, he prepared to welcome al Mu'tamid as a refugee from his brother. When the flight from Samarra' was halted by al Muwaffaq, Aḥmad summoned the *fuqaha'* (jurists) to declare al Muwaffaq a traitor who had forfeited his claim to obedience, imprisoning the *qaḍī* (chief judge) of Egypt, Bakkar ibn Qutayba, for his refusal. For this, it is said, he died penitent, returning from Cilicia in 270/884 to die at al Qaṭa'i', the city that might have become the new capital of the caliphate.

Founded by a *ghulam* (pl. *ghilman*), a so called slave soldier, Aḥmad's empire was what Kennedy has called a *ghulam* state, in which the pay of such troops was the principal charge upon the exchequer, as well as the means to secure their crucial loyalty.⁴⁰ The resulting onus upon the fisc led in this case to the appointment in 265/879 of a replacement for Ibn al Mudabbir in the shape of the Iraqi Aḥmad al Madhara'i, the founder of a dynasty of such 'amils who ensured the continuity of the financial administration through the

40 H. Kennedy, *The Prophet and the age of the caliphates* (London and New York, 1986), pp. 208–10.

vicissitudes of the next seventy years. The foundation of a *dīwan al insha'* (chancery) with the appointment of the equally Iraqi Muḥammad ibn 'Abd al Kan as secretary of state was likewise required to conduct the correspondence of the regime, not least with the caliphate. On this firm basis Khumarawayh, the second son of Aḥmad, not a professional soldier like his father, but like him brought up as a member of the Arab Persian aristocracy of the caliphate, took possession of his inheritance in the aftermath of the Zanj war, when al Muwaffaq was at last free to challenge him. But invasions of Syria in 271/885 and 272/886 failed to install ibn Kundajik, the governor of Mosul, at Damascus, and by caliphal diploma Khumarawayh was confirmed in his father's dominions for thirty years in exchange for a modest tribute. In 274/887 he went on to campaign in northern Mesopotamia, while the governor of Tarsus in Cilicia returned to his former obedience. His success was crowned after the death of al Muwaffaq in 278/891 and that of al Mu'tamid in 279/892, when his daughter was married to the new caliph, al Mu'taḍid, at fabulous expense, and the accord of 273/886 was renewed for a further thirty years. The marriage was a token of the wealth at his disposal now that the revenues of Egypt were retained in the country, and an indication of the prosperity this engendered. But it was at the same time a sign of the legendary luxury in which he lived, and which by all accounts precipitated the downfall of his dynasty.

In contrast to Aḥmad, Khumarawayh enjoys a bad reputation in the sources, in which the sins of the father against the caliphate have been visited on the son as a figure of immorality and extravagance. Murdered, appropriately, in his harem at Damascus in 282/896, he allegedly left an empty treasury. He certainly left a succession that was murderously disputed among his sons and brothers. While his young son Jaysh was almost immediately deposed and killed, the still younger Harun survived until murdered in 292/904 by his uncle Shayban, who had himself survived the execution of several of his brothers. Tulunid troops from Syria defected to Iraq, and in 285/898 the caliph seized the opportunity to revise the original agreement with Khumarawayh, raising the tribute while recovering Cilicia and Aleppo for the empire. Just as Aḥmad had risen to power on the back of the Zanj rebellion, however, so his dynasty was finally brought down by a second wave of Mahdism in Iraq, which spread into Syria. Unlike the Zanj, the Qaramiṭa (or Carmathians) had no single leader; the term is applied in the sources to a range of movements at least partially focused on the expected appearance of the *mahdī* in 290/902f.⁴¹ Certainly in Syria the

41 See Brett, *Rise of the Fatimids*, pp. 61–72.

Ṭulūnids, 254–92/868–905

1. 254/868 Aḥmad ibn Ṭulūn
2. 270/884 Khumārawayh, Abū al-Jaysh (son of 1)
3. 282/896 Jaysh, Abū al-ʿAsākīr (son of 2)
4. 283/896 Hārūn, Abū Mūsā (son of 2)
5. 292/904 Shaybān, Abū al-Manāqīb (son of 1)

292/905 reconquest by the ʿAbbāsīd general Muḥammad ibn Sulaymān

Ikhshīdids, 323–35/935–69

1. 323/935 Muḥammad ibn Ṭughj, Abū Bakr al-ikhshīd
2. 334/946 ʾUnjūr, Abū al-Qāsim (son of 1)
3. 349/961 ʿAlī, Abū al-Ḥasan (son of 1)
4. 355/966 Kāfūr al-Lābī, Abū al-Misk
5. 357/968 Aḥmad, Abū al-Fawāris, d. 371/981 (son of 3)

358/969 conquest of Egypt by Fāṭimids

Fāṭimids, 297–567/909–1171

1. 297/909 ʿAbd Allāh (ʿUbayd Allāh) ibn Ḥusayn, Abū Muḥammad al-Mahdī
2. 322/934 Muḥammad, Abū al-Qāsim al-Qāʾim (son of 1?)
3. 334/946 Ismāʿīl, Abū Ṭāhir al-Manṣūr (son of 2)
4. 341/953 Maʿadd, Abū Tamīm al-Muʿizz (son of 3)

358/969 caliph in Egypt

5. 365/975 Nizār, Abū Manṣūr al-ʿAzīz (son of 4)
6. 386/996 al-Manṣūr, Abū ʿAlī al-Ḥākīm (son of 5)
7. 411/1021 ʿAlī, Abū al-Ḥasan al-Zāhir (son of 6)
8. 427/1036 Maʿadd, Abū Tamīm al-Mustansīr (son of 7)

8. The rulers of Egypt, 868–1036.

After Carl F. Petry (ed.), *The Cambridge history of Egypt* vol. I, 1998, p. 517. Copyright Cambridge University Press, reproduced with permission.

year saw the siege of Damascus by the messianic *ṣaḥīb al naqa* ('man with the she camel'), whose place was taken after his death in battle by the *ṣaḥīb al shama* ('man with the birthmark'). Although Damascus was held against them, the Ṭulunid forces under Ṭughj ibn Juff were unable to crush them. A Mahdist state was proclaimed at Salamiyya, Homs and Hama, which was only overthrown in 291/903 by the forces of Baghdad under their commander in chief, the minister Muḥammad ibn Sulaymān al-Katīb. In 292/904, joined by Ṭughj ibn Juff at Damascus and fortified by the Cilician fleet, these moved by land and sea against Egypt. In December Harun, awaiting the invasion at the head of his army out beyond Bilbays on the eastern edge of the Delta, was murdered by Shayban, who withdrew to Fustaṭ before the advance of Muḥammad, to whom he surrendered in Ṣafar 292/January 905. The radical hostility of Baghdad to Ṭulunid pretensions was demonstrated not by the execution of Shayban and his relatives, who were deported to Iraq, but by the total destruction of al-Qaṭaʾi' apart from the mosque.

From province to empire: The Ikhshīdids

The extirpation of the Ṭulunids brought the return of Egypt to provincial status with a recrudescence of provincial unrest, immediately manifested in the welcome at Fuṣṭaṭ to one ibn al Khalīj, or al Khalījī. An Egyptian officer deported to Baghdad, he had escaped at Aleppo and returned to Egypt to proclaim the restoration of the Ṭulunids under Ibrahīm ibn Khumarawayh. Not only did he drive out the 'Abbasid governor al Nusharī, but he repelled an initial expedition from Baghdad before his defeat and capture by a second in 293/906. His success and failure are equally significant. With the defection of Turks such as Ṭughj ibn Juff to the 'Abbasids, and the massacre by Muḥammad ibn Sulayman of the black troops of the Ṭulunids, the fallen dynasty was identified with the cause of the men of Egypt, half military, half popular, going back to the beginning of the previous century. His failure was the failure, yet again, of that cause to provide the country with a government, either for or against Baghdad.

In the thirty years that followed, the question of for and against Baghdad was exacerbated, on the one hand by the descent of the caliphate under al Muqtadir and his successors into an ultimately fatal struggle for power between its Men of the Pen and Men of the Sword, and on the other by the third and ultimately triumphant wave of Mahdism, that of the Faṭimids. Where the death in 260/874 of al Ḥasan al 'Askarī, the eleventh imam in line from 'Alī, had left his followers to await the return of his vanished son as the second Muḥammad, the Faṭimid *mahdī* 'Abd Allah and his son Muḥammad al Qa'im claimed a different line of descent from Ja'far al Ṣādiq, the sixth imam. 'Arising with the sword' as 'the Sun of God in the West', 'Abd Allah came to power in Ifrīqiya in 297/910, two years after the accession of al Muqtadir, and promptly turned his attention to Egypt.⁴² For Baghdad the country was held, along with Syria, not so much by its governors as by the 'amils of the Madhara'ī family, members of the administrative elite of Iraq, and consequently involved in the factional politics of the period. Having been introduced by Aḥmad ibn Ṭulun, they survived the downfall of his dynasty as tax farmers on a gigantic scale, undertaking responsibility for the fiscal regime of the two provinces in return for annual payments to Baghdad. In the process they built the Egyptian treasury into the central organ of government, but found difficulty in paying the troops stationed in the country. These, however, were relatively few and the governors who commanded them

42 See *ibid.*, pp. 29–132.

correspondingly weak, in no position as yet to repeat the exploit of Aḥmad ibn Ṭulun in disposing of ibn al Mudabbir and creating their own state. By the same token they were in no condition to repel an invasion, all the more because the country was not united behind them. Against Baghdad were not only those who regretted the demise of the Ṭulunids but those who favoured the Faṭimids, whose *mahdī* had passed through Egypt on his way to the west in 292/905 with the connivance of sympathisers.

Like the rebellion of ibn al Khalīj, the Faṭimid invasions of 301 2/914 15 and 306 9/919 21 were nevertheless defeated. Determined attempts by the Faṭimid al Qa'im, the *mahdī*'s son and heir Abu 'l Qasim Muḥammad, to carry the revolution in the west eastwards to Baghdad were thwarted by logistics. Barqa in Cyrenaica was a long way from Fustaṭ, and easily taken and retained by the Ifrīqiyyans. From there Alexandria, isolated on the coast to the west of the Delta, was on both occasions taken with the aid of the Faṭimid fleet. But Fustaṭ was still some 200 kilometres further for an expedition whose lines of communication were already long, and on both occasions was not reached before the arrival of reinforcements. In 302/915 the invaders were defeated at Giza by the governor Takīn with the aid of troops from Syria, and retreated to Alexandria and finally Ifrīqiya as Mu'nīs al Muẓaffar, the principal 'Abbasid commander, arrived from Baghdad. The Iraqis were unpopular, and quickly withdrew, while the new governor, Dhuka al Rumī (Ducas the Greek), imprisoned those who had been in correspondence with the invaders; many had hands and feet cut off. Agitated by Faṭimid propaganda, however, the country was divided. When slogans appeared on the doors of the Mosque of 'Amr extolling the first three caliphs, Abu Bakr, 'Umar and 'Uthman, in defiance of their denunciation as usurpers by the Faṭimids, crowds demonstrating their support with the approval of the chief of police were dispersed by troops, and the slogans themselves effaced. In 306 7/919 the regime almost collapsed as the Faṭimid al Qa'im returned to claim not only Egypt but Iraq for the rightful heirs of the Prophet. Alexandria was occupied, the Berber tribes to the west of the Delta revolted, and the governor, Dhuka, died and was not immediately replaced. But al Qa'im waited until the next year for the arrival of the Faṭimid fleet to escort the army upriver to Fustaṭ, and when it came it was caught on a lee shore by the fleet from Cilicia and destroyed most probably in Aboukir Bay, where Nelson in similar fashion destroyed the French fleet in 1798. God's wind, said al Kindī for the Egyptian opposition, had saved Islam, not least by allowing time for Mu'nīs to arrive yet again from Baghdad. For a year al Qa'im occupied the Fayyum until the

Cilician fleet recaptured Alexandria and he was obliged once again to retire.⁴³

Barqa in Faṭimid hands remained a forward base for raiding in the western desert, but no third expedition was forthcoming for the next fifteen years, until Egypt was again on the verge of independence. After the retreat of al Qa'im, discontent in the country reverted to that of the army with its irregular pay, but subsided with the replacement of the governor Aḥmad ibn Kayghalagh by the former governor Takīn in 312/924, and the return, after four years' absence, of Ḥusayn followed by Muḥammad al Madhara'ī to the post of 'amil in 313/926. The crisis came in 933: with the death of Takīn in the same year as the execution of Mu'nis at Baghdad the rapid dissolution of the central government of the empire began. Not only did the troops mutiny over pay, but fighting broke out between Takīn's son Muḥammad at the head of the Mashariqa (Easterners), the Turkish soldiery, and the former governor Aḥmad ibn Kayghalagh at the head of the Maghariba (Westerners), most probably Berbers and blacks. Used for the first time, these two terms reflected the long standing divisions within the army and the equally long standing hostility of the Egyptians to the Iraqis. The contest between the two rival governors was juggled by the 'amil, Muḥammad al Madhara'ī, until cut short by the arrival of Muḥammad ibn Ṭughj in 323/935. The son of the Tulunid commander Ṭughj ibn Juff, he had served Takīn in Egypt, then risen as a client of Mu'nis to become governor of Damascus in 319/931. Appointment to Egypt on the death of Takīn was halted by Mu'nis's execution, but renewed in 323/935 with the support of Mu'nis's ally al Faḍl ibn Ja'far, member of the great vizieral family of the Banu al Furat at Baghdad and political opponent of the Madhara'īs. Like Muḥammad ibn Sulayman thirty years previously, ibn Ṭughj came as an invader by land and sea to put down a rebel. Like Shayban, ibn Kayghalagh abandoned Fustaṭ but, fleeing westward to Faṭimid Barqa, procured from al Qa'im, now imam caliph in succession to the *mahdī*, a third expedition which in 324/936 retook possession of Alexandria. It was, however, rapidly expelled. Muḥammad al Madhara'ī was imprisoned until restored to his essential role in 327/939, by which time ibn Ṭughj had welcomed at Fustaṭ in 325/937 his ally at Baghdad, Faḍl ibn Ja'far ibn al Furat, in flight from ibn Ra'iq, the new master of the empire. In 327/939 his own effective independence was recognised with the grant of the title *al ikhshīd*, the designation of the princes of his original homeland in Farghana to the east of Transoxania.

43 Details in H. Halm, *The empire of the Mahdi*, trans. M. Bonner (Leiden, 1996), pp. 196–213.

Coming to Egypt from Damascus, Ibn Ṭughj had no difficulty in returning to Syria to secure its possession, and reconstitute the empire created by Ibn Ṭulun when he invaded Syria from Egypt. That invasion had been justified by the holy war with Byzantium, which turned the northern borders of Syria, including Cilicia, into a militarised zone of conflict for which Ibn Ṭulun had claimed responsibility. But Cilicia in particular had proved recalcitrant, and had been returned to Baghdad in 285/898, while for Ibn Ṭughj the championship of the holy war was an obligation that he was happy to lose at a time of renewed Byzantine aggression: in 322/934 the frontier city of Malatya was taken, and in 331/943 the Byzantines raided deep into northern Iraq and Syria. Syria itself proved difficult to retain when ibn Ra'iq, driven from Baghdad, entered Damascus and held it from 328/940 to his death in 330/942. Ibn Ṭughj was then able to obtain from Baghdad in 331/943 the prestigious custodianship of the holy places of Mecca and Medina, and was tempted in 332/944 to repeat Ibn Ṭulun's offer of hospitality to the caliph al Mu'tamid, making a similar offer to the caliph al Muttaqī in a meeting at al Raqqa on the Euphrates. But that was after he had been obliged to recover Aleppo from the Ḥamdanids of Mosul. The offer to al Muttaqī was declined, and the Ḥamdanids in the person of the adventurous Sayf al Dawla 'Alī ibn Ḥamdan not only returned to Aleppo but occupied Damascus. In 334/945 Ibn Ṭughj agreed to a partition which left him in possession of Damascus as ruler of the centre and south, and gave Aleppo to Sayf al Dawla as commander of the holy war on the frontier. At his death in 335/946 the second Egyptian empire to emerge from the troubles of Iraq had taken permanent shape.

Its internal character was likewise in formation. Like that of the Ṭulunids, that of the Ikhshīdids was a *ghulam* state, in which the payment of the army was central to the administration. Founded and ruled by a *ghulam*, it was moreover ruled after his death by a *ghulam* of very different origin, the black eunuch Abu 'l Misk Kafur. Coming from Nubia, and acquired by ibn Ṭughj at Fustāṭ in the 310s/920s, Kafur represented the strong African element underlying the dominant Turkish and Iraqi presence in the government of the country. As the lieutenant of his master in command of the army, he had the power as well as the authority, not only to secure the succession for his patron's sons, first Unujur (r. 335 49/946 61), then 'Alī (r. 349 55/961 6), but to rule in their name as their *ustadh* (tutor). Despite a brief attempt by Unujur to take power in 343/954, they remained condemned to a life of idleness. Kafur's position was quickly consolidated in Syria vis à vis the Ḥamdanids, and in Egypt with the defeat of Ghalbun, rebel governor of Ashmunayn, in 336/947, leaving him free to govern as a statesman rather than a politician or

administrator. His recruitment of a household regiment of guardsmen, the Kafuriyya, alongside the Ikhshīdiyya of ibn Ṭughj, reinforced his control of the army, while his prompt dismissal of Muḥammad al Madharaʿī in 335/946 removed his most obvious rival from control of the administration. This was then handed to a different figure in a different capacity, Jaʿfar, son of the refugee al Faḍl ibn al Furat whom ibn Ṭughj had welcomed in 325/937, whom he appointed to the position of *wazīr*. The Banu al Furat were only the greatest of such immigrants into Egypt, executives of the caliphate displaced by the collapse of central government in Iraq,⁴⁴ who provided the nascent Ikhshīdīd regime with staff, and helped to create it on the model of Baghdad. With the appointment of Jaʿfar, the principal feature of that model was introduced into the country. The ʿAbbasid *wazīr* had been head of government on behalf of the sovereign, although in the latter years of increasingly murderous competition for control of the caliphate, his position had been undermined by rivalry within his own secretarial class and with the military. Under Jaʿfar the *wazīrate* became central to the administration which the Madharaʿīs had directed as heads of finance, and which now expanded to embrace the whole range of offices developed by the ʿAbbasids for the government of the empire. Of these the most notable, as in Ṭulunīd times, was the *dīwan al inshaʿ* (chancery).

The Faṭīmid conquest

After the retreat from Alexandria in 324/936 the threat of Faṭīmid invasion receded. The revolutionary *élan* that had sought to extend ‘the rising of the sun of God in the West’ in the person of the *mahdī* ʿAbd Allah to the east in the person of his son Muḥammad al Qaʿim had subsided before the son succeeded his father in 322/934. The claim to universal sovereignty remained, and with it the design upon Egypt. But the years that saw the foundation of the Ikhshīdīd empire by Muḥammad ibn Ṭughj culminated in Ifrīqiya in a crisis that brought his dynasty to the verge of extinction. The final suppression in 336/947 of the rising of Abu Yazīd, ‘the man with the donkey’, was the occasion for a revival of Faṭīmid imperialism that culminated twenty years later in the final invasion and conquest of Egypt. For most of that time, however, the dynasty was preoccupied with the restoration of its position in the western Mediterranean, and with the redevelopment by al Muʿizz, the fourth imam caliph, of its

⁴⁴ See E. Ashtor, ‘Migrations de l’Irak vers les pays méditerranéens’, in E. Ashtor, *The Medieval Near East: Social and economic history*, Variorum Series IV (London, 1978).

appeal to the Shī'a in the east. At a time when the followers of Muḥammad al Muntazar, the expected twelfth imam, had reconciled themselves to his occultation, al Mu'izz declared himself the lineal descendant of Muḥammad ibn Isma'il ibn Ja'far al Ṣādiq, and the second founder of his dynasty, with whom the original promise of the *mahdī* would at last be fulfilled. The conquest of Egypt was the necessary proof of that claim, but al Mu'izz waited for the death of Kafur in 357/968, two years after the regent had himself ascended the throne with the title of Ustadh, and opened up the question of the succession in the absence of a son and heir.

For many years, therefore, Kafur was left in peace. The prestigious role of protector of the holy places was carried out by supplies of grain to feed the annual multitude, and payments to the Qaramiṭa of Baḥrayn to secure the passage of the pilgrimage from Egypt and Syria. To the south, incursions from Nubia in 339/951 and 344/956 provoked a retaliatory expedition to the frontier fortress of Qaṣr Ibrīm in 345/957. A more serious invasion in the early 350s/960s, however, seems to have brought the Nubians 200 miles north of Aswan to Ikhmim, and kept them there for three years.⁴⁵ By then the general situation had deteriorated. The Byzantines took Crete in 350/961 and Cyprus in 354/965, provoking anti Christian riots in Egypt and a disastrous naval expedition, whose destruction exposed the coast of Egypt and Syria to Byzantine attack. In 353/964 the Qaramiṭa of Baḥrayn invaded Syria in concert with their Bedouin allies, who plundered the pilgrim caravan from Damascus in 355/966. In Egypt itself a prolonged period of famine from 352/963 to 357/968 led to Bedouin raids. At Fustaṭ, in anticipation of Kafur's death, rivalry was intensified by the rise of the Iraqi Jewish ibn Killis to control of the fisc, and his aspiration to the wazīrate. When Kafur died in 357/968, the crisis came to a head. The child Aḥmad ibn 'Alī ibn Muḥammad ibn Ṭughj was enthroned with the wazīr Ja'far ibn al Faql as regent supported by the *ghulam* Shamul in command of the army. But Ya'qub ibn Killis fled to Ifrīqiya, where al Mu'izz had long since prepared his invasion, and now set it in train.

As befitted the logistical nature of the enterprise, wells had been dug and depots established along the route as far as Barqa, while its commander, Jawhar al Ṣiqlabī, was chosen as an administrator rather than a soldier to take over the country on behalf of his master. With an end to the 'Abbasid empire, Egypt was isolated, and the imam caliph the strongest candidate for a throne effectively left vacant by Kafur's death. Mustered over the summer and

45 See Ḥasan, *Arabs and the Sudan*, p. 91; P. L. Shinnie, 'Christian Nubia', in Fage and Oliver (eds.), *The Cambridge history of Africa*, vol. II, p. 579.

winter of 357/8/968–9, the Faṭimid host set out in February, to arrive outside Alexandria in May. At Fuṣṭaṭ Jaʿfar had been deserted by Shamul, who had left for Syria with the Ikhshīdīd prince Ḥasan, and sued for peace through the agency of the *ashraf* (nobles), like the Faṭimids of ʿAlid descent. This was granted by Jawhar, who took from them an oath of fidelity in the *ʿahd* (pact) by which he granted the protection of the imam caliph in return for their obedience.⁴⁶ At Fuṣṭaṭ in July the regiments of the Ikhshīdiyya and Kafuriyya made a stand, but were rapidly overwhelmed; and Jawhar proceeded to lay the foundations of al Muʿizziyya (the city of al Muʿizz), out beyond the ruins of al Qaṭaʿīʿ to the north east of Fuṣṭaṭ. Laid out on the model of al Mahdiyya, the Ifrīqiyan capital of the dynasty on the coast of (modern) Tunisia, it was divided by a central street with a palace on either side and, as al Qahira (the victorious), eventually gave its name to the Egyptian metropolis. It was certainly intended as the new capital of Islam.

The acquiescence of Jaʿfar in the assumption of power by Jawhar on behalf of his master ensured the continuity of government, with the two men sitting together to hear the petitions that occupied a central place in the routine of government, and a similar duplication of personnel in control of the police and finance. Arriving after yet another low Nile in 357/968, Jawhar was obliged to take emergency measures to force grain onto the market, while funds to meet his expenses were probably obtained from the estates whose income had been assigned to the Ikhshīdiyya and Kafuriyya. Normality returned with a good harvest in spring 360/970, by which time Jawhar had set in train the invasion of Syria. Between May and October the resistance of the Ikhshīdīd prince Ḥasan at al Ramla was overcome, Jawhar's general Jaʿfar ibn Falaḥ took Damascus, and the *ghulam* Futuḥ began to summon volunteers to the holy war. The enemy was Byzantium, whose own holy war had overwhelmed the defences of the Syrian borders and culminated in the siege and capture of Antioch in 358/969. At the time of Jawhar's arrival in Egypt this assault upon Islam had added urgency to the claim of the imam caliph to the throne. The muster elicited an enthusiastic response in Palestine and Tiberias, but the campaign was called off in 360 (June 971), when Damascus came under attack from a different quarter. Brutally treated by Jaʿfar ibn Falaḥ, the citizens of Damascus appealed to the Qaramiṭa of Baḥrayn, whose subsidy from the Ikhshīdīds had been stopped by Jawhar. A coalition of Qaramiṭa, Arab Bedouin and refugee Ikhshīdīd *ghilman*, formed with the blessing of the ʿAbbasid caliph and the aid of the Ḥamdanids of Mosul, then defeated and killed Jaʿfar in August. In

46 See Brett, *Rise of the Fatimids*, p. 301.

September the horde entered Egypt and overran the eastern Delta. It was only driven out in 361 (December 971), after defeat at Fustaṭ, where a wall and ditch thrown up from the river to the Muqattam cliffs was held by the citizens whom Jawhar had conscripted and armed.

Syria was lost together with the momentum of the Faṭimid invasion, but Egypt was ready to welcome the imam caliph himself. Al Mu'izz left Ifrīqiya in 362 (November 972), to arrive at Fustaṭ in June 973, and take up residence in the palace city of al Mu'izziyya. Jawhar was retired and Ja'far ibn al Faḍl dismissed by a monarch who took personal control of the state. Ya'qub ibn Killis was appointed with an Ifrīqiyān colleague to the position he had enjoyed under Kafur in charge of the revenue. Such resolution carried the regime through the crises of the next two years. On behalf of Egypt the *ashraf*, certified descendants of the Prophet and putative kinsmen of the imam caliph, were prepared to welcome the new sovereign; but one of their number, Akhu Muslim, defected to the Qaramiṭa, who remained deaf to al Mu'izz's appeal for recognition. It required the defeat of a second assault upon Fustaṭ in 363/974 to put an end to their threat, and permit the reoccupation of Damascus by Faṭimid forces. In 364/975, however, the rebellious citizenry found a new ally in the Turkish *ghulam* Aftakīn, in flight from Buyid Baghdad; and the death of the heir apparent 'Abd Allah was followed by that of al Mu'izz himself at the end of the year.

The Faṭimid empire

His death meant that the reign of the Faṭimids in Egypt began with a new monarch, his son and successor al 'Azīz, under whom the dynasty assumed its Egyptian character and Egyptian outlook.⁴⁷ Through the work of Ibn Zulaq, the pro Faṭimid continuator of the anti Faṭimid al Kindī's *Wulat*, the dynasty took over the historiographical tradition of Egypt, and made it their own in a court chronicle on which al Maqrīzī based his history of the dynasty, his *Itti'az al ḥunafa'*.⁴⁸ The dynasty's remarkably determined pursuit of the Mahdist aim of restoring to the community its true faith and true government at the

47 See *ibid.*, chs. 10 and 11; Y. Lev, *State and society in Fatimid Egypt* (Leiden, 1991), chs. 1, 4 and 5; P. Sanders, 'The Faṭimid state, 969–1171', in Petry (ed.), *The Cambridge history of Egypt*, vol. I. The most recent history of the Faṭimids in Egypt down to 1074 is H. Halm, *Die Kalifen von Kairo. Die Fatimiden in Ägypten 973–1074* (Munich, 2003). For the history of their doctrine, see F. Daftary, *The Isma'īlīs: Their history and doctrines* (Cambridge, 1990).

48 Al Maqrīzī, *Itti'az al ḥunafa'*, ed. J. D. al Shayyāl and M. H. M. Aḥmad, 3 vols. (Cairo, 1967–73).

hands of the true heirs of the Prophet was similarly modified. The pursuit was based on two requirements: belief in their imamate; and acceptance of their caliphate. The first was the principle of their *da'wa*, their call to join the ranks of the *mu'minun* (faithful), those for whom belief in the imam was the way to God. The second was that of their *dawla* (state), in which the generality of *muslimun* was summoned to obedience on the strength of their *islam*, or submission to God. While all *mu'minun* were *muslimun*, most *muslimun* were not such believers, a division of the community which was reflected in the reach of the *da'wa* to a minority across the Muslim world, while the *dawla* was restricted to the territory controlled by the caliph. But since it was of the essence of his mission that he should rule the entire world, and certainly the whole of the *dar al islam*, the extension of the *dawla* continued to be a fundamental aim of the dynasty after the appropriation of Ikhshīdīd Egypt. The way it was pursued and accomplished by al 'Azīz determined the character of the empire for the next hundred years.

The principle of the *dawla* in Egypt remained that of the 'ahd concluded by Jawhar with the representatives of the Ikhshīdīd regime on behalf of the population. Its accent upon the *dhimma* (protection accorded to that population) effectively placed Muslims on the same level as the *dhimmiyyun*, the Christians and Jews under the protection of the Muslim community, under the sway of a monarch situated on an altogether higher plane. But under al 'Azīz, the son and successor of al Mu'izz, the father's close direction of both *dawla* and *da'wa* gave way to an extensive delegation of responsibility to a new generation of servants. Of these, the sons of the great Qaḍī al Nu'man, whose *Da'a'im al Islam* (Pillars of Islam) had spelled out the doctrine of the law on the authority of the imam, established a dynasty which held the post of chief *qaḍī* almost continuously down to the 430s/1040s. In that capacity they represented the monarch in his dual capacity as imam and caliph, laying down the law and supervising its administration by subordinates often belonging to other schools. But both as administrators of the law and as custodians of the doctrine of the imamate enunciated by their father, they were challenged by Ya'qub ibn Killis, for whom the post of *wazīr* was reintroduced in 368/979. For the Fatimids this was a major innovation which relieved the monarch of the care of government, including the all important task of hearing petitions in his capacity as the fount of justice. In this judicial role ibn Killis clashed with the sons of al Nu'man, all the more because he had joined the ranks of the *mu'minun* as an initiate who composed a treatise on the law in place of the *Da'a'im*, endowed a number of scholars to teach in al Azhar, the dynastic mosque of al Qahira, and as an arbiter of the faith conducted doctrinal

disputations which included Severus Ibn al Muqaffa', Coptic bishop of Ashmunayn.⁴⁹ The conflict only ended with his death in 380/991.

More importantly for Egypt, ibn Killis had presided over a renewal of prosperity which began when he supervised a reallocation of tax farms, in effect inviting the Egyptians to buy into the new regime. Such investment in the fiscal yield of the economy was matched by investment in its agricultural and industrial production and commercial activity. Waste land was reclaimed for the cultivation of the old winter crops of grain and flax, while artificial irrigation supported the more recent summer crops of sugar cane and cotton. While grain came onto the market largely through taxation of the harvest, flax, sugar cane and cotton were cash crops that fed major industries. Peasant initiative was important, but only at the base of a commercial and industrial enterprise dominated by the wealthy landholding aristocracy of the regime: at his death ibn Killis left a huge stock of linen and perhaps other cloth to be sold by merchants on his behalf. The export of such manufactures was matched by the import of commodities from across the Mediterranean, ranging from timber and metals, olive oil and leather, to silks and other textiles, carried increasingly in Italian ships. The Mediterranean was paired with the Sahara, across which came slaves and gold; but these were only the western extension of an intercontinental commercial network centred upon Egypt. With the decline of Iraq and the Persian Gulf, Egypt had returned to its position in Antiquity as the focus of exchange between the Indian Ocean and the Mediterranean via the Red Sea.⁵⁰ Pepper and spices were only the most exotic of the commodities that travelled from east to west.

With such economic growth a rise in population is indicated, which may have slowed if not halted the long term decline of the Coptic community.⁵¹ It certainly favoured the Jews, as we see from the Geniza documents of the immigrant North African Jewish community at Fustat, employed by Goitein to paint a broad picture of urban society in the Fatimid period.⁵² But as we see

49 See, in addition to Brett, *Rise of the Fatimids*, pp. 386–8, M. Brett, 'al Karaza al Marqusiya: The Coptic Church in the Fatimid empire', in Vermeulen and Van Steenbergen (eds.), *Egypt and Syria in the Fatimid, Ayyubid and Mamluk Eras*, vol. IV (Leuven, 2005).

50 See M. Lombard, *The golden age of Islam* (Amsterdam, Oxford and New York, 1975); K. N. Chaudhuri, *Trade and civilisation in the Indian Ocean* (Cambridge, 1985).

51 See Brett, 'Way of the peasant'; Brett, 'Population and conversion', pp. 10–11.

52 Studied by S. D. Goitein, *A Mediterranean society: The Jewish communities of the Arab world as portrayed in the documents of the Cairo Geniza*, 5 vols. (Berkeley and Los Angeles, 1967–88), vol. I: *The economic foundations*. See also Lev, *State and society*, chs. 9 and 10, 'The urban society of Fustat Cairo' and 'The non Muslim communities'.

in the case of ibn Killis, the greatest beneficiaries were the great men, and women, of the dynasty, whose wealth was increased by investment in long distance trade, and redistributed in lavish expenditure.⁵³ Through such expenditure the dynasty reaped a further reward in the association of the populace with its political and religious programme. Construction work in the capital afforded employment while creating the setting for the celebration of its grandeur. The mosque built by the queen mother Durzan became the centre piece of the royal cemetery and residential suburb of al Qarafa, a place of Shī'ite devotion and popular rendezvous.⁵⁴ Al Qahira itself developed as the ritual city, in Paula Sanders' phrase,⁵⁵ of what Geertz has described in Java as the theatre state, whose spectacular ceremony was at the heart of government.⁵⁶ (For army and bureaucracy, see below.)

Egypt nevertheless remained a *ghulam* state, with an army whose character was determined by the protracted effort of al 'Azīz to regain possession of Syria, first by the reoccupation of Damascus, second by the annexation of Ḥamdanid Aleppo. The opposition of Damascus was not finally overcome until 373/983, and a governor from al Qahira not installed until 378/988; Aleppo, defended by its citizens in alliance with Byzantium, remained independent at al 'Azīz's death in 386/996. In the process, however, the Turkish *ghulam* (see above for preference for the Arabic) Aftakīn, whom Damascus had welcomed as its champion, was defeated in 368/978, captured and received into the Faṭimid army, which thus acquired the nucleus of a force of Turkish cavalry alongside the more lightly armed Kutama Berbers from Ifrīqiya. Meanwhile a force of Daylamī infantry from Iran was recruited alongside blacks from the Sudan. In this way the army became permanently, and dangerously, divided between westerners and easterners. Their rivalry came into the open at the death of al 'Azīz, when the veteran Ifrīqiyan Ḥasan ibn 'Ammar at the head of the Kutama regiments of the army took power as regent for the infant al Ḥakim, only to be defeated by the Turks and ousted by the boy's tutor Barjawan.⁵⁷

The death of al 'Azīz in 386/996, and the accession for the first time of a minor to the imamate and caliphate, put an end to the formidable build up of

53 For the nature of this economy, see Brett, *Rise of the Fatimids*, pp. 286 7, 332 9.

54 See D. Cortese and S. Calderini, *Women and the Fatimids in the world of Islam* (Edinburgh, 2006), pp. 167 9, 187.

55 P. Sanders, *Ritual, politics and the city in Fatimid Cairo* (Albany, 1994).

56 C. Geertz, *Islam observed: Religious development in Morocco and Indonesia* (Chicago and London, 1968), pp. 36 8.

57 See Lev, *State and society*, ch. 5, 'The evolution of the tribal army'.

forces in Syria for an attack upon Aleppo, whose possession was essential for any advance into Iraq. Instead, the pause that it induced in the expansion of the empire set the seal upon the direction this had taken under al 'Azīz. The long drive to recover the Ikhshīdīd and Ṭulunīd territories in Syria had been accompanied by withdrawal from the government of Ifrīqiya, where the death in 373/984 of Buluggīn, the viceroy installed by al Mu'izz, had been followed by an unsuccessful attempt by al 'Azīz to demote his son al Maṣṣūr. The killing by al Maṣṣūr of Muḥammad al Katīb, the minister at Qayrawan whom the caliph had endeavoured to promote, marked the independence of the Zīrid dynasty in return for recognition of Faṭimīd suzerainty. Forced upon al Qahira, this solution to the question of its relationship to the state that the dynasty had left behind became the means to the extension of Faṭimīd sovereignty over the Islamic world. Outside the *dawla* proper, where the imam-caliph ruled as well as reigned, there formed a circle of territories over which he reigned but did not rule, from Ifrīqiya, Sicily and Barqa through al Raqqā, Baḥrayn and Sind to the holy places of Mecca and Medina; their various princes offered the Friday prayer in his name, while the Christian king of Nubia offered the equivalent in the form of the *baqt*. Beyond this circle was what might be called the *Dawla Irredenta*, the lands where the caliph neither ruled nor reigned, but where he strove for recognition to achieve the goal of universal empire. While conquest remained focused on Aleppo, a propaganda campaign conducted by the *du'at* (missionaries) of the imam aimed to bring about the necessary revolution by peaceful or violent means.

The patrimonial state

In Egypt the accession of al Ḥakīm proved to be the beginning of a revolution of a different kind. The Faṭimīds provided Max Weber with a prime example of the institutionalisation of charisma in the patrimonial state, of the way in which government passed out of the hands of a dynasty founded by a religious revolutionary into those of its servants, who governed its patrimony in the ruler's name.⁵⁸ This is indeed the story of their reign in the eleventh century, which began with a rapid and frequently sanguinary turnover of personnel that resolved itself into a more stable ministerial regime before a second crisis ended in government by the commander of the army. Initial responsibility lay with the new caliph. Controversial in his lifetime, al Ḥakīm has remained an

⁵⁸ See B. S. Turner, *Weber and Islam* (London, 1974), ch. 5, 'Patrimonialism and charismatic succession'.

enigmatic figure, with insanity an unsatisfactory explanation for his behaviour.⁵⁹ Controversy was both religious and political, leading to conflict within the dynasty and its following; with the Sunnī population; and with the 'Abbasids, who formally challenged the claim of the dynasty to descent from the Prophet. Analysis is not helped by the paucity of information on the last seven years of the reign, perhaps because of subsequent censorship of the court chronicle of al Musabbihī (d. 420/1029). What is clear is that, after a century of firm direction, the dynasty wavered under al Ḥakim, uncertain of its religious policy and unsure of its servants.

The institutionalisation of the *da'wa* with the creation of the post of chief *da'ī* (caller to the faith) was symptomatic of the underlying problem. While the appointment reflected the consolidation of the Faṭimid following into a worldwide congregation, it emphasised its constitution as the Isma'īliyya, the sectarian name by which the faithful were distinguished from the similarly sectarian followers of the twelfth imam, and *a fortiori* from the body of Sunnī Islam. A movement predicated upon its universal appeal to the entire Muslim community was becoming increasingly separate and increasingly minoritarian. The contrast became apparent in the course of al Ḥakim's reign, as he struggled to come to terms with his role as representative of God on earth. Apart from a string of moral and curious dietary prohibitions, repeated from year to year, policy was inconsistent over the three main periods of the reign, after he took power with the murder of his tutor Barjawan in 390/1000. In the first, he broke with the previously generous interpretation of Jawhar's '*ahd* to curse the Companions and the first three caliphs, and impose their distinctive dress upon Christians and Jews. In 395 8/1005 7, however, he was confronted by the Mahdist rising of Abu Rakwa ('the man with the goatskin waterbottle') in the western desert, prompting a *rapprochement* with the Sunnī population in which the cursing was forbidden, Sunnī observances tolerated and the caliph himself came to lead the prayer in the Mosque of 'Amr in 402 3/1012. In contrast, prohibitions on Christians and Jews hardened into outright persecution. Perhaps in response to Christian millenarianism, around 398 400/1007 10 the Church of the Holy Sepulchre in Jerusalem was destroyed, along with many others. But in 401 4/1011 13 revolt in Syria briefly installed a rival caliph at al Ramla, and in 404/1013 the toleration of Sunnism came to an end along with the persecution of Christians, who were allowed to return, to rebuild

59 See M. Canard, 'al Ḥakim bi Amrī'llah', *Elz*, vol. III, pp. 76–82; Lev, *State and society*, pp. 25–37; T. Bianquis, 'al Ḥ'ākīm bi amr Allāh ou la folie de l'unité chez un souverain fāt'imide', in C. A. Julien *et al.* (eds.), *Les Africains*, vol. XI (Paris, 1978); J. Forsyth, *The Byzantine Arab chronicle (938–1034) of Yahya b. Sa'īd al Anṭakī* (Ann Arbor, 1977).

their churches and resume their faith. Much more radical was the designation in 404/1013 of a cousin, ibn Ilyas, as heir apparent (*walī 'ahd al muslimin*), while he himself withdrew from public life. The most plausible explanation of this departure from the dynasty's fundamental rule of patrilineal succession is that al Ḥakīm considered himself to be the ninth and last imam from the ancestral Muḥammad ibn Isma'īl, after whom only the caliphate would continue in his line. No record of the consternation in the palace has survived, but in 409/1018f. there were riots in Fustāṭ against the preaching of his divinity by two Iranians, al Darazī and Ḥamza. The *da'ī* in Iraq, al Kirmanī, was summoned to clear al Ḥakīm himself of responsibility, but the conjunction of extreme sectarianism with so radical a departure from dynastic orthodoxy dramatically demonstrated the difficulty faced by the Faṭimids in sustaining their appeal after their triumph in the previous century. The crisis only ended with al Ḥakīm's disappearance, presumed murdered, in the desert in 411/1021.

Al Ḥakīm's seclusion in the last seven years of his reign was in contrast to his earlier accessibility, walking in Fuṣṭaṭ and hearing petitions in person. Equally in contrast to what had gone before was the length of the wazīrate of 'Alī, son of the Ja'far ibn Falah slain at Damascus in 360/971, a member of the Berber military aristocracy who governed with the title of Dhu 'l Riyasatayn (the man of two headships, the Pen and the Sword) from 405/1015 until he was murdered by unknown attackers in 409/1019. From the assassination of Barjawan onwards his fellows from the coterie of Ifrīqiyan, Ṣiqḷabī, Berber, Coptic and Iraqi families in the upper echelons of the regime, officiating as judges, generals and ministers, usually with the lesser title of *wasīṭa* (middle man), had been regularly dismissed, and in the previous period frequently executed or mutilated. The pattern resumed in 409/1019, but ended with al Ḥakīm's presumed murder, when ibn Ilyas was put to death, and the succession reverted to al Ḥakīm's youthful son under the name of al Ḥaḥir li i'zaz Dīn Allah ('he who appears openly to strengthen the religion of God').

The title is significant of the return of the dynasty to its previous orthodoxy, but not of a return to firm direction by the sovereign. Until her death in 413/1023 the government was controlled by al Ḥakim's sister Sitt al Mulk, and thereafter manipulated by the queen mother Ruqiyya, with whose support al Jarjara'ī became *wazīr* in 418/1028. An immigrant from Iraq whose hands had been cut off in one of al Ḥakim's many purges, al Jarjara'ī had returned to office as a skilled administrator and consummate politician, who came to the *wazīrate* at the head of a patronage party whose members formed his government. After the turbulence of the previous reign the palace and the personnel of the dynasty colluded in a regime that excluded the monarch but satisfied

the expectations of his servants in the administration and the army. As head of the administration the *wazīr* presided over a miscellany of boards, departments and offices collectively known as the *dawawīn* or *dīwans*, broadly divided between the permanent bureaux dealing with the main areas of revenue, expenditure and documentation, and others created for specific and perhaps temporary purposes, such as the affairs of Syria or the property of the queen mother.⁶⁰ In an age when specific revenues were typically assigned to specific purposes, many of these boards would have arisen within the main departments to take care of special interests, most notably a *dīwan khaṣṣ* or 'privy purse' to meet the expenses of the palace. All of them came under the supervision of the *dīwan al majlis*, the meeting of the heads of department in the presence of the *wazīr*, which had its own secretary. Among the main departments the *dīwan al rasa'il* or *insha'*, the chancellery dealing with state correspondence, was prestigious but peripheral to the *bayt al mal* or treasury, divided between the supervision of taxation and the direction of expenditure. Taxation of all kinds was now generally farmed out on the basis of treasury assessments and valuations. The most essential item of expenditure in this *ghulam* state was the army, which in this period seems to have been paid out of central funds, with specific revenues assigned to specific regiments under the name of *iqṭa'at*, (sing. *iqṭa'*, 'portions'). It was a large and composite force, ethnically divided between Turks, Berbers, Slavs, Greeks, blacks, Iranian Daylamīs and Arab Bedouin, and technically between heavy and light cavalry, heavy and light infantry, archers and spearmen, which required all the political skills of the *wazīr* to control.⁶¹ The navy was a major expense, but from its low profile in the sources lacked a corporate identity and political significance.⁶²

Outside Egypt the main aim of al Jarjara'ī was to restore the Faṭimid position in Syria, where after the death of al 'Azīz the dynasty had been forced back onto the defensive by the Arab Bedouin: the Kilab in the north, who in 1015 established the Mirdasid dynasty at Aleppo in succession to the Ḥamdanids, and the Jarraḥid chiefs of the Ṭayyī' in the centre and south. At Uqhuwana in northern Palestine the Mirdasids and Jarraḥids were

60 See A. F. Sayyid, *al Dawla al faṭīmiyya fī Miṣr/Les Fatimides en Egypte* (in Arabic) (Cairo, 1992), pp. 255–90; Brett, *Rise of the Fatimids*, pp. 341–4.

61 See Brett, *Rise of the Fatimids*, pp. 342–5; M. Brett, 'The origins of the Mamluk military system in the Fatimid period', in U. Vermeulen and D. De Smet (eds.), *Egypt and Syria in the Fatimid, Ayyubid and Mamluk Periods*, vol. I (Leuven, 1995).

62 See Y. Lev, 'The Fatimid navy, Byzantium and the Mediterranean sea, 909–1036 CE', *Byzantion*, 54 (1984).

overwhelmingly defeated in 420/1029. The victor, the Turkish *ghulam* al Dizbirī, became governor of Damascus, while negotiations with Constantinople led to an agreement which not only permitted the Byzantines to rebuild the Church of the Holy Sepulchre, but opened the way for his conquest of Aleppo in 429/1038. This, however, was far from being a resumption of the dynasty's offensive against Baghdad. Politics took precedence over imperial ambitions when al Dizbirī was ousted from Damascus in 433/1041 by an army revolt provoked by the *wazīr*, and Aleppo was lost. Following the death of al Ṣāḥib in 427/1036, the accession of the infant al Mustanṣir and the replacement of his patroness Ruqīyya by a new queen mother, Raṣād, al Jarjara'ī no longer had the palace on his side. Raṣād's own protégé, the Iranian Jewish al Tustarī, was not in a position to replace him as *wazīr*, and his party survived in office after his death in 436/1045. An alternative party had nevertheless begun to form, prompting the murder of al Tustarī in 439/1047, for which the *wazīr*, al Fallaḥī, was arrested and executed in 440/1048. Al Fallaḥī was succeeded by the nephew of al Jarjara'ī; Abu 'l Barakat; but Raṣād's patronage continued to grow at the hands of al Yazurī, the steward of her estates. When the failure of the attack upon Aleppo ordered by the new *wazīr* in 440/1049 prompted his dismissal in 442/1050, al Yazurī had the necessary support to form a government. While never able to command the same broad following as al Jarjara'ī, he was strong enough vigorously to react to the rapidly developing crisis east and west.

The growth of the *da'wa* under al Ḥakīm had been marked by the shift of its intellectual centre from al Qahira to Iran and Iraq, where the *da'ī* al Kirmanī emerged as a major philosopher, and from where al Darazī and Ḥamza came to proclaim al Ḥakīm's divinity before Ḥamza and his followers fled into Syria as the Druzes. The fading of Faṭimid imperialism since the beginning of the century, however, had been matched by the growth of 'Abbasid propaganda, which by the 430s/1040s threatened not only the mission of the dynasty but the whole fabric of its empire. By the time al Yazurī came to power the Zīrids of Ifrīqiya had turned to Baghdad; more seriously, the incoming Saljuqs had taken up the 'Abbasid cause.⁶³ In 443 4/1052 al Yazurī scored a military victory over the Zīrids' allies the Banu Qurra at Barqa, and in 445/1053f. a propaganda victory over the Zīrids themselves after their defeat by the Banu Hilal at the battle of Ḥaydaran in 443/1052; by 449/1057 they had returned to Faṭimid

63 See Brett, *Rise of the Fatimids*, pp. 404 7, 429 30; and M. Brett, 'Abbasids, Fatimids and Seljuqs', in David Luscombe and Jonathan Riley Smith (eds.), *The new Cambridge medieval history*, vol. IV (Cambridge, 2004).

allegiance.⁶⁴ An unsought bonus was the conquest of the Yemen by the *da'ī* al Ṣulayhī between 429/1038 and 455/1063. To counter the Saljuqs after the arrival of Ṭughril Beg at Baghdad in 447/1055 al Yazurī then turned to the *da'ī* al Shīrazī, who had worked to win the last Buyids for al Qahira, and was now entrusted with the raising of an army in Syria for an invasion of Iraq to restore al Basasirī, the former governor of Baghdad, to the 'Abbasid capital. In 450/1058 the invasion was unexpectedly successful, to the delight of al Mustanşir; but not before al Yazurī had been accused of treasonable correspondence with Ṭughril Beg, and executed. Domestic politics had once again proved decisive in determining the direction of both *dawla* and *da'wa*, on this occasion with disastrous consequences. The offensive in Iraq may have been doomed; sixty years after the death of al 'Azīz the *élan* of the dynasty had been lost, and under the *wazīrs* of the Pen the regime was in no shape to repel the Saljuqs, let alone resume the drive for universal empire. It was in Egypt, however, that its fundamental weakness was exposed. The execution of al Yazurī grievously backfired, since now there was no one with sufficient support to form a government. When Ṭughril Beg finally re entered Baghdad in 452/1060 al Qahira was in disarray.⁶⁵

As *wazīrs* came and went with increasing rapidity, the inability of the caliph to take back control of the government was demonstrated by the fiasco of al Mustanşir's attempt to hear petitions himself. A scholarly man, unlike his father, who had the mission of the dynasty at heart, his failure to do so was a measure of the distance travelled by the regime since its installation in Egypt, and a sign of worse to come. The failure of al Yazurī's general, the Ḥamdanid prince Naşir al Dawla, to recapture Aleppo brought him back to Egypt in 454/1062. In 455/1063 the Turks and the blacks, the Mashariqa and the Maghariba, came to blows on the parade ground; from 458/1066 onwards the Turks held the caliph to ransom in al Qahira, while Naşir al Dawla based himself at Alexandria in a bid for power; the countryside was plundered by soldiers and Bedouin. Only after Naşir al Dawla was murdered in 465/1073 was order restored by Badr al Jamalī, the governor of what remained of Faṭimid Syria at Acre, with whom the *wazīrate* passed out of the control of the Men of the Pen into the hands of a Man of the Sword. The pretensions of the imam caliph to universal sovereignty remained, and were indeed revived by the new regime.

64 See Michael Brett, 'The central lands of North Africa and Sicily until the beginning of the Almohad period', in *The new Cambridge history of Islam* (Cambridge, 2010), vol. II: Maribel Fierro (ed.), *The western Islamic world, eleventh to eighteenth centuries*, ch. 2.

65 See M. Brett, 'The execution of al Yazurī', in U. Vermeulen and D. De Smet (eds.), *Egypt and Syria in the Fatimid, Ayyubid and Mamluk Eras*, vol. II (Leuven, 1998).

For Egypt as well as the Faṭimids, however, it was the end of an era. In the great Shidda, the prolonged famine that accompanied the conflict, the population fell;⁶⁶ and with an end to the demographic buoyancy of the previous hundred years it is likely that the balance tipped finally for the Muslims against the Copts.

66 See Brett, 'Way of the peasant', pp. 51–5; Brett, 'Population and conversion', pp. 28–30.

The Iberian Peninsula and North Africa

EDUARDO MANZANO MORENO

The expansion in the west

The Arab conquests in North Africa began soon after the fall of Alexandria to the army commanded by 'Amr ibn al 'Āṣ in 21/642. Unlike previous expansion in the Near East, the march westwards of the Arab soldiers was not marked by sweeping victories and the resigned acquiescence of the conquered populations. Widespread revolts, crushing defeats and hasty evacuations of recently conquered territories fill the terse accounts of the few Arab sources that provide some information on this huge area. In contrast, the narrative of the conquest of Hispania in 92/711 recalls a similar pattern to the invasions in Byzantine and Sasanian territories: after one pitched battle and the defeat of the king's army the Visigothic administration crumbled, clearing the way for an Arab rule which consolidated with remarkable ease and no serious challenges.

The resistance met by the conquerors in the southern Mediterranean was due to the political and social diversity of the region. In the land extending from Alexandria to Tangier the Arabs did not meet one single enemy, but rather a number of enemies whose actions and motivations were diverse, and not always comprehensible to modern historians. Arguably, the main opponent of the invading armies was the Byzantine empire, whose foothold in North Africa went back to the times when, in 534, the generals of the emperor Justinian conquered the Vandal kingdom. As shown by the rescripts he issued in the aftermath of the conquest, Justinian's grandiose idea had been to restore the ancient limits of Roman Africa, from Tripolitania, adjoining Egypt, to Mauritania on the Atlantic shores, from coastal cities to pre desert enclaves.¹ This ambitious scheme was doomed to failure, however. In classical times North Africa had become a vast frontier, which stood against the sporadic

1 *Codex Iustinianus*, ed. P. Krueger (Berlin, 1954), I, 27, I, 7 12 and I, 27, 2, 1^a.

attacks of peripheral Berber tribes. Its government rested on the loyalty of assimilated native populations, on a complex network of diplomatic dealings with tribal chieftains, and on tight control, through military operations by police and garrisoned checkpoints, of the tribes' nomadic movements. This system gradually collapsed from the second half of the fourth century onwards. The inability of the Roman frontier (*limes*) to protect the rich coastal cities against tribal incursions and the growing disaffection of the class of indigenous landowners, who became tribal warlords at the final stages of imperial rule, made up the awkward legacy left by the late empire to its successors in North Africa. Tribal pressure on Tripolitania increased throughout the Vandal period as witnessed by the devastation of Leptis Magna (Lebda in modern day Libya) or the heavy defeat inflicted on the Vandal army before 523 by the Laguantan, a tribe which came from the oases of western Egypt. The last Vandal kings were familiar with the names of Ortaias, Iaudas or Antalas, Berber warlords whose rule over pastoralist tribes and sedentary communities of pre desert regions in the Hodna, the Aurès or the Tunisian Dorsal posed a serious threat to their domains in *Africa Proconsularis* and northern *Byzacium*, broadly speaking the same land that the Arabs later called Ifrīqiya.

The Vandal kingdom disintegrated before the Byzantine army, but the complex socio political conditions of North Africa remained almost unchanged. Some tribal leaders switched their loyalty to the new rulers and were invested with insignia and emblems of power following a Roman practice, which had been maintained by the Vandal kings. The most skilled Byzantine generals (*duces*) and governors (*exarchs*) managed to draw other warlords into this sort of alliance, either extolling force or resorting to diplomacy. Berber troops swelled the field armies in the capacity of auxiliary troops, not always trustworthy but nevertheless always at hand, even in the final moments of imperial rule. However, relations were often strained. The plundering of cities and rural areas by uncommitted tribes such as the Laguantan continued throughout the whole period, particularly in Tripolitania and *Byzacium*; ill timed killings or humiliations of hitherto allied tribal chieftains by Byzantine officials sparked fierce rebellions, which were also inflamed by the depredations of imperial troops in tribal territories.

If we bear these precedents in mind, it is hardly surprising that Arab sources do not mention any serious opposition from the Berber tribes found by the conquerors in the lands bordering on Egypt. The troublesome Laguantan (Ar. Lawata), who inhabited the vicinity of Barqa, agreed to come to terms with the newcomers. Perhaps the key to this understanding was the fact that Arab

governors of Egypt led the early campaigns in the form of raids against cities in Tripolitania and Byzacium, very much in the same way that this tribe had been doing until then. The most successful of these expeditions was commanded by ‘Abd Allah ibn Abi Sarḥ, which defeated the army of the Byzantine exarch Gregorius near Sufetula in 27/647. However, ‘Abd Allah did not attempt to gain a territorial foothold in the region, and retreated to Egypt after having exacted tribute from the province.²

The actual occupation of North Africa was only carried out under the Umayyad caliphs of Damascus. Raiding expeditions were abandoned when the caliph Mu‘awiya (41 60/661 80) entrusted Ifrīqiya to ‘Uqba ibn Nafi‘. The campaigns of the previous decades had somehow ensured the occupation of Tripolitania, and at this juncture (50/670) ‘Uqba managed to found a new city, Qayrawan, in a strategic location at the heartland of former Byzacium, which rapidly became the main outpost of Arab settlement in North Africa. Although still in possession of Carthage, the Byzantines were unable to prevent this move, and in the following decades the main opposition to the Arabs came from Berber tribes throughout the extensive lands, which lay outside the former *limes*.

Umayyad governors of Qayrawan soon had to face the same dilemma as their Byzantine predecessors: how to accommodate these Berber populations into the imperial scheme the governors represented. Military conquest and cooperation were the mutually exclusive options considered from the very beginning, as shown by the fierce rivalry that pitted the governor ‘Uqba ibn Nafi‘, an advocate of aggressive warfare, against his successor, Abu ‘l Muhajir Dīnar (55 61/674 680), who seems to have been more inclined to reach compromises with Berber chieftains. Although the former option prevailed during ‘Uqba’s second tenure of governorship (61 3/680 3), it was handicapped by the vastness of the region and the military strength that tribal warlords were able to assemble. The celebrated campaign led by ‘Uqba against the Maghrib allegedly reached the Atlantic shores of today’s Morocco, but ended with his death and the defeat of his army in Tahuda (south east of Biskra) at the hands of a confederation of Berber and Byzantine troops led by a shadowy figure called Kusayla (or Kasīla). The disaster forced the Arabs to evacuate Qayrawan, allowing a brief Byzantine recovery from Carthage. It took a vast number of troops mobilised with characteristic

2 This tribute was presumably paid in gold, which seems to have circulated in significant amounts in the province in this period: see R. Guéry, C. Morrison and H. Slim, *Recherches archéologiques franco tunisiennes à Rougga. 3: Le trésor de monnaies d’or byzantines* (Rome, 1982), pp. 76–94.

boldness by the caliph 'Abd al Malik (65 86/685 705) to dispose of Kusayla. Arab sources claim that the new governor, Ḥasan ibn al Nu'man, entered Qayrawan again and conquered Carthage for the first time in 78/697, but these events suggest that at this juncture Arab rule still depended exclusively on military might, without affecting the social fabric of North African populations.

The weaving of this social fabric involved a long and complex process. Arab sources encapsulate it in a narrative whose main character is a riveting female figure called al Kahina ('the sorceress'), who fought Ḥasan ibn al Nu'man with her Jarawa tribe from the Aurès mountains. The broad 'historical' details of her deeds are quite similar to those mentioned in the war against Kusayla: under al Kahina's leadership Berber tribes massacred Ḥasan's army, forcing him to evacuate Qayrawan, while a short lived reconquest of Carthage by the Byzantine navy once again shook the foundations of Ifrīqiya. But, more than the historical circumstances, it is the legend that matters in these accounts. Al Kahina is depicted as a soothsayer and mother of two sons: one Berber, the other of a Greek father. The family grows when al Kahina adopts an Arab prisoner through a rite of simulated suckling. But she is well aware that it is not her destiny to reign over this mixed progeny, as she foresees her own defeat and death at the hands of the reshuffled troops of Ḥasan ibn al Nu'man. The recognition that the rule of the Arabs will prevail moves her to entrust her sons to Ḥasan, who fulfils the prophecy by defeating and killing al Kahina, but also by giving to one of her sons the command of the Berber troops of his army. The death of al Kahina and the assimilation of her offspring were the preconditions for the establishment of the new administration: the account ends with the Arab governor peacefully ruling in Qayrawan and organising the fiscal system which taxed Christians of both Byzantine (*'ajam*) and Berber origin.

As the final narrative of the conquest of Ifrīqiya, the legend of al Kahina enshrines an interpretation of the consolidation of Arab rule over Berber tribal chieftains. Under these new circumstances, joining the ranks of the conquerors as troops in the service of Arab military leaders was the way to fit into the new order, as al Kahina had prophesied to the son who was later promoted in the army of Ḥasan ibn al Nu'man. In what may be seen as a fulfilment of al Kahina's vision, a few years after the pacification of Ifrīqiya, in 92/711, Berber troops took part in the Arab expedition that crossed the Straits from Ceuta, landed in the Iberian Peninsula and defeated the Visigothic army. Most of the 18,000 soldiers who allegedly took part in this early campaign were Berbers who had joined the Arab army of the governor Musa ibn Nuṣayr. The conquered had become the conquerors, and for a moment it seemed that

further expansion offered the possibility of a smooth integration of the Berbers into the empire of the Umayyads.³

The consolidation of Arab rule in the Iberian Peninsula took a different path. The Arab and Berber troops who landed in Hispania in 92/711 had responded to an appeal made by one of the factions fighting in a dynastic dispute, which opposed the sons of the late Visigothic king, Witiza (d. 710), against the partisans of Roderic, who was considered a usurper by his foes. Lacking enough military resources, the sons of Witiza appealed to the new authority, which had emerged beyond the Straits. The expedition was commanded by Ṭariq ibn Ziyad, probably a Berber chieftain acting as a lieutenant of Musa ibn Nuṣayr, the new Arab governor of Ifrīqiya. The defeat of Roderic at the battle of Guadalete and the success of the ensuing campaign convinced Musa that a full fledged conquest was feasible. He decided to lead the expeditions personally, rapidly conquering the main cities – Cordoba, Seville, Toledo and Saragossa – while Visigothic administration broke down.⁴ When Musa was summoned to the east by the caliph al Walid (86 96/705 15), who was increasingly worried by the independence his warlike governor was showing, he could boast that he had left behind a territory that, although perhaps not wholly subdued, certainly lacked any unified opposition against the new rulers.

The sudden fall of the Visigothic kingdom was caused by its own political and social fragmentation. The bitter dispute, which had involved King Roderic and the sons of his predecessor, was the outcome of decades of internal turmoil marked by an increasing estrangement of the landowning class from the monarchy. A number of military laws issued by the last kings show this class ignoring summonses to join the royal army or turning up with a minimal part of their private retinues. Harsh penalties and fines were decreed for those who failed to comply with royal appeals, but the fact that the problem had to be addressed again and again indicates a growing alienation of the monarchy from its social base.⁵ When the kingdom had to face a threat as serious as the Arab invasion, the aristocracy reacted as the kings had been fearing: after the defeat of Guadalete cities and territories were left to their own devices, and resistance was only possible where local defences could be gathered. In the absence of any centralised authority the Visigothic aristocracy opted to

3 M. Brett and E. Fentress, *The Berbers* (Oxford, 1996), pp. 83 7.

4 P. Chalmeta, *Invasión e islamización: La sumisión de Hispania y la formación de al Andalus* (Madrid, 1994).

5 A. Barbero and M. Vigil, *La formación del feudalismo en la Península Ibérica* (Barcelona, 1978), pp. 201 7; A. Isla, 'Conflictos internos y externos en el fin del reino visigodo', *Hispania*, 62 (2002), pp. 619 36.

safeguard their own interests. Local and personal pacts were established, which explain the variety of situations that the conquest engendered. Characteristically, these different outcomes expressed themselves in terms of ethnicity, of the assimilation into the Arab stock of some members of the aristocracy, while others preserved their indigenous identity even though they also converted to Islam at a very early stage.

Assimilation was the path followed by those who chose to collaborate with the conquerors from the very beginning. Among them the sons of Witiza Arṭubas, Waqīla and Alamund were the most outspoken partisans of the new order. As its beneficiaries they prospered in the aftermath of the conquest. Their wealth was based on the extensive lands inherited from their father, whose undisputed property was recognised by the Arabs. The senior brother, Arṭubas, is described as a great landowner, revered and respected by the conquerors, who entrusted to him the collection of taxes among the Christians. He was still alive several decades later, when the first Umayyad *amīr*, ‘Abd al Raḥman I (138 72/756 88), confiscated some of his extensive landholdings. Nothing is known of Arṭubas’s offspring. If we are to believe the Arab sources the only descendants of this family were those of Sara, daughter of Alamund, who managed to preserve her father’s extensive properties in the Seville region against the rapacity of her uncle Arṭubas. Sara was married twice, to prominent members of the Arab army, and her descendants became leading Arab families of Seville in later centuries, such as the Banu Ḥajjaj or the Banu Maslama. The unyielding system of Arab kinship, which was based on patrilineal descent, obscured the distant Visigothic ascendancy of these lineages, and in fact we would be unaware of their distinguished ancestry were it not for the fact that one of her descendants, Ibn al Qutīyya (d. 361/971), wrote an account of the conquest in which the deeds of his great grandmother were described in some detail.⁶

A similar case was that of Theodomir, a Visigothic *dux* who ruled in the south east of the Peninsula, in a region which the Arabs named Tudmīr after him. At the time of the conquest Theodomir entered into a pact with the conquerors, a pact whose wording has been preserved in late compilations and which bears strong resemblances to similar post conquest agreements in the Near East: in exchange for recognition of his rule and the guarantee of safety for his subjects and religion, Theodomir undertook to pay a certain amount of taxes in cash and kind to the Arabs. Whether the wording of this

⁶ Ibn al Qutīyya, *Ta’rīkh iftītaḥ al Andalus*, ed. P. de Gayangos, E. Saavedra y F. Codera (Madrid, 1868), pp. 2 4.

pact is genuine or not, it is clear that Theodomir established a close relationship with the new rulers, which led to the marriage of his daughter to a member of the Arab army, one 'Abd al Jabbar ibn Khattāb. The descendants of this union were called the Banu Khattāb, and became a rich and influential family of local 'ulama' until the end of Islamic rule in the region of Murcia in the eighth/thirteenth century.

In the decades after the conquest this kind of marriage alliance may have been quite common. Echoes of this practice reached even Rome, as witnessed by a letter written by Pope Hadrian around 785, in which he complained that in Hispania some who called themselves Catholics had no objection to marrying their daughters to the heathen breed. Bishops who met at a council held at Cordoba in 836 also condemned mixed unions. The concerns of the Church were fully justified, as marriage of indigenous women with members of the conquering army resulted in their integration into the rigid structures of Arab patrilineal kinship and their detachment from the social networks where the Church had hitherto maintained its influence.⁷

However, not all members of the Visigothic aristocracy who reached agreements with the conquerors were assimilated into Arab kinship. Some accounts in early Latin chronicles refer to diehards who continued to resist for several years after 92/711, sheltered in their domains in the rural areas.⁸ Eventually they also came to terms with the conquerors, but they managed to preserve not only their realms but also their own distinctive identity. This was the case with Casius, a military man who was stationed in the Upper Ebro valley, on the northern frontier that the Visigothic kings had established against the restless northern populations. When the conquerors arrived in his domains Casius came to an agreement with them, and it is even claimed that he converted to Islam in Damascus at the hand of the caliph al Walīd, becoming his *mawla*. Be this as it may, the offspring of Casius, the so called Banu Qasī, were Muslims, and in the two centuries following the conquest they ruled, with a high degree of independence, a territory which stood as a frontier (*thaghr*) against the northern Christian kingdoms.

7 *Monumenta Germaniae Historica, Epistolae Merowingici et Karolini. Aevi*, III/I, ed. E. Dümmler and W. Gundlach (1892), p. 643. 'Concilium Cordubense', in *Corpus Scriptorum Muzarabicorum*, 2 vols., ed. I. Gil (Madrid, 1973), vol. I, p. 140. On the role of women in networks of kinship and power, see M. Marín, *Mujeres en al Andalus* (Madrid, 2000), pp. 395–597.

8 *Crónica Mozárabe de 745*, ed. J. E. López Pereira (Saragossa, 1980), p. 54; *Crónica de Albelda*, in *Crónicas Asturianas*, ed. J. Gil, J. L. Moralejo and J. I. Ruiz de la Peña (Oviedo, 1985), p. 183.

Like the Banu Qasī, other powerful Muslim families of indigenous stock were in command of rural districts in different parts of the Peninsula. Their agreements with the conquerors guaranteed their rule over territories, which included fortifications and villages (*castris et vicis*) where they collected taxes which were forwarded to the Arab governors, provided the latter had enough political and military resources to enforce their authority. Arab chroniclers of the fourth/tenth century called them *muwalladun* in the accounts of the endless struggles that Umayyad *amīrs* faced in order to subdue them, as will be seen below.

Although most written Arab sources from the third and fourth (ninth tenth) centuries in Umayyad Cordoba insist that the conquest had been accomplished following the legal rules regarding territories conquered 'by the force of arms' (*'anwatan*), such claims were designed to support legal claims based on Maliki law, which decreed that a territory conquered on these conditions belonged to the Muslim community. The descendants of the conquerors upheld a different interpretation, however: the conquest had been carried out by means of ad hoc agreements, and the lands they possessed had been acquired through dealings with the indigenous population and not as concessions that the Umayyad *amīrs* had bestowed upon them in their capacity as administrators of the lands of the Muslim community. As we have seen, this view of the conquest was the closest to reality, but late Umayyad historiography and legal opinions staunchly rejected it, as it also denied central government the control of that fifth (*khums*) of the lands that legally would have corresponded to the *amīrs* had al Andalus been conquered 'by the force of arms'.⁹

It is doubtful, therefore, whether the way the conquest had in fact been conducted justified the collection of large tax revenues for the caliphal administration and even more doubtful that tax receipts ever reached Damascus. If coinage is an indicator of tax collection, the limited number of coins issued by the first governors shows a poor fiscal harvest. Soon after his arrival Musa ibn Nuṣayr coined gold pieces in Hispania which were imitations of the Byzantine *solidi* from North Africa. These early coins date from as early as 93/711f., and give testimony to a conquest led by a strong and self aware military command. They bear Latin inscriptions which translate the Muslim profession of faith, 'There is no god but God': *Non Deus Nisi Deus Non Deus Alius*. Soon the model changed, incorporating bilingual legends in Latin and Arabic, which proves that al Andalus, the name given by the conquerors to

9 E. Manzano Moreno, 'Las fuentes árabes sobre la conquista de al Andalus: Una nueva interpretación', *Hispania*, 202 (1999), pp. 389–432.

Hispania, was already in use by 98/716f. Finally, the coins issued in al Andalus adopted the reformed model of the caliph 'Abd al Malik in 102/720f. However, gold coinage stopped in 127/744f. The governors minted silver *dirhams* more or less regularly, but they do not seem to have circulated in large amounts, judging from the number of preserved specimens.¹⁰

The extent to which the conquest of al Andalus may have been unprofitable for the caliphal treasury is further confirmed by the fact that most of its governors were appointed by rulers of Ifrīqiya. The caliph 'Umar II (r. 99 101/717 20) even considered the idea of abandoning the new territory altogether, possibly because the resources it yielded to the caliphate did not justify the deployment of the army in such a distant land.¹¹ However, 'Umar was convinced to give up his plans, and instead he appointed al Samḥ ibn Malik al Khawlanī as governor of al Andalus. His short tenure (100 2/718 21) was important for two reasons: first, he ordered the first tax census of the whole province; and second, he led the first Arab expeditions into southern France. Both decisions had the same aim (to improve the meagre resources yielded by the province) but in the long run their success was uneven. Military campaigns in southern France achieved the occupation of Septimania, the last stronghold of Visigothic rule, which served as a base for further raids into the land where Carolingian rule was emerging. However, the crushing defeat of one of these expeditions at Poitiers by the Carolingian Charles Martel in 732 and the conquest of Narbonne by the Carolingians in 759 marked the end of these adventures beyond the Pyrenees. In contrast, the organisation of the tax administration had far reaching consequences. Al Samḥ's was the first of the three surveys conducted under the rule of the governors. They were probably carried out every fifteen years, as in other parts of the empire.¹² Once the expansion was over, the conquerors began to turn to a more systematic exploitation of the new province. The achievement of this goal was possible through the invaluable help of fresh troops, who arrived in al Andalus in the dramatic circumstances of a revolt, which shook the foundations of Arab rule in the west.

10 A. Balaguer, *Las emisiones transicionales árabe musulmanas de Hispania* (Barcelona, 1976), pp. 105 11. On the name 'al Andalus', see J. Vallvé, *La división territorial de la España Musulmana* (Madrid, 1986), pp. 17 62; F. Corriente, *Léxico estándar y andalusí del Dīwan de Ibn Quzman* (Saragossa, 1993), pp. 22 3.

11 Ibn al Qutīya, *Ta'rikh*, p. 12; *Akhbar majmu'a*, ed. and trans. E. Lafuente Alcántara (Madrid, 1867), pp. 23/34.

12 *Crónica de 754*, pp. 84, 104, 122. After the first census by al Samḥ, the other two were conducted by governors 'Uqba ibn al Ḥajjaj (117 23/735 or 736 40) and Yusuf al Fihri (130 8/747 56). Note that an interval of fifteen years fits the periods of tenure of these three governors.

The Berber revolt

The earliest surviving account of the conquest of North Africa was written not by a chronicler but by a jurist, Ibn 'Abd al Ḥakam (d. 257/870), who belonged to the Malikī circles of Egypt. One of the pieces of information he included in his work was supported by other Malikī jurists and described the submission of the Lawata Berbers from Cyrenaica during the first campaign led by 'Amr ibn al 'Āṣ. Under the terms of a pact they agreed to pay a tax (*jizya*) of 13,000 *dīnars*, but in order to gather this cash they were given permission to sell their own children. This historical account bears witness to the interest of Egyptian religious scholars in the narratives of the early conquests as a means to justify certain legal interpretations, in this case how to deal with heathen peoples. In this connection, there is no doubt that some Egyptian *fuqaha* (jurists) deemed the buying and selling of certain Berbers as lawful.¹³ There was no lack of arguments for this position: the difficulties of the conquest, the paganism or, at least, the uncertain religious persuasion of some tribes and the number of revolts that the Berbers had led against Arab rule all justified their harsh treatment. Slaves taken in triumphant campaigns were counted by the thousand, and once the conquests were over their flow to the east did not stop. Even the 'Abbasid caliph al Maṣṣūr (r. 136 58/754 75) is reported to have been enraged when at the time of his accession he did not receive the usual shipment of slaves as a gift from Ifrīqiya; its governor, 'Abd al Raḥman ibn Ḥabīb, claimed that all the population of his province had become Muslims and that their enslavement was therefore unlawful.¹⁴

These harsh conditions contrasted with the fact that many Berber chieftains had agreed to join the Arab armies as auxiliary troops. They had taken part in the conquest of al Andalus, where they had settled in extensive regions in the eastern and central Peninsula, or had joined the ranks of the Arab army stationed in North Africa. These Berbers realised now that their submission (*islam*) had been 'employed as an instrument of government', and they decided to resist.¹⁵ When the Arab governor of Ifrīqiya, Yazīd ibn Abī Muslim, ordered his Berber body troops to be tattooed, as was the custom

13 Ibn 'Abd al Ḥakam (d. 257/870), *Futuḥ Miṣr wa l Magrib wa l Andalus*, ed. C. C. Torrey (New Haven, 1922), pp. 170 1; R. Brunschvig, 'Ibn 'Abd alhakam et la conquête de l'Afrique du Nord par les Arabes', *Annales de l'Institut d'Etudes Orientales Université d'Alger*, 6 (1942 7).

14 M. Talbi, *L'émirat aghlabide (184 296/800 909): Histoire politique* (Paris, 1966), pp. 25 35.

15 M. Brett, 'The Arab conquests and the rise of Islam in North Africa', in J. D. Fage and R. Oliver (eds.), *The Cambridge history of Africa*, 8 vols. (Cambridge, 1978), vol. II: *From c. 500 BC to AD 1050*, p. 512.

with slaves, they killed him (102/720). Twelve years later, in al Andalus, a Berber called Munuza, who was stationed in the garrison posts near the Pyrenees, rebelled against the governor of Cordoba due to the oppression suffered by his people.¹⁶ Munuza was easily disposed of, but his revolt shows that al Kahina's vision was waning as former subjects were becoming restless foes. An account highly sympathetic to Berber claims describes an attempt made by ten military chieftains to transmit their grievances to the caliph Hisham (r. 105 25/724 43): they felt utterly discriminated against by governors who, favouring the Arabs, humiliated them in the distribution of booty, deployed Berber soldiers in sieges while the Arabs were retained at the rear and, finally, imposed harsh levies in cattle and slave girls on Berber tribes. The petitioners waited in vain for an audience with the caliph and, once they became convinced that their complaints would never receive attention, they decided to raise the standard of rebellion in 122/740.¹⁷

It was a long and complex revolt. Its first leader was Maysara al Madgharī, allegedly one of the frustrated ambassadors to the caliph Hisham. Under his command the rebels occupied Tangier and most of today's Morocco. Soon afterwards the rebels decided to depose him and appointed Khalid ibn Ḥumayd al Zanatī as their leader. An Arab army sent by the Ifrīqiyan governor 'Ubayd Allah ibn al Ḥabḥab was annihilated at what came to be known as the battle of the Nobles (123/740) due to the large number of principals killed on the field. By then the rebellion had extended to al Andalus: three columns of Berber troops marched against Toledo, Cordoba and the Straits.¹⁸ Alarmed by the news coming from the west, the caliph Hisham dispatched the imperial troops of the Syrian army (*jund*) led by Kulthum ibn 'Iyād, who also recruited troops in Egypt. The army, plagued by dissent between its Syrian commanders and North African Arabs, was routed in the battle of the river Sebou, another disaster in the long list of military calamities that filled the caliphate of Hisham.¹⁹

The outcome of this defeat was very different in al Andalus and North Africa. Most of the remnants of the Syrian army gathered in the garrison harbour of Ceuta. Surrounded by enemies who denied any possibility of return, the survivors had no choice but to cross the Straits towards al Andalus. An initial

¹⁶ *Crónica de 754*, p. 96.

¹⁷ *The history of al Ṭabarī*, vol. XV: *The crisis of the early caliphate*, trans. R. S. Humphreys (Albany, 1990), pp. 20 2 [2815 16].

¹⁸ *Crónica de 754*, pp. 108 10.

¹⁹ K. Y. Blankinship, *The end of the jihad state: The reign of Hisham ibn 'Abd al Malik and the collapse of the Umayyads* (New York, 1994), pp. 206 12.

refusal to admit them by the governor, ‘Abd al Malik ibn Qaṭan, changed to a conditional approval once he realised that he lacked the resources necessary to quell the Berber rebels threatening his own rule. The arrival of the Syrians in the Peninsula helped to crush this revolt, but they soon made it clear that, contrary to the governor’s desires, they had no intention of returning to their own country or of crossing the Straits again to face the rebellion that was still active on the African shores. They decided to settle in al Andalus, a move that found staunch opposition from the early conquerors. The Syrians finally got the upper hand, but only after a decade of fighting which coincided with the fall of the Umayyad caliphate in the east and the de facto independence of the province.

The conditions that regulated the final settlement of the Syrian army had far reaching consequences. In al Andalus the *jund* kept its original organisation of troops divided into a number of army districts. The original names of these districts were maintained, and each of them was allotted a territorial circumscription. Thus, the *jund* of Ḥimṣ settled in the province (*kura*) of Seville; Damascus received the *kura* of Elvira; Palestine the *kura* of Algeciras; Qinnasrīn the *kura* of Jaén; Jordan the *kura* of Rayyo whereas the troops of the *jund* of Egypt were divided among the *kuras* of Niebla and Tudmīr. In these conscriptions the troops did not remain garrisoned in cities; they settled in villages (*qarya*; pl. *qura*) where they were in charge of the collection of taxes from the indigenous populations: a fixed amount of the tax receipts were forwarded to the governor’s coffers in Cordoba, while the rest was kept by the troops as their means of living. Whenever the army was mustered for an expedition, both the commanders and the rank and file received stipends. By the terms of this arrangement the Syrians were accommodated and the rights of the early conquerors, who had become landowners and were obliged to pay the tithe (*‘ushr*), were respected. When the Umayyad ‘Abd al Raḥman ibn Mu‘awiya arrived in al Andalus a few years later, the foundations of the fiscal administration of this territory had already been laid.²⁰

Meanwhile, what remained of Umayyad North Africa was plunged into chaos. After their victory at Sebou the rebels advanced eastwards to Qayrawan, gaining the support of Berber groups from Ifrīqiya led by ‘Ukkasha ibn Ayyub al Fazarī, perhaps a Persian who had deserted the ranks of the Syrian army. The capital would have fallen to the rebels had it not been for the victories gained at its gates by the former governor of Egypt, Ḥanzala

²⁰ E. Manzano Moreno, ‘The settlement and organization of the Syrian junds in al Andalus’, in M. Marín (ed.), *The formation of al Andalus*, vol. I: *History and society* (Aldershot, 1998), pp. 85–115.

ibn Ṣafwan, in 125/743. But the times of hasty expansions and recoveries were definitively over. Caliphal rule never extended again beyond the Zab. Western North Africa became a distant territory populated by countless tribes whose chieftains were convinced that al Kahina was wrong when she had predicted that Berbers were doomed to assimilation into the imperial scheme of the Arabs. Consequently, local dynasties replaced caliphal governors. The origins of these dynasties were very varied – some indigenous, some founded by oriental exiles – and their ideological justification is not always clear, as it is possible that their dogmas were not so well established at this period as later accounts would lead us to believe. But it is difficult to overlook the fact that eastern preachers and fugitives, sharing, in one way or another, the deep impact of the new order, succeeded where caliphal armies had previously failed.

The arrival of eastern ideologies and dynasties

The last governor appointed by the Umayyads in Ifrīqiya was Ḥanzala ibn Ṣafwan, who was deposed in 127/745, following the assassination in the east of the caliph al Walīd II; a year later Abu 'l Khaṭṭar al Kalbī, the Umayyad governor of al Andalus, was also overthrown by the army. Another coincidence is that the political vacuum was filled by members of the same family: in North Africa 'Abd al Raḥman ibn Ḥabīb had been the leader of the coup that expelled Ḥanzala, while in al Andalus his cousin 'Abd al Raḥman ibn Yusuf al Fihri became governor with the support of the army. Both were descendants of the celebrated conqueror 'Uqba ibn Nafi', whose offspring had emerged as one of the most influential families in the region after his heroic death.²¹ Both attempted to establish independent rule during the years of turmoil caused by the fall of the Umayyads in the east and the coming of the 'Abbasids. Both of them failed. In the case of the self-proclaimed governor of Ifrīqiya, family disputes prevented him from consolidating his dynasty as he was assassinated by his brothers in 137/755. Three years later (140/757) Qayrawan was plundered by the Berber tribe of the Warfajjuma, who had been summoned by one of the factions struggling for power.²²

Meanwhile, the arrival in 137/755 of an Umayyad, 'Abd al Raḥman ibn Mu'awiya, frustrated the plans of Yusuf al Fihri. His rule in al Andalus was

21 P. Guichard, *al Andalus: Estructura antropológica de una sociedad islámica en Occidente* (Barcelona, 1976; repr. Granada, 1998), pp. 526–45.

22 G. Marcais, *La berbérie musulmane et l'Orient au moyen âge* (Paris, 1946), pp. 43–53.

an extraordinary achievement. He was a grandson of caliph Hisham who had escaped the manslaughter of his family that was ordered by the 'Abbasids in the east. A young man in his twenties, when 'Abd al Raḥman came ashore in al Andalus he was met by an army whose leaders had never seen him before but who, nevertheless, were ready to fight for his cause. Many of these leaders were Umayyad clients (*mawālī*), who had arrived in al Andalus in the ranks of the Syrian *jund*. Among the factions bidding for power in these years they displayed sufficient cohesion and political shrewdness to be able to convince other *jund* commanders to join their ranks in order to defeat Yusuf al Fihri. The descendants of these *mawālī* became the backbone of the Umayyad administration for more than two centuries. Generations of the Banu Abī 'Abda, the Banu Khalid or the Banu Bukht to name just a few of these families were appointed as viziers, generals or district governors, and all of them could boast that their ancestors had supported the claims of 'Abd al Raḥman I when he arrived as a destitute fugitive.²³

After his proclamation 'Abd al Raḥman I (r. 138 72/756 88) had to curb a number of internal rebellions. Some were led by members of the Fihrid family or by ambitious leaders of the *jund*, and others were ill fated attempts to extend 'Abbasid rule to this distant land. The most serious of these rebellions, however, affected the Berber tribes who had settled in central al Andalus. It lasted several years (c. 151 60/768 77, the chronology is uncertain), until its leader, a certain Shaqya al Miknaṣī, was killed by some of his supporters, perhaps fearing the authority he commanded among their fellow tribesmen. According to the cursory accounts of the sources, Shaqya pretended to be a descendant of the Prophet because his mother was called Faṭīma, like the celebrated daughter of Muḥammad. It is difficult to draw any conclusive interpretation of what the preaching of Shaqya stood for, but it seems that if it had any Islamic sectarian influence, it was Shi'ism that coloured it. In contrast, Kharijism seems to have lost momentum among the Berbers of al Andalus. Even though the great rebellion of 122/740 is portrayed by some sources as inspired by Ṣufrism, later heterodox movements stirred by Kharijism were very few and unimportant.²⁴

Quite the opposite happened in North Africa, where the political seeds of Kharijism took strong root among populations whose tribal structures were fertile ground for this movement. Sources depict two stages in the Islamisation

23 M. Méouak, *Pouvoir souverain, administration centrale et élites politiques dans l'Espagne umayyade (Ile IVe/VIIIe Xe siècles)* (Helsinki, 1999), pp. 74 7.

24 M. I. Fierro, *La heterodoxia en al Andalus durante el periodo omeya* (Madrid, 1987), pp. 28 30, 39 41.

of the region. The first coincided with the Arab conquest, when some governors strove to extend the preaching of Islam among the Berbers with the help of numerous *tabi'un*, a name given to prestigious Muslims who had met Companions of the Prophet and could therefore boast a first hand knowledge of his life and deeds. However, if we are to believe the accounts claiming that the great Berber rebellion of Maysara was inspired by Kharijism, these orthodox agents had been replaced by missionaries sent from Baṣra, the headquarters of the movement in the first decades of the second century AH.

The beginnings of the agitation by these missionaries are far from clear. Late sources describe the arrival in the west of a group of preachers with no weapon other than a message, which associated salvation with political action. The preference shown towards these missionaries in marginal regions allowed them to give up the practice of concealment (*taqiyya*), which caliphal repression had made obligatory in the east, and to turn their message into one that called for open rebellion, which found enthusiastic adherence among countless supporters. Oppressed audiences were receptive to an ideology that rejected the notion that Muslim authority had to be restricted to a single family, the Qurashite Umayyads, who, as holders of the caliphate, had been responsible for all the grievances suffered by North African populations. The loathing of tyranny and injustice was accompanied in Kharijite discourses by a historical interpretation, which deemed the unfair treatment of the Berbers to be the consequence of the wrongdoings of the caliphs who had ruled the *umma* since the first civil war (*fitna*).

The fading of caliphal administration in western North Africa allowed for the re emergence of tribal leaders who, sources claim, profited from the ideological framework of Kharijism to consolidate their rule. Some narratives of the origins of these leaders explicitly link them with the rebellion of 122/740. This was the case of the Banu Midrar, who defined themselves as Kharijites and whose ancestor is said to have belonged to the tribe of Miknasa and to have fought in the ranks of Maysara al Madgharī. With a number of fellow tribesmen and believers he marched from Tangier southwards, to the region of Tafilalt, where he founded the city of Sijilmasa in 140/757. In the following decades the city was surrounded by walls and endowed with a mosque. Its strategic location on the western route connecting the Maghrib with the rest of Africa stimulated its growth in the third and fourth (ninth tenth) centuries as slave and gold trade with the Sudan and mining in the neighbouring regions attracted a mixed population of Arabs, Berbers, Jews and black Africans.

Sources also claim that a certain Ṣaliḥ ibn Ṭarīf had fought in the army of Maysara, along with his father, who had taken part in the early conquest of


al Andalus. This Ṣaliḥ is credited with the foundation of the Bargawāṭa sect among the Maṣmuda and other tribes settled on the plain of Tamasna, south of the river Bou Regreg in modern Morocco. In this milieu he decided to present himself as a new prophet. He therefore produced a Qur'an written in Berber and laid down a number of prescriptions on fasting, praying and dealings with unbelievers, which were kept secret until his grandson, Yunus ibn Ilyas (227 71/842 84), decided that the time was ripe for preaching them in public.²⁵ Although this account is probably spurious, it reflects the perception of the Berber revolt as a reference for legitimacy which set the foundations of a dynasty that managed to rule on the Atlantic shores of Morocco until the time of the Almohads.

The Ibaḍī dynasty of Tahert was the only Kharijite rule that fostered a doctrinal development in the Maghrib at this period. Its origins are associated with the arrival in Ifrīqiya of five 'bearers of learning' (*ḥamalāt al 'ilm*) around 139/757.²⁶ All of them came from Baṣra where they had received doctrinal training which stressed the need for active and communal adherence (*wala'*) to godly principles of justice, and rejection (*bara'a*) of the iniquities of Islamic rule as it had been exercised since the times of caliph 'Uthman. Their success in getting Kharijite doctrines accepted by tribal chieftains earned them wide support, which soon became military strength. At the head of a tribal army one of these 'bearers of learning', Abu 'l Khaṭṭab al Ma'afirī, expelled the Warfajjuma from Qayrawan in 140/758. For a moment it seemed that a Kharijite imamate would be established in the Islamic capital of North Africa, but an army led by the 'Abbasid general Ibn al Ash'ath expelled the Ibaḍīs and recovered Ifrīqiya for the caliphal administration in 144/761.

Despite this setback, one of the Ibaḍī missionaries, the Persian 'Abd al Raḥman ibn Rustam, managed to recover the tribal following that the doctrine had attracted in previous years. Far away from the reach of 'Abbasid governors in Qayrawan, whose troops refused to get involved in campaigns beyond the Zab, he was acclaimed as imam in the recently founded city of Tahert, near the ancient Roman settlement of Tiaret, in modern day Algeria. Family and political links with some tribal groups, such as the Banu Ifran, who had retreated to the west in the face of 'Abbasid advance, allowed 'Abd

25 M. Talbi, 'Hérésie, acculturation et nationalisme des Berbères Bargawāṭa', in *Actes du Premier Congrès d'Etudes des Cultures Méditerranéennes d'Influence Arabo Berbère* (Algiers, 1973), pp. 217 33, repr. in M. Talbi, *Études d'histoire ifriqiyenne et de la civilisation musulmane médiévale* (Tunis, 1982), pp. 81 104.

26 W. Schwartz, *Die Anfänge der Ibaditen in Nordafrika: Der Beitrag einer islamischen Minderheit zur Ausbreitung des Islams* (Wiesbaden, 1983), pp. 105 18.



9. The Umayyads of Spain.

After P. M. Holt, A. V. S. Lambton and B. Lewis, *The Cambridge history of Islam*, vol. 1B, 1977, p. 736. Copyright Cambridge University Press, reproduced with permission.

al Raḥman ibn Rustam to proclaim himself imam in around 160/777. His rule was not so much territorial as based on the allegiance of a number of tribes whose leaders respected his authority and in turn were consulted on certain matters.

The Ibaḍī imamate had a seat, Tahert, but no clear boundaries: it stretched loosely from the border with Tlemcen in the west to the Jabal Nafusa in the east, occasionally also including Berbers from Tripolitania as the *imam al muslimīn* was only concerned with the rule of justice and the well being of believers. The accessible and simple lifestyle, a genuine concern for the poor and the vastness of his wisdom lent 'Abd al Raḥman ibn Rustam widespread recognition as the imam who fulfilled the Kharijite programme of moral rule. This programme had to be somewhat modified in 168/784 when 'Abd al Raḥman died and his son, 'Abd al Wahhab, succeeded him. Dynastic rule had replaced the choice of the believers, and controversy naturally arose. Those

who claimed that the son of the best Muslim was the best Muslim himself allegedly gained the backing of Baṣran arbitrators, but some were not persuaded and abandoned their allegiance to ‘Abd al Wahhab, becoming the al Nukkariyya branch of Ibaḍism. This schism did not prevent Rustamid imams from continuing to transmit authority through the offspring of the dynasty for more than a century. However, the times of uprisings were also over and the rulers of Tahert showed no apparent interest in further expansion in the neighbouring lands.

The map that emerged in western North Africa during the first decades of the second century was completed with the dynasty of the Idrīsids. Its origins are also linked to the arrival of an Eastern fugitive, called Idrīs ibn ‘Abd Allah. He was a relative of al Ḥusayn ibn ‘Alī, a descendant of ‘Alī ibn Abī Ṭalib, who had rebelled against the caliph al Maṣṣur under the banner of the greater claim of his family to rule the Muslim community and had been easily defeated near Mecca in 169/786. His cousin fled to the Maghrib, where he found refuge among the Awraba Berbers who lived around the ancient Roman city of Volubilis (Ar. Walīla).²⁷ The vexing question of how this Berber tribe came to acknowledge the superiority of Idrīs’s lineage and be prepared to proclaim him imam in 172/789 is difficult to answer. Leaving aside the unclear ideas of the Andalusian heretic Shaqya al Miknaṣī, this was the first time that the charisma associated with the descendants of ‘Alī ibn Abī Ṭalib was recognised in the Maghrib. At this stage Berbers were only familiar with the straightforward teachings of Kharijism, but late sources claim that the tribal chieftain who harboured Idrīs, the Awraba leader Ishaq ibn Muḥammad ibn ‘Abd al Ḥamid, was a Mu’tazilite. It is doubtful whether at this early period this school of theological thought had reached this remote corner of the Muslim world, but it has been argued that Mu’tazilite beliefs were incorporated into Shī‘ism very quickly, and that the proclamation of Idrīs as imam might reflect an early infiltration of Shī‘ite missionaries seeking the overthrow of the ‘Abbasids by turning the Maghrib into a new Khurasan. But if this preaching actually took place, it only yielded the establishment of a dynasty, the Idrīsids, who notoriously lacked a strong Shī‘ite doctrine. In contrast, a hundred years later a new movement preached in North Africa on behalf of ‘Alid claims – the one that led to the proclamation of the Faṭimid caliphs – bore the sound ideological contents that characterised Shī‘ism but which are conspicuously missing in the making of the Idrīsīd dynasty.

27 A. Akerraz, ‘Recherches sur les niveaux islamiques de Volubilis’, in P. Cressier and M. García Arenal (eds.), *Genèse de la ville islamique en al Andalus et au Maghreb occidental* (Madrid, 1998), pp. 295–304.

The extraordinary career of Idrīs ibn ‘Abd Allah culminated in the Maghrib with a short rule that was no less remarkable. He laid the foundations of Fez, near Volubilis, and also began territorial expansion to the south and east of his realm. When he was killed in 175/791, allegedly poisoned by an agent sent by the caliph Harun al Rashīd, his Berber concubine, Kanza, was pregnant; several months later a child was born, and the supporters of the new dynasty were ready to endure a long minority which lasted eleven years until the child was proclaimed as Idrīs II in 187/803. The narrative of his rule suspiciously insists that he followed his father’s footsteps by fostering the growth of Fez and undertaking an expansive policy towards the High Atlas, the Sus al Aqṣa and Tlemcen. When he died in 213/828 his domains were divided among his sons. Thus the Maghrib of the Idrīsids became a mosaic of petty principalities plagued by internal rivalries but with all of their rulers claiming descent from the prestigious ancestor, whose Sharīfian origins became a landmark in the process of Islamisation of the region.²⁸

In the complex shaping of Islamic North Africa, Ifrīqiya remained a strong hold of caliphal rule. After having escaped the Kharijite tide, Qayrawan was firmly in the hands of ‘Abbasid governors thanks to the victories of Ibn al Ash‘ath over the Ibaḍīs in 144/761. By then the province had become a *de facto* border against the potential rivals who had mushroomed in the Maghrib during the preceding decades. Instructions to fortify Qayrawan, the arrival of considerable numbers of troops and the appointment of experienced officials such as those from the family of the Muhallabids, who provided five governors between 155/772 and 178/794, show the importance of this frontier province for the early ‘Abbasids.

Although these governors managed to keep the Kharijite threat in check, they were less successful in extending their rule beyond the limits of a territory that in broad terms coincided with the old Byzantine province. Their capacity for action was severely curtailed by an army that became increasingly restless during these years due to internecine conflicts. Open rebellions of the *jund* in 178/794 and, particularly, 183/799 convinced the caliph Harun al Rashīd of the intractability of the province and the ineffectiveness of sending governors who either became frustrated with prevailing conditions or were expelled by rebels. In 184/800 he accepted a request by Ibrahīm ibn Aghlab, a military leader whose father had already acted as governor of Ifrīqiya in 148 50/765 8, and appointed him *amīr*. Under the terms of this arrangement Ibrahīm seems to have agreed to

28 H. L. Beck, *L'image d'Idris II, ses descendants de Fes et la politique sharifienne des sultans marinites (656 869/1258 1465)* (Leiden, 1989), pp. 28 48.

forward a fixed amount of 40,000 *ḍīnars* to the caliphal treasury every year in exchange for making his rule hereditary. With the hallmark of 'Abbasid legitimacy all the Ifrīqīyan *amīrs* seem to have received investiture from Baghdad the Aghlabids managed to rule the westernmost territory in which the caliphs could claim recognition for more than a century.²⁹

The creation of the new societies

The conquest of North Africa and al Andalus took the Arabs to the western and southern shores of the Mediterranean basin. In a celebrated work published in 1937 the Belgian scholar H. Pirenne deemed this expansion the turning point that gave the final blow to the legacy of the late Roman empire.³⁰ Networks of exchange and political bonds had survived the upheavals of the fifth and sixth centuries, but in Pirenne's view the coming of Islam disrupted the ancient unity of the Mediterranean and produced the landlocked landscape that was the hallmark of the European Middle Ages. As is always the case with visionary theses, Pirenne's has attracted a considerable amount of criticism since its inception, but has managed to survive, perhaps not as the grandiose explanation of long term processes that its author had intended, but at least as an accurate perception of some symptoms prevailing in the Dark Ages which saw the emergence of the new societies that followed the Arab conquests.

One of these symptoms rightly singled out by Pirenne was the shrinking pattern of exchange throughout the Mediterranean in the seventh and eighth centuries. Contrary to what the Belgian scholar thought, this decline was not caused by the Arabs, as it clearly pre dates their arrival, but, contrary to what some of his critics have claimed, the conquests did not produce a homogeneous realm where trade connections flourished all of a sudden.³¹ From the seventh century onwards – or even earlier in some inland areas – archaeologists find growing evidence of a general withdrawal from trading circuits in the western Mediterranean. Pottery is a good indicator of this trend. In the Vandal and Byzantine periods industrial kilns located in modern day Tunisia produced massive amounts of a pottery known as African red slip, which is

29 Talbi, *L'emirat aghlabide*, pp. 89–116. Talbi's remains the classic work on the history of the Aghlabid dynasty. Essential critical remarks on its contents and approach in J. Wansbrough, 'On recomposing the Islamic history of North Africa', *JRAS* (1969).

30 H. Pirenne, *Mahomet et Charlemagne* (Paris and Brussels, 1937).

31 D. C. Dennett, 'Pirenne and Muhammad', in A. Havighurst (ed.), *The Pirenne thesis: Analysis, criticism and revision* (Boston, 1958), pp. 84–101.

found throughout the whole Mediterranean basin. Suddenly these wares were replaced by local manufactures in urban and rural sites, reflecting a contraction of long distance networks of exchange. In the early period following the conquests this trend did not change: kilns producing African red slip disappeared and the archaeological record dating from the second/eighth century, particularly in al Andalus (North African data are more sketchy) provides no evidence of any substantial number of distinctive forms comparable to contemporary wares from the Near East.³²

The conquerors therefore did not disrupt prevailing conditions in the territories they settled, but rather adjusted to emerging situations.³³ This adaptation allowed for a slow rearrangement of social and economic patterns, a transformation which ran so deep in the functioning of western Muslim societies that by the late third/ninth century the legacy of Late Antiquity was not easily recognisable in them. This process is fairly noticeable in the territorial configuration of the new conquests. In the western lands the collapse of sea routes had left coastal harbours as mere shadows of their former splendour. In contrast, inland sites experienced a demand which could benefit from local or regional trading circuits, as they were not so dependent on long distance relations. The pattern is reflected in North Africa by the foundations of Qayrawan, Tahert and Fez; in al Andalus, where the Arabs took up the existing urban network rather than creating new cities from scratch, inland Cordoba soon became the residence of the governors, while Seville, Mérida, Toledo and Saragossa were the only cities worthy of the name. The decline of Carthage, Tangier, Tarragona or Valencia, to name just a few cases of formerly thriving cities whose importance diminished in the aftermath of the conquest, confirms the crisis of some coastal urban centres in the early stages of Arab rule.

This picture slowly changed during the second half of the third/ninth century when long distance relations, unquestionably fostered by the slave trade, which in many cases was the same as naval piracy, favoured the growth of coastal cities. The case of Sousse, in Ifrīqiya, is paradigmatic. To its early *ribat*, which was designed to defend the coast against attacks by the Byzantine navy, was added a great mosque in 236/850, thus reflecting the conversion of the garrison city into a busy port where trade activities took the place of military ones. A similar

32 M. Mackensen, *Die Spätantiken Sigillata und Lampentöpfereien von El Mahrine (Nordtunesien)* (Munich, 1992), p. 492.

33 W. H. C. Frend, 'The end of Byzantine North Africa: Some evidence of transitions', *Bulletin Archéologique du Comité des Travaux Historiques et Scientifiques*, 19, 2 (1985).

conversion of a *ribaṭ* into a flourishing merchant town is seen in the case of Pechina in south eastern al Andalus from 271/884 onwards.³⁴

During the early stages of Arab rule, however, inland cities were the main centres of demand. Some of them underwent rapid growth, boosted by having been selected as seats of power. The Umayyads changed the physiognomy of Cordoba by erecting new buildings and fostering its extraordinary expansion. An existing palace and the site of a nearby Christian church became respectively the *qaṣr* (Sp. *alcázar*), where the dynasty made its residence, and the mosque built by 'Abd al Raḥman I in the final years of his life (c. 170/786). The two buildings faced each other, and were enlarged by 'Abd al Raḥman's successors, who were well aware of their meaning as emblems of the dynasty. The *alcázar* was not only the main seat of Umayyad power, crowded with secretaries and officials of an administration that was becoming increasingly complex and inspired by eastern models at the time of 'Abd al Raḥman II (r. 206 38/822 52), it was also a symbolic enclosure that housed the graves of the successive *amīrs*, who were buried within its walls. The nearby mosque also reflects this sense of dynastic continuity, as the original design consisting of double arched naves was respected by all 'Abd al Raḥman I's successors, who enlarged it during the following two centuries in order to meet the growing number of Cordoban Muslims. This conservatism went so far as to preserve the original orientation of the *qibla* in the full knowledge that it was totally misplaced and not properly aligned towards Mecca.

The expansion of Cordoba soon surpassed the limits of the Visigothic city.³⁵ Among the suburbs that sprang up outside the city walls was Shaqunda, which lay on the left bank of the Guadalquivir river opposite the *alcázar* and was connected to the city by a Roman bridge which had been restored in the aftermath of the conquest. The population of Shaqunda consisted of artisans and traders who were attracted by the growing demand from palatine officials and soldiers from the neighbouring *alcázar*. The relations between this emerging urban class and the Umayyad *amīr* al Ḥakam

34 A. Lézine, *Deux villes d'Ifrīqiya: Études d'archéologie, d'urbanisme de démographie. Sousse Tunis* (Paris, 1971), pp. 17–32. Brett, 'The Arab conquests', pp. 551–2. M. Acíén, F. Castillo and R. Martínez, 'Excavación de un barrio artesanal en Pechina', *Archéologie Islamique*, 1 (1990), pp. 147–68. On urban growth in the Maghrib al aqṣa, see S. Ennahid, 'Beyond al Basra: Settlement systems of medieval northern Morocco in archaeological and historical perspective', in N. L. Benco (ed.), *Anatomy of a medieval Islamic town: al Basra, Morocco*, BAR Series 1234 (Oxford, 2004), pp. 79–91.

35 J. Murillo, M. T. Casal and E. Castro, 'Madinat Qurtuba: Aproximación al proceso de formación de la ciudad emiral y califal a partir de la información arqueológica', *Cuadernos de Madīnat al Zahra'*, 5 (2004), pp. 257–90.

I (180/206–796/822) became increasingly strained, due to the mounting tax demands decreed by this unpopular ruler. In 202/818 an incident between a craftsman and a soldier of the palatine guard sparked a fierce mutiny which led the inhabitants of Shaqunda to attack the *alcázar* with the aim of overthrowing al Ḥakam and pillaging the palace. The uprising was defeated, brutal repression followed and al Ḥakam ordered the destruction of Shaqunda, with strict orders that nothing was to be rebuilt there, a prohibition that apparently was duly respected by his successors.³⁶

An unexpected outcome of the revolt of Shaqunda was that survivors were exiled, and some of them left al Andalus for good. A group of outcasts crossed the Straits and settled in the Idrīsid city of Fez, on the riverbank opposite Idrīs I's original settlement. The arrival of these Andalusīs helped Idrīs II to consolidate the city his father had founded, which until then had been no more than a tribal agglomeration endowed with a mosque. This gave Fez its distinctive double centred character with two quarters, the 'Idwat al Andalusīyyīn and what later became known as the 'Idwat al Qarawiyyīn.³⁷

Fez was located at the crossroads of routes which linked the northern and southern regions of the extreme west (*Maghrib al aqṣā*) and these with the rest of North Africa. The expansion of Idrīsid rule along these two axes shows that this choice was not accidental. The conquests led by Idrīs I and his son were aimed at controlling trade routes and natural resources, particularly the silver mines in the Atlas mountains, which allowed the early Idrīsids to coin *dirhams* in a number of mints scattered throughout their lands.³⁸ These coins were probably used to purchase the allegiance of tribal leaders, but also perhaps to assure the peaceful coexistence of the dynasty with the governors of Ifrīqiya. This may explain why Idrīsid coins show up alongside 'Abbasid pieces in hoards found in the Near East, the Caucasus and even Scandinavia – admittedly in small numbers, but nevertheless quite consistently. The lust for silver in the central lands of the caliphate during the early years of the third/ninth century was appeased with massive deliveries of *dirhams* which the governors of Ifrīqiya coined in their own province, but which they also received, perhaps as a tribute, from the Idrīsid lands. In contrast, Idrīsid *dirhams* are scarcely found in al Andalus, and even less so in western Europe, a clear indication

36 New evidence for this episode in the recently uncovered Ibn Hayyan, *al Sifr al thanī min Kitāb al muqtabis*, ed. M. A. Makki (Riyadh, 2003), pp. 140–74.

37 E. Lévi Provençal, 'La fondation de Fès', *Annales de l'Institut d'Études Orientales*, 4 (Algiers, 1938).

38 D. Eustache, *Corpus des dirhams idrīsides et contemporaines* (Rabat, 1970 1).

that ties between the two seaboards were virtually non-existent at this early period.³⁹

The urban expansion of Fez has been described as the result of a conscious attempt to create a centre for Arabisation and Islamisation in the region with the help of immigrants from al Andalus and Ifrīqiya. As such it may be compared to Tahert, which under the aegis of the Rustamids seems to have kept a more distinctive Berber outlook. As described by Arab sources, the city lacked any central planning – it is unlikely that it was even walled – and was essentially an agglomeration of population clusters interspersed with mosques, whose inhabitants were of mixed origin who dealt with neighbouring Berber tribes. The main commodity traded at Tahert was probably slaves from sub-Saharan Africa, and also raw materials such as gold.⁴⁰

Founded at the early stages of the conquest, Qayrawan was a different sort of city. Although Arab sources describe ‘Uqba ibn Nafi’ laying its foundations on a deserted spot frequented by wild animals, it is clear that a settlement had existed at least since Roman times. Its excellent strategic position dominated access to inland routes, making it a privileged garrisoned enclave for the early Arab expeditions. At the time of its foundation ‘Uqba gave Qayrawan a mosque and a residence for governors (*dar al imara*), which were also built opposite each other. It is not clear whether Arab troops were accommodated in the city as in the *amṣar* of Kufa and Baṣra, but the existence of several quarters bearing Arab tribal names points to a settlement of troops. Despite the internal turmoil of its early period, the city grew as markets were organised and impressive hydraulic works ensured the water supply. After demolishing and rebuilding the primitive mosque attributed to ‘Uqba on several occasions, the Aghlabid ruler Ziyadat Allah decided to rebuild it in 221/836, following a regular scheme that is still visible today in the present building.

It is telling that the Aghlabid rulers also faced revolts by the inhabitants of Qayrawan and that they decided to raze the walls that had surrounded the city during the decades of upheaval of the second/eighth century. Restless opposition within the city and the need to make their distinctive rule apparent led the Aghlabids to abandon Qayrawan and to take up residence at a palatine complex 3 miles to the south east which was named al ‘Abbasiyya. Ibrāhīm I

39 B. Rosenberger, ‘Les premières villes islamiques du Maroc: Géographie et fonctions’, and E. Manzano Moreno, ‘El desarrollo económico de las ciudades idrīsīs: La evidencia numismática’, both in Cressier and M. García Arenal (eds.), *Genèse de la ville islamique*, pp. 229–55 and 353–75.

40 B. Zerouki, *L’imamat de Tahart: Premier état musulman du Maghreb (144–296 de l’hégire)* (Paris, 1987), pp. 20–4.

coined *dirhams* in this mint and recruited a personal guard of freed slaves who garrisoned its strong fortifications. Baths, markets and a Friday mosque gave shape to a self sufficient city which was organised around its main palace called Ruṣafa and was inspired by eastern models.⁴¹ Several decades later, and soon after his accession in 263/876, the *amīr* Ibrāhīm II decided to move his residence to a new settlement, called al Raqqada, a few miles south of the former city, the townscape of which was dominated by a number of palaces (*quṣur*).

Unlike the Ifrīqiyan *amīrs* the Umayyads of al Andalus kept Cordoba as their seat for almost two hundred years. After the crushing of the revolt of Shaqunda their grasp on the capital seems to have been remarkably solid, as shown by the surviving tax receipts from the rural districts around the city or by the important role played by the *ṣaḥīb al madīna* in the Umayyad administration.⁴² It was not until 325 9/936 40 that ‘Abd al Raḥman III al Naṣir, who had previously taken the title of caliph, decided to found the city of Madīnat al Zahra’ a few miles west of Cordoba. The city, which covered 112 hectares, was also walled and possessed a Friday mosque and a mint. Its impressive remains, still visible today, bear witness to extraordinary urban planning which included roads, hydraulic infrastructures and the separation of residential, reception and administrative areas.⁴³

Al ‘Abbasiyya, al Raqqada and Madīnat al Zahra’ did not outlive their founding dynasties. They were abandoned once the Aghlabids had been replaced by the Faṭimids and a destructive civil war brought the downfall of the Umayyads in al Andalus. In contrast, both Qayrawan and Cordoba remained important urban centres even though the fall of these dynasties reduced their splendour. At least in part, this continuity was founded on the prestige that both cities had attained as centres of Islamisation in the west due to the number and influence of the ‘*ulama*’ who lived and taught in them.

The growth in the study of religious disciplines in Qayrawan may have started at a very early date. If we are to believe *fiqh* (jurisprudential) and *ṭabaqat* (biographical) literature, by the middle of the second century AH respected Muslim scholars were transmitting, teaching and writing about Qur’anic exegesis and Islamic law in Qayrawan.⁴⁴ Apparently, a number of North African

41 A. Lézine, *Architecture de l’Ifriqiya: Recherches sur les monuments aghlabides* (Paris, 1966), pp. 137–8.

42 Al ‘Udhri, *Tarṣīṭ al akhbar wa tanwīṭ al athar wa l bustan fī gara’ib al buldan*, ed. A. al Ahwani (Madrid, 1965), pp. 124–7.

43 A. Vallejo, *Madīnat al Zahra’: Guía oficial del yacimiento arqueológico* (Seville, 2004).

44 M. Muranyi, *Beiträge zur Geschichte der Ḥadīth und Rechtsgelehrsamkeit der Malikiyya in Nordafrika bis zum 5. Jh. DH* (Wiesbaden, 1997), pp. 1–59.

students attended the teachings of Malik ibn Anas (d. 179/796) in Medina and spread his legal views back in their native lands. How and when these interpretations became a coherent corpus of legal and doctrinal practices is a question that has given rise to considerable controversy in modern scholarship, but there remains little doubt that the Aghlabid period witnessed considerable activity among circles of scholars concerned with religious interpretation.⁴⁵ One of the most prominent figures of these circles was Saḥnūn ibn Saʿīd (d. 240/854), who gathered the teachings of Malik ibn Anas in a compilation known as the *Mudawwana*, which became the main reference work for Malikism in North Africa.

Saḥnūn left behind him a large number of disciples, many of whom had come from al Andalus 'in pursuit of knowledge' (*fi ṭalab al 'ilm*). Long journeys to North Africa, Egypt and the Near East were very common among the early generations of Andalusī religious scholars of the third century, many of whom were descendants of converts. The outcome of their endeavours was an imported Malikism which spread mainly from Cordoba and was firmly endorsed by Umayyad rulers. An Andalusī contemporary of Saḥnūn was Yahya ibn Yahya al Laythī (d. 234/848), whose Berber origins did not prevent him from becoming the most influential scholar of his time. He was a member of the council (*shura*) that advised the Umayyad *amīr* on legal matters and was famed for being responsible for the transmission of Malik's legal work the *Muwattaʿa*, which gained wide recognition in the Maghrib.⁴⁶

A comparison between the Islamic milieu in Ifrīqiya and al Andalus at this early period shows a number of telling differences. Malikism was not prevalent in North Africa, as Aghlabid rulers were prone to favour the Ḥanafī school of law. As a result of this, religious circles in Qayrawan became more heterogenous than those in Cordoba. The step taken by the Aghlabid ruler Ziyadat Allah (201–23/817–38), of appointing both a Malikī and a Ḥanafī judge in the capital was a measure of appeasement that would have been unthinkable in al Andalus. The class of religious scholars that emerged in Cordoba under the shadow of Umayyad rule was always staunchly orthodox, and deviations from the dominant Malikī doctrine were regarded with suspicion, if not with threats of accusation of heresy (*zandaqa*).

45 See, however, the controversial work by N. Calder, *Studies in early Muslim jurisprudence* (Oxford, 1993).

46 M. I. Fierro, 'El alfaquí bereber Yahyà ibn Yahyà al Laythī (m. 234/848), el inteligente de al Andalus', in M. L. Avila and M. Marín (eds.), *Biografías y género biográfico en el Occidente islámico*, Estudios Onomástico Biográficos de al Andalus 8 (Madrid, 1997), pp. 269–344.

Relations between rulers and religious scholars in Ifrīqiya and al Andalus also contrasted. Rejection of the wrongdoings of political power and detachment from its mundane corruption (*inqibād ‘an al sultān*) were widespread *topoi* which contributed to shape the moral standing of the ‘*ulama*’ all over the Muslim world. But beyond these generic ideals a close bond is easily discernible between the Umayyad rulers and the religious circles of Cordoba, which compares with the more strained relationships that the Aghlabids maintained with the Qayrawan ‘*ulama*’. At the height of the dangerous revolts against the North African *amīrs*, men of religion firmly refused to legitimise their fight against the rebels, emphasising instead the evils of their rule and their lack of arguments to claim authority over the Muslim community.⁴⁷ There are no records that the Umayyad dynasty suffered such strong condemnations. Even its most unpopular ruler, al Ḥakam I, who did not hesitate to execute and crucify ‘*ulama*’ opposing his rule, is portrayed in some accounts as a pious Muslim and conscious defender of the frontiers of the *dar al islam*. In contrast to the defensive attitude of the Aghlabids vis à vis the religious establishment of Qayrawan, the Umayyads seem to have enjoyed almost uncontested support from Cordoban ‘*ulama*’. This ensured them a religious legitimacy, which was based on the idea that their deeds in the defence of orthodoxy justified the divine choice bestowed upon them to guide the *umma*.

It is not coincidental that by the fourth/tenth century, under the auspices of the Umayyad rulers, the names, origins and careers of these ‘*ulama*’ began to be compiled in Cordoba in thick registers which included the stereotyped intellectual careers of literally hundreds of religious scholars. Recent work on these registers – also known as ‘biographical dictionaries’ – has uncovered the complex transmission of knowledge among this class of scholars and the orientation that religious learning took in a territory far away from the main centres of Islamic studies. These sources also provide an insight into the patterns and extension of Islam in al Andalus because they usually mention the city or village where a given scholar came from. According to these data the main centres of Islamisation were the southern Peninsula, the Ebro valley and the central axis around Toledo, territories where the number of Muslims allowed for the emergence of a significant number of people who could engage in learning, teaching and enforcing the principles and commands of religion.⁴⁸

47 M. Marín, ‘Inqibād ‘an al sultān. ‘Ulama’ and political power in al Andalus’, in *Saber religioso y poder político en el Islam: Simposio Internacional (Granada 15-18 de octubre 1991)* (Madrid, 1994), pp. 127–39. Talbi, *L’émirat aghlabide*, pp. 184–5, 243–4.

48 M. I. Fierro and M. Marín, ‘La islamización de las ciudades andalusíes a través de sus ulemas (s.II/VIII comienzos del siglo IV/X)’, in P. Cressier and M. García Arenal (eds.), *Genèse de la ville islamique*, pp. 65–97.

Archaeology is also a good indicator of the unrelenting Islamisation of the Iberian Peninsula. There is evidence of Christian cemeteries containing graves where the corpse has been laid following the Muslim ritual. The practice condemned in Qur'an 9.85 is possibly indicative of the conversion of indigenous people who still employed ancient burial sites but had adopted the new rites of the conquerors.⁴⁹ The decay of churches or their conversion into mosques also pinpoints the steady decline of Christianity in this period. In Tolmo de Minateda (Albacete), which was the same Madīnat Iyyih mentioned in the pact of Theodomir as one of the cities included in the domains of this aristocrat, a Visigothic seventh century basilica became, within two centuries, a residential area with dwellings standing alongside kilns. Some fine examples of late Visigothic architecture such as Melque (Toledo) or Santa María del Trampal (Cáceres) have survived up to the present day, but excavations have revealed that by the fourth/tenth century they were no longer occupied.⁵⁰

Arabic also spread rapidly. It not only affected the indigenous population, but also the Berbers who had arrived at the time of the conquest and maintained their original tongue, but quickly lost it in favour of Arabic. A very peculiar trait of Arabic words adopted in Spanish is the assimilation of the determinative article *al* to the borrowed word such as *algodón* (Ar. (*al*) *quṭun*: cf. Eng. *cotton*) or *alguacil* (Ar. (*al*) *wazīr*.) This uncommon feature has been explained as deriving from the pidgin Arabic spoken by Berber populations who tended to incorporate a classifying prefix to commonly used words in the same way as they did in their original tongue.⁵¹

The decreasing use of Latin among the indigenous population was acutely felt by some Christians living under Muslim rule, usually called Mozarabs (a term that modern scholarship derives from *musta'rib*, meaning 'Arabised', and which is only mentioned in Latin documents, but never in Arab sources). In a celebrated text a Cordoban Mozarab called Alvarus complained that in his time only one among a thousand Christians was able to write a letter in Latin. Young Mozarabs in Cordoba preferred the beauty of Arabic poetry to the study of religious texts. Alvarus's complaints were bitter and accurate, but they made no impact on his co religionists: by the fourth/tenth century

49 M. Almagro Basch, *La necrópolis hispano visigoda de Segóbriga: Saetices (Cuenca)*, Excavaciones Arqueológicas en España 84 (Madrid, 1975). J. L. Serrano Peña and J. C. Castillo Armenteros, 'Las necrópolis medievales de Marroquíes Bajos (Jaén)', *Arqueología y Territorio Medieval*, 7 (2000), pp. 93–115.

50 L. Abad, S. Gutiérrez, and B. Gamo, 'La basilica y el baptisterio del Tolmo de Minateda (Hellín, Albacete)', *Archivo Español de Arqueología*, 73 (2000), pp. 193–221.

51 F. Corriente, *Diccionario de arabismos y voces afines en iberorromance* (Madrid, 1999), pp. 58–63.

Christian sacred books were being translated into Arabic in significant numbers, which bears witness that even among Christian populations that language was more widespread than Latin.⁵²

Alvarus belonged to a group of militant Christians in Cordoba who were well aware of the decline of their religion and the growing supremacy of Islam a century after the conquest. They complained of the ruin of churches and the tax burdens, but their main concern was the increasing rate of conversion, a deep social change which was acutely resented by this group of well to do Cordobans. Feeling that they were facing a desperate situation, some of them decided to take desperate action: in the same way as early Christendom had prevailed thanks to the blood of the martyrs during the persecutions carried out by the Roman emperors, a similar response was necessary to meet the tough times they were living through. The voluntary martyrs thus presented themselves to the judge of Cordoba, hurling blasphemy and abuse against the Prophet and Islam in the full knowledge that this left the official no choice but to condemn them to death in application of the law. As a result almost fifty Christians were executed in Cordoba between 850 and 859. This movement of suicidal zealots gave rise to a considerable amount of apologetic and polemical literature. Apart from this, its only outcome was an increase of martyrs' relics in the monasteries around Cordoba. Their blood was shed in vain, as Umayyad authority remained unscathed. All these suicides did not justify the deep divisions they produced among the Christian community, and as a consequence the movement slowly disappeared.

The fate of North African Christendom was similar. In its heyday before the Arab conquest, Church councils would assemble more than two hundred bishops, but by the tenth century the list of episcopal seats had been reduced to about forty, many of which only existed in name. By the middle of the eleventh century only four or five bishoprics can be documented. This decline had begun shortly after the Arab conquest, when many clerics left North Africa for the northern shores of the Mediterranean. In the second half of the tenth century Christians from Carthage complained of the fortunes of their city: whereas it had once been a celebrated metropolis, now it was scarcely possible to find a priest in it. Although Christian communities survived even in cities founded by the Muslims, such as in Qayrawan and Tahert, the only traces left of them are occasional inscriptions – such as those found in the cemetery of Ngila near Tripoli, which date from the second half of the tenth

⁵² Alvaro de Córdoba, *Indiculus Luminosus*, in *Corpus Scriptorum Muzarabicorum*, vol. I, p. 314.

century and the eleventh – or occasional statements by Arab geographers.⁵³ Contrary to what happened in al Andalus, however, these communities do not seem to have produced literary or doctrinal works, or at least none of them has come down to us.

Internal and external enemies

The most serious rebellions against the rule of the Aghlabids in Ifrīqiya were led by members of the Arab army. Military leaders formed a hereditary aristocracy with extensive landholdings, cultivated in many cases by slaves.⁵⁴ Ibrāhīm I in 194/810 and, particularly, his son Ziyadat Allah in 207/822 had to face this challenge as some of these leaders were able to gather sufficient support to dispute the authority of the *amīrs* in considerable parts of their domains. During the first uprising Ibrāhīm I was besieged by the rebels in al ‘Abbasiyya, whereas Ziyadat Allah suffered several defeats which brought the dynasty to the brink of extinction. In both cases powerful army leaders seem to have resisted certain policies of the *amīrs* and to have contested the legitimacy of their rule over them. Failed appeals to the ‘*ulama*’ in Qayrawan who staunchly refused to take sides for any contender – to declare the Aghlabids unlawful show that the bid for power of this Arab aristocracy was based on the idea that this dynasty only deserved their loyalty as far as it was prepared to meet their demands. Allegedly, Ibrāhīm I only managed to put an end to the rebellion of 194/810 when fresh financial resources sent by the ‘Abbasid caliph were distributed among the rebel army. During the second rebellion of the *jund* one of its leaders, Maṣṣūr al Ṭunbudhī, minted coins in Qayrawan in 210/825, a clear sign that the aim of the insurgents was the overthrow of the Aghlabids. If they did not achieve their goal, it was only because internal divisions among the rebels permitted the military recovery of the forces that had remained loyal to the Aghlabid *amīr*.

It is significant that, once the danger posed by this rebellion was over, the triumphant Ziyadat Allah embarked on an ambitious programme of holy war

53 M. Talbi, ‘Le Christianisme magrébine de la conquête musulmane à sa disparition: Une tentative d’explication’, in M. Gervers and R. J. Bikhazi (eds.), *Conversion and continuity: Indigenous Christian communities in Islamic lands, eighth to eighteenth centuries* (Toronto, 1990); J. Cuoq, *L’église d’Afrique du Nord du IIe au XIIe siècle* (Paris, 1984), pp. 105–51.

54 M. Talbi, ‘Law and economy in Ifrīqiya (Tunisia) in the third Islamic century: Agriculture and the role of slaves in the country’s economy’, in A. L. Udovitch (ed.), *The Islamic Middle East, 700–1900: Studies in economic and social history* (Princeton, 1981), pp. 209–49.

against the neighbouring island of Sicily, where Byzantine imperial administration was facing internal disarray. The expedition that left the port of Sousse in 212/827 was entrusted to Asad ibn al Furat, an old and respected religious scholar who had been an outspoken critic of some aspects of Aghlabid rule. As the first attempt of territorial expansion since the times of the great conquests, the invasion of Sicily was characterised by the alliance of militant Islam with a restless class of soldiers whose rebellions had provoked havoc and destruction in the previous decades. The timing was also propitious as sea raiding expeditions by sailors from al Andalus and North Africa had been attacking Christian shores for some decades in quest of slaves, unquestionably the most precious merchandise in the western Mediterranean. The same year as the departure of the Aghlabid expedition, Crete had been conquered by a band of Andalusī sailors coming from Alexandria, where they had earned a well deserved reputation for violence and ruthless behaviour. Now it was the turn of the Aghlabids, a dynasty with a constant deficit of legitimacy, to profit from this situation with the support of the *jund* and the religious establishment of Qayrawan.

It was a long and difficult conquest, however. By the time Asad ibn al Furat died in 213/828 the conquerors had gained only a foothold in Mazara, after suffering several defeats and the devastating effects of plague. It was not until 216/831 that Palermo fell, allowing them to begin an expansion in the western part of the island. At the same time, intermingling of the complex politics of the Lombard ducate of Benevento and the cities of southern Italy led to a number of raids, which culminated in the sack of Rome in 231/846. During the following decades campaigns of attrition and conquests of strategic enclaves ensured the complete domination of Sicily, which was strengthened by the taking over of Syracuse in 264/878 and the creation of the emirate of Bari on the Italian Peninsula.⁵⁵

Compared to the extraordinary achievements of the Aghlabids in Sicily, the outcome of Umayyad warfare in al Andalus was far more modest. Although most Cordoban rulers regularly sent summer campaigns against the Christian kingdoms in the north, these never produced significant territorial gains. Their commanders seem to have been more interested in receiving the stipends from the Cordoban government they were entitled to for every military campaign, and in taking booty and captives, than in extending the

55 M. Amari, *Storia dei musulmani di Sicilia* (Catania, 1933 9) remains the classic work. But see also A. Ahmad, *A history of Islamic Sicily* (Edinburgh, 1975); or U. Rizzitano, *Storia e cultura della Sicilia musulmana* (Rome, 1995).

land under their rule. The defensive character of Umayyad *jihad* could not prevent some significant losses such as the conquest of Barcelona in 185/801 by the armies of Louis the Pious or the expansion of the kings of Asturias into the no man's land of the Duero valley during the ninth and tenth centuries. As a consequence, Christian kingdoms consolidated and, despite the supremacy of Andalusī armies throughout the whole period, by the time the Umayyad dynasty fell in 422/1031 northern kings and lords were more powerful than their forebears had been 300 years before.

For more than a century the Umayyads never faced widespread rebellion. Local revolts certainly disrupted some regions, but they were never a serious threat to their rule. Most of these revolts originated in the frontier regions (*thughur*) and were led either by local aristocratic families such as the Banu Qasī or the Banu 'Amrus or, more intriguingly, by cities such as Toledo or Mérida, whose populations seem to have rejected the attempts of the Cordoban administration to impose certain taxes, a reason which may explain similar contemporary rebellions in Ifrīqiyan cities.⁵⁶ During the second half of the third/ninth century, though, these revolts extended to the whole of al Andalus. Starting during the rule of *amīr* Muḥammad (238 83/852 86), local landlords severed their links with the Umayyads, erected fortresses (*ḥuṣun*) and ceased forwarding taxes to Cordoba. By the time of *amīr* 'Abd Allah (275 300/888 912) minting of coins had practically ceased and Umayyad authority was barely recognised beyond the limits of the capital.

The major rebel of the period was a *muwallad*, a descendant of indigenous ancestors who had converted to Islam, called 'Umar ibn Ḥafṣun, who managed to build a considerable territorial domain extending from the fortress of Bobastro, set in the craggy mountains of Málaga, in south eastern al Andalus. 'Umar ibn Ḥafṣun was the main but not the only *muwallad* who rebelled during this period. Although sources point to the opposition of these *muwalladun* to the Arabs as the main cause of the countless battles of these years, this explanation is belied by accounts from the same sources which show that ethnic divisions were not always followed by rebels in their alliances and political alignments. The bone of contention of these *muwalladun* was more their loss of power within a rapidly changing social milieu. The undisputed authority, which the agreements of the time of the conquest had guaranteed them within their domains, was breaking up as the result of the

56 E. Manzano Moreno, *La frontera de al Andalus en época de los Omeyas* (Madrid, 1991), pp. 314 83. Cf. Talbi, *L'emirat aghlabide*, p. 145.

increasing demands of the central administration and the flight of rural populations to the urban areas where Umayyad rule was more visible. Under these circumstances rebellion was the only alternative for this class, and the fact that during the first decades of the fourth/tenth century all these revolts were put down by the Umayyad 'Abd al Raḥman III, who sometimes even received the support of the rebels' subjects, shows that at this period al Andalus was rapidly becoming a more homogeneous social realm where the last remnants of the old Visigothic heritage were disappearing.⁵⁷

The western caliphates

It is no coincidence that both Ifrīqiya and al Andalus witnessed the proclamation of two rival caliphates in the early fourth/tenth century. Both societies had reached such a degree of Islamisation that the vast implications borne by the title 'Commander of the Faithful' were fully acknowledged by a considerable part of their populations. Religious authority of the caliphs entailed a political organisation, a legal system and an ideological framework which were shaped according to Islamic principles of government, law and legitimacy. In al Andalus the principles upheld by the Umayyad orthodoxy faced no serious challenge, especially once the *muwallad* rebellions of the previous century had been defeated. By contrast, Ifrīqiya was again a much more complex social milieu, in which the definition of what exactly 'Islamic orthodoxy' stood for was not yet universally recognised.

It is likely that, by taking the unprecedented step of claiming spiritual rule over the whole Muslim community in 316/929, the Umayyad 'Abd al Raḥman III al Naṣir was reacting to the defeat of the Aghlabid dynasty and the proclamation of the Faṭimid caliph 'Abd Allah al Maḥdī in Ifrīqiya in 297/910. The consolidation of this militant rule in North Africa made a deep impact in the whole Islamic world. Faṭimid partisans saw in the event the rising of the sun in the west, an image that was unashamedly plagiarised by Umayyad poets who also boasted that their masters' aim was to extend their authority to the east.⁵⁸

The claims to legitimacy of the two caliphates were, however, different. The Umayyad *amīrs* of al Andalus had always portrayed themselves as 'descendants of the caliphs'. But when al Naṣir took the title of *amīr al*

57 M. Acien, *Entre el feudalismo y el Islam: 'Umar ibn Ḥaṣṣun en los historiadores, en las fuentes y en la historia*, 2nd edn (Jaén, 1997).

58 Cf. al Qaḍī al Nu'man, *Iftitāḥ al da'wa wa ibtida' al dawla*, ed. F. Dachraoui (Tunis, 1975), p. 65 and Ibn Ḥayyān, *al Muqtabis fī ajbar bilad al Andalus (al Ḥakam II)*, ed. A. A. Hajji (Beirut, 1965), p. 163.

mu'minīn, it was not so much the genealogy linking him to the caliphs of Damascus that he stressed – perhaps because this argument could not explain why his predecessors had failed to assert their claim to the title – but rather the preference shown by God on account of his actions and good government.⁵⁹ In contrast, Fatimid claims were based on the lines of descent that connected this dynasty to 'Alī ibn Abī Ṭalib and his wife Faṭīma, the daughter of the Prophet, through a succession of imams who had been appointed by God to preserve His faith.

It was not an undisputed claim. For the Shī'a the genealogical line of imams had continued uninterrupted among the descendants of 'Alī until the death in Samarra' of the eleventh imam, al Ḥasan al 'Askarī, in 260/874. Then, his infant son, known as Muḥammad al Muntazar, had disappeared, becoming the hidden twelfth imam, who was expected to reappear at the end of time. While these ideas were followed by what was becoming the mainstream majority of Shī'a, some were unpersuaded and claimed instead that upon the death in 148/765 of Ja'far al Ṣādiq, great grandson of al Ḥusayn ibn 'Alī, the imamate had passed to his second son Isma'īl, who had transmitted it to his own son Muḥammad.⁶⁰ As this Muḥammad ibn Isma'īl also went into hiding, for the next century the internal history of this group is made blurry by the genealogical arguments, allegations and counter claims of its followers, dissidents and foes. These discussions were the product of the political and social circumstances of the end of the third century, when messianic expectations spread throughout many parts of the Muslim world. The generic idea that the period of hiding of the imam was over and that a new era was about to begin with the coming of the *mahdī*, a saviour sent by God to guide His community according to His principles of law and justice, was preached in a number of different ways by a number of different missionaries (*da'īs*). These travelled through different lands and found an encouraging response in places such as Yemen, Khurasan or Baḥrayn.⁶¹ A leadership located in the Syrian village of Salamiyya claimed ascendancy over this network of highly committed agitators, presenting itself as the proof (*hujja*) that endorsed the truthfulness of the whole movement. In 286/899 this cautious idea was abandoned and the leader

59 *Una Crónica Anónima de 'Abd al Raḥman al Naṣir*, ed. and trans. E. Lévi Provençal and E. García Gómez (Madrid and Granada, 1950), pp. 78–9.

60 See, however, a contradictory account on this succession by the caliph al Mahdī himself: A. Hamdani and F. de Blois, 'A re examination of al Mahdī's letter to the Yemenites on the genealogy of the Fatimid caliphs', *JRAS* (1983), pp. 173–207.

61 M. Brett, *The rise of the Fatimids: The world of the Mediterranean and the Middle East in the fourth century of the hijra, tenth century CE* (Leiden, 2001), p. 47.

of Salamiyya decided to present himself as the awaited imam, claiming lordship over the whole Muslim community. This bold decision was met with varying degrees of acceptance by the followers of the movement. Some of them were unimpressed by what seemed to them an allegation that was not clearly grounded.

One of the *da'īs* who maintained his allegiance to the general direction of the movement was a man called Abu 'Abd Allah, who had been recruited in Kufa and later sent to Egypt and Yemen. In 279/892 while on a pilgrimage in Mecca he met a group of Berbers from the Kutama tribe, an encounter which convinced him that the region of the Lesser Kabyilia (present day Algeria) was a fertile ground for his activities. Abu 'Abd Allah spent the following nine years in that marginal area, making a place called Ikjan his particular *dar al hijra* ('abode of emigration'), which mirrored the role played by Medina in the life of the Prophet Muḥammad, when he had to take residence in this city after escaping from Mecca. The *da'ī* preached among the Kutama a salvational message which stressed the idea that big things were about to happen when the *mahdī* finally arrived, provided the community of believers went back to its original roots. This message proved successful at a juncture in which Aghlabid rule was facing growing discontent due to the ruthless policies followed by Ibrahīm II during his long government (261 89/875 902). The call of the *jihad* felt by this unpredictable *amīr* took him and his troops to Sicily and southern Italy, a circumstance from which Abu 'Abd Allah, who led the Kutama to conquer Mila in 289/902, was to profit. Two years later the conquest of Sétif made his movement such a serious challenge that the 'ulama' from Qayrawan issued a *fatwa* accusing the *da'ī* of propagating heretical ideas. But by then the uprising was unstoppable: further conquests and the defeat of the Aghlabid army by Laribus in 296/909 forced the last Aghlabid *amīr*, Ziyadat Allah II, to flee just before the *da'ī* Abu 'Abd Allah made his triumphal entry into Qayrawan.

The road was open for the proclamation of the rule of the *mahdī*, who had fled from Salamiyya in 289/902 in the face of a mounting threat coming from both 'Abbasid armies and enraged co religionists who did not recognise him as imam. His eventful escape had taken him to the west, but for some reason he had not joined his *da'ī* in the territory of the Kutama but had settled instead in Sijilmasa in the *Maghrib al aqsa*. It was there that the victorious Abu 'Abd Allah went to rescue him. Soon afterwards the self styled 'Abd Allah al Mahdī (297 322/910 34) was sworn in as caliph in the Ifrīqiyan city of al Raqqada. Despite a number of mutinies and local revolts in Sicily and Tripoli, his government rapidly consolidated, and even endured the internal crisis caused

by the suspicious attitude of both Abu 'Abd Allah and his brother Abu 'l 'Abbas – the latter a key figure of the movement in previous years – who seem to have entertained some doubts about the authenticity of the *mahdī* and were killed in 298/911.

The Faṭimids were not the first easterners who had arrived in North Africa and found support there for their claims; nor were they the last religious reformers to spread their message among marginal Berber tribes, who stood outside the main centres of Islamisation but would become the core of an expanding state, as the later cases of Almoravids and Almohads show. Their distinctiveness lay in the fact that their preaching had been bred in the east and that its *raison d'être* entailed universal rule, as the coming of the *mahdī* signalled the beginning of a new era. The conquest of Ifrīqiya was a first step towards this aim, and as a result of this the political map of North Africa, which for a century had remained almost unchanged, suffered a radical transformation.

The Rustamids of Tahert were the first casualties of Faṭimid expansionism. They were disposed of during the expedition led by Abu 'Abd Allah in search of the *mahdī*. A few years later, in 311/923, the Idrīsīd ruler of Fez, Yaḥya IV, was also deposed, whereas in Sijilmasa the dynasty of the Midrarīds was allowed to survive in exchange for recognition of the Ifrīqīyan caliph. It is telling, however, that the Faṭimids never attempted to impose direct rule over territories west of Tahert. They preferred to entrust the control of these regions to powerful tribal leaders such as the Miknasa chieftain Masala ibn Ḥabus and his cousin Musa ibn Abi 'l Āfiya. This was an implicit recognition that tribalism held a supremacy in the *Maghrib al aqṣa* that state administration could not challenge.

Tribal politics, however, were unstable, and they proved very unreliable as the Umayyad 'Abd al Raḥman III began to show a deep interest in the situation in North Africa. Masala ibn Ḥabus was defeated and killed in 312/924 at the hands of the rival Maghrawa chieftain, Muḥammad ibn Khazar, who became the main Umayyad ally in the region. Soon afterwards 'Abd al Raḥman III ordered his navy to take the North African cities of Melilla and Ceuta in 317–19/929–31. With this bold move the self-proclaimed Cordoban caliph made clear his intention to stand up to Faṭimid expansionism, which eventually could threaten his own lands.⁶² In this situation tribal leaders such as Musa ibn Abi 'l Āfiya, the scions of the Idrīsīd dynasty still active in

62 E. Lévi Provençal, *Historia de la España Musulmana (711–1031)*, vol IV: *Historia de España dirigida por R. Menéndez Pidal* (Madrid, 1950), pp. 313–21, 385–97, 430–7 remains the most comprehensive account of Umayyad expansionism in the Maghrib.

the Maghrib or the rulers of Sijilmasa could bargain for their loyalties with both caliphates. Faṭimids and Umayyads engaged in a fierce competition to attract allies to their causes, converting the *Maghrib al aqṣa* into a battlefield where these allies fought each other with the support of Umayyad armies deployed on the African coast and Faṭimid governors established in the newly founded citadels of Msila and Ashīr, which commanded the route to Tahert.

Therefore, despite the early support of the Kutama, the revolutionary message of the Faṭimids had failed to overcome the conditions that traditionally had made North Africa a distinctive region within the *dar al islam*. This became clear to the caliph al Qa'im (r. 322–34/934–46), the successor of al Maḥdī, when a widespread rebellion of Berber tribes arose in the Hodna plains and the Aurès mountains in 322/944 under the leadership of Abu Yazīd Makhḥad ibn Kaydad, a former schoolteacher who belonged to the Nukkarite branch of Kharijism. Rejection of the evil rule of the Faṭimids, which had turned out to be as oppressive as any other, and the belief that the caliphate belonged to the best Muslim irrespective of his genealogy, led Berber tribes to conquer most of Ifrīqiya, including Qayrawan. In 333/945 al Qa'im found himself besieged by Abu Yazīd in al Maḥdiyya, a coastal city built by his predecessor as a symbol of the new order which now became the last stronghold of true faith against the attacks of the Dajjal, the Muslim Antichrist, as Faṭimid propaganda portrayed Abu Yazīd. His failure at the gates of the capital and his total defeat by al Qa'im's successor, al Maṣṣūr (r. 334–41/946–53), earned the dynasty fresh justification for its divine mission.

The revolt of Abu Yazīd also affected the covert war between the Faṭimids and the Umayyads. At the height of his power the rebel had pleaded his allegiance to 'Abd al Raḥman III through a delegation composed of some Malikī scholars from Qayrawan. Although the Andalusian navy arrived too late to be of any help to the rebels, the episode increased the enmity between the two dynasties. The caliph al Mu'izz (r. 341–65/953–76) accused the Umayyad of being a usurper who belonged to an impious family and had adopted a title that his ancestors in al Andalus had never dared to use.⁶³ In 347/958 he sent his general Jawhar on an expedition that took Tahert, Fez and Sijilmasa, and delayed retaliation for several decades of Umayyad supremacy.

63 M. Yalaoui, 'Controverse entre le Fatimide al Mu'izz et l'Omeyyade al Nasir d'après le Kitab al Majalis w l Musarayat du cadī Nu'man', *Cahiers de Tunisie*, 26 (1978), suppl. pp. 7–33.

But the sights of the dynasty were no longer set on the west. Campaigns against Egypt had begun as early as 301/914.⁶⁴ Neither this nor subsequent expeditions in 307 and 323/919–35 proved to be successful, but they helped to increase military pressure which bore its fruits in 358/969 when Jawhar conquered Egypt almost without resistance. Four years later the departure of al Mu'izz for al Qahira with the coffins of his ancestors showed that the intention of the Faṭimids was to bring the new era to the east and to leave behind the land that had witnessed their early success, but had also failed to earn them widespread recognition. The government of North Africa was entrusted to a military man: Buluggīn ibn Zīrī, a tribal leader who belonged to the tribe of Ṣinhaja and whose father had earned a well deserved reputation as a loyal supporter of the Faṭimid cause in the wars in central Maghrib. As a deputy of the caliph, Buluggīn was expected to continue the fight on the western frontier, while the administration of Ifrīqiya was left in the hands of civil officials. The first task was accomplished by Buluggīn in the campaigns he led between 368/979 and 373/984, which disrupted the supremacy of the Umayyad allies in the *Maghrib al aqṣā*. What had been left by the Faṭimid caliphs as a subsidiary administration became the framework of an independent rule and this was the achievement of Buluggīn's successors, the Zīrid rulers of Ifrīqiya.

The wars in the Maghrib had far reaching consequences for the Umayyads in al Andalus. These struggles were not only caused by the rivalry with the Faṭimids, but also by the need to control the trade routes of African gold. Soon after his self proclamation as caliph al Naṣir began to strike *dīnars*, the first time they had been minted in almost two centuries.⁶⁵ These *dīnars* and the large amount of silver *dirhams* also minted by the caliphs bear witness to an economic expansion which is noticeable in both rural and urban areas. The extension of settlements, the introduction of agrarian techniques and crops imported from the east and the colonisation of marginal areas responded to a growing demand in urban areas.⁶⁶ Hitherto modest sites, such as Murcia,

64 H. Halm, *The empire of the Mahdi: The rise of the Fatimids*, trans. Michael Bonner (Leiden, 1996), pp. 196–213.

65 A. Canto, 'De la ceca de al Andalus a la de Maḍīnat al Zahra', *Cuadernos de Maḍīnat al Zahra*, 3 (1991); M. Barceló, 'El hiato en las acuñaciones de oro en al Andalus, 127–316/744(5)–936(7): Los datos fundamentales de un problema', *Moneda y Crédito. Revista de Economía*, 132 (1975), pp. 33–71.

66 New local examples based on the archaeological record in S. Gutiérrez, *La cora de Tudmūr de la Antigüedad tardía al mundo islámico: Poblamiento y cultura material* (Madrid and Alicante, 1996); and J. C. Castillo Armenteros, *La campiña de Jaén en época emiral* (Jaén, 1998).

Jaén, Almería or Badajoz, became thriving cities in an increasingly complex urban network, whose traditional main centres – Cordoba, Seville, Saragossa and Toledo – also underwent an extraordinary growth.⁶⁷

All these cities made up the backbone of the provincial administration of the caliphate. Al Andalus was divided into a series of provinces (*kuras*) whose governors were appointed and dismissed regularly. Each *kura* comprised districts (*iqlīms*) which included rural settlements (*qaryas*) also serving as fiscal units liable to pay a sum in taxes which was fixed in advance. This organisation, which went back to the times of the settlement of the Syrian *junds*, seems to have worked very efficiently. The eastern traveller Ibn Ḥawqal, who visited al Andalus in 337/948 and was probably an informant for the Faṭimids, estimated that caliphal wealth amounted to 20 million *dīnars*, a sum which is consistent with data indicating that the income from taxes for the whole of al Andalus totalled 4 to 5 million *dīnars* per year.⁶⁸

The religious authority of the caliphs also depended on the territorial extension of Islamic institutions. Judges, mosque preachers, market supervisors and curators of charitable trusts (*awqaf*) were increasingly appointed not only for Cordoba but also for the main cities of al Andalus. Most of these positions were filled by ‘*ulama*’ who, despite their different geographical origins, had acquired their knowledge among the religious circles of the capital. The main corpus of doctrine that inspired the regulation of issues connected to ritual practices (*‘ibadat*) or civil affairs (*mu‘amalāt*) had already been fixed according to Malikī principles, as shown by treatises such as the *Mukhtaṣar* by ‘Alī ibn ‘Isa al Ṭulayṭulī (d. after 297/910). Legal practice, which sprang from these principles, became increasingly complex. Opinions on difficult legal questions (*fatwas*) began to be compiled, as did the rulings of Cordoban judges. Other compilations, such as the *Kitāb al wathā’iq wa l sijillāt* (Book of notary documents and records) by Ibn al ‘Aṭṭar (d. 399/1009), gathered models of notarial documents which were used for a variety of contracts (sales, share cropping agreements, freeing of slaves, marriages, etc.) and whose contents bear witness to the high degree of sophistication that the practice of Islamic *fiqh* had attained in al Andalus at this period.⁶⁹

67 The standard work on Andalusian cities remains L. Torres Balbas, *Ciudades hispanomusulmanas* (Madrid, 1972).

68 Ibn Ḥawqal, *Kitāb ṣurat al arḍ*, ed. M. J. de Goeje, rev. J. H. Kramers, BGA 2 (Leiden, 1938), p. 112.

69 Alī b. ‘Isa al Ṭulayṭulī, *Muḥtaṣar (Compendio)*, ed. and trans. M. J. Cervera (Madrid, 2000); Ibn al ‘Aṭṭar, *Kitāb al wathā’iq wa l sijillāt*, ed. P. Chalmers (Madrid, 1983), trans. P. Chalmers and M. Maruḡān as *Formulario notarial y judicial andalusí*, estudio y traducción (Madrid, 2000).

There are some indications, however, of a mounting crisis in the Umayyad civil administration during the second half of the fourth/tenth century. Protests against the corruption and rapacity of some provincial governors grew worse during the caliphate of al Naṣīr's son and successor, al Ḥakam II (r. 350 66/961 76). Unlike his father, al Ḥakam seems to have distrusted the powerful families of *mawālī* who had traditionally served in the main positions of the administration. His preference for the *ṣaqaliba* (eunuch slaves of northern European origin), or for obscure individuals who were notable for their meteoric careers, may have been a conscious policy dictated by a desire to get rid of the families that had become too powerful thanks to their control of the Umayyad administration.

It was in this context that the rapid promotion of the celebrated al Maṣṣur (Sp. Almanzor) took place. A scion of an Arab family whose ancestor had taken part in the early conquest and had settled in Algeciras, and which afterwards kept a very low profile, Muḥammad ibn Abī Āmir managed to set up a solid network of power relations which brought him from the humblest posts to the highest ranks of the caliphate. With other leading officials of the civil and military administration he profited from the situation created by the death of al Ḥakam II in 366/976 and from the minority of his only son and successor, Hisham II, who was proclaimed caliph in spite of the rulings that explicitly forbade the title commander of the faithful being conferred upon a child. In subsequent years al Maṣṣur systematically eliminated all his rivals until he was appointed *ḥajib*. Once in full control of the administration he relegated Hisham II to the role of puppet caliph, assuming for himself and his family all positions of power that the Umayyad administration had set up in the preceding decades.

Aggressive warfare against the Christian kingdoms, staunch religious orthodoxy and a firm grip on the apparatus of the caliphate were the means by which al Maṣṣur attempted to legitimise his rule. A crucial element in this scheme was the enrolment of Berber troops recruited in North Africa, whose ranks had been increasing since the time of al Ḥakam II, but which now became the main body of the Umayyad army, replacing the old system of *junds*. Ibn Ḥawqal estimated their number at 5,000, but by the end of the fourth/tenth century they were at least 7,000, including tribal groups such as the Zanata Banu Birzal or the Ṣinhaja Zīrids, who were relatives of the ruler of Ifrīqiya but had deserted his ranks due to their frustration with the distribution of power in their native land. These troops received regular stipends and were garrisoned in Cordoba and in the new palatine city, Maḍinat al Zahira, the construction of which the ambitious *ḥajib* ordered somewhere to the east of the capital.

Al Maṣṣūr's aim was to create a dynasty. Upon his death in 392/1002 his son, 'Abd al Malik al Muẓaffar, was also entrusted with the title of *ḥajib* by the weak Hisham II, and during the six years of his rule he followed the same policy as his father. His death in 399/1008 marked the beginning of the end of the Umayyad caliphate.⁷⁰ He was immediately replaced by his brother, 'Abd al Raḥman nicknamed Sanjul because his mother was the daughter of King Sancho II of Navarra who took the unprecedented step of forcing Hisham II to designate him as successor to the caliphate. Although the caliph had no offspring there were a number of descendants of al Naṣir, who were ready to oppose this extravagant move. A riot in the capital ended with the killing of Sanjul but also sparked internal strife among members of the Umayyad kin. For more than two decades Cordoba was the scene of fierce fighting among these factions. Its population took an active role in these struggles, always siding with the party that opposed the Berber militias. The rejection of this army by the Cordobans enshrined their hostility to caliphal rule, which had become particularly oppressive in the preceding decades. The sacking of Madīnat al Zahira or the massacre of Berbers in 399/1009 were followed by the destruction of Madīnat al Zahra' and the pillage of Cordoba by the North African troops.

While these events were taking place in the capital, caliphal administration broke down in the rest of al Andalus. Local elites severed their links with Cordoba throughout these years of turmoil, paving the way for the emergence of the *Ṭa'ifa* kingdoms. When in 422/1031 the last Umayyad caliph, al Mu'tadd, was deposed in one of the frequent riots in the capital, he and his family were banned from Cordoba. As the former unity of the caliphate collapsed the new political map comprised a number of petty kingdoms, ruled by families of different origin: some were descendants of the early conquerors, such as the Berbers Banu Dhi 'l Nun of central al Andalus; some were Berbers of the caliphal armies who had left Cordoba and had settled in new territories, such as the Zirids who founded the *Ṭa'ifa* of Granada; others were former members of the caliphal administration who managed to build up a territorial domain in some parts of eastern al Andalus, as was the case of the *ṣaqaliba* who briefly ruled in Almería or Denia. All of them knew that the Umayyads had disappeared for good, but all maintained a fiction that the caliphate still existed and presented themselves as its self appointed representatives. This was a recognition that political authority in al Andalus could only be expressed in terms of Islamic legitimacy.

⁷⁰ P. Scales, *The fall of the caliphate of Cordoba: Berbers and Andalusis in conflict* (Leiden, 1994), pp. 38–109.

PART IV

★

THE HISTORIOGRAPHY OF EARLY
ISLAMIC HISTORY

Modern approaches to early Islamic history

FRED M. DONNER

Preliminary considerations

Western writing on Islam, including early Islamic history, has roots reaching back to the medieval period.¹ These earliest Western writings were almost without exception religious polemics – tracts intended to assert the theological claims of Christianity and to disprove or discredit those of Islam. They often pursued these goals by presenting grotesque misrepresentations of Islam and its history.² Polemicists devoted special attention to discrediting the Qur'an and Muḥammad because this, they thought, would most effectively undermine Islam's faith claims – that Muḥammad was a prophet, and that the Qur'an was God's revealed word.

This polemical tradition cannot, of course, be considered scientific scholarship, the goal of which is to understand the subject of its study, not to discredit it; but it is important to remember that the Western tradition of anti-Islamic polemic formed the background against which more scholarly writings first developed, and thus in some ways inevitably helped shape the latter. Early Islamic history in particular, because it includes the story of the life of Muḥammad, the revelation of the Qur'an and the early expansion of the Believers, was long closely entangled with polemic. Moreover, the polemical

¹ 'Modern' and 'Western' are obviously not exact equivalents, but the problem is too complex to be examined here. In the present chapter they will be used as rough equivalents, even though some examples of 'modern' writing have been produced by scholars who themselves hail from outside the 'West', and some Western authors write works that are not 'modern' in that they depart from widely accepted standards of modern scholarship.

² On the polemical tradition see Norman Daniel, *Islam and the West: The making of an image*, 2nd edn (Oxford, 1993 [1960]); R. W. Southern, *Western views of Islam in the Middle Ages* (Cambridge, MA, 1962); Hugh Goddard, *A history of Christian Muslim relations* (Edinburgh and Chicago, 2000); John Victor Tolan, *Saracens: Islam in the medieval European imagination* (New York, 2002). A deft summary of the origins of Western views of the 'Orient' is found in Zachary Lockman, *Contending visions of the Middle East: The history and politics of Orientalism* (Cambridge, 2004), pp. 8–65.

tradition never completely died out, but has survived right up to the present in a variety of guises. Besides straightforward tracts denouncing Islam as 'false religion', of which many continue to be published, particularly in the United States, there have occasionally been the more insidious works that adopt the externals of rigorous scholarship, but still adhere to the basic assumptions of the polemical tradition; the works of Sir William Muir (1819–1905), such as *The Life of Muhammad*,³ are cases in point.⁴ In another vein, there has emerged in recent years a secularised contemporary avatar of the medieval religious polemics against Islam that essentialises 'Islamic civilisation' as antagonist to the 'West' and which sometimes reaches back to the founding events of early Islamic history in an effort to find ammunition for its arguments.⁵ In considering how scholars in the modern West have studied early Islamic history, then, it is important to be mindful of the many forms of the polemical tradition against Islam, even though that tradition cannot be considered scholarship in the proper sense of that word.

A few Western writers began to study Islamic history in a manner that was free of the assumptions of religious polemic as early as the seventeenth century,⁶ but it was the Enlightenment of the eighteenth century, with its emphasis on the use of human reason to attain understanding of all subjects, that finally created the conditions under which some people in the West could leave polemics behind and begin to examine Islam and its history more open mindedly. This process of looking at Islam and its history in a more sympathetic way was limited, however, by two factors. For one thing, not all people in the West were willing to abandon polemic and embrace rationalist principles. Moreover, the very rationalism of Enlightenment thinkers, which had caused them to reject the Church's polemical condemnations of Islam as 'false religion', also made them likely to view critically some religious dogmas of Islam as well, for human reason was seen as being of universal applicability in examining all traditional beliefs.

3 William Muir, *The life of Muhammad*, 1st edn (Edinburgh, 1861).

4 See Clinton Bennett, *Victorian images of Islam* (London, 1992), esp. pp. 176–7.

5 The historian Bernard Lewis's 'The roots of Muslim rage', *The Atlantic Monthly* (September 1990), and the political scientist Samuel P. Huntington's *The clash of civilizations and the remaking of the world order* (New York, 1996) seem to have served as the intellectual stimulus for this new kind of polemic. On this trend in modern writing, see Emran Qureshi and Michael A. Sells (eds.), *The new crusades: Constructing the Muslim enemy* (New York, 2003); Lockman, *Contending visions*, pp. 233–41. Maxime Rodinson, *La mystique de l'Islam* (Paris, 1980), trans. Roger Veinus as *Europe and the mystique of Islam* (Seattle, 1987), pp. 67, 104–5, seems to be warning against this trend towards essentialism and what he calls 'theologocentrism' – that is, a tendency to see 'Islam' as the root of all problems with modern Middle Eastern states.

6 On these pioneering writers see Daniel, *Islam and the West*, pp. 317–23.

Nonetheless, the Enlightenment greatly accelerated the study of Islam on a truly scholarly, rather than polemical, basis – that is, in a systematic way and with the goal of understanding Islam and its history, rather than of ‘defeating’ it intellectually. During this period, moreover, close first hand observations of Muslim societies by Western sojourners became more numerous and provided Europeans with fuller information about Islamic societies than the polemical tradition had offered. Not all this information was accurate; it has been plausibly suggested that the bizarre stereotypes of ‘the Oriental’ that circulated in Europe and helped shape popular perceptions and colonial policy were probably the heritage not of scholars but of those increasing numbers of Europeans who had had direct contact with ‘the Orient’ but not with scholarship on it: sailors, merchants, colonial agents and others.⁷ But some European contacts did yield accurate descriptions, which helped to counter the more grotesque misconceptions about Islam and Muslim societies that survived from the polemical tradition: noteworthy examples are the massive *Déscription de l’Égypte* (1809–29), prepared by the scholars who accompanied Napoleon’s invasion of Egypt in 1798, and *An account of the manners and customs of the modern Egyptians* (1836) by E. W. Lane (1801–76).

As far as early Islamic history is concerned, Western scholars of the Enlightenment began to consult key texts of the Islamic tradition itself (often, of course, in manuscript) in search of information. This process was advanced not only by the establishment of chairs of Oriental languages at a number of European universities (notably Leiden, Paris and Oxford) – something that was already happening by the sixteenth century – but also by the demand in the courts of Vienna, Paris, London and elsewhere for diplomats and interpreters skilled in Oriental languages, some of whom, such as Joseph Freiherr von Hammer Purgstall (1774–1856), published the fruits of their learning and experience. For the first time there emerged in the West a body of scholars who were competent to consult Islamic sources directly as they attempted to describe Islam’s beliefs and historical development. In addition, some Oriental sources began to appear in translation into Latin, French and other European languages through the efforts of scholars such as Barthélemy d’Herbelot (1625–95), whose *Bibliothèque orientale* (1697) was reprinted several times (including a German translation) during the eighteenth century. This activity made some detailed information, drawn from Islamic sources, available to writers whose works commanded a large audience, but

⁷ William Montgomery Watt, *Muslim Christian encounters: Perceptions and misperceptions* (London and New York, 1991), pp. 108–9.

who were not themselves trained in Oriental languages. Edward Gibbon's *Decline and fall of the Roman empire* (the first volume of which appeared in 1776), for example, contained a lengthy section on the rise of Islam, derived mainly from translations of late medieval Muslim authorities such as Abu 'l Fida' (d. 1331). Two generations later Thomas Carlyle (1795–1881) was inspired by translated sources to write a relatively sympathetic biography of Muḥammad in his *On heroes, hero worship, and the heroic in history* (1841).

All of the activity briefly sketched above constitutes the background to the scientific study of early Islamic history in the modern West, which really only got under way in the middle of the nineteenth century. It was only at this time that the study of Islamic history began to be consistently disentangled from Islamic religious studies on a continuous basis by a (small) critical mass of scholars relatively free of the assumptions of the polemical tradition.⁸

In considering more closely the further evolution of Western scholarship on early Islamic history, it will be useful to discuss separately two aspects of it: first, the different approaches Western scholars have taken to the Muslim sources for early Islamic history, including the Qur'an; and second, various problems of perception, conceptualisation and bias.

Approaches to the sources for early Islamic history

The general development of history as a scholarly discipline in the West following the Enlightenment – a process that encompassed, of course, much more than the study of the Islamic world and that was often closely tied to the early articulation of national identities in Europe – posited that the writing of history should rest as much as possible on the analysis of actual documents originating in the time and place under study. A major difficulty facing the historian who wishes to write about early Islamic history, however, is that for many chapters of this history truly documentary sources are either scarce or non-existent.⁹ This is particularly true for the crucial earliest phases of Islam's history – the life of the Prophet Muḥammad, the expansion of the earliest community of Believers (often called the 'Islamic conquests' or the 'Arab conquests'), and the early caliphate and civil wars – for which almost no true documentation survives. Indeed, for most of what happened during at

⁸ On the nineteenth century background in particular, see the illuminating comments of Albert H. Hourani, *Islam in European thought* (Cambridge, 1991).

⁹ A fuller discussion of the material presented in this section is found in Fred M. Donner, *Narratives of Islamic origins: The beginnings of Islamic historical writing* (Princeton, 1998), pp. 1–31.

least the first two centuries of the Islamic era (corresponding roughly to the seventh and eighth centuries CE) only a limited number of documents are extant, mostly from the later years of that time span.

The dearth of documentary evidence for much of early Islamic history forced Western historians to rely instead on the Muslim tradition's own narratives about Islam's origins, enshrined in a variety of Muslim chronicles, biographical dictionaries, geographical treatises, genealogical works, poetry collections and religious literature, particularly collections of *ḥadīths* or sayings attributed to the Prophet Muḥammad himself. (Works such as the *History* of al Ṭabarī (d. 923), the biographical dictionary of Ibn Sa'd (d. 845), the *Futuḥ al buldan* of al Baladhurī (d. 892) and the *Muṣannaḥ* of 'Abd al Razzaq al Ṣan'anī (d. 827) may be mentioned as representative examples.) This body of narrative source material was voluminous in size and offered copious detail about many events, but even the earliest of these works are not documents, but rather literary compositions, compiled many years – sometimes several centuries – after the events they describe. While these texts were compiled from yet earlier (now lost) sources or informants, the transmission of this material and its reliability were often uncertain.

The first Western historians who wished to write about early Islamic history in the eighteenth and nineteenth centuries overestimated the documentary value of the Muslim literary sources and, wishing to move beyond the misrepresentation and bigotry of the earlier polemical tradition, understandably were drawn to the literary sources both by their rich detail and by the fact that, as Muslim sources, they were assumed to offer a less biased view of early Islam than did the overly fertile imaginations of polemicists. The Western scholarship that resulted can thus be said to have followed the Descriptive Approach: that is, it utilised Muslim sources in the first instance to describe Islam and its early history. The summary provided in Gibbon's *Decline and fall*, just mentioned, fits into this category, as did the works of the Orientalist Gustav Weil (1808–89), such as his *Muhammed der Prophet* (1843) and *Geschichte der Chalifen* (1846–51);¹⁰ and, as we shall see, this approach is still widely followed, especially in survey texts.

Greater familiarity with the Islamic sources that provided the substance of what Western scholars said about early Islamic history soon brought an awareness of the limitations of these sources. It became clear, for example, that they contained many contradictory reports, such as the conflicting

¹⁰ On the latter, see D. M. Dunlop, 'Some remarks on Weil's History of the caliphs', in Bernard Lewis and P. M. Holt (eds.), *Historians of the Middle East* (London, 1962).

accounts of the early Islamic conquests or of the events of the first civil war. In the interest of establishing 'what actually happened' some scholars attempted to harmonise these reports by attributing their contradictions to different informants who had different agendas and degrees of reliability as reporters. Tracing earlier informants was possible in many cases because individual reports were introduced by a chain of narrators (called the *sanad* or *isnad*) that listed the putative originator of the report and those who had transmitted it. This scrutiny of earlier informants, which we can call the Source Critical Approach, first came into general use in the second half of the nineteenth century, and yielded some astute analyses that shaped the contours of historical critical scholarship on various aspects of early Islamic history for many years – and, indeed, still does. Julius Wellhausen's *Prolegomena zur ältesten Geschichte des Islams* (1899), for example, which followed on and further developed some of the insights of M.J. de Goeje's *Mémoire sur la conquête de la Syrie* (1864), led subsequent generations of Western scholars to dismiss, or at least to handle with great scepticism, the narrations – and especially the chronology – of the early Kufan compiler Sayf ibn 'Umar (fl. c. 800?), and to prefer the reports of Ibn Ishaq (d. 767 or 768), al Waqidī (d. 823), al Mada'inī (d. c. 845) and others; only in the last decade of the twentieth century did some revision of Wellhausen's judgements of Sayf appear.¹¹ The massive compilations of Leone Caetani (1869–1935), particularly his *Annali dell'Islam* (1905–26), were based on the assumption that by tabulating all extant accounts for a given event, with their narrators, historians could successfully reconstruct early Islamic history by comparing all reports and setting aside those traceable to 'weak' informants and by identifying spurious later elaborations. The works of Tor Andrae (1885–1947) on the life of Muḥammad similarly assumed that one could sift earlier 'historical' from later 'legendary' material.¹² More recently, analogous assumptions underlie the works of W. Montgomery Watt (1909–2006) on Muḥammad and Wilferd Madelung (b. 1930) on the early caliphate.¹³

Another trend in Western scholarship on early Islam, also developing first in the late nineteenth century, challenged the assumption of the source critics that the information in the traditional Islamic narratives represented copies of

11 Ella Landau Tasseron, 'Sayf ibn 'Umar in medieval and modern scholarship', *Der Islam*, 67 (1990).

12 Tor Andrae, *Die Person Muhammads in Lehre und Glauben seiner Gemeinde* (Stockholm, 1918); Tor Andrae, 'Die Legenden von der Berufung Muḥammeds', *Le monde oriental*, 6 (1912).

13 W. Montgomery Watt, *Muḥammad at Mecca* (Oxford, 1953); W. Montgomery Watt, *Muḥammad at Medina* (Oxford, 1956); Wilferd Madelung, *The succession to Muḥammad* (Cambridge, 1997).

early documents or the verbatim reports of actual eyewitnesses. Instead, these scholars, whom we may call advocates of the Tradition Critical Approach, argued that the reports we find in the Islamic sources were in most cases merely the capture in written form of oral traditions about the past. These traditions had diverse and often uncertain origins, and had undergone a period of oral transmission of indeterminate duration; hence, they could be used to reconstruct events of the past only with great caution, because it is usually impossible to know what material may have been dropped, added or changed in the course of transmission. The pioneer in these studies was the Hungarian scholar Ignaz Goldziher (1850–1921), whose revolutionary *Muhammedanische Studien* (1889–90) presented insights many of which still seem essentially sound over a century later, such as the fact that many reports attributed to the Prophet (*ḥadīths*) seem to be stalking horses for the claims of later partisan groups in the Islamic community.¹⁴ A number of scholars subsequent to Goldziher built on his work; particularly noteworthy are Joseph Schacht (1902–69) in the field of Islamic law,¹⁵ Erling Ladewig Petersen (b. 1929) on reports about the first civil war¹⁶ and Albrecht Noth (1938–99) on the conquest narratives.¹⁷ Since the last third of the twentieth century numerous scholars have offered detailed tradition critical studies of particular problems, among which the works of M.J. Kister (b. 1914), U. Rubin (b. 1944), Michael Lecker (b. 1951), Klaus Klier and many others can be taken as representative.¹⁸

The problem of the instability of orally transmitted reports was exacerbated by the likelihood that many of the early written compilations from the second

14 See Ignaz Goldziher, *Muhammedanische Studien* (Halle, 1889–90), vol. II, pp. 88–130, trans. S. M. Stern and C. R. Barber as *Muslim studies*, 2 vols. (London, 1967–71), vol. II, pp. 89–125. The enduring value of Goldziher's work is apparent from the fact that, many decades after their first publication, some of his major works were still being translated, e.g. Stern and Barber's *Muslim studies* and his *Vorlesungen über den Islam* (Heidelberg, 1910) trans. Andras and Ruth Hamori as *Introduction to Islamic theology and law* (Princeton, 1981).

15 Especially Joseph Schacht, *The origins of Muhammadan jurisprudence* (Oxford, 1950).

16 Erling Ladewig Petersen, 'Ali and Mu'awiya in early Arabic tradition: *Studies on the genesis and growth of Islamic historical writing until the end of the ninth century*, 2nd edn (Odense, 1974 [Copenhagen, 1964]).

17 Albrecht Noth, *Quellenkritische Untersuchungen zu Themen, Formen, und Tendenzen frühislamischer Geschichtsüberlieferung* (Bonn, 1973) rev. edn (with Lawrence I. Conrad), trans. Michael Bonner as *The early Arabic historical tradition* (Princeton, 1994); Albrecht Noth, 'Iṣfahan Nihawand. Eine quellenkritische Studie zur frühislamischen Historiographie', *ZDMG*, 118 (1968).

18 E.g. M.J. Kister, *Studies in jahiliyya and early Islam* (London, 1980); Uri Rubin, 'Morning and evening prayers in Islam', *JSAI*, 10 (1987); Michael Lecker, *The 'Constitution of Medina': Muhammad's first legal document* (Princeton, 2004); Klaus Klier, *Halid und 'Umar: Quellenkritische Untersuchung zur Historiographie der frühislamischen Zeit* (Berlin, 1998).

and third centuries AH in which such reports are found were themselves transmitted orally; that is, compilers of early written works often transmitted their material to their students by lecturing. Hence many 'books' exist in two or more recensions traceable to the notebooks or other records made by different students of the work's compiler. F. Sezgin, R. Sellheim, S. Leder, N. Calder, G. Schöler and others have vigorously debated the question of the stability of the texts of the early 'books' of which we have knowledge, or even whether they originally existed in the form of books at all, rather than just as collections of notes.¹⁹

In recent years the complexities of the sources have led some to adopt what can be called the Sceptical Approach, which, building especially on the work of Schacht and the tradition critics, rejects the historicity of almost all the traditionally conveyed material; noteworthy early contributions in this vein were Patricia Crone and Michael Cook's *Hagarism* (1977) and John Wansbrough's *The sectarian milieu* (1978).²⁰ The fundamental argument of scholars in this group is that the tradition may not, in fact, contain any 'kernel' of true material; and even if it does, it is impossible now to disentangle it from the many layers of distortion and fabrication built up over centuries of manipulation. Whatever 'true' memories about Islam's origins may have been retained by early generations and subsequently preserved by the Islamic community in written form, the sceptics argue, have been subjected to so many successive waves of compression, fragmentation, recombination and reinterpretation that we now have only what Crone terms 'debris of an obliterated past'.²¹ The sceptical school has raised many pointed and valuable questions about the reliability of the sources for early Islamic history and, therefore, what the appropriate attitude of the historian towards these sources might be. These questions continue to be discussed, but the sceptics

19 See esp. Fuat Sezgin, *Geschichte des arabischen Schrifttums*, vol. I (Leiden, 1967); Rudolf Sellheim, 'Abu 'Alī al Qalī: Zum Problem mündlicher und schriftlicher Überlieferung am Beispiel von Sprichwörtersammlungen', in H. R. Roemer and A. Noth (eds.), *Studien zur Geschichte und Kultur des vorderen Orients: Festschrift für Bertold Spuler* (Leiden, 1981); Stefan Leder, *Das Korpus al Haitam ibn 'Adī (st. 207/822): Herkunft, Überlieferung, Gestalt früher Texte der ahbar Literatur* (Frankfurt, 1991); Norman Calder, *Studies in early Muslim jurisprudence* (Oxford, 1993); Gregor Schoeler, 'Die Frage der schriftlichen oder mündlichen Überlieferung der Wissenschaften in frühen Islam', *Der Islam*, 62 (1985); Gregor Schoeler, *Écrire et transmettre dans les débuts de l'Islam* (Paris, 2002).

20 See also Patricia Crone, *Slaves on horses: The evolution of the Islamic polity* (Cambridge, 1980), pp. 3–17; Yehuda D. Nevo and Judith Koren, 'The origins of the Muslim descriptions of the Jahili Meccan sanctuary', *JNES*, 49 (1990); G. R. Hawting, *The idea of idolatry and the emergence of Islam: From polemic to history* (Cambridge, 1999).

21 Crone, *Slaves on horses*, p. 10.

have encountered some scepticism about their own approach, because some of their claims seem overstated – or even unfounded.²² Moreover, their work has to date been almost entirely negative – that is, while they have tried to cast doubt on the received version of ‘what happened’ in early Islamic history by impugning the sources, they have not yet offered a convincing alternative reconstruction of what might have happened.²³

These different approaches to the sources emerged at successive historical moments but, rather than supplanting its predecessors, each new approach simply coexisted beside them, and all approaches continue to be practised today in varying degrees. A descriptive approach still seems to provide the basis of most modern overviews of early Islamic history, which offer the externals of the Islamic tradition’s own origins narratives, adjusted slightly in order to bracket out the miraculous and the assumptions of Islam’s faith claims (in particular, that Muḥammad was a prophet and that the Qur’an is God’s revelation). Such works rely so heavily on Muslim literary sources in formulating their own reconstructions, however, that they have recently been characterised, with much justice, as ‘Muslim chronicles in modern languages and graced with modern titles’.²⁴ The descriptive approach’s continuing popularity with authors of survey texts about early Islamic history, despite the misgivings of scholars about the sources, is probably attributable to the fact that it offers the kind of smooth, outwardly plausible narrative that other approaches have not yet been able to muster.

On the other hand, contemporary scholars who examine Islam’s origins in depth mainly tend to follow the source critical or tradition critical school in their handling of the Islamic sources. This work should lead in time to a more historically grounded general presentation of early Islamic history, but

22 An overview of the criticisms of the sceptical approach is found in Donner, *Narratives of Islamic origins*, pp. 25–31.

23 John Wansbrough, *The sectarian milieu: Content and composition of Islamic salvation history* (Oxford, 1978), p. x, explicitly eschews the possibility that the history of early Islam can be reconstructed. The reconstruction in Patricia Crone and Michael Cook’s *Hagarism: The making of the Islamic world* (Cambridge, 1977) is imaginative, but raises more questions than it resolves and has not been generally accepted. Gerald Hawting, ‘The rise of Islam’, in Youssef M. Choueiri (ed.), *A companion to the history of the Middle East* (Oxford, 2005), offers general revisionist perspectives on the traditional view of how Islam first arose, but not a coherent synthesis of what might have happened, and his survey of Umayyad history in *The first dynasty of Islam: The Umayyad caliphate, AD 661–750* (Beckenham and Carbondale, 1987) offers a view fully consonant in most respects with the traditional Muslim sources and with earlier studies such as Julius Wellhausen’s *Das arabische Reich und sein Sturz* (Berlin, 1902), trans. Margaret Graham Weir as *The Arab kingdom and its fall* (Calcutta, 1927).

24 Crone, *Slaves on Horses*, p. 13.

progress towards this goal has been slow. For one thing, many contributions in the tradition critical mould focus almost entirely on problems of textual criticism and leave it unclear how much can be said about 'what actually happened', at least for the origins period.²⁵ While a number of specific issues have been clarified in careful tradition critical studies, these studies do not yet add up to a clear general picture.²⁶ Most alternative narratives based squarely on revisionist perspectives still seem too general or vague, and are often presented explicitly as a critique of the traditional narrative, knowledge of which on the part of the reader they therefore take for granted.²⁷ For these reasons, scholars have not yet had much success translating the insights of tradition critical work into a clear narrative of Islam's origins suitable for non specialists that stands independent of most aspects of the traditional narrative. At the same time, their tradition critical work on the Islamic sources some times creates tensions between Western (or Western trained) scholars and their counterparts in the Muslim world who still cling to the assumption that the traditional Islamic sources, including Prophetic *ḥadīth* and the *akhbar* (reports) of the chronicles and biographical dictionaries, are quasi documentary in character, an assumption the tradition critics cannot accept.

Finally, it is necessary to say a few words about use of the Qur'an as a source for writing early Islamic history. The Qur'an has occupied a special place among the sources for early Islamic history, and probably always will, if only because of its special stature as Islam's scripture. Western scholars, while usually distancing themselves from the idea that the Qur'an is the actual word of God, nevertheless generally accepted it as a text contemporary with the Prophet Muḥammad and hence valuable as a source for his life (some flatly declared, or implied, that Muḥammad was the text's author or compiler, which is of course patent heresy to some Believers). Even the historian who accepts the idea that the Qur'an is contemporary with Muḥammad, however,

25 E.g. Uri Rubin, *The eye of the beholder: The life of Muḥammad as viewed by the early Muslims. A textual analysis* (Princeton, 1995), who admits (p. 3) that in his work 'the effort to isolate the "historical" from the "fictional" in the early Islamic texts is given up entirely'.

26 E.g. the many articles by M.J. Kister, a selection of which can be seen in his *Studies in Jahiliyya and early Islam*; but Kister nowhere offers his sense of the overall historical development of the early Islamic community.

27 Perhaps the most successful attempt is Albrecht Noth's chapter 'Früher Islam', in Ulrich Haarmann et al. (eds.), *Geschichte der arabischen Welt* (Munich, 1987). Other noteworthy recent efforts are Jacqueline Chabbi, *Le seigneur des tribus: L'Islam de Mahomet* (Paris, 1997), which focuses particularly on the Prophet's Arabian context, and Alfred Louis de Prémare, *Les fondations de l'Islam: Entre écriture et histoire* (Paris, 2002), which tries to read through the formation of key texts to the historical realities that lay behind them.

has difficulty deriving much information about specific historical events from the Qur'an, because its references to its own historical context are maddeningly vague: it rarely provides a specific name or time or event. Serious critical study of the Qur'an in the West began with the pioneering *Geschichte des Qorans* (first edn 1860) of Theodor Nöldeke (1836–1930), which accepted many of the Islamic tradition's own assumptions about how the Qur'an text came to be, and long served as a point of departure for scholars in the West.²⁸ Since the 1970s, however, our assumptions about the historical context of the Qur'an and its evolution as a text have been challenged fundamentally. John Wansbrough proposed in his *Qur'anic studies* (1977) that the Qur'an text did not coalesce as a canon of scripture shortly after the Prophet's death, as maintained by Muslim tradition and long accepted by most modern scholars, but rather that it emerged as a canon only at the end of a process that took two centuries or more. John Burton (*The collection of the Qur'an*, 1977), on the other hand, proposed that the Qur'an text as we have it was already fixed by the time of Muḥammad's death. Günter Lüling (*Über den ur Qur'an*, 1974) and Christoph Luxenberg (*Die syro aramäische Lesart des Koran*, 2000) advanced hypotheses that, while quite different from one another, both implied that the Qur'an may contain material that antedates the life of Muḥammad. All these hypotheses can be deeply unsettling to believing Muslims, and the circulation of such ideas in popular media²⁹ has attracted the attention, not always favourable, of more traditionally minded members of the Muslim community and sparked a debate over the text's authority and over who has the right to interpret it, and how. There is some danger that traditional believers may misinterpret critical studies of the Qur'an by scholars as polemical efforts to undermine Islam's faith claims,³⁰ and that popular pressure may deter scholars from pursuing this line of research. But these ideas are not much less unsettling for historians who were accustomed to

28 Theodor Nöldeke, *Geschichte des Qorans* (Göttingen, 1860). The text was in later editions completely reworked and greatly expanded by Friedrich Schwally and Gotthelf Bergsträsser.

29 E.g. Toby Lester, 'What is the Koran?', *The Atlantic Monthly* (January 1999). Lester's article appeared before the publication of Christoph Luxenberg's *Die syro aramäische Lesart des Koran: Ein Beitrag zur Entschlüsselung der Koransprache* (Berlin, 2000), which has reignited the discussion with, if anything, greater intensity; discussion of the debate it generated is surveyed in Christoph Burgmer (ed.), *Streit um den Koran: Die Luxenberg Debatte: Standpunkte und Hintergründe* (n.p., 2004).

30 This danger is increased by some who are, in fact, anti-Islamic polemicists, who irresponsibly seize on the work of critical scholars to advance their own anti-religious agenda; for example, the pseudonymous 'Ibn Warraq', who has edited several collections of scholarly articles, such as *The quest for the historical Muhammad* (Amherst, NY, 2000).

resorting to the Qur'an as a source for what the Islam of the time of the Prophet may have been. The debate on the nature and history of the Qur'an text is still full throated in the early twenty first century, and will doubtless continue so for many years to come.³¹

One consequence of these disagreements over how to view, and consequently how to exploit, the sources for the period of Islam's origins is that there continue to be dramatic differences of opinion among active scholars on 'what actually happened' in early Islamic history. Differences over the Qur'an have been noted above, and they are echoed for other aspects of Islam's origins. In the realm of *ḥadīth* studies, the view of Goldziher and Schacht that most *ḥadīths* are spurious interpolations of later opinions that were put in the mouth of the Prophet, and that their *isnads* 'grew backwards' was developed more fully by Gautier Juynboll³² and others, but it must be tempered by the work of Motzki,³³ who has shown that the transmission of *ḥadīths* as recorded in their *isnads*, even back to the seventh century CE, may be more secure than hitherto believed. Regarding the conquest narratives, Noth emphasised their salvation historical character and questioned whether the conquests had any centralised impetus or direction,³⁴ Sharon and others suggested they never occurred at all,³⁵ and Conrad has shown that some conquest accounts appear to have no secure factual basis;³⁶ on the other hand, Donner stressed the cogency of understanding the conquests as a unitary phenomenon³⁷ and Robinson demonstrated that some early, independent non Muslim sources confirm certain Muslim conquest reports.³⁸

31 A survey is found in Fred M. Donner, 'The Qur'an in recent scholarship: Challenges and desiderata', in Gabriel Said Reynolds (ed.), *Towards a new reading of the Qur'an* (Abingdon, 2008).

32 Gautier Juynboll, *Muslim tradition* (Cambridge, 1983).

33 Harald Motzki, *Die Anfänge der islamischen Jurisprudenz* (Stuttgart, 1991).

34 Noth, *Early Arabic historical tradition*.

35 Moshe Sharon, 'The birth of Islam in the Holy Land', in M. Sharon (ed.), *Pillars of smoke and fire: The Holy Land in history and thought* (Johannesburg, 1988); Yehuda D. Nevo and Judith Koren, *Crossroads to Islam: The origins of the Arab religion and the Arab state* (Amherst, NY, 2003). See also several essays in Karl Heinz Ohlig and Gerd Rüdiger Puin (eds.), *Die dunklen Anfänge: Neue Forschungen zur Entstehung und frühen Geschichte des Islam* (n.p., 2006).

36 Lawrence I. Conrad, 'The conquest of Arwad: A source critical study in the historiography of the medieval Near East', in A. Cameron and L. Conrad (eds.), *The Byzantine and early Islamic Near East*, vol. I: *Problems in the literary source material*, Studies in Late Antiquity and Early Islam 1 (Princeton, 1993).

37 Fred M. Donner, 'Centralized authority and military autonomy in the early Islamic conquests', in A. Cameron (ed.), *The Byzantine and early Islamic Near East*, vol. III: *States, resources, and armies* (Princeton, 1995).

38 Chase F. Robinson, 'The conquest of Khuzistan: A historiographical reassessment', *BSOAS*, 67 (2004).

The examples offered above illustrate some of the vexations that have afflicted those who work on Islam's origins. For periods subsequent to the origins era (that is, after c. 750 CE) historians are blessed not only with somewhat more plentiful documentary sources, but also with a much larger corpus of textual materials that, while not documentary, passed through a shorter period of oral and literary transmission than the Islamic origins narratives before being fixed in their present forms. This makes them a somewhat more secure basis for reconstructing 'what actually happened', but even these sources were sometimes subjected to tendentious redaction and literary shaping, and must be used circumspectly.³⁹

Practical and conceptual problems

Beyond the thorny problems posed by the heritage of the polemical tradition and by the deficiencies of the sources for early Islamic history, there exist other problems of perception and conceptualisation, as well as practical obstacles, that have affected Western approaches to early Islamic history.

Balance

The historian viewing the gradual crystallisation and elaboration of 'classical' Islamic civilisation would surely consider this to be a process that spanned four to five centuries, from the time of the Prophet Muḥammad in the late sixth century until at least the eleventh century. It took this long for the crucial questions of communal identity to be resolved and for the religious doctrines, legal and political institutions, and cultural and social practices that we consider typical of fully developed 'classical Islam' to emerge from the robust debates and disparate materials of the early Islamic centuries. For example, the institution of Muslim *qadīs* or judges, or the systematised law they administered, or the concepts of Prophetic *sunna* and scholarly consensus (*ijma'*) that were among the fundamental principles of this law, were all things that emerged at the earliest only a century after the time of the Prophet.

39 See, for example, Tayeb El Hibri, *Reinterpreting Islamic historiography: Harun al Rashīd and the narrative of the 'Abbasid caliphate* (Cambridge, 1999), which explores how these sources were shaped to fit a political agenda; also Boaz Shoshan, *Poetics of Islamic historiography: Deconstructing Ṭabarī's History* (Leiden, 2004); Jacob Lassner, *Islamic revolution and historical memory. An inquiry into the art of 'Abbasid apologetics*, AOS Series 66 (New Haven, 1986); Antoine Borrut, 'Entre mémoire et pouvoir: L'espace syrien sous les derniers omeyyades et les premiers abbassides (v. 72 193/692 809)', Ph.D. thesis, Université de Paris I (2007).

Yet within this half millennium of early Islamic history, Western scholarship has until very recently focused overwhelmingly on the very earliest episodes, while later periods, which must be seen as equally part of the long story of the formation of the classical Islamic paradigm, were relatively neglected. Thus, if one surveys the literature on the Islamic world written in the West before the mid twentieth century one finds numerous contributions and some debate on the Prophet, the Qur'an, the early Islamic conquests, early statecraft (including early taxation), the early civil wars and emergence of sectarian groups etc., but far less on the later Umayyads, the history of the 'Abbasid caliphate, and even less on such things as the Buyid emirate and Saljuq sultanate, the Faṭimid caliphate, the Almoravids, the Ghaznavids, the history of Yemen etc.

There were probably several reasons for this imbalance. It may merely reflect a general tendency among historians to search for 'origins' on the assumption that they hold the key to later developments. It may also be that Western scholars inherited a bias against later periods from their Muslim sources, which viewed the age of the Prophet and Companions as the 'golden age' against which all others paled. But it also seems likely that this imbalance, or skewed focus, is an unintended echo of the many centuries of anti Islamic polemic, which concentrated on the earliest chapters of Islamic history because it was there, the polemicists believed, that they could most easily score theological 'points' against Islam. This had the unintended consequence of bringing the historical problems of the beginnings of Islam into clearer focus and fuller debate, and in this way inadvertently set the historical agenda even for non polemical scholars of a later age, who mostly ignored later episodes in early Islamic history (from Umayyad times to the eleventh century). There were a few exceptions, which revealed the preoccupations of late nineteenth and twentieth century Europe. The small subfield of Arabic Islamic philosophy and science became relatively developed at an early stage because Western scholars of the nineteenth and early twentieth centuries, steeped since secondary school in Greek and in the classical philosophical tradition, were keen to help recover lost Greek works that survived in Arabic translation. They also became concerned with tracing the original contributions of Muslim philosophers such as al Farabī, al Kindī and Ibn Rushd, who received serious scholarly attention by the nineteenth century.⁴⁰ The history of the Levant in the time of the European Crusades similarly piqued the curiosity of numerous scholars in

⁴⁰ E.g. M. Steinschneider, *al Farabī*, Mémoires de l'Académie Impériale de Sciences de Saint Petersburg 7, 8, 4, (St Petersburg, 1869); Ibn Rushd in particular has been the

the nineteenth century, as reflected in the compilation of the massive *Recueil des historiens des croisades* (1896–1906), containing excerpts of relevant texts, including Arabic and other Oriental texts, in the original and French translation; Claude Cahen's pioneering study of the principality of Antioch marked a watershed in such work.⁴¹ But generally, studies of the historical, social and literary development of the Islamic world in the period after the Prophet and conquests were few and far between, at least until the 1960s, when the pace began to quicken. The Harvard historian Sir Hamilton Gibb (1895–1971) seems to have played some role in this process, as he encouraged many students to work in later periods, among them I. Lapidus, R. Bulliet and R. Mottahedeh.

Practical impediments

The problem of imbalance was partly also a consequence of the fact that the number of scholars actually engaging in research on early Islam was until recently very small, whereas the range of material they needed to cover was enormous. As late as the 1960s it was often the case that for a given major subfield (even something as vast as Islamic law) there was in each Western country (or even in several together) only one scholar who made that subfield his or her speciality and actively pursued research on it. The number of young scholars entering the field in each generation was sufficiently small that a new recruit was often encouraged to concentrate on something that was not 'already being done' by someone else. This contributed to an overly deferential attitude towards that one scholar, who was deemed a generation's real expert on a given subject because there was precious little by way of vigorous exchange of different views on it. (Thus, for two decades or more, Montgomery Watt was the dominant scholar in the British Isles who studied the Prophet Muḥammad, Joseph Schacht was almost the sole figure of renown in the United States who concentrated on Islamic law etc.)⁴² There also seemed to be an exaggerated deference shown to traditional views, so that the work of scholars who challenged established orthodoxies was neglected; the works of Henri Lammens

subject of a huge bibliography. A compact survey of this material is found in Franz Rosenthal, *Das Fortleben der Antike im Islam* (Zurich, 1965), trans. Emile and Jenny Marmorstein as *The classical heritage in Islam* (Berkeley, 1975).

⁴¹ *Recueil des historiens des croisades* (Paris, 1869–1906) included six large volumes devoted to 'historiens orientaux', including Arabic, Armenian, Greek and other sources. Claude Cahen, *La Syrie du Nord à l'époque des croisades et la principauté d'Antioche* (Paris, 1940) was among the first works to study closely the regions taken by the Crusaders, rather than just the movement itself and its Latin participants.

⁴² This also affected later historical periods: for example, David Ayalon was for roughly a quarter century virtually the only Western scholar who specialised in the study of the Mamluks of Egypt.

(1862–1937), criticised for their anti-Islamic tenor, or the study by Paul Casanova (1861–1926), *Mohamed et la fin du monde*, considered too radical for their day, come to mind.⁴³ This meant that these fields tended for long periods to be static, rather than involved in a dynamic scholarly discourse, and that in general the opening of new subfields was slow.

This problem was exacerbated by the fact that the teaching of Arabic and other languages relevant to early Islamic history (Persian, Syriac, Coptic, Pahlavi) was limited to a very few institutions in the West until the mid twentieth century, and, as everyone knows, Arabic in particular is not an easy language to acquire. Moreover, these languages were often taught inadequately, and were in many cases never mastered sufficiently to enable a scholar to read the sources with facility. Most programmes of study before the mid twentieth century provided little if any opportunity for students to polish their knowledge of living languages in parts of the Near East where they were actually spoken.

Furthermore, the heavily philological training that, while indispensable, should have been a necessary preliminary, often took so much time that it became virtually a scholar's complete scholarly formation, leaving little opportunity for strong training in historical method, literary analysis, intellectual history, social theory and the like.⁴⁴ Generations of Western scholars groomed above all to excel at close philological analysis of classical Arabic texts were usually neither trained nor temperamentally prepared to venture into synthetic considerations of a broader kind, and when they did so the results were often methodologically naive. In the field of history, moreover, the existence of voluminous Muslim chronicles seems to have sapped enthusiasm for undertaking the arduous labours of synthetic work in a field so understaffed; it was much easier to translate or paraphrase these chronicles to secure a basic historical story line about 'what actually happened' in Islamic history⁴⁵ – a story that frequently accepted the interpretation embedded in the source either uncritically or with minimal critical scrutiny. When persuasive syntheses were prepared, moreover, they often remained the dominant paradigm for decades. For example, Wellhausen's *Das arabische Reich und sein Sturz*, first published in 1902, found its first real monographic alternative

43 E.g. Henri Lammens, *Fatima et les filles de Mahomet: Notes critiques pour l'étude de la Sîra* (Rome, 1912); Paul Casanova, *Mahomet et la fin du monde*, 3 vols. (Paris, 1911–24).

44 Rodinson, *Europe and the mystique of Islam*, pp. 88–9, 92–3; Richard Bulliet, 'Orientalism and medieval Islamic studies', in John Van Engen (ed.), *The past and future of medieval studies* (Notre Dame, 1994), esp. p. 98.

45 A case in point is Julius Wellhausen's *Muhammad in Medina, daß ist Vakidi's Kitab al Maghazi in verkürzter deutscher Wiedergabe herausgegeben* (Berlin, 1882).

only in the 1970s, and is still referred to regularly in the early twenty first century.⁴⁶ The result was a fairly static picture of most of Islamic history, closely tied in its approach and emphases to the Muslim sources themselves (what we have above termed the descriptive approach).

Fortunately, since the middle of the twentieth century matters have improved markedly with regard to both balance and staffing. Partly due to funding provided by Western governments concerned with global diplomacy in the Cold War era, universities were in the 1960s able to devote more attention than before to training specialists in Middle Eastern languages, and many of these students also pursued Islamic studies generally, including early Islamic history.⁴⁷ Additional university positions were created, and more students drawn into the field. This process seems to have accelerated in the last years of the twentieth century with growing public awareness of the importance of Islam and the Middle East in the modern world. Language training underwent a transformation; the purely philological approach gave way to one that emphasised languages as living forms of expression, and language courses became both more widespread and more intense, and university programmes of study increasingly involved time spent in countries where the target languages were spoken.

As a result of these changes many fields that were hardly studied at all including those in the later phases of the early Islamic period, such as Buyid or Fatimid history – or were the preserve of one or two specialists in a generation such as Islamic law – are now actively pursued by numerous practitioners, and intellectual debate is often lively, sometimes carried out in an increasing array of specialised journals. Scholars of early Islamic history have shown increased interest in developing new approaches and methods, and in looking at such things as social history, gender relations, identity formation and economic history. Whole new disciplinary foci have begun to develop, such as the archaeology of the early Islamic period. At the same time, certain well established but torpid subfields have been revitalised, often by the publication of revisionist works that have aroused controversy; the most notable example is the study of the Qur'an and of Islam's origins, ignited by the near simultaneous publication in 1977 of Wansbrough's *Qur'anic studies* and Crone and Cook's *Hagarism*. In the early twenty first century the study of early Islamic history seems finally to have shaken off its earlier stagnancy, inadequate linguistic training, methodological naïveté and conceptual conservatism, and to have matured as a field.

46 The alternative, inferior in some ways to Wellhausen's synthesis, was M. A. Shaban's *Islamic history: A new interpretation*, 2 vols. (Cambridge, 1971–6), vol. I: AD 600–750 (AH 132).

47 Lockman, *Contending visions*, pp. 241–5.

Reductionism

The obvious parallels that any reader can note between some material in the Qur'an and various passages in the Hebrew Bible or New Testament became a focus of early comparative research, often of a crassly reductionist kind: that is, it dismissively 'reduced' early Islam or the Qur'an to being merely a deformed version of Judaic or Christian materials, which, it implied, were better because older. Such studies often proceeded on the simplistic assumption that the Qur'an had borrowed material directly from the earlier scriptures, or at least was dependent on them in a way that, they implied, somehow undermined its truth claims.⁴⁸ Sometimes one suspects that these works represent a thinly veiled (and perhaps partly subconscious) form of polemic, written by Western scholars who, despite their extensive scientific training, were deeply committed to their own faith (usually Christianity or Judaism). While a relationship of some kind between the Qur'an and the earlier scriptures can hardly be doubted, these reductionist studies were marred by their failure to consider the possibility that the Qur'an's contents might represent a truly original, creative reinterpretation of older materials, that the objectives of the Qur'anic version of these materials might be utterly different from the objectives of the earlier scriptures, or that what was not 'borrowed' by the Qur'an is just as important in assessing its spirit, intent and originality.⁴⁹

Since the last quarter of the twentieth century Western scholarship (particularly on the Qur'anic materials) has generally begun to move beyond a reductionist view of early Islam, and has emphasised the uniqueness and originality even of those Qur'anic passages that find close parallels in earlier scriptural traditions. At the same time, some new works have appeared that argue for an even closer *textual* relationship between the Qur'an and earlier scriptures than had hitherto been assumed – notably the studies of Lüling and Luxenberg, mentioned above. The debate on these issues continues.

Grip of traditional origins narrative

Another serious shortcoming of most Western studies of early Islam since the Enlightenment has been, until recently, a difficulty in constructing a

48 Noteworthy studies of this sort were Abraham Geiger's *Was hat Mohamed aus dem Judenthume aufgenommen* (Berlin, 1833); Richard Bell, *The origin of Islam in its Christian environment* (London, 1926); Charles Cutler Torrey, *The Jewish foundations of Islam* (New York, 1933).

49 A reaction to such reductionism is found in Marilyn Robinson Waldman, 'New approaches to "biblical" materials in the Qur'an', *MW*, 75 (1985).

truly historical picture of Islam's origins due to an overdependence on the traditional origins narrative constructed long ago by early Muslim historians – what we have termed the 'descriptive approach'. The dearth of truly documentary sources and the apparent plausibility of the traditional origins narrative meant that it was not until the problem of the sources for early Islam was tackled more intensively that progress could be made on constructing a truly historical picture of early Islam. A series of revisionist works appearing since the mid 1970s have challenged some of the most familiar tenets of the older view. These include, to mention a few, the idea that the environment in which the Qur'an crystallised was primarily one of paganism (challenged by Lüling (in 1974) and Hawting (in 1999)); that Mecca was a vibrant centre of international trade (Crone (1987)); that the Qur'an text was a fixed textual canon from an early date, and even that it emerged in Arabia (Wansbrough (1977)); that anything recognisable as 'Islam' had crystallised during the time of the Prophet (Cook and Crone (1977)); that there occurred any military campaigns corresponding to the 'Islamic conquests' in the three decades after the death of the Prophet in 632 (Sharon (1988); Koren and Nevo (1991, 2003)); or that the earliest community of Believers was confessionally distinct from Christians, Jews and other monotheists (Donner (2002 3)). In general, there is a need to incorporate more fully a vision of early Islamic history as an organic continuation of trends in the history of the Late Antique Near East,⁵⁰ such as that articulated by Peter Brown's *The world of Late Antiquity* (1971) or Garth Fowden's *Empire to commonwealth* (1993). Such a perspective does not deny the importance of the Arabian context, but emphasises more fully the significance of Hellenistic Roman and Sasanian Iranian traditions in weaving the fabric of early Islamic history. These revisionist positions are still being vigorously debated, and the degree to which they will temper the vision of Islam's beginnings inherited from the Islamic origins narrative remains to be seen.

Secularising perspective

Another shortcoming of many Western studies of early Islamic history, particularly during the first two thirds of the twentieth century, stemmed from the prevalence of a secular mentality among Western scholars. This

50 Cf. the remarks of Wilfred Cantwell Smith, 'The historical development in Islam of the concept of Islam as an historical development', in Lewis and Holt (eds.), *Historians of the Middle East*, pp. 484–502.

appears to have led many of them to discount the possibility that religious motivations may have been central to the spread of the Believers' movement: it was sometimes argued, in reductionist fashion, that the expansion was 'really' driven by economic interests, or a desire for social reform, or was a mere by-product of a process of state formation.⁵¹ The fact that secular minded historians do not themselves subscribe to the faith claims of Islam, however, should not cause them to dismiss the efficacy of religious belief as a motivating factor in human societies. It seems more honest to acknowledge frankly the possibility that the early Believers' rapid expansion may indeed have been a consequence of religious inspiration and zeal for the faith. The fact that the early conquerors do not seem to have been particularly concerned with 'converting' the conquered populations to 'Islam' sometimes offered as evidence against seeing the expansion process as fundamentally a religious movement is hardly convincing; the Believers may have been concerned not to 'convert' individuals to their faith, but merely to sweep away what they viewed as the impious older regimes and replace them with a righteous public order, one that adhered more closely to what they understood as God's revealed law. In any case, the possibility that the early Believers' movement was not confessionally conceived – that is, that pious Jews and Christians may have formed an integral part of it – suggests that the whole question of 'conversion' is, for this early period, misleading and inappropriate, a retrojection of later conditions of confessional distinctness back into the origins period.

The dynamism ascribed to the early Believers during their rapid expansion from Arabia into Syria, Iraq, Egypt and Iran might be well explained by another kind of religious motivation, namely that the movement may have been inspired by apocalyptic speculations. Conviction that the Last Judgement was imminent is exactly the kind of idea that is sufficient to cause people to drop their normal way of life and join a cause in the interest of their own presumed salvation at the End Time. The idea that Muḥammad and his followers may have been inspired by apocalyptic concerns, raised early in the twentieth century by Paul Casanova,⁵² was long given a cool reception by most Western scholars, and is staunchly opposed by most devout Muslims. In recent years, however, the idea has

51 Among these are works by Grimme, Winkler, Caetani, Lammens, Becker, Hitti, von Grunebaum, Watt, Donner and Crone. See the discussion in Fred M. Donner, 'Orientalists and the rise of Islam', in Sami A. Khasawneh (ed.), *Conference on Orientalism: Dialogue of Cultures*, 22–24 October 2002 (Amman, 2004), pp. 75–8.

52 Casanova, *Mahomet et la fin du monde*.

again gained some favour, particularly because evidence for apocalyptic concerns in the later seventh and eighth centuries CE has become more abundant,⁵³ so a final verdict on the question of apocalypticism as part of the original impetus of Islam remains for the future.

Nationalist conceptualisations

Yet another problem of perception that afflicts much modern scholarship on early Islam (in this case including both Western scholarship and that written in Islamic countries) is the projection of recent and modern nationalist identities into the distant past. Throughout the nineteenth and early twentieth centuries nationalism (and its foundations in racism) was the regnant ideology in Western historical studies, and was subsequently adopted by most non Western societies, especially during the age of Western colonial domination. Nationalism, a manifestation of the Romantic reaction against Enlightenment concepts of rationalism, was one form of that philosophy that saw history as a kind of mysterious force moving towards certain ends through the agency of large collectivities such as nations or classes.⁵⁴ Nationalist ideology posited that human kind was 'naturally' divided into races or nations (such as 'Arabs', 'Turks', 'Jews' (as a national, rather than a religious, identity), 'Armenians' etc.), each of which exhibited a distinctive pattern of physical, mental and emotional or psychological characteristics; and much scholarship prior to the Second World War analysed history, including early Islamic history, as the product of the interaction (sometimes unconscious) of these supposed 'natural' national groups. So, for example, the 'Abbasid overthrow of the Umayyad regime in 750 was interpreted as a 'Persian national uprising' against 'Arab' domination,⁵⁵ and countless books and articles referred to the first expansion of the Believers following Muḥammad's death in 632 as the 'Arab conquest', implying (if not arguing outright) that the movement was at heart an expression of a kind of national solidarity among the

53 E.g. David Cook, *Studies in Muslim apocalyptic* (Princeton, 2002); M. J. Kister, "'A booth like the booth of Moses...': A study of an early *ḥadīth*", *BSOAS*, 25 (1962); Wilferd Madelung, 'Apocalyptic prophecies in Hims in the Umayyad age', *JSS*, 31 (1986); Michael Cook, 'An early Islamic apocalyptic chronicle', *JNES*, 52 (1993); F. M. Donner, 'Piety and eschatology in early Kharijite poetry', in Ibrahim As Sa'afin (ed.), *Fī miḥrab al ma'rifa: Festschrift for Ihsan 'Abbas* (Beirut, 1997).

54 Hourani, *Islam in European thought*, p. 44.

55 E.g. Theodor Nöldeke, *Orientalische Skizzen* (Berlin, 1892), p. 88: 'The victory of the Abbasids brought an end to the purely Arab, and therewith the purely Semitic, state; we see here for the most part a reaction of the Persian element and the restoration of the old Asiatic empires.'

‘Arabs’, the realisation of their ‘natural’ yearning for unity.⁵⁶ It is, however, highly questionable whether the peoples of Arabia in the seventh century, or those peoples who spoke some form of language that we today would categorise as Arabic, conceived of themselves as constituting a single ‘people’.⁵⁷ Their operative identities were, rather, based on tribal and lineage categories, or on local (geographical) or religious conceptions. They would have thought of themselves as Tamīmīs or Qurashīs or Hashimites, as Meccans or Yathribīs, or as Monophysite Christians or Jews or worshippers of Hubal; any ethnic or ‘national’ identity they felt would have been decidedly secondary and probably very weak.⁵⁸ The imposition of essentially modern national identities such as ‘Arabs’ onto a remote past when they were not yet operative thus distorts, sometimes grotesquely, the interpretation of what happened; at the very least it tends to mask other factors that may have been more important. So, for example, referring to the expansion of the early Believers as the ‘Arab conquest’ – a term that is still widely used – obscures its nature as a religious movement and converts it instead into an expression of a presumed ‘national’ solidarity. The damage caused by use of inappropriate ‘national’ conceptualisations has been increased by the translation of many of these Western works into Middle Eastern languages; this has reinforced these conceptualisations among Middle Eastern scholars, many of whom already embrace strongly nationalist ideas. ‘National’ conceptualisations remain deeply ingrained in much modern writing on early Islamic history, and eradicating them remains a challenge for the coming generations of historians.

Fragmentation

A final challenge that faces historians of early Islam is a consequence of the rapidly increasing pace of scholarship since the 1960s. As recently as the 1970s it was still possible for the determined fledgling scholar to read, within a few years, the majority of the important secondary literature in Western languages on medieval Islamic history from the rise of Islam up to the Mamluks. The avalanche of new publications since that time means that

56 See J. Fück, ‘Islam as an historical problem in European historiography since 1800’, in Lewis and Holt (eds.), *Historians of the Middle East*. Even the great Goldziher could not completely escape the influence of such ideas: in his *Muhammedanische Studien* he frequently speaks of the ‘national Arab character’ of the Umayyad regime, etc.

57 See Jan Retsö, *The Arabs in Antiquity* (London and New York, 2003), esp. pp. 108–10.

58 See Saleh Said Agha and Tarif Khalidi, ‘Poetry and identity in the Umayyad age’, *al-Abhath*, 50.1 (2002–3); F. M. Donner, ‘Modern nationalism and medieval Islamic history’, *al-Usur al Wusta*, 13 (2001).

scholars now can only really keep up with developments in one or two corners of what used to be a more unified field of study. As noted earlier, whole new specialisations have emerged, the mastering of which is today virtually a full time undertaking: Qur'anic studies, *ḥadīth* studies, Islamic law, Islamic archaeology, the history of Islamic Spain and many others have developed a momentum of their own, and many long recognised fields, such as Islamic art history and numismatics, have developed in depth and sophistication of method to the point that one cannot hope to control them without devoting one's full attention to them. The rich rewards brought by our advancing knowledge of early Islamic history are thus sometimes won at the cost of making it more difficult to encompass a broader view of things. This fragmentation caused by increased specialisation is, to be sure, a problem faced by all areas of knowledge, but historians of the early Islamic world will have to develop their own ways of handling the particular challenges it poses for them.

Numismatics

STEFAN HEIDEMANN

Islamic coins as a historical source

At least since Leopold von Ranke (1795–1886), the historical critical approach to any study of history has demanded parallel independent proof in order to establish firmly a given historical fact. Historians of Islamic societies have almost no primary documents or archives for the period prior to the fifteenth century. In contrast to the scarce primary documents, the secondary sources literary and historical accounts, especially from the ninth to the tenth centuries are abundant.

This gross imbalance between the lack of primary documents, produced in the course of the events, and chronicles written much later has led scholars to depend greatly upon medieval but secondary authors. Since they typically wrote from the point of view of a city, a ruling house, a ruler or a religious community or school of law their accounts are necessarily biased. Without independent documents or material evidence the modern historian is often unable to corroborate or to refute these literary accounts; sometimes even important lacunae in our knowledge may remain unnoticed. After being widely neglected following the First World War the study and use of Islamic numismatic documents have again become a prospering academic subject, particularly in the 1990s.¹

Islamic coins of the classical period can be characterised above all as bearers of texts of up to 150 words (fig. 16.35). The texts on coins struck during the first six and a half centuries of Islam often mention up to five names, providing the entire hierarchy of power from the local governor up to the caliph at the time and location of minting. They usually name the mint town, sometimes even the urban quarter, usually the year, and sometimes even the month and the day. Religious legends provide hints of the political orientation of the ruler

¹ See the chapter bibliography below.

who commissioned the coin. The inclusion of the name onto the coin protocol (*sikka*) and in the Friday prayer (*khuṭba*) served in their time as proof of who the actual ruler was. Both had a similar political value. The reference to the hierarchy of rulers in the Friday prayer was purely verbal and therefore transient, whereas on coins the protocol can be found permanently stored on a metal object that was frequently reproduced, like a 'bulletin of state'. As what are normally precisely datable archaeological artefacts, they open a further dimension of information.²

Coins as source of economic and legal history

Money as a means of coordinating human decisions and economic exchange is a complex social invention. It must always adjust to the prevailing economic, political and juridical conditions. Seen from another angle, its design and evolution reveal much about the societies creating it. In the pre modern world the supply of coins – the physical instruments for the exchange of goods and services – were usually scarce. However, in order to function as an 'absolute price' (*thaman muṭlaq*) or 'equivalent' (*thaman*) – that is, as money at least one certain type of coin has to be available in sufficient quantities. Non physical forms of money, bills of exchange (*hawala*) and cheques (*suftaja*), were developed in the Middle East, but they were used only among small communities bound by ties of trust and kinship, such as, for example, in networks of long distance merchants in major trade cities.

The value of coins was determined by market forces. It always exceeded the value of the same amount of metal as a mere commodity, although it was bound to the metal content, the difference being smaller for high value coins than for petty coinage. If a coin type was generally accepted and was in sufficient supply, it was maintained over a long period and remained stable in design and usually in metallic content.

Two separate currencies always existed side by side, serving distinct needs within different social classes: high value money, usually gold or pure silver coins; and petty coinage, usually debased silver, billon or copper coins. Gold coins, and, to a certain extent, silver coins, constituted the principal currency for wholesale and long distance merchants (*tujjar* and *jallabun*) as well as for

2 S. Heidemann, 'Settlement patterns, economic development and archaeological coin finds in Bilad aš Šam: The case of the Diyar Muḍar', in K. Bartl and A. Moaz (eds.), *Residences, castles, settlements: Transformation processes from Late Antiquity to early Islam in Bilad al Sham. Proceedings of the International Conference held at Damascus, 5-9 November 2006*, *Orient Archäologie* 24 (Rahden, 2009).

fiscal administration and state expenditure. It was also the money of high ranking state officials and military, who needed it to store wealth, to transfer it conveniently over long distances and to make payments of large sums. High value coins could be traded between regions, and stood in competition with other similar coins. Geographically well defined borders of currency zones hardly existed. If they did exist, then it was for economic reasons and fiscal measures.

The second currency type fulfilled the needs for daily purchases. It was the money of small dealers, artisans, workers (*suqa* and *ba'a*) in the urban market (*suq*) and, of course, of the rest of the urban population. The urban population was dependent for their livelihood on income that usually came from their activities within the boundaries of a city or town, and thus on purchases within the urban markets. The majority of the people in pre modern societies – the rural population, peasants and nomads – relied mainly on subsistence. Only certain extra requirements and excess produce were bought and sold in the *suq*.

The ratio in price between high value and petty coinage was usually determined by supply and demand. The demand for small coins far exceeded their supply, as the central authorities usually neglected to provide a sufficient supply. This allowed a much higher profit for those who could provide these means of exchange – in other words, the local fiscal and political authorities or private money changers. Petty coins could also be imported from other regions at a profit.

During the third/ninth century the legal prescriptions for money became fully developed, the most important among them being the theory of value and the prohibition of *riba* (illegitimate profit according to the *shari'a*). Islamic law forbids two equal amounts of precious metal from being valued differently in one single transaction. This is the core of the prohibition of *riba*. Islamic legal theory determined the value of money to be identical with the intrinsic value of the bullion. Only silver and gold were the commodities that could be legally used for any transaction as 'absolute price'. Muslim jurists of the fifth/eleventh century, however, were aware of the contradiction between observed empirical reality and the normative imperative of the revealed law. They recognised that the fluctuating value of coins was based on the interest of the public in it – that is, on the market forces. In order to facilitate a monetary economy in the period of regional currencies with different finenesses and weights the jurists invented several legal arguments to ensure that market exchanges were in accord with Islamic law.

The majority of the jurists did not regard copper coins – the generic term is *fals/fulus* – as money or ‘absolute price/equivalent’; if they regarded them at all, then they did so only as a substitute for money. Copper coins could serve in some, but not all, legal transactions, as did gold and silver.³

The development of the representation of a new universal religion and its empire: Zubayrid and Kharijite challenge and Umayyad reform

Coins and their imagery are our only contemporary continuous primary source for the genesis of the self representation of the new religion and its empire in the seventh century. Our understanding on these early coins has grown quickly since the 1990s.⁴

The Islamic armies swiftly conquered three major zones of monetary circulation, and took over much of their fiscal organisation: the former Byzantine territories in the centre; the Sasanian empire in the east; and Germanic North Africa and Spain. In the Byzantine territories the workhorse of the fiscal cycle, of taxation and state expenditure, was the gold *solidus* or *nomisma* of about 4.55 grams (fig. 16.1). The money used for the daily

3 C. M. Cipolla, *Money, prices and civilization in the Mediterranean world* (Princeton, 1956), pp. 27–37; R. Brunschvig, ‘Conceptions monétaires chez les juristes musulmanes (VIIIe–XIIIe siècles)’, *Arabica*, 14 (1967); Avram L. Udovitch, *Partnership and profit in medieval Islam* (Princeton, 1970), pp. 55–6; S. Heidemann, *Die Renaissance der Städte in Nordsyrien und Nordmesopotamien: Städtische Entwicklung und wirtschaftliche Bedingungen in ar-Raqqā und Ḥarran von der Zeit der beduinischen Vorherrschaft bis zu den Seldschuken*, *Islamic History and Civilization, Studies and Texts* 40 (Leiden, 2002), pp. 356–61, 367.

4 M. Bates, ‘History, geography and numismatics in the first century of Islamic coinage’, *Schweizerische Numismatische Rundschau*, 65 (1986); S. Heidemann, ‘The merger of two currency zones in early Islam: The Byzantine and Sasanian impact on the circulation in former Byzantine Syria and northern Mesopotamia’, *Iran*, 36 (1998); L. Treadwell, *The chronology of the pre reform copper coinage of early Islamic Syria*, *Supplement to Oriental Numismatic Society Newsletter* 162 (London, 2000); S. Album and T. Goodwin, *The pre reform coinage of the early Islamic Period*, *Sylloge of Islamic Coins in the Ashmolean* 1 (London, 2002); A. Oddy, ‘Whither Arab Byzantine numismatics? A review of fifty years’ research’, *Byzantine and Modern Greek Studies*, 28 (2004); T. Goodwin, *Arab Byzantine coinage*, *Study in the Khalili Collection* 4 (London, 2005); C. Foss, *Arab Byzantine coins: An introduction, with a catalogue of the Dumbarton Oaks Collection* (Cambridge, MA, 2009). For the economic and political history see esp. J. Johns, ‘Archaeology and the history of early Islam: The first seventy years’, *JESHO*, 46 (2003); M. G. Morony, ‘Economic boundaries? Late Antiquity and early Islam’, *JESHO*, 47 (2004). For the iconographic development see S. Heidemann, ‘The development of the representation of the early Islamic empire and its religion on coin imagery’, in Angelika Neuwirth, Nicolai Sinai and Michael Marx (eds.), *The Qurʾān in context: Historical and literary investigations into the Qurʾānic milieu* (Leiden, forthcoming).

purchases, the copper *folles* (pl. *folles*) (fig. 16.2), was sold by the treasury as well. In 629/30 Heraclius (r. 610–41) had concentrated all minting in the imperial capital, Constantinople. During the Sasanian occupation between 606–7 and 628 irregular mints were established in Syria, supplementing the circulating stock of copper coins.⁵ In the Sasanian empire the money of the fiscal cycle was the uniform silver *drahm* of about 4.2 grams, which was struck in the days of Khusrau II (r. 590/591–628) in about thirty-four mints (fig. 16.3). Almost nothing is known about late Sasanian copper coinage. Tiny coppers, which are now rare, probably circulated in the major urban centres. Their issues became especially rich in design under Arab rule, and constitute an excellent source for art history.⁶ In Spain and North Africa monetary economy had receded since the Roman empire, since the fifth century. The third of the *solidus*, the *tremisses* (c. 1.5 g), was the main and only coin struck in Spain and the rest of western Europe (cf. fig. 16.4). In North Africa Carthage was the only mint to continue striking petty coinage.

In the first decades after the battle of Yarmuk in 636 CE and the establishment of the Taurus border zone, Byzantine coppers remained in circulation, and were with few interruptions almost continuously supplemented by new imports from Byzantium. In contrast, the influx of *nomismata* dropped considerably. The obverse of the *folles* shows the emperor here (fig. 16.2) the standing figure of Constans II (r. 641–68) wearing a crown with cross, holding a globus cruciger in one hand and a long cross in the other. On the reverse the *m* indicates the Greek numeral 40, the mark of value of the Byzantine standard copper coin. According to archaeological finds, an end to the importing of these coins can be discerned in the late 650s.

The importing obviously disregarded political boundaries. The selling of coppers was profitable for the Byzantine treasury. Early Islam, outside the Hijaz, was the elite religion of a tribally organised military. During the period of conquest the Islamic religion possessed only a rudimentary theology, which was probably even more basic among military units. Contemporary Byzantium might have perceived the conquest as a menacing rebellion and if they had noticed the religious dimension at all – an Arab heresy of Judaeo-Christian origin. This perception would not necessarily have challenged the universal claim of the all-embracing Roman empire, since the idea of Rome

5 H. Pottier, *Le monnayage de la Syrie sous l'occupation perse (610–630)*, Cahiers Ernest Babelon 9 (Paris, 2004).

6 R. Gyselen, *Arab Sasanian copper coinage*, Österreichische Akademie der Wissenschaften, Philosophisch-Historische Klasse, Denkschriften 284, Veröffentlichungen der numismatischen Kommission 34 (Vienna, 2000).

was neutral to religion. In these early days the Umayyads in Damascus did not develop an imperial state ideology of their own. As leaders of the victorious Arab armies they were probably content with their de facto rule and modest fiscal exploitation. Numerous attempts to conquer Constantinople might be interpreted as the inheritance by the rising Islamic Arab power of the universal Roman claim.

The minting of the first copper coins in the former Byzantine territories commenced after 636 CE. These imitations supplemented the circulating stock and followed even weight reductions in Byzantium.⁷ We do not know who the regulating authorities were, but it is possible that military authorities in the garrisons, local authorities in the cities, money changers or merchants were involved in their production. Beginning in the 660s with the Sufyanid reforms, some sort of coordination, if not central policy, can be assumed. In a study, Luke Treadwell focused his attention on the developments in the mints of the provincial capitals Damascus, Tiberias and Ḥimṣ. Although these 'imperial image' coppers still depict Byzantine emperors with cross insignias, they now have carefully prepared flans and carefully engraved dies. The mints were named on the coins, in Greek, Arabic or both. Validating expressions were included, such as KAAON or *ṭayyib* (both meaning 'good'), or *ja'iz* ('current') (figs. 16.5, 16.6). No attempt to represent the new state or religion was made; petty coinage first of all served as means of exchange. The Sufyanid government set up a 'very loose tributary state'.⁸

As a centralised state, the Sasanian empire fell while at its apogee – at least as far as its administration, its army, which was based on cash payments, and its monetary economy were concerned. Silver coins were the backbone of the fiscal cycle, and were available in enormous quantities. The typical late Sasanian *drahm* (fig. 16.3) of about 4.2 grams shows on the obverse the portrait of the *shahanshah* – either Khusrau II (r. 590–628) or Yazdegerd III (r. 632–51) with an enormous winged crown as sign of their royalty. On the reverse, the fire altar served as the central symbol of the dualistic Iranian religion, Zoroastrianism. Priest attendants stand on either side, and beside them are abbreviations indicating the mint and the regnal year of the ruler. Dies were probably cut in a central workshop and then distributed to the provincial mints, a recurrent phenomenon in the later Islamic coinage. In his twentieth regnal year, 651, the last *shahanshah* Yazdegerd III was assassinated in Marw,

7 H. Pottier, I. Schulze and W. Schulze, 'Pseudo Byzantine coinage in Syria under Arab rule (638 c.670): Classification and dating', *Revue numismatique belge*, 154 (2008).

8 C. F. Robinson, *Empire and elites after the Muslim conquest: The transformation of northern Mesopotamia*, Cambridge Studies in Islamic Civilization (Cambridge, 2000), p. 166.

the last eastern remnant of his empire. The coins in the conquered territories are almost indistinguishable from the coins under the authority of Yazdegerd III, except that mints lay outside his shrinking realm. For some time after 31/651 coins continued to be struck with the names and portraits of Khusrau II or Yazdegerd III and with the fire altar. Frequently but not always additional Arabic validating marks were set on the margin, such as *bism Allah* ('in the name of God') or *jayyid* ('good'), as on Syrian copper coins. The resulting picture for the early decades seems to correspond to a situation in which the Sasanian administration remained operational, but broken down to a provincial level and now responsible to Arab governors.⁹ Starting in about 40/661, with Mu'awiya's regime, the names of Khusrau II and Yazdegerd III were replaced, first occasionally and then regularly with the names of the provincial governors in Pahlavi, placed in front of the traditional portrait of the *shahanshah*. In many mints, but not in all, the dating shifted to the *hijra* year (fig. 16.7)

The Zubayrid and Kharijite challenges between 681 and 697 – the period of the second *fitna* – mark the watershed towards the initial inclusion of Islamic symbols in the coin imagery and finally to a clear iconographic expression of religion and state. 'Abd Allah ibn al Zubayr was a close, venerated and merited member of the family of the Prophet. He emphasised the religious political character of his caliphate and demanded a state in accordance with the principles of Islam, whatever this meant at that time. After Mu'awiya's death in 60/680 he strongly opposed the Sufyanid regime, and was supported in many parts of the empire. As early as 62/681f. his name was put on coins of Kirman. The coins show in 64/684 that he assumed the caliphal title '*amīr* of the believers' (fig. 16.8). In 67/687 his brother Muṣ'ab secured Baṣra, Iraq and the territories to the east as far as Sistan. The Umayyads seemed to have lost their cause.

Between 66/685 and 69/688f., in the city of Bishapur, *Muḥammad rasul Allah* (Muḥammad is the messenger of God) was placed for the first time on coinage, on that of the Zubayrid governor of the east. The coin image itself remained as before, the portrait of the *shahanshah* and the fire altar. The Zubayrids thus propagated the new Islamic imperial rule with reference to the Prophet and putative founder of the state. Probably in 70/689f. the Zubayrid authorities created a coin with the name of Muḥammad in front of the portrait of the *shahanshah* and in the margin a reference to Muḥammad, for the first time including the profession of faith and the unity of God, the *shahada*, in

9 S. Sears, 'A monetary history of Iraq and Iran, ca. CE 500 to 750', Ph.D. thesis, University of Chicago (1997).

Arabic: *la ilaha illa Allah waḥdahu*.¹⁰ In 72/69f. the Zubayrid governor of the province of Sīstan, in south eastern Iran, replaced the Zoroastrian fire altar with the profession of the new faith (*shahada*). Iraj Mochiri read the Pahlavi script thus: 'Seventy two / One God but He / another God does not exist / Muḥammad [is] the messenger of God / SK [mint abbreviation for Sīstan]' (fig. 16.9).¹¹ Clearly dated, the *shahada* appears here on a contemporary document in Pahlavi script and in the Persian language. Together with the Prophetic mission of Muḥammad, it is the first symbol of the Islamic religion and its empire known. The Zubayrid governor had targeted the ideological religious deficiencies of the Umayyad regime. In the same year the Marwanids re conquered Iraq, and in 73/692 the caliphate of 'Abd Allah ibn al Zubayr was brutally suppressed in Mecca.

The Marwanid activities that followed can be seen as aimed at integrating the defeated moderate Zubayrid movement in ideological terms, as well as a forceful reaction to the ongoing Kharijite menace. At this point in history at the latest, the idea was created of an Islamic universal empire in its own ideological right. In 72/69f. 'Abd al Malik built the present Dome of the Rock and the al Aqṣa Mosque in Jerusalem as probably the first architectural manifestations of the new Islamic empire. The choice of Jerusalem placed the imperial religion in the tradition of Judaism and Christianity and in the centre of the medieval world.

Between 72/69f. and 77/696f. the Marwanid government experimented with new symbols as representations of religion and imperial power, not all of which are well understood today. Most famous is the image of the standing caliph on gold, silver and copper coins in Syria and northern Mesopotamia (figs. 16.10, 16.11). On the Syrian silver *drahms* and on some copper coins 'Abd al Malik asserted his claim to being *khalīfat Allah* (the deputy of God), to enhance his politico religious leadership (fig. 16.11).¹² However, the recurrent theme of all

10 L. Ilisch, 'The Muhammad drachms and their relation to Umayyad Syria and northern Mesopotamia', *Supplement of the Journal of the Oriental Numismatic Society*, 193 (Autumn 2007).

11 M. I. Mochiri, 'A Pahlavi forerunner of the Umayyad reformed coinage', *JRAS*, (1981). Further discussion in S. Sears, 'A hybrid imitation of early Muslim coinage struck in Sijistan by Abu Bardha'a', *American Journal of Numismatics*, 1 (1989); and L. Ilisch, Review of *American Journal of Numismatics*, 1, *Der Islam*, 69 (1992).

12 For the iconographic interpretation see N. Jamil, 'Caliph and Qutb: Poetry as a source for interpreting the transformation of the Byzantine cross on steps on Umayyad coinage', in Jeremy Johns (ed.), *Bayt al Maqdis: Jerusalem and early Islam*, Oxford Studies in Islamic Art 9, part 2 (Oxford, 1999); L. Treadwell, 'The "orans" drachms of Bishr ibn Marwan and the figural coinage of the early Marwanid period', in Johns (ed.), *Bayt al Maqdis: Jerusalem and early Islam*; L. Treadwell, '"Mihrab and 'Anaza" or "sacrum and spear"? A reconsideration of an early Marwanid silver drachm', *Muqarnas*, 30 (2005).

experiments in coin design was the inclusion of the name of the founder of the religion and the putative founder of the empire, *Muḥammad rasul Allah*, some times together with the *shahada*. This was the symbol of Islam comparable to cross, fire altar and menorah. The Zubayrid idea was firmly adopted.

Between 77/696 and 79/699, just after the final defeat of the Kharijite caliph Qaṭarī ibn al Fuja'a, the definitive symbolic representation of Islam and the Islamic empire on coinage was launched. In 77/696 new *dīnars* were produced (fig. 16.12) probably in Damascus bearing the new religious symbols of the Islamic empire: the *shahada*, encircled by the *risala*, the Prophetic mission of Muḥammad (Q 9:33), and on the opposite side the word of God, the *surat ikhlāṣ* (Q 112) and the date of minting. Late in 78/697f. al Ḥajjaj ibn Yusuf, the governor of the east, ordered the reform of the *dirhams* in his realm, similar to the new *dīnars*, but stating the mint name also, as on Sasanian *drahms*. The reform started in Kufa, Azerbaijan, Armenia, Jāy and Shaqq al Taymara in al Jibal, as far as we can currently tell. The following year saw the application of the new design in more than forty mints (fig. 16.13).¹³

Precious metal coins remained anonymous until the time of the 'Abbasid al Maṣṣūr (r. 136 58/754 75). The image and the name of the ruler were taken out of any representation of the empire. This constituted a historically unprecedented breach with a tradition of Hellenistic coin imagery going back about a millennium. The epigraphic image of the profession of faith and the words of God can be read as 'the sovereignty belongs to God', almost a concession to Kharijite thinking. Anonymity did not mean modesty, because the new Islamic universal emperor claimed nothing less than being *khalīfat Allah*: the deputy of God.

Umayyad and early 'Abbasid coinage

The new currency system of the empire consisted of an almost pure gold *dīnar* regulated to the *mithqal* weight (4.2 g), an almost pure silver *dirham* regulated to a *dirham* weight (2.8–2.9 g) and unregulated copper coins which had a token character. This became the standard model for currency in the emerging Islamic law. Although the Umayyad empire was far from a centralised state, the coinage does show a high degree of organisation and centralisation, owing

¹³ M. Klat, *Catalogue of the post reform dirhams: The Umayyad dynasty* (London, 2002); L. Ilisch in *Dr. Busso Peus Nachf. Münzhandlung Frankfurt, Katalog 369* (31 October 2001), no. 1467, pp. 80–1.

to its Sasanian heritage.¹⁴ It can be supposed that the gold coinage, which mentions no mint, would have been struck almost exclusively at the caliph's court, first in Damascus and later in Baghdad. Mints for *thulths* (*tremisses*), *niṣf* (*semmissis*) and some *ḍīnars* were set up in al Andalus and Ifrīqiya (Qayrawan) (fig. 16.4). With 'Abd al Malik's reforms all old Byzantine gold coinage vanished immediately from circulation in Egypt, Syria and northern Mesopotamia, indicating a tight fiscal regime on the gold circulation in the former Byzantine territories. During the reign of Harun al Rashīd (r. 170 93/786 809) the production of gold *ḍīnars* in more than one mint became apparent, as indicated by the inclusion of the names of provincial governors and specific mint marks (fig. 16.14).

The organisation of silver coinage serving the fiscal authorities in the former Sasanian east was different. The new design soon spread to all mints in the east and the capital Damascus; in 97/715f. it was adopted in Ifrīqiya, and finally, in 100/718f., in al Andalus. It was struck in about a hundred mints. After the foundation of Wasīṭ in Iraq and the move of al Ḥajjaj to his new capital in 83/703f., Wasīṭ became the paramount silver mint of the empire until the 'Abbasid *coup d'état*. For a brief time between 84/703f. and 89/707f. Wasīṭ was the only *dirham* mint except for Damascus; all others were closed down.¹⁵

Between 132/749f. and 147/765f. Baṣra and Kufa became the principal silver mints of the empire. This paramount role then shifted in 146 7/765 7 to Maḍīnat al Salam and to Rayy/al Muḥammadiyya, the first after the foundation of the palace city in Baghdad the mint was opened in 146/765f. and the latter after the establishment of the heir apparent in Rayy in 145/762f.¹⁶ The 'Abbasid takeover had little impact at first on the coin design; except that the *surat al ikhlāṣ*, which was associated with the Umayyads, was replaced by *Muḥammad rasul Allah*, stressing the connection of the 'Abbasids to the family of the Prophet (fig. 16.15).

In Rayy in 145/762f., the year of the menacing 'Alīd revolt and its repression, the heir apparent, Muḥammad (r. 158 69/775 86), began to insert the newly adopted honorific title (*laqab*) al Mahdī and his name into the *dirham* coin protocol, abandoning the anonymity of precious metal coinage (fig. 16.16). Later he continued this as caliph.¹⁷ From now on, until the coinage reform of

14 A. S. DeShazo and M. L. Bates, 'The Umayyad governors of al 'Iraq and the changing annulet patterns on their dirhams', *Numismatic Chronicle*, 14 (1974); M. Bates, 'The dirham mint of the northern provinces of the Umayyad caliphate', *Armenian Numismatic Journal*, 15 (1989).

15 R. Darley Doran, 'Wasīṭ, The mint', *Elz*, vol. XI, pp. 169 71.

16 T. S. Noonan, 'Early 'Abbasid mint output', *JESHO*, 29 (1986).

17 M. L. Bates, 'Khurasanī revolutionaries and al Mahdī's title', in F. Daftary and J. W. Meri (eds.), *Culture and memory in medieval Islam: Essays in honour of Wilferd Madelung* (London and New York, 2003).

al Ma'mun (r. 194–218/810–33), various names appear on the coinage – the caliph, the heir apparent, viziers, governors, officials – sometimes as many as four names, giving a kaleidoscope of the administrative structure of the empire, which is not yet fully understood (figs. 16.17, 16.22).¹⁸

The circulation of silver coins was far from uniform, unlike the new gold *ḍīnars*. Umayyad and Sasanian *dirhams* still circulated until the early fourth/tenth century. Some regions maintained, along with the imperial coinage, a local one, usually debased silver of Sasanian appearance, notably in Ṭabaristan (an exception as they are of pure silver) (fig. 16.18), Sīstan and the oasis of Bukhara (fig. 16.19).¹⁹

The copper coinage was of almost no concern to the central government; it was left for the regional or local Umayyad and 'Abbasid authorities to supply, and for some supplemental coinage even private commercial enterprises can be assumed. According to Islamic law copper coins did not constitute money that was legally valid in all transactions. Thus a huge variety of copper coins with many names of local *amūrs* and officials existed. Images were occasionally applied too. Thus the copper coins are an excellent source for local administration, history and art history (fig. 16.20).²⁰ This decentralised production resulted in temporary and regional shortages in petty coinage, frequently bridged by cast imitations (fig. 16.21) and importation from other regions. In the period of Harun al Rashīd the growing demand in northern Mesopotamia exceeded by far the regular production of copper coinage. Coins were thus cast until their model was unrecognisable, and plain copper sheets were cut into mainly octagonal pieces.²¹

18 N. D. Nicol, 'Early 'Abbasid administration in the central and eastern provinces, 132–218 AH/750–833 AD', Ph.D. thesis, University of Washington (1979); N. Lowick and E. Savage, *Early 'Abbasid coinage: A type catalogue 132–218 H/AD 750–833. A posthumous work by Nicholas Lowick*, ed. Elisabeth Savage, distributed MS (London, 1996).

19 For Ṭabaristan: H. M. Malek, *The Dabuyid Ispahbads and early 'Abbasid governors of Ṭabaristan: History and numismatics*, Royal Numismatic Society Special Publication 39 (London, 2004). For Sīstan: S. Sears, 'The Sasanian style drachms of Sistan', *Yarmouk Numismatics*, 11 (1999).

20 H. Bone, 'The administration of Umayyad Syria: The evidence of the copper coins', Ph.D. thesis, Princeton University (2000); Lowick and Savage, *Early 'Abbasid coinage*; S. Shamma, *A catalogue of 'Abbasid copper coins: Thabat al-fulus al-'abbasiyya* (London, 1998). Single studies: see L. Ilisch, 'Die Kupferprägung Nordmesopotamiens unter Harun ar Rashīd und seinen Söhnen (786–842 AD)', in International Association of Professional Numismatists (eds.), *Numismatics: Witness to history*, IAPN publication 8 (Basle, 1986); S. Heidemann, 'Die frühe Münzprägung von ar Raqqa/ar Rafīqa als Dokumente zur Geschichte der Stadt', in S. Heidemann and A. Becker (eds.), *Raqqa*, vol. II: *Die islamische Stadt* (Mainz, 2003).

21 S. Heidemann, 'Der Kleingeldumlauf in der Ghazīra in früh-'abbasidischer Zeit und die Münzmissionen aus al Kufa', in Heidemann and Becker (eds.), *Die islamische Stadt*.

a



b



Plate 16.1 (a, b, obverse and reverse)
Byzantium, Heraclius and Heraclius Constantine, *nomisma*, Constantinople,
(ca. 616–25 AD)

a



b



Plate 16.2 (a, b, obverse and reverse)
Byzantium, Constans II, *follis*, Constantinople, regnal year 3 (643–4 CE).

a



b



Plate 16.3 (a, b, obverse and reverse)
Sasanians, Khusrau II, *drachm*, 'HM (Hamadhan), regnal year 29.

a



b



Plate 16.4 (a, b, obverse and reverse)
Umayyads, *tremisses*/*thulth dinar*, Afrika (Qairawan).
Scale 1.5:1

a



b



Plate 16.5 (a, b, obverse and reverse)
Umayyads, *fals*, Emisis/Himş, [c. 50s/670s 74/692].

a



b



Plate 16.6 (a, b, obverse and reverse)
Umayyads, *fals*, Damaskos/Dimashq, [c. 50s/670 74/692].

a



b



Plate 16.7 (a, b, obverse and reverse)
Umayyads, 'Abd Allah ibn 'Amir ibn Kurayz, *drahm*,
(Darabjird), AH 43 (663 4 CE).

a



b



Plate 16.8 (a, b, obverse and reverse) Zubayrids, 'Abd Allah ibn al Zubayr, *drahm*, (Darabjird Jahrum), Yazdegerd era 60 (72/692).

a



b



Plate 16.9 (a, b, obverse and reverse) Zubayrids, 'Abd al 'Aziz ibn 'Abd Allah, *drahm*, (Sistan), year 72 AH (691–2 CE).

a



b



Plate 16.10 (a, b, obverse and reverse) Umayyads, *dinar*, [Damascus], year 77 AH (696 CE).

a



b



Plate 16.11 (a, b, obverse and reverse) Umayyads, *fals*, Manbij, [74–7/692–6].

a



b



Plate 16.12 (a, b, obverse and reverse)
Umayyads, *dinar*, [Damascus], year 93 AH (711–12 CE).

a



b



Plate 16.13 (a, b, obverse and reverse)
Umayyads, *dirham*, al Kufa, year 79 AH (698–9 CE).

a



b



Plate 16.14 (a, b, obverse and reverse)
‘Abbasids, *dinar*, [al Rafiqa], year 191 AH (806–7 CE).

a



b



Plate 16.15 (a, b, obverse and reverse)
‘Abbasids, *dirham*, al Kufa, year 132 AH (749–50 CE).

a



b



Plate 16.16 (a, b, obverse and reverse)
 'Abbasids, al Mahdī, *dirham*, al Rayy, year 146 AH (763–4 CE).

a



b



Plate 16.17 (a, b, obverse and reverse)
 'Abbasids, al Amin, *dirham*, Arminiya (Dabil), year 190 AH (805–6 CE).

a



b



Plate 16.18 (a, b, obverse and reverse)
 'Abbasids, 'Umar ibn al 'Ala', *dirham*, Ṭabaristan, 123
 post Yazdegerd era (158/774–5).

a



b



Plate 16.19 (a, b, obverse and reverse)
 ‘Abbasids, al Mahdī, *dirham*, [Bukhara], [158 69/775 85].

a



b



Plate 16.20 (a, b, obverse and reverse)
 ‘Abbasids, al Mu‘taṣim, *fals*, al Rafīqa, 226 AH (840 1 CE).

a



b



Plate 16.21 (a, b, obverse and reverse)
 ‘Abbasids, *fals*, (Syria), [c. 130 50/750 70], cast.

a



b



Plate 16.22 (a, b, obverse and reverse)
 ‘Abbasids, al Ma‘mun, *dirham*, Iṣfahan, year 204 AH (819 20 CE).

a



b



Plate 16.23 (a, b, obverse and reverse)
 'Abbasids, *dirham*, Madinat al Salam, year 208 AH (823–4 CE).

a



b



Plate 16.24 (a, b, obverse and reverse)
 'Abbasids, al Mu'tasim, *dirham*, Madinat al Salam, year 226 AH (840–1 CE).

a



b



Plate 16.25 (a, b, obverse and reverse)
 Šaffarids, Ya'qub ibn al Layth, *dirham*, Panjhir, 261 AH (874–5 CE).

a



b



Plate 16.26 (a, b, obverse and reverse)
 Dulafids, Aḥmad ibn 'Abd al 'Aziz, *dinar*, Mah al Başra, year 273 AH (886–7 CE).

a



b



Plate 16.27 (a, b, obverse and reverse)
 'Abbasids, al Muttaqi, *dirham*, Madīnat al Salam, year 329 AH (940 ± CE).

a



b



Plate 16.28 (a, b, obverse and reverse)
 Buyids, Qiwām al Dīn, *dirham*, Shiraz, year 400 AH (1009 ± CE).

a



b



Plate 16.29 (a, b, obverse and reverse)
 'Uqaylids, Janāḥ al Dawla, *dirham*, Naṣībīn, year 385 AH (995 ± CE).

a



b



Plate 16.30 (a, b, obverse and reverse)
 Sallarids, Jastan and Ibrāhīm, *dīnār*, Maragha, year 347 AH (958 ± CE).

a



b



Plate 16.31 (a, b, obverse and reverse)
Samanids, Isma'īl, *dirham*, al Shash, year 292 AH (904–5 CE).

a



b



Plate 16.32 (a, b, obverse and reverse)
Samanids, Naṣr, *fals*, Bukhara, year 305 AH (917–6 CE).

a



b



Plate 16.33 (a, b, obverse and reverse)
Ghaznavids, Maḥmūd, *dirham*, Ghazna, year 399 AH (1008–9 CE).

a



b



Plate 16.34 (a, b, obverse and reverse)
Saljuqs, Malikshah, *dinar*, Nishapur, year 484 AH (1091–2 CE).

a



b



Plate 16.35 (a, b, obverse and reverse)
Saljuqs, Sanjar, *dinar*, Walwalij, Muḥarram 493 AH (1099 CE).

a



b



Plate 16.36 (a, b, obverse and reverse)
Faṭimids, al-ʿAziz, *dinar*, Miṣr, year 368 AH (978–9 CE).

a



b



Plate 16.37 (a, b, obverse and reverse)
Faṭimids, al-Muʿizz, *dirham*, al-Manṣuriyya, year 358 AH (968–9 CE).



Plate 16.38 Faṭimids, al Mustanṣir, glass token.

a



b



Plate 16.39 (a, b, obverse and reverse)
Numayrids, Mani' (r. c. 440 54/1050 62), *dirham*.

a



b



Plate 16.40 (a, b, obverse and reverse)
Zangids, Nur al Dīn, *qirṭas*, Damascus, year 558 AH (1162 3 CE).

a



b



Plate 16.41 (a, b, obverse and reverse)
Zangids, al Ṣāliḥ Isma'īl, *dirham*, Aleppo, year 571 AH (1175 6 CE).

The reforms of al-Ma'mun and al-Mu'tasim billah

The devastating war of succession between al Amīn (r. 193 8/809 13) and al Ma'mun marked a turning point. The latter initiated a reform in the design of the coinage, which went along with a reorganisation of coin production as a whole. The reform started with the first changes in design in 201/816f. (fig. 16.22) and found its definitive appearance in 206/821f. (fig. 16.23). The new style was consecutively adopted during the following years in almost all mints.²²

First of all, gold and silver coins were given a standardised design based on the *dirham* without altering the weight standards. The most obvious change in the design was a second marginal obverse legend praising the victory of God (Q 30:4 5). This design continued with few alterations until the fifth/eleventh century. Whereas the old style preferred an angular Kufic script, the new style exhibited a neat curvilinear calligraphy. The new style coinage of al Ma'mun once again became anonymous. The number of mints was reduced to the major capitals of the empire. The production of silver and gold coinage dropped considerably, and even more under his successors.

Al Mu'tasim billah (r. 218 27/833 42) dismissed anonymity again, and added his name to the new design on the reverse in 219/834 (fig. 16.24). This became the rule. From 236/850 under al Mutawakkil 'ala Allah (r. 231 47/847 61) the name of the heir apparent was also included. The production and distribution of dies was almost centralised. The extent of the new capital city of Samarra', built and provisioned entirely by tax money, is impressive proof of the high degree of the empire's centralisation at its peak.²³

In the wake of the second devastating war of succession in 251 2/865 6 al Mu'tazz billah (r. 252 5/866 9) resumed the production of precious metal coins on a large scale. Many mints were set up in the provinces. Weakened, the empire gradually lost its grip on its peripheral provinces. In Panjhīr/Transoxania in 259/872f. Ya'qub ibn al Layth (r. 247 65/861 79)

22 T. El Hibri, 'Coinage reform under the 'Abbasid caliph al Ma'mun', *JESHO*, 36 (1993); S. Shamma, *Aḥdath 'aṣr al Ma'mun kama tarwīha al nuqud* (Irbid, 1995).

23 M. Bates, *The expression of sovereignty in the Abbasid caliphate*, 218 334 H/833 946 CE (forthcoming); L. Ilisch, 'Stempelveränderungen an islamischen Münzen des Mittelalters als Quelle zur Münzstättenorganisation', in T. Hackens and R. Weiller (eds.), *Actes du 9ème congrès international de numismatique. Berne, Septembre 1979: Proceedings of the 9th International Congress of Numismatics, Berne, September 1979* (Louvain la Neuve and Luxembourg 1982). Cf. L. Treadwell, 'Notes on the mint at Samarra', in C. Robinson (ed.), *A medieval Islamic city reconsidered: An interdisciplinary approach to Samarra*, Oxford Studies in Islamic Art 14 (Oxford, 2001).

was probably the first provincial ruler to add his name to the caliph's protocol on silver coins as proof of his autonomy (fig. 16.25). At least from 265/878f. on, with the rule of Aḥmad ibn Ṭulun in Egypt, the inclusion as an autonomous *amīr* into the coin protocol became a regular feature (fig. 16.26). His model was followed by the Samanids in Transoxania and many other ruling houses. *Sikka* and *khuṭba* in the name of the regional ruler became a sign of autonomy within the frame of the 'Abbasid empire until its end in 656/1258.

In the 'Abbasid core provinces the inclusion of the vizier's honorific title (*laqab*) in 291/903f. and in 320/932f. set precedents for the imperial government. In 324/936 the first *amīr al umara'*, Ibn Ra'iq, had abolished the distinction between civil and military administration. The *amīr al umara'* Bajkam was the first to be included in the coin protocol in 329/940 (fig. 16.27). In 334/945 the caliph delegated his power to the Buyids (fig. 16.28) and following them to the Saljuqs (figs. 16.31, 16.32), and these always with few exceptions appear on the coinage with flourishing honorific titles (figs. 16.28, 16.32) until the sixth/twelfth century when the caliph freed himself from Saljuq political domination.²⁴ Autonomous rulers who depended on the Buyids, such as the 'Uqaylids in northern Mesopotamia (fig. 16.29), and the Ḥasanwayhids²⁵ in Kurdistan, among others, acknowledged the Buyids as overlords and added their names to the hierarchy of power listed in the coin protocol. Others at the periphery, such as the Ikshīdids²⁶ in Egypt or the Sallarids²⁷ in Azerbaijan (fig. 16.30) acknowledged only the caliph. Sometimes further mint marks, names of die engravers and dynastic emblems (*tamghas*) were added (figs. 16.34, 16.35). For the historian the *sikka* became an unrivalled tool for defining length of reigns, the extent of territories, especially for local dynasties, and shifting political religious allegiance (cf. fig. 16.39), which are not in the focus of the main chronicles.

During the middle decades of the third/ninth century copper coinage vanished almost completely from the urban markets from Spain to Iran (fig. 16.20), remaining only in certain limited regions such as Samanid Transoxania (fig. 16.32). Fragmentation of the circulating precious metal coins served the needs of small change in the rest of the Islamic empire.

24 L. Treadwell, *Buyid coinage: A die corpus (322–445 AH)* (Oxford, 2001).

25 'A. Quchanī, 'The territory of Abu al Nadjm Badr b. Hasanuyah based on his coins', *Iranian Journal of Archaeology and History*, 8, 2 (1994) (in Persian).

26 J. L. Bacharach, *Islamic history through coins: An analysis and catalogue of tenth century Ikshīdīd coinage* (Cairo, 2006).

27 R. Vasmer, 'Zur Chronologie der Gâstaniden und Sallariden', *Islamica*, 3 (1927).

Coins were circulating more and more by weight expressed in standard *dirhams* and *dīnars* instead of by tale or count.²⁸

Starting slowly, probably in the time of al Muqtadir billah (r. 295–320/908–32), the fineness of the silver coinage dropped, varying from region to region, and the strict weight regulation was abandoned. After the political, economic and military collapse of the central lands of the 'Abbasid empire during the fourth/tenth century the silver *dirham* declined to a debased copperish coin with no regulated fineness or weight.²⁹ Now different kinds of *dirhams* were used, each current only within a limited region. Amounts of money were expressed in terms of monies of account.³⁰ Actual payments of coins were transacted by weighing the coins. In the fourth/tenth and fifth/eleventh centuries the number of coins being struck diminished dramatically in the central lands of the empire. In the narrative sources these coins are referred to as 'black *dirhams*' (sing. *dirham aswad*), because of their dark appearance (fig. 16.39). In Egypt they were then called *dirham wariq*,³¹ the 'silver[ish] *dirham*'. Legal texts addressed them more appropriately as *darahim maghshusha*, 'debased *dirhams*'. The monetary sector of the urban economy in the core lands of the Islamic empire northern Syria, northern Mesopotamia, Iraq and western Iran shrank to a low that may not have been experienced since Hellenistic Antiquity.

This monetary situation caused frequent complaints by jurists and theologians. It was open to unintended violations of the *riba* prohibition, the unequal market value of the same amount of precious metal: *dirham aswads* from different circulation zones might contain a different amount of silver alloy; the intrinsic amount of silver in foreign *dirhams* might be unknown (*majhul*), or the coins might be valued differently in the market with no regard to the real content of precious metal. In order to avoid *riba* and to facilitate commerce, jurists allowed transactions with *dirham aswads* only as long as they involved current *dirhams* circulating within a single zone (*ra'ij fi l balad*).³² In order to distinguish one issue of black *dirhams* from the other the issuing authorities gradually diverged from the classical coin design. To remedy this

28 L. Ilisch, 'Whole and fragmented dirhams in Near Eastern hoards', in K. Jonsson and B. Malmer (eds.), *Sigtuna Papers: Proceedings of the Sigtuna symposium on Viking age coinage 1–4 June 1989, Stockholm*, Commentationes de nummis saeculorum in Suecia repertis. Nova Series 6 (London, 1990).

29 T. S. Noonan, 'The start of the silver crisis in Islam: A comparative study of Central Asia and the Iberian peninsula', M. Gomes Marques and D. M. Metcalf (eds.), *Problems of medieval coinage in the Iberian area*, vol. III (Santarém, 1988).

30 'Monies of account' are denominations not actually struck, or no longer struck, but used to determine legally amounts of money in transactions, contracts or debts.

31 M. Bates, 'Wariq', *El2*, vol. IX, p. 147.

32 Heidemann, *Renaissance*, pp. 369–80.

unsatisfactory monetary situation, sporadic attempts at coinage reform were made in some regions, but were of no avail in the long run (fig. 16.28).

The eleventh century: the currency system at the brink of the reform

In the periphery, however, in Central Asia and in Egypt, a high level of monetary economy and an army based on cash payment remained. The Samanids had the advantage of rich silver mines in present day Afghanistan, and the resulting huge volume of coinage fostered a trade with these coins which, via the Volga river, reached the countries around the Baltic Sea in the fourth/tenth century (fig. 16.31). Although by contrast the *dirhams* of the Ghaznavids (384–582/994–1186) with a high silver content in the late fourth/tenth and first half of the fifth/eleventh centuries were a regional coinage, they were nevertheless struck in abundant quantities. As early as the Samanid period the *dīnār* of Nishapur gained fame for its purity and stability (fig. 16.34). It became one of the preferred trade coins circulating between Iraq, eastern northern Mesopotamia and Central Asia. It maintained its leading position into the Saljuq period while the *dīnars* of the other eastern Iranian and Transoxanian mints, Ghazna, Herat, Marw, Balkh, Bukhara and others debased, sometimes to such an extent that they consisted almost of pure silver and served only as regional standard currency (fig. 16.35).

The situation was different in Egypt. The Ismaʿīlī Shīʿite Faṭimids challenged the ʿAbbasid claim of universal rulership both ideologically and militarily, and thus their coinage named only the Faṭimid caliph. After their conquest of Egypt their coins presented a visual distinction to the classical late ʿAbbasid coinage, moving towards a design consisting mainly of rings of concentric inscriptions (figs. 16.36, 16.37). The Faṭimids profited from the North African gold trade as well as from trade with the northern Italian mercantile republics. The Faṭimid *dīnār* (fig. 16.36) of a regulated weight and an undisputed pure gold content became the preferred trade coinage for the Islamic Mediterranean, the Red Sea, the Persian Gulf and Iraq. On the level of the petty coinage the North African Egyptian *dirham* suffered the same decline as it did in the entire Islamic world (fig. 16.37).³³ Copper coinage was also abandoned. A debate between Paul Balog and Michael Bates centring around the question whether the abundant glass tokens of the Egyptian

³³ N. D. Nicol, *A corpus of Faṭimid coins* (Trieste, 2006).

Faṭimid and Ayyubid period served the purposes of daily purchases has not yet been settled (fig. 16.38).³⁴

Outlook: the reform

Islamic coinage of the middle Islamic period was quite different from the degenerated state of the classical coinage system. The renewal commenced slowly from the end of the fifth/eleventh century and ended at about the middle of the seventh/thirteenth. The 'black *dirham*' (fig. 16.39) disappeared mostly in the course of the sixth/twelfth century. In Syria Nur al Dīn Maḥmud (r. 541 69/1150 74) issued it for the last time in 546/1151f. in Aleppo, although it continued to be struck in Mosul into the 650s/1250s and in Egypt into the Mamluk period. In the last decades of the fifth/eleventh century copper coinage resumed in northern Syria, northern Mesopotamia and the Caucasus through the appearance of imported Byzantine *folles*, called in Arabic sources *qirṭas* or *qarṭīs* (pl. *qaraṭīs*). In the middle decades of the sixth/twelfth century a successful indigenous copper coin production commenced, mainly in the Zangid and Artuqid realm (fig. 16.40). Regional copper coinages spread to the other western Saljuq successor states. In 571/1175f. after almost 250 years the Zangids in Aleppo and the Ayyubids in Damascus reintroduced a *dirham* of almost pure silver with a regulated weight of about 2.8 grams (fig. 16.41). The success of the reform was achieved through the northern Italian trade of European silver. The reform spread from the Levant to the entire Middle East. Once again a currency system was established that conformed to the requirements of Islamic law.³⁵

34 P. Balog, 'Faṭimid glass jetons: Token currency or coin weights?', *JESHO*, 24 (1981); M. L. Bates, 'The function of Faṭimid and Ayyubid glass weights', *JESHO*, 24 (1981).

35 S. Heidemann, 'Economic growth and currency in Ayyubid Palestine', in R. Hillenbrand and S. Auld (eds.), *Ayyubid Jerusalem: The Holy City in context* (London, 2009) pp. 1187–1250.

Archaeology and material culture

MARCUS MILWRIGHT

The last four decades have witnessed a massive expansion in the archaeology of the Islamic past in regions stretching from the Iberian Peninsula to Indonesia. While the coverage of research is far from complete – for instance, the first/seventh and second/eighth century occupation phases in key cities such as Baṣra, Damascus and Baghdad remain largely unexplored, and excavations are not permitted in the Holy Cities of Mecca and Medina – archaeology is now able to provide important insights into the study of the early Islamic period. Aside from its obvious role in the discovery and recording of artefacts, the discipline's most notable contribution to the study of early Islam is in the identification of economic, demographic and environmental processes that occur over the course of decades or centuries.

A recurrent concern in the archaeological study of early Islam is the degree to which the physical record exhibits significant continuity with the centuries prior to 1/622 (i.e. the Late Antique period). Conversely, the analysis of spatial and temporal patterns in the archaeological record from the first/seventh to the fourth/tenth centuries can reveal the emergence of new socio-cultural or economic phenomena. These competing dynamics are examined here with reference to four themes. The first part summarises the earliest evidence for a distinctive Muslim identity in the archaeological record. The second part assesses changes in the countryside with particular emphasis on the elite country residences (*qaṣr*, pl. *quṣur*) of Greater Syria and the evolution of complex irrigation systems in different parts of the Islamic world. The third part discusses the changes in the urban environment from the Late Antique period to the creation of new cities in Syria and Iraq during the early 'Abbasid caliphate (132–279/750–892). The final part addresses changes in international trade from the Late Antique period to around 390/1000.

Muslim identity in the archaeological record

The Dome of the Rock in Jerusalem (dated by an inscription to 72/69f.) marks a watershed in Islamic material culture – not just in the fact of its remarkable preservation, but also in the evidence it gives about the new sense of artistic ambition among the Muslim elite. Leaving aside the Qur'an pages in Ḥijazī script and inscriptions dated on palaeographic grounds, we are left with a small group of artefacts from the period prior to the construction of the Dome of the Rock. Bilingual papyri (from 22/642) and Arab Sasanian coins (*drachm/dirham*, from 31/651f.) bear the words *bism allah* ('in the name of God') (see fig. 16.7). Longer inscriptions appear on the gravestone of one 'Abd al Raḥman ibn Khayr in Egypt (31/652) and on graffiti in the Ḥijaz (from 40/660f.). Although these examples carry recognisably Muslim invocations, references to Muḥammad and his status as the prophet of Allah are absent. Mu'awiya ibn Abī Sufyan (r. 41 60/661 80) is the first caliph whose honorific, *amīr al mu'minīn* ('commander of the faithful'), written in Arabic, or transcribed into Greek or Persian, appears on coins, papyri and monumental inscriptions.¹ Coins dating from 66/685f. until the minting of the first purely epigraphic issue of 77/696f. are notable for the inclusion of versions of the profession of faith (*shahada*), as well as the name of Muḥammad (see chapter 16).²

In architecture the picture is even more sparse; prior to the Dome of the Rock we lack any buildings with inscriptions, and all dating is circumstantial. Recently it has been suggested that the first construction phase identified in Hamilton's survey of the Aqsa Mosque in Jerusalem should be dated to the rule of Mu'awiya in the 40s/660s.³ Excavation of the *dar al imara* (governor's residence) in the garrison town (*miṣr*, pl. *amṣar*) of Kufa revealed a large brick building surrounded by an *intervallum* and a fortified wall on the *qibla* side of the mosque (of which only one re-entrant corner was located). The *dar al imara* itself was constructed in three phases, the earliest of which may have

1 A graffito at Qa' al Mu'tadil near al Hijr in Saudi Arabia, dated 24/644, does contain a reference to the death of 'Umar ibn al Khaṭṭab (r. 13 23/634 44), though without employing the title of caliph or the honorific *amīr al mu'minīn*. See www.islamicawareness.org/History/Islam/Inscriptions/kuficsaud.html.

2 Jeremy Johns, 'Archaeology and the history of early Islam: The first seventy years', *JESHO*, 46, 4 (2003), pp. 414–24; Robert Hoyland, 'New documentary texts and the early Islamic state', *BSOAS*, 69, 3 (2006); www.islamicawareness.org/History/Islam/Inscriptions.

3 Jeremy Johns, 'The "House of the Prophet" and the concept of the mosque', in Jeremy Johns (ed.), *Bayt al Maqdis: Jerusalem and Early Islam*, Oxford Studies in Islamic Art, 9, part 2 (Oxford, 1999), pp. 62–4.

been built by the governor, Ziyad ibn Abī Sufyan, in around 50/670 (fig. 17.1).⁴ The earliest positive evidence for the dating of the *quṣūr* in Bilad al Sham (Greater Syria) consists of a graffito carrying the date of 92/710 in Qaṣr al Kharana in Jordan (fig. 17.2), but recent archaeological research has provided plausible evidence for two earlier palatial structures. The first, Khirbat al Karak in northern Israel, has been associated with Sinnabra/Sinnabris, a palace employed by both Mu‘awiya and ‘Abd al Malik. The second is al Bakhra’, a Tetrarchic fort (293–305 CE) south of Palmyra, that was converted into a Muslim *qaṣr* through the construction, probably before 65/684, of an additional fortified zone to the north east.⁵

This small body of data suggests that the period c. 72/622–91f. was one of rapid evolution for both the practices associated with the faith of Islam and the administrative framework of the nascent Islamic state. That so little that is recognisably ‘Islamic’ has been recovered is not, of course, due to a lack of archaeological activity; excavations and surveys have revealed considerable evidence of first/seventh century occupation in the Middle East and North Africa. The overwhelming impression, however, is that the Arab conquests did not bring about radical and sudden change in the daily lives of the inhabitants of these regions. Continuity with the practices of Late Antiquity is evident in many aspects of the archaeological record into the second/eighth century and later.


The countryside

While knowledge of the urban palaces created by the Umayyad elite is limited,⁶ the *quṣūr* (often misleadingly described as ‘desert castles’) survive in much larger numbers in diverse environments ranging from the Syrian desert to the plains of Jordan and the sub-tropical Jordan valley. Commonly adopting a square plan with a fortified outer wall and square or round towers at the corners, this building type derives ultimately from the Roman *castrum* (fig. 17.3). Recent research has highlighted the importance of fifth- and

4 K. Creswell, *A short account of early Muslim architecture*, rev. and suppl. James Allan (Aldershot, 1989), pp. 10–15; Johns, ‘The first seventy years’, p. 417.

5 For Khirbat al Karak and al Bakhra’ see Denis Genequand, ‘Umayyad castles: The shift from Late Antique military architecture to early Islamic palatial building’, in Hugh Kennedy (ed.), *Muslim military architecture in Greater Syria: From the coming of Islam to the Ottoman Period*, *History of Warfare* 35 (Leiden and Boston, 2006), pp. 10–12, figs. 2.5, 6.3.

6 See, however, Alastair Northedge, *Studies on Roman and Islamic ‘Amman*, vol. I: *History, site and architecture*, British Academy Monographs in Archaeology 3 (Oxford and New York, 1992).



17.1 Plan of the *dar al imara* at Kufa, Iraq, first/seventh century and later. After K. Creswell, *Early Muslim Architecture* (revised edition, 1969), volume I.1, fig. 18.

sixth century Syrian fortified country residences of al Andarīn, Iṣṭabl ‘Antar and probably Ḍumayr as intermediaries in the evolution of the specific characteristics of the second/eighth century *qushur*.⁷ While the opulent decoration encountered on sites such as Khirbat al Mafjar and Qusayr ‘Amra offers intriguing insights into the culture of Umayyad princely pleasure (known otherwise from textual sources), archaeological interpretations are increasingly focusing upon the roles played by the *qushur* in the cultivation of land and the maintenance of trade routes. For instance, an early Islamic perimeter wall enclosing an irrigated area of some 535 hectares has been

7 Genequand, ‘Umayyad castles’, pp. 20–4, figs. 6.2, 7.2, 7.4.



17.2 Exterior of Qaṣr al Kharana, Jordan (before 92/710). Photo: Marcus Milwright



17.3 Late Roman *castrum* known as Qaṣr al Bashir, Jordan (293–305). Photo: Marcus Milwright

identified at Ma'an in southern Jordan.⁸ In the cases of Qaşr al Ḥayr al Gharbī and Khirbat al Maḥjar the cultivation of surrounding land involved the renovation of Roman dams and aqueducts.⁹

Key considerations in the placement of many of the *quṣur* were proximity to the ancient routes running north from the Ḥijaz into Syria, and the availability of water (map 7). For instance, the existence of a major route from the Arabian city of Tayma north via Wādī Sirḥan toward the plain of Balqa' in Jordan helps to account for the locations of Qaşr al Ṭuba, Qaşr al Kharana (fig. 17.2) and Quṣayr 'Amra. One of the northern routes from the Wādī Sirḥan passed around the eastern fringes of the basalt desert of southern Syria, and this makes sense of the otherwise remote Qaşr al Burqu' and Jabal Says (both of which were well provided with cisterns, and the latter also with a spring).¹⁰ Several important Umayyad *quṣur* can also be found along the Strata Diocletiana (established c. 297) linking Damascus to the Euphrates via Palmyra and Ruṣafa. Another significant route that received extensive patronage in the second/eighth and early third/ninth centuries was the Darb Zubayda leading from Mecca to Kufa. Reconnaissance along this road has revealed numerous fortified structures, as well as hundreds of wells, cisterns and rain catchment devices designed to provide a reliable water supply for the pilgrims, merchants and others passing through this arid region.¹¹

Surveys in Iran and Iraq have demonstrated the extent to which the agricultural prosperity of the early Islamic period was reliant upon the engineering of the Sasanian period (c. 224–651), and earlier dynasties. Comprising large canals (such as the sixth century Kaṭul al Kisrawī drawing water from the Tigris river and feeding the Diyala plain in Iraq), underground channels (*qanat*) and networks of smaller irrigation canals, these systems greatly enhanced the productivity of lands under Sasanian control. The most intensively studied of these is the ancient canal system of the Diyala plain east of Baghdad. While both the methodology employed by Adams and his conclusions should be assessed in the light of criticisms made by economic historians and revisions made to his ceramic chronology, this study gives

8 Denis Genequand, 'Ma'an, an early Islamic settlement in southern Jordan: Preliminary report on the survey in 2002', *Annual of the Department of Antiquities of Jordan*, 47 (2003).

9 Creswell, *Short account*, pp. 135, 180.

10 Geoffrey King, 'The distribution of sites and routes in the Jordanian and Syrian deserts', *Proceedings of the Seminar for Arabian Studies*, 20 (1987).

11 Barbara Finster, 'Die Reiseroute Kufa Sa'udī Arabien in frühislamische Zeit', *Baghdader Mitteilungen*, 9 (1978); J. Wilkinson, 'Darb Zubayda architectural documentation program. B. Darb Zubayda 1979: The water resources', *Atlat*, 4 (1980).

important insights into an agricultural region in the transition to Islamic rule. While there appears to have been a reduction in settlement levels and the number of active canals after the late Sasanian phase, the Diyala plain remained relatively prosperous until the end of the third/ninth century. Political instability, overtaxation and lack of investment probably contributed to the deterioration of the agricultural infrastructure in subsequent centuries.¹²

In the Arabian Peninsula complex networks of open channels, *qanat* and water mills have been identified inland from the Omani port of Ṣuḥar. Allowing for the cultivation of 6,100 hectares, this system was probably constructed in the third/ninth and fourth/tenth centuries, when the area enjoyed considerable prosperity in international maritime trade.¹³ The evidence from Spain suggests that, following the conquest in 92 100/711 20, the irrigation systems of the Islamic period synthesised aspects of the existing Roman Visigothic infrastructure (which concentrated upon the provision of water to urban centres) with types of *qanat* and rain fed reservoirs introduced from the Middle East. These novel technologies in Islamic Spain were a necessary precursor to the introduction of new crops such as sugar cane, rice, mulberries, cotton and oranges.¹⁴

The urban environment

Important changes can be detected in the towns and cities of the Late Antique period. Excavations of urban centres report a broadly consistent pattern from the fourth century with urban institutions such as theatres, large public baths and pagan temples falling out of use, while church building proliferated.¹⁵ These changes reflect both the increasing irrelevance of theatrical performance and other entertainment and the dominating role of the Church. Equally

12 Robert Adams, *Land behind Baghdad: A history of settlement on the Diyala plains* (Chicago and London, 1965), pp. 69 111. See also criticisms in Michael Morony, 'Land use and settlement patterns in late Sasanian and early Islamic Iraq', in Geoffrey King and Averil Cameron (eds.), *The Byzantine and early Islamic Near East*, vol. II: *Land use and settlement patterns*, Studies in Late Antiquity and Early Islam 1 (Princeton, 1994), pp. 221 9.

13 T. J. Wilkinson, 'Sohar ancient fields project: Interim report no. 1', *Journal of Oman Studies*, 1 (1975). See also 2 (1976), pp. 75 80; 3 (1977), pp. 13 16.

14 Thomas Glick, 'Hydraulic technology in al Andalus', in S. Jayyusi (ed.), *The legacy of Muslim Spain* (Leiden, 1992); Andrew Watson, *Agricultural innovation in the early Islamic world: The diffusion of crops and farming techniques*, Cambridge Studies in Islamic Civilization (Cambridge, 1983), pp. 9 73, 103 11.

15 Hugh Kennedy, 'From polis to madina: Urban change in Late Antique and early Islamic Syria', *Past and Present*, 106 (February 1985).

important is the tendency for public spaces – fora and the wide colonnaded streets – to be encroached upon by private building. The abandonment of wheeled transport in favour of pack animals may have been a contributing factor, though the construction of shops, houses and industrial installations on public thoroughfares presumably also reflects the decreasing authority of municipal officials. This gradual evolution of the urban space through the Late Antique and early Islamic periods has been demonstrated on numerous excavations, of which the ancient Decapolis towns of Pella and Scythopolis (Bet Shean, Baysan) in the Jordan valley are well published examples.¹⁶ The discovery in Baysan of an impressive market ornamented with two inscriptions in blue and gold mosaic built in 120/737f. by the caliph Hisham (r. 105 25/724–43) demonstrates that the Umayyad elite did, at times, seek to invest in the improvement of the urban infrastructure.¹⁷ The remarkable persistence of the idea of the ‘classical’ city is illustrated by the Islamic urban foundation of ‘Anjar (c. 92 6/711–15) in Lebanon (fig. 17.4). The unfinished city preserves its original rectangular plan with a *tetrapylon* marking the intersection of the colonnaded north–south and east–west streets (*cardo* and *decumanus* respectively).¹⁸


Similar dynamics can be detected in the towns and cities of Late Antique North Africa, though there are significant differences in the overall chronology. Excavations in Uchi Maius (now known as Henchir al Douamis) in Tunisia revealed the intrusion after 364–75 of a cistern, an olive oil press, and later a kiln, into the Antique forum and surrounding areas. This radical change correlates well with archaeological evidence in other towns for increased agricultural productivity during Vandal rule.¹⁹ A further shift away from the classical urban plan in Uchi Maius is signalled by the construction of a citadel in the late sixth century. A *miṣr* was established at Qayrawan in 50/670, and settlements such as Sétif and Rougga probably exhibit signs of continuous occupation into the first/seventh and second/eighth centuries, but more commonly the archaeological record indicates a hiatus in urban settlement from some time prior to the Islamic conquest until

16 Anthony McNicoll *et al.*, *Pella in Jordan*, 2 vols., Mediterranean Archaeology Supplements 2 (Sydney, 1992), vol. II, pp. 145–98; Yoram Tsafrir and Gideon Foerster, ‘From Scythopolis to Baysan: changing concepts of urbanism’, in King and Cameron (eds.), *Land use and settlement patterns*, pp. 95–115.

17 Elias Khamis, ‘Two wall mosaic inscriptions from the Umayyad market place in Bet Shean/Baysan’, *BSOAS*, 64 (2001).

18 Creswell, *Short account*, pp. 122–4.

19 Anna Leone, ‘Late Antique North Africa: Production and changing use of buildings in urban areas’, *al Masaq*, 15, 1 (March 2003), pp. 25–7.




17.4 Plan of the town of 'Anjar, Lebanon. After *Early Muslim Architecture* (revised edition, 1969), volume 1.2, fig. 540.

the fourth/tenth or fifth/eleventh centuries. Like a number of other settlements in Islamic North Africa (Ifriqiya), the re urbanisation of Uchi Maius comprised a mosque and an area of closely packed courtyard houses within the citadel.²⁰

Inscriptions on items as diverse as coins, seals, documents, road markers and buildings performed the task of announcing the religious and political values of the Muslim elite, but this was also achieved through the imposition of new architectural forms. As already noted, the conquests were often followed by the founding of *amṣar*, usually in the vicinity of established settlements. Of the first/seventh century *amṣar*, only Kufa, Fuṣṭaṭ (Egypt, 21/642)

20 Sauro Gelichi and Marco Milanese, 'Problems in the transition toward the Medieval in Ifriqiya: First results from the archaeological excavations at Uchi Maius (Teboursouk, Béja)', in M. Khanoussi, P. Ruggieri and C. Vismara (eds.), *L'Africa Romana: Atti del XII Convegno di Studio* (Sassari, 1998).



17.5 Plans of mosques I (possibly 84/703: marked in black) and II (marked in grey) in Wasit. After F. Safar, *Wâsit, the sixth season's excavations* (1945), fig. 5.

and Ayla (Jordan, c. 30/650) have been excavated, and in each case little remains from the early decades of occupation.²¹ Textual descriptions make clear the central role played by the congregational mosque (*masjid al jami'*) and the governor's residence. The earliest mosque to preserve its original plan was excavated in the Iraqi *miṣr* of Wasīṭ (dated on historical grounds to 84/703) (fig. 17.5).²² Reviewing the archaeological data for the following decades, it becomes apparent how rapidly the concept of the courtyard mosque was adopted into the urban centres of the expanding Islamic empire. Early examples are known from widely dispersed locations including Banbhore and al Manṣūra in Pakistan (before 108/727f. and second/eighth century respectively), Samarqand/Afrasiyab in Uzbekistan (c. 142 63/760 80), Susa in Iran

21 Roland Pierre Gayraud, 'Fostat: Évolution d'une capitale arabe du VII^e au XII^e siècle d'après les fouilles d'Istabl 'Antar', in Roland Pierre Gayraud (ed.), *Colloque international d'archéologie islamique, IFAO, Le Caire, 3-7 février 1993*, Textes arabes et études islamiques 36 (Cairo, 1999); Donald Whitcomb, 'The *misr* of Ayla: Settlement at 'Aqaba in the early Islamic period', in King and Cameron (eds.), *Land use and settlement patterns*, pp. 155-70.

22 Fuad Safar, *Wâsit: The sixth season's excavations* (Cairo, 1945), pp. 20, 24-7, fig. II.

(second/eighth century), Ṣan‘a’ in Yemen (92 6/711 16), Damascus in Syria (86 96/705 16), Ḥarran in south east Turkey (probably 127 32/744 50), the citadel and lower town of ‘Amman in Jordan (c. 90 111/709 30 and before 133/750 respectively) and Cordoba in Spain (171 2/787 8).²³

In archaeological terms what is of interest is the distribution of the mosques and their spatial relationship to other structures. Mosques were located in close proximity to the commercial centre within existing cities. At the Persian Gulf port of Sīraf the mosque, constructed after 188/803f., occupied the site of the old Sasanian fort, but was also surrounded by the market (the lower storey of the south eastern side of the mosque being made up of a series of shops).²⁴ At ‘Anjar the north wall of the mosque functions as the back wall of five shops that face onto the *decumanus* (fig. 17.4), while excavations in Ayla revealed that the expansion of the mosque necessitated the alteration of the route of the *cardo*. The close integration of the congregational mosque and governor’s residence has been demonstrated in excavations at Kufa, Wasīṭ, ‘Anjar and al Manṣura. The extant urban plans of the second/eighth century reveal another important process: the spatial separation of the religious and palatial/administrative structures and the creation of a ceremonial route between them. This increased elaboration can be found in such cases as Hisham’s palace and mosque in Sergiopolis/al Ruṣafa, the Aqṣa Mosque and the palaces to the south of the Ḥaram al Sharīf in Jerusalem, and the citadels of ‘Amman and Samarqand.²⁵

The new cities of the early ‘Abbasid period represent a break with the concept of the classical urban plan seen so powerfully at ‘Anjar. While the famous Round City of Baghdad constructed by the caliph al Manṣur (r. 136 58/754 75) is only known from written descriptions, two ‘Abbasid urban foundations – al Rafīqa in Syria (after 155/771f.) and Samarra’ in Iraq (221 79/836 92) – have been subjected to archaeological study. The garrison city of al Rafīqa (lit. ‘the Companion’) was

23 F. Khan, *Banbhore: A preliminary report on the recent archaeological excavations at Banbhore*, 4th edn (Karachi, 1976); Abdul Aziz Farooq, ‘Excavations at Mansurah (13th season)’, *Pakistan Archaeology*, 10 12 (1974 86); Creswell, *Short account, passim*; Johns, ‘Concept of the mosque’, pp. 64 9; Yury Karev, ‘Samarqand in the eighth century: The evidence of transformation’, in Donald Whitcomb (ed.), *Changing social identity with the spread of Islam: Archaeological perspectives*, Oriental Institute Seminars 1 (Chicago, 2004).

24 David Whitehouse, *Sīraf III: The congregational mosque and other mosques from the ninth to the twelfth centuries* (London, 1980), pp. 9 19.

25 On these structures see Dorothee Sack, *Resafa IV: Die Grosse Moschee von Resafa Ruṣafat Hisam* (Mainz, 1996); Creswell, *Short account*, pp. 94 6; Antonio Almagro and Pedro Jiménez, ‘The Umayyad mosque on the citadel of Amman’, *Annual of the Department of Antiquities of Jordan*, 44 (2000); Karev, ‘Samarqand’, pp. 53 60.

constructed on the north bank of the Euphrates river about 600 metres west of the existing settlement of al Raqqa (ancient Kallinikos). Built largely of mud brick, and following a similar system to the fortifications of Baghdad, the double line of walls was punctuated with numerous major and minor entrances (fig. 17.6). To the north was an extensive complex of palaces and administrative structures, while to the west at Hiraqla is an unfinished structure surrounded by a circular wall that is believed to be a victory monument.²⁶ Another significant aspect of the plan was the creation of a large industrial zone. Excavations in the area known today as Tal Aswad, directly north of al Raqqa, identified groups of ceramic kilns (operating until c. 210/825f.) producing a wide range of unglazed and glazed vessels, while further to the west a glass workshop was discovered constructed over the hypocaust of a bathhouse. Later industrial activity was largely focused in the land between al Raqqa and al Rafiqa. Provided with its own defensive wall and a market, this industrial area was, by the late fourth/tenth century, understood as a distinct urban entity (*madīna*).²⁷

Established by al Mu'tasim (r. 218 27/833 42) in 221/836, and expanded by later caliphs, most notably al Mutawakkil (r. 232 47/847 61), Samarra' stretches more than 35 kilometres along the banks of the Tigris river. Like Baghdad, this 'Abbasid foundation made use of existing watercourses constructed in the Sasanian period. Comprising numerous palaces, two congregational mosques, barracks, a mausoleum, pavilions, racecourses, polo grounds, highways and hunting reserves, Samarra' is perhaps best considered as a series of linked urban units rather than a conventional city with a single administrative and economic centre. Indeed, the erection of a second congregational mosque of Abu Dulaf (245 7/859 61) lends the northern development of al Mutawakkiliyya the status of city distinct from that of the remainder of Samarra' (fig. 17.7). The palaces and other monumental structures of Samarra' owe their scale partly to the cheap building materials mud brick and pisé employed in much of the construction. Baked brick and expensive decorative media were reserved for the two congregational mosques and the most important sectors of the palaces. While the palaces are evidently the focal points of each urban unit, they should not be seen in isolation; many are surrounded by 'cantonments' built in mud brick

26 Verena Daiber and Andrea Becker (eds.), *Raqqa III: Baudenkmäler und Paläste I* (Mainz am Rhein, 2004).

27 Julian Henderson *et al.*, 'Experiment and innovation: Early Islamic industry at al Raqqa, Syria', *Antiquity*, 79 (2005); Stefan Heidemann, 'The history of the industrial and commercial area of 'Abbasid al Raqqa, called *al Raqqa al Muhtariqa*', *BSOAS*, 69, 1 (2006).



17.6 Corona satellite photograph of Raqqa, Syria, taken between 1960 and 1972. 1) Raqqa (Kallinikos); 2) walled city of Rafiq; 3) North gate; 4) 'Baghdad gate'; 5) Congregational Mosque; 6) Possible line of the wall enclosing al Raqqa al Muhtariqa ('the burning Raqqa'); 7) site of an Abbasid period glass workshop; 8) Tal Aswad.



17.7 Aerial view of Samarra' with the mosque of Abu Dulaf (245 47/859 61). Creswell archive: EA.CA.271. Creswell Archive, courtesy of the Ashmolean Museum, University of Oxford.

that probably functioned as the housing blocks and markets of the Turkish troops.²⁸

International trade

Two major spheres of Late Antique international mercantile activity – the Mediterranean and the Persian Gulf – are of particular relevance for the development of long distance trading relationships in the early Islamic period (maps 2, 5, 7). In the fifth and sixth centuries volumes of trade in the Mediterranean declined considerably from the levels seen in earlier centuries. There is, however, textual and archaeological evidence for the continuity of established economic contacts. Furthermore, the supply to Europe of luxury goods from North Africa and the Middle East was not terminated by the Islamic conquests. For instance, papyrus from Egypt continued to be employed by the Merovingian chancery until the early second/eighth century, and the latest Papal papyrus carries the date of 1057.²⁹ Another interesting example of continuity with earlier Mediterranean trading practices can be seen in the occurrence of resin coated ceramic amphorae, corresponding to a Late Roman type, in late second/eighth to early third/ninth century excavated contexts in Iṣṭabl ‘Antar/Fuṣṭaṭ in Egypt. Comparable amphorae are reported from long established wine producing sites in Middle Egypt.³⁰ A similar continuity in amphora production may also have occurred in North Africa.³¹

The Persian Gulf presents a different picture. The phase from the second to the fourth or fifth centuries witnessed a decline in settlement levels in eastern Arabia, as well as the construction of fortified dwellings at sites such as Mheila and al Dur (similar structures in the Ḥijaz, including Qaryat al Faw, also date to this phase). In spite of the evidence for reduced levels of sedentary occupation, mercantile activity remained vigorous, with the presence of South Asian ceramics being an indication of the long distance commercial contacts. On the Persian coast the major port of Bushihr was established during the rule of the Sasanian shah Ardashīr (r. 224–40), while the fort at Siraf is attributed to Shapur II (r. 309–79). While many of the Arabian fortified buildings were abandoned between the fifth and the first/seventh second/

28 Alastair Northedge, *The historical topography of Samarra*, Samarra Studies 1 (London, 2005).

29 Richard Hodges and David Whitehouse, *Mohammed, Charlemagne and the origins of Europe: Archaeology and the Pirenne thesis* (London, 1983).

30 C. Vogt et al., ‘Notes on some of the Abbasid amphorae of Iṣṭabl ‘Antar Fustat (Egypt)’, *BASOR*, 326 (2002).

31 Leone, ‘Late Antique North Africa’, pp. 21–4.



17.8 Earthenware bowl with tin glaze and cobalt (blue) and copper (green) painting, Iraq, third/ninth century. 1978.2141. Courtesy of the Ashmolean Museum, University of Oxford.

eighth centuries, sites such as Khatt, Şuḥar and Kush perhaps continued to trade into the early Islamic period.³² Conversely, the decline in long distance land trade via the Silk Route caused by Perso Roman wars in 502–6, 527–61 and 602–29 may have invigorated Persian maritime activity. The presence of Sasanian *drachms* and bullae (perhaps used to seal packages destined for transport) in Oman, India, Sri Lanka and coastal sites in China illustrates the extent of Persian trading links.³³

Archaeology has established that the greatest expansion in Persian Gulf commerce occurred in the early 'Abbasid period. The extent of this trade is well illustrated by the wide distribution of second/eighth to fourth/tenth century Iraqi glazed pottery (fig. 17.8) from ports such as Baṣra and Sīraf; for

32 Derek Kennet, 'On the eve of Islam: Archaeological evidence from Eastern Arabia', *Antiquity*, 79 (2005); Derek Kennet, *Sasanian and Islamic pottery from Ras al Khaimah. Classification, chronology and analysis of trade in the western Indian Ocean*, BAR International Series 1248 (Oxford, 2004), pp. 68–85.

33 Touraj Daryaee, 'The Persian Gulf trade in Late Antiquity', *Journal of World History*, 14, 1 (March 2003).

instance, tin opacified wares and turquoise glazed storage jars appear on sites as dispersed as Fustaṭ, Zabīd (Yemen), Mantai (Sri Lanka), Ko Kho Khao (Thailand), the East African coast and possibly Kwa Gandaganda (South Africa).³⁴ Finds of Islamic glass vessels in elite burials in China are another indication of the widespread demand for luxury commodities manufactured in the cities of the Islamic Middle East.³⁵ Although transport by sea was the most efficient mode of long distance transport, reports of Iraqi ceramics at sites such as al Raqqa, al Rafīqa, Susa and Samarqand demonstrate that there was also vigorous trade along the major land routes and rivers. Glazed ceramics, glass and metalwork found along the Darb Zubayda (most notably at the town of al Rabadha) reveal that, in addition to the annual ḥajj, this major road was also employed by caravans bringing luxury merchandise from Iraq to the Hijaz.³⁶

The excavations of the congregational mosque and other sites in Sīraf provide evidence for the introduction of ceramics from South East Asia. The imports of the late second/eighth and third/ninth centuries included stone ware storage jars ('Dusun ware'), two inscribed with Arabic names (probably those of merchants), as well as various types of Tang period (618–906) glazed stoneware bowls. Dusun ware has also been located at numerous sites in southern Iran (as far north as Sīrjan), on the island of Socotra, Banbhore in Pakistan, the East African coast and Sri Lanka.³⁷ Equally impressive is the distribution of the green glazed stoneware produced between the third/ninth and fifth/eleventh centuries in the area of Yuezhou, south of Shanghai. Finds of Yueh wares are concentrated in the Persian Gulf, Mesopotamia and Sind, but they also made their way along land routes as far as Nishapur and Rayy.³⁸ Excavated contexts of the fourth

34 Robert Mason, *Shine like the sun: Lustre painted and associated pottery from the medieval Middle East* (Toronto and Costa Mesa, 2004), pp. 23–60.

35 Numerous Islamic glass vessels were reported in the tomb of a Liao princess from Ch'en state, dated 1018. See Ts'ai Mei fen, 'A discussion of Ting ware with unglazed rims and related twelfth century official porcelain', in Maxwell Hearn and Judith Smith (eds.), *Arts of the Sung and Yuan* (New York, 1996), pp. 116–17.

36 Sa'd b. 'Abd al 'Azīz al Rashīd, *al Rabadha: A portrait of early Islamic civilization in Saudi Arabia* (Harlow, 1986).

37 David Whitehouse, 'Chinese stoneware from Sīraf: The earliest finds', in N. Hammond (ed.), *South Asian archaeology* (Park Ridge, NJ, 1973); Jessica Rawson, Michael Tite and M. Hughes, 'The export of Tang sancai wares: Some recent research', *Transactions of the Oriental Ceramics Society*, 52 (1987–8). On the criticisms of the Sīraf ceramic chronology, see Kennet, *Sasanian and Islamic pottery*, pp. 83–4.

38 Andrew Williamson, 'Regional distribution of mediaeval Persian pottery in the light of recent investigations', in James Allan and Caroline Roberts (eds.), *Syria and Iran: Three studies in medieval ceramics*, Oxford Studies in Islamic Art 4 (Oxford, 1987), pp. 11–14.

or fifth to third/ninth centuries at Kush in Ras al Khaimah are notable for the occurrence of significant quantities of Indian ceramics; Chinese wares only start to appear in the fifth/eleventh century.³⁹ Storage vessels for date syrup akin to types manufactured at Sīraf in the fourth/tenth century have been located at sites including Manda, Shanga and Pate on the Lamu archipelago, while timbers employed in the buildings in Sīraf were probably shipped from East Africa.⁴⁰

Another dimension of the economic patterns from the late second/eighth to the fourth/tenth centuries is revealed by hoards found in Scandinavia, Denmark and the regions between the Black Sea and the Baltic. Of the huge number of coins from recovered hoards (more than 80,000 *dirhams* in Sweden, about 5,000 in Denmark and over seventy separate hoards of third/ninth century coins are reported from European Russia) the vast majority are *dirhams* minted in the east of the Islamic world particularly Madīnat al Salam (Baghdad), al Muḥammadiyya (Rayy), Balkh and Samarqand about 164 390/780 1000 (see fig. 16.23). Umayyad, Sasanian and Byzantine coins are all very scarce, as are examples minted in North Africa or Spain (for a detailed consideration of early Islamic numismatics, see chapter 16). The northern flow of silver from the 'Abbasid caliphate and the lands controlled by the Samanid dynasty (204 395/819 1005) is an indicator of a vigorous period of mercantile activity conducted with the peoples living beyond the borders of the eastern Islamic world. Focused on slaves, furs, wax, honey and amber, this trade required the interaction of Muslim merchants, Bulghars, Khazars and the group known in Arabic sources as the Rus (probably Vikings as well as Slavs and Finns) at entrepôts along the Volga and as far north as Old Ladoga (Staraja) in north western Russia. The rarity in Scandinavian hoards of coins minted after the 360s/970s probably gives an approximate date for the decline of this long distance trading network.⁴¹

39 Kennet, *Sasanian and Islamic pottery*, pp. 69 72.

40 David Whitehouse, 'East Africa and the maritime trade of the Indian Ocean, AD 800 1500', in B. Amoretti (ed.), *Islam in East Africa: New sources* (Rome, 2001).

41 Thomas Noonan, 'Ninth century dirham hoards from European Russia: A preliminary analysis', in M. Blackburn and D. M. Metcalf (eds.), *Viking age coinage in northern lands*, BAR International Series 122 (Oxford, 1981), pp. 47 117; Bengt Hovén, 'On Oriental coins in Scandinavia', in Blackburn and Metcalf (eds.), *Viking age coinage*, pp. 119 28; Anne Kromann and Else Roesdahl, 'The Vikings and the Islamic lands', in K. von Folsach et al. (eds.), *The Arabian journey: Danish connections with the Islamic world over a thousand years* (Aarhus, 1996).

Conclusion

Many areas of continuity can be detected between the early Islamic period and the patterns of Late Antiquity. This continuity is particularly apparent in the archaeological record of the first/seventh and much of the second/eighth centuries. At the same time, artefacts do provide indications of new directions. Arabic, though sometimes employed on monumental inscriptions prior to 1/622, becomes the pre eminent vehicle for the expression of a new Muslim identity. The somewhat tentative experiments with religious formulae from 1/622 to 72/691f. give little indication, however, of the dominant place that the written word would have in later Islamic art and architecture. Other important developments of this first phase were the creation of the *amṣar* and the introduction of new institutions, the congregational mosque and the *dar al imara*, into the urban environment. It is evident that the orderly planning of the 'classical city' had started to erode from at least the fourth century, and that this process continued after 1/622, but it is perhaps the great 'Abbasid foundations of the later second/eighth and third/ninth centuries that mark the decisive shift in Islamic urbanism. Attracting skilled workers from other regions, these great cities provided a fertile environment for innovation in media such as glass, glazed pottery and metalwork. The fate of the irrigation networks of Iraq during the 'Abbasid period remains the subject of debate, but elsewhere the centuries after the Arab conquests brought renewed vitality to agriculture through the synthesis of existing technologies and the introduction of new crops. Likewise, the arrival of Islam does not appear to have radically altered the existing routes of international trade. What does change from the late second/eighth century onward is the volume of traffic. The presence of Far Eastern stonewares in the Middle East, *dirham* hoards in Scandinavia and Iraqi glazed ceramic bowls in locations as dispersed as Spain, East Africa, Sri Lanka and China attests to the vibrancy of commercial exchange in this new era.

Conclusion: From formative Islam to classical Islam

CHASE F. ROBINSON

The ancient and Late Antique history of Eurasia could be reasonably (if not generously) characterised as a series of experiments in assembling communities through two sometimes complementary, contradictory or overlapping processes. The first was unambiguously political: building states and empires through conquest and some combination of occupation, emigration, colonisation, administration and exploitation. The other was ambiguously ideological, intellectual, spiritual and cultural: creating religious and philosophical systems of thought and conduct through some combination of inspiration, revelation, reflection and systematic teaching. Some 1,500 years or so after the end of Late Antiquity some of the religious and philosophical systems have proven more durable than the necessarily fragile political ones, in large measure because they have ridden the back of those strong polities: from Hellenism through Christianity to Confucianism, the biggest success stories feature ruling elites that offered robust sanction and patronage. What would Near Eastern history be like had the Sasanian shah Wahram I followed his predecessors in favouring, rather than imprisoning, Mani (d. 276)? The opposite scenario poses questions too. How would Chinese history appear had the Song failed to oversee the rise of Neo Confucianism?

What is clearer is that only in the seventh and eighth century Near East did the two processes of community building fully synchronise and thereby inaugurate what was arguably one of the most creative stages of human history. This synchronicity – early Muslims were founders of both world empire and world religion, possessors of both power and truth¹ – is perhaps the most striking feature of Islamic history. As readers of this volume now know well, in the short space of a century the Arabs moved from the political and cultural margins of the Late Antique Fertile Crescent to the centre of Eurasia's political stage. Arguably the least promising environment for state

1 See P. Crone, *Medieval Islamic political thought* (Edinburgh, 2004), p. 16.

and empire building – the modest oasis settlements of western Arabia, which remained largely outside the influence of successive Byzantine, Sasanian and South Arabian imperialists who quite reasonably invested their moneys and armies elsewhere – produced Late Antiquity's most dynamic movement of organised expansion and rule.

It is difficult to exaggerate the scale and speed of the achievement or the role of exceptionally visionary and able leaders in realising it. We saw in chapter 5 how, in about a decade, Muḥammad extended his authority over most of the Arabian Peninsula, setting his polity on a policy of local expansion that his successors transformed into regional conquest. Given how quickly this happened, and also the divisions that appeared when the movements of conquest slowed, expansion seems to have been essential to the nascent polity's survival. For the most part, conquest destruction was restrained and, at least in some respects, discretionary: low- and mid-level bureaucratic functionaries were preserved so as to ensure fiscal continuity, and the material evidence shows continuities at other levels too. Having destroyed the Sasanian and dismembered the Byzantine empires in the middle of the seventh century, by the second decade of the eighth Muslim rulers shared continental hegemony with Eurasia's other great superpower, the Tang, whose armies they would defeat a generation later on the Talas river. Aside from inaccessible (and unattractive) pockets of mountainous and desert-filled regions, the Umayyad caliphs, necessarily relying on a variety of intermediaries, proxies and local elites, thus ruled territories that stretched all the way from the Atlantic to the Oxus. Stitched together by an increasingly uniform and centralising administration that took hold in the late seventh century, the lands formed in the first instance an enormous catchment area for agricultural revenues, since they conjoined the fertile soils of Byzantine Africa and Egypt with those of Sasanian Mesopotamia and Khurasan. The tax bases of the two great powers of Late Antiquity were now funding the single state that succeeded them both. At the same time, the caliphate also functioned as a grid of interlocking networks of land-based and seaborne trade, which funnelled goods (especially through the Indian Ocean and across Central Asia), peoples, ideas and technologies into and through the cities of Iraq and Syria.

The revolutionaries who brought the 'Abbasids to power in 750 did so with a programme that called for the restoration of just rule by members of the Prophet's family, but the architects of that state worked with the ingredients they had to hand. They inherited Umayyad institutions and accelerated the Marwanids' move towards an increasingly complex, centralised and fully Arabic administration. The eastward move of the capital from Syria to

Baghdad also symbolised some changes to Umayyad practices of rule. Brought to power by eastern armies, and heirs to an easterly oriented political tradition in Iraq, they broke from Umayyad tradition by building fixed and huge capital cities in the Iraqi heartland. They also greatly increased the recruitment of Central Asian retainers, eventually placing them at the very centre of the state's military establishment. Meanwhile, they were content to let the Mediterranean west rule itself under dynasties that respected, acknowledged or largely ignored their sovereignty, provided they did not directly and effectively challenge it; in any case, we saw in chapter 14 that Umayyad rule in al Andalus appears to have been unprofitable. So instead of trying presumably vainly to reconstitute imperial power that had dissolved in al Andalus and North Africa in the 740s, the 'Abbasids chose instead to concentrate their energies on consolidating and expanding in the east, thus challenging regions that had resisted Umayyad rule from within (such as Tabaristan) or had managed to remain outside it (such as much of Transoxania). Yet here too 'Abbasid rule did not necessarily mean direct rule, and although much of the symbolism and rhetoric of empire would have had its subjects believe otherwise, already at what is often considered to be the height of 'Abbasid absolutism (the reign of Harun al Rashīd, 786–809), delegation to clients, especially on the empire's periphery, was a rule. But the lines between temporary delegation, structural devolution, alienation and usurpation were blurry, and the loyalty of these clients was more effectively retained when Baghdad could project power and authority than when it could not; given any slack by temporary instability in the capital, provincial elites were often inclined to wander towards self reliance,² and by the end of the ninth century the two institutions originally designed for the task of enforcing centralised rule – the army and the office of the caliphate – were no longer fit for the purpose. Empire had been reconfigured as commonwealth, as chapters 8 and 9 have shown. From this perspective, one of the 'Abbasids' solutions to the logistical problem of ruling a huge empire emerged as one of the underlying causes of its dissolution in the tenth century.

Be this as it may, in both its late Umayyad and early 'Abbasid forms the caliphate was the most spectacular instalment of Mediterranean and Near Eastern empire building between the Achaemenids, about a millennium earlier, and the Ottomans, about half a millennium later. And all this, of course, the Arabs accomplished as Muslims, who, following in the footsteps of a

² See H. Kennedy, 'Central government and provincial elites in the early 'Abbasid caliphate', *BSOAS*, 44 (1981).

visionary and reforming monotheist prophet, conquered and ruled for explicitly religious reasons. The caliphate was a political and military unit, but one that was assembled by believer soldiers inspired to fight for God and His Prophet, and mustered and coordinated by men who had pledged their allegiance to a 'commander of the faithful' – the caliph, God's representative on earth. (The title is attested already in the reign of Mu'awiya.) The Muslims' victories came quickly in part because their adversaries appear in at least some respects to have been weakened, and in part because their conviction to 'strive' for God – to make their belief manifest by carrying out *jihad* – was so strong: it seems to have been as intrinsic to belief as any other religious duty. Islam was made sovereign over all other religions, and non Muslim monotheists (the category was interpreted generally so as to include Zoroastrians) were forced at least in theory to make open acknowledgement of their subordinate status as 'protected peoples'. They may have been second class citizens in a theocracy designed to preserve Muḥammad's vision, but they were citizens with legally enforceable rights all the same, and the continuing vitality of non Muslim communities within the multi ethnic and religiously pluralist caliphate goes some way towards explaining its cultural creativity.³

So what made the state Islamic was not a majority population of Muslims, which would take some centuries to achieve; it was the state's purpose and design. Most important, the polity institutionalised in the caliphal office the Prophet's role as commander, leader and legislator – a strikingly concentrated portfolio of authority that owes its origins to the Late Antique Christian and Arabian tribal traditions out of which it emerged. As the state grew in size and complexity, successive caliphs naturally delegated their effective power to governors, tax agents, commanders, judges and the like, all of whom wielded legitimate power only in so far as they served God's caliph on earth. In this way society was aligned with God's will as Muslims understood it through the Qur'an and the cultural memory of the earliest community. Other transformations were at work too: as society grew more complex, especially through conversion and acculturation, the social and religious authority of late eighth and ninth century caliphs leached into its soil, producing in the short term legal authorities who rationalised and codified legal practice with reference to a past that they claimed to preserve and interpret. By the tenth century, with accounts of the failed *miḥna* of the 830s and 840s serving to

3 For one discussion of the traditional literature, see Y. Friedmann, *Tolerance and coercion in Islam: Interfaith relations in the Muslim tradition* (Cambridge, 2003).

underline the Traditionists' victory over the caliphs and their embrace of Ḥanafī rationalism,⁴ it was the rare caliph who ventured into religious debates, which were taking place independently of state institutions. For all but those with revolutionary commitments (most significantly, Ismaʿīlī Shīʿa who, in the late ninth century, inherited the Kharijite mantle as the caliphs' most activist critics, rejecting 'Abbasid claims altogether), the caliphs now functioned as the symbolic centre of the 'abode of Islam', an unbroken dynasty of ruler imams that linked the problematic present to the glorious and inspired first phase of the community's history. As such, the 'Abbasid caliphs legitimised, conventionally through increasingly archaic rituals and tokens of delegation, those who held de facto power in the provinces.

As much as it conditioned a social order, the caliphate also functioned as a greenhouse for cultivating the Islamic religious tradition. This was especially the case in the fast growing towns and cities of Arabia and Iraq, where patronage was offered by the caliphs, their governors and their courts; meanwhile, non state wealth deriving from landowning and mercantile activity promoted the accumulation, specialisation and professionalisation of knowledge more generally. By the early 'Abbasid period the means (including the wide availability of paper) were thus in place for an explosion of learning.⁵ So, too, were the reasons. For as memories of the foundational periods of prophecy and conquest faded, and as Arab Muslims settled and mixed with non Arabs in provinces that were at great geographical and cultural distances from Arabia, new bridges had to be built to a past that was at once increasingly remote from, and increasingly significant for, Arab and Muslim identity. Eighth century Muslims disagreed about whether the Qur'an fully preserved Muḥammad's revelations, about how it was transmitted or exactly what a given word or passage in the text might mean, but they all agreed that there *was* to be such a text, and, moreover, that it was now closed.⁶ (This is a considerable achievement: in producing and then closing their scripture so quickly, Muslims telescoped into perhaps as few as five or six decades a process that Jews and Christians took centuries to accomplish.) Similarly, they disagreed about what had happened in 632 or 656 such that they even

4 For two accounts focusing on the Traditionist hero Aḥmad ibn Hanbal, see N. Hurvitz, *The formation of Ḥanbalism: Piety into power* (London, 2002); and C. Melchert, *Aḥmad ibn Hanbal* (Oxford, 2006).

5 A summary account of paper's introduction into the Middle East can be found in H. Loveday, *Islamic paper: A study of the ancient craft* (London, 2001), ch. 2.

6 There is a great deal of literature, but, despite its title, an enormous amount of ground is covered in H. Modarressi, 'Early debates on the integrity of the Qur'an: A brief survey', *SI*, 77 (1993).

took up arms, but they all agreed that a given set of events *was* important, and that the battles over the past should take place as much (or more) in books of history, exegesis and law as they should in the field. The conspicuous exception aside, Muslim historians very rarely suppressed embarrassing facts, generally choosing instead to discredit them or obscure them in mountains of alternatives.⁷

How things had been, and what they meant for the present and future, were thus both 'academic' and fiercely political concerns. Of course, the impulse to record, classify, interpret, elaborate and argue was not just driven by curiosity, professional ambition or intra Muslim debate, although such 'internalist' factors can be adduced for fields of knowledge (such as theology) that one would usually assume to have roots outside the Islamic community itself.⁸ Living in cities and towns that typically accommodated large non Muslim populations, scholars often rubbed shoulders with transmitters of Classical and Late Antique traditions and techniques of learning that were much deeper and more richly developed than their own. As it happens, many learned men (and women) fully a third, by one measure were non Arab converts to Islam.⁹ Fuelled as they were by the confidence and enthusiasm that came with a newly revealed truth, along with the privilege and favour (both direct and indirect) that came with Islamic rule, Muslims argued with non Muslim adversaries when they felt it necessary, appropriated of their tools what they needed, ignored what they did not, and so made up the cultural deficit by consistent industry and occasional brilliance. (Volume 4 of this series charts some of this very rich history.) The social context of learning, teaching and the transmission of ideas is as much as unrecoverable for nearly all of the first century of Islam, after which things improve unsteadily; in the late eighth and ninth centuries we have recognisable schools of thought in several disciplines (such as grammar, law, theology and history), some crystallising (or starting to crystallise) around master eponyms who had taught, more or less formally or informally, in mosques and houses. Not surprisingly, Iraq in general, and Baghdad especially, were hugely

7 On the early historical tradition in general, see F. M. Donner, *Narratives of Islamic origins: The beginnings of Islamic historical writing* (Princeton, 1998); and C. F. Robinson, *Islamic historiography* (Cambridge, 2003).

8 The standard work is J. van Ess, *Theologie und Gesellschaft im 2. und 3. Jahrhundert Hidschra: Eine Geschichte des religiösen Denkens im frühen Islam*, 6 vols. (Berlin, 1991–7); for a review of the influences on theology, see S. Rissanen, *Theological encounter of Oriental Christians with Islam during early Abbasid rule* (Turku, 1993).

9 Thus J. Nawas, 'A profile of the *mawālī* 'ulama'', in J. Nawas and M. Bernards (eds.), *Patronage and patronage in early and classical Islam* (Leiden, 2005); cf., however, H. Motzki, 'The role of non Arab converts in the development of early Islamic law', *Islamic Law and Society*, 6 (1999).

productive of these teachers.¹⁰ What is clearer is that a tidal wave of book writing in a wide variety of disciplines and genres began to rise in the late eighth century, especially in the law, whose increasingly traditionalist character exercised much of the gravitational force: 'Individual teachers the traditionalists would not trust: what they wanted was an inspired textual basis for doctrine and practice.'¹¹ Late ninth century Baghdad, along with Tang Chang an, was becoming what must have been the most literate city in the world.¹²

That the Islamic religious tradition grew so explosively hardly means that it was fixed early on, despite the tradition's assumptions (and frequent assertions) that ideas, practices and institutions current in the ninth and tenth centuries were inspired or established by the Prophet, his contemporaries or immediate followers in the seventh. Instead, it took some time for the dust of this explosion to settle and for the ideas, practices and institutions to come on line; early Muslims were creatively faithful to the past, rather than dogmatically reverential towards it. To signify the very considerable differences between the earliest and subsequent phases of Islamic intellectual history, some Islamicists draw a distinction between the 'formative' and 'classical' periods. Periodisation is always imperfect, but the distinction is heuristically valuable because it reminds one that early Islam conforms to the broad patterns of religious history of Antiquity and Late Antiquity, when, far from being fully formed at birth, monotheist communities defined and organised themselves over time and in relation to other monotheist communities. Since these developments figure only marginally in the previous chapters, we might usefully outline in only very schematic terms the shape of these changes.

Here it is immensely important to see the tradition's assumptions and assertions for what they are. The very traditionalism that framed the experience of the first generation as necessarily paradigmatic for subsequent generations is itself a development of the mid to late eighth century;¹³ and only a century later did this development culminate, when accounts of the Prophet's conduct came to hold a virtual monopoly on the market of precedents, elbowing aside

10 Thus an entire volume (III) of van Ess's *Theologie und Gesellschaft* is devoted to Baghdad, about 850–950; see also D. Gutas, *Greek thought, Arabic culture: The Graeco Arabic translation movement in Baghdad and early 'Abbasid society (2nd–4th/8th–10th centuries)* (London and New York, 1998).

11 C. Melchert, *The formation of the Sunni schools of law, 9th–10th centuries CE* (Leiden, 1997), p. 14.

12 For some sense of this culture, see S. Toorawa, *Ibn Abī Tāhir Tayfur and Arabic writerly culture* (London and New York, 2005); and M. Cooperson and S. Toorawa (eds.), *Arabic literary culture, 500–925, Dictionary of Literary Biography*, vol. CCCXI (Detroit, 2005).

13 See, for example, G. H. A. Juynboll, 'Some new ideas on the development of *sunna* as a technical term in early Islam', *JSAI*, 10 (1987).

other authorities (especially his contemporaries, the 'Companions', their Followers and early 'Abbasid jurists). In this way, practices that owed their origins to extra Arabian legal systems – especially varieties of Jewish and Roman law, no single tradition remaining uninfluenced by others – were naturalised into Islam and legitimised by Prophetic sanction.¹⁴ (Such was the Sunnī formulation; the Imamī Shī'a endowed their imams with this paradigmatic authority.) This – the secondary emergence of the doctrine of Prophetic precedent (*sunna*) and its elevation to a governing principle of jurisprudence, along with the accompanying coining of traditions ascribed to the Prophet – is the single best documented case of the retrofitting of late Umayyad and 'Abbasid era ideas onto seventh and early eighth century history. But there are many others. For example, closely related to the dogma of the Companions was the view, which came to be shared by the emerging Sunnī orthodoxy of the ninth century,¹⁵ that there were four 'rightly guided caliphs' (Abu Bakr, 'Umar, 'Uthman and 'Alī), all considered legitimate rulers, though some held that they were of declining merit. The formulation is nearly as ubiquitous in the secondary literature of early Islam as it is in the primary sources. Even so, it would have made little or no sense to these caliphs or their partisans, whose loyalties tended to be exclusive and whose polemics could be brutal, or indeed to most anyone else who actually lived during the seventh and eighth centuries.

The secondary appearance of this doctrine makes good sense because the political culture of early Islam was thoroughly adversarial. Above I emphasised the great speed of political and cultural change over the first three centuries, but I have understated just how deeply contentious and controversial things were to those experiencing that change. Despite the generally eirenic and triumphalist narratives that fill the surviving (and overwhelmingly Sunnī) sources of the late ninth and tenth centuries, a great deal of early Islamic history was made by men whose commitments and convictions were far too deep to allow them much room for negotiating consensus and unity. Although most agreed on the caliph's function, there were deep divisions about who was qualified to hold the office and what the necessary qualifications should be to hold it; and since obedience to the right imam was widely

¹⁴ The literature is enormous, but a clear statement can be found in P. Crone, *Roman, provincial and Islamic law: The origins of the patronate* (Cambridge, 1987); U. Mitter, 'Origin and development of the Islamic patronate', in Nawas and Bernards (eds.), *Patronate and patronage in early and classical Islam*; P. Crone, 'Jahili and Jewish law: The *qasama*', *JSAI*, 4 (1984); M. Cook, 'Early Islamic dietary law', *JSAI*, 7 (1986); cf. N. Calder, *Studies in early Muslim jurisprudence* (Oxford, 1993), esp. pp. 209ff.

¹⁵ See, for example, Crone, *Medieval Islamic political thought*, pp. 134f.; cf. E. Kohlberg, 'Some Imamī Shī'ī views on the *ṣaḥāba*', *JSAI*, 5 (1984).

regarded as salvific, the stakes could not have been higher.¹⁶ We saw in chapter 5 that, by any reasonable reading of the evidence, Ibn al Zubayr was as close as the Islamic community had to a caliph from 683 to 692, for all that the later tradition presents him as a heretic, rebel or 'counter caliph'. Exclusive political and religious loyalties divided partisans of 'Alī from those of 'Uthman (and vice versa), Umayyads from 'Abbasids, Kharijites and so forth. Although it is perfectly true that some (such as the Murji'a) chose to 'suspend judgement' about the fate of the first two caliphs in the Hereafter, this hardly stopped them from taking active part in the political controversies of the day.¹⁷

Why was the political culture of early Islam so adversarial – indeed, so revolutionary? We began the volume with an account of Baghdad's founding and city plan, which put the all powerful caliph at the symbolic centre, the 'Round City', of a world bestriding empire, and gave physical expression to the early Islamic fusion of right belief and political power: authority was concentrated in salvific imams who occupied an office established by God in order to establish His rule the world over. One accordingly expects to find a political culture that was highly centripetal – and that is exactly what one finds. As we have seen, it is not merely that elite politics was conducted in Iraq, its capitals and courts, or that Iraq produced a disproportionate number of the most articulate spokesmen and critics and learned culture more generally, or even that the provinces' fates were invariably conditioned by political and military conditions prevailing in or around Baghdad. It is also that the radical model marrying belief and power fostered radical movements of opposition. Far more than secession, seclusion, much less indifferent individuality or Qumran like withdrawal, it engendered organised rebellion for the purposes of reforming or replacing wayward caliphs who abused their power.

And all of this is just to mention the *explicitly* politico religious issues that divided early Muslims. Other issues appear more narrowly intellectual or academic, and may appear to us now as only *implicitly* political; but this hardly made them any less contentious. I have already alluded to one such conflict among those specialising in the law, the *aṣḥab al ḥadīth* (the Traditionists) and

16 P. Crone and M. Hinds, *God's caliph: Religious authority in the first centuries of Islam* (Cambridge, 1986).

17 See, for examples, W. Madelung, 'The early Murji'a in Khurasan and Transoxiana and the spread of Ḥanafism', *Der Islam*, 59 (1982); M. Cook, 'Activism and quietism in Islam: The case of the early Murji'a', in A. Cudsi and A. E. Dessouki (eds.), *Islam and power* (London, 1981); and S. S. Agha, 'A viewpoint on the Murji'a in the Umayyad period: Evolution through application', *Journal of Islamic Studies*, 8 (1997).

the *aṣḥab al ra'y* (the Rationalists). Since what was at stake here was nothing less than the authority to determine the law, the bitterness between the two parties is difficult to exaggerate. Of course holding scripture – that is, both the *sunna* and the Qur'an – to be authoritative did not exhaust potential scripturalist positions: some held that the Qur'an alone was authoritative.¹⁸ In sum, what is characteristic of the 'formative' period of Islam is its very contentiousness, its controversies and unsettled questions: What constituted individual belief? How was one to know God's law? Where were the limits of community to be drawn? Who was to rule and by what qualifications? These and other questions were frequently asked, and although answers were given, they did not command broad agreement.

If the outstanding features of early Islam were the number and depth of some of its disagreements, those of the 'classical' period can be said to have been greater consensus – there is now a clearer sense of what constituted belief and membership in the community of Islam and its constituent sub-communities – as well as the (closely related) emergence of a traditionalist based 'orthodoxy' itself. For in the end – that is, towards the end of the ninth century, which can reasonably mark the end of 'formative' Islam – it would be traditionalism that would dominate, imprinting its values not only on jurisprudence, but also on theology, historiography and other disciplines and fields as well.¹⁹

The 'four caliph' theory is as good an example as any for the changes under way. By admitting 'Alī and 'Uthman respectively into the fold of legitimacy, partisans for 'Uthman and for 'Alī alike were burying the hatchet, exchanging exclusive partisanship for the unity of the community. In various forms, this accommodating narrative colonised historiography; the sources thus record not the story of competing communities, most holding the others misguided and unsaved, but that of a single community riven by civil war, rebellion and dissension. The emergence of another numbered doctrine, that of the 'five pillars' of Islam (witnessing faith, charity, prayer, pilgrimage and fasting) has a more complicated and less well understood history. Still, in this pithy 'classical' form, which omits *jihad* and sets an inclusively low threshold for faith that turns principally on the discharge of ritual acts, it also reflects 'classical' concerns, which is why it too dates from no earlier than the late ninth

¹⁸ M. Cook, 'Anan and Islam: The origins of Karaite scripturalism', *JSAI*, 9 (1987).

¹⁹ W. Graham, 'Traditionalism in Islam: An essay in interpretation', *Journal of Interdisciplinary History*, 23 (1993).

century.²⁰ Allegiance to a salvific imam has been eclipsed by adherence to the law that had been articulated in traditionalist terms by the scholars. In time the ascendance of Sunnī traditionalism would be institutionalised in the form of four schools of jurisprudence (Malikī, Shafi‘ī, Ḥanbalī and Ḥanafī, each named after an eighth or early ninth century eponym), which, in offering mutual recognition to each other, contrast sharply with some of the bitter polemics associated with their purported founders.²¹

As faith and the law were being reconfigured, identity was too. In fact, the embrace of the ‘four caliph’ doctrine was part of the process by which Sunnism emerged in its classical form, moving from a largely undefined set of implicit assumptions into a discrete body of beliefs and an increasingly sharply edged mode of communal identity that claimed the orthodox centre. The process extended into the tenth and eleventh centuries, when Sunnism became a rallying cry for weakened caliphs within Baghdad and powerful dynasts outside it, and it took place alongside, and in interaction with, the maturation of Imamī Shī‘ism. Compared to Sunnism, modalities of Shī‘ite identity and thought are rooted more deeply in early Islam because, as opponents of the state, those who favoured ‘Alī’s claims more clearly defined their views; some essential Imamī ideas and institutions, for example, do seem to belong to the mid to late eighth century.²² But the fact remains that it took the occultation of the twelfth imam and its aftermath in the tenth and eleventh centuries to produce, under direct and indirect Buyid patronage, not only many institutions of Imamī popular piety,²³ but also the full emergence of a scholarly elite that promoted its own brand of traditionism. As much as Buyid era Sunnī jurists had to come to terms with a caliphate whose power had been usurped, Shī‘ite jurists had to come to terms with the stubborn endurance of a Sunnī caliphate.

The solution that emerged was coexistence: the absence of the imam was taken to mean that the obligation to realise God’s will politically (through revolution or secession) could instead be realised intellectually and socially, by putting in place institutions and hierarchies that framed and guided an Imamī community within a non Shī‘ite state. Here, as in the Sunnī case, adherence to

20 For one discussion, see W. C. Smith, ‘Arkan’, in D. P. Little (ed.), *Essays on Islamic civilization presented to Niyazi Berkes* (Leiden, 1976).

21 For an overview, see Melchert, *The formation of the Sunni schools of law*.

22 See, for example, H. Modarressi, *Crisis and consolidation in the formative period of Shi‘ite Islam: Abu Ja‘far ibn Qiba al Razi and his contribution to Imamite Shi‘ite thought* (Princeton, 1993); for an overview, Crone, *Medieval Islamic political thought*, pp. 111ff.

23 See chapter 9 above, and, more generally, H. Halm, *Shi‘ism*, 2nd edn (Edinburgh, 2004), pp. 38ff.

the tradition and the law thus became the standard. It is true that some Shī'a opted out of this co-optation and autonomy within the Sunnī state, stubbornly holding on to a revolutionary programme that the Imamīs had abandoned in the ninth century by rationalising in quietist terms the disappearance and continued absence of the imam. The programme was now preached by those either propagandising for, or claiming to embody, the imams of the Isma'īlī line; as we have seen, they had some real success, particularly in North Africa and Arabia. But the imams' charisma could routinise fairly quickly (as it did in the Faṭimid case), and when it did not, it could lead (as it did in the Nizārī case) to movements that were as futile as they were spectacular. Not only did the Isma'īlī experiments in revolutionary state building fail in the end, but the tenth century also witnessed the final disappearance of what was arguably the most potent opposition movement of early Islam, the Kharijites, who had receded to the peripheries (eastern Iran and the far west) during the ninth. The age of widespread revolutionary ideas seems to have closed – at least until the aftermath of the Mongol conquests and rule in the thirteenth and fourteenth centuries, which reordered the eastern lands of the Islamic world.

What explains these changes? As much as intellectual and cultural traditions can bear the signs of a centralising, imperial state, so too can they reflect the disintegration or reconfiguration of such imperial states.²⁴ This volume's chronological survey ends with caliphs being held under something close to house arrest by Daylamī commanders, and with Baghdad in decline, now merely one of three capitals of the Buyids' confederated state, which was itself just one of several states that had replaced the empire. Baghdad and its centripetal political culture belonged to the past; belief was increasingly a matter of tradition-based law, and the production of high culture took place increasingly in what had been its provinces. Although some caliphs would exercise a measure of influence over the political life of the late 'Abbasid period, and forms of Shī'ism provided a language of state building in the short term, the future lay in a multiplicity of Sunnī states, capitals and ruling courts, all following trajectories that were largely independent of Baghdad. These could offer sporadic patronage to peripatetic scholars, authors and poets (such as Ḥamdānī Aleppo or Mosul), or the deeper soil in which new traditions of learning could flourish (such as Imamī Qumm). At the same time, they produced rulers whose legitimacy derived not only from fictional devolution from weakened 'Abbasid caliphs, but also from practices and traditions that complemented or challenged the symbols of 'Abbasid sovereignty. Rulers in

24 Cf. D. McMullen, *State and society in T'ang China* (Cambridge, 1989).

Iran (such as the Buyids and Samanids) could tap into ancient Persian symbols of sovereignty, while rulers on the frontiers (such as the Ghaznavids or Marīnids) could prove their credentials by carrying out *jihad*. Meanwhile, Islamic societies in the west and east had become increasingly divergent in their politics (how they became so is described in volumes 2 and 3). Beneath all this diversity, however, a basic grammar of Islamic rule and belief was now in place. The Crusaders might have wished it otherwise, but Islam had taken irreversible hold on the Middle East.

Glossary

' <i>abd</i>	servant; slave; appears often in names, e.g. 'Abd Allah (lit. 'servant of God')
Abu	'father', appears often in construct in names, e.g. 'Abu Bakr' (lit. 'Father of Bakr')
Abna'	'sons' (<i>abna'</i> ; sing. <i>ibn</i>), but in 'Abbasid political terminology, 'sons of the state (or dynasty)', that is, the soldiers and commanders who brought the 'Abbasids to power
<i>ahl</i>	people; family; <i>ahl al bayt</i> , 'members of the (Prophet's) family'
' <i>amil</i>	administrator; financial controller; governor
<i>amīr</i>	commander, governor, leader; thus <i>amīr al mu'minīn</i> ('commander of the believers', caliphal title); <i>amīr al umara'</i> ('commander of commanders', title for military rulers of tenth and eleventh centuries)
<i>amṣar</i>	see <i>miṣr</i>
<i>aṣṣar</i>	'helpers' (of Muḥammad): the tribesmen of Medina who embraced Muḥammad
<i>ashraf</i>	(sing. <i>sharīf</i>) tribal chiefs; descendants of Muḥammad
' <i>atā</i> '	military pay; stipend, gift or pension
<i>banu</i>	'sons of', used in construct with tribal names, e.g. Banu Taghlib (the 'Taghlib (tribe)')
caliph	(Ar. <i>khalīfa</i>) sovereign of the Islamic state; God's 'deputy' or 'representative'
<i>da'ī</i>	'one who carries out the <i>da'wa</i> ' ('call', 'propaganda' and, by extension, the clandestine phase of revolution), thus 'missionary'

<i>dar</i>	residence, abode; thus <i>dar al islam</i> ('the abode of Islam'), <i>dar al imara</i> (governor's residence)
<i>dawla</i>	dynasty; state; ('Abbasid) revolution
<i>dhimma</i>	protection granted by treaty; thus <i>ahl al dhimma</i> or <i>dhimmīs</i> or <i>dhimmiyun</i> 'protected peoples' those monotheists ('People of the Book') given protected status by Islamic states
<i>dirham</i>	silver coin; cf. <i>dīnār</i> (gold)
<i>dīwan</i>	register; administrative bureau; chancery; thus <i>dīwan al jaysh</i> (Bureau of the Army); <i>dīwan al dar</i> (Bureau of the Palace)
<i>dihqan</i>	village landlord; lower nobility; gentry
<i>fiqh</i>	(lit. 'understanding') Islamic jurisprudence; thus <i>faqīh</i> ('jurisprudent', 'jurist', pl. <i>fuqaha</i>)
<i>fitna</i>	in early Islamic political terminology, 'civil war', 'strife'; said of the first (656–61), second (683–92), third (744–49) and fourth (809–13) civil wars
<i>ghazī</i>	Muslim warrior, typically against non Muslims on the frontier
<i>ghulam</i>	(pl. <i>ghilman</i>) young man; slave; slave soldier
<i>ḥadīth</i>	tradition, especially by or about Muḥammad
<i>ḥajib</i>	chamberlain
<i>ḥajj</i>	the Pilgrimage
<i>hijra</i>	emigration: thus <i>dar al hijra</i> ('abode of emigration'); also sacred enclave
<i>Ibādī</i>	surviving branch of the Kharijites (<i>see below</i>)
<i>ibn</i>	son; e.g. Muḥammad ibn 'Abd Allah (Muḥammad, son of 'Abd Allah); <i>see also</i> Abu
<i>ijma'</i>	scholarly consensus
<i>imam</i>	religious (and Shī'ite political) leader; thus imamate (<i>imama</i> , the office of religious leadership) and Imamī (a Shī'ite of the Twelver persuasion)
<i>imam</i>	prayer leader
<i>iqṭa'</i>	(pl. <i>iqṭa'at</i>) land grant; concession (of revenue)
<i>jama'a</i>	community; communal practice
<i>jihad</i>	the 'struggle' on behalf of God; holy war

<i>jizya</i>	(poll) tax levied on ‘People of the Book’ (<i>see above</i> , <i>dhimma</i>)
<i>jund</i>	(pl. <i>ajnad</i>) army; district
<i>khaqan</i>	(Tur.) leader; ruler
<i>kharaj</i>	(land) tax
Kharijite	‘one who goes out (or against)’ in rebellion; member of a Kharijite sect
<i>khuṭba</i>	Friday sermon
<i>kura</i>	(pl. <i>kuwar</i>) administrative district
<i>mahdī</i>	‘rightly guided’; <i>al mahdī</i> (‘the rightly guided one; the Saviour’)
<i>mawla</i>	(pl. <i>mawalī</i>) client; in Umayyad usage, usually non Arab convert to Islam
<i>miṣr</i>	(pl. <i>amṣar</i>) military garrison; garrison city
<i>muhajirun</i>	‘those who emigrated’ (from Mecca to Medina with Muḥammad); <i>see also anṣar</i>
<i>qaḍī</i>	judge
<i>qaṣr</i>	(pl. <i>quṣur</i>) palace; estate
<i>qibla</i>	prayer direction (towards Mecca)
<i>ribat</i>	frontier fort or fortress
<i>ridda</i> wars	‘wars of apostasy’ that broke out upon Muḥammad’s death
<i>ṣaḥīb</i>	(pl. <i>aṣḥāb</i>) master; ruler; owner
Shī‘a	those who held that the imams were to be drawn from the Prophet’s family, eventually organised into three branches: Imamīs (Twelvers), Zaydīs and Isma‘īlīs
<i>sunna</i>	(adj. <i>sunnī</i> , lit. ‘path’); normative conduct as prescribed by Prophetic <i>ḥadīth</i>
Sunnī	Sunnite; majoritarian Muslim
‘ulama’	(sing. ‘ <i>alim</i> ’) those who possess ‘ilm (religious knowledge); people of learning; religious scholars
<i>umma</i>	‘community of believers’, the Muslim community
‘ushr	tithe
<i>wazīr</i>	vizier; minister
<i>zandaqa</i>	heresy

Bibliography

Introduction

- Acton, J. E. E. D. A. (Lord), *Lectures on modern history*, ed., J. N. Figgis and R. V. Laurence, London, 1906.
- Becker, A. H., *Fear of God and the beginning of wisdom: The School of Nisibis and the development of scholastic culture in Late Antique Mesopotamia*, Philadelphia, 2006.
- Bowersock, G. W., P. Brown and O. Grabar (eds.), *Late Antiquity: A guide to the post classical world*, Cambridge, MA, 1999.
- Brown, P., *The world of Late Antiquity*, London, 1971.
- Bulliet, R., *Islam: The view from the edge*, New York, 1994.
- The patricians of Nishapur: A study in medieval Islamic social history*, Cambridge, MA, 1972.
- Cameron, A., B. Ward Perkins and M. Whitby (eds.), *The Cambridge ancient history*, vol. XIV: *Late Antiquity: Empire and successors, AD 425–600*, Cambridge, 2000.
- Chalmers, P., *Invasión e islamización: La sumisión de Hispania y la formación de al Andalus*, Madrid, 1994.
- Cobb, P., *White banners: Contention in 'Abbasid Syria, 750–880*, Albany, 2001.
- Crone, P., *Meccan trade and the rise of Islam*, Princeton, 1987; repr. Piscataway, NJ, 2004.
- Slaves on horses: The evolution of the Islamic polity*, Cambridge, 1980.
- Crone, P., and M. Cook, *Hagarism: The making of the Islamic world*, Cambridge, 1977.
- Daniel, E., *The political and social history of Khurasan under Abbasid rule, 747–820*, Minneapolis and Chicago, 1979.
- Fowden, E. K., *The barbarian plain: Saint Sergius between Rome and Iran*, Berkeley and Los Angeles, 1999.
- Fowden, G., *Empire to commonwealth: Consequences of monotheism in Late Antiquity*, Princeton, 1994.
- Gil, M., *A history of Palestine, 634–1099*, Cambridge, 1992.
- Goldziher, I., *Muhammedanische Studien*, Halle, 1889–90, trans. S. M. Stern and C. R. Barber as *Muslim Studies*, London, 1967–71.
- Greatrex, G., *Rome and Persia at war, 502–535*, ARCA Classical and Medieval Texts, Papers and Monographs 37, Leeds, 1998.
- Haldon, J. F., *Byzantium in the seventh century: The transformation of a culture*, rev. edn, Cambridge, 1997.
- Harvey, S. A., *Asceticism and society in crisis: John of Ephesus and the Lives of the Eastern Saints*, Berkeley, 1990.
- Heidemann, S., and A. Becker (eds.), *Raqqa II: Die islamische Stadt*, Mainz am Rhein, 2003.

- Herrin, J., *The formation of Christendom*, Princeton, 1987.
- Hoyland, R., *Seeing Islam as others saw it: A survey and evaluation of Christian, Jewish and Zoroastrian writings on early Islam*, Princeton, 1997.
- Irwin, R., *For lust of knowing: The Orientalists and their enemies*, London, 2006; published in the USA as *Dangerous knowledge: Orientalism and its discontents*, Woodstock and New York, 2006.
- Kennet, D., 'The decline of eastern Arabia in the Sasanian period', *Arabian Archaeology and Epigraphy*, 18 (2007), pp. 86–122.
- Liebeschuetz, J. H. W. G., 'Late Antiquity and the concept of decline', *Nottingham Medieval Studies*, 45 (2001), pp. 1–11.
- Macfie, A. L., *Orientalism: A reader*, New York, 2000.
- Manzano Moreno, E., *Conquistadores, emires y califas: Los omeyas y la formación de al Andalus*, Barcelona, 2006.
- Martin, R., 'Qu'est ce que l'antiquité tardive?' in R. Chevallier (ed.), *Aïôn: le temps chez les romains*, Paris, 1976, pp. 261–304.
- Morony, M., *Iraq after the Muslim conquest*, Princeton, 1984.
- Noth, A., *Quellenkritische Studien zu Themen, Formen und Tendenzen frühislamischer Geschichtsüberlieferung*, Bonn, 1973, trans., rev. and expanded by A. Noth and L. I. Conrad as *The early Arabic historical tradition: A source critical study*, Princeton, 1994.
- Robinson, C. F., *Empire and elites after the Muslim conquest: The transformation of northern Mesopotamia*, Cambridge Studies in Islamic Civilization, Cambridge, 2000.
- Said, E., *Orientalism*, New York, 1978.
- al Ṭabarī, Abu Ja'far Muḥammad ibn Jarīr, *Ta'rikh al rusul wa'l muluk*, ed. M. J. de Goeje et al., 15 vols. in 3 series, Leiden, 1879–1901.
- Walker, J., *The legend of Mar Qardagh: Narrative and Christian heroism in Late Antique Iraq*, Berkeley and Los Angeles, 2006.
- Wansbrough, J., *Quranic studies: Sources and methods of scriptural interpretation*, Oxford, 1977.
- The sectarian milieu: Content and composition of Islamic salvation history*, Oxford, 1978.
- Wendell, C., 'Baghdad: *Imago Mundi* and other foundation lore', *IJMES*, 2 (1971), 99–128.
- Wickham, C., *Framing the early Middle Ages: Europe and the Mediterranean, 400–800*, Oxford, 2005.

Chapter 1: The resources of Late Antiquity

Practical suggestions for further reading

- Belke, K., and F. Hild, J. Koder and P. Soustal (eds.), *Byzanz als Raum. Zu Methoden und Inhalten der historischen Geographie des östlichen Mittelmeerraumes*, Denkschriften der Österreichischen Akademie der Wissenschaften, philosophisch-historische Klasse 283, Vienna, 2000.
- Cameron, A., and P. Garnsey (eds.), *The Cambridge ancient history*, vol. XIII: *The late empire, AD 337–425*, Cambridge, 1998.
- Cameron, A., B. Ward Perkins and M. Whitby (eds.), *The Cambridge ancient history*, vol. XIV: *Late Antiquity: Empire and successors, AD 425–600*, Cambridge, 2000.
- Carter, F. W. (ed.), *An historical geography of the Balkans*, London, San Francisco and New York, 1977.

Bibliography

- Chavarría, A., and T. Lewit, 'The Late Antique countryside: A bibliographic essay', in W. Bowden, L. Lavan and C. Machado (eds.), *Recent research on the Late Antique countryside*, Leiden, 2004, 3–51.
- Christensen, P., *The decline of Iranshahr: Irrigation and environments in the history of the Middle East, 500 BC to AD 1500*, Copenhagen, 1993.
- Fisher, W. B. (ed.), *The Cambridge history of Iran*, vol. I: *The land of Iran*, Cambridge, 1968.
- Foss, C., 'The Near Eastern countryside in Late Antiquity: A review article', in J. Humphrey (ed.), *The Roman and Byzantine Near East*, vol. II: *Some recent archaeological research*, JRA Supplementary Series 31, Portsmouth, 1995, 213–34.
- Gyselen, R. (ed.), *Contributions à l'histoire et la géographie historique de l'empire sassanide*, Res Orientales 16, Bures sur Yvette, 2004.
- Horden, P., and N. Purcell, *The corrupting sea: A study of Mediterranean history*, Oxford, 2000.
- King, G. R. D., and A. Cameron (eds.), *The Byzantine and early Islamic Near East*, vol. II: *Land use and settlement patterns*, Princeton, 1994.
- Kingsley, S., and M. Decker (eds.), *Economy and exchange in the east Mediterranean during Late Antiquity*, Oxford, 2001.
- McCormick, M., *Origins of the European economy: Communications and commerce, AD 300–900*, Cambridge, 2001.
- Morony, M. G., *Iraq after the Muslim conquest*, Princeton, 1984; repr. Piscataway, NJ, 2006.
- Simpson, St J., 'From Tekrit to the Jaghjagh: Sasanian sites, settlement patterns and material culture', in K. Bartl and S. R. Hauser (eds.), *Continuity and change in northern Mesopotamia from the Hellenistic to the early Islamic period*, Berlin, 1996, 87–126.
- Wagstaff, J. M., *The evolution of the Middle Eastern landscapes*, Canterbury, 1984.
- Wickham, C. J. *Framing the early Middle Ages: Europe and the Mediterranean, 400–800*, Oxford, 2005.
- Yarshater, E. (ed.), *The Cambridge history of Iran*, vol. III: *The Seleucid, Parthian and Sasanian periods*, Cambridge, 1983.

Secondary sources

- Adams, R. M., *The land behind Baghdad: A history of settlement on the Diyala plains*, Chicago and London, 1965.
- Alcock, S., *Graecia capta: The landscapes of Roman Greece*, Cambridge, 1993.
- Avramea, A., *Le Péloponnèse du IV^e au VIII^e siècle: Changements et persistances*, Paris, 1997.
- Banaji, J., *Agrarian change in Late Antiquity: Gold, labour and aristocratic dominance*, Oxford, 2001.
- Barthold, V., *Turkestan down to the Mongol invasion*, London, 1928.
- Baruch, U., 'The late Holocene vegetation history of Lake Kinneret (Sea of Galilee)', *Palaeorient*, 12 (1986), 37–48.
- Beaumont, P., G. H. Blake and M. Wagstaff, *The Middle East: A geographical study*, London, 1988.
- Behnam, J., 'Population', in W. B. Fisher (ed.), *The Cambridge history of Iran*, vol. I: *The land of Iran*, Cambridge, 1968, 468–85.
- Belke, K., 'Roads', in E. Jeffreys, J. F. Haldon and R. Cormack (eds.), *The Oxford handbook of Byzantine studies*, Oxford, forthcoming.
- Blockley, R. C., *East Roman foreign policy: Formation and conduct from Diocletian to Anastasius*, Leeds, 1992.

- Bobek, H., 'Vegetation', in W. B. Fisher (ed.), *The Cambridge history of Iran*, vol. I: *The land of Iran*, Cambridge, 1968, 280–93.
- Bowden, W., L. Lavan and C. Machado (eds.), *Recent research on the late Antique countryside*, Leiden, 2004.
- Bowen Jones, H., 'Agriculture', in W. B. Fisher (ed.), *The Cambridge history of Iran*, vol. I: *The land of Iran*, Cambridge, 1968, 565–98.
- Brandes, W., *Die Städte Kleinasiens im 7. und 8. Jahrhundert*, Berliner Byzantinistische Arbeiten 56, Berlin, 1989.
- Brandes, W., and J. F. Haldon, 'Towns, tax and transformation: State, cities and their hinterlands in the East Roman world, ca. 500–800', in N. Gauthier (ed.), *Towns and their hinterlands between Late Antiquity and the early Middle Ages*, Leiden, 2000, 141–72.
- Braudel, F., *The Mediterranean and the Mediterranean world in the age of Philip II*, 2 vols., London and New York, 1973.
- Brogiolo, G. P., N. Gauthier and N. Christie (eds.), *Towns and their territories between Late Antiquity and the early Middle Ages*, *The Transformation of the Roman World* 9, Leiden, 2000.
- Brunner, C., 'Geographical and administrative divisions: Settlements and economy', in E. Yarshater (ed.), *The Cambridge history of Iran*, vol. III: *The Seleucid, Parthian and Sasanian periods*, Cambridge, 1983, 747–77.
- Bulliet, R. W., *The camel and the wheel*, Cambridge, MA, 1975.
- Canard, M., 'Le riz dans le Proche Orient aux premiers siècles d'Islam', *Arabica*, 6 (1959), 113–31.
- Canivet, P., and J. P. Rey Coquais (eds.), *La Syrie de Byzance à l'Islam: VIIe–VIIIe siècles*, Damascus, 1992.
- Christensen, A., *L'Iran sous les Sassanides*, Copenhagen, 1944.
- Conrad, L., 'Epidemic disease in central Syria in the late sixth century: Some new insights from the verse of Ḥassan ibn Thābit', *Byzantine and Modern Greek Studies*, 18 (1994), 12–58.
- Curtis, P., S. Feerman, L. Thompson and J. Vansina, *African history: From earliest times to the present*, London and New York, 1995.
- Dewdney, J. C., *Turkey*, London, 1971.
- Donner, F., 'The role of nomads in the Near East in Late Antiquity (400–800 CE)', in F. Clover and R. S. Humphreys (eds.), *Tradition and innovation in Late Antiquity*, Madison, 1989, 73–85.
- Durliat, J., *De la ville antique à la ville byzantine: Le problème des subsistances*, Rome, 1990.
- Fisher, W. B., 'Physical geography', in W. B. Fisher (ed.), *The Cambridge history of Iran*, vol. I: *The land of Iran*, Cambridge, 1968, 3–110.
- Friedmann, Y., 'A contribution to the early history of Islam in India', in M. Rosen Ayalon (ed.), *Studies in memory of Gaston Wiet*, Jerusalem, 1977, 309–34.
- Garnsey, P., and C. R. Whittaker, 'Trade, industry and the urban economy', in A. Cameron and P. Garnsey (eds.), *The Cambridge ancient history*, vol. XIII: *The late empire, AD 337–425*, Cambridge, 1998, 312–37.
- Gatier, P. L., 'Villages du Proche Orient protobyzantin (4^{ème}–7^{èmes}): Étude régionale', in G. R. D. King and A. Cameron (eds.), *The Byzantine and early Islamic Near East*, vol. II: *Land use and settlement patterns*, Princeton, 1994, 17–48.

- Geyer, B., 'Physical factors in the evolution of the landscape and land use', in A. Laiou et al. (eds.), *The economic history of Byzantium from the seventh through the fifteenth century*, Washington, DC, 2002, 31–45.
- Girgis, M. S., *Mediterranean Africa*, New York and London, 1987.
- Haas, C., 'Alexandria and the Mareotis region', in T. S. Burns and J. W. Eadie (eds.), *Urban centres and rural contexts in Late Antiquity*, East Lansing, 2001, 47–62.
- Haerinck, E., *Le céramique en Iran pendant le période parthe*, Ghent, 1983.
- Haldon, J. F., *Byzantium in the seventh century: The transformation of a culture*, Cambridge, 1997.
- 'Some considerations on Byzantine society and economy in the seventh century', *Byzantinische Forschungen*, 10 (1985), 75–112 (1985).
- Warfare, state and society in Byzantium*, 565–1204, London, 1999.
- Hassan, F. A., *Demographic archaeology*, London, 1981.
- Hendy, M. F., *Studies in the Byzantine monetary economy, c. 300–1450*, Cambridge, 1985.
- Horden, P., and N. Purcell, *The corrupting sea: A study of Mediterranean history*, Oxford, 2000.
- Howard Johnston, J., 'The two great powers in Late Antiquity: A comparison', in A. Cameron, (ed.), *The Byzantine and early Islamic Near East*, vol. III: *States, resources and armies*, Studies in Late Antiquity and Early Islam, 1, Princeton, 1995, 157–226.
- Huff, D., 'Sasanian cities', in M. Y. Kiani (ed.), *A general study of urbanization and urban planning in Iran*, Tehran, 1986, 176–204.
- Inalcik, H. (ed.), *An economic and social history of the Ottoman Empire*, vol. I: 1300–1600, Cambridge, 1994/1997.
- Issar, A. S., *Climate changes during the Holocene and their impact on hydrological systems*, Cambridge, 2003.
- Jones, A. H. M., 'The cities of the Roman empire: Political, administrative and judicial functions', *Recueils de la Société Jean Bodin*, 6 (1954), 135–73; repr. in P. A. Brunt (ed.), *The Roman economy: Studies in ancient economic and administrative history*, Oxford, 1974, 1–34.
- The Greek city from Alexander to Justinian*, Oxford, 1967.
- Kaplan, M., *Les hommes et la terre à Byzance du VI^e au XI^e siècles*, Paris, 1992.
- Karagiorgou, O., 'Urbanism and economy in Late Antique Thessaly (3rd–7th century AD): The archaeological evidence', D.Phil. thesis, Oxford University, 2001.
- Kennedy, H., 'The last century of Byzantine Syria: A reinterpretation', *Byzantinische Forschungen*, 10 (1985), 141–83.
- Kennet, D., *Sasanian and Islamic pottery from Ras al Khaimah: Classification, chronology and analysis of trade in the western Indian Ocean*, BAR International Series 1248, Oxford, 2004.
- 'Sasanian pottery in southeastern Iran and eastern Arabia', *Iran*, 40 (2002), 153–62.
- Koder, J., 'The urban character of the early Byzantine empire: Some reflections on a settlement geographical approach to the topic', in *17th International Byzantine Congress, Major Papers*, New Rochelle, NY, 1986, 155–87.
- Krawczyk, J. L., 'The relationship between pastoral nomadism and agriculture: Northern Syria and the Jazira in the eleventh century', *Jusur*, 1 (1985), 1–22.
- Le Strange, G., *Lands of the eastern caliphate*, Cambridge, 1930.
- Lev Yadun, S., N. Lipschitz and Y. Waisel, 'Annual rings in trees as an index to climate changes intensity in our region in the past', *Rotem*, 22 (1987), 6–17 (Eng. summary p. 113).

- Liebeschuetz, J. H. W. G., 'Administration and politics in the cities of the fifth to the mid seventh century', in A. Cameron, B. Ward Perkins and M. Whitby (eds.), *The Cambridge ancient history*, vol. XIV: *Late Antiquity: Empire and successors, AD 425 600*, Cambridge, 2000, 207 37.
- The decline and fall of the Roman city*, Oxford, 2001.
- MacAdam, H., 'Settlements and settlement patterns in northern and central Transjordan, ca. 550 750', in G. R. D. King and A. Cameron (eds.), *The Byzantine and early Islamic Near East*, vol. II: *Land use and settlement patterns*, Princeton, 1994, 49 93.
- Maier, A. M., 'Sassanica varia Palaestinensia: A Sassanian seal from T. Istaba, Israel, and other Sassanian objects from the southern Levant', *Iranica Antiqua*, 35 (2000), 159 83.
- Mason, R. B., 'Early medieval Iraqi lustre painted and associated wares: Typology in a multidisciplinary study', *Iraq*, 59 (1997), 15 61.
- McCormick, M., *Origins of the European economy: Communications and commerce, AD 300 900*, Cambridge, 2001.
- Mitchell, S., *Anatolia: Land, men and gods in Asia Minor*, vol. II: *The rise of the Church*, Oxford, 1993.
- Morony, M. G., 'Economic boundaries? Late Antiquity and early Islam', *JESHO*, 47 (2004), 166 94.
- 'Land use and settlement patterns in late Sasanian and early Islamic Iraq', in G. R. D. King and A. Cameron (eds.), *The Byzantine and early Islamic Near East*, vol. II: *Land use and settlement patterns*, Princeton, 1994, 221 9.
- 'Trade and exchange: The Sasanian world to Islam', in L. Conrad (ed.), *Trade and exchange in the Late Antique and early Islamic Near East*, Studies in Late Antiquity and Early Islam 5, forthcoming.
- Morrisson, C., and J. P. Sodini, 'The sixth century economy', in A. Laiou et al. (eds.), *The economic history of Byzantium from the seventh through the fifteenth century*, Washington, DC, 2002, 171 220.
- Nandris, J., 'The perspective of long term change in south east Europe', in Carter (ed.), *An historical geography of the Balkans*, 25 57.
- Neely, J. A., 'Sassanian and early Islamic water control and irrigation systems on the Deh Luran plain, Iran', in T. E. Downing and M. Gibson (eds.), *Irrigation's impact on society*, Tucson, 1974, 21 42.
- Nicolle, D., *Historical atlas of the Islamic world*, New York, 2003.
- Oates, D., *Studies in the ancient history of northern Iraq*, Oxford, 1968.
- Philippson, A., *Das byzantinische Reich als geographische Erscheinung*, Leiden, 1939.
- de Planhol, X., *Les fondements géographiques de l'histoire de l'Islam*, Paris, 1968.
- 'Geography of settlement', in W. B. Fisher (ed.), *The Cambridge history of Iran*, vol. I: *The land of Iran*, Cambridge, 1968, 409 67.
- Priestman, S. M. N., 'The Williamson Collection project: Sasanian and Islamic survey ceramics from southern Iran, current research', *Iran*, 40 (2002), 265 7, 41 (2003), 345 8.
- Puschnigg, G., 'A diachronic and stylistic assessment of the ceramic evidence from Sasanian Merv', Ph.D. thesis, University College London, 2000.
- Reynolds, P., *Trade in the western Mediterranean AD 400 700: The ceramic evidence*, BAR International Series 604, Oxford, 1995.
- Russell, J. C., *Late ancient and medieval population*, Philadelphia, 1958.

- ‘Transformations in early Byzantine urban life: The contribution and limitations of archaeological evidence’, in *Seventeenth International Byzantine Congress: Major Papers*, New York, 1986, 137–54.
- Sajjadi, M., ‘A class of Sassanian ceramics from southeastern Iran’, *Rivista di Archeologia*, 13 (1989), 31–40.
- Shoup, J., ‘Middle Eastern sheep pastoralism and the hima system’, in J. G. Galaty and D. L. Johnson (eds.), *The world of pastoralism: Herding systems in comparative perspective*, New York, 1990, 195–215.
- Slicher van Bath, B. H., *An agrarian history of western Europe*, London, 1963.
- Spieser, J. M., ‘L’Évolution de la ville byzantine de l’époque paléochrétienne à l’iconoclisme’, in C. Morrisson et al. (eds.), *Hommes et richesses dans l’Empire byzantin, IVe–VIIIe siècles*, Paris, 1989, 97–106.
- Stathakopoulos, D., *Famine and pestilence in the late Roman and early Byzantine Empire: A systematic survey of subsistence crises and epidemics*, Birmingham Byzantine and Ottoman Monographs 9, Aldershot, 2004.
- ‘The Justinianic plague revisited’, *Byzantine and Modern Greek Studies*, 24 (2000), 256–76.
- Tate, G., *Les campagnes de la Syrie du nord du IIe au VIIe siècle: Un exemple d’expansion démographique et économique dans les campagnes à la fin de l’Antiquité*, Paris, 1992.
- Telelis, I. G., *Μετεωρολογικά Φαινόμενα και κλίμα στο Βυζάντιο*, 2 vols., Athens, 2003.
- Tsafrir, Y., and G. Foerster, ‘From Scythopolis to Baysân: changing concepts of urbanism’, in G. R. D. King and A. Cameron (eds.), *The Byzantine and early Islamic Near East*, vol. II: *Land use and settlement patterns*, Princeton, 1994, 95–115.
- Van der Veen, M., A. Grant and G. Barker, ‘Romano Libyan agriculture: Crops and animals’, in G. Barker et al. (eds.), *Farming the desert: The UNESCO Libyan valley archaeological survey*, Tripoli, 1996, 227–63.
- Wagstaff, J. M., *The evolution of the Middle Eastern landscapes*, Canterbury, 1984.
- Ward Perkins, B., ‘The cities’, in A. Cameron and P. Garnsey (eds.), *The Cambridge ancient history*, vol. XIII: *The late empire, AD 337–425*, Cambridge, 1998, 371–410.
- ‘Land, labour and settlement’, in A. Cameron, B. Ward Perkins and M. Whitby (eds.), *The Cambridge ancient history*, vol. XIV: *Late Antiquity: Empire and successors*, AD 425–600, Cambridge, 2000, 315–45.
- ‘Specialised production and exchange’, in A. Cameron, B. Ward Perkins and M. Whitby (eds.), *The Cambridge ancient history*, vol. XIV: *Late Antiquity: Empire and successors*, AD 425–600, Cambridge, 2000, 346–91.
- Wenke, R. J., ‘Imperial investments and agricultural development in Parthian and Sasanian Khuzistan: 150 BC to AD 640’, *Mesopotamia*, 10–11 (1975/6), 31–221.
- Wheatley, P., *The places where men pray together: Cities in Islamic lands, seventh through the tenth centuries*, Chicago, 2001.
- Whitcomb, D., ‘The “commercial crescent”: Red Sea trade in Late Antiquity and early Islam’, in L. Conrad (ed.), *Trade and exchange in the Late Antique and early Islamic Near East*, Studies in Late Antiquity and Early Islam 5, forthcoming.
- Whittaker, C. R., ‘Rural life in the later Roman empire’, in A. Cameron and P. Garnsey (eds.), *The Cambridge ancient history*, vol. XIII: *The late empire, AD 337–425*, Cambridge, 1998, 277–311.
- Whittow, M., ‘Ruling the late Roman and early Byzantine city: A continuous history’, *Past and Present*, 129 (1990), 3–29.

- Wilkinson, T. J., *Archaeological landscapes of the Near East*, Tucson, 2003.
 Williams, T., K. Kurbansakhatov et al., 'The ancient Merv project, Turkmenistan: Preliminary report on the first season (2001)', *Iran*, 40 (2002), 15–41.

Chapter 2: The late Roman/early Byzantine Near East

Practical suggestions for further reading

- Ball, W., *Rome in the East: The transformation of an empire*, London, 2000.
 Bowman, A. K., P. Garnsey and A. Cameron (eds.), *The Cambridge ancient history*, vol. XII: *The crisis of empire, AD 193–337*, 2nd edn, Cambridge, 2005.
 Butcher, K., *Roman Syria and the Near East*, London, 2003.
 Cameron, A., and P. Garnsey (eds.), *The Cambridge ancient history*, vol. XIII: *The late empire, AD 337–425*, Cambridge, 1998.
 Cameron, A., B. Ward Perkins and M. Whitby (eds.), *The Cambridge ancient history*, vol. XIV: *Late Antiquity: empire and successors, AD 425–600*, Cambridge, 2000.
 Fowden, G., *Empire to commonwealth: Consequences of monotheism in Late Antiquity*, Princeton, 1993.
 Greatrex, G., *Rome and Persia at war, 502–532*, ARCA Classical and Medieval Texts, Papers and Monographs 37, Leeds, 1998.
 Isaac, B., *The limits of empire*, Oxford, 1990.
 Jones, A. H. M., *The later Roman empire, 284–602: A social, economic, and administrative study*, 3 vols., Oxford, 1964.
 Matthews, J., *The Roman empire of Ammianus*, London, 1989.
 Meier, M., *Justinian: Herrschaft, Reich und Religion*, Munich, 2004.
 Millar, F., *The Roman Near East, 31 BC–AD 337*, Cambridge, MA, 1993.
 Morrison, C. (ed.), *Le monde Byzantin I: L'Empire romain d'Orient (330–641)*, Paris, 2004.
 Potter, D. S., *The Roman Empire at bay, AD 180–395*, London, 2004.
 Sartre, M., *The Middle East under Rome*, trans. C. Porter and E. Rawlings, Cambridge, MA., 2005.
 Tate, G., *Justinien: L'épopée de l'Empire d'Orient (527–565)*, Paris, 2004.
 Whitby, M., *The Emperor Maurice and his historian: Theophylact Simocatta on Persian and Balkan Warfare*, Oxford, 1988.
 Whittow, M., *The making of Orthodox Byzantium, 600–1025*, Basingstoke, 1996.

Primary sources

- Ammianus Marcellinus, *Rerum gestarum libri*, ed. and trans. J. C. Rolfe, 3 vols., Cambridge, MA, 1935–9, rev. edn 1986.
 Calvet, Y., and C. Robin, *Arabie heureuse Arabie déserte: Les antiquités arabiques du Musée du Louvre*, Notes et documents des musées de France 31, Paris, 1997.
 Cameron, A., and J. Herrin (eds.), *Constantinople in the early eighth century: The Parastaseis Syntomoi Chronikai*, Leiden, 1984.
Chronicle of Pseudo Joshua the Stylite, trans. with notes and introd. by F. R. Trombley and J. W. Watt, Translated Texts for Historians 32, Liverpool, 2000.
Codex Theodosianus, ed. T. Mommsen and P. M. Meyer as *Theodosiani libri XVI cum Constitutionibus Sirmondianis*, Berlin, 1905, trans. C. Pharr as *The Theodosian Code*, New York, 1952.

Bibliography

- Diodorus Siculus, *Bibliotheca historica*, ed. and trans. C. H. Oldfather, C. L. Sherman, C. Bradford Welles, R. M. Geer and F. R. Walton, 12 vols., Cambridge, MA, 1933–67.
- Dodgeon, M. H., and S. N. C. Lieu (eds.), *The Roman eastern frontier and the Persian wars*, part 1: AD 226–363: *A documentary history*, London, 1991.
- Greatrex, G., and S. N. C. Lieu (eds.), *The Roman eastern frontier and the Persian wars*, part 2: AD 363–630, London and New York, 2002.
- Herrmann, G., D. N. Mackenzie and R. Howell, *The Sasanian reliefs at Naqsh-e Rostam*, *Naqsh-e Rostam 6, The Triumph of Shapur I*, *Iranische Denkmäler* 13, Berlin, 1989.
- John of Ephesus, *Ecclesiastical history*, ed. E. W. Brooks as *Iohannis Ephesini historiae ecclesiastica pars tertia*, CSCO, Scr. Syr. III.3, Louvain, 1935–6, trans. R. Payne Smith as *The third part of the ecclesiastical history of John, bishop of Ephesus*, Oxford, 1860.
- Pliny, *Naturalis historia*, ed. and trans. H. Rackham, W. H. S. Jones and D. E. Eichholz, 10 vols., Cambridge, MA, 1917–32.
- Procopius, *History of the wars*, ed. and trans. H. B. Dewing, 5 vols., Cambridge, MA, 1914–28.
- Sebeos, *The Armenian history attributed to Sebeos*, trans. R. W. Thomson, with commentary by J. Howard Johnston, *Translated Texts for Historians* 31, 2 vols., Liverpool, 1999.
- Socrates, *Ecclesiastical history*, ed. G. C. Hansen, trans. P. Périchon and P. Maraval as *Histoire ecclésiastique*, vol. I, Paris, 2004.
- Sozomen, *Ecclesiastical history*, ed. J. Bidez, trans. A. J. Festugière as *Histoire ecclésiastique*, vol. I, Paris, 1983.
- Strabo, *Geography*, ed. and trans. H. L. Jones, 8 vols., Cambridge, MA, 1917–32.
- Theophanes, *Chronographia*, ed. C. de Boor as *Theophanis chronographia*, 2 vols., Leipzig, 1883–5, trans. C. Mango and R. Scott as *The chronicle of Theophanes Confessor*, Oxford, 1997.

Secondary sources

- Ando, C., *Imperial ideology and provincial loyalty in the Roman Empire*, Berkeley and Los Angeles, 2000.
- Banaji, J., *Agrarian change in Late Antiquity: Gold, labour, and aristocratic dominance*, Oxford, 2001.
- Banning, E. B., 'De Bello Paceque: A reply to Parker', *BASOR*, 265 (1987), 52–4.
- 'Peasants, pastoralists and Pax Romana: Mutualism in the southern highlands of Jordan', *BASOR*, 261 (1986), 25–50.
- Blachère, R., *Histoire de la littérature arabe des origines à la fin du xve siècle de J. C.*, 3 vols., Paris, 1952–66.
- Blockley, R. C., *East Roman foreign policy: Formation and conduct from Diocletian to Anastasius*, Leeds, 1992.
- Christensen, A., *L'Iran sous les Sassanides*, 2nd edn, Copenhagen, 1944.
- Dagron, G., *Naissance d'une capitale: Constantinople et ses institutions de 330 à 451*, Paris, 1974.
- Dagron, G., and V. Déroche, 'Juifs et Chrétiens dans l'Orient du viie siècle', *Travaux et Mémoires*, 11 (1991), 17–273.
- Elton, H., *Warfare in Roman Europe AD 350–425*, Oxford, 1996.
- Equini Schneider, E., *Septimia Zenobia Sebaste*, Rome, 1993.
- Foss, C., 'The Persian Near East (602–630 AD)', *JRAS*, 3rd series, 13 (2003), 149–70.
- Genequand, D., 'Some thoughts on Qasr al-Hayr al-Gharbi, its dam, its monastery and the Ghassanids', *Levant*, 38 (2006), 63–83.

- van Ginkel, J., 'John of Ephesus: A monophysite historian in sixth century Byzantium', Ph.D. thesis, Groningen, 1995.
- Golden, P. B., *An introduction to the history of the Turkic peoples: Ethnogenesis and state formation in medieval and early modern Eurasia and the Middle East*, Wiesbaden, 1992.
- Harris, W. V., *War and imperialism in republican Rome, 327 70 BC*, Oxford, 1979.
- Hartmann, U., *Das palmyrenische Teilreiche*, Stuttgart, 2001.
- Heather, P., *Goths and Romans 332 489*, Oxford, 1991.
- 'The Huns and the end of the Roman Empire in Western Europe', *English Historical Review*, 110 (1995), 4 41.
- 'The late Roman art of client management', in W. Pohl, I. Wood and H. Reimitz (eds.), *The transformation of frontiers: From Late Antiquity to the Carolingians*, Leiden, 2001, 36 56.
- 'New men for new Constantines? Creating an imperial elite in the eastern Mediterranean', in P. Magdalino (ed.), *New Constantines: The rhythm of imperial renewal in Byzantium, 4th 13th centuries*, Aldershot, 1994, 11 33.
- Hendy, M., *Studies in the Byzantine monetary economy, c. 350 1450*, Cambridge, 1985.
- Howard Johnston, J., *East Rome, Sasanian Persia and the end of Antiquity: Historiographical and historical studies*, Aldershot, 2006.
- 'Heraclius' Persian campaigns and the revival of the East Roman Empire, 622 630', *War in History*, 6 (1999), 1 44.
- 'Pride and fall: Khusro II and his regime, 626 628', in *La Persia e Bisanzio*, Atti dei convegni Lincei 201, Roma, 14 18 ottobre 2002, Rome, 2004, 93 113.
- 'The two great powers in Late Antiquity: A comparison', in A. Cameron (ed.), *The Byzantine and early Islamic Near East*, vol. III: *States, resources and armies*, Studies in Late Antiquity and Early Islam 1, Princeton, 1995, 157 226.
- Hoyland, R. G., *Arabia and the Arabs from the Bronze Age to the coming of Islam*, London and New York, 2001.
- Jones, A. H. M., J. R. Martindale and J. Morris, *The prosopography of the later Roman Empire*, 3 vols., Cambridge, 1971 92.
- Liebeschuetz, J. H. W. G., *The decline and fall of the Roman city*, Oxford, 2001.
- Lightfoot, C. S., 'Trajan's Parthian war and the fourth century perspective', *Journal of Roman Studies*, 80 (1990), 115 26.
- Macdonald, M. C. A., 'Nomads and the Hawran in the late Hellenistic and Roman periods: A reassessment of the epigraphic evidence', *Syria*, 70 (1993), 303 413.
- Mattern, S. P., *Rome and the enemy: Imperial strategy in the principate*, Berkeley and Los Angeles, 1999.
- Moorhead, J., 'The Monophysite response to the Arab invasions', *Byzantion*, 51 (1981), 579 91.
- Nicholson, R. A., *A literary history of the Arabs*, Cambridge, 1930.
- Nöldeke, T., *Die Ghassanischen Fürsten aus dem Hause Gafna's*, Abhandlungen der königl. Akademie der Wissenschaften zu Berlin, Philosophisch historische Klasse Abh. 1887, II, Berlin, 1887.
- Parker, S. T., 'The defense of Palestine and Transjordan from Diocletian to Heraclius', in L. E. Stager, J. A. Greene and M. D. Coogan (eds.), *The archaeology of Jordan and beyond: Essays in honor of James A. Sauer*, Studies in the Archaeology and History of the Levant 1, Winona Lake, IN, 2000, pp. 367 88.

Bibliography

- The Roman frontier in Central Jordan: Final report on the Limes Arabicus Project, 1980–1989*, 2 vols., Dumbarton Oaks Studies 40, Washington, DC, 2006.
- Pollard, N., *Soldiers, cities, and civilians in Roman Syria*, Ann Arbor, 2000.
- Potter, D. S., *Prophecy and history in the crisis of the Roman Empire: A historical commentary on the Thirteenth Sibylline Oracle*, Oxford, 1990.
- Price, S., *Rituals and power: The Roman imperial cult in Asia Minor*, Cambridge, 1984.
- Retsö, J., *The Arabs in Antiquity: Their history from the Assyrians to the Umayyads*, London, 2003.
- Rothstein, G., *Die Dynastie der Lähmiden in al Hira: Ein Versuch zur arabisch persischen Geschichte zur Zeit der Sasaniden*, Berlin, 1899.
- Sartre, M., *Trois études sur l'Arabie romaine et byzantine*, Brussels, 1982.
- Schippmann, K., *Grundzüge der Geschichte des Sasanidischen Reiches*, Darmstadt, 1990.
- Shahid, I., *Byzantium and the Arabs in the fifth century*, Washington, DC, 1989.
- Byzantium and the Arabs in the fourth century*, Washington, DC, 1984.
- Byzantium and the Arabs in the sixth century*, vols. I, Washington, DC, 1995.
- 'Byzantium and the Arabs in the sixth century. A propos of a recent review', *Byzantinische Forschungen*, 26 (2000), 125–60.
- Byzantium and the Semitic Orient before the rise of Islam*, London, 1988.
- Rome and the Arabs: A prolegomenon to the study of Byzantium and the Arabs*, Washington, DC, 1984.
- Whitby, M., 'Greek historical writing after Procopius: Variety and vitality', in A. Cameron and L. I. Conrad (eds.), *The Byzantine and early Islamic Near East*, vol. I: *Problems in the literary source material*, Princeton, 1992, 25–80.
- 'Recruitment in Roman armies from Justinian to Heraclius (ca. 565–615)', in A. Cameron (ed.), *The Byzantine and early Islamic Near East*, vol. III: *States, resources and armies*, Studies in Late Antiquity and Early Islam 1, Princeton, 1995, 61–124.
- Whittow, M., 'Rome and the Jafnids: Writing the history of a 6th c. tribal dynasty', in J. H. Humphrey (ed.), *The Roman and Byzantine Near East*, vol. II: *Some recent archaeological research*, JRA Supplementary series 31, Portsmouth, RI, 1999, 207–24.
- Wickham, C., *Framing the early Middle Ages: Europe and the Mediterranean, 400–800*, Oxford, 2005.
- Wolf, G., *Becoming Roman: The origins of provincial civilization in Gaul*, Cambridge, 1998.
- Zwettler, M., 'Imra' alqays, Son of 'Amr: King of ...???'', in M. Mir and J. E. Fossum (eds.), *Literary heritage of classical Islam: Arabic and Islamic studies in honor of James A. Bellamy*, Princeton, 1993, 3–37, pl. 1–5.

Chapter 3: The late Sasanian Near East

Practical suggestions for further reading

- Börm, H., *Prokop und die Perser*, OrOcc 16, Stuttgart, 2007.
- Cereti, C. G., *La letteratura pahlavi*, Milan, 2001.
- Christensen, A., *L'Iran sous les Sassanides*, 2nd rev. edn, Copenhagen, 1944.
- Demange, F., et al. (eds.), *Les Perses sassanides: Fastes d'un empire oublié (224–642): Musée Cernuschi, Musée des arts de l'Asie de la ville de Paris, 15 septembre–30 décembre 2006*, Paris, 2006.

Bibliography

- Donner, F. M., 'The background to Islam', in M. Maas (ed.), *The Cambridge companion to the age of Justinian*, Cambridge, 2005, 510–33.
- Greatrex, G., 'Byzantium and the east in the sixth century', in M. Maas (ed.), *The Cambridge companion to the age of Justinian*, Cambridge, 2005, 477–509.
- Güterbock, K., *Byzanz und Persien in ihren diplomatisch völkerrechtlichen Beziehungen im Zeitalter Justinians*, Berlin, 1906.
- Gyselen, R., *La géographie administrative de l'empire sassanide: Les témoignages sigillographiques*, Paris, 1989.
- Howard Johnston, J., *East Rome, Sasanian Persia and the end of Antiquity: Historiographical and historical studies*, Ashgate, 2006.
- Huyse, P., *La Perse antique*, Paris, 2005.
- Reinink, G., and B. Stolte (eds.), *The reign of Heraclius (610–641): Crisis and confrontation*, Louvain, 2002.
- Rubin, Z., 'Nobility, monarchy and legitimation under the later Sasanians', in J. Haldon and L. I. Conrad (eds.), *The Byzantine and early Islamic Near East*, vol. VI: *Elites old and new in the Byzantine and early Islamic Near East*, Princeton, 2004, 235–73.
- 'The reforms of Khusro Anushirwan', in A. Cameron (ed.), *The Byzantine and early Islamic Near East*, vol. III: *States, resources and armies*, Studies in Late Antiquity and Early Islam 1, Princeton, 1995, 227–96.
- 'The Sasanid monarchy', in A. Cameron, B. Ward Perkins and M. Whitby (eds.), *The Cambridge ancient history*, vol. XIV: *Late Antiquity: Empire and successors, AD 425–600*, 2nd edn, Cambridge, 2000, 638–61.
- Wiesehöfer, J., *Ancient Persia*, 2nd edn, London and New York, 2001.
- 'Chusro I. und das Sasanidenreich: Der König der Könige "mit der unsterblichen Seele"', in M. Meier (ed.), *Sie schufen Europa: Historische Portraits von Konstantin bis Karl dem Großen*, Munich, 2007, 195–215.
- Wiesehöfer, J., and P. Huyse (eds.), *Eran und Aneran: Studien zu den Beziehungen zwischen dem Sasanidenreich und der Mittelmeerwelt*, *OrOcc* 13, Stuttgart, 2006.
- Yarshater, E., 'Iranian national history', in E. Yarshater (ed.), *The Cambridge history of Iran*, vol. III: *The Seleucid, Parthian and Sasanian periods*, Cambridge, 1983, part 1, 359–477.

Primary sources

- Alram, M., and R. Gyselen, *Sylloge Nummorum Sasanidarum Paris – Berlin – Wien*, vol. I: *Ardashir I. Shapur I.*, Vienna, 2003.
- Assemani, S. E., *Acta Sanctorum Martyrum Orientalium et Occidentalium in duas partes distributa*, Rome, 1748; repr. 1970.
- Back, M., *Die sassanidischen Staatsinschriften: Studien zur Orthographie und Phonologie des Mittelpersischen der Inschriften zusammen mit einem etymologischen Index des mittelpersischen Wortgutes und einem Textcorpus der behandelten Inschriften*, *Acta Iranica* 18, Leiden, 1978.
- Bedjan, P., *Acta martyrum et sanctorum*, 7 vols., Paris and Leipzig, 1890–7; repr. 1968.
- Bosworth, C. E. (ed.), *The history of al-Ṭabarī*, vol. V: *The Sasanids, the Byzantines, the Lakmids, and Yemen*, Albany, 1999.
- Braun, O., *Ausgewählte Akten persischer Märtyrer*, Kempten and Munich, 1915.
- Brock, S. P., and S. Harvey (eds.), *Holy women of the Syrian Orient*, Berkeley, 1987.

- Dodgeon, M. H., and S. N. C. Lieu (eds.), *The Roman eastern frontier and the Persian wars*, part 1: AD 226–363: A documentary history, London and New York, 1991.
- Gardner, I., and S. N. C. Lieu (eds.), *Manichaean texts from the Roman empire*, Cambridge, 2004.
- Gignoux, P., *Les quatre inscriptions du mage Kirdir: Textes et concordances*, Paris, 1991.
- Greatrex, G., and S. N. C. Lieu, *The Roman eastern frontier and the Persian wars*, part 2: AD 363–630, London and New York, 2002.
- Grenet, F., *La geste d'Ardashir fils de Pâbag: Karnamag 1 Ardashēr 1 Pabagan*, Paris, 2001.
- Hintze, A., *Der Zamyād Yašt: Edition, Übersetzung, Kommentar*, Beiträge zur Iranistik 15, Wiesbaden, 1994.
- Hoffmann, G., *Auszüge aus syrischen Akten persischer Märtyrer*, Leipzig, 1880.
- Humbach, H., and P. O. Skjærvø, *The Sassanian inscription of Paikuli*, 3 parts, Wiesbaden, 1978–83.
- Hutter, M., *Manis kosmogonische Šabuhrağan Texte: Edition, Kommentar und literargeschichtliche Einordnung der manichäischen mittelpersischen Handschriften M 98/99 I und M 7980 7985*, Studies in Oriental Religion 21, Wiesbaden, 1992.
- Huyse, P., *Die dreisprachige Inschrift Šabuhra I. an der Ka'ba i Zardušt (ŠKZ)*, CII 3, vol. I, texts I, vols. I–II, London, 1999.
- Kawerau, P., *Die Chronik von Arbela*, CSCO 467–8, 2 vols., Louvain, 1985.
- Luther, A., *Die syrische Chronik des Josua Stylites*, Untersuchungen zur antiken Literatur und Geschichte 49, Berlin and New York, 1997.
- MacKenzie, D. N., 'Kerdir's inscription: Synoptic text in transliteration, transcription and commentary', in G. Herrmann and D. N. MacKenzie (eds.), *The triumph of Shapur I (together with an account of the representation of Kerdīr)*, Iranische Denkmäler, Lief. 13, Reihe II, Iranische Felsreliefs I: *The Sasanian rock reliefs at Naqsh-e Rostam*. *Naqsh-e Rostam 6*, Berlin, 1989, 35–72.
- Nöldeke, T., *Geschichte der Perser und Araber zur Zeit der Sasaniden*, Leiden, 1878.
- Die von Guidi herausgegebene syrische Chronik: Übersetzt und kommentiert, Sitzungsberichte der Akademie der Wissenschaften zu Wien, Philosophisch-Historische Klasse 128, Vienna, 1893, 1–48.
- Panaino, A., *La novella degli scacchi e della tavola reale: Un'antica fonte orientale sui due giochi da tavoliere più diffusi nel mondo eurasiatico tra Tardoantico e Medioevo e sulla loro simbologia militare e astrale. Testo pahlavi, traduzione e commento al Wizarišn ī čatrang ud nihišn ī new ardashīr*, Milan, 1999.
- Schindel, N., *Sylloge Nummorum Sasanidarum* Paris–Berlin–Wien, vol. III, parts 1–2: *Shapur II. Kawad I./2. Regierung*, Vienna, 2004.
- Sebeos, *The Armenian history attributed to Sebeos*, trans. R. W. Thomson, with commentary by J. Howard Johnston, *Translated Texts for Historians* 31, 2 vols., Liverpool, 1999.
- Sundermann, W., *Mitteliranische manichäische Texte kirchengeschichtlichen Inhalts*, Schriften zur Geschichte und Kultur des Alten Orients, Berliner Turfantexte 11, Berlin, 1981.
- al-Ṭabarī, Abu Ja'far Muḥammad ibn Jarīr, *Ta'rikh al-rusul wa'l muluk*, ed. M. J. de Goeje et al., 15 vols. in 3 series, Leiden, 1879–1901.
- Trombley, F. R., and J. W. Watt (eds.), *The chronicle of Pseudo Joshua the Stylite*, *Translated Texts for Historians* 32, Liverpool, 2000.
- Unvala, J. M., *Der Pahlavi Text 'Der König Husrav und sein Knabe'*, Heidelberg, 1917.
- The Pahlavi text King Husrav and his boy: Published with its translation, transcription and copious notes*, Paris, 1921.

- Weber, D., *Berliner Papyri, Pergamente und Leinenfragmente in mittelpersischer Sprache*. CII III, 4 5, London, 2003.
Ostraca, Papyri und Pergamente: Textband, CII III, 4 5, London, 1992.
 Winter, E., and B. Dignas, *Rom und das Perserreich: Zwei Weltmächte zwischen Konfrontation und Koexistenz*, Berlin, 2001.

Secondary sources

- Abka'i Khavari, M., *Das Bild des Königs in der Sasanidenzeit: Schriftliche Überlieferungen im Vergleich mit Antiquaria*, Texte und Studien zur Orientalistik 13, Hildesheim, 2000.
 Altheim, F., *Geschichte der Hunnen*, vols. IV V, Berlin, 1962.
 Altheim, F., and R. Stiehl, *Ein asiatischer Staat*, Wiesbaden, 1954.
Finanzgeschichte der Spätantike, Frankfurt, 1957.
 Altheim Stiehl, R., 'Das früheste Datum der sasanidischen Geschichte, vermittelt durch die Zeitangabe der mittelpersisch parthischen Inschrift aus Bišapur', *Archäologische Mitteilungen aus Iran*, n.s. 11 (1978), 113 16.
 'The Sasanians in Egypt: Some evidence of historical interest', *Bulletin de la Société d'Archéologie Copte*, 31 (1992), 87 96.
 'Zur zeitlichen Bestimmung der sasanidischen Eroberung Ägyptens', in O. Brehm and S. Klie (eds.), *Mousikos Aner: Festschrift für M. Wegner zum 90. Geburtstag*, Bonn, 1992, 5 8.
 Arafa, M., J. Tubach and G. S. Vashalomidze (eds.), *Inkulturation des Christentums im Sasanidenreich*, Wiesbaden, 2007.
 Abßalg, J., and P. Krüger (eds.), *Kleines Wörterbuch des christlichen Orients*, Wiesbaden, 1975.
 Baumstark, A., *Geschichte der syrischen Literatur mit Ausschluß der christlich palästinensischen Texte*, Bonn, 1922; repr. 1968.
 Bier, L., 'Notes on Mihr Narseh's bridge near Firuzabad', *Archäologische Mitteilungen aus Iran*, n.s. 19 (1986), 263 8.
 'Sasanian palaces in perspective', *Archaeology*, 35, 1 (1982), pp. 29 36.
 Bivar, A. D. H., 'Hephthalites', *Elr*, vol. XII, 198 201.
 Blockley, R. C., 'The division of Armenia between the Romans and the Persians', *Historia*, 36 (1987), 222 34.
East Roman foreign policy: Formation and conduct from Diocletian to Anastasius, Leeds, 1992.
 'The Romano Persian peace treaties of AD 299 and 363', *Florilegium*, 6 (1984), 28 49.
 'Subsidies and diplomacy: Rome and Persia in Late Antiquity', *Phoenix*, 39 (1985), 62 74.
 de Blois, F., *Burzoy's voyage to India and the origin of the Book of Kalilah wa Dimna*, London, 1990.
 Börm, H., 'Der Perserkönig im Imperium Romanum: Chosroes I. und der sasanidische Einfall in das Oströmische Reich 540 n.Chr.', *Chiron*, 36 (2006), 299 328.
 Boyce, M., 'Gosan', *Elr*, vol. XI, 161 70.
 'Middle Persian literature', in *Iranistik II, Literatur I*, Handbuch der Orientalistik I.IV.2.1, Leiden, 1968, 31 66.
 'The Parthian gosan and Iranian minstrel tradition', *JRAS* (1957), 10 45.
 Brock, S. P., *Brief outline of Syriac literature*, Kottayam, 1997.
 Brockelmann, C., *Geschichte der arabischen Literatur*, 2nd edn, 2 vols., Leiden, 1943 9; suppl. 1 3, Leiden, 1937 42.
 Bury, J. B., *A history of the later Roman empire*, vol. II, London, 1889.

- Busse, H., 'Arabische Historiographie und Geographie', in H. Gätje (ed.), *Grundriß der arabischen Philologie*, vol. II, Wiesbaden, 1987, 264–97.
- Cameron, A., 'Agathias on the Sassanians', *Dumbarton Oaks Papers*, 23–4 (1969–70), 1–150.
- Procopius and the sixth century, London and New York, 1985.
- Cereti, C. G., 'Primary sources for the history of inner and outer Iran in the Sasanian period', *Eurasiae Medii Aevi*, 9 (1997), 17–71.
- Cribb, J., 'Numismatic evidence for Kushano Sasanian chronology', *Studia Iranica*, 19 (1990), 151–93.
- Curtis, V. S., 'Minstrels in ancient Iran', in V. S. Curtis, R. Hillenbrand and J. M. Rogers (eds.), *The art and archaeology of ancient Persia: New light on the Parthian and Sasanian empires*, London and New York, 1998, 182–7.
- Daryaei, T., 'The construction of the past in Late Antique Persia', *Historia*, 55 (2006), 493–503.
- 'Memory and history: The reconstruction of the past in Late Antique Persia', *Nâme ye Irân e Bâstân*, 1, 2 (2001–2), 1–14.
- 'Mind, body, and the cosmos: Chess and backgammon in ancient Persia', *Iranian Studies*, 35 (2002), 281–312.
- 'National history or Keyanid history? The nature of Sasanid Zoroastrian historiography' *Iranian Studies*, 28 (1995), 129–41.
- Döpp, S., and W. Geerlings (eds.), *Lexikon der antiken christlichen Literatur*, Freiburg, 1998.
- Drijvers, J. W., 'Ammianus Marcellinus' image of Sasanian society', in J. Wiesehöfer and P. Huysse (eds.), *Eran und Aneran: Studien zu den Beziehungen zwischen dem Sasanidenreich und der Mittelmeerwelt*, *OrOcc* 13, Stuttgart, 2006., 45–69.
- Drijvers, J. W., and D. Hunt (eds.), *The late Roman world and its historian: Interpreting Ammianus Marcellinus*, London and New York, 1999.
- Enderlein, V., and W. Sundermann (eds.), *Schahname: Das persische Königsbuch: Miniaturen und Texte der Berliner Handschrift von 1605*, Leipzig and Weimar, 1988.
- Felix, W., *Antike literarische Quellen zur Außenpolitik des Sasanidenstaates*, vol. I: 224–309, Österreichische Akademie der Wissenschaften, philosophisch-historische Klasse, Sitzungsberichte 456 = Veröffentlichungen der Iranischen Kommission 18, Vienna, 1985.
- Fiey, J. M., 'Review of P. Kawerau, *Die Chronik von Arbela*', *Revue d'Histoire Ecclésiastique*, 81 (1986), 544–8.
- Fowden, E., *The barbarian plain: Saint Sergius between Rome and Iran*, *Transformation of the Classical Heritage* 28, Berkeley, 1999.
- Frye, R. N., *The history of ancient Iran*, *Handbuch der Altertumswissenschaft* III, 7, Munich, 1984.
- 'The political history of Iran under the Sassanians', in E. Yarshater (ed.), *The Cambridge history of Iran*, vol. III: *The Seleucid, Parthian and Sasanian periods*, Cambridge, 1983, part 2, 116–80.
- Fukai, S., *Persian glass*, New York, 1977.
- von Gall, H., *Das Reiterkampfbild in der iranischen und iranisch beeinflussten Kunst parthischer und sasanidischer Zeit*, *Teheraner Forschungen* 6, Berlin, 1990.
- Garsoian, N. G., 'Byzantium and the Sassanians', in E. Yarshater (ed.), *The Cambridge history of Iran*, vol. III: *The Seleucid, Parthian and Sasanian periods*, Cambridge, 1983, part 1, 568–92.

- Gerland, E., 'Die persischen Feldzüge des Kaisers Herakleios', *Byzantinische Zeitschrift*, 3 (1894), 330–73.
- Gerster, G., and D. Huff, 'Die Paläste des Königs Ardaschir', *Bild der Wissenschaft*, 11 (1977), 48–60.
- Ghirshman, R., *Bichapour I II*, Paris, 1956 71.
- Gignoux, P., 'La chasse dans l'Iran sasanide', in G. Gnoli (ed.), *Essays and lectures*, vol. III: *Orientalia Romana*, Rome, 1983, 101–18.
- 'D'Abnun à Mahan: Étude de deux inscriptions sassanides', *Studia Iranica*, 20 (1991), 9–17.
- 'Éléments de prosopographie de quelques mobads sasanides', *JA*, 270 (1982), 257–69.
- 'Une nouvelle collection de documents en pehlevi cursif du début du septième siècle de notre ère', *Comptes Rendus de l'Académie des Inscriptions et Belles Lettres* (1991), 683–700.
- 'Pour une esquisse des fonctions religieuses sous les Sasanides', *JSAI*, 7 (1986), 93–108.
- 'Pour une évaluation de la contribution des sources arméniennes à l'histoire sassanide', *Acta Antiqua Academiae Scientiarum Hungaricae*, 31 (1985–8), 53–65.
- 'Pour une nouvelle histoire de l'Iran sasanide', in W. Skalmowski and A. van Tengerloo (eds.), *Middle Iranian studies*, Louvain, 1984, 253–62.
- 'Prolégomènes pour une histoire des idées de l'Iran sassanide: Convergences et divergences', in J. Wiesehöfer and P. Huyse (eds.), *Eran und Aneran: Studien zu den Beziehungen zwischen dem Sasanidenreich und der Mittelmeerwelt*, *OrOcc* 13, Stuttgart, 2006, 71–81.
- 'Die religiöse Administration in sasanidischer Zeit: Ein Überblick', in H. Koch and D. N. MacKenzie (eds.), *Kunst, Kultur und Geschichte der Achämenidenzeit und ihr Fortleben*, Berlin, 1983, 253–66.
- 'Review of M. Back, Die sassanidischen Staatsinschriften', *Studia Iranica*, 13 (1984), 268–73.
- Gnoli, G., 'Farr(ah)', *Elr*, vol. IX, 312–19.
- The idea of Iran: An essay on its origin*, Serie Orientale Roma 62, Rome, 1989.
- 'L'inscription de Šabühr à la Ka'be ye Zardošt et la propagande sassanide', in P. Bernard and F. Grenet (eds.), *Histoire et cultes de l'Asie Centrale préislamique*, Paris, 1991, 57–63.
- Iran als religiöser Begriff im Mazdaismus*, Rheinisch Westfälische Akademie der Wissenschaften, Vorträge G 320, Opladen, 1993.
- 'Nuovi studi sul Mazdakismo', in G. Gnoli and A. Panaino (eds.), *La Persia e Bisanzio*, *Atti dei Convegni Lincei* 201, Rome, 2004, 439–56.
- Göbl, R., 'The Rabatak inscription and the date of Kanishka', in M. Alram and D. Klimburg Salter (eds.), *Coins, art and chronology: Essays on the pre Islamic history of the Indo Iranian borderlands*, Österreichische Akademie der Wissenschaften, philosophisch historische Klasse, Denkschriften 280, Vienna, 1999, 151–75.
- Graf, G., *Geschichte der christlichen arabischen Literatur*, 4 vols., Vatican, 1944 53; repr. 1964 6.
- Greatrex, G., 'Review of W. E. Kaegi, *Heraclius*', *The Medieval Review* (2004), available at <http://quod.lib.umich.edu/cgi/t/text/textidx?c=tmr;cc=tmr;q1=2004;rgn=main;view=text;idno=baj9928.0401.028>.
- Rome and Persia at war*, 502–532, ARCA Classical and Medieval Texts, Papers and Monographs 37, Leeds, 1998.
- Grignaschi, M., 'La riforma tributaria di Hosro I e il feudalismo sassanide', in *La Persia nel medioevo*, Rome, 1971, 87–138.

- Guidi, M., and M. Morony, 'Mazdak', *El2*, vol. VI, 949–52.
- Gyselen, R., *L'art sigillaire dans les collections de Leyde*, Leiden, 1997.
Collection générale, Paris, 1993, vol. I of *Catalogue des sceaux, camées et bulles sasanides de la Bibliothèque Nationale et du Musée du Louvre*.
- The four generals of the Sasanian empire: Some sigillographic evidence*, Rome, 2001.
- Nouveaux matériaux pour la géographie historique de l'empire sassanide: Sceaux administratifs de la collection Ahmad Saeedi*, *Studia Iranica*, Cahier 24, Paris, 2002.
- 'Sasanian glyptic: An example of cultural interaction between the Hellenistic world and the Iranian world', in M. Alram and D. Klimburg Salter (eds.), *Coins, art and chronology: Essays on the pre Islamic history of the Indo Iranian borderlands*, Österreichische Akademie der Wissenschaften, philosophisch historische Klasse, Denkschriften 280, Vienna, 1999, 293–301.
- Sceaux magiques en Iran sassanide*, *Cahiers de Studia Iranica* 17, Paris, 1995.
- (ed.), *Charmes et sortilèges: Magie et magiciens*, *Res Orientales* 14, Bures sur Yvette, 2002.
- (ed.), *Sceaux d'Orient et leur emploi*, *Res Orientales* 10, Bures sur Yvette, 1997.
- (ed.), *La science des cieux: Sages, mages, astrologues*, *Res Orientales* 12, Bures sur Yvette, 1999.
- Gyselen, R., et al., 'Sylloge Nummorum Sasanidorum: Die Münzen der Sasaniden aus der Bibliothèque Nationale de France, dem Münzkabinett der Staatlichen Museen zu Berlin und dem Münzkabinett am Kunsthistorischen Museum in Wien (in Zusammenarbeit mit M. Alram u.a.)', *Anzeiger der philosophisch historischen Klasse der Österreichischen Akademie der Wissenschaften*, 134 (1999), 15–41.
- Haldon, J. F., *Byzantium in the seventh century: The transformation of a culture*, Cambridge, 1990.
- Harper, P. O., 'Sasanian silver', in J. Boardman, I. E. S. Edwards, E. Sollberger and N. G. L. Hammond (eds.), *The Cambridge ancient history*, vol. III, part 2: *The Assyrian and Babylonian Empires and other states of the Near East, from the eighth to the sixth centuries BC*, Cambridge, 1983, 1113–29.
- 'Sasanian silver vessels: Recent developments', in V. S. Curtis, R. Hillenbrand and J. M. Rogers (eds.), *The art and archaeology of ancient Persia: New light on the Parthian and Sasanian empires*, London and New York, 1998, 67–73.
- Silver vessels of the Sasanian period*, vol. I: *Royal imagery*, New York, 1981.
- 'La vaisselle en métal', in *Splendeur des Sassanides: L'empire perse entre Rome et la Chine* (224–642), 12 février au 25 avril 1993, Brussels, 1993, 95–108.
- Hartmann, U., 'Geist im Exil: Römische Philosophen am Hof der Sasaniden', in M. Schuol, U. Hartmann and A. Luther (eds.), *Grenzüberschreitungen: Formen des Kontakts zwischen Orient und Okzident im Altertum*, *OrOcc* 3, Stuttgart, 2002, 123–60.
- Hinz, W., *Altiranische Funde und Forschungen*, Berlin, 1969.
- Howard Johnston, J., 'Heraclius' Persian campaigns and the revival of the east Roman empire, 622–630', *War in History*, 6 (1999), 1–44.
- 'The two great powers in Late Antiquity: A comparison', in A. Cameron (ed.), *The Byzantine and early Islamic Near East*, vol. III: *States, resources and armies*, *Studies in Late Antiquity and Early Islam* 1, Princeton, 1995, 157–226.
- Huff, D., 'Architecture, III', *Elr*, vol. II, 329–34.
- 'Architecture sassanide', in *Splendeur des Sassanides: L'empire perse entre Rome et la Chine* (224–642), 12 février au 25 avril 1993, Brussels, 1993, 45–61.

- 'Recherches archéologiques à Takht i Suleiman', *Comptes Rendus de l'Académie des Inscriptions et Belles Lettres* (1978), 774–89.
- 'Sasanian cities', in M. Y. Kiani (ed.), *A general study of urbanization and urban planning in Iran*, Tehran, 1986, 176–204.
- 'Der Takht e Suleiman: Sassanidisches Feuerheiligtum und mongolischer Palast', in T. Stöllner et al. (eds.), *Persiens antike Pracht*, vol. II, Bochum, 2004, 462–71.
- Humbach, H., 'Herrscher, Gott und Gottessohn in Iran und in angrenzenden Ländern', in D. Zeller (ed.), *Menschwerdung Gottes: Vergöttlichung von Herrschern*, Fribourg and Göttingen, 1988, 89–114.
- Huyse, P., 'Histoire orale et écrite en Iran ancien entre mémoire et oubli' (unpublished thesis).
- 'Kerdir and the first Sasanians', in N. Sims Williams (ed.), *Proceedings of the Third European Conference of Iranian Studies, held in Cambridge, 11th to 15th September 1995*, part 1, Wiesbaden, 1998, 109–20.
- 'Noch einmal zu Parallelen zwischen Achaimeniden und Sasanideninschriften', *Archäologische Mitteilungen aus Iran*, n.s. 23 (1990), 177–83.
- 'La revendication de territoires achéménides par les Sassanides: Une réalité historique?' in P. Huyse (ed.), *Iran: Questions et connaissances: Actes du IVe congrès européen des études iraniennes organisé par la Societas Iranologica Europaea*, t. 1: *La période ancienne*, Studia Iranica 25, Paris, 2002, 297–311.
- 'Die sasanidische Königstitulatur: Eine Gegenüberstellung der Quellen', in J. Wiesehöfer and P. Huyse (eds.), *Eran und Aneran: Studien zu den Beziehungen zwischen dem Sasanidenreich und der Mittelmeerwelt*, *OrOcc* 13, Stuttgart, 2006., 181–201.
- 'Vorbemerkungen zur Auswertung iranischen Sprachgutes in den Res Gestae des Ammianus Marcellinus', in W. Skalmowski and A. van Tongerloo (eds.), *Medioiranica*, *Orientalia Lovaniensia Analecta* 48, Leuven, 1993, 87–98.
- Jeroussalimskaja, A., 'Soieries sassanides, A. Histoire culturelle', in *Splendeur des Sassanides: L'empire perse entre Rome et la Chine (224–642)*, 12 février au 25 avril 1993, Brussels, 1993, 113–20.
- de Jong, A., 'Sub Specie Maiestatis: Reflections on Sasanian court rituals', in M. Stausberg (ed.), *Zoroastrian ritual in context*, Leiden, 2004, 345–66.
- de Jonghe, D., 'Soieries sassanides', in *Splendeur des Sassanides: L'empire perse entre Rome et la Chine (224–642)*, 12 février au 25 avril 1993, Brussels, 1993, 121–2.
- Jullien, C., and F. Jullien, *Apôtres des confins: Processus missionnaires chrétiens dans l'Empire iranien*, *Res Orientales* 15, Bures sur Yvette, 2002.
- Kaegi, W. E., *Heraclius: Emperor of Byzantium*, Cambridge, 2003.
- Kaegi, W. E., and P. M. Cobb, 'Heraclius, Shahrbaraz, and al Ṭabarī', in H. Kennedy (ed.), *al Ṭabarī: A medieval Muslim historian and his work*, Princeton, 1999, 121–43.
- Kaldellis, A., *Procopius of Caesarea: Tyranny, history, and philosophy at the end of Antiquity*, Philadelphia, 2004.
- Kalmin, R. L., *Jewish Babylonia between Persia and Roman Palestine: Decoding the literary record*, Oxford, 2006.
- Kawerau, P., 'Correspondance', *Revue d'Histoire Ecclésiastique*, 82 (1987), 338–40.
- Keall, E. J., 'Ayvan (or Taq) e Kesra', *Elr*, vol. III, 155–9.
- Kellens, J., 'L'idéologie religieuse des inscriptions achéménides', *JA*, 290 (2002), 417–64.

- Kettenhofen, E., 'Die Chronik von Arbela in der Sicht der Althistorie', in L. Criscuolo, G. Geraci and C. Salvaterra (eds.), *Simblos: Scritti di storia antica*, Bologna, 1995, 287–319.
- 'Deportations, II', *EIr*, vol. VII, 297–308.
- 'Die Einforderung der achaimenidischen Territorien durch die Sasaniden: eine Bilanz', in S. Kurz (ed.), *Festschrift I. Khalifeh Soltani zum 65. Geburtstag*, Aachen, 2002, 49–75.
- 'Einige Überlegungen zur sasanidischen Politik gegenüber Rom im 3. Jh. n.Chr.', in E. Dabrowa (ed.), *The Roman and Byzantine army in the east: Proceedings of a colloquium held at the Jagiellonian University, Kraków in September 1992*, Crakow, 1994, 99–108.
- 'Review of E. Winter, Die sasanidisch römischen Friedensverträge des 3. Jahrhunderts n. Chr.', *Bibliotheca Orientalis*, 47 (1990), 163–78.
- Die römisch persischen Kriege des 3. Jahrhunderts n.Chr. nach der Inschrift Šāhpuhrs I. an der Ka'be ye Zartošt*, Beihefte zum Tübinger Atlas des Vorderen Orients, series B, no. 35, Wiesbaden, 1982.
- Tirdad und die Inschrift von Paikuli: Kritik der Quellen zur Geschichte Armeniens im späten 3. und frühen 4. Jh. n.Chr.*, Wiesbaden, 1995.
- Kleiss, W., *Die Entwicklung von Palästen und palastartigen Wohnbauten in Iran*, Sitzungsberichte der Österreichischen Akademie der Wissenschaften, Philosophisch historische Klasse 524, Vienna, 1989.
- Kröger, J., 'From Ctesiphon to Nishapur: Studies in Sasanian and Islamic glass', in V. S. Curtis, R. Hillenbrand and J. M. Rogers (eds.), *The art and archaeology of ancient Persia: New light on the Parthian and Sasanian empires*, London and New York, 1998, 133–40.
- Sasanidischer Stuckdekor*, Mainz, 1982.
- Lee, A. D., 'Close kin marriage in Late Antique Mesopotamia', *Greek, Roman and Byzantine Studies*, 29 (1988), 403–13.
- Information and frontiers: Roman foreign relations in Late Antiquity*, Cambridge, 1993.
- Lieu, S. N. C., *Manichaeism in Central Asia and China*, Leiden, 1998.
- Manichaeism in Mesopotamia and the Roman east*, 2nd edn, Leiden, 1999.
- Manichaeism in the later Roman empire and medieval China*, 2nd rev. edn, Tübingen, 1992.
- Litvinsky, B. A., 'The Hephthalite empire', in B. A. Litvinsky (ed.), *History of civilizations of Central Asia*, vol. III: *The crossroads of civilization AD 250 to 750*, Paris, 1996, 135–62.
- Livshits, V. A., and A. B. Nikitin, 'Some notes on the inscription from Nasrabad', *Bulletin of the Asia Institute*, 5 (1991), 41–3.
- Luschey, H., 'Ardašir I., II. Rock reliefs', *EIr*, vol. II, 329–34.
- MacKenzie, D. N., 'The fire altar of Happy *Frayosh', *Bulletin of the Asia Institute*, 7 (1993), 105–9.
- 'Review of M. Back, Die sassanidischen Staatsinschriften', *Indogermanische Forschungen*, 87 (1982), 280–97.
- Macuch, M., 'Barda and Bardadaran II', *EIr*, vol. II, 763–6.
- 'Charitable foundations, I', *EIr*, vol. V, 380–2.
- 'Inzest im vorislamischen Iran', *Archäologische Mitteilungen aus Iran*, 24 (1991), 141–54.
- Rechtskasuistik und Gerichtspraxis zu Beginn des siebenten Jahrhunderts in Iran*, Iranica 1, Wiesbaden, 1993.
- 'Die sasanidische Stiftung "für die Seele": Vorbild für den islamischen waqf', in P. Vavroušek (ed.), *Iranian and Indo European studies: Memorial volume of Otakar Klima*, Prague, 1994, 163–80.

- Malek, H. D., 'A survey of research on Sasanian numismatics', *Numismatic Chronicle*, 153 (1993), 227–69.
- Mancini, M., 'Bilingui greco iraniche in epoca sasanide: Il testo di Šāhpuhr alla Ka'ba yi Zardušt', in E. Campanile, G. R. Cardona and R. Lazzeroni (eds.), *Bilinguismo e biculturalismo nel mondo antico: Atti del colloquio interdisciplinare tenuto a Pisa il 28 e 29 settembre 1987*, Pisa, 1988, 75–99.
- Meisami, J. C., and P. Starkey (eds.), *Encyclopedia of Arabic literature*, 2 vols., London, 1998.
- de Menasce, J., 'Zoroastrian Pahlavi writings', in E. Yarshater (ed.), *The Cambridge history of Iran*, vol. III: *The Seleucid, Parthian and Sasanian periods*, Cambridge, 1983, part 2, 1166–95.
- Metzler, D., *Ziele und Formen königlicher Innenpolitik im vorislamischen Iran*, Münster, 1977.
- Meyer, M., 'Die Felsbilder Shapurs I.', *Jahrbuch des Deutschen Archäologischen Instituts*, 105 (1990), 237–302.
- Mikkelsen, G. B., *Bibliographia Manichaica: A comprehensive bibliography of Manichaeism through 1996*, Corpus Fontium Manichaeorum, Subsidia 1, Turnhout, 1997.
- Millar, F. G. B., *The Roman Near East 31 BC AD 337*, 2nd edn, Cambridge, MA, and London, 1994.
- Morony, M., 'Bahar e Kesra', *Elr*, vol. III, 479.
- Mosig Walburg, K., *Die frühen sasanidischen Könige als Vertreter und Förderer der zarathustrischen Religion: Eine Untersuchung der zeitgenössischen Quellen*, Frankfurt and Bern, 1982.
- Movassat, J. D., *The large vault at Taq i Bustan: A study in late Sasanian royal art*, Lewiston, 2005.
- Musche, B., *Vorderasiatischer Schmuck zur Zeit der Arsakiden und Sasaniden*, Handbuch der Orientalistik VII.1.2B.5, Leiden, 1988.
- Naumann, R., *Die Ruinen von Tacht e Suleiman und Zendan e Suleiman*, Berlin, 1977.
- Neusner, J., *A history of the Jews in Babylonia*, vols. II–V, Leiden, 1960–70.
- Israel and Iran in Talmudic times*, Lanham, 1986.
- Israel's politics in Sasanian Iran*, Lanham, 1986.
- Nöldeke, T., *Das iranische Nationalepos*, Straßburg, 1896.
- Oppenheimer, A., *Babylonia Judaica in the Talmudic period*, Beihefte zum Tübinger Atlas des Vorderen Orients, series B, no. 47, Wiesbaden, 1983.
- Panaino, A., 'The bayan of the Fratarakas: Gods or "divine" kings?', in C. G. Cereti, M. Maggi and E. Provasi (eds.), *Religious themes and texts of pre Islamic Iran and Central Asia: Studies in honour of Prof. Gherardo Gnoli on the occasion of his 65th birthday on 6th December 2002*, Beiträge zur Iranistik 24, Wiesbaden, 2003, 265–88.
- 'Greci e Iranici: Confronto e conflitti', in S. Settis (ed.), *I Greci*, vol. III: *I Greci oltre la Grecia*, Torino, 2001, 79–136.
- 'Women and kingship: Some remarks about the enthronisation of Queen Boran and her sister Azarmigduxt', in J. Wiesehöfer and P. Huyse (eds.), *Eran und Aneran: Studien zu den Beziehungen zwischen dem Sasanidenreich und der Mittelmeerwelt*, OrOcc 13, Stuttgart, 2006, 221–40.
- Peck, E. H., 'Clothing, IV', *Elr*, vol. V, 739–52.
- Perikhanian, A., 'Iranian society and law', in E. Yarshater (ed.), *The Cambridge history of Iran*, vol. III: *The Seleucid, Parthian and Sasanian periods*, Cambridge, 1983, part 2, 627–80.

- Pieler, P., 'L'aspect politique et juridique de l'adoption de Chosroes proposée par les Perses à Justin', *Revue Internationale des Droits de l'Antiquité*, 3 (1972), 399–433.
- Potter, D. S., *Prophecy and history in the crisis of the Roman empire: A historical commentary on the Thirteenth Sibylline Oracle*, Oxford, 1990.
- Potts, D. T., 'Gundeshapur and the Gondeis', *Iranica Antiqua*, 24 (1989), 323–35.
- Preißler, H., 'Arabien zwischen Byzanz und Persien', in L. Rathmann et al. (eds.), *Geschichte der Araber*, vol. I, 2nd edn, Berlin, 1975, 36–56.
- Richter Bernburg, L., 'Iran's contribution to medicine and veterinary science in Islam AH 100–900/AD 700–1500', in J. A. C. Greppin et al. (eds.), *The diffusion of Greco Roman medicine into the Middle East and the Caucasus*, Delmar, 1999, 139–67.
- 'Mani's Dodecads and Sasanian chronology', *Zeitschrift für Papyrologie und Epigraphik*, 95 (1993), 71–80.
- 'Medicine, pharmacology and veterinary science in Islamic eastern Iran and Central Asia', in C. E. Bosworth and M. S. Asimov (eds.), *History of civilizations of Central Asia*, vol. IV: *The age of achievement: AD 750 to the end of the fifteenth century*, part 2: *The achievements*, Paris, 2000, 299–317.
- 'On the diffusion of medical knowledge in Persian court culture during the fourth and fifth centuries AH', in Z. Vezel et al. (eds.), *La science dans le monde iranien à l'époque islamique*, Tehran, 1998, 219–33.
- Rothstein, G., *Die Dynastie der Lahmiden in al Ḥira: Ein Versuch zur arabisch persischen Geschichte zur Zeit der Sasaniden*, Berlin, 1899.
- Rubin, B., *Das Zeitalter Iustinians*, vol. I, Berlin, 1960.
- Rubin, Z., 'Diplomacy and war in the relations between Byzantium and the Sassanids in the fifth century AD', in P. W. Freeman and D. L. Kennedy (eds.), *The defence of the Roman and Byzantine east: Proceedings of a colloquium held at the University of Sheffield in April 1986*, BAR International Series 297, part 2, Oxford, 1986, 677–95.
- 'Ibn al Muqaffa' and the account of Sasanian history in the Arabic Codex Sprenger 30', *JSAI*, 30 (2005), 52–93.
- 'Res Gestae Divi Saporis: Greek and Middle Iranian in a document of Sasanian anti Roman propaganda', in J. N. Adams, M. Janse and S. Swain (eds.), *Bilingualism in ancient society: Language contact and the written text*, Oxford, 2002, 267–97.
- 'The Roman empire in the Res Gestae Divi Saporis: The Mediterranean world in Sasanian propaganda', in E. Dabrowa (ed.), *Ancient Iran and the Mediterranean world*, *Electrum* 2, Crakow, 1998, 177–85.
- Sako, L., *Le rôle de la hiérarchie syriaque orientale dans les rapports diplomatiques entre la Perse et Byzance aux Ve–VIIe siècles*, Paris, 1986.
- Schick, R., *The Christian communities of Palestine from Byzantine to Islamic rule: A historical and archaeological study*, Studies in Late Antiquity and Early Islam 2, Princeton, 1995.
- Schippmann, K., *Grundzüge der Geschichte des sasanidischen Reiches*, Darmstadt, 1990.
- Schneider, R. M., 'Orientalism in Late Antiquity: The Oriental other in imperial and Christian imagery', in J. Wiesehöfer and P. Huyse (eds.), *Eran und Aneran: Studien zu den Beziehungen zwischen dem Sasanidenreich und der Mittelmeerwelt*, *OrOcc* 13, Stuttgart, 2006, 241–78.
- Scholten, H., *Der Eunuch in Kaisernähe: Zur politischen und sozialen Bedeutung des praepositus sacri cubiculi im 4. und 5. Jahrhundert n. Chr.*, *Prismata* 5, Frankfurt, 1995.

- Schwaigert, W., *Das Christentum in Huzistan im Rahmen der frühen Kirchengeschichte Persiens*, Marburg, 1989.
- Sezgin, F., *Geschichte des arabischen Schrifttums*, vol. I, Leiden, 1967.
- Shahbazi, A. S., 'Army, I', *EIr*, vol. II, 489–99.
- 'Bahram VI Čobin', *EIr* vol. III, 519–22.
- 'Early Sasanians' claim to Achaemenid heritage', *Nâme ye Irân e Bâstân*, 1, 1 (2001), 61–73.
- 'On the X^waday namag', *Acta Iranica*, 30 (1990), 208–29.
- Shahid, I., *Byzantium and the Arabs in the fifth century*, Washington, 1989.
- Byzantium and the Arabs in the fourth century*, Washington, 1984.
- Byzantium and the Arabs in the sixth century*, I.1–2, Washington, 1995.
- 'The Iranian factor in Byzantium during the reign of Heraclius', *Dumbarton Oaks Papers*, 26 (1971), 295–320.
- Skjærvø, P. O., 'L'inscription d'Abnun et l'imperfait moyen perse', *Studia Iranica*, 21 (1992), 153–60.
- 'Thematic and linguistic parallels in the Achaemenian and Sasanian inscriptions', *Acta Iranica*, 25 (1985), 593–603.
- Springberg Hinsen, M., *Die Zeit vor dem Islam in arabischen Universalgeschichten des 9. bis 12. Jahrhunderts*, Würzburg and Altenberge, 1989.
- Stausberg, M., *Die Religion Zarathushtras*, vol. I, Stuttgart, 2002.
- Strobel, K., *Das Imperium Romanum im '3. Jahrhundert'*, *Historia Einzelschriften* 75, Stuttgart, 1993.
- Sundermann, W., 'The date of the Barm e Delak inscription', *Bulletin of the Asia Institute*, n.s. 7 (1993), 203–5.
- 'Ke čîhr az yazda: Zur Titulatur der Sasanidenkönige', *Archiv Orientalni*, 56 (1988), 338–40.
- 'Mazdak und die mazdakitischen Volksaufstände', *Altertum*, 23 (1977), 245–9.
- 'Review of H. Humbach and P. O. Skjærvø, *The Sassanian inscription of Paikuli*', *Kratylos*, 28 (1983), 82–9.
- 'Shapur's coronation: The evidence of the Cologne Mani Codex reconsidered and compared with other texts', *Bulletin of the Asia Institute*, n.s. 4 (1990), 295–9.
- 'Studien zur kirchengeschichtlichen Literatur der iranischen Manichäer I/II', *Altorientalische Forschungen*, 13 (1986), 40–92, 239–317.
- 'Studien zur kirchengeschichtlichen Literatur der iranischen Manichäer III', *Altorientalische Forschungen*, 14 (1987), 41–107.
- Tanabe, K., 'Iconography of the royal hunt bas reliefs at Taq i Bustan', *Orient* (Tokyo), 19 (1983), 103–16.
- Tavadia, J. C., *Die mittelpersische Sprache und Literatur der Zarathustrier*, Leipzig, 1956.
- Tavoosi, M., and R. N. Frye, 'An inscribed capital dating from the time of Shapur I', *Bulletin of the Asia Institute*, n.s. 3 (1990), 25–38.
- Teitler, H., 'Visa vel lecta? Ammianus on Persia and the Persians', in J. W. Drijvers and D. Hunt (eds.), *The late Roman world and its historian*, London and New York, 1999, 216–23.
- Trümpelmann, L., *Zwischen Persepolis und Firuzabad*, Mainz, 1991.
- Tyler Smith, S., 'Calendars and coronations: The literary and numismatic evidence for the accession of Khusrâu II', *Byzantine and Modern Greek Studies*, 28 (2004), 33–65.
- Ullmann, M., *Islamic medicine*, Edinburgh, 1978.

- Weber, U., *Prosopographie des frühen Sasanidenreiches*, Kiel, 2004, available at www.uni-kiel.de/klassalt/projekte/sasaniden/index.html.
- Whitby, M., *The emperor Maurice and his historian: Theophylact Simocatta on Persian and Balkan warfare*, Oxford, 1988.
- ‘The Persian king at war’, in E. Dabrowa (ed.), *The Roman and Byzantine army in the east: Proceedings of a colloquium held at the Jagiellonian University, Kraków, in September 1992*, Crakow, 1994, 227–63.
- Whitehouse, D., ‘La verrerie’, in *Splendeur des Sassanides: L’empire perse entre Rome et la Chine (224–642)*, 12 février au 25 avril 1993, Brussels, 1993, 109–11.
- Widengren, G., ‘Sources of Parthian and Sasanian history’, in E. Yarshater (ed.), *The Cambridge history of Iran*, vol. III: *The Seleucid, Parthian and Sasanian periods*, Cambridge, 1983, part 2, 1261–83.
- Wiesehöfer, J., ‘Ardašīr I., I. History’, *Elr*, vol. II, 371–6.
- ‘From Achaemenid imperial order to Sasanian diplomacy: War, peace and reconciliation in pre Islamic Iran’, in K. Raaflaub (ed.), *War and peace in the ancient world*, Oxford, 2007, 121–40.
- ‘Gebete für die “Urahen” oder: Wann und wie verschwanden Kyros und Dareios aus der Tradition Irans?’, in E. Dabrowa (ed.), *Tradition and innovation in the ancient world*, Electrum 6, Crakow, 2002, III–17.
- ‘Geteilte Loyalitäten: Religiöse Minderheiten des 3. und 4. Jahrhunderts n.Chr. im Spannungsfeld zwischen Rom und dem sasanidischen Iran’, *Klio*, 75 (1993), 362–82.
- Iraniens, Grecs et Romains*, Cahiers à Studia Iranica 32, Paris, 2005.
- ‘Iranische Ansprüche an Rom auf ehemals achaimenidische Territorien’, *Archäologische Mitteilungen aus Iran*, n.s. 19 (1986), 177–86.
- ‘Narseh, Diokletian, Manichäer und Christen’, in M. Arafat, J. Tubach and G. S. Vashalomidze (eds.), *Inkulturation des Christentums im Sasanidenreich*, Wiesbaden, 2007, 161–9.
- “‘Randkultur’ oder ‘Nabel der Welt’? Das Sasanidenreich und der Westen: Anmerkungen eines Althistorikers”, in J. Wiesehöfer and P. Huyse (eds.), *Eran und Aneran: Studien zu den Beziehungen zwischen dem Sasanidenreich und der Mittelmeerwelt*, *OrOcc* 13, Stuttgart, 2006., 9–28.
- ‘Rum as enemy of Iran’, in E. Gruen (ed.), *Cultural borrowings and ethnic appropriations in Antiquity*, *OrOcc* 8, Stuttgart, 2005, 105–20.
- ‘Zeugnisse zur Geschichte und Kultur der Persis unter den Parthern’, in J. Wiesehöfer (ed.), *Das Partherreich und seine Zeugnisse The Arsacid empire: Sources and documentation. Beiträge des Internationalen Colloquiums, Eutin (27. 29. Juni 1996)*, Historia Einzelschriften 122, Stuttgart, 1998, 338–40.
- ‘Zum Nachleben von Achaimeniden und Alexander in Iran’, in H. Sancisi Weerdenburg, A. Kuhrt and M. C. Root (eds.), *Achaemenid history VIII: Continuity and change*, Leiden, 1994, 389–97.
- Winter, E., ‘Legitimität als Herrschaftsprinzip: Kaiser und “König der Könige” im wechselseitigen Verkehr’, in H. J. Drexhage and J. Sünskes (eds.), *Migratio et Commutatio: Studien zur Alten Geschichte und deren Nachleben. Th. Pekáry zum 60. Geburtstag am 13. September 1989 dargebracht von Freunden, Kollegen und Schülern*, St Katharinen, 1988, 72–92.
- ‘On the regulation of the eastern frontier of the Roman empire in 298’, in D. H. French and C. S. Lightfoot (eds.), *The eastern frontier of the Roman empire: Proceedings of a colloquium held at Ankara in September 1988*, BAR International Series 553, part 1, Oxford, 1989, 555–71.

- Die sasanidisch römischen Friedensverträge des 3. Jahrhunderts n.Chr.: Ein Beitrag zum Verständnis der außenpolitischen Beziehungen zwischen den beiden Großmächten*, Europäische Hochschulschriften III, 350, Frankfurt, 1988.
- Zeimal, E. V., 'The Kidarite kingdom in Central Asia', in B. A. Litvinsky (ed.), *History of civilizations of Central Asia*, vol. III: *The crossroads of civilization AD 250 to 750*, Paris, 1996, 119–33.

Chapter 4: Pre-Islamic Arabia

Practical suggestions for further reading

- Hoyland, Robert G., *Arabia and the Arabs from the Bronze Age to the coming of Islam*, London and New York, 2001.
- Kister, M. J., *Studies in jahiliyya and early Islam*, London, 1980.
- Peters, F. E. (ed.), *The Arabs and Arabia on the eve of Islam*, Aldershot, 1999.

Primary sources

- Caskel, Werner, and Gert Strenziok, *Ġamharat an Nasab: Das genealogische Werk des Hišam ibn Muḥammad al Kalbi*, 2 vols., Leiden, 1966.
- al Ḥilli, Abu l Baqa' Hibat Allah, *al Manaḡib al mazyadiyya*, ed. Ṣaliḥ Musa Daradika and Muḥammad 'Abd al Qadir Khrisat, 2 vols., Amman, 1404/1984.
- Ibn al Kalbi, *al Aṣnam*, ed. Aḥmad Zakī Basha, Cairo, 1343/1924.
- Ibn Sa'īd al Andalusī, *Nashwat al ʿarab bi ta'rīkh jahiliyyat al 'arab*, ed. Naṣrat 'Abd al Raḥman, 2 vols., Amman, 1982.
- al Marzuqī, Abu 'Alī, *Kitab al azmina wa'l amkina*, Hyderabad, 1332 {1913}; repr. Cairo, n.d.
- al Samhūdī, 'Alī ibn Aḥmad, *Wafa' al wafa*, ed. Qasim al Samarra'ī, 5 vols., London and Jiddah, 1422/2001.

Secondary sources

- Abdalla, Abdelgadir M., Sami al Sakkar and Richard Mortel (eds.), *Pre Islamic Arabia: Proceedings of the Second International Symposium on Studies in the History of Arabia*, 1399/1979, Riyadh, 1984.
- Kister, M. J., 'Labbayka, allahumma, Labbayka: On a monotheistic aspect of a Jahiliyya practice', *JSAI*, 2 (1980), 33–57.
- 'Mecca and the tribes of Arabia', in M. Sharon (ed.), *Studies in Islamic history and civilization in honour of David Ayalon*, Jerusalem and Leiden, 1986, 33–57.
- Levi della Vida, Giorgio, 'Pre Islamic Arabia', in Nabih Amin Faris (ed.), *The Arab heritage*, Princeton, 1944, 25–57.
- Maraqten, Mohammed, 'Writing materials in pre Islamic Arabia', *JSS*, 43 (1998), 287–310.
- Robin, Christian Julien, 'South Arabia, religions in pre Islamic', *Encyclopaedia of the Qur'an*. 'Yemen', *Encyclopaedia of the Qur'an*.

Chapter 5: The rise of Islam, 600–705

Practical suggestions for further reading

- Cook, M., *Muhammad*, Oxford, 1983.
- Crone, P., *Meccan trade and the rise of Islam*, Princeton, 1987; repr. Piscataway, NJ, 2004.

Bibliography

- Slaves on horses: The evolution of the Islamic polity*, Cambridge, 1980.
- Donner, F. M., *The early Islamic conquests*, Princeton, 1981.
- Hawting, G. R., *The first dynasty of Islam: The Umayyad caliphate, AD 661–750*, 2nd edn, London and Sydney, 2000.
- Hoyland, R., *Seeing Islam as others saw it: A survey and evaluation of Christian, Jewish and Zoroastrian writings on early Islam*, Princeton, 1997.
- Humphreys, R. S., *Mu'awiya ibn Abi Sufyan: From Arabia to empire*, Oxford, 2006.
- Ibn Warraq (ed.), *The quest for the historical Muhammad*, Amherst, NY, 2000.
- Kennedy, H., *The great Arab conquests*, London, 2007.
- The Prophet and the age of the caliphates*, 2nd edn, London, 2004.
- Madelung, W., *The succession to Muḥammad: A study of the early caliphate*, Cambridge, 1997.
- Motzki, H. (ed.), *The biography of Muḥammad: The issue of the sources*, Leiden, 2000.
- de Prémare, A. L., *Les fondations de l'islam: Entre écriture et histoire*, Paris, 2002.
- Robinson, C. F., *ʿAbd al Malik*, Oxford, 2005.
- Rubin, U., *The eye of the beholder: The life of Muḥammad as viewed by the early Muslims*, Princeton, 1995.

Primary sources

- Abu al Faṭḥ al Samiri, *The continuatio of the Samaritan chronicle of Abu al Faṭḥ al Samiri al Danaḥi*, ed. and trans. M. Levy Rubin, Princeton, 2002.
- Ibn Hisham, al Sira al nabawiyya, ed. M. al Ṣaqqā et al., 4 vols., Cairo, 1936; trans. A. Guillaume as *The Life of Muhammad*, Oxford, 1955.
- John of Damascus, *Écrits sur l'Islam*, ed. and trans. R. Le Coz, Paris, 1992.
- Sebeos, *The Armenian history attributed to Sebeos*, trans. R. W. Thomson with commentary by J. Howard Johnston, Translated Texts for Historians 31, Liverpool, 1999.
- al Ṭabarī, Abu Ja'far Muḥammad ibn Jarīr, *Ta'rikh al rusul wa'l muluk*, ed. M. J. de Goeje et al., 15 vols. in 3 series, Leiden, 1879–1901; sections trans. I. K. Poonawala as *The history of al Ṭabarī*, vol. IX: *The last years of the Prophet*, Albany, 1990; trans. G. H. A. Juynboll as *The history of al Ṭabarī*, vol. XIII: *The conquest of Iraq, southwestern Persia, and Egypt*, Albany, 1989.

Secondary sources

- Agha, S., and T. Khalidi, 'Poetry and identity in the Umayyad age', *al Abhath*, 50 1 (2002 3), 55–120.
- Album, S., and T. Goodwin, *Sylloge of Islamic coins in the Ashmolean*, vol. I: *The pre reform coinage of the early Islamic period*, London, 2002.
- Andrae, T., 'Der Ursprung des Islams und das Christentum', *Kyrkohistorisk Årsskrift*, 23 (1923), 149–206.
- Athamina, K., 'Abraham in Islamic perspective: Reflections on the development of monotheism in pre Islamic Arabia', *Der Islam*, 81 (2004), 184–205.
- 'Arab settlement during the Umayyad period', *JSAI*, 8 (1986), 185–207.
- Bamyeh, M., *The social origins of Islam: Mind, economy, discourse*, Minneapolis, 1999.
- Bashear, S., 'Ashura, an early Muslim fast', *ZDMG*, 141 (1991), 281–316; repr. in S. Bashear, *Studies in early Islamic tradition*, Jerusalem, 2004.

- Bates, M., 'Byzantine coinage and its imitations, Arab coinage and its imitations: Arab Byzantine coinage', *Aram*, 6 (1994), 381–403.
- Beauchamp, J., F. Briquel Chatonnet and C. Robin, 'La persécution des chrétiens de Nagran et la chronologie Himyarite', *Aram*, 11–12 (1999–2000), 15–83.
- Beauchamp, J., and C. Robin, 'Le Christianisme dans le péninsule arabique dans l'épigraphie et l'archéologie', *Hommage à Paul Lemerle, Travaux et mémoires*, 8, Paris, 1981, 45–61.
- Beeston, A., 'Himyarite monotheism', in A. M. Abdulla *et al.* (eds.), *Studies in the history of Arabia*, vol. II: *Pre Islamic Arabia*, Riyadh, 1984, 149–54.
- 'Kingship in ancient South Arabia', *JESHO*, 15 (1972), 256–68.
- Berg, H., 'Islamic origins reconsidered: John Wansbrough and the study of early Islam', *Method and Theory in the Study of Religion*, 9 (1997), 3–22.
- Berthier, S. (ed.), *Peuplement rural et aménagements hydroagricoles dans la moyenne vallée de l'Euphrat, fin VIIe–XIXe siècle*, Damascus, 2001.
- Bone, H., 'The administration of Umayyad Syria: The evidence of the copper coins', Ph.D. thesis, Princeton University, 2000.
- Boyd, S., and M. Mango (eds.), *Ecclesiastical silver plate in sixth century Byzantium*, Washington, DC, 1992.
- Brock, S. P., 'North Mesopotamia in the late seventh century: Book xv of John Bar Penkaye's *Riṣ Melle*', *JSAI*, 9 (1987), 51–75.
- Busse, H., 'Omar b. al Ḥaṭṭab in Jerusalem', *JSAI*, 5 (1984), 73–119.
- Combe, E., J. Sauvaget and G. Wiet, *Répertoire chronologique d'épigraphie arabe I*, Cairo, 1931.
- Conrad, L. I., 'Abraha and Muḥammad: Some observations apropos of chronology and literary topoi in the early Arabic historical tradition', *BSOAS*, 50 (1987), 225–40.
- 'The conquest of Arwad: A source critical study in the historiography of the early medieval Near East', in A. Cameron and L. I. Conrad (eds.), *The Byzantine and early Islamic Near East*, vol. I: *Problems in the literary source material*, Princeton, 1992, 317–401.
- Constantelos, D. J., 'The Moslem conquests of the Near East as revealed in the Greek sources of the seventh and eighth centuries', *Byzantion*, 42 (1972), 325–57.
- Cook, M., 'Anan and Islam: The origins of Karaite scripturalism', *JSAI*, 9 (1987), 161–82.
- 'Magian cheese: An archaic problem in Islamic law', *BSOAS*, 47 (1984), 449–67.
- 'The opponents of the writing of tradition in early Islam', *Arabica*, 44 (1997), 437–530.
- Crone, P., 'The first century concept of *hiğra*', *Arabica*, 41 (1994), 352–87.
- Medieval Islamic political thought*, Edinburgh, 2004.
- 'Quraysh and the Roman army: Making sense of the Meccan leather trade', *BSOAS*, 70 (2007), 63–88.
- 'Were the Qays and Yemen of the Umayyad period political parties?', *Der Islam*, 71 (1994), 1–57.
- Crone, P., and M. Cook, *Hagarism: The making of the Islamic world*, Cambridge, 1977.
- Crone, P., and M. Hinds, *God's caliph: Religious authority in the first centuries of Islam*, Cambridge, 1986.
- Crone, P., and F. Zimmermann, *The Epistle of Salim ibn Dhakwan*, Oxford, 2001.
- Dixon, A. A., *The Umayyad caliphate 65–86/684–705 (a political study)*, London, 1971.
- Djait, H., *La grande discorde: Religion et politique dans l'Islam des origines*, Paris, 1989.
- Donner, F. M., 'The formation of the Islamic state', *JAOS*, 106 (1986), 283–96.

- 'From believers to Muslims: Confessional self identity in the early Islamic community', *al Abhath*, 50 1 (2002 3), 9 53.
- Elad, A., 'The southern Golan in the early Muslim period: The significance of two newly discovered milestones of 'Abd al Malik', *Der Islam*, 76 (1999), 33 88.
- Finster, B., *Frühe iranische Moscheen*, Berlin, 1994.
- Flood, F. B., *The Great Mosque of Damascus: Studies on the makings of an Umayyad visual culture*, Leiden, 2001.
- Foote, R. M., 'Commerce, industrial expansion, and orthogonal planning: Mutually compatible terms in settlements of Bilad al Sham during the Umayyad period', *Mediterranean Archaeology*, 13 (2000), 25 38.
- Foss, C., 'The coinage of Syria in the seventh century: The evidence of excavations', *Israel Numismatic Journal*, 13 (1994 9), 119 32.
- 'The Near Eastern countryside in Late Antiquity: A review article', *The Roman and Byzantine Near East: Journal of Roman Archaeology*, supplementary series 14 (1995), 213 34.
- 'The Persians in Asia Minor and the end of Antiquity', *The English Historical Review*, 90 (1975), 721 47.
- 'Syria in transition, AD 550 750: An archaeological approach', *Dumbarton Oaks Papers*, 51 (1997), 189 269.
- 'A Syrian coinage of Mu'awiya?', *Revue Numismatique*, 157 (2002), 353 65.
- Gascou, J., 'De Byzance à l'Islam: Les impôts en Egypte après la conquête arabe', *JESHO*, 26 (1983), 97 109.
- Gil, M., 'The creed of Abu 'Amir', *Israel Oriental Studies*, 12 (1992), 9 57.
- Gilliot, C., 'Le Coran, fruit d'un travail collectif', in D. De Smet et al. (eds.), *al Kitab: La sacralité du texte dans le monde de l'Islam*, Brussels, 2004, 186 231.
- Gran, P., 'Political economy as a paradigm for the study of Islamic history', *IJMES*, 11 (1980), 511 26.
- Grierson, P., 'The monetary reforms of 'Abd al Malik: Their metrological basis and their financial repercussions', *JESHO*, 3 (1960), 241 64.
- Griffith, S. H., 'Disputes with Muslims in Syriac Christian texts: From Patriarch John (d. 648) to Bar Hebraeus (d. 1286)', in B. Lewis and R. Niewöhner (eds.), *Religionsgespräche in Mittelalter*, Wiesbaden, 1992, 251 73.
- Grohmann, A., *Arabische Chronologie*, Leiden, 1966.
- The world of Arabic papyri*, Cairo, 1952.
- Gyselen, R., and L. Kalus, *Deux trésors monétaires des premiers temps de l'islam*, Paris, 1983.
- Halevi, L., 'The paradox of Islamization: Tombstone inscriptions, Qur'anic recitations, and the problem of religious change', *History of Religions*, 44 (2004), 120 52.
- Halm, H., *Shiism*, Edinburgh, 1991.
- Hawting, G. R., *The idea of idolatry and the emergence of Islam: From polemic to history*, Cambridge, 1999.
- 'The significance of the slogan *la hukma illa lillah* and the references to the *hudud* in the traditions about the *fitna* and the murder of 'Uthman', *BSOAS*, 41 (1978), 453 63.
- Healey, J. F., 'The Christians of Qatar in the 7th century AD', in I. R. Netton (ed.), *Studies in honour of Clifford Edmund Bosworth*, vol. I: *Hunter of the east: Arabic and Semitic studies*, Leiden, 2000, 222 37.
- Heck, G. W., "'Arabia without spices": An alternate hypothesis', *JAOS*, 123 (2003), 547 76.

- Heidemann, S., 'The merger of two currency zones in early Islam: The Byzantine and Sasanian impact on the circulation in former Byzantine Syria and northern Mesopotamia', *Iran*, 36 (1998), 95–112.
- Hinds, M., 'The first Arab conquests of Fars', *Iran*, 22 (1984), 39–53.
- 'Kufan political alignments and their background in the mid seventh century AD', *IJMES*, 2 (1971), 346–67.
- Howard Johnston, J., 'The official history of Heraclius' Persian campaigns', in E. Dabrowa (ed.), *The Roman and Byzantine army in the east: Proceedings of a colloquium held at the Jagiellonian University, Kraków, in September 1992*, Crakow, 1994, 57–87.
- Hoyland, R., *Arabia and the Arabs from the Bronze Age to the coming of Islam*, London and New York, 2001.
- 'New documentary texts and the early Islamic state', *BSOAS*, 69, 3 (2006), 395–416.
- 'Writing the biography of the Prophet Muhammad: Problems and solutions', *History Compass*, 5 (2007), 581–602.
- Humphreys, R. S., 'Qur'anic myth and narrative structure in early Islamic historiography', in F. M. Clover and R. S. Humphreys (eds.), *Tradition and innovation in Late Antiquity*, Madison, 1989, 271–90.
- Ibrahim, A., *Der Herausbildungsprozeß des arabisch islamischen Staates*, Berlin, 1994.
- Ibrahim, M., *Merchant capital and Islam*, Austin, 1990.
- Johns, J., 'Archaeology and the history of early Islam: The first seventy years', *JESHO*, 46 (2003), 411–36.
- 'The "House of the Prophet" and the concept of the mosque', in J. Johns (ed.), *Bayt al Maqdis: Jerusalem and early Islam*, Oxford Studies in Islamic Art 9, part 2, Oxford, 1999, 59–112.
- Jones, A., 'The language of the Qur'an', in K. Dévényi, T. Iványi and A. Shvigel (eds.), *Proceedings of the Colloquium on Arabic Lexicology and Lexicography*, Budapest, 1993, 29–48.
- Kaplony, A., *Konstantinopel und Damaskus: Gesandtschaften und Verträge zwischen Kaisern und Kalifen 639–750*, Berlin, 1996.
- Kennedy, H., 'From polis to madina: Urban change in Late Antique and early Islamic Syria', *Past and Present*, 106 (1985), 3–27.
- Kennet, D., 'The decline of eastern Arabia in the Sasanian period', *Arabian Archaeology and Epigraphy*, 18 (2007), 86–122.
- 'On the eve of Islam: Archaeological evidence from eastern Arabia', *Antiquity*, 79 (2005), 107–18.
- Kister, M. J., 'Haddithu 'an banī isra'īla wa la ḥaraja', *Israel Oriental Studies*, 2 (1972), 215–47.
- 'Labbayka, allahuma, labbayka: On a monotheistic aspect of a jahiliyya practice', *JSAI*, 2 (1980), 33–57.
- 'The massacre of the Banu Qurayza: A re examination of a tradition', *JSAI*, 8 (1986), 61–96.
- 'On the papyrus of Wahb b. Munabbih', *BSOAS*, 37 (1974), 545–71.
- '"Rajab is the month of God": A study in the persistence of an early tradition', *Israel Oriental Studies*, 1 (1971), 191–223.
- Korotayev, A., V. Klimenko and D. Proussakov, 'Origins of Islam: Political anthropological and environmental context', *Acta Orientalia Academiae Scientiarum Hungaricae*, 52 (1999), 243–76.

- Landau Tasserón, E., 'Features of the pre conquest Muslim army in the time of Muḥammad', in A. Cameron (ed.), *The Byzantine and early Islamic Near East*, vol. III: *States, resources and armies*, Studies in Late Antiquity and Early Islam 1, Princeton, 1995, 299–336.
- Lecker, M., *'The Constitution of Medina': Muḥammad's first legal document*, Princeton, 2004.
- 'The death of the Prophet Muḥammad: Did Waqidī invent some of the evidence?', *ZDMG*, 145 (1995), 9–27.
- 'Did Muḥammad conclude treaties with the Jewish tribes Naḍir, Qurayza and Qaynuqa?', *Israel Oriental Studies*, 17 (1997), 29–36.
- 'Judaism among Kinda and the ridda of Kinda', *JAOS*, 115 (1995), 635–50.
- Luxenberg, C., *Die syro aramäische Lesart des Koran*, 2nd edn, Berlin, 2004; trans. as *The Syro Aramaic reading of the Koran*, Berlin, 2007.
- Magness, J., *The archaeology of the early Islamic settlement in Palestine*, Winona Lake, IN, 2003.
- Morelli, F., *Documenti Greci per la fiscalità e la amministrazione dell'Egitto Arabo*, Vienna, 2001.
- Morimoto, K., *The fiscal administration of Egypt in the early Islamic period*, Kyoto, 1981.
- Morony, M., 'Economic boundaries? Late Antiquity and early Islam', *JESHO*, 47 (2004), 166–94.
- 'The effects of the Muslim conquest on the Persian population of Iraq', *Iran*, 14 (1976), 41–59.
- Iraq after the Muslim conquest*, Princeton, 1984.
- Morrison, C., 'La monnaie en Syrie byzantine', in J. M. Dentzer and W. Orthmann (eds.), *Archéologie et histoire de la Syrie II*, Saarbrücken, 1989, 191–204.
- 'Monnayage omeyyade et l'histoire administrative et économique de la Syrie', in P. Canivet and J. P. Rey Coquais (eds.), *La Syrie de Byzance à l'Islam*, Damascus, 1992, 309–21.
- Nevo, Y., and J. Koren, *Crossroads to Islam: The origins of the Arab religion and the Arab state*, Amherst, NY, 2003.
- Nicoll, D., 'Arms of the Umayyad era: Military technology in a time of change', in Y. Lev (ed.), *War and society in the eastern Mediterranean, 7th–15th centuries*, Leiden, 1997, 9–100.
- Olagüe, I., *Les arabes n'ont jamais envahi l'Espagne*, Paris, 1969.
- Palmer, A., S. Brock and R. Hoyland, *The seventh century in the West Syrian chronicles*, Liverpool, 1993.
- Pampus, K. H., *Über die Rolle der Ḥarīḡya im frühen Islam*, Wiesbaden, 1980.
- Peters, F. E., 'The quest for the historical Muhammad', *IJMES*, 23 (1991), 291–315.
- Petersen, E. L., *ʿAlī and Muʿawiya in early Arabic tradition: Studies on the genesis and growth of Islamic historical writing until the end of the ninth century*, 2nd edn, Odense, 1974 [Copenhagen, 1964].
- Potts, D., *The Arabian Gulf in Antiquity*, Oxford, 1990.
- Puin, G., *Der Dīwan von ʿUmar ibn al Ḥaṭṭab: Ein Beitrag zur frühislamischen Verwaltungsgeschichte*, Bonn, 1970.
- Rippin, A., 'RḤMNN and the Ḥanīfs', in W. B. Hallaq and D. P. Little (eds.), *Islamic studies presented to Charles J. Adams*, Leiden, 1991, 153–68.
- Robin, C., 'Judaïsme et christianisme en Arabie du sud d'après les sources épigraphiques et archéologiques', *Proceedings of the Seminar for Arabian Studies*, 10 (1980), 85–96.
- 'Le judaïsme de Himyar', *Arabia*, 1 (2003), 97–172.

- 'Du paganisme au monothéisme', in C. Robin (ed.), *L'Arabie antique de Karib'il à Mahomet: Nouvelles données sur l'histoire des arabes grâce aux inscriptions*, Aix en Provence, 1991, 139–55.
- Robinson, C. F., 'The conquest of Khuzistan: A historiographic reassessment', *BSOAS*, 67 (2004), 14–39.
- Empire and elites after the Muslim conquest: The transformation of northern Mesopotamia*, Cambridge Studies in Islamic Civilization, Cambridge, 2000.
- 'Neck sealing in early Islam', *JESHO*, 48 (2005), 401–44.
- 'Reconstructing early Islam: Truth and consequences', in H. Berg (ed.), *Method and theory in the study of Islamic origins*, Leiden, 2003, 101–34.
- Rotter, G., *Die Umayyaden und der zweite Bürgerkrieg (680–692)*, Wiesbaden, 1982.
- Rubin, U., *Between Bible and Qur'an: The Children of Israel and the Islamic self image*, Princeton, 1999.
- Sayed, R., *Die Revolte des Ibn al Ash'at und die Koranleser*, Freiburg, 1977.
- Schick, R., *The Christian communities of Palestine from Byzantine to Islamic rule: A historical and archaeological study*, Princeton, 1995.
- Schmucker, W., *Untersuchungen zu einigen wichtigen bodenrechtlichen Konsequenzen der islamischen Eroberungsbewegung*, Bonn, 1972.
- Schoeler, G., *Charakter und Authentie der muslimischen Überlieferung über das Leben Mohammeds*, Berlin, 1996.
- Sfar, M., *Le coran est il authentique?*, Paris, 2000.
- Shahid, I., *Byzantium and the Arabs in the fifth century*, Washington, DC, 1989.
- Byzantium and the Arabs in the sixth century*, vol. I, parts 1–2, Washington, DC, 1995 and 2002.
- Shoshan, B., *Poetics of Islamic historiography: Deconstructing Tabari's History*, Leiden, 2004.
- Sijpesteijn, P., 'New rule over old structures: Egypt after the Muslim conquest', in H. Crawford (ed.), *Regime change in the ancient Near East and Egypt, from Sargon of Agade to Saddam Hussein*, *Proceedings of the British Academy* 136, London, 2007, 183–200.
- Simonsen, J. B., *Studies in the genesis and early development of the caliphal taxation system*, Copenhagen, 1988.
- Sims Williams, N., *Bactrian documents from northern Afghanistan*, vol. I: *Legal and economic documents*, Oxford, 2000.
- Smith, S., 'Events in Arabia in the 6th century AD', *BSOAS*, 16 (1954), 425–68.
- Suermann, H., *Die geschichtstheologischen Reaktion auf die einfallenden muslimen in der edessenischen Apokalypstik des 7. Jahrhunderts*, Frankfurt, 1985.
- Trimingham, J. S., *Christianity among the Arabs in pre Islamic times*, London, 1979.
- Walmsley, A., *Early Islamic Syria: An archaeological assessment*, Bath, 2007.
- 'The social and economic regime at Fihl (Pella)', in P. Canivet and J. P. Rey Coquais (eds.), *La Syrie de Byzance à l'Islam*, Damascus, 1992, 249–61.
- Wansbrough, J., *The sectarian milieu: Content and composition of Islamic salvation history*, Oxford, 1978.
- Ward Perkins, B., *The fall of Rome and the end of civilization*, Oxford, 2005.
- Watt, W. M., 'Belief in a "High God" in pre Islamic Mecca', *JSS*, 16 (1971), 35–40.
- Muhammad at Mecca*, Oxford, 1953.
- Muhammad at Medina*, Oxford, 1956.

- Whitby, C., 'Recruitment in Roman armies from Justinian to Heraclius (ca. 565–615)', in A. Cameron (ed.), *The Byzantine and early Islamic Near East*, vol. III: *States, resources and armies*, Princeton, 1995, pp. 61–124.
- Whitehouse, D., and A. Williamson, 'Sasanian maritime trade', *Iran*, 11 (1973), 29–49.
- Ye'or, B., *The decline of Eastern Christianity under Islam: From jihad to dhimmitude*, Cranbury, NJ, 1996.

Chapter 6: The empire in Syria, 705–763

Practical suggestions for further reading

- Cobb, Paul M., *White banners: Contention in 'Abbasid Syria, 750–880*, Albany, 2001.
- Crone, Patricia, *Slaves on horses: The evolution of the Islamic polity*, Cambridge, 1980.
- Hawting, G. R., *The first dynasty of Islam: The Umayyad caliphate, AD 661–750*, 2nd edn, London, 2000.
- Kennedy, Hugh, *The Prophet and the age of the caliphates*, 2nd edn, London, 2004.

Primary sources

- Agapius (Maḥbub) of Manbij, *Kitab al 'unwan*, part 2, ed. and trans. Alexandre Vasiliev as 'Kitab al 'unwan (histoire universelle)', *Patrologia Orientalis*, 8 (1911), 399–550.
- Akhbar al dawla al 'Abbasīyya wa fihi akhbar al 'Abbas wa wuldihi, ed. 'Abd al 'Azīz al Durī and 'Abd al Jabbar al Muṭṭalibī, Beirut, 1971.
- al Azdī, Yazīd ibn Muḥammad, *Ta'rikh al Mawṣil*, ed. 'Alī Ḥabība, Cairo, 1967.
- al Baladhurī, Aḥmad ibn Yaḥya, *Ansab al ashraf*, ed. M. al 'Azīm, Damascus, 1997.
- Kitab futuḥ al buldan*, ed. M. J. de Goeje, Leiden, 1866.
- Chachnamah*, ed. N. A. Baloch, Islamabad, 1983.
- al Dinawarī, Abū Ḥanīfa Aḥmad, *al Akhbar al tiwal*, ed. V. Guirgass, Leiden, 1888.
- Fragmenta historicorum arabicorum*, ed. M. J. de Goeje, 2 vols., Leiden, 1869.
- Ibn 'Abd al Ḥakam, Abū Muḥammad 'Abd Allah, *Surat 'Umar ibn 'Abd al 'Azīz*, ed. Aḥmad 'Ubayd, Cairo, 1983.
- Ibn 'Abd al Ḥakam, Abū al Qasim 'Abd al Raḥman, *Futuḥ Miṣr wa akhbaruha*, ed. C. C. Torrey, New Haven, 1922.
- Ibn al 'Adīm, Kamāl al Dīn 'Umar, *Zubdat al ḥalab min ta'rikh Ḥalab*, ed. Samī Dahhan, 3 vols., Damascus, 1951–68.
- Ibn 'Asakir, Abū al Qasim 'Alī, *Ta'rikh madīnat Dimashq*, ed. 'Umar al 'Amrawī, 70 vols., Beirut, 1995–8.
- Ibn A'tham al Kufī, Abū Muḥammad Aḥmad, *al Futuḥ*, ed. Muḥammad 'Abd al Mu'īd Khan *et al.*, 8 vols., Hyderabad, 1968–75.
- Ibn 'Idharī, Aḥmad ibn Muḥammad, *al Bayan al mughrib fi akhbar al Andalus wa al Maghrib*, ed. G. S. Colin and E. Lévi Provençal, 4 vols., Leiden, 1948–51.
- Ibn Khayyāṭ, Khalīfa, *al Ta'rikh*, ed. Akram al 'Umārī, 2 vols., Najaf, 1967.
- Ibn al Qūṭīyya, Abū Bakr ibn 'Umar, *Ta'rikh iftitāḥ al Andalus*, ed. Ibrāhīm al Abyārī, Cairo, 1982.
- al Iṣbahānī, Abū al Faraj 'Alī, *al Aghani*, 31 vols., Cairo, 1969–79.
- Maqatil al Ṭalibiyyin*, ed. Kaẓīm al Muẓaffar, Najaf, 1965.

- al Kindī, Abu 'Umar Muḥammad ibn Yusuf, *al Wulat wa al quḍat*, ed. R. Guest, Leiden and London, 1912.
- Lewond (Ghevond), *History of Lewond the eminent Vardapet of the Armenians*, trans. Zaven Arzoumanian, Wynnewood, PA, 1982.
- al Mas'ūdī, 'Alī ibn al Ḥusayn, *Muruj al dhahab wa ma'adin al jawhar*, ed. Charles Pellat, 7 vols., Beirut, 1965–79.
- Michael the Syrian, *Chronique de Michel le Syrien*, ed. and trans. J. B. Chabot, 4 vols., Paris, 1924.
- al Ṭabarī, Abu Ja'far Muḥammad ibn Jarīr, *Ta'rikh al rusul wa al muluk*, ed. M. J. de Goeje et al., 15 vols. in 3 series, Leiden, 1879–1901.
- Ta'rikh al Ya'qubi*, ed. M. T. Houtsma, 2 vols., Leiden, 1883.
- Ta'rikh i Sistan*, ed. Malik al Shu'ara' Bahar, Tehran, 1935.
- Theophanes Confessor, *Theophanis chronographia*, ed. C. de Boor, Leipzig, 1883.
- al Ya'qubi, Aḥmad ibn Abī Ya'qub, *Kitab al buldan*, ed. M. J. de Goeje, Leiden, 1892.

Secondary sources

- Abbott, Nabia, *The Ḳurrah papyri from Aphroditō in the Oriental Institute*, Chicago, 1930.
- 'A new papyrus and a review of the administration of 'Ubaid Allah b. al Ḥabḥab', in G. Makdisi (ed.), *Arabic and Islamic studies in honor of Hamilton A. R. Gibb*, Cambridge, MA, 1965, 19–35.
- Agha, Saleh Said, *The revolution which toppled the Umayyads: Neither Arab nor 'Abbasid*, Leiden, 2003.
- 'Athamina, Khalil, 'Arab settlement during the Umayyad caliphate', *JSAI*, 8 (1986), 185–207.
- Bacharach, Jere L., 'Marwanid building activities: Speculations on patronage', *Muqarnas*, 13 (1996), 27–44.
- Banaji, Jairus, *Agrarian change in Late Antiquity: Gold, labour, and aristocratic dominance*, Oxford, 2001.
- Bates, Michael L., 'The coinage of Syria under the Umayyads, 692–750 AD', in M. A. Bakhit and R. Schick (eds.), *The history of Bilad al Sham during the Umayyad period: Proceedings of the third symposium*, Amman, 1989, vol. II, 195–228.
- 'Coins and money in the Arabic papyri', in Y. Ragib (ed.), *Documents de l'Islam medieval: Nouvelles perspectives de recherche*, Cairo, 1991, 43–64.
- 'History, geography and numismatics in the first century of Islamic coinage', *Revue Suisse de Numismatique* 65 (1986), 231–61.
- Becker, C. H., 'Studien zur Omajjadengeschichte. A) 'Omar II', *Zeitschrift für Assyriologie*, 15 (1900), 1–36.
- Bell, H. I., 'The administration of Egypt under the Umayyad khalifs', *Byzantinische Zeitschrift*, 28 (1928), 278–86.
- Blankinship, Khalid Yahya, *The end of the jihad state: The reign of Hisham Ibn 'Abd al Malik and the collapse of the Umayyads*, Albany, 1994.
- Bligh Abramski, Irit, 'Evolution vs. revolution: Umayyad elements in the 'Abbasid regime 133/75–32/932', *Der Islam*, 65 (1988), 226–43.
- Borrut, Antoine, 'Entre tradition et histoire: Genèse et diffusion de l'image de 'Umar b. 'Abd al 'Aziz', *Mélanges de l'Université Saint Joseph*, 58 (2005), 329–78.
- Bosworth, C. E., 'Raja' b. Ḥaywa al Kindī and the Umayyad caliphs', *Islamic Quarterly*, 15 (1971), 69–85.

- Sistan under the Arabs, from the Islamic conquest to the rise of the Saffarids (30 250/651 864)*, Rome, 1968.
- Brett, Michael, 'The Arab conquest and the rise of Islam in North Africa', in J. D. Fage and Roland Oliver (eds.), *The Cambridge history of Africa*, 8 vols., Cambridge, 1978, vol. II: *From c. 500 BC to AD 1050*, 490 555.
- Brooks, E. W., 'The Arabs in Asia Minor 641 750, from Arabic sources', *Journal of Hellenic Studies*, 18 (1898), 182 208.
- Brunschvig, Robert, 'Ibn Abd al H'akam et la conquête de l'Afrique du Nord par les Arabes: Etude critique', *Annales de l'Institut des Études Orientales* (Algiers), 6 (1942 7), 108 55.
- Canard, Marius, 'Les expéditions des Arabes contre Constantinople dans l'histoire et dans la légende', *JA*, 208 (1926), 61 121.
- Chalmeta, Pedro, *Invasión e islamización: La sumisión de Hispania y la formación de al Andalus*, Madrid, 1994.
- Chavannes, Eduard, *Documents sur les Tou Kiue (Turcs) occidentaux*, St Petersburg, 1903.
- Collins, Roger, *The Arab conquest of Spain, 710 797*, Oxford, 1989.
- Conrad, Gerhard, *Die Quḍat Dimasq und der Madhab al Auza'i: Materialien zur syrischen Rechtsgeschichte*, Beirut, 1994.
- Conrad, Lawrence I., 'The quṣur of medieval Islam: Some implications for the social history of the Near East', *al Abḥath*, 29 (1981), 7 23.
- Crone, Patricia, *God's rule: Government and Islam: Six centuries of medieval Islamic political thought*, New York, 2004.
- 'On the meaning of the 'Abbasid call to al Riḍa', in C. E. Bosworth et al. (eds.), *The Islamic world from classical to modern times: Essays in honor of Bernard Lewis*, Princeton, 1989, 95 III.
- 'Were the Qays and Yemen of the Umayyad period political parties?', *Der Islam*, 71 (1994), I 57.
- Daniel, Elton, 'The anonymous history of the Abbasid family and its place in Islamic historiography', *IJMES*, 14 (1982), 419 34.
- Décobert, Christian, 'L'autorité religieuse aux premiers siècles de l'islam', *Archives de Sciences Sociales des Religions*, 125 (2004), 23 44.
- Le mendiant et le combattant: L'institution de l'islam*, Paris, 1991.
- Derenk, Dieter, *Leben und Dichtung des Omayyadenkalifen al Walid ibn Yazid*, Freiburg im Breisgau, 1974.
- Djaït, Hicham, 'Le Wilaya d'Ifriqiya au IIe/VIIIe siècle', *SI*, 27 (1967), 88 94.
- Donner, Fred M., *Narratives of Islamic origins: The beginnings of Islamic historical writing*, Princeton, 1998.
- Dunlop, D. M., *A history of the Jewish Khazars*, New York, 1954.
- al Duri, 'Abd al 'Aziz, 'al Fikra al mahdiyya bayna al da'wa al 'abbasiyya wa al 'aṣr al 'abbasī al awwal', in W. al Qaḍi (ed.), *Studia arabica et islamica: Festschrift for Ihsan 'Abbas*, Beirut, 1981, 123 32.
- Eisener, Reinhard, *Zwischen Faktum und Fiktion: Eine Studie zum Umayyadenkalifen Sulaiman b. 'Abdalmalik und seinem Bild in den Quellen*, Wiesbaden, 1987.
- Elad, Amikam, 'Aspects of the transition from the Umayyad to the 'Abbasid caliphate', *JSAI*, 19 (1995), 89 132.
- van Ess, Josef, 'Les Qadarites et la Gailaniyya de Yazid III', *SI*, 31 (1970), 269 86.

- Foote, Rebecca M., 'Commerce, industrial expansion, and orthogonal planning: Mutually compatible terms in settlements of Bilad al Sham during the Umayyad period', *Mediterranean Archaeology*, 13 (2000), 25–38.
- Fowden, Garth, *Qaṣayr 'Amra: Art and the Umayyad elite in Late Antique Syria*, Berkeley, 2004.
- Frantz Murphy, Gladys, *The agrarian administration of Egypt from the Arabs to the Ottomans*, Cairo, 1986.
- Gabrieli, Francesco, *Il Califato di Hisham: Studi di storia omayyade*, Mémoires de la Société Royale d'Archéologie d'Alexandrie 7, Alexandria, 1935.
- 'Muḥammad ibn Qasim ath Thaqafi and the Arab conquest of Sind', *East and West*, n.s., 15 (1964–5), 281–95.
- 'al Walid b. Yazid, il califfo e il poeta', *RSO*, 15 (1935), 1–64.
- Gaube, Heinz, 'Die syrischen Wüstenschlösser: Einige wirtschaftliche und politische Gesichtspunkte zu ihrer Entstehung', *Zeitschrift der Deutschen Palästina Vereins*, 95 (1979), 182–209.
- Genequand, Denis, 'Implantations umayyades de Syrie et de Jordanie', in *SLSA Jahresbericht 2001*, Zürich, 2001, 131–61, and *SLSA Jahresbericht 2002*, Zürich, 2003, 31–68.
- 'Rapport préliminaire de la campagne de fouille 2002 à Qasr al Hayr al Sharqi (Syrie)', in *SLSA Jahresbericht 2002*, Zurich, 2003, 69–96.
- 'Rapport préliminaire de la campagne de fouille 2003 à Qasr al Hayr al Sharqi et al Bakhra' (Syrie)', in *SLSA Jahresbericht 2003*, Zurich, 2004, 69–98.
- Gibb, H. A. R., 'Arab Byzantine relations under the Umayyad caliphate', *Dumbarton Oaks Papers*, 12 (1958), 219–33.
- The Arab conquests in Central Asia*, London and New York, 1923.
- 'Chinese records of the Arabs in Central Asia', *BSOAS*, 2 (1922), 613–22.
- Golden, Peter B., *Khazar studies: An historico philosophical inquiry into the origins of the Khazars*, 2 vols., Budapest, 1980.
- Grabar, Oleg, R. Holod, J. Knustad and W. Trousdale, *City in the desert: Qasr al Hayr East*, 2 vols., Cambridge, MA, 1978.
- Griffith, Sidney H., 'Images, Islam and Christian icons', in Pierre Canivet and Jean Paul Rey Coquais (eds.), *La Syrie de Byzance à l'Islam, VIIe–VIIIe siècles*, Damascus, 1992, 121–38.
- Grousset, René, *Histoire de l'Arménie des origines à 1071*, Paris, 1947.
- Guichard, Pierre, 'Les Arabes ont bien envahi l'Espagne: Les structures sociales de l'Espagne musulmane', *Annales*, 29 (1974), 1483–513.
- Guilland, Rodolphe, 'L'expédition de Maslama contre Constantinople (717–718)', *Revue des études byzantines*, 17 (1959), 109–33.
- Hamilton, Robert, *Walid and his friends: An Umayyad tragedy*, Oxford Studies in Islamic Art 6, Oxford, 1988.
- Hillenbrand, Robert, 'La dolce vita in early Islamic Syria: The evidence of later Umayyad palaces', *Art History*, 5 (1982), 1–35.
- Humphreys, R. Stephen, *Islamic history: A framework for inquiry*, rev. edn, Princeton, 1991.
- Judd, Steven C., 'Ghaylan al Dimashqi: The isolation of a heretic in Islamic heresiography', *IJMES*, 31 (1999), 161–84.
- 'Narratives and character development: al Ṭabarī and al Baladhuri on late Umayyad history', in Sebastian Guenther (ed.), *Ideas, images, and methods of portrayal: Insights into classical Arabic literature and Islam*, Leiden, 2005, 209–27.

- Jun yan, Zhang, 'Relations between China and the Arabs in early times', *Journal of Oman Studies*, 6 (1983), 91–109.
- Kennedy, Hugh, 'Byzantine Arab diplomacy in the Near East from the Islamic conquests to the mid eleventh century', in J. Shepard and S. Franklin (eds.), *Papers from the Twenty fourth Spring Symposium of Byzantine Studies*, Aldershot, 1992, 133–43.
- The early Abbasid caliphate: A political history*, London, 1981.
- 'Egypt as a province in the Islamic caliphate, 641–868', in C. F. Petry (ed.), *The Cambridge history of Egypt*, vol. I: *Islamic Egypt, 640–1517*, Cambridge, 1998, 62–85.
- 'Elite incomes in the early Islamic state', in John Haldon and L. I. Conrad (eds.), *The Byzantine and early Islamic Near East*, vol. VI: *Elites old and new in the Byzantine and early Islamic Near East*, Princeton, 2004, 13–28.
- Muslim Spain and Portugal: A political history of al Andalus*, London, 1996.
- King, G. R. D., 'The distribution of sites and routes in the Jordanian and Syrian deserts in the early Islamic period', *Proceedings of the Seminar for Arabian Studies*, 17 (1987), 91–105.
- Lapidus, Ira M., 'Arab settlement and economic development of Iraq and Iran in the age of the Umayyad and early Abbasid caliphs', in A. L. Udovitch (ed.), *The Islamic Middle East, 700–1900: Studies in economic and social history*, Princeton, 1981, 177–208.
- Lassner, Jacob, *Islamic revolution and historical memory: An inquiry into the art of 'Abbasid apologetics*, New Haven, 1986.
- Laurent, Joseph, *L'Arménie entre Byzance et l'Islam depuis la conquête arabe jusqu'en 886*, rev. Marius Canard, Paris, 1980.
- Lévi Provençal, Evariste, *Histoire de l'Espagne musulmane*, 3 vols., Leiden, 1950–3.
- Maclean, Derryl N., *Religion and society in Arab Sind*, Leiden, 1989.
- Martin Hisard, B., 'Les Arabes en Géorgie occidentale au VIII^e siècle: Étude sur l'idéologie politique Géorgienne', *Bedi Kartlisa*, 40 (1982), 105–38.
- Morimoto, K., *The fiscal administration of Egypt in the early Islamic period*, Kyoto, 1981.
- Morony, Michael G., 'Economic boundaries? Late Antiquity and early Islam', *JESHO*, 47 (2004), 166–94.
- (ed.), *Manufacturing and labour*, Aldershot, 2003.
- (ed.), *Production and the exploitation of resources*, *The Formation of the Classical Islamic World II*, Princeton and Aldershot, 2002.
- Nagel, Tilman, *Untersuchungen zur Entstehung des abbasidischen Kalifates*, Bonn, 1972.
- Northedge, Alastair, 'Archaeology and new urban settlement patterns in early Islamic Syria and Iraq', in G. R. D. King and Averil Cameron (eds.), *The Byzantine and early Islamic Near East*, vol. II: *Land use and settlement patterns*, Princeton, 1994, 231–65.
- de Prémare, Alfred Louis. 'Wahb b. Munabbih, une figure singulière du premier islam', *Annales HSS* (2005), 531–49.
- al Qaḍi, Wadad, 'The development of the term *ghulat* in Muslim literature with special reference to the Kaysaniyya', in A. Dietrich (ed.), *Akten des VII. Kongresses für Arabistik und Islamwissenschaft*, Göttingen, 1976, 295–319.
- 'The religious foundation of late Umayyad ideology and practice', in *Saber religioso y poder político en el Islam: Actas del simposio internacional (Granada, 15–18 octubre 1991)*, Madrid, 1994, 231–73.

- Qedar, Shraga, 'Copper coinage of Syria in the seventh and eighth century AD', *Israel Numismatic Journal*, 10 (1988 9), 27 39.
- Ragib, Yusuf, 'Lettres nouvelles de Qurra ibn Šarik', *JNES*, 49 (1981), 173 88.
- Robinson, Chase F., *Empire and elites after the Muslim conquest: The transformation of northern Mesopotamia*, Cambridge Studies in Islamic Civilization, Cambridge, 2000.
- Sauvaget, Jean, 'Châteaux umayyades de Syrie: Contribution à l'étude de la colonisation arabe aux Ier et IIe siècles de l'Hégire', *REI*, 35 (1967), 1 52.
- Savage, Elizabeth, *A gateway to hell, a gateway to paradise: The North African response to the Arab conquest*, Princeton, 1997.
- Sénac, Philippe, *Musulmans et Sarrazins dans le Sud de la Gaule du VIIIe au XIe siècle*, Paris, 1980.
- Shaban, M. A., *The 'Abbasid revolution*, Cambridge, 1970.
- Islamic history: *A new interpretation*, 2 vols., Cambridge, 1971 6.
- Sharon, Moshe, *Black banners from the east*, Jerusalem, 1983.
- Revolt: *The social and military aspects of the 'Abbasid revolution*, Jerusalem, 1990.
- Sijpesteijn, Petra M., 'Shaping a Muslim state: Papyri related to a mid eighth century Egyptian official', Ph.D. thesis, Princeton University, 2004.
- 'Travel and trade on the river', in P. Sijpesteijn and L. Sundelin (eds.), *Papyrology and the history of early Islamic Egypt*, Leiden, 2004, 115 52.
- Spellberg, Denise A., 'The Umayyad north: Numismatic evidence for frontier administration', *American Numismatic Society Museum Notes*, 33 (1988), 119 27.
- Suermann, H., 'Notes concernant l'apocalypse copte de Daniel et la chute des Omayyades', *Parole de l'Orient*, 11 (1983), 329 48.
- Taha, 'Abdulwahid Dhanun, *The Muslim conquest and settlement of North Africa and Spain*, London, 1989.
- Tucker, William F., 'Abd Allah b. Mu'awiya and the Janahiyya: Rebels and ideologues of the late Umayyad period', *SI*, 51 (1980), 39 57.
- 'Abu Manšur al 'Ijlī and the Manšuriyya: A study in medieval terrorism', *Der Islam*, 54 (1977), 66 76.
- 'Bayan ibn Sam'an and the Bayaniyya: Shi'ite extremists of Umayyad Iraq', *MW*, 65 (1975), 241 53.
- 'Rebels and gnostics: al Mugīra Ibn Sa'id and the Mugriyya', *Arabica*, 22 (1975), 33 47.
- Tuqan, Fawwaz, *al Ḥa'ir: Baḥṭh fi al quṣur al umawiyya fi al badiya*, Amman, 1979.
- Vilá Hernández, Salvador, 'El nombramiento de los walies de al Andalus', *al Andalus*, 4 (1936 9), 215 20.
- Walker, John, *A catalogue of the Muhammadan coins in the British Museum*, vol. I: *A catalogue of the Arab Sassanian coins*, London, 1941; vol. II: *A catalogue of the Arab Byzantine and post reform Umayyad coins*, London, 1956.
- Walmsley, Alan, 'Production, exchange and regional trade in the Islamic east Mediterranean: Old structures, new systems?', in Inge Lyse Hansen and Chris Wickham (eds.), *The long eighth century*, Leiden, 2000, 265 344.
- Wellhausen, Julius, *Das arabische Reich und sein Sturz*, Berlin, 1902; trans. M. G. Weir as *The Arab kingdom and its fall*, Calcutta, 1927.
- Die religiös politischen Oppositionsparteien im alten Islam*, Berlin, 1901; trans. R. C. Ostle as *The religio political factions in early Islam*, Amsterdam, 1975.
- Wickham, Chris, *Framing the early Middle Ages: Europe and the Mediterranean, 400 800*, Oxford, 2005.

Chapter 7: The empire in Iraq, 763–861

Practical suggestions for further reading

- Abbott, Nabia, *Two queens of Baghdad*, Chicago, 1946.
- Abun Nasr, Jamil, *A history of the Maghrib in the Islamic period*, Cambridge, 1987.
- Collins, Roger, *Early Medieval Spain: Unity in diversity, 400–1000*, New York, 1983.
- Daniel, E., *The political and social history of Khurasan under Abbasid rule, 747–820*, Minneapolis and Chicago, 1979.
- Elad, A. 'Aspects of the transition from the Umayyad to the 'Abbasid caliphate', *JSAI*, 19 (1995), 89–128.
- El Hibri, Tayeb, *Reinterpreting Islamic historiography: Harun al Rashid and the narrative of the 'Abbasid caliphate*, Cambridge, 1999.
- Kennedy, H., *The Prophet and the age of the caliphates*, London, 1986.
- Lassner, J., *The shaping of 'Abbasid rule*, Princeton, 1980.
- Le Strange, G., *The lands of the eastern caliphate: Mesopotamia, Persia, and Central Asia from the Moslem conquest to the time of Timur*, Cambridge, 1905.
- Meinecke, Michael, 'al Rakka', *Elz*, vol. VIII, 410–14.
- Nawas, John, 'A reexamination of three current explanations for al Ma'mun's introduction of the miḥna', *IJMES*, 26 (1994), 615–29.
- Northedge, Alastair, 'The palaces of the 'Abbasids at Samarra', in C. F. Robinson (ed.), *A medieval Islamic city reconsidered: An interdisciplinary approach to Samarra*, Oxford Studies in Islamic Art 14, Oxford, 2001, 24–67.
- Rogers, J. M., 'Samarra: A study in medieval town planning', in A. Hourani and S. M. Stern (eds.), *The Islamic city: A colloquium*, Oxford, 1970, 119–55.
- Watt, M., *The formative period of Islamic thought*, Edinburgh, 1973.
- Wendell, C., 'Baghdad: *Imago Mundi* and other foundation lore', *IJMES*, 2 (1971), 99–128.

Primary sources

- al Baghdadi, Abu Bakr Ahmad ibn 'Alī al Khaṭīb, *Ta'rikh Baghdad*, 14 vols., Cairo, 1931.
- Baladhuri, Ahmad ibn Yahya, *Futuḥ al buldan*, ed. S. al Munajjid, 3 vols., Cairo, 1957.
- Ibn 'Abd Rabbihi, Abu 'Umar Ahmad ibn Muḥammad, *Kitab al 'iqd al farid*, ed. Ahmad Amin *et al.*, 8 vols., Cairo, 1940–53.
- Ibn Abī Ṭahir Ṭayfur, Abu'l Faḍl Ahmad ibn Ṭahir, *Kitab Baghdad*, Baghdad, 1968.
- Ibn al Athir, 'Izz al Dīn 'Alī ibn Ahmad, *al Kamil fi'l ta'rikh*, 13 vols., Beirut, 1965–7.
- Ibn al Muqaffa', *Athar Ibn al Muqaffa'*, ed. 'Umar Abu'l Nasr, Beirut, 1966.
- al Jahshiyari, Muḥammad ibn 'Abdus, *Kitab al wuzara' wa'l kuttāb*, ed. M. al Saqqā *et al.*, Cairo, 1938.
- al Kindī, Muḥammad ibn Yusuf, *Wulat Miṣr*, ed. H. Nassar, Beirut, 1959.
- al Ma'sūdi, 'Alī ibn al Ḥusayn, *Muruj al dhahab*, ed. C. Pellat, Beirut, 1973 (the relevant sections for the early 'Abbasid caliphate are available in an English translation by P. Lunde and C. Stone, *Meadows of gold*, London, 1989).
- al Ṭabari, Abu Ja'far Muḥammad ibn Jarir, *Ta'rikh al rusul wa'l muluk*, ed. M. J. de Goeje, 15 vols. in 3 series, Leiden, 1879–1901 (al Ṭabari's work has been translated into English in a well known multi volume project entitled *The history of al Ṭabari*, Albany, 1985–99).

- The relevant sections for 'Abbasid history for the period 763–861 are available in vols. XXVIII–XXXIV).
- al Ya'qubi, Ahmad ibn Abi Ya'qub, *Kitab al buldan*, ed. M. J. de Goeje, Leiden 1892.
- Ta'rikh al Ya'qubi*, 2 vols., Beirut, 1960.

Secondary sources

- Bakhit, M. A., and R. Schick (eds.), *Bilad al Sham during the 'Abbasid period, 132 AH/750 AD–451 AH/1059 AD: Proceedings of the Fifth International Conference on the history of Bilad al Sham*, 2 vols., English and French section Amman, 1991; Arabic section Amman, 1992.
- Beckwith, C. I., 'Aspects of the early history of the Central Asian guard corps in Islam', *Archivum Eurasiae Medii Aevi*, 4 (1984), 29–43.
- Bligh Abramski, I., 'Evolution vs. revolution: Umayyad elements in the 'Abbasid regime 133/75–320/932', *Der Islam*, 65 (1988), 226–43.
- Bonner, Michael, 'Some observations concerning the early development of jihad on the Arab–Byzantine frontier', *SI*, 75 (1992), 5–31.
- *Bosworth, C. E., 'The Tahirids and Arabic culture', *JSS*, 14 (1969), pp. 45–79.
- 'The Tahirids and Persian literature', *Iran*, 7 (1969), pp. 103–6.
- Buckler, F. W., *Harun al Rashid and Charles the Great*, Cambridge, MA, 1931.
- Canfield, Robert (ed.), *Turko Persia in historical perspective*, Cambridge, 1991.
- Cooperson, Michael, *Classical Arabic biography: The heirs of the Prophet in the age of al Ma'mun*, Cambridge, 2000.
- Crone, P., *Slaves on horses*, Cambridge, 1980.
- al Duri, 'Abd al 'Aziz, al 'Aṣr al 'Abbasī al awwal, Baghdad, 1945.
- El Hibri, Tayeb, 'Coinage reform under the 'Abbasid caliph al Ma'mun', *JESHO*, 36 (1993), 58–83.
- 'Harun al Rashid and the Mecca Protocol of 802: A plan for division or succession', *IJMES*, 24 (1992), 461–80.
- Gordon, Matthew, *The breaking of a thousand swords: A history of the Turkish military community of Samarra (AH 200–275/815–889 CE)*, Albany, 2001.
- Isma'il, O. S., 'Mu'taṣim and the Turks', *BSOAS*, 29 (1966), 12–24.
- Katibi, Ghayda, *al Kharaj, mundhu al fath al Islami ila awasit al qarn al thalith al hijri*, Beirut, 1997.
- Kennedy, H., *The early Abbasid caliphate: A political history*, London, 1981.
- Kimber, R. A., 'The early 'Abbasid vizierate', *JSS*, 37 (1992), 65–85.
- Lassner, J., *Islamic revolution and historical memory: An inquiry into the art of 'Abbasid apologetic*, American Oriental Society Series 66, New Haven, 1986.
- The topography of Baghdad in the early Middle Ages*, Detroit, 1970.
- Le Strange, G., *Baghdad during the 'Abbasid caliphate from the contemporary Arabic and Persian sources*, Oxford, 1900.
- Palestine under the Moslems: A description of Syria and the Holy Land from AD 650 to 1500*, London, 1890.
- Lewis, B., 'The regnal titles of the first 'Abbasid caliphs', in Tara Chand (ed.), *Dr Zakir Husain presentation volume*, New Delhi, 1968, 13–22.
- Miah, S., *The reign of al Mutawakkil*, Dacca, 1969.

- Morony, Michael, 'Landholding and social change: Lower al 'Iraq in the early Islamic period', in Tarif Khalidi (ed.), *Land tenure and social transformation in the Middle East*, Beirut, 1984, 209–22.
- Noonan, Thomas, 'The 'Abbasid mint output', *JESHO*, 29 (1986), 113–64.
- Northedge, Alastair, 'Archaeology and new urban settlement patterns in early Islamic Syria and Iraq', in G. R. D. King and A. Cameron (eds.), *The Byzantine and early Islamic Near East*, vol. II: *Land use and settlement patterns*, Princeton, 1994, 231–65.
- The historical topography of Samarra*, Samarra Studies 1, British Academy Monographs in Archaeology / British School of Archaeology in Iraq, London, 2005.
- Omar, F., *The 'Abbasid caliphate*, Baghdad, 1969.
- Radtke, B., 'Toward a typology of 'Abbasid universal chronicles', *Occasional Papers of the School of 'Abbasid Studies*, 3 (1990), 1–18.
- Sourdell, D., *Le vizirat abbaside de 749 à 936*, 2 vols., Damascus, 1959–60.
- Talbi, Mohamed, *L'émirat aghlabide (184–296/800–909): Histoire politique*, Paris, 1966.
- Yunus, Ahmad, *Taṭawwur anẓimat istithmar al araḍ al zira'īyya fī'l 'aṣr al 'Abbāsī*, Beirut, 1986.
- Zaman, Muhammad Q., *Religion and politics under the early 'Abbasids: The emergence of the proto Sunni elite*, Leiden, 1997.

Chapter 8: The waning of empire, 861–945

Practical suggestions for further reading

- Bianquis, Thierry, 'Autonomous Egypt from Ibn Ṭulun to Kafur, 868–969', in Carl F. Petry (ed.), *The Cambridge history of Egypt*, vol. I: *Islamic Egypt, 640–1517*, Cambridge, 1998, 86–119.
- Bosworth, C. E., *The history of the Ṣaffarids of Sistan and the Maliks of Nimruz (247/861 to 949/1542)*, Costa Mesa and New York, 1994.
- Bowen, H., *The life and times of 'Alī b. 'Isa, the 'Good Vizier'*, Cambridge, 1928.
- Brett, Michael, *The rise of the Fatimids: The world of the Mediterranean and the Middle East in the fourth century of the hijra, tenth century CE*, Leiden, 2001.
- Frye, Richard N., *The golden age of Persia: The Arabs in the east*, London, 1975.
- 'The Samanids', in R. N. Frye (ed.), *The Cambridge history of Iran*, vol. IV: *The period from the Arab invasion to the Saljuqs*, Cambridge, 1975, 136–61.
- Gordon, Matthew, *The breaking of a thousand swords: A history of the Turkish military community of Samarra (AH 200–275–815/899 CE)*, Albany, 2001.
- Halm, Heinz, *The empire of the Mahdi: The rise of the Fatimids*, trans. Michael Bonner, Leiden, 1996.
- Madelung, W., 'The minor dynasties of northern Iran', in R. N. Frye (ed.), *The Cambridge history of Iran*, vol. IV: *The period from the Arab invasion to the Saljuqs*, Cambridge, 1975, 198–249.
- Melchert, Christopher, 'Religious policies of the caliphs from al Mutawakkil to al Muqtadir, AH 232–295/AD 847–908', *Islamic Law and Society*, 3 (1996), 316–42.
- Mottahedeh, R. P., 'The 'Abbasid caliphate in Iran', in R. N. Frye (ed.), *The Cambridge history of Iran*, vol. IV: *The period from the Arab invasion to the Saljuqs*, Cambridge, 1975, 57–89.

- Loyalty and leadership in an early Islamic society*, Princeton, 1980; repr. 2001.
- Paul, Jürgen, *The state and the military: The Samanid case*, Papers on Inner Asia 26, Bloomington, 1994.
- Popovic, A., *The revolt of African slaves in the 3rd/9th century*, Princeton, 1998.
- Tor, Deborah G., *Violent order: Religious warfare, chivalry, and the 'Ayyar phenomenon in the medieval Islamic world*, Istanbul Texts und Studien 11, Würzburg, 2007.
- Walker, Paul, 'The Isma'ili da'wa and the Fatimid caliphate', in Carl F. Petry (ed.), *The Cambridge history of Egypt*, vol. I: *Islamic Egypt, 640–1517*, Cambridge, 1998, 120–50.

Primary sources

- Abu Bakr al Maliki, *Riyad al nufus*, 3 vols., Beirut, 1981.
- Anon., *Tarikh i Sistan*, ed. Malik al Shu'ara' Bahar, Tehran, 1935; trans. Milton Gold as *Literary and historical texts from Iran*, vol. II, Rome, 1976.
- 'Arif ibn Sa'd al Katib al Qurṭubī, *Ṣilat Ta'rīkh al Ṭabarī*, Leiden, 1897.
- al Balawī, 'Abdallāh ibn Muḥammad, *Sirat Aḥmad ibn Ṭulun*, Damascus, 1939.
- al Hamadhani, Muḥammad ibn 'Abd al Malik, *Takmilat Ta'rīkh al Ṭabarī*, Leiden, 1897.
- Hilāl ibn al Muḥassin al Ṣabī, *Rusum dar al khilafa*, Beirut, 1964; repr. Beirut, 1986.
- Tuḥfat al umara' fi ta'rīkh al wuzara'*, Cairo, 1958.
- Ibn al Athir, 'Izz al Dīn, *al Kamil fi l ta'rīkh*, Beirut, 1418/1998.
- Ibn Ḥawqal, *Ṣurat al arḍ*, Leiden, 1938.
- Ibn Khurradadbih, Abu l Qasim 'Ubaydallāh, *al Masalik wal mamalik*, Leiden, 1889.
- al Iṣṭakhri, Abu Ishaq Ibrahim, *Kitab al masalik wal mamalik*, Leiden, 1870.
- al Khaṭīb al Baghdādī, Abu Bakr Aḥmad, *Ta'rīkh Baghdad*, 14 vols., Cairo, 1931.
- al Maqrīzī, Aḥmad ibn 'Alī, *Itti'az al ḥunafa' bi akhbar al a'imma al faṭīmiyyin al khulafa'*, Cairo, 1967.
- al Mas'ūdī, 'Alī ibn al Ḥusayn, *Kitab al tanbīh wal ishraf*, Leiden, 1894.
- Muruj al dhahab wa ma'adin al jawhar*, 5 vols., Beirut, 1966–74.
- Miskawayh, Abu 'Alī al Rāzī, *Tajarib al umam*, ed. A. Emami, Tehran, 2001; partial ed. and trans. H. F. Amedroz and D. S. Margoliouth in *The eclipse of the 'Abbasid caliphate: Original chronicles of the fourth Islamic century*, vols. I II IV V, London, 1921.
- Nu'aym ibn Ḥammad, *Kitab al fitan*, Beirut, 1993.
- al Qaḍī al Nu'man, *Ifṭitāḥ al dawla wa ibtida' al da'wa*, ed. W. al Qaḍī, Beirut, 1970; ed. F. Dachraoui [Dashrawī], Tunis, 1975.
- al Majalis wal musayarat*, Tunis, 1978.
- Qudama ibn Ja'far, *Kitab al kharaj wa ṣina'at al kitaba*, ed. M. H. al Zubaydi, Baghdad, 1981.
- Sibt Ibn al Jawzī, *Mir'at al zaman*, British Museum, OR 4169.
- al Ṣulī, Abu Bakr Muḥammad al Shaṭranjī, *Akhbar al Raḍī wal Muttaqī*, London, 1935, trans. Marius Canard as *Histoire de la dynastie abbaside de 322 à 333/933 à 944*, 2 vols., Algiers, 1950.
- al Ṭabarī, Abu Ja'far Muḥammad ibn Jarīr, *Ta'rīkh al rusul wal muluk*, ed. M. J. de Goeje *et al.*, 15 vols. in 3 series, Leiden, 1879–1901; trans. as *The history of al Ṭabarī*, 39 vols., Albany, 1985–99; see vol. XXXIV, trans. Joel L. Kraemer as *Incipient decline*, Albany, 1989; vol. XXXV, trans. George Saliba as *The crisis of the 'Abbasid caliphate*, Albany, 1985; vol. XXXVI, trans. David Waines as *The revolt of the Zanj*, Albany, 1992; vol. XXXVII, trans. Philip M. Fields as *The 'Abbasid recovery*, Albany, 1987; vol. XXXVIII, trans. Franz Rosenthal as *The return of the caliphate to Baghdad*, Albany, 1985.

al Ya'qubī, Aḥmad ibn Abī Ya'qub ibn Waḍīḥ, *Kitab al buldan*, Leiden, 1892.
Ta'rikh, Leiden, 1883.

Secondary sources

- Ali, Samer, 'Praise for murder? Two odes by al Buḥturi surrounding an 'Abbasid patricide', in Beatrice Gruendler and Louise Marlow (eds.), *Writers and rulers*, Wiesbaden, 2004, 1 38.
- Bacharach, J., 'The career of Muḥammad ibn Ṭughj al Ikhshid', *Speculum*, 50 (1975), 586 612.
- Bonner, Michael, *Jihad in Islamic history: Doctrines and practices*, Princeton, 2006.
- 'al Khalifa al Marḍī: The accession of Harun al Rashid', *JAOS*, 109, 1 (1988), 79 91.
- Bosworth, C. E., 'The armies of the Ṣaffarids', *BSOAS*, 31 (1968), 534 54.
- The new Islamic dynasties: A chronological and genealogical manual*, New York, 1996.
- 'Ṣanawbari's elegy on the pilgrims slain in the Carmathian attack on Mecca (317/930): A literary historical study', *Arabica*, 19, 3 (1972), 222 39.
- 'The Ṭahirids and Arabic culture', *JSS*, 14 (1969), 45 79.
- 'The Ṭahirids and Ṣaffarids', in R. N. Frye (ed.), *The Cambridge history of Iran*, vol. IV: *The period from the Arab invasion to the Saljuqs*, Cambridge, 1975, 90 135.
- Bray, Julia, 'Samarra in ninth century Arabic letters', in Chase F. Robinson (ed.), *A medieval Islamic city reconsidered: An interdisciplinary approach to Samarra*, Oxford Studies in Islamic Art 14, Oxford, 2001, 21 8.
- Brett, Michael, 'The Mīm, the 'Ayn, and the making of Isma'ilism', *BSOAS*, 57 (1994), 24 39; repr. in Michael Brett, *Ibn Khaldun and the medieval Maghrib*, Aldershot, 1999.
- 'The way of the peasant', *BSOAS*, 47, 1 (1984), 44 56.
- Bulliett, Richard, *Conversion to Islam in the medieval period: An essay in quantitative history*, Cambridge, MA, 1979.
- Busse, H., 'Das Hofbudget des Chalifen al Mu'taḍid billah', *Islam*, 43 (1967), 11 36.
- Cahen, C., 'L'évolution de l'iqṭa' du IX^e au XIII^e siècle: Contribution à une histoire comparée des sociétés médiévales', in C. Cahen, *Les peuples musulmans dans l'histoire médiévale*, Damascus, 1977, 231 69; first published in *Annales, Economies Sociétés Civilisations*, 7 (1953), 25 52.
- Mouvements populaires et autonomisme urbain dans l'Asie musulmane du moyen âge*, Leiden, 1959.
- Canard, M., *Histoire de la dynastie des H'amdānides de Jazīra et de Syrie*, Paris, 1953.
- Chabbi, Jacqueline, 'Remarques sur le développement historique des mouvements ascétiques et mystiques au Khurasan', *SI*, 46 (1977), 5 72.
- Chamberlain, Michael, *Knowledge and social practice in medieval Damascus, 1190 1350*, Cambridge, 1994.
- Cobb, Paul, 'al Mutawakkil's Damascus: A new 'Abbasid capital?', *JNES*, 58 (1999), 241 57.
- Crone, Patricia, *God's rule: Government and Islam*, New York, 2004.
- Crone, Patricia, and Martin Hinds, *God's caliph: Religious authority in the first centuries of Islam*, Cambridge, 1986.
- de la Puente, Cristina, 'El Ȳihad en el califato omeya de al Andalus y su culminación bajo Hiṣām II', in Fernando Valdés Fernández (ed.), *Almanzor y los terrores del Milenio*, Aguilar de Campoo, 1999, 25 38.
- Haarmann, Ulrich (ed.), *Geschichte der arabischen Welt*, Munich, 1987.

- Halm, Heinz, *Die Traditionen über den Aufstand 'Alī Ibn Muḥammad's, des 'Herrn der Zang'*: Eine quellenkritische Untersuchung, Bonn, 1967.
- Kennedy, Hugh, *Muslim Spain and Portugal: A political history of al Andalus*, London and New York, 1996.
- The Prophet and the age of the caliphates*, 2nd edn, Harlow, 2004.
- Kimber, Richard, 'The succession to the caliph Musa al Hadī', *JAOS*, 121, 3 (2001), 428–48.
- Kraemer, Joel L., *Humanism in the Renaissance of Islam: The cultural revival during the Buyid age*, Leiden, 1993.
- Lewis, Bernard, *The Arabs in history*, London, 1958.
- Massignon, Louis, *The Passion of al Ḥallaj*, trans. Herbert Mason, 4 vols., Princeton, 1980.
- Mez, A., *The renaissance of Islam*, trans. Khuda Bakhsh, London, 1937.
- Miles, George, *The numismatic history of Rayy*, New York, 1938.
- Minorsky, Vladimir, 'La domination des Dailamites', *Société des Etudes Iraniennes*, 3 (1932), 1–26.
- Miquel, André, *La géographie humaine du monde musulman*, 4 vols., Paris and The Hague, 1967.
- Muth, Franz Christoph, "'Entsetzte" Kalifen: Depositionsverfahren im mittelalterlichen Islam', *Der Islam*, 75 (1998), 104–23.
- Paul, Jürgen, *Herrscher, Gemeinwesen, Vermittler: Ostiran und Transoxanien in vormongolischer Zeit*, Beirut and Stuttgart, 1996.
- 'The histories of Samarqand', *Studia Iranica*, 22 (1993), 69–92.
- Robinson, Chase (ed.), *A medieval city reconsidered: An interdisciplinary approach to Samarra*, Oxford Studies in Islamic Art 14, Oxford, 2001.
- Rosenthal, Franz, *A history of Muslim historiography*, Leiden, 1968.
- Sabari, S., *Mouvements populaires à Bagdad à l'époque 'Abbaside, IXe–XIe siècles*, Paris, 1981.
- Sato, Tsugitaka, 'The iqṭā' system of Iraq under the Buwayhids', *Orient*, 18 (1982), 83–105.
- State and society in medieval Islam: Sultans, muqṭa's and fallāḥun*, Leiden, 1997.
- Savage, Elizabeth, *A gateway to hell, a gateway to paradise: The North African response to the Arab conquest*, Princeton, 1997.
- Scott Meisami, Julie, 'The palace complex as emblem: Some Samarran *qasidas*', in Chase F. Robinson (ed.), *A medieval Islamic city reconsidered: An interdisciplinary approach to Samarra*, Oxford Studies in Islamic Art 14, Oxford, 2001, 69–78.
- Sourdel, Dominique, *Le vizirat 'abbaside de 749 à 936*, 2 vols., Damascus, 1959–60.
- Stern, Samuel Miklos, 'Ya'qub the Coppersmith and Persian national sentiment', in C. E. Bosworth (ed.), *Iran and Islam, in memory of Vladimir Minorsky*, Edinburgh, 1971, 535–55.
- Talbi, Mohamed, *L'émirat aghlabide (184–296/800–909): Histoire politique*, Paris, 1966.
- Tor, Deborah G., 'A numismatic history of the first Ṣaffarid dynasty (AH 247–300/AD 861–911)', *Numismatic Chronicle*, 162 (2002), 293–314.
- Treadwell, Luke, 'The political history of the Samanid state', D.Phil. thesis, Oxford University, 1991.
- Vasiliev, A. A., and Marius Canard, *Byzance et les Arabes*, vol. II, part I, Brussels, 1968.
- Waines, D., 'The third century internal crisis of the 'Abbasids', *JESHO*, 20 (1977), 282–306.
- Walker, Paul, *Exploring an Islamic empire: Fatimid history and its sources*, London and New York, 2002.

- Wansbrough, John, *The sectarian milieu: Content and composition of Islamic salvation history*, Oxford, 1978.
- Wittek, Paul, *The rise of the Ottoman empire*, London, 1938.

Chapter 9: The late ‘Abbāsid pattern, 945–1050

Practical suggestions for further reading

- Bosworth, C. E., *The Ghaznavids: Their empire in Afghanistan and eastern Iran*, Edinburgh, 1963.
- Donohue, John J., *The Buwayhid dynasty in Iraq 334H/945 to 403H/1012: Shaping institutions for the future*, Leiden, 2003.
- Frye, R. N., *The golden age of Persia*, London, 1975.
- Ibn Miskawayh, *Tajārīb al umam*, ed. and trans. H. Amedroz and D. S. Margoliouth in *The eclipse of the ‘Abbasid caliphate*, 7 vols., London, 1920 1.
- Kennedy, Hugh, *The Prophet and the age of the caliphates*, 2nd edn, London, 2004.
- Mottahedeh, R., *Loyalty and leadership in an early Islamic society*, 2nd edn, Princeton, 2001.
- al Muqaddasi, *Aḥsan al taqasīm*, trans. B. Collins as *The best divisions for the knowledge of the regions*, Reading, 2001.

Primary sources

- Ibn al Athīr, *al Kamil fi ’l ta’rīkh*, ed. C. J. Tornberg, 14 vols., Leiden, 1851 76.
- Ibn al Azraq al Fariqī, *Ta’rīkh Mayyafariqīn*, ed. B. A. Awad, Cairo, 1959.
- Ibn Ḥawqal, *Kitāb surat al arḍ*, ed. J. Kraemer, Leiden, 1938.
- al Muqaddasi, *Aḥsan al taqasīm*, ed. M. J. de Goeje, Leiden, 1906.
- Sibt Ibn al Jawzi, *Mir’at al zaman*, ed. J. J. al Hamawundi, Baghdad, 1990.

Secondary sources

- Amedroz, H. F., ‘The Marwanid dynasty of Mayyafariqīn’, *JRAS* (1903), 123 54.
- Berthier, S., *Peuplement rural et aménagements hydroagricoles dans la moyenne vallée de l’Euphrate, fin VIIe XIX siècle*, Damascus, 2001.
- Bosworth, C. E., ‘Military organization under the Buyids of Persia and Iraq’, *Oriens*, 18 19 (1965 6), 143 67.
- Bowen, H., ‘The last Buwayhids’, *JRAS* (1929), 225 45.
- Bürgel, J. C., *Die Hofkorrespondenz ‘Aḡud ad Daulas*, Wiesbaden, 1965.
- Busse, H., *Chalif und Grosskonig: Die Buyiden im Iraq (945 1055)*, Beirut, 1969.
- Cahen, C., ‘L’évolution de l’iqṭa’ du IX au XIII siècle: Contribution à une histoire comparée des sociétés médiévales’, *Annales, Economies Sociétés Civilisations*, 7 (1953), 25 52.
- ‘Mouvements populaires et autonomisme urban dans l’Asie musulmane du moyen âge’, *Arabica*, 5 (1958), 225 50; 6 (1959), 25 56, 223 65.
- Heidemann, S., *Die Renaissance der Städte in Nordsyrien und Nordmesopotamien: Städtische Entwicklung und wirtschaftliche Bedingungen in ar Raqqā und Ḥarran von der Zeit der beduinischen Vorherrschaft bis zu Seldschuken*, Islamic History and Civilization, Studies and Texts 40, Leiden, 2002.
- Kennedy, Hugh, *The armies of the caliphs*, London, 2001.

- 'The decline and fall of the first Muslim empire', *Der Islam*, 81 (2004), 3 30; repr. in H. Kennedy, *The Byzantine and Islamic Near East*, Aldershot, 2006, XIV.
- 'The Uqaylids of Mosul: The origins and structure of a nomad dynasty', in *Actas del XII Congreso de la UEA*, Madrid, 1986, 391 402; repr. in H. Kennedy, *The Byzantine and Islamic Near East*, Aldershot, 2006, XIII.
- Kraemer, J. L., *Humanism in the renaissance of Islam: The cultural revival of the Buyid age*, Leiden, 1992.
- Madelung, W., 'The assumption of the title shahanshah by the Buyids and "the reign of the Daylam (dawlat al Daylam)"', *JNES*, 28, (1969), 168 83.
- Makdisi, G., *Ibn 'Aql et la résurgence de l'Islam traditionaliste au XI siècle*, Damascus, 1962.
- 'Notes on Hilla and the Mazyadids in medieval Islam', *JAOS*, 74 (1954), 249 62.
- Mez, A., *The renaissance of Islam*, trans. Khuda Bakhsh, London, 1937; repr. New York, 1975.
- Minorsky, V., *La domination des dailamites*, Paris, 1927.
- A history of Sharvan and Darband*, Cambridge, 1958.
- Studies in Caucasian history*, London, 1953.
- Mottahedeh, R., 'Administration in Buyid Qazwin', in D. S. Richards (ed.), *Islamic civilization 950 1150*, Oxford, 1975, 33 45.
- Vanly, I. C. 'Le déplacement du pays kurde vers l'ouest', *RSO*, 50 (1976), 353 63.
- Waines, D., 'The third century internal crisis of the 'Abbasids', *JESHO*, 20 (1977), 282 306.
- Zakkar, S., *The emirate of Aleppo 1004 94*, Beirut, 1971.

Chapter 10: Arabia

Practical suggestions for further reading

- Casey Vine, P. (ed.), *Oman in history*, London, 1995.
- Dresch, P., *Tribes, government and history in Yemen*, Oxford, 1989.
- Gochenour, D. T., 'The penetration of Zaydi Islam into early medieval Yemen', Ph.D. thesis, Harvard University, 1984.
- al Juhany, U. M., *Najd before the Salafi reform movement*, Reading and Riyadh, 2002.
- al Mad'aj, 'Abd al Muhsin Mad'aj M., *The Yemen in early Islam 9 233/630 847: A political history*, London, 1988.
- Motzki, H., *The origins of Islamic jurisprudence: Meccan fiqh before the classical schools*, Leiden, 2002.
- Sayyid, Ayman Fu'ad, *Ta'rikh al madhahib al dmiyya fi bilad al Yaman*, Cairo, 1988/1408.
- Vidal, F. S., *The oasis of al Ḥasa*, Dhahran, 1955.
- Wilkinson, John C., *The imamate tradition of Oman*, Cambridge, 1987.

Primary sources

- 'Abd al Razzaq al Ṣan'ani, *Muṣannaf 'Abd al Razzaq*, ed. Ḥ. al A'zamī, 11 vols., Beirut, 1403/1983.
- Abu Nu'aym al Iṣbahānī, *Ḥilyat al awliya'*, 10 vols., Beirut, 1405/1985.
- al Ahdal, Ḥusayn ibn 'Abd al Raḥman, *Tuhfat al zaman fi ta'rikh al Yaman*, ed. 'A. M. al Ḥibshī, Beirut, 1407/1986.
- 'Alī ibn Muḥammad ibn 'Ubaydallah, *Swat al Hadī Yahya b. al Ḥusayn*, ed. Suhayl Zakkar, Beirut, 1972.

- Anonymous, *Ta'rikh ahl 'Uman*, ed. S. 'A. 'Ashur, Oman, 1986.
- al Baladhuri, Aḥmad ibn Yahya, *Ansab al ashraf*, vol. V, ed. S. D. Goitein, Jerusalem, 1936.
- Futuḥ al buldan*, ed. R. M. Riḍwan, Beirut, 1403/1983.
- al Bukharī, Muḥammad ibn Isma'īl, *al Ta'rikh al kabīr*, ed. H. al Nadwī, 8 vols., Beirut, n.d.
- al Dhahabī, Muḥammad ibn Aḥmad, *Siyar a'lam al nubala'*, ed. S. al Arna'ut and M. N. al 'Arqasusī, 23 vols., Beirut, 1413/1993.
- al Fakiḥī, Muḥammad ibn Ishāq, *Ta'rikh Makka*: see Wüstenfeld, *Akhbar Makka*.
- al Fasi, Muḥammad ibn Aḥmad, *al 'Iqd al thamīn fi ta'rikh al balad al amīn*, ed. M. H. al Faqī, F. Sayyid and M. M. al Ṭanaḥī, 8 vols., Cairo, 1378 88/1958 69.
- Shifa' al gharam bi akhbar al balad al ḥaram*, vol. II, ed. 'Umar 'Abd al Salam Tadmurī, Beirut, 1405/1985.
- al Zuhur al muqtatafa min ta'rikh Makka al musharrafā*, ed. A. M. al Ghazawī, Beirut, 2000.
- Francesca, E., 'Ṭalīb al Ḥakḳ', *El2* (suppl.), vol. XII, 785.
- al Hamdanī, Ḥasan ibn Aḥmad, *Shifat jazirat al 'Arab*, ed. M. ibn 'Alī al Akwa', Beirut and Ṣan'a', 1403/1983.
- al Hamdanī, Muḥammad ibn 'Abd al Malik, *Takmilat ta'rikh al Ṭabarī*, ed. A. Y. Kan'an, Beirut, 1957.
- Ibn 'Abd al Barr al Namārī al Qurṭubī, Yusuf ibn 'Abd Allah, *al Isti'ab fi ma'rifat al aṣḥab*, ed. 'A. M. al Bijawī, 4 vols., Beirut, 1992/1412.
- Ibn al Athīr, 'Izz al Dīn, *al Kamil fi al ta'rikh*, 10 vols., Beirut, 1415/1995.
- Ibn al Dayba', 'Abd al Raḥman ibn 'Alī, *Qurrat al 'uyun bi akhbar al Yaman al maymun*, ed. M. ibn 'Alī al Akwa' al Ḥīwalī, Cairo, n.d.
- Ibn Fahd, 'Izz al Dīn 'Abd al 'Azīz ibn 'Umar, *Ghayat al muram bi akhbar saltanat al balad al ḥaram*, vol. I, ed. Fahīm Muḥammad Shaltut, Mecca, 1406/1986.
- Ibn Ḥajar al 'Asqalanī, Aḥmad ibn 'Alī, *al Iṣāba fi tamyiz al ṣaḥāba*, ed. A. M. al Bijawī, 8 vols., Beirut, 1992/1412.
- Ibn Ḥazm, 'Alī ibn Aḥmad, *Jamharat ansab al 'Arab*, ed. 'A. M. Harun, Cairo, 1382/1962.
- Ibn al 'Imad, 'Abd al Ḥayy ibn Aḥmad, *Shadharat al dhahab fi akhbar man dhahab*, 4 vols., Beirut, n.d.
- Ibn Kathīr, Isma'īl ibn 'Umar, *al Bidaya wa l nihaya*, 14 vols., Beirut, n.d.
- Ibn Manẓur, Muḥammad ibn Mukram, *Lisan al 'Arab*, 15 vols., Beirut, n.d.
- Ibn al Taghribirdī, Yusuf, *al Nujum al zahira fi muluk Miṣr wa l Qahira*, 12 vols., Cairo, n.d.
- Ibn Zāhira, Muḥammad ibn Amīn, *al Jamī' al latīf fi faḍa'il Makka*: see Wüstenfeld, *Akhbar Makka*.
- 'Imad al Dīn, Idrīs, *Uyun*: see Sayyid, Walker and Pomerantz, *The Fatimids and their successors*.
- al Iṣfahānī, Abu al Faraj, *Maqatil al Ṭalibiyyīn*, ed. Aḥmad Ṣaqr, Beirut, n.d.
- al Izkiwī, Sirḥan ibn Sa'īd ibn Sirḥan (attrib.), *Annals of Oman to 1728*, trans. and annot. E. C. Ross, Cambridge and New York, 1984.
- (attrib.), *Kapitel XXXIII de anonym arabischen Chronik Kasfal Ghumma al Gami' li Akhbar al Umma*, ed. and trans. Hedwig Klein, Hamburg, 1938.
- al Juddī al Ḥijazī, 'Abd al Qadīr ibn Muḥammad ibn Muḥammad ibn Faraj, *al Silaḥ wa l 'udda fi ta'rikh Judda*, ed. M. al Ḥudrī, Damascus, Beirut and Medina, 1988.
- al Kalā'ī, Sulaymān ibn Mūsā, *al Iktifa' bi ma taḍammanahu min maghazī rasul allah wa l thalatha al khulafa'*, ed. M. K. 'Alī, 4 vols., Beirut, 1417/1997.
- Khalīfa ibn Khayyāṭ al 'Uṣfurī, *Ta'rikh*, ed. A. Ḍ. al 'Umarī, 2 vols., Beirut and Damascus, 1397/1976.

- al Maqrızı, Taqı al Dın Aḥmad ibn ‘Alı, *Itti‘az al ḥunafa’ bi akhbar al a’imma al Faṭimiyyın al khulafa’*, ed. Jamal al Dın al Shayyal, Cairo, 1368/1948.
- al Muqaddası, Shams al Dın, *Aḥsan al taqasım fi ma’rifat al aqalım*, ed. M. J. de Goeje, Leiden, 1906.
- al Muṭa‘, A. ibn A., *Ta’rīkh al Yaman al Islāmı min sanat arba’ wa mi’atayn ila sanat alf wa sitt*, ed. ‘A. M. al Ḥibshı, Beirut, 1986/1407.
- al Nahrwalı, Quṭb al Dın, *al I‘lam bi a‘lam bayt allah al ḥaram: see* Wüstenfeld, *Akhbar Makka*.
- Naşer e Khosraw, *Book of travels (Safarnama)*, trans. W. M. Thackston Jr., Bibliotheca Persica, Albany, 1986.
- al Razı, Aḥmad ibn ‘Abd Allah, *Ta’rīkh madınat Şan‘a’*, ed. Ḥ. ibn ‘Abd Allah al ‘Amrı, Şan‘a’, 1401/1981.
- al Sakhawı, Shams al Dın, *al Tuḥfa al latıfa fi ta’rīkh al Madına al sharıfa*, 3 vols., Cairo, 1376/1957.
- al Salımı, Nur al Dın ‘Abd Allah ibn Ḥumayd, *Tuḥfat al a‘yan bi sirat ahl ‘Uman*, vol. I, Cairo, 1380/1961.
- Sayyid, A. F., P. Walker and M. A. Pomerantz, *The Faṭimids and their successors in Yaman: The history of an Islamic community*, Arabic edn and English summary of Idrıs ‘Imad al Dın’s *‘Uyun al akhbar*, vol. VII, London and New York, 2002.
- al Sinjarı, ‘Alı ibn Taj al Dın, *Mana’ih al karam fi akhbar Makka wa l bayt wa wulat al ḥaram*, ed. J. ‘A. Muḥammad al Mişrı, 6 vols., Mecca, 1419/1998.
- al Ṭabarı, Abu Ja‘far Muḥammad ibn Jarır, *Ta’rīkh al rusul wa l muluk*, ed. M. A. Ibrahim, 10 vols., Cairo, 1960.
- ‘Umarı al Yamani, *al Mufid fi akhbar Şan‘a’ wa Zabıd wa shu‘ara’ mulukiha wa a‘yaniha wa udaba’iha*, ed. Muḥammad b. ‘Alı al Akwa‘, Şan‘a’, 1985.
- Wüstenfeld, F., *Akhbar Makka al musharrafa*, 3 vols., Göttingen, 1274/1857.
- Yahya ibn al Ḥusayn, *Ghayat al amanı fi akhbar al quṭr al yamani*, ed. S. ‘A. ‘Ashur and M. M. Ziyada, Cairo, 1388/1968.
- al Ya‘qubı, Aḥmad ibn Abı Ya‘qub, *Ta’rīkh*, 2 vols., Beirut, 1379/1960.
- Yaqut ibn ‘Abd Allah, *Mu‘jam al buldan*, 5 vols., Beirut, n.d.
- Zabara al Ḥasanı, Muḥammad ibn Muḥammad, *al Inba’ ‘an dawlat Bilqıs wa Saba’*, Şan‘a’, 1404/1984.
- Itḥaf al muḥtadın bi dhikr al a’imma al mujaddidin*, Şan‘a’, 1343/1925.
- Ta’rīkh al Zaydiyya*, ed. M. Zaynahm, Cairo, n.d.
- al Zubayrı, Muş‘ab ibn ‘Abd Allah, *Nasab Quraysh*, ed. E. Lévi Provençal, Cairo, n.d.

Secondary sources

- ‘Abd al Ghani, ‘A., *Ta’rīkh umara’ Makka al mukarrama*, Damascus, 1413/1992.
- Umara al Madına al munawwara*, Damascus, n.d.
- al ‘Alı, S. A., *al Ḥijaz fi şadr al Islam: dirasat fi ahwalıhi al ‘umraniyya wa l idariyya*, Beirut, 1410/1990.
- ‘Mulkiyyat al arḍ fi al Ḥijaz fi al qarn al awwal al hijrı’, *al ‘Arab*, 3 (1969), 961–1005.
- al ‘Anı, ‘A. ‘A., *Ta’rīkh ‘Uman fi al ‘uşur al Islamiyya al ula*, London, 1420/1999.
- van Arendonck, C., *Les débuts de l’imamat zaidite du Yemen*, trans. J. Ryckmans, Leiden, 1960.

- Basha, Ayyub Şabrı, *Mir'at jazirat al 'Arab*, trans. A. F. Mutawallı and A. al Mursı, Cairo, 1419/1999.
- Bathurst, R. D., 'Maritime trade and imamate government: Two principal themes in the history of Oman to 1728', in D. Hopwood (ed.), *The Arabian Peninsula: Society and politics*, London, 1972, 89 106.
- Bawazır, Sa'id 'Awađ, *Şafaḥat min al ta'rıkh al ḥađramı*, Aden, n.d.
- Canard, M., 'al Ḥasan al A'sam', *EL2*, vol. III, 246.
- Cook, Michael A., 'The historians of pre Wahabı Najd', *SI*, 76 (1992), 163 76.
- Crone, P., 'Muhallabids', *EL2*, vol. VII, 358.
- Dietrich, A., 'al Djar', *EL2*, vol. II, 454.
- Drees, 'A. A.', 'A critical edition of *Ta'rıkh al Madına* by al Shaykh Quṭb al Dın', Ph.D. thesis, University of Edinburgh, 1985.
- Elad, A., 'The rebellion of Muḥammad b. 'Abdallah b. al Ḥasan (known as al Nasf al Zakıyya) in 145/762', in J. E. Montgomery (ed.), *Abbasid studies: Occasional papers of the School of 'Abbasid Studies*, 6 10 July 2002, Leuven, Paris and Dudley, MA, 2004, 147 98.
- Grohman, A., 'Nadjd', *EL2*, vol. VII, 864.
- al Ḥamid, Şalıḥ, *Ta'rıkh Ḥađramawt*, Jiddah, 1968.
- al Ḥarırı, M. 'I. *Dirasat wa buḥuth fi ta'rıkh al Yaman al Islāmı*, Beirut, 1418/1998.
- Hartmann, R., and Phebe Ann Marr, 'Djudda', *EL2*, vol. II, 571.
- al Hayla, Muḥammad al Ḥabıb, *al Ta'rıkh wa l mu'arrıkhun bi Makka min al qarn al thalith al hijrı ila al qarn al thalith 'ashar*, Mecca, 1994.
- al Ḥıbshı, 'A. M., *Maşadir al fıkır al Islāmı fi al Yaman*, Beirut, 1408/1988.
- Mu'allafat ḥukkam al Yaman*, ed. Elke Niewoehner Eberhard, Wiesbaden, 1979.
- Hinds, M., 'An early Islamic family from Oman: al 'Awtabı's account of the Muhallabids', *JSS*, Monograph 17, Manchester, 1991.
- Holes, C., 'Uman', *EL2*, vol. X, 814.
- Horovitz, J., *The earliest biographies of the Prophet and their authors*, ed. Lawrence Conrad, Princeton, 2002.
- Hourani, G. F., *Arab seafaring in the Indian Ocean in ancient and medieval times*, Princeton, 1951.
- al Jasir, Ḥamad, *Bilad Yanbu'*, Riyadh, n.d.
- Fı shımal gharb al Jazıra*, Riyadh, 1981.
- 'al Ḥafşı wa kitabuhu 'an al Yamama', *al 'Arab*, 1 (1967), 673 91, 769 94.
- Madınat al Riyađ 'abra atıwar al ta'rıkh*, Riyadh, 1386/1966.
- 'Mu'allafat fi ta'rıkh al Madına', *al 'Arab*, 4 (1969), 97 100, 262 7, 327 34, 385 8, 465 8.
- 'Mu'allafat fi ta'rıkh Makka', *al 'Arab*, 4 (1970), 949 58.
- al Mu'jam al jughrafi li l bilad al 'Arabiyya al Su'udiyya*, Riyadh, 1399 1401/1979 81.
- 'al Rabadha fi kutub al mutaqaaddımın', *al 'Arab*, 1 (1966), 418 27, 546 50, 625 31, 724 7.
- 'Wulat al Aḥsa' fi al 'ahd al Umawiyy', *al 'Arab*, 1 (1966 7), 28 37.
- al Kaf, Saqqaf 'Alı, *Ḥađramawt 'abra arba'at 'ashar qarnan*, Beirut, 1410/1990.
- Kister, M. J., 'The battle of the Ḥarra: Some socio economic aspects', in M. Rosen Ayalon (ed.), *Studies in memory of Gaston Wiet*, Jerusalem, 1977, 33 49.
- 'The struggle against Musaylima', *JSAI*, 27 (2002), 1 56.
- Landau Tasserón, E., 'Zaydı imams as restorers of religion: *Iḥya'* and *tajdid* in Zaydı literature', *JNES*, 49 (1990), 247 63.

- Madelung, W., 'The Faṭimids and the Qarmāṭis of Baḥrayn', in F. Daftary (ed.), *Medieval Isma'īlī history and thought*, Cambridge, 1996, 21–74.
- 'Qarmāṭ', *ELz*, vol. IV, 660.
- 'Maṇṣūr al Yaman', *ELz*, vol. VI, 438.
- 'The origin of the Yemenite *hijra*', in A. Jones (ed.), *Arabicus Felix: Luminosus Britanicus, essays in honour of A. F. L. Beeston on his eightieth birthday*, Oxford, 1991, 25–44.
- Mayy, Muḥammad al Khalīfa, *Min Sawad al Kufa ila al Baḥrayn*, Beirut, 1999.
- Muṣṭafa, S., *al Ta'rīkh al 'arabī wa l mu'arrikhun*, vol. I, Beirut, 1979.
- al Naboodah, Ḥasan M., 'Banu Nabhan in the Omani sources', in G. R. Smith, J. R. Smart and B. R. Pridham (eds.), *New Arabian Studies*, 4 (Exeter, 1997), 181–95.
- von Oppenheim, M. F., *Die Beduinen*, vol. II, ed. E. Bräunlich and W. Caskel, Leipzig, 1943.
- Die Beduinen*, vol. III, ed. W. Caskel, Wiesbaden, 1952.
- al Rashid, Sa'ad, *Darb Zubayda: The pilgrim road from Kufa to Mecca*, Riyadh, 1980.
- al Rabadha: A portrait of early Islamic civilization in Saudi Arabia*, Riyadh, 1986.
- Rentz, G., 'Qatīf', *ELz*, vol. IV, 763.
- Rotter, G., *Die Umayyaden und der zweite Bürgerkrieg (680–692)*, Wiesbaden, 1982.
- al Sayyabī, Salīm ibn Ḥamūd, *al Ḥaḡiqa wa l majaz fi ta'rīkh al Ibaḡiyya bi l Yaman wa l Ḥijaz*, Muscat, 1400/1980.
- Is'af al a'yan fi ansab ahl 'Uman*, Beirut, 1384.
- Sayyid, Ayman Fu'ad, *Maṣādir ta'rīkh al Yaman fi al 'asr al Islāmī*, Cairo, 1974.
- Schmucker, W., 'Die Christliche Minderheit von Najran', *Studien zum Minderheitenproblem im Islam*, 1 (1973), 183–281.
- Serjeant, R. B., 'Historians and historiography of Ḥaḡramawt', in R. B. Serjeant, *Studies in Arabian history and civilization*, Variorum Collected Studies, Aldershot and Brookfield, VT, 1981, X.
- 'The interplay between tribal affinities and religious (Zaydi) authority in the Yemen', *al Abḡath*, 30 (1982), 11–47.
- 'Materials for South Arabian history', *BSOAS*, 13 (1950), 281–307, 581–601.
- 'The sayyids of Ḥaḡramawt', in R. B. Serjeant, *Studies in Arabian history and civilization*, Variorum Collected Studies, Aldershot and Brookfield, VT, 1981, VIII.
- 'South Arabia', in R. B. Serjeant, *Studies in Arabian history and civilization*, Variorum Collected Studies, Aldershot and Brookfield, VT, 1981, IX.
- Shalabī, Aḡmad, *Mawsu'at al ta'rīkh al Islāmī wa l ḡaḡara al Islāmīyya*, vol. VII, Cairo, 1982.
- al Shamī, Aḡmad ibn Muḥammad, *Ta'rīkh al Yaman al fikrī fi al 'asr al 'Abbāsī*, 4 vols., Beirut, 1407/1987.
- Shoufani, E., *al Riddah and the Muslim conquest of Arabia*, Toronto and Beirut, 1975.
- Smith, G. R., 'The political history of the Islamic Yemen down to the first Turkish invasion (1945/622–1538)', in G. R. Smith, *Studies in the medieval history of the Yemen and Arabia Felix*, Variorum Collected Studies, Aldershot and Brookfield, VT, 1997, I.
- 'Yemenite history: Problems and misconceptions', in G. R. Smith, *Studies in the medieval history of the Yemen and Arabia Felix*, Variorum Collected Studies, Aldershot and Brookfield, VT, 1997, II.
- Stookey, R. W., *Yemen: The politics of the Yemen Arab Republic*, Boulder, 1978.
- Veccia Vaglieri, Laura, 'L'Imamato Ibaḡita dell' Oman', *Annali (Istituto Universitario Orientale, Napoli)*, n.s. 3 (1949), 245–82.

- Wilkinson, J. C., 'Bibliographical background to the crisis period in the Ibaḍi imamate (end of the ninth to end of the fourteenth century)', *Arabian Studies*, 3 (1976), 137–64.
- 'The Julanda of Oman', *Journal of Oman Studies*, 1 (1975), 97–108.
- Zakkar, Suhayl, *al-Jami' fi akhbar al-Qaramiṭa fi al-Aḥsa'*, al-Sham, al-'Iraq, al-Yaman, Damascus, 1407/1987.
- von Zambauer, Edward, *Mu'jam al-ansab wa l-usarat al-ḥakima fi al-ta'rikh al-Islamī*, Beirut, 1980.

Chapter II: The Islamic east

Practical suggestions for further reading

- Bartold, W., *Turkestan down to the Mongol invasion*, 4th edn, London, 1977.
- Bosworth, C. E., *The history of the Saffarids of Sistan and the Maliks of Nimruz*, Costa Mesa, 1994.
- Sistan under the Arabs, from the Islamic conquest to the rise of the Ṣaffarids (30–250/651–864)*, Rome, 1968.
- Daniel, Elton, *The political and social history of Khurasan under Abbasid rule, 747–820*, Minneapolis and Chicago, 1979.
- Frye, R. N., *Bukhara: The medieval achievement*, Norman, OK, 1965.
- The golden age of Persia*, New York, 1963.
- (ed.), *The Cambridge history of Iran*, vol. IV: *The period from the Arab invasion to the Saljuqs*, Cambridge, 1975.
- Hovannisian, Richard G., and Georges Sabbagh (eds.), *The Persian presence in the Islamic world*, Cambridge, 1998.
- Madelung, W., *Religious trends in early Islamic Iran*, New York, 1988.
- Spuler, Bertold, *Iran in frühislamischer Zeit*, Wiesbaden, 1952.

Primary sources

- Akhbar al-dawla al-'Abbasiyya wa fihi akhbar al-'Abbas wa wuldihi*, ed. 'Abd al-'Azīz al-Durī and 'Abd al-Jabbar al-Muṭṭalibī, Beirut, 1971.
- al-Baghdādī, 'Abd al-Qāhir ibn Ṭahir, *al-Farq bayna 'l-firaq*, ed. M. 'Abd al-Ḥamīd, Cairo, 1964.
- al-Baladhurī, Aḥmad ibn Yahyā, *Ansab al-ashraf*, ed. M. al-'Azm, 25 sections to date, Damascus, 1996–2004.
- Kitab futuḥ al-buldan*, ed. M. J. de Goeje, Leiden, 1866; trans. P. K. Hitti and F. C. Murgotten as *The origins of the Islamic state*, 2 vols., New York, 1916–24.
- Bal'ami, Abu 'l-Faḍl Muḥammad, *Tarjamah yi Tarikh i Tabari*, first part ed. M. Bahar as *Tarikh i Bal'ami*, 2 vols., Tehran, 1962; second part ed. M. Rawshan as *Tarikh namah ye Tabari*, 3 vols., Tehran, 1988; ed. and trans. H. Zotenberg as *Chronique de Abou Djafar Mohammed ben Djarir ben Yezid Tabari*, 4 vols., Paris, 1867–74.
- Balkhī, 'Abd Allah, *Faḍa'il i Balkh*, ed. 'A. Ḥabībī, Tehran, 1350/1972.
- Bayhaqī, Abu 'l-Faḍl Muḥammad, *Tarikh i Bayhaqī*, ed. 'Alī Fayyād, Mashhad, 1350/1971.
- Biruni, Abu 'l-Rayḥān, *Athar al-baqiya*, trans. C. Edward Sachau, London, 1879.
- al-Dīnawarī, Abu Ḥanīfa Aḥmad, *al-Akhbar al-tiwal*, ed. A. 'Amīr, Cairo, 1960.
- Fragmenta Historicorum Arabicorum*, ed. M. J. de Goeje, 2 vols., Leiden, 1869.

- Gardīzi, Abu Sa'īd, *Zayn al akhbar*, ed. 'A. H. Ḥabībī, Tehran, 1347/1969.
- Ḥamza al Iṣfahānī, *Ta'rikh sanī muluk al ard wa'l anbiya'*, ed. Y. al Maskunī, Beirut, 1961.
- Hudud al 'alam*, trans. V. Minorsky, London, 1937.
- Ibn 'Abd Rabbīhi, Abu 'Umar Aḥmad ibn Muḥammad, *Kitab al 'iqd al fard*, ed. A. Amin *et al.*, 8 vols., Cairo, 1940 53.
- Ibn Abī Ṭahir Ṭayfur, Abu 'l Faḍl Aḥmad ibn Ṭahir, *Baghdad fi ta'rikh al khilafa al 'abbasiyya*, Baghdad, 1968.
- Ibn A'tham al Kufī, Abu Muḥammad Aḥmad, *al Futuḥ*, ed. Muḥammad 'Abd al Mu'īd Khan *et al.*, 8 vols., Hyderabad, 1968 75.
- Ibn al Athīr, 'Izz al Dīn 'Alī ibn Aḥmad, *al Kamil fi 'l ta'rikh*, 13 vols., Beirut, 1965 7.
- Ibn al Balkhī, *Fars namah*, ed. G. LeStrange and R. A. Nicholson, London, 1927.
- Ibn al Faqīh, Muḥammad ibn Ishāq, *Kitab al buldan*, ed. M. J. de Goeje, Leiden, 1885.
- Ibn Funduq Bayhaqī, Abu 'l Ḥasan, *Tarikh i Bayhaq*, ed. A. Bahmanyar, Tehran, 1317/1939.
- Ibn Ḥazm, *al Faṣl fi'l milal wa'l ahwa' wa'l niḥal*, ed. A. Khalīfa *et al.*, 5 vols., Cairo, 1317 21 / 1899 1903.
- Ibn al 'Imrānī, Muḥammad ibn 'Alī, *al Inba' fi ta'rikh al khulafa'*, ed. Q. al Samarra'ī, Leiden, 1973.
- Ibn Isfandīyar, *Tarikh i Ṭabaristan*, ed. 'Abbas Iqbal, Tehran, 1944.
- Ibn Khurradadbih, Abu 'l Qasim, *Kitab al masalik wa'l mamalik*, ed. M. J. de Goeje, Leiden, 1889.
- Ibn Miskawayh, Abu 'Alī Aḥmad ibn Muḥammad, *Tajarih al umam*, ed. M. J. de Goeje, Leiden, 1871.
- Ibn al Muqaffa', *Athar Ibn al Muqaffa'*, ed. 'U. Abu 'l Naṣr, Beirut, 1966.
- Ibn al Nadīm, *Kitab al fihrist*, ed. R. Tajaddud, Tehran, 1971; trans. Bayard Dodge as *The Fihrist of al Nadīm*, 2 vols., New York, 1970.
- Ibn Qutayba, Abu Muḥammad 'Abd Allah ibn Muslim, *Kitab al Ma'arif*, ed. T. 'Ukasha, Cairo, 1969.
- Kitab 'uyun al akhbar*, 4 vols., Cairo, 1964.
- Ibn Rustah, *Kitab al a'laq al nafisa*, ed. M. J. de Goeje, Leiden, 1892.
- al Iṣbahānī, Abu al Faraj 'Alī, *al Aghānī*, 31 vols., Cairo, 1969 79.
- Maqatil al Ṭalibiyyin*, ed. Kaẓīm al Muẓaffar, Najaf, 1965.
- al Iṣṭakhrī, Abu Ishāq, *al Masalik wa'l mamalik*, ed. M. J. de Goeje, Leiden, 1870.
- al Jahshīyārī, Muḥammad ibn 'Abdus, *Kitab al wuzara' wa'l kuttāb*, ed. M. al Saqqā, Cairo, 1938.
- Khalīfa ibn Khayyāṭ, *al Ta'rikh*, ed. Akram al 'Umarī, 2 vols., Najaf, 1967.
- al Khwarizmī, Abu 'Abd Allah, *Mafatih al 'ulum*, ed. G. van Vloten, Leiden, 1895.
- al Maqdisī, Muṭahhar ibn Ṭahir, *al Bad' wa'l ta'rikh*, ed. and trans. C. Huart as *Le Livre de la création et de l'histoire*, 6 vols., Paris, 1899 1919.
- al Maqrīzī, Abu 'l 'Abbas, *al Muqaffa' al kabīr*, ed. M. al Ya'lawī, 8 vols., Beirut, 1991.
- al Niza' wa'l takhaṣum fima bayna Banī Umayya wa Banī Hashim*, Cairo, 1947.
- al Mas'ūdī, 'Alī ibn al Ḥusayn, *Mujmal al tawarikh wa'l qīṣaṣ*, ed. M. Bahar, Tehran, 1940.
- Muruḥ al dhahab wa ma'adin al jawhar*, ed. Charles Pellat, 7 vols., Beirut, 1965 79.
- al Muqaddasī [Maqdisī], Shams al Dīn Muḥammad ibn Aḥmad, *Aḥsan al taqasim fi ma'rifat al aqalim*, ed. M. J. de Goeje, Leiden, 1906.
- Narshakhi, Abu Bakr Muḥammad, *Tarikh i Bukhara*, ed. Mudarris Raḍavī, Tehran, 1972; ed. and trans. R. N. Frye as *The history of Bukhara*, Cambridge, MA, 1954.

Bibliography

- al Nawbakhti, Ḥasan ibn Musa, *Firq al shi'a*, Najaf, 1932; trans. Javad Mashkur as *Les sectes shiites*, Tehran, 1980.
- Nizām al Mulk, *Nubdha min Kitāb al ta'rikh*, published as manuscript facsimile by P. A. Gryaznevich as *Arabskii anonim XI veka*, Moscow, 1960.
- Siyasatnamah (Siar al muluk)*, ed. J. Shi'ar, Tehran, 1969; trans. Hubert Darke as *The book of government: Or, rules for kings*, New Haven, 1960.
- Qummi, Ḥasan ibn Muḥammad, *Kitāb i tarikh i Qumm*, Tehran, 1353/1934.
- Sa'd al Qummi, *Kitāb al maqalat wa'l firq*, ed. M. J. Mashkur, Tehran, 1963.
- al Sam'ani, 'Abd al Karīm, *Kitāb al ansab*, ed. 'A. al Yamani, 13 vols., Hyderabad, 1962–82.
- al Shabushti, Abu 'l Ḥasan, *Kitāb al diyarat*, ed. Kurkī 'Awwad, Baghdad, 1386/1966.
- al Ṭabari, Abu Ja'far Muḥammad ibn Jarīr, *Ta'rikh al khulafā'*, published as manuscript facsimile by P. A. Gryaznevich, Moscow, 1967.
- Ta'rikh al rusul wa'l muluk*, ed. M. J. de Goeje et al., 15 vols. in 3 series, Leiden, 1879–1901.
- Tarikh i Sistan*, ed. Malik al Shu'ara' Bahar, Tehran, 1935, trans. Milton Gold as *The Tarikh e Sistan*, Rome, 1976.
- al Tha'alibi, 'Abd al Malik, *Ghurur akhbar muluk al furs*, ed. and trans. H. Zotenberg, Paris, 1900.
- Thimar al qulub*, ed. M. Ibrahim, 5 vols., Cairo, 1965.
- al 'Utbi, Muḥammad ibn 'Abd al Jabbar, *al Yammi*, ed. D. al Thamiri, Beirut, 2004.
- al 'Uyun wa'l hada'iq fi akhbar al haqa'iq*, ed. M. J. de Goeje, Leiden, 1869.
- al Ya'qubi, Ahmad ibn Abi Ya'qub, *Kitāb al buldan*, ed. M. J. de Goeje, Leiden, 1892.
- Ta'rikh*, ed. M. Houtsma as *Ibn Wadhih qui dicitur al Ja'qubi historiae*, 2 vols., Leiden, 1883.

Secondary sources

- Agha, Saleh Said, 'Abu Muslim's conquest of Khurasan', *JAOS*, 120 (2000), 333–47.
- 'The Arab population in Hurasan during the Umayyad period', *Arabica*, 46 (1999), 211–29.
- The revolution which toppled the Umayyads: Neither Arab nor 'Abbasid*, Leiden, 2003.
- 'A viewpoint on the Murji'a in the Umayyad period: Evolution through application', *Journal of Islamic Studies*, 8 (1997), 1–42.
- al 'Ali, Ṣaliḥ, 'Istiqān al 'arab fi Khurasan', *Majallat kulliyat al adab wa'l 'ulum fi Baghdad* (1958), 36–83.
- Amabe, Fukuzo, *The emergence of the 'Abbasid autocracy: The 'Abbasid army, Khurasan and Adharbayjan*, Kyoto, 1995.
- Amoretti, B. S., 'Sects and heresies', in R. N. Frye (ed.), *Cambridge history of Iran*, vol. IV: *The period from the Arab invasion to the Saljuqs*, Cambridge, 1975, 481–519.
- 'Athamina, Khalil, 'Arab settlement during the Umayyad caliphate', *JSAI*, 8 (1986), 185–207.
- 'The early Murji'a: Some notes', *JSS*, 35 (1990), 109–30.
- Azizi, Muhsen, *La Domination arabe et l'épanouissement du sentiment national en Iran*, Paris, 1938.
- Bartold, W., *An historical geography of Iran*, trans. S. Soucek, Princeton, 1984.
- Beckwith, C., 'Aspects of the early history of the Central Asian guard corps in Islam', *Archivum Eurasiae Medii Aevi*, 4 (1984), 29–43.
- 'The plan of the City of Peace: Central Asian Iranian factors in 'Abbasid design', *Acta Orientalia*, 38 (1984), 143–64.

- 'The revolt of 755 in Tibet', *Wiener Studien zur Tibetologie und Buddhismuskunde*, 10 (1983), 1–16.
- The Tibetan empire in Central Asia*, Princeton, 1987.
- Blankinship, Khalid Yahya, *The end of the jihad state: The reign of Hisham Ibn 'Abd al Malik and the collapse of the Umayyads*, Albany, 1994.
- 'The tribal factor in the 'Abbasid revolution: The betrayal of the Imam Ibrahim b. Muḥammad', *JAOS*, 108 (1988), 589–603.
- Bligh Abramski, Irit, 'Evolution vs. revolution: Umayyad elements in the 'Abbasid regime 133/750–320/932', *Der Islam*, 65 (1988), 226–43.
- Bosworth, C. E., 'The armies of the Ṣaffarids', *BSOAS*, 31 (1968), 534–54.
- 'Dailamis in Central Iran: The Kakuyids of Jibal and Yazd', *Iran*, 8 (1970), 73–95.
- 'The development of Persian culture under the early Ghaznavids', *Iran*, 6 (1968), 33–44.
- 'An early Arabic mirror for princes: Ṭahir Dhu 'l Yaminain's epistle to his son 'Abdallah (206/821)', *JNES*, 29(1970), 25–41.
- 'The early Islamic history of Ghur', *Central Asiatic Journal*, 6 (1961), 116–33.
- The Ghaznavids*, 2nd edn, Beirut, 1973.
- 'The heritage of rulership in early Islamic Iran and the search for dynastic connections with the past', *Iran*, 11 (1973), 51–62.
- 'The interaction of Arabic and Persian literature and culture in the 10th and early 11th centuries', *al Abhath*, 27 (1978–9), 59–75.
- 'Notes on the pre Ghaznavid history of eastern Afghanistan', *Islamic Quarterly*, 9 (1965), 12–24.
- 'The rise of the Karamiyya in Khurasan', *MW*, 50 (1960), 6–14.
- 'The rulers of Chaghaniyan in early Islamic times', *Iran*, 19 (1981), 1–20.
- 'The Tahirids and Arabic culture', *JSS*, 14 (1969), 45–79.
- 'The Tahirids and Persian literature', *Iran*, 7 (1969), 103–6.
- Bulliet, R. W., *Conversion to Islam in the medieval period: An essay in quantitative history*, Cambridge, MA, 1979.
- Islam: The view from the edge*, New York, 1994.
- The patricians of Nishapur*, Cambridge, MA, 1972.
- Cahen, Claude, 'Points de vue sur la "Révolution abbaside"', *Revue Historique* (1963), 295–335.
- Canfield, R. (ed.), *Turko Persia in historical perspective*, Cambridge, 1991.
- Cereti, C. G. 'Primary sources for the history of Inner and Outer Iran in the Sasanian period', *Archivum Eurasiae Medii Aevi*, 9 (1997), 17–71.
- Chabbi, J., 'Remarques sur le développement historique des mouvements ascétiques et mystiques au Khurasan', *SI*, 46 (1977), 5–72.
- Chavannes, Eduard, *Documents sur les Tou Kiue (Turcs) Occidentaux*, St Petersburg, 1903.
- Choksy, Jamsheed K., *Conflict and cooperation: Zoroastrian subalterns and Muslim elites in medieval Iranian society*, New York, 1997.
- Chowdhry, S. R., *al Ḥajjaj Ibn Yusuf*, Delhi, 1972.
- Christensen, A. E., *L'Iran sous les Sassanides*, 2nd edn, Copenhagen, 1944.
- Christensen, Peter, *The decline of Iranshahr: Irrigation and environments in the history of the Middle East 500 BC to 1500 CE*, Copenhagen, 1993.
- Cooperson, M., *Classical Arabic biography: The heirs of the Prophet in the age of al Ma'mun*, Cambridge, 2000.

- Crone, Patricia, 'The 'Abbasid Abna' and Sasanid cavalrymen', *JRAS*, ser. 3, 8 (1998), I 19.
 'On the meaning of the 'Abbasid call to al Ridā', in C. E. Bosworth et al. (eds.), *The Islamic world from classical to modern times: Essays in honor of Bernard Lewis*, Princeton, 1989, 95 III.
Slaves on horses: The evolution of the Islamic polity, Cambridge, 1980.
 'Were the Qays and Yemen of the Umayyad period political parties?', *Der Islam*, 71 (1994), I 57.
- Crone, Patricia, and Martin Hinds, *God's caliph: Religious authority in the first centuries of Islam*, Cambridge, 1986.
- Czegledy, K., 'Gardīzi on the history of Central Asia (746–780 AD)', *Acta Orientalia*, 27(1973), 257–67.
- Daniel, Elton, 'The "Ahl al Taqadum" and the problem of the constituency of the Abbasid revolution in the Merv Oasis', *Journal of Islamic Studies*, 7 (1996), 150–79.
 'The anonymous history of the Abbasid family and its place in Islamic historiography', *IJMES*, 14 (1982), 419–34.
 'Manuscripts and editions of Bal'ami's Tarjamah yi Tarikh i Tabari', *JRAS* (1990), 282–321.
 'The Samanid "translations" of al Tabari', in Hugh Kennedy (ed.), *al Tabari: The life and works of a medieval Muslim historian* (forthcoming).
- Daryaei, Touraj, 'Apocalypse now: Zoroastrian reflections on the early Islamic centuries', *Medieval Encounters*, 4 (1998), 188–202.
- Dennett, Daniel C., *Conversion and the poll tax in early Islam*, Cambridge, MA, 1950.
- Dixon, A. A., *The Umayyad caliphate 658/684–705*, London, 1971.
- Donner, F., *The early Islamic conquests*, Princeton, 1981.
- Dunlop, D. M., 'Arab relations with Tibet in the 8th and early 9th centuries AD', *Islām Tetkikleri Enstitüsü Dergisi*, 5 (1973), 301–18.
The history of the Jewish Khazars, Princeton, 1954.
 'A new source of information on the battle of Talas or Atlakh', *Ural Altaische Jahrbücher*, 36 (1964), 326–30.
- al Durī, 'Abd al 'Azīz, *al 'Aṣr al 'abbasi al awwal*, Baghdad, 1945.
 'al Fikra al mahdiyya bayna al da'wa al 'abbasiyya wa al 'aṣr al 'abbasi al awwal', in W. al Qaḍī (ed.), *Studia Arabica et Islamica: Festschrift for Ihsan 'Abbas*, Beirut, 1981, 123–32.
 'Nizām al ḥarā'ib fī Khurasan fī ṣaḍr al islām', *Majallat al majma' al 'ilmi al 'iraqi*, 11 (1964), 75–7.
- Elad, Amikam, 'Aspects of the transition from the Umayyad to the 'Abbasid caliphate', *JSAI*, 19 (1995), 89–132.
 'The ethnic composition of the 'Abbasid revolution: A reevaluation of some recent research', *JSAI*, 24 (2000), 246–326.
- El Hibri, T., 'The Mecca Protocol of 802: A plan for division or succession?' *IJMES*, 24 (1992), 461–80.
Reinterpreting Islamic historiography: Harun al Rashid and the narrative of the 'Abbasid caliphate, Cambridge, 1999.
- Esin, Emel, 'Tarkhan Nizak or Tarkhan Tirek? An enquiry concerning the prince of Badkhis ...', *JAOS*, 97 (1977), 323–32.
- Forstner, M., 'Ya'qub b. al Lait und der Zunbil', *ZDMG*, 120 (1970), 69–83.
- Fragner, B. G., *Die 'Persophonie': Regionalität, Identität und Sprachkontakt in der Geschichte Asiens*, Berlin, 1999.

- Frye, R. N., 'The fate of Zoroastrians in eastern Iran', in R. Gyselen (ed.), *Au carrefour des religions: Mélanges offert à Philippe Gignoux*, Bures sur Yvette, 1995, 67–72.
- 'Feudalism in Sasanian and early Islamic Iran', *JSAI*, 9 (1987), 13–18.
- Islamic Iran and Central Asia*, London, 1979.
- 'The role of Abu Muslim in the 'Abbasid revolt', *MW*, 37 (1947), 28–38.
- 'The Samanids', in R. N. Frye (ed.), *The Cambridge history of Iran*, vol. IV: *The period from the Arab Invasion to the Saljuqs*, Cambridge, 1975, 136–61.
- 'Die Wiedergeburt Persiens um die Jahrtausandwande', *Der Islam*, 35 (1960), 42–51.
- Gabrieli, Francesco, 'Muḥammad ibn Qasim ath Thaqafi and the Arab conquest of Sind', *East and West*, n.s. 15 (1964–5), 281–95.
- 'La successione di Harun al Rashid e la guerra fra al Amin e al Ma'mun', *RSO*, 11 (1926–8), 341–97.
- Ghirshman, R., *Les Chionites Hephtalites*, Cairo, 1948.
- Gibb, H. A. R., *The Arab conquests in Central Asia*, London and New York, 1923.
- 'Chinese records of the Arabs in Central Asia', *BSOAS*, 2 (1922), 613–22.
- 'The social significance of the Shu'ubriya', in *Studia Orientalia Ioanni Pedersen septuagenario AD VII id. nov. anno MCMLIII a collegis discipulis amicis dicata*, Copenhagen, 1953, 105–14.
- Golden, Peter B., *An introduction to the history of the Turkic peoples*, Wiesbaden, 1992.
- 'The Karakhanids and early Islam', in D. Sinor (ed.), *The Cambridge history of early Inner Asia*, Cambridge, 1990, 343–70.
- Gordon, M., *The breaking of a thousand swords: A history of the Turkish military community of Samarra (AH 200–275/815–889 CE)*, Albany, 2001.
- Grenet, F., *La geste d'Ardashir fils de Pâbag: Karnamag i Ardashēr ī Pabagan*, Paris, 2001.
- Grignaschi, M., 'La riforma tributaria di Ḥosro ī e il feudalismo sassanide', *Atti del Convegno internazionale sul tema: La Persia nel medioevo* (Roma, 31 marzo–5 aprile 1970), Rome, 1971, 87–138.
- Guest, R., 'A coin of Abu Muslim', *JRAS* (1932), 54–6.
- Gyselen, R., *La géographie administrative de l'empire sassanide*, Paris, 1989.
- Hasan, S., 'A survey of the expansion of Islam into Central Asia during the Umayyad caliphate', *Islamic Culture*, 48 (1974), 177–86.
- Hawting, G. R., *The first dynasty of Islam: The Umayyad caliphate, AD 661–750*, London and Sydney, 1986.
- Hill, D. R., *The termination of hostilities in the early Arab conquests, AD 634–656*, London, 1971.
- Hinds, M., 'The first Arab conquests of Fars', *Iran*, 22 (1984), 39–53.
- 'Kufan political alignments and their background in the mid seventh century AD', *IJMES*, 2 (1971), 346–67.
- Housseini, A. M., 'The Umayyad policy in Khorasan and its effect on the formulation of Muslim thought', *Journal of the University of Peshawar*, 4 (1955), 1–21.
- Hoyland, R., *Seeing Islam as others saw it: A survey and evaluation of Christian, Jewish and Zoroastrian writings on early Islam*, Princeton, 1997.
- Kaabi, Mongi, 'Les origines Ṭahirides dans la da'wa 'abbaside', *Arabica*, 29 (1972), 145–64.
- Les Ṭahirides*, Paris, 1983.
- Karev, Yury, 'La politique d'Abu Muslim dans le Mawara'annahr: Nouvelles données textuelles et archéologiques', *Der Islam*, 79 (2002), 1–46.
- Kennedy, Hugh, *The armies of the caliphs: Military and society in the early Islamic state*, London and New York, 2001.

- 'The Barmakid revolution in Islamic government', in C. Melville (ed.), *Persian and Islamic studies in honor of P. W. Avery*, London, 1990, 89–98.
- 'Central government and provincial elites in the early 'Abbasid caliphate', *BSOAS*, 44 (1981), 26–38.
- The early Abbasid caliphate: A political history*, London, 1981.
- 'Elite incomes in the early Islamic state', in John Haldon and L. I. Conrad (eds.), *The Byzantine and early Islamic Near East*, vol. VI: *Elites old and new in the Byzantine and early Islamic Near East*, Princeton, 2004, 13–28.
- The Prophet and the age of the caliphate*, London 1986.
- Khanbaghi, Aptin, *The fire, the star and the cross: Minority religions in medieval and early modern Iran*, London, 2006.
- Kimber, R. A., 'The early Abbasid vizierate', *JSS*, 37 (1992), 65–85.
- 'Harun al Rashid's Meccan settlement of AH 186/AD 802', *School of Abbasid Studies Occasional Papers*, 1 (1986), 55–79.
- Klima, O., *Mazdak: Geschichte einer sozialen Bewegung im sassanidischen Persien*, Prague, 1957.
- Lambton, Ann K. S., 'An account of the Tarikhi Qumm', *BSOAS*, 12 (1948), 586–96.
- Lapidus, Ira M., 'Arab settlement and economic development of Iraq and Iran in the age of the Umayyad and early Abbasid caliphs', in A. L. Udovitch (ed.), *The Islamic Middle East, 700–1900: Studies in economic and social history*, Princeton, 1981, 177–208.
- Lassner, Jacob, 'Abu Muslim al Khurasani: The emergence of a secret agent from Khurasan, Iraq, or was it Isfahan?', *JAOS*, 104 (1984), 165–75.
- 'Abu Muslim, son of Saḥī: A skeleton in the 'Abbasid closet?', in M. Sharon (ed.), *Studies in Islamic history and civilization in honour of Professor David Ayalon*, Jerusalem and Leiden, 1986, 91–104.
- Islamic revolution and historical memory: Abbasid apologetics and the art of historical writing*, New Haven, 1986.
- The shaping of Abbasid rule*, Princeton, 1980.
- Laurent, Joseph, *L'Arménie entre Byzance et l'Islam depuis la conquête arabe jusqu'en 886*, rev. edn, Paris, 1980.
- Lazard, G., *La langue des plus anciens monuments de la prose persane*, Paris, 1963.
- Les premiers poètes persans (IXe–Xe siècles)*, Paris and Tehran, 1964.
- Le Strange, G., *The lands of the eastern caliphate*, London, 1905.
- Lieu, S. N. C., *Manichaeism in Central Asia and China*, Leiden, 1998.
- Litvinsky, B. A., 'The Hephthalite empire', in B. A. Litvinsky (ed.), *History of civilizations of Central Asia*, vol. III: *The crossroads of civilization AD 250 to 750*, Paris, 1996, 135–62.
- Madelung, W., 'Abu Ishāq al Ṣabī on the Alids of Tabaristan and Gilan', *JNES*, 26 (1967), 15–57.
- 'The early Murji'a in Khurasan and Transoxiana and the spread of Ḥanafism', *Der Islam*, 59 (1982), 32–9.
- Der Imam al Qasim ibn Ibrahim und die Glaubenslehre der Zaiditen*, Berlin, 1965.
- 'The minor dynasties of northern Iran', in R. N. Frye (ed.), *The Cambridge history of Iran*, vol. IV: *The period from the Arab invasion to the Saljuqs*, Cambridge, 1975, 198–249.
- 'New documents concerning al Ma'mun, al Faḍl b. Sahl and 'Alī al Riḍā', in W. al Qaḍī (ed.), *Studia Arabica et Islamica: Festschrift for Iḥsan 'Abbas on his sixtieth birthday*, Beirut, 1981, 333–46.
- 'The spread of Maturidism and the Turks', in *Actas, IV Congresso de Estudos Árabes e Islâmicos, Coimbra Lisboa, 1 a 8 de setembro de 1968*, Leiden, 1971, 109–68.

- The succession to Muḥammad: A study of the early caliphate*, Cambridge, 1997.
- 'The vigilante movement of Sahl b. Salama al Khurasani and the origins of Ḥanbalism reconsidered', *Journal of Turkish Studies*, 14 (1990), 331–7.
- Marín Guzmán, Roberto, 'The 'Abbasid revolution in Central Asia and Khurasan', *Islamic Studies*, 33 (1994), 227–52.
- Popular dimensions of the 'Abbasid revolution*, Cambridge, MA, 1990.
- Markwart, J. *A catalogue of the provincial capitals of Eranshahr*, ed. G. Messina, Rome, 1931.
- Mason, Herbert, 'The role of the Azdite Muhallibid family in Marw's anti Umayyad power struggle', *Arabica*, 14 (1967), 191–207.
- Mélikoff, Irène, *Abu Muslim: Le 'Porte Hache' du Khorassan dans la tradition épique turco iranienne*, Paris, 1962.
- Miah, S., *The reign of al Mutawakkil*, Dacca, 1969.
- Miles, G. C., 'Some new light on the history of Kirman in the first century of the Hijrah', in J. Kritzeck and R. B. Winder (eds.), *The world of Islam: Studies in honour of Philip K. Hitti*, London, 1960, 85–98.
- Minorsky, V., *Studies on Caucasian history*, London, 1953.
- Morony, Michael G., 'Continuity and change in the administrative geography of late Sasanian and early Islamic al 'Iraq', *Iran*, 20 (1982), 1–49.
- 'The effects of the Muslim conquest on the Persian population of Iraq', *Iran*, 14 (1976), 41–59.
- Iraq after the Muslim conquest*, Princeton, 1984.
- Moscatti, S., 'La rivolta di 'Abd al Gabbar contro il califfo al Manṣur', *Rendiconti della Reale Accademia dei Lincei*, 8 (1947), 613–15.
- 'Studi su Abu Muslim', *Rendiconti della Reale Accademia dei Lincei*, 8 (1949–50), 323–35, 474–95, 8/5, 89–105.
- Mottahedeh, Roy, 'Bureaucracy and the patrimonial state in early Islamic Iran and Iraq', *al Abḥath*, 29 (1981), 25–36.
- Loyalty and leadership in an early Islamic society*, Princeton, 1980.
- 'The Shu'ubiyya controversy and the social history of early Islamic Iran', *IJMES*, 7(1976), 161–82.
- 'The transmission of learning: The role of the Islamic northeast', in N. Grandin and M. Gaborieau (eds.), *Madrasa: La transmission du savoir dans le monde musulman*, Paris, 1997, 63–72.
- Nafisi, Sa'īd, *Tarikh i khandan e ṭahirī*, Tehran, 1956.
- Nagel, Tilman, *Untersuchungen zur Entstehung des Abbasidischen Kalifates*, Bonn, 1972.
- Nicol, N. D., 'Early 'Abbasid administration in the central and eastern provinces, AH 132–218/AD 750–833', Ph.D. thesis, University of Washington, 1979.
- Nöldeke, T., *Geschichte der Perser und Araber zur Zeit der Sasaniden*, Leiden, 1878.
- Sketches from eastern history*, trans. J. S. Black, London, 1892; repr. Beirut, 1963.
- Noth, Albrecht, 'Iṣfahan Nihawand: Eine quellenkritische Studie zur frühislamischen Historiographie', *ZDMG*, 118 (1968), 274–96.
- Omar, Farouq, *The Abbasid caliphate*, Baghdad, 1969.
- 'The nature of the Iranian revolts in the early Islamic period', *Islamic Culture*, 48 (1974), 1–9.
- Petrushevskii, I. P., *Islam in Iran*, trans. H. Evans, Albany, 1985.
- Pourshariati, Parvaneh, *Decline and fall of the Sasanian empire*, London, forthcoming.

- 'Iranian tradition in Ṭus and the Arab presence in Khurasan', Ph.D. thesis, Columbia University, 1995.
- 'Khurasan and the crisis of legitimacy: A comparative historiographical approach', in N. Yavari *et al.* (eds.), *Views from the edge: Essays in honor of Richard W. Bulliet*, New York, 2004, 208–29.
- 'Local histories of Khurasan and the pattern of Arab settlement', *Studia Iranica*, 27 (1998), 41–81.
- 'Local historiography in medieval Iran and the Tarikh Bayhaq', *Journal of Iranian Studies*, 33 (2000), 133–64.
- al Qaḍi, Wadad, 'The development of the term *ghulat* in Muslim literature with special reference to the Kaysaniyya', in A. Dietrich (ed.), *Akten des VII. Kongresses für Arabistik und Islamwissenschaft*, Göttingen, 1976, 295–319.
- Rekaya, Mohamed, 'Le Hurrām Dīn et les mouvements Hurramites sous les 'Abbasides', *SI*, 60 (1984), 5–57.
- 'Mazyar: Résistance ou intégration d'une province iranienne au monde musulman au milieu du IX^e siècle ap. JC', *Studia Iranica*, 2 (1973), 143–92.
- 'Mise au point sur Théophobe et l'alliance de Bābek avec Théophile (833/34–839/40)', *Byzantion*, 44 (1974), 43–67.
- 'La place des provinces sud caspiennes dans l'histoire de l'Iran de la conquête arabe à l'avènement des Zaydites (16–250 H/637–864 JC): Particularism régional ou rôle "national"?', *RSO*, 48 (1974), 117–52.
- Richter Bernburg, L., 'Iran's contribution to medicine and veterinary science in Islam AH 100–900/AD 700–1500', in J. Greppin *et al.* (eds.), *The diffusion of Greco Roman medicine into the Middle East and the Caucasus*, Delmar, 1999, 139–67.
- 'Linguistic Shu'ubiya and early Neo Persian prose', *JAOS*, 94 (1974), 55–64.
- Robinson, Chase F., 'The conquest of Khuzistan: A historiographic reassessment', *BSOAS*, 67 (2004), 14–39.
- Empire and elites after the Muslim conquest: The transformation of northern Mesopotamia*, Cambridge Studies in Islamic Civilization, Cambridge, 2000.
- Sadighi, G. H., *Les mouvements religieux iraniens*, Paris, 1938.
- Scarcia, G., 'Lo scambio di lettere fra Harun al Rašīd e Hamza al Ḥarīḡi secondo il "Ta'riḡ i Sistan"', *Annali dell'Istituto Universitario Orientale di Napoli*, n.s. 14 (1964), 623–45.
- Shaban, M. A., *The 'Abbasid revolution*, Cambridge, 1970.
- Islamic history: A new interpretation*, 2 vols., Cambridge, 1971–6.
- Shahbazi, A. S., 'On the X^waday namaḡ', *Acta Iranica*, 30 (1990), 208–29.
- Sharon, Moshe, *Black banners from the east*, Jerusalem, 1983.
- Revolt: The social and military aspects of the 'Abbasid revolution*, Jerusalem, 1990.
- Sims Williams, N., *Bactrian documents from northern Afghanistan*, vol. I: *Legal and economic documents*, Oxford, 2000.
- Skladanek, B., 'External policy and interdynastic relations under the Saffarids', *Rocznik Orientalistyczny*, 36 (1974), 133–50.
- 'The Kharijites in Iran', *Rocznik Orientalistyczny*, 44/1 (1985), 65–92, 44/2 (1985), 89–101.
- 'Khujistani's uprising in Khurasan (860–869): The anatomy of an unsuccessful rebellion', *Rocznik Orientalistyczny*, 46 (1989), 63–77.
- 'Settlements in Gharchistan during the early Islamic period', *Rocznik Orientalistyczny*, 34 (1971), 57–71.

- Sourdel, D., 'Les circonstances de la mort de Ṭahir Ier au Ḥurasan en 207/828', *Arabica*, 5 (1958), 66–9.
- Le vizirat Abbaside de 749 à 936*, Damascus 1959.
- Stern, S. M., 'The early missionaries in north west Persia and in Khurasan and Transoxania', *BSOAS*, 23 (1960), 56–90.
- Studies in early Isma'ilism*, Jerusalem, 1983.
- 'Ya'qub the Coppersmith and Persian national sentiment', in C. E. Bosworth (ed.), *Iran and Islam*, Edinburgh, 1970, 535–55.
- Sundermann, W., 'Mazdak und die mazdakitischen Volksaufstände', *Altertum*, 23 (1977), 245–49.
- Treadwell, W. L., 'Ibn Zafir al Azdi's account of the murder of Aḥmad b. Isma'īl al Samanī and the succession of his son Naṣr', in Carol Hillenbrand (ed.), *Studies in honour of Clifford Edmund Bosworth*, vol. II, Leiden, 2000, 397–419.
- 'The political history of the Samanid state', D.Phil. thesis, Oxford, 1991.
- Tucker, William F., 'Abd Allah b. Mu'awiya and the Janahiyya: Rebels and ideologues of the late Umayyad period', *SI*, 51 (1980), 39–57.
- 'Abu Maṣṣur al 'Ijlī and the Maṣṣuriyya: A study in medieval terrorism', *Der Islam*, 54 (1977), 66–76.
- 'Bayan ibn Sam'an and the Bayaniyya: Shi'ite extremists of Umayyad Iraq', *MW*, 65 (1975), 241–53.
- 'Rebels and gnostics: al Mugīra Ibn Sa'id and the Mugiriyya', *Arabica*, 22 (1975), 33–47.
- van Vloten, G., *De Opkomst der Abbasiden in Chorasān*, Leiden, 1890.
- Recherches sur la domination arabe*, Amsterdam, 1894.
- Watt, M., *The formative period of Islamic thought*, Edinburgh, 1973.
- Wellhausen, Julius, *Das arabische Reich und sein Sturz*, Berlin, 1902, trans. M. G. Weir as *The Arab kingdom and its fall*, Calcutta, 1927.
- Die religiös politischen Oppositionsparteien im alten Islam*, Berlin, 1901, trans. R. C. Ostle as *The religio political factions in early Islam*, Amsterdam, 1975.
- Wright, E. M., 'Babak of Badkhih and al Afshin', *MW*, 38 (1948), 43–59, 124–131.
- Yakubovskii, A. Y., 'Vosstanie Mukanny', *Sovetskoe Vostokovedenie*, 5 (1948), 35–54.
- Zakeri, Mohsen, *Sasanid soldiers in early Muslim society: The origins of 'Ayyaran and Futuwwa*, Wiesbaden, 1995.
- Zaman, M. Q., *Religion and politics under the early 'Abbasids*, Leiden 1997.
- Zarrinkub, 'Abd al Ḥusayn, *Du qarn sukut*, Tehran, 1965.

Chapter 12: Syria

Practical suggestions for further reading

- Cameron, A. (ed.), *The Byzantine and early Islamic Near East*, vol. III: *States, resources, and armies*, Princeton, 1995.
- Cameron, A., and G. R. D. King (eds.), *The Byzantine and early Islamic Near East*, vol. II: *Land use and settlement patterns*, Princeton, 1994.
- Canivet, P., and J. P. Rey Coquais (eds.), *La Syrie de Byzance à l'Islam, VIIe–VIIIe siècles: Actes du colloque international, 11–15 septembre 1990*, Damascus, 1992.
- Cobb, Paul M., *White banners: Contention in Abbasid Syria, 750–880*, Albany, 2001.

Bibliography

- Donner, Fred M., *The early Islamic conquests*, Princeton, 1981.
- Gil, Moshe, *A history of Palestine, 634–1099*, trans. Ethel Broido, Cambridge, 1992.
- Grabar, Oleg, *The shape of the holy: Early Islamic Jerusalem*, Princeton, 1996.
- Hawting, G. R., *The first dynasty of Islam: The Umayyad caliphate AD 661–750*, London and Sydney, 1986.
- Hoyland, Robert G., *Seeing Islam as others saw it: A survey and evaluation of Christian, Jewish, and Zoroastrian writings on early Islam*, Princeton, 1997.
- Humphreys, R. Stephen, *Mu'awiya ibn Abi Sufyan: From Arabia to empire*, Oxford, 2006.
- Kennedy, Hugh, *The Byzantine and early Islamic Near East*, Aldershot, 2006.
- Le Strange, Guy, *Palestine under the Moslems*, London, 1890.
- Robinson, C. F., *ʿAbd al Malik*, Oxford, 2005.
- Sack, Dorothee, *Damaskus: Entwicklung und Struktur einer orientalisches islamischen Stadt*, Mainz, 1989.
- Sauvaget, Jean, *Alep: Essai sur le développement d'une grande ville syrienne des origines au milieu du XIXe siècle*, 2 vols., Paris, 1941.
- Wellhausen, Julius, *Das arabische Reich und sein Sturz*, Berlin, 1902; trans. M. G. Weir as *The Arab kingdom and its fall*, Calcutta, 1927.
- Wirth, Eugen, *Syrien: Eine geographische Landeskunde*, Darmstadt, 1971.

Primary sources

- Abu Yusuf, *Kitab al kharaj*, Bulaq, 1302/1184 5; trans. E. Fagnan as *Livre de l'impôt foncier*, Algiers, 1921.
- Abu Zur'a al Dimashqi, Ta'rikh, ed. S. A. al Qujani, 2 vols., Damascus, 1980.
- Agapius of Manbij (Maḥbub ibn Qusṭantīn), *Kitab al 'unvan, histoire universelle*, ed. and trans. A. A. Vasiliev, part 2/2, *Patrologia Orientalis* 8 (Paris, 1912), 399–547.
- Artsruni, Thomas, *History of the house of the Artsrunik*, trans. R. W. Thomson, Detroit, 1985.
- al Azdi, Yazid ibn Muḥammad, *Ta'rikh Mawṣil*, ed. ʿAlī Ḥabība, Cairo, 1967.
- al Azdi al Baṣrī, *Ta'rikh futuḥ al Sham*, ed. W. Nassau Lees, Calcutta, 1854.
- al ʿAzīmī, Muḥammad ibn ʿAlī, *Ta'rikh Ḥalab*, ed. Ibrāhīm Zaʿrūr, Damascus, 1984.
- al Baladhuri, Aḥmad ibn Yahya, *Ansab al ashraf*, vol. III, ed. A. A. al Duri, Wiesbaden and Beirut, 1978; vol. IV/1 2, ed. Iḥṣān ʿAbbas, Wiesbaden and Beirut, 1979 (see also Levi della Vida and Pinto, (trans.), *Il Califfo Mu'awiya*).
- Futuḥ al buldan*, ed. M. J. de Goeje, Leiden, 1866; trans. Philip Hitti and Francis Murgotten as *The origins of the Islamic state*, 2 vols., New York, 1916–24.
- Chronica minora (Maronite chronicle, Anon. chronicles of 724, 813, 846)*, ed. I. Guidi, E. W. Brooks and J. B. Chabot, CSCO 1 6, Paris, 1903 5 (texts), 1903 7 (translations).
- Chronicle of Zuqnin* (=pseudo Dionysius of Tell Mahré), ed. J. B. Chabot as *Incerti auctoris chronicon anonymum pseudo Dionysianum dictum II*, CSCO 104, Paris, 1933; parts 3 and 4 trans. Amir Harrak, Toronto, 1999; part 4 trans. Robert Hespel, CSCO 507, Louvain, 1989.
- Chronicon anonymum ad annum Christi 1234 pertinens*, ed. and trans. J. B. Chabot, CSCO 81 2, 109, Paris, 1916, 1920, 1937; trans. A. Abouna, CSCO 354, Louvain, 1974.
- Elisséeff, Nikita, *La description de Damas d'Ibn ʿAsakir*, Damascus, 1959.
- al Harawī, Abu al Ḥasan ʿAlī, *Kitab al ziyarat*, ed. Janine Sourdél Thomine, Damascus, 1953; trans. Janine Sourdél Thomine as *Guide des lieux de pèlerinage*, Damascus, 1957.

- Histoire nestorienne: Chronique de Séert*, ed. and trans. Addai Scher, *Patrologia Orientalis* 4, 7, 13, Paris, 1907, 1911, 1919.
- History of the patriarchs of the Coptic Church of Alexandria*, ed. and trans. B. Evetts, *Patrologia Orientalis* 1, 5, 10, Paris, 1904, 1910, 1915.
- Ibn al 'Adīm, Kamāl al Dīn 'Umar, *Bughyat al ṭalab fi ta'rīkh Ḥalab*, ed. Suhayl Zakkar, 11 vols., Damascus, 1988.
- Zubdat al ḥalab min ta'rīkh Ḥalab*, ed. Samī al Dahhan, vol. I, Damascus, 1951.
- Ibn 'Asakir, *Ta'rīkh madīnat Dimashq*, ed. 'Alī Shūrī, 70 vols., Beirut, 1995 8 (see also Elisséeff, *La description*).
- Ibn al Athīr, 'Izz al Dīn 'Alī, *al Kamil fi ta'rīkh*, ed. C. J. Tornberg, rev. Iḥsan 'Abbas, 13 vols., Beirut, 1965 7.
- Ibn al Faqīh al Hamadhānī, *Kitab al Buldan*, ed. M. J. de Goeje, BGA 5, Leiden, 1885.
- Ibn Ḥawqal, *Kitab ṣurat al arḍ*, ed. M. J. de Goeje, rev. J. H. Kramers, BGA 2, Leiden, 1938; trans. J. H. Kramers and Gaston Wiet as *Configuration de la terre*, 2 vols., Paris, 1964.
- Ibn Khallikan, Shams al Dīn Aḥmad, *Wafayat al a'yan wa 'anba' abna' al zaman*, ed. Iḥsan 'Abbas, 8 vols., Beirut, 1972.
- Ibn Manẓūr, Muḥammad ibn Mukarram, *Mukhtaṣar ta'rīkh Dimashq li Ibn 'Asakir*, ed. R. A. H. Murad et al., 31 vols., Damascus, 1984 96.
- Ibn Shaddad, 'Izz al Dīn, *al A'laq al khaṭira fi dhikr umara' al sham wa l jazira*: (a) *Ta'rīkh Ḥalab*, ed. D. Sourdel, Beirut 1953; (b) *Ta'rīkh Dimashq*, ed. Samī al Dahhan, Damascus, 1956; (c) *Ta'rīkh Lubnan wa l Urdunn wa Filastīn*, ed. Samī al Dahhan, Damascus, 1963; (d) *Ta'rīkh al Jazīra*, ed. Yaḥya 'Abbara, 2 vols., Damascus, 1977 8; (e) 'Description de la Syrie du Nord', ed. and trans. Anne Marie Eddé, Damascus, 1984; *Bulletin d'Études Orientales*, 32 3 (1980 1), 265 402 (Arabic text).
- Ibn al Shīḥna, Muḥibb al Dīn, *al Durr al muntakhab fi ta'rīkh Ḥalab*, ed. Keiko Ohta, Tokyo, 1990; trans. Jean Sauvaget as *Les perles choisies d'Ibn al Chihna*, Beirut, 1933.
- al Iṣṭakhri, Abu Ishāq Ibrāhīm, *Kitab al masalik wa l mamalik*, ed. M. J. de Goeje, BGA 1, Leiden, 1870.
- al Jahshiyārī, Muḥammad ibn 'Abdus, *Kitab al wuzara' wa al kuttab*, ed. Muṣṭafa al Ṣaqqā', Cairo, 1938.
- Khalīfa ibn Khayyāt al 'Uṣfurī, *Kitab al ta'rīkh*, ed. Akram Ḍiyya' al 'Umārī, 2 vols., Najaf, 1967.
- Levi della Vida, G., and Olga Pinto (trans.), *Il Califfo Mu'awiya i secondo il Kitab Ansab al Asraf di Aḥmad ibn Yaḥya al Baladhuri*, Rome, 1938.
- Lewond (Ghevond), *History of Lewond the eminent Vardapet of the Armenians*, trans. Z. Arzoumanian, Wynnwood, PA, 1982.
- al Mas'ūdī, *Kitab al tanbih wa al ishraf*, ed. M. J. de Goeje, BGA 8, Leiden, 1894; trans. B. Carra de Vaux as *Livre de l'avertissement et de la révision*, Paris, 1896.
- Muruj al dhab wa ma'adin al jawhar*, 7 vols., Beirut, 1965 79; ed. and trans. Charles Pellat as *Les prairies d'or*, 5 vols., Paris, 1965 74.
- Michael the Syrian, *Chronique de Michel le Syrien, patriarche jacobite d'Antioche (1166 1199)*, ed. and trans. J. B. Chabot, 4 vols., Paris, 1899 1924.
- Mingana, Alphonse, (ed. and trans.), 'The apology of Timothy the Patriarch before the caliph Mahdi', *Woodbrooke Studies*, 2 (Cambridge, 1928), 1 162.
- al Muqaddasī, Muḥammad ibn Aḥmad, *Aḥsan al taqasim fi ma'rifat al aqalim*, ed. M. J. de Goeje, BGA 3, Leiden, 1906; trans. B. A. Collins as *The best divisions for knowledge of the*

- regions, Reading, 1994; partial trans. André Miquel as *La meilleure répartition pour la connaissance des provinces*, Damascus, 1963.
- Nau, François, 'Un colloque du patriarche Jean avec l'emir des Agaréens et faits divers des années 712 and 716 d'après le ms. du British Museum 17193', *JA*, 11, 5 (1915), 225–79.
- al Nu'aymī, 'Abd al Qadir, *al Daris fi ta'rikh al madaris*, ed. Ja'far al Ḥassanī, 2 vols., Damascus, 1948–51 (see also Sauvaire, *Description de Damas*).
- Palmer, Andrew, S. Brock and R. Hoyland, *The seventh century in the West Syrian chronicles*, Liverpool, 1993.
- Reinink, G. J. (ed. and trans.), *Die syrische Apokalypse des Pseudo Methodius*, CSCO 540–1 (syr. 220–1), Louvain, 1983.
- al Ṣafadī, Khaliḥ ibn Ayybak, *Tuḥfat dhawī al albab fi man ḥakama bi Dimashq min al khulafā' wa l muluk wa l nuwwab*, ed. Ihsan Khuluṣī and Zuhayr al Ṣamṣam, 2 vols., Damascus, 1991–2.
- Sauvaire, Henri, *Description de Damas*, 2 vols., Paris, 1895–6; originally published in *JA*, 3–7 (1879–87).
- Sebeos, *The Armenian history attributed to Sebeos*, trans. R. W. Thomson, with commentary by J. Howard Johnson, 2 vols., Translated Texts for Historians 31, Liverpool, 1999.
- al Shabushṭī, 'Alī ibn Muḥammad, *Kitab al Diyarat*, ed. Girgis 'Awwad, Baghdad, 1951.
- al Ṭabarī, Abu Ja'far Muḥammad ibn Jarīr, *Ta'rikh al rusul wa'l muluk*, ed. M. J. de Goeje et al., 15 vols. in 3 series, Leiden, 1879–1901; trans. as *The history of al Tabari*, gen. ed. Ehsan Yarshater, 39 vols., Albany, 1985–99.
- Theophanes, *The chronicle of Theophanes Confessor*, trans. C. Mango and R. Scott, Oxford, 1997.
- Wilkinson, John, (ed. and trans.), *Jerusalem pilgrims before the Crusades*, Warminster, 2002.
- Wood, D., 'The 60 martyrs of Gaza and the martyrdom of Bishop Sophronius of Jerusalem', *Aram*, 15 (2003), 129–50.
- al Ya'qubī, Aḥmad ibn Abī Ya'qub, *Kitab al buldan*, ed. M. J. de Goeje, BGA 7, Leiden, 1892; trans. Gaston Wiet as *Les pays*, Cairo, 1937.
- Yaqut al Rumī, *Mu'jam al buldan*, ed. F. Wüstenfeld with Latin trans. as *Jacut's Geographisches Wörterbuch*, 6 vols., Leipzig, 1866–73; ed. Anon., 5 vols., Beirut, 1955–7.

Secondary sources

- 'Abbas, Ihsan, *Ta'rikh bilad al sham fi al 'aṣr al 'abbasī*, 132–255 H/750–870 M, Amman, 1993.
- Abbott, Nabia, 'Arabic papyri of the reign of Ga'far al Mutawakkil 'ala llah (AH 232–47/AD 847–61)', *ZDMG*, 92 (1938), 88–135.
- Abiad, Malake, *Culture et education arabo islamiques au Sam pendant les trois premiers siècles de l'Islam, d'après Ta'rikh madīnat Dimasq d'Ibn 'Asakir (499/1105–571/1176)*, Damascus, 1981.
- 'Athamina, Khalil, 'Arab settlement during the Umayyad caliphate', *JSAI*, 8 (1986), 185–207.
- al Bakhit, M. A., and I. Abbas (eds.), *Proceedings of the Second Symposium on the History of Bilad al Sham during the Early Islamic Period up to 40 AH/660 AD*, Amman, 1987.
- al Bakhit, M. A., and R. Schick (eds.), *Bilad al Sham during the Abbasid period: Proceedings of the Fifth International Congress on the History of Bilad al Sham*, Amman, 1992.
- Fourth International Congress on the History of Bilad al Sham during the Umayyad Period*, Amman, 1989.

- Bates, Michael, 'History, geography and numismatics in the first century of Islamic coinage', *Revue Suisse de Numismatique*, 65 (1986), 231–61.
- Bianquis, Thierry, 'Sayf al Dawla', *EL*, vol. IX, 103–10.
- Blankinship, Khalid Y., *The end of the jihad state: The reign of Hisham ibn 'Abd al Malik and the collapse of the Umayyads*, Albany, 1994.
- Bonner, Michel, *Aristocratic violence and holy war: Studies in the jihad and the Arab Byzantine frontier*, New Haven, 1996.
- Brock, S. P., 'North Mesopotamia in the late seventh century: Book xv of John Bar Penkaye's *Riṣ Melle'*', *JSAI*, 9 (1987), 51–75.
- Brown, Peter, *Society and the holy in Late Antiquity*, Berkeley and Los Angeles, 1979.
- Bulliet, Richard, *Conversion to Islam in the medieval period: An essay in quantitative history*, Cambridge, MA, 1979.
- Cahen, Claude, 'Fiscalité, propriété, antagonismes sociaux en Haute Mésopotamie au temps des premiers 'Abbasides, d'après Denys de Tell Mahré', *Arabica*, 1 (1954), 136–52.
- 'Le problème préjudiciel de l'adaptation entre les autochtones et l'Islam', in Claude Cahen, *Les peuples musulmans dans l'histoire médiévale*, Paris, 1977, 169–88.
- Cameron, A., and L. I. Conrad (eds.), *The Byzantine and early Islamic Near East*, vol. I: *Problems in the literary source material*, Princeton, 1995.
- Canard, Marius, *Histoire de la dynastie des H'amdaniides de Djazira et de Syrie*, Algiers, 1951.
- Sayf al dawla, recueil de texts*, Algiers, 1934.
- Cobb, Paul M., 'al Mutawakkil's Damascus: A new 'Abbasid capital?', *JNES*, 5 (1999), 241–57.
- Conrad, Gerhard, *Die Quḍāt Dimasq und der madhab al Auza'ri: Materialien zur syrischen Rechtsgeschichte*, Beirut and Stuttgart, 1994.
- Crone, Patricia, *Slaves on horses: The evolution of the early Islamic polity*, Cambridge, 1980.
- 'Were the Qays and Yemen of the Umayyad period political parties?', *Der Islam*, 71 (1994), 1–57.
- Crone, Patricia, and Martin Hinds, *God's caliph: Religious authority in the first centuries of Islam*, Cambridge, 1986.
- Dagron, Gilbert (ed.), *Travaux et mémoires*, 11, Paris, 1991.
- Dennett, Daniel C., *Conversion and the poll tax in early Islam*, Cambridge, MA, 1950.
- Déroches, Vincent, 'Polémique anti judaïque et émergence de l'Islam (7e–8e siècles)', *Revue des études byzantines*, 57 (1999), 141–61.
- Dussaud, René, *Topographie historique de la Syrie antique et médiévale*, Paris, 1927.
- Elad, Amikam, 'Aspects of the transition from the Umayyad to the 'Abbasid caliphate', *JSAI*, 19 (1995), 89–132.
- Medieval Jerusalem and Islamic worship*, Leiden, 1995.
- Fattal, Antoine, *Le statut légal des non musulmans en pays d'Islam*, Beirut, 1958.
- Foss, Clive, 'The coinage of the first century of Islam', *Journal of Roman Archaeology*, 16 (2003), 748–60.
- 'A Syrian coinage of Mu'awiya?', *Revue numismatique*, 158 (2002), 353–67.
- Fowden, Elizabeth, *The barbarian plain: Saint Sergius between Rome and Iran*, Transformation of the Classical Heritage 28, Berkeley, 1999.
- Fowden, Garth, *Qusayr 'Amra: Art and the Umayyad elite in Late Antique Syria*, Berkeley, 2004.
- Gènequand, Denis, 'The early Islamic settlement in the Syrian steppe: A new look at Umayyad and medieval Qasr al Hayr al Sharqi (Syria)', *al 'Usur al Wusta*, 17 (2005), 21–7.

- Gervers, M., and Ramzi Bikhazi (eds.), *Conversion and continuity: Indigenous Christian communities in Islamic lands, eighth to eighteenth centuries*, Toronto, 1990.
- Grabar, Oleg, *The formation of Islamic art*, New Haven, 1973; 2nd rev. edn 1987.
- Grabar, Oleg, R. Holod, J. Knustad and W. Trousedale, *City in the desert: Qasr al Hayr East*, 2 vols., Cambridge, MA, 1978.
- Griffith, S. H., *Arabic Christianity in the monasteries of ninth century Palestine*, Aldershot, 1992.
- ‘From Aramaic to Arabic: The languages of the monasteries of Palestine in the Byzantine and early Islamic periods’, *Dumbarton Oaks Papers*, 52 (1997), 12–31.
- Hage, W., *Die syrisch jakobitische Kirche in frühislamischer Zeit*, Wiesbaden, 1966.
- Haldon, John F., *Byzantium in the seventh century: The transformation of a culture*, Cambridge, 1990.
- Hoyland, Robert, ‘New documentary texts and the early Islamic state’, *BSOAS*, 69, 3 (2006), 395–416.
- Ḥusayn, Falih, *al Ḥayat al zira‘iyya fi bilād al sham fi al ‘aṣr al umawī*, Amman, 1978.
- Johns, Jeremy, ‘Archaeology and the history of early Islam: The first seventy years’, *JESHO*, 46 (2003), 411–36.
- (ed.), *Bayt al Maqdis: Jerusalem and early Islam*, Oxford Studies in Islamic Art 9, part 2, Oxford, 1999.
- Johns, Jeremy, and J. Raby (eds.), *Bayt al Maqdis: ‘Abd al Malik’s Jerusalem*, Oxford Studies in Islamic Art 9, part 1, Oxford, 1992.
- Kaegi, Walter E., *Byzantium and the early Islamic conquests*, Cambridge, 1992.
- Kennedy, Hugh, *The early Abbasid caliphate: A political history*, London and Sydney, 1981.
- The Prophet and the age of the caliphate*, London and New York, 1986; 2nd rev. edn 2004.
- King, G. R. D., ‘Islam, iconoclasm, and the declaration of doctrine’, *BSOAS*, 48 (1985), 267–77.
- Kraemer, Caspar J., *Excavations at Nessana*, vol. III: *Non literary papyri*, Princeton, 1958.
- Kurd ‘Alī, Muḥammad, *Khīṭaṭ al sham*, 6 vols., Damascus, 1925.
- Lammens, Henri, *Le califat de Yazid Ier*, Beirut, 1921.
- La Syrie: Précis historique*, 2 vols., Beirut, 1921.
- Le Strange, Guy, *Lands of the eastern caliphate*, Cambridge, 1905.
- Liebeschuetz, J. H. G., *The decline and fall of the Roman city*, Oxford, 2001.
- Lindsay, J. E. (ed.), *Ibn ‘Asakir and early Islamic history*, Princeton, 2001.
- Madelung, Wilferd, ‘Fatimiden und Bahrainqarmaten’, *Der Islam*, 34 (1959), 34–88.
- ‘The Sufyani between tradition and history’, *SI*, 63 (1984), 5–48.
- Magness, Jodi, *The archaeology of the early Islamic settlement in Palestine*, Winona Lake, IN, 2003.
- Moscatti, Sabatino, ‘Le massacre des Umayyades dans l’histoire at dans les fragments poétiques’, *Archiv Orientalni*, 18 (1950), 88–115.
- Répertoire chronologique d’épigraphie arabe*, 17 vols., in progress, Cairo, 1931.
- Robinson, C. F., *Empire and elites after the Muslim conquest: The transformation of northern Mesopotamia*, Cambridge Studies in Islamic Civilization, Cambridge, 2000.
- ‘Neck sealing in early Islam’, *JESHO*, 48 (2005), 401–41.
- Rotter, Gerhard, *Die Umayyaden und der zweite Bürgerkrieg*, Wiesbaden, 1982.
- Salibi, Kamal S., *Syria under Islam: Empire on trial*, 634–1097, Delmar, NY, 1977.
- Sauvaget, Jean, ‘Esquisse d’une histoire de la ville de Damas’, *REI*, 8 (1934), 421–80.
- Schick, Robert, *The Christian communities of Palestine from Byzantine to Islamic rule: A historical and archaeological study*, Studies in Late Antiquity and Early Islam 2, Princeton, 1995.

- Sourdel, Dominique, 'La Syrie au temps des premiers califes abbassides (132/750–264/878)', *REI*, 48 (1980), 155–75.
- Sourdel, D., and J. Sourdel Thomine, 'Nouveaux documents sur l'histoire religieuse et sociale de Damas au moyen âge', *REI*, 32 (1964), 1–25.
- 'Trois actes de vente damascains du début du IV^e/Xe siècle', *JESHO*, 8 (1965), 164–85.
- Tate, Georges, *Les campagnes de la Syrie du Nord, du II^e au VII^e siècle: Un exemple d'expansion démographique et économique à la fin de l'Antiquité*, Paris, 1992.
- Travaux et mémoires*: see Dagron, Gilbert.
- Von Sievers, Peter, 'Military, merchants and nomads: The social evolution of the Syrian cities and countryside during the classical period, 780–969/164–358', *Der Islam*, 56 (1979), 212–44.
- Wellhausen, Julius, 'Arab wars with the Byzantines in the Umayyad period', in M. Bonner (ed.), *Arab Byzantine relations in early Islamic times*, Burlington, VT, 2005, 31–64.
- Wickham, Chris, *Framing the early Middle Ages: Europe and the Mediterranean, 400–800*, Oxford, 2005.
- Witakowski, W., *The Syriac chronicle of Pseudo Dionysius of Tell Mahré: A study in the history of historiography*, Uppsala, 1987.
- Wulzinger, K., and C. Watzinger, *Damaskus: Die islamische Stadt*, Berlin and Leipzig, 1924.
- Yusuf, Muhsin D., *Economic survey of Syria during the tenth and eleventh centuries*, Berlin, 1985.

Chapter 13: Egypt

Practical suggestions for further reading

- Brett, M., 'Abbasids, Fatimids and Seljuqs', in David Luscombe and Jonathan Riley Smith (eds.), *The new Cambridge medieval history*, vol. IV, Cambridge, 2004, 675–720.
- The rise of the Fatimids: The world of the Mediterranean and the Middle East in the fourth century of the hijra, tenth century CE*, Leiden, 2001.
- Goitein, S. D., *A Mediterranean society: The Jewish communities of the Arab world as portrayed in the documents of the Cairo Geniza*, 5 vols., Berkeley and Los Angeles, 1967–88, vol. I: *The economic foundations*.
- Kennedy, H., *The Prophet and the age of the caliphates*, London and New York, 1986.
- Lane Poole, S., *A history of Egypt in the Middle Ages*, 4th edn, London, 1925.
- The story of Cairo*, London, 1902.
- Petry C. F. (ed.), *The Cambridge history of Egypt*, vol. I: *Islamic Egypt, 640–1517*, Cambridge, 1998.
- Raymond, A., *Le Caire*, Paris, 1993.
- Sanders, P., *Ritual, politics and the city in Fatimid Cairo*, Albany, 1994.

Primary sources

- (Abu Ṣāliḥ the Armenian), *Churches and monasteries of Egypt*, ed. and trans. B. T. A. Evetts, Oxford, 1895.
- Grohmann, A. (ed. and trans.), *Arabic papyri in the Egyptian Library*, 6 vols., Cairo, 1934–62.
- Ibn 'Abd al Ḥakam, *Kitab futuḥ Miṣr wa 'l Maghrib*, ed. C. C. Torrey, New Haven, 1922.
- Ibn Ḥawqal, *Ṣurat al arḍ*, ed. J. H. Kramers, 2 vols., Leiden, 1938–9; trans. G. Wiet as *Configuration de la terre*, 2 vols., Beirut and Paris, 1964.

- Ibn Muyassar, *Choix de passages de la Chronique d'Égypte d'Ibn Muyassar*, ed. A. F. Sayyid, Cairo, 1981.
- Ibn al Ṣayrafi, *al Ishara ila man nala al wizara*, ed. A. Mukhlis, *Bulletin de l'Institut Français d'Archéologie Orientale du Caire*, 26 (1924).
- John of Nikiou, *Chronique de Jean, Evêque de Nikiou*, ed. and trans. A. Zotenberg, Paris, 1883; trans. R. M. Charles as *The chronicle of John, bishop of Nikiu*, Oxford, 1916.
- Karabacek, J., *Papyrus Erzherzog Rainer: Führer durch die Ausstellung*, Vienna, 1892.
- al Kindi, *Governors and judges of Egypt*, ed. R. Guest, Leiden and London, 1912.
- al Maqrīzī, *Itti'az al ḥunafa'*, ed. J. D. al Shayyāl and M. H. M. Aḥmad, 3 vols., Cairo, 1967–73.
- Kitab al mawa'iz wa 'l i'tibar fi dhikr al khitat wa 'l athar (al Khitat)*, ed. G. Wiet (4 vols. only), Cairo, 1911; full text, Bulaq, 1853–4; autograph, ed. A. F. Sayyid, London, 1995.
- al Muqaffa*, ed. M. Yalaoui, Beirut, 1991.
- al Muqaddasi, *Aḥsan al taqasim fi ma'rifat al aqalm*, Damascus, 1980.
- Sa'id ibn Batrīk [Eutychius], *Eutychii Patriarchae Alexandrini Annales*, ed. L. Cheikho, CSCO, Scriptores Arabici, 3rd series, vols. VI, VII, Beirut, Paris and Leipzig, 1906, 1909.
- (Severus ibn al Muqaffa'), *History of the patriarchs of the Coptic Church of Alexandria/the Egyptian Church*, ed. and trans. B. T. A. Evetts, Y. 'Abd al Masih, O. H. E. Burmester and A. Khater, 3 vols., Paris, 1901; Cairo, 1943–59, 1968–70.
- Yahya al Anṭaki, *Ta'rikh*, ed. L. Cheikho, CSCO, Scriptores Arabici, 3rd series, vol. VII, Beirut, Paris and Leipzig, 1909; and J. Forsyth, *The Byzantine Arab chronicle (938–1034) of Yahya b. Sa'id al Anṭaki*, Ann Arbor, 1977.

Secondary sources

- Ashtor, E., 'Migrations de l'Irak vers les pays méditerranéens', in E. Ashtor, *The medieval Near East: Social and economic history*, Variorum Series, London, 1978, IV.
- Bianquis, T., 'al H'âkim bi amr Allâh ou la folie de l'unité chez un souverain fât'imide', in C. A. Julien et al. (eds.), *Les Africains*, vol. XI, Paris, 1978, 105–33.
- Brett, M., 'The Arab conquest and the rise of Islam in North Africa', in J. D. Fage and Roland Oliver (eds.), *The Cambridge history of Africa*, 8 vols., Cambridge, 1978, vol. II: *From c. 500 BC to AD 1050*, 490–555.
- 'The execution of al Yazurī', in U. Vermeulen and D. De Smet (eds.), *Egypt and Syria in the Fatimid, Ayyubid and Mamluk Eras*, vol. II, Leuven, 1998, 15–27.
- 'al Karaza al Marqusiya: The Coptic Church in the Fatimid empire', in U. Vermeulen and J. Van Steenbergen (eds.), *Egypt and Syria in the Fatimid, Ayyubid and Mamluk eras*, vol. IV, Leuven, 2005, 33–60.
- 'The origins of the Mamluk military system in the Fatimid period', in U. Vermeulen and D. De Smet (eds.), *Egypt and Syria in the Fatimid, Ayyubid and Mamluk Periods*, vol. I, Leuven, 1995, 39–52.
- 'Population and conversion to Islam in the mediaeval period', in U. Vermeulen and J. Van Steenbergen (eds.), *Egypt and Syria in the Fatimid, Ayyubid and Mamluk eras*, vol. IV, Leuven, 2005, 1–32.
- 'The way of the peasant', *BSOAS*, 47 (1984), 44–56.
- Brunschvig, R., 'Ibn 'Abd al ḥakam et la conquête de l'Afrique du Nord par les Arabes', in R. Brunschvig, *Études sur l'Islam classique et l'Afrique du Nord*, ed. A. M. Turki, Variorum Reprints, London, 1986, XI.

- Butler, A. J., *The Arab conquest of Egypt and the last thirty years of the Roman dominion*, 2nd edn, with critical bibliography by P. M. Fraser, Oxford, 1978.
- Canard, M., 'al Ḥakim bi Amrī'llah', *EL*, vol. III, 76–82.
- Chaudhuri, K. N., *Trade and civilisation in the Indian Ocean*, Cambridge, 1985.
- Cortese, D., and S. Calderini, *Women and the Fatimids in the world of Islam*, Edinburgh, 2006.
- Crone, P., and M. Cook, *Hagarism: The making of the Islamic world*, Cambridge, 1977.
- Daftary, F., *The Isma'ilis: Their history and doctrines*, Cambridge, 1990.
- Décobert, C., 'Sur l'arabisation et l'islamisation de l'Égypte médiévale', in C. Décobert (ed.), *Itinéraires de l'Égypte: Mélanges offerts au père Maurice Martin*, SJ, Cairo, 1992, 273–300.
- Dennett, D. C., *Conversion and the poll tax in early Islam*, Cambridge, MA, 1950.
- Forsyth, J., *The Byzantine Arab chronicle (938–1034) of Yahya b. Sa'ud al Anṭakī*, Ann Arbor, 1977.
- Geertz, C., *Islam observed: Religious development in Morocco and Indonesia*, Chicago and London, 1968.
- Gellens, S. I., 'Egypt, Islamization of', in A. S. Atiya (gen. ed.), *The Coptic encyclopedia*, New York, 1991, vol. II, 609–11.
- Goodchild, R. G., 'Byzantines, Berbers and Arabs in seventh century Libya', *Antiquity*, 51 (1967), 115–24; repr. in R. G. Goodchild, *Libyan studies: Selected papers of the late R. G. Goodchild*, ed. J. Reynolds and Paul Elek, London, 1976, 255–67.
- Halm, H., *The empire of the Mahdī*, trans. M. Bonner, Leiden, 1996.
- Die Kalifen von Kairo: Die Fatimiden in Ägypten 973–1074, Munich, 2003.
- Ḥasan, Y. F., *The Arabs and the Sudan*, Edinburgh, 1967.
- Hurst, H. E., *The Nile*, London, 1952.
- Issawi, C., 'The area and population of the Arab empire', in A. Udovitch (ed.), *The Islamic Middle East, 700–1900*, Princeton, 1981, 375–96.
- Egypt: An economic and social analysis*, London, New York and Toronto, 1948.
- Johns, J., *Arabic administration in Norman Sicily: The royal diwan*, Cambridge, 2002.
- Kaegi, W. E., 'Egypt on the eve of the Muslim conquest', in C. F. Petry (ed.), *The Cambridge history of Egypt*, vol. I: *Islamic Egypt, 640–1517*, Cambridge, 1998, 34–61.
- Kennedy, H., 'Egypt as a province of the Islamic caliphate, 641–868', in C. F. Petry (ed.), *The Cambridge history of Egypt*, vol. I: *Islamic Egypt, 640–1517*, Cambridge, 1998, 62–85.
- Kubiak, W., *al Fustat: Its foundation and early urban development*, Cairo, 1987.
- Lapidus, I. M., 'The conversion of Egypt to Islam', *Israel Oriental Studies*, 2 (1972), 248–62.
- Lev, Y., 'The Fatimid navy, Byzantium and the Mediterranean sea, 909–1036 CE', *Byzantion*, 54 (1984), 220–52.
- State and society in Fatimid Egypt*, Leiden, 1991.
- 'Tinnis: An industrial medieval town', in M. Barrucand (ed.), *L'Égypte fatimide: Son art et son histoire*, Paris, 1999, 83–96.
- Lombard, M., *The golden age of Islam*, Amsterdam, Oxford and New York, 1975.
- Martin, M., 'La province d'Ashmunayn', *Annales Islamologiques*, 23 (1987), 1–29.
- Miquel, A., 'L'Égypte vue par un géographe arabe du IVe/Xe siècle: al Muqaddasi', *Annales Islamologiques*, 11 (1972), 109–39.
- Morimoto, K., *The fiscal administration of Egypt in the early Islamic period*, Kyoto, 1981.
- Rabie, H. H., 'Technical aspects of agriculture in medieval Egypt', in A. Udovitch (ed.), *The Islamic Middle East, 700–1900*, Princeton, 1981, 75–80.

- Sanders, P., 'The Faṭimid state, 969–1171', in C. F. Petry (ed.), *The Cambridge history of Egypt*, vol. I: *Islamic Egypt, 640–1517*, Cambridge, 1998, 151–74.
- Sato, T., 'Irrigation in rural Egypt from the 12th to the 14th centuries', *Orient*, 8 (1972), 81–92.
- Shaban, M. A., *Islamic history: A new interpretation*, 2 vols., Cambridge, 1971–6; vol. I: AD 600–750 (AH 132), Cambridge, 1971.
- Shinnie, P. L., 'Christian Nubia', in J. D. Fage and Roland Oliver (eds.), *The Cambridge history of Africa*, 8 vols., Cambridge, 1978, vol. II: *From c. 500 BC to AD 1050*, 556–88.
- Sijpesteijn, P. M., and L. Sundelin (eds.), *Papyrology and the history of early Islamic Egypt*, Leiden, 2004.
- Turner, B. S., *Weber and Islam*, London, 1974.
- Walters, C. C., *Monastic archaeology in Egypt*, Warminster, 1974.
- Wilfong, T., 'The non Muslim communities: Christian communities', in C. F. Petry (ed.), *The Cambridge history of Egypt*, vol. I: *Islamic Egypt, 640–1517*, Cambridge, 1998, 175–97.

Chapter 14: The Iberian Peninsula and North Africa

Practical suggestions for further reading

- Abun Nasr, J. M., *A history of the Maghrib in the Islamic period*, Cambridge, 1987.
- Brett, M., and E. Fentress, *The Berbers*, Oxford, 1996.
- Fierro, M. I., 'Abd al Rahman III: The first Cordoban caliph', Oxford, 2005.
- Fierro, M. I., and J. Samsó (eds.), *The formation of al Andalus*, vol. II: *Language, religion, culture and the sciences*, Aldershot and Brookfield, VT, 1998.
- Guichard, P., *From the Arab conquest to the Reconquest: The splendour and fragility of al Andalus*, Granada, 2006.
- Jayyusi, S. K. (ed.), *The legacy of Muslim Spain*, Leiden, 1992.
- Julien, C. A., *History of North Africa from the Arab conquest to 1830*, London, 1970.
- Kennedy, H., *Muslim Spain and Portugal: A political history of al Andalus*, London, 1996.
- Laroui, 'A. A., *The history of the Magrib: An interpretative essay*, Princeton, 1977.
- Lévi Provençal, E., *Historia de la España Musulmana (711–1031)*, vol IV: *Historia de España dirigida por R. Menéndez Pidal*, Madrid, 1950.
- Historia de la España Musulmana: Instituciones y vida social e intelectual*, vol V: *Historia de España dirigida por R. Menéndez Pidal*, Madrid, 1957.
- Marçais, G., *La berbérie musulmane et l'Orient au moyen âge*, Paris, 1946.
- Marín, M. (ed.), *The formation of al Andalus*, vol. I: *History and society*, Aldershot, 1998.
- Norris, H. T., *The Berbers in Arabic literature*, London, 1982.
- Sénac, P., *al Mansur: Le fléau de l'an mil*, Paris, 2006.
- Terrasse, M., *Islam et Occident méditerranéen: De la conquête aux ottomans*, Paris, 2001.
- Torres Balbas, L., *Ciudades hispanomusulmanas*, Madrid, 1972.
- Vallejo, A., *Madīnat al Zahra': Guía oficial del yacimiento arqueológico*, Seville, 2004.
- Vernet, J., *Lo que Europa debe al Islam de España*, Barcelona, 1999.
- Viguera, M. J., and C. Castillo (coords), *El Esplendor de los Omeyyas Cordobeses: La civilización Musulmana de Europa Occidental*, Granada, 2001.

Primary sources

- ‘Abd al Malik ibn Ḥabīb, *Kitab al ta’rīkh*, ed. J. Aguadé, Madrid, 1991.
- Abu l ‘Arab al Tamīmī, *Classes des savants de l’Ifriqiya*, trans. Muhammad ben Cheneb, Algiers, 1920.
- Akhbar majmu‘a*, ed. and trans. E. Lafuente Alcántara, Madrid, 1867.
- ‘Alī ibn ‘Isa al Ṭulayṭulī, *Muṭjaṣṣar (Compendio)*, ed. and trans. M. J. Cervera, Madrid, 2000.
- al Bakrī, *Kitab al masalik*, ed. M. J. de Goeje, Leiden, 1889; ed and trans. M. de Slane as *Description de l’Afrique Septentrionale*, rev. edn, Paris, 1965.
- Corpus Scriptorum Muzarabiorum*, 2 vols., ed. I. Gil, Madrid, 1973.
- Crónica Mozárabe de 754*, ed. J. E. López Pereira, Saragossa, 1980.
- Crónica del Moro Rasis*, ed. D. Catalán and M. S. de Andrés, Madrid, 1974.
- Fath al Andalus*, ed. L. Molina, Madrid, 1994; trans. M. Penellas as *La conquista de al Andalus*, Madrid, 2002.
- al Ḥimyan, *Kitab al Rawḍ al Mi‘ṭar fi khabar al aqṭar*, ed. I. ‘Abbas, Beirut, 1975; trans. E. Lévi Provençal as *La peninsule ibérique au moyen âge d’après le Kitab al Rawḍ al Mi‘ṭar*, Leiden, 1938.
- Ibn ‘Abd al Ḥakam, *Futuḥ Miṣr wa l Magrib wa l Andalus*, ed. C. C. Torrey, New Haven, 1922.
- Ibn al Athīr, *al Kamil fi l ta’rīkh*, ed. J. C. Tornberg, Beirut, 1979; partial trans. E. Fagnan as *Annals du Maghreb et de l’Espagne*, Argel, 1898.
- Ibn al ‘Aṭṭar, *Kitab al watha’iq wa l sijillat*, ed. P. Chalmeta, Madrid, 1983, trans. P. Chalmeta and M. Marugán as *Formulario notarial y judicial andalusí*, Madrid, 2000.
- Ibn Ḥawqal, *Kitab ṣurat al arḍ*, ed. M. J. de Goeje, rev. J. H. Kramers, BGA 2, Leiden, 1938.
- Ibn Ḥayyan, *al Muqtabis V*, ed. P. Chalmeta, F. Corriente and M. Sobh, Madrid, 1979; trans. M. J. Viguera and F. Corriente as *Crónica del califa ‘Abdarrāḥman III an Naṣir entre los años 912 y 942*, Saragossa, 1981.
- al Muqtabis fi aḥbar bilad al Andalus (al Ḥakam II)*, ed. A. A. Hajji, Beirut, 1965; trans. E. García Gómez as *El Califato de Córdoba en el Muqtabis de Ibn Ḥayyan*, *Anales Palatinos del Califa de Córdoba al Ḥakam II*, Madrid, 1967.
- al Muqtabis min anba’ ahl al Andalus*, ed. M. A. Makki, Cairo, 1971.
- al Muqtabis fi ta’rīkh rijal al Andalus*, ed. M. Antuña, Paris, 1937.
- al Siṣr al thanī min Kitab al Muqtabis*, ed. M. A. Makki, Riyadh, 2003; trans. M. A. Makki and F. Corriente as *Crónica de los emires Alḥakam i y ‘Abdarrāḥman I entre los años 796 y 847*, Saragossa, 2001.
- Ibn Ḥazm, *Jamharat ansab al ‘arab*, ed. A. S. M. Harun, Beirut, 1982.
- Ibn ‘Idharī, *Kitab al Bayan al Muḡrib*, vols. I II, ed. G. S. Colin and E. Lévi Provençal, Leiden, 1948 51; vol. III, ed. E. Lévi Provençal, Paris, 1930, trans. E. Fagnan as *Histoire de l’Afrique et de l’Espagne intitulée al bayano l Muḡrib*, Algiers, 1901 4 and F. Maíllo as *La Caída del Califato de Córdoba y los Reyes de Taifas*, Salamanca, 1993.
- Ibn Khaldun, *Ta’rīkh ‘alamat Ibn Khaldun. Kitab al ‘Ibar*, ed. Y. A. Dagir, vol. I, *Muqaddima*, Beirut, 1956; trans. F. Rosenthal as *The Muqaddimah: An introduction to history*, repr. London 1987; trans. M. de Slane as *Histoire des Berbères et des dynasties musulmanes de l’Afrique Septentrionale*, Paris, 1925.
- Ibn al Qutīya, *Ta’rīkh iftitāḥ al Andalus*, ed. P. de Gayangos, E. Saavedra and F. Codera, Madrid, 1868.

Bibliography

- Ibn Ṣaḡir, 'La chronique d'Ibn Saghīr sur les imams rustumides de Tahert', ed. and trans. A. C. Motylinski in *Actes du XI^e Congrès International des Orientalistes*, Algiers, 1905.
- Ibn Sa'īd, *al Muḡrib fi hula al Maḡrib*, ed. Sawqī Dayf, Cairo, 1953.
- Ibn Sallam, *Kitab Ibn Sallam*, ed. W. Schwartz and Salim ibn Ya'qub, Wiesbaden, 1986.
- 'Iyaḍ, *Tartīb al madarik wa taqrīb al masalik li ma'rifat a'lam madhhab Malik*, various eds., Rabat, 1980 7.
- al Khushani, *Akhbar al fuqaha' wa l muḥaddithin*, ed. L. Molina and M. L. Avila, Madrid, 1992.
- Kitab al qudat bi Qurṭuba*, ed. and trans. J. Ribera as *Historia de los Jueces de Córdoba por Aljoxani*, Madrid, 1914.
- al Maqqari, *Nafḥ al ṭib min ḡuṣn al Andalus al raṭīb*, ed. I. 'Abbas, 8 vols., Beirut, 1968.
- al Qaḍī al Nu'man, *Ifṭitah al da'wa wa ibtida' al dawla*, ed. F. Dachraoui, Tunis, 1975.
- al Raḡiq, 'L'Occident musulman à l'avènement des Abbassides d'après le chroniqueur ziride al Raḡiq', trans. H. R. Idris, *REI*, 39 (1971), 209 91.
- al 'Udhri, *Tarṣī' al akhbar wa tanwī' al athar wa l bustan fi gara'ib al buldan*, ed. A. al Ahwani, Madrid, 1965.
- Una Crónica Anónima de 'Abd al Raḥman al Naṣir*, ed. and trans. E. Lévi Provençal and E. García Gómez, Madrid and Granada, 1950.
- al Ya'qubi, *Kitab al buldan*, ed. and trans. G. Marçais as *Description du Maghreb*, Argel, 1962.

Secondary sources

- Ación, M., *Entre el feudalismo y el Islam: 'Umar ibn Ḥaṣṣun en los historiadores, en las fuentes y en la historia*, 2nd edn, Jaén, 1997.
- 'Poblamiento indígena en al Andalus e indicios del primer poblamiento andalusí', *al Qantara*, 20 (1999), 47 64.
- 'Sobre el papel de la ideología en la caracterización de las formaciones sociales: La formación social islámica', *Hispania*, 200 (1998), 915 68.
- Akerraz, A., 'Note sur l'enceinte tardive de Volubilis', *Bulletin Archéologique du Comité des Travaux Historiques*, 19 (1985), 429 36.
- Balaguer, A., *Las emisiones transicionales árabe musulmanas de Hispania*, Barcelona, 1976.
- Barceló, M., *El sol que salió por Occidente: Estudios sobre el estado Omeya en al Andalus*, Jaén, 1997.
- Bazzana, A., P. Cressier and P. Guichard, *Les châteaux ruraux d'al Andalus: Histoire et archéologie des ḥuṣn du sud est de l'Espagne*, Madrid, 1988.
- Benco, N. L. (ed.), *Anatomy of a medieval Islamic town: al Basra, Morocco*, BAR Series 1234, Oxford, 2004.
- Berque, J., 'Qu'est ce qu'une tribu nord africaine', *Éventail de l'Histoire Vivante: Hommage à Lucien Febvre*, 2 vols., Paris, 1953, vol. I, 261 71.
- Blachère, R., 'Fes chez les géographes arabes du moyen âge', *Hespéris*, 20 (1934), 90 113.
- Brett, M., 'The Arab conquests and the rise of Islam in North Africa', in J. D. Fage and Roland Oliver (eds.), *The Cambridge history of Africa*, 8 vols., Cambridge, 1978, vol. II: *From c. 500 BC to AD 1050*, 490 555.
- 'Ibn Khaldun and the Arabisation of North Africa', *Maghreb Review*, 4 (1979), 9 16.
- The rise of the Fatimids: The world of the Mediterranean and the Middle East in the fourth century of the hijra, tenth century CE*, Leiden, 2001.

- Brunschvig, R., 'Ibn 'Abdalhakam et la conquête de l'Afrique du Nord par les Arabes', *Annales de l'Institut d'Etudes Orientales Université d'Alger*, 6 (1942-7), 108-55.
- Caballero, L., and P. Mateos, *Visigodos y Omeyas: Un debate entre la Antigüedad y la Alta Edad Media, Anejos de Archivo Español de Arqueología*, XXIII, Mérida, 2000.
- Caballero, L., P. Mateos and M. Retuerce (eds.), *Cerámicas tardorromanas y altomedievales en la Península Ibérica*, Madrid, 2003.
- Camps, G., 'De Masuna à Koceila: Les destinées de la Maurétanie aux VI^e et VII^e siècles', *Bulletin Archéologique du Comité des Travaux Historiques et Scientifiques*, 19 (1985), 307-24.
- Canto, A., 'De la ceca de al Andalus a la de Madinat al Zahra', *Cuadernos de Madinat al Zahra*, 3 (1991), III-31.
- Canto, A., and T. Ibrahim, *Moneda Andalusí: La colección de la Casa de la Moneda*, Madrid, 2004.
- Chalmeta, P., *Invasión e islamización: La sumisión de Hispania y la formación de al Andalus*, Madrid, 1994.
- 'Monnaie de compte, monnaie fiscale et monnaie réelle en al Andalus', in Y. Raguib (ed.), *Documents de l'Islam médiéval: Nouvelles perspectives de recherche*, Cairo, 1991, 65-88.
- Corriente, F., *Diccionario de arabismos y voces afines en iberorromance*, Madrid, 1999.
- Cressier, P., and M. García Arenal (eds.), *Genèse de la ville islamique en al Andalus et au Maghreb occidental*, Madrid, 1998.
- Cressier, P., M. I. Fierro and J. P. Van Staëvel (eds.), *L'urbanisme dans l'Occident musulman au moyen âge: Aspects juridiques*, Madrid, 2000.
- Cuoq, J., *L'église d'Afrique du Nord du II^e au XII^e siècle*, Paris, 1984.
- Dachraoui, F., *Le califat fatimide au Maghreb*, Tunis, 1981.
- Djaït, H., 'La Wilaya d'Ifrīqiya au II^e/VIII^e siècle: Étude institutionnelle', *SI*, 27 (1967), 77-121.
- Doménech Belda, C., *Dinares, dirhams y feluses: Circulación monetaria islámica en el País Valenciano*, Alicante, 2003.
- Estudios Onomásticos y Biográficos de al Andalus*, 14 vols., Madrid, 1988-2004.
- Eustache, D., *Corpus de dirhams idrisites et contemporaines*, Rabat, 1970-1.
- de Felipe, H., *Identidad y onomástica de los bereberes de al Andalus*, Madrid, 1997.
- Fentress, E., 'The house of the Prophet: North African Islamic housing', *Archeologia Medievale*, 14 (1987), 47-68.
- Fierro, M. I., *La heterodoxia en al Andalus durante el período omeya*, Madrid, 1987.
- Freund, W. H. C., 'The end of Byzantine North Africa: Some evidence of transitions', *Bulletin Archéologique du Comité des Travaux Historiques et Scientifiques*, 19, 2 (1985), 387-97.
- García Arenal, M., *Messianism and puritanical reform: Mahdis of the Muslim west*, Leiden, 2006.
- García Arenal, M., and E. Manzano, 'Idrissisme et villes idrissides', *SI*, 82 (1995), 5-33.
- García Sanjuán, A., *Till God inherits the earth: Islamic pious endowments in al Andalus*, Leiden, 2007.
- Gelichi, S., and M. Milanese, 'The transformation of the ancient towns in central Tunisia during the Islamic period: The example of Uchi Maius', *al Masaq: Islam and the medieval Mediterranean*, 14 (2002), 33-45.
- Gil, J., 'Judíos y cristianos en Hispania (siglos VIII y IX)', *Hispania Sacra*, 31 (1978-9), 9-80.
- Guichard, P., *al Andalus: Estructura antropológica de una sociedad islámica en Occidente*, Barcelona, 1976; repr. Granada, 1998.

- Gutiérrez, S., *La cora de Tudmir de la Antigüedad tardía al mundo islámico: Poblamiento y cultura material*, Madrid and Alicante, 1996.
- Halm, H., *The empire of the Mahdi: The rise of the Fatimids*, trans. Michael Bonner, Leiden, 1996.
- Hirschberg, H. Z., *A history of the Jews in North Africa*, Leiden, 1974.
- Idris, H. R., 'Contribution à l'histoire de l'Ifrīqiya: Tableau de la vie intellectuelle et administrative à Kairouan sous les Aglabites et les Fatimites (4 premiers siècles de l'Hégire) d'après le *Riyad En Nufus* de Abu Bakr al Maliki', *Revue d'Études Islamiques, Cahiers* (1935), 105–77.
- Lévi Provençal, E., 'La fondation de Fès', *Annales de l'Institut d'Études Orientales*, 4 (Algiers, 1938), 23–53.
- 'Un nouveau récit de la conquête de l'Afrique du nord par les Arabes', *Arabica*, 1 (1954), 17–43.
- Lewicki, T., 'The Ibadi community at Basra in the seventh to ninth centuries and the origins of the Ibadite states in Arabia and North Africa', *Journal of World History*, 13 (1971), 51–130.
- 'Prophètes, devins et magiciens chez les Berbers médiévaux', *Folia Orientalia*, 7 (1965), 3–27.
- Lirola Delgado, J., and J. M. Puerta Vilchez (eds.), *Biblioteca de al Andalus*, vol. III: *De Ibn al Dabbag a Ibn Kurz*; vol IV: *De Ibn al Labbana a Ibn al Ruyuh*, Almería, 2004.
- Madelung, W., 'Some notes on non Isma'īlī Shiism in the Maghrib', *SI*, 44 (1976), 87–97.
- Makki, M. A., 'Egipto y los orígenes de la historiografía árabe española', *Revista del Instituto Egipcio de Estudios Islámicos*, 5 (1957), 157–248.
- Malpica, A., 'Arqueología de los paisajes medievales granadinos: Medio físico y territorio en la costa de Granada', *Arqueología y Territorio Medieval*, 2 (1995), 25–62.
- Manzano Moreno, E., *Conquistadores, emires y califas: Los Omeyas y la formación de al Andalus*, Barcelona, 2006.
- La frontera de al Andalus en época de los Omeyas*, Madrid, 1991.
- Marín, M., 'Altos funcionarios para el Califa: Jueces y otros cargos de la administración de 'Abd al Raḥmān III', *Cuadernos de Madīnat al Zahra'*, 5 (2004), 91–105.
- Mujeres en al Andalus*, Madrid, 2000.
- 'Ṣaḥāba et tabi'un dans al Andalus: Histoire et légende', *SI*, 54 (1981), 5–49.
- Martínez, M. A., 'Epígrafes a nombre de al Ḥakam en Madīnat al Zahra'', *Cuadernos de Madīnat al Zahra'*, 4 (1999), 83–103.
- Mattingly, D., 'Explanations: People as agency', in G. Barker (ed.), *Farming the desert: The UNESCO Libyan valleys archaeological survey*, Tripoli and London, 1996, 319–42.
- Méouak, M., *Pouvoir souverain, administration centrale et élites politiques dans l'Espagne umayyade (Ile IVe/VIIIe Xe siècles)*, Helsinki, 1999.
- Muranyi, M., *Beiträge zur Geschichte der Ḥadīth und Rechtsgelehrsamkeit der Malikiyya in Nordafrika bis zum 5. Jh. DH*, Wiesbaden, 1997.
- Ocaña Jiménez, M., 'Inscripciones árabes fundacionales de la mezquita catedral de Córdoba', *Cuadernos de Madīnat al Zahra'*, 2 (1988–1990), 9–28.
- Picard, C., *Le Portugal musulman (VIIIe–XIIIe siècle): L'occident d'al Andalus sous domination islamique*, Paris, 2000.
- Ramírez del Río, J., *La orientalización de al Andalus: Los días de los árabes en la Península Ibérica*, Seville, 2002.

- Savage, E., *A gateway to hell, a gateway to paradise: The North African response to the Arab conquest*, Princeton, 1997.
- Scales, P., *The fall of the caliphate of Cordoba: Berbers and Andalus in conflict*, Leiden, 1994.
- Schwartz, W., *Die Anfänge der Ibaditen in Nordafrika: Der Beitrag einer islamischen Minderheit zur Ausbreitung des Islams*, Wiesbaden, 1983.
- Sénac, P., *La frontière et les hommes (VIIIe–XIIe siècle): Le peuplement musulman au nord de l'Èbre et les débuts de la reconquête aragonaise*, Paris, 2000.
- Siraj, A., *L'image de la Tingitane: L'historiographie arabe médiévale et l'antiquité nord africaine*, Rome, 1995.
- Talbi, M., 'Le Christianisme maghrébine de la conquête musulmane à sa disparition: Une tentative d'explication', in M. Gervers and R. J. Bikazi (eds.), *Conversion and continuity: Indigenous Christian communities in Islamic lands, eight to eighteenth centuries*, Toronto, 1990, 313–51.
- L'émirat aghlabide (184–296/800–909): Histoire politique*, Paris, 1966.
- Études d'histoire ifrîqiyenne et de la civilisation musulmane médiévale*, Tunis, 1982.
- Vallejo, A., 'El proyecto urbanístico del estado califal: *Madīnat al Zahra'*', in R. López Guzmán (coord.), *La Arquitectura del Islam Occidental*, Madrid, 1995, 69–82.
- Vallvé, J., *La división territorial de la España Musulmana*, Madrid, 1986.
- Viguera, M. J., *Aragón Musulmán*, 2nd edn, Saragossa, 1988.
- Wansbrough, J., 'On recomposing the Islamic history of North Africa', *JRAS* (1969), 161–70.
- Wilkinson, J. C., 'The Ibaḥī imama', *BSOAS*, 39, 3 (1976), 535–51.
- Wolf, K. B., *Christian martyrs in Muslim Spain*, Cambridge, 1988.
- Zerouki, B., *L'imamat de Tahart: Premier état Musulman du Maghreb (144–296 de l'hégire)*, Paris, 1987.

Chapter 15: Modern approaches to early Islamic history

Practical suggestions for further reading

- Daniel, Norman, *Islam and the West: The making of an image*, Edinburgh, 1960; 2nd edn Oxford, 1993.
- Donner, Fred M., *Narratives of Islamic origins: The beginnings of Islamic historical writing*, Princeton, 1998, introduction.
- Goddard, Hugh, *A history of Muslim Christian relations*, Edinburgh and Chicago, 2000.
- Lockman, Zachary, *Contending visions of the Middle East: The history and politics of Orientalism*, Cambridge, 2004.
- Said, Edward W., *Orientalism*, New York, 1978.
- Southern, R. W., *Western views of Islam in the Middle Ages*, Cambridge, MA, 1962.
- Tibawi, A. L., 'English speaking Orientalists: A critique of their approach to Islam and Arab nationalism', *MW*, 53 (1963), 185–204, 298–313.
- 'On the Orientalists again', *MW*, 70 (1980), 56–61.
- 'Second critique of English speaking Orientalists and their approach to Islam and the Arabs', *Islamic Quarterly*, 23 (1979), 3–54.
- Tolan, John Victor, *Saracens: Islam in the medieval European imagination*, New York, 2002.
- Waardenburg, Jacques, *Islam: Historical, social, and political perspectives*, Religion and Reason 40, Berlin and New York, 2002.

Bibliography

- Islam and Christianity: Mutual perceptions since the mid twentieth century*, Leuven, 1998.
Watt, William Montgomery, *Muslim Christian encounters: Perceptions and misperceptions*, London and New York, 1991.

Primary sources

- Abu l Fida', Isma'il ibn 'Alī, *Mukhtaṣar ta'rīkh al bashar*, trans. J. Reiske as *Annales Moslemici*, Leipzig, 1754.
al Baladhuri, Aḥmad ibn Yaḥya ibn Jabir, *Futuh al buldan*, ed. M. J. de Goeje, Leiden, 1866.
Ibn Sa'd, Muḥammad, *al Ṭabaqat al kabir*, ed. E. Sachau et al., 9 vols., Leiden, 1917–40.
al Ṣan'ani, 'Abd al Razzaq ibn Hammam, *al Muṣannaf*, ed. Ḥabīb al Raḥman al A'zamī, 11 vols., n.p. and Beirut, 1970–2.
al Ṭabari, Abu Ja'far Muḥammad ibn Jarīr, *Kitab al rusul wa l muluk*, ed. M. J. de Goeje et al., 15 vols. in 3 series, Leiden, 1879–1901; English translation: *The history of al Ṭabari*, 39 vols., Albany, 1985–99.

Secondary sources

- Agha, Saleh Said, and 'arif Khalidi, 'Poetry and identity in the Umayyad age', *al Abhath*, 50 1 (2002 3), 55–120.
Andrae, Tor, 'Die Legenden von der Berufung Muḥammads', *Le monde oriental*, 6 (1912), 5–18.
Die Person Muhammads in Lehre und Glauben seiner Gemeinde, Stockholm, 1918.
Becker, Carl Heinrich, 'The expansion of the Saracens', in H. M. Gwatkin et al. (eds.), *The Cambridge medieval history*, vol. II, Cambridge, 1913, chs. 11 and 12.
Bell, Richard, *The origin of Islam in its Christian environment*, London, 1926.
Bennett, Clinton, *Victorian images of Islam*, London, 1992.
Borrut, Antoine, 'Entre mémoire et pouvoir: L'espace syrien sous les derniers omeyyades et les premiers abbassides (v. 72–193/692–809)', Ph.D. thesis, Université de Paris I, 2007.
Bousquet, Georges Henri, 'Observations sur la nature et les causes de la conquête arabe', *SI*, 6 (1956), 37–52.
Brown, Peter, *The world of Late Antiquity, AD 150–750*, London, 1971.
Bulliet, Richard, 'Orientalism and medieval Islamic studies', in John Van Engen (ed.), *The past and future of medieval studies*, Notre Dame, 1994, 94–104.
Burgmer, Christoph (ed.), *Streit um den Koran: Die Luxenberg Debatte: Standpunkte und Hintergründe*, n.p., 2004.
Caetani, Leone, *Studi di storia orientale*, 3 vols., Milan, 1911–14.
Cahen, Claude, *La Syrie du Nord à l'époque des croisades et la principauté d'Antioche*, Paris, 1940.
Calder, Norman, *Studies in early Muslim jurisprudence*, Oxford, 1993.
Cameron, Averil, and Lawrence I. Conrad (eds.), *The Byzantine and early Islamic Near East*, vol. I: *Problems in the literary source material*, Studies in Late Antiquity and Early Islam 1, Princeton, 1993.
Carlyle, Thomas, *On heroes, hero worship, and the heroic in history*, London, 1841.
Casanova, Paul, *Mahomet et la fin du monde*, 3 vols., Paris, 1911–24.
Chabbi, Jacqueline, *Le seigneur des tribus: L'Islam de Mahomet*, Paris, 1997.

- Conrad, Lawrence I., 'The conquest of Arwad: A source critical study in the historiography of the medieval Near East', in A. Cameron and L. I. Conrad (eds.), *The Byzantine and early Islamic Near East*, vol. I: *Problems in the literary source material*, Studies in Late Antiquity and Early Islam 1, Princeton, 1993, 317–401.
- Cook, David, *Studies in Muslim apocalyptic*, Princeton, 2002.
- Cook, Michael, 'An early Islamic apocalyptic chronicle', *JNES*, 52 (1993), 25–9.
- Crone, Patricia, *Meccan trade and the rise of Islam*, Princeton, 1987; repr. Piscataway, NJ, 2004.
- Slaves on horses: The evolution of the Islamic polity*, Cambridge, 1980.
- Crone, Patricia, and Michael Cook, *Hagarism: The making of the Islamic world*, Cambridge, 1977.
- Déscription de l'Égypte: Ou, recueil des observations et des recherches qui ont été faites en Égypte pendant l'expédition de l'armée française/publié par les ordres de Sa Majesté l'empereur Napoléon le Grand*, 23 vols., Paris, 1809–29.
- Donner, Fred M., 'Centralized authority and military autonomy in the early Islamic conquests', in A. Cameron (ed.), *The Byzantine and early Islamic Near East*, vol. III: *States, resources, and armies*, Studies in Late Antiquity and Early Islam 1, Princeton, 1995, 337–60.
- 'From believers to Muslims: Confessional self identity in the early Islamic community', *al Abhath*, 50 1 (2002 3), 9–53.
- 'Modern nationalism and medieval Islamic history', *al 'Usur al Wusta*, 13 (2001), 21–2.
- Narratives of Islamic origins: The beginnings of Islamic historical writing*, Princeton, 1998.
- 'Orientalists and the rise of Islam', in Sami A. Khasawnih (ed.), *Conference on Orientalism: Dialogue of Cultures*, 22–24 October 2002, Amman, 2004, 57–84.
- 'Piety and eschatology in early Kharijite poetry', in Ibrahim As Sa'afin (ed.), *Fī miḥrab al ma'rifa: Festschrift for Iḥsan 'Abbas*, Beirut, 1997, 13–19 (English section).
- 'The Qur'an in recent scholarship: Challenges and desiderata', in Gabriel Said Reynolds (ed.), *Towards a new reading of the Qur'an*, Abingdon, 2008, 29–50.
- Dunlop, D. M., 'Some remarks on Weil's history of the caliphs', in Bernard Lewis and P. M. Holt (eds.), *Historians of the Middle East*, London, 1962, 315–29.
- El Hibri, Tayeb, *Reinterpreting Islamic historiography: Harun al Rashid and the narrative of the 'Abbasid caliphate*, Cambridge, 1999.
- Fowden, Garth, *Empire to commonwealth: Consequences of monotheism in Antiquity*, Princeton, 1993.
- Fück, J. W., 'Islam as an historical problem in European historiography since 1800', in B. Lewis and P. M. Holt (eds.), *Historians of the Middle East*, London, 1962, 303–14.
- Geiger, Abraham, *Was hat Mohamed aus dem Judenthume aufgenommen*, Berlin, 1833.
- Gibbon, Edward, *The history of the decline and fall of the Roman empire*, 6 vols., London, 1776–88.
- de Goeje, Michael Jan, *Mémoire sur la conquête de la Syrie*, Mémoires d'histoire et de géographie orientales 2, 1st edn, Leiden, 1864.
- Goldziher, Ignaz, *Muhammedanische Studien*, 2 vols., Halle, 1889–90; trans. S. M. Stern and C. R. Barber as *Muslim studies*, 2 vols., London, 1967–71.
- Vorlesungen über den Islam*, Heidelberg, 1910; trans. Andras and Ruth Hamori as *Introduction to Islamic theology and law*, Princeton, 1981.
- Grimme, Hubert, *Mohamed*, 2 vols., Münster, 1892–5.

- von Grunebaum, Gustave, 'The first expansion of Islam: Factors of thrust and containment', *Diogenes*, 54 (1966), 64–72.
- Hawting, Gerald R., *The first dynasty of Islam: The Umayyad caliphate, AD 661–750*, Beckenham and Carbondale, 1987.
- The idea of idolatry and the emergence of Islam: From polemic to history*, Cambridge, 1999.
- 'The rise of Islam', in Youssef M. Choueiri (ed.), *A companion to the history of the Middle East*, Oxford, 2005, 9–27.
- d'Herbelot, Barthélemy, *Bibliothèque orientale*, Paris, 1697.
- Hitti, Philip, *The Arabs in history*, London, 1937.
- Hourani, Albert H., *Islam in European thought*, Cambridge, 1991.
- Huntington, Samuel P., *The clash of civilizations and the remaking of the world order*, New York, 1996.
- Hurgronje, C. Snouck, *selected works*, ed. in French and English by G. H. Bousquet and J. Schacht, Leiden, 1957.
- 'Ibn Warraq' [pseud.] (ed.), *The quest for the historical Muhammad*, Amherst, NY, 2000.
- Juynboll, Gautier, *Muslim tradition*, Cambridge, 1983.
- Kister, M. J., "'A booth like the booth of Moses...': A study of an early *ḥadīth*", *BSOAS*, 25 (1962), 150–5.
- Studies in jahiliyya and early Islam*, London, 1980.
- Klier, Klaus, *Halid und 'Umar: Quellenkritische Untersuchung zur Historiographie der frühislamischen Zeit*, Berlin, 1998.
- Koren, Judith, and Yehuda Nevo, 'Methodological approaches to Islamic studies', *Der Islam*, 68 (1991), 87–107.
- Lammens, Henri, *Fatima et les filles de Mahomet: Notes critiques pour l'étude de la Sira*, Rome, 1912.
- 'La république marchande de la Mecque vers l'an 600 de notre ère', *Bulletin de l'Institut Égyptien*, 5, 4 (1910), 23–54.
- Landau Tasseron, Ella, 'Sayf ibn 'Umar in medieval and modern scholarship', *Der Islam*, 67 (1990), 1–26.
- Lane, Edward W., *An account of the manners and customs of the modern Egyptians*, London, 1836.
- Lassner, Jacob, *Islamic revolution and historical memory: An inquiry into the art of 'Abbasid apologetics*, AOS Series 66, New Haven, 1986.
- Lecker, Michael, *The 'Constitution of Medina': Muḥammad's first legal document*, Princeton, 2004.
- Leder, Stefan, *Das Korpus al-Haitam ibn 'Adī (st. 207/822): Herkunft, Überlieferung, Gestalt früher Texte der aḥbar Literatur*, Frankfurt, 1991.
- Lester, Toby, 'What is the Koran?', *The Atlantic Monthly* (January 1999), 43–56.
- Lewis, Bernard, *The Arabs in history*, London, 1958.
- 'The roots of Muslim rage', *The Atlantic Monthly* (September 1990), 47–60.
- Lewis, Bernard, and Peter M. Holt (eds.), *Historians of the Middle East*, London, 1962.
- Lüling, Günter, *Über den Ur-Qur'an: Ansätze zur Rekonstruktion vorislamischer christlicher Strophenglieder im Qur'an*, Erlangen, 1974.
- Luxenberg, Christoph [pseud.], *Die syro-aramäische Lesart des Koran: Ein Beitrag zur Entschlüsselung der Koransprache*, Berlin, 2000.

- Madelung, Wilferd, 'Apocalyptic prophecies in Ḥimṣ in the Umayyad age', *JSS*, 31 (1986), 141–85.
- The succession to Muḥammad: A study of the early caliphate*, Cambridge, 1997.
- Motzki, Harald, *Die Anfänge der islamischen Jurisprudenz*, Stuttgart, 1991.
- Muir, Sir William, *The life of Muhammad*, Edinburgh, 1861.
- Nevo, Yehuda D., and Judith Koren, *Crossroads to Islam: The origins of the Arab religion and the Arab state*, Amherst, NY, 2003.
- 'The origins of the Muslim descriptions of the jahilī Meccan sanctuary', *JNES*, 49 (1990), 23–44.
- Nöldeke, Theodor, *Geschichte des Qorans*, Göttingen, 1860; 2nd rev. edn ed. F. Schwally and G. Bergsträsser, 3 vols., Leipzig, 1909–38.
- Nöldeke, Theodor, *Orientalische Skizzen*, Berlin, 1892.
- Noth, Albrecht, 'Früher Islam', in Ulrich Haarmann et al. (eds.), *Geschichte der arabischen Welt*, Munich, 1987, 11–101.
- 'Iṣfahan Nihawand: Eine quellenkritische Studie zur frühislamischen Historiographie', *ZDMG*, 118 (1968), 274–96.
- Quellenkritische Untersuchungen zu Themen, Formen, und Tendenzen frühislamischer Geschichtsüberlieferung*, Bonn, 1973; rev. edn (with Lawrence I. Conrad), trans. Michael Bonner as *The early Arabic historical tradition*, Princeton, 1994.
- Petersen, Erling Ladewig, 'Alī and Mu'awiya in early Arabic tradition: Studies on the genesis and growth of Islamic historical writing until the end of the ninth century, 2nd edn, Odense, 1974 [Copenhagen, 1964].
- de Prémare, Alfred Louis, *Les fondations de l'Islam: Entre écriture et histoire*, Paris, 2002.
- Qureshi, Emran, and Michael A. Sells (eds.), *The new Crusades: Constructing the Muslim enemy*, New York, 2003.
- Recueil des historiens des croisades*, Paris, 1869–1906.
- Retsö, Jan, *The Arabs in Antiquity*, London and New York, 2003.
- Robinson, Chase F., 'The conquest of Khuzistan: A historiographical reassessment', *BSOAS*, 67 (2004), 14–39.
- Rodinson, Maxime, *La mystique de l'Islam*, Paris, 1980; trans. Roger Veinus as *Europe and the mystique of Islam*, Seattle, 1987.
- Rosenthal, Franz, *Das Fortleben der Antike im Islam*, Zurich, 1965; trans. Emile and Jenny Marmorstein as *The classical heritage in Islam*, Berkeley, 1975.
- Rubin, Uri, *The eye of the beholder: The life of Muḥammad as viewed by the early Muslims: A textual analysis*, Princeton, 1995.
- 'Morning and evening prayers in Islam', *JSAI*, 10 (1987), 40–64.
- Schacht, Joseph, *The origins of Muhammadan jurisprudence*, Oxford, 1950.
- Schoeler, Gregor, *Écrire et transmettre dans les débuts de l'Islam*, Paris, 2002.
- 'Die Frage der schriftlichen oder mündlichen Überlieferung der Wissenschaften in frühen Islam', *Der Islam*, 62 (1985), 201–30.
- Sellheim, Rudolf, 'Abu 'Alī al Qalī: Zum Problem mündlicher und schriftlicher Überlieferung am Beispiel von Sprichwörtersammlungen', in H. R. Roemer and A. Noth (eds.), *Studien zur Geschichte und Kultur des vorderen Orients: Festschrift für Bertold Spuler*, Leiden, 1981, 362–74.
- Sezgin, Fuat, *Geschichte des arabischen Schrifttums*, vol. I, Leiden, 1967.
- Shaban, M. A., *Islamic history: A new interpretation*, 2 vols., Cambridge, 1971.

- Sharon, Moshe, 'The birth of Islam in the Holy Land', in Moshe Sharon (ed.), *Pillars of smoke and fire: The Holy Land in history and thought*, Johannesburg, 1988, 225–35.
- Shoshan, Boaz, *Poetics of Islamic historiography: Deconstructing Tabari's History*, Leiden, 2004.
- Steinschneider, M., *al Farabi*, Mémoires de l'Académie Impériale de Sciences de Saint Petersburg 7, 8, 4, St Petersburg, 1869.
- Torrey, Charles Cutler, *The Jewish foundations of Islam*, New York, 1933.
- Waldman, Marilyn Robinson, 'New approaches to "biblical" materials in the Qur'an', *MW*, 75 (1985), 1–16.
- Wansbrough, John, *Qur'anic studies*, Oxford, 1977.
- The sectarian milieu: Content and composition of Islamic salvation history*, Oxford, 1978.
- Watt, William Montgomery, *Muhammad at Mecca*, Oxford, 1953.
- Muhammad at Medina*, Oxford, 1956.
- Muhammad, Prophet and statesman*, Oxford, 1961.
- Wellhausen, Julius, *Das arabische Reich und sein Sturz*, Berlin, 1902; trans. Margaret Graham Weir as *The Arab kingdom and its fall*, Calcutta, 1927.
- Muhammad in Medina, daß ist Vakidi's Kitab al Maghazi in verkürzter deutscher Wiedergabe herausgegeben*, Berlin, 1882.
- Prolegomena zur ältesten Geschichte des Islams, Skizzen und Vorarbeiten* 6, Berlin, 1899.

Chapter 16: Numismatics

Practical suggestions for further reading

- Bacharach, Jere L., *Islamic history through coins: An analysis and catalogue of tenth century Ikhshidid coinage*, Cairo, 2006.
- Broome, Michael, *A handbook of Islamic coins*, London, 1985.
- Brunschvig, Robert, 'Conceptions monétaires chez les juristes musulmanes (VIIIe–XIIIe siècles)', *Arabica*, 14 (1967), 113–43.
- Cipolla, Carlo M., *Money, prices and civilization in the Mediterranean world*, Princeton, 1956.
- Heidemann, Stefan, 'Economic growth and currency in Ayyubid Palestine', in Robert Hillenbrand (ed.), *Ayyubid Jerusalem: The Holy City in context*, 1187–1250, London, 2009, 275–99.
- 'Settlement patterns, economic development and archaeological coin finds in Bilad al Sham: The case of the Diyar Muḍar', in K. Bartl and A. Moaz (eds.), *Residences, castles, settlements: Transformation processes from Late Antiquity to early Islam in Bilad al Sham. Proceedings of the International Conference held at Damascus, 5–9 November 2006*, *Orient Archäologie* 24, Rahden, 2009, 489–513.
- (ed.), *Islamische Numismatik in Deutschland: Eine Bestandsaufnahme*, *Jenaer Beiträge zum Vorderen Orient* 2, Wiesbaden, 2000.
- Johns, Jeremy, 'Archaeology and the history of early Islam: The first seventy years', *JESHO*, 46 (2003), 411–36.
- Noonan, Thomas S., 'Early 'Abbasid mint output', *JESHO*, 29, (1986), 113–75.
- 'The start of the silver crisis in Islam: A comparative study of Central Asia and the Iberian peninsula', in Mário Gomes Marques and D. Michael Metcalf (eds.), *Problems of medieval coinage in the Iberian area*, vol. III, Santarém, 1988, 119–44.

Phillips, Marcus, 'Currency in seventh century Syria as a historical source', *Byzantine and Modern Greek Studies*, 28 (2004), 13–31.

Primary sources

- Album, Stephen, *Arabia and East Africa*, Sylloge of Islamic coins in the Ashmolean 10, Oxford, 1999.
A checklist of Islamic coins, 2nd edn, Santa Rosa, 1998.
Iran after the Mongol invasion, Sylloge of Islamic coins in the Ashmolean 9, Oxford, 2001.
- Album, Stephen, and Tony Goodwin, *The pre reform coinage of the early Islamic period*, Sylloge of Islamic coins in the Ashmolean 1, London, 2002.
- Bone, Harry, 'The administration of Umayyad Syria: The evidence of the copper coins', Ph.D. thesis, Princeton University, 2000.
- Diler, Ömer, *Islamic mints*, 3 vols., Istanbul, 2009.
- Djaparidze, Gotcha I., 'Nouvelles additions à l'ouvrage de Zambaur: Die Münzprägungen des Islams', *Bulletin d'Etudes Orientales*, 32–3 (1980–1), 89–97.
- Goodwin, Tony, *Arab Byzantine coinage*, Study in the Khalili Collection 4, London, 2005.
- Gyselen, Rika, *Arab Sasanian copper coinage*, Österreichische Akademie der Wissenschaften, Philosophisch Historische Klasse, Denkschriften 284, Veröffentlichungen der numismatischen Kommission 34, Vienna, 2000.
- Ilisch, Lutz, *Sylloge Numorum Arabicorum Tübingen: Palästina IVa Bilad aš Šam*, Tübingen, 1993.
- International Numismatic Commission, *A survey of numismatic research 1972–1977*, ed. Robert A. G. Carson *et al.*, Berne, 1979.
A survey of numismatic research 1978–1984, ed. Martin Price, London, 1986.
A survey of numismatic research 1985–1990, ed. Tony Hackens *et al.*, Brussels, 1991.
A survey of numismatic research 1990–1995, ed. Cécile Morrisson and Bernd Kluge, Berlin, 1997.
A survey of numismatic research 1996–2001, ed. Carmen Alfaro, Madrid, 2003.
- Klat, Michel, *Catalogue of the post reform dirhams: The Umayyad dynasty*, London, 2002.
- Kochnev, Boris and Michael Fedorov, *Sylloge Numorum Arabicorum, Buḥara*, Samarqand Mittelasiien, 25a, Berlin, 2008.
- Leimus, Ivar, *Sylloge of Islamic coins Estonian public collections*, Thesaurus historiae 2, Tallinn, 2007.
- Lowick, Nicholas, and Elisabeth Savage, *Early 'Abbasid coinage: A type catalogue 132–218 H/AD 750–833. A posthumous work by Nicholas Lowick*, ed. Elisabeth Savage, distributed manuscript, London, 1996.
- Malek, Hodge Mehdi, *The Dabuyid Ispahbads and early 'Abbasid governors of Ṭabaristan: History and numismatics*, Royal Numismatic Society Special Publication 39, London, 2004.
- Mayer, Leo Ari, *The bibliography of Moslem numismatics India excepted*, Oriental Translation Fund 35, London, 1954.
- Mayer, Tobias, *Sylloge der Münzen des Kaukasus und Osteuropas im Orientalischen Münzkabinett Jena*, Orientalisches Münzkabinett Jena 1, Wiesbaden, 2005.
- Sylloge Numorum Arabicorum: Nord und Ostzentralasien XVb, Mittelasiien II*, Tübingen, 1998.

Bibliography

- Miles, Georges Carpenter, 'Additions to Zambaur's Münzprägungen des Islams', *American Numismatics Society Museum Notes*, 12 (1971), 229–33.
- Nicol, Norman Douglas, *A corpus of Fatimid coins*, Trieste, 2006.
- The Egyptian dynasties*, Sylloge of Islamic coins in the Ashmolean 6, Oxford, 2007.
- Schwarz, Florian, *Sylloge Numorum Arabicorum Tübingen: Balḥ und die Landschaften am obereren Oxus XIVc Ḥurasan III*, Tübingen, 2002.
- Sylloge Numorum Arabicorum Tübingen, Ḡazna/Kabul XIV ad Ḥurasan IV*, Tübingen and Berlin, 1995.
- Sears, Stuart, 'A monetary history of Iraq and Iran, ca. CE 500 to 750', Ph.D. thesis, University of Chicago, 1997.
- Shamma, Samir, *A catalogue of 'Abbasid copper coins: Thabat al fulus al 'abbasiyya*, London, 1998.
- Treadwell, Luke, *Buyid coinage: A die corpus (322–445 AH)*, Oxford, 2001.
- von Zambaur, Eduard, *Die Münzprägung des Islams*, ed. Peter Jaekel, Wiesbaden, 1968.

Secondary sources

- Balaguer Prunés, Anna M., *Las emisiones transicionales árabe musulmanas de Hispania*, Barcelona, 1976.
- Balog, Paul, 'Fatimid glass jetons: Token currency or coin weights?', *JESHO*, 24 (1981), 93–109.
- Bates, Michael L., 'The dirham mint of the northern provinces of the Umayyad caliphate', *Armenian Numismatic Journal*, 15 (1989), 89–111.
- The expression of sovereignty in the Abbasid caliphate*, 218–334 H/833–946 CE (forthcoming).
- 'The function of Fatimid and Ayyubid glass weights', *JESHO*, 24 (1981), 63–92.
- 'History, geography and numismatics in the first century of Islamic coinage', *Schweizerische Numismatische Rundschau*, 65 (1986), 231–61.
- 'Khurasani revolutionaries and al Mahdī's title', in Farhad Daftary and Josef W. Meri (eds.), *Culture and memory in medieval Islam: Essays in honour of Wilferd Madelung*, London and New York, 2003, 279–317.
- DeShazo, Alan S., and Michael L. Bates, 'The Umayyad governors of al 'Iraq and the changing annulet patterns on their dirhams', *Numismatic Chronicle*, 14 (1974), 110–18.
- El Hibri, Tayyeb, 'Coinage reform under the 'Abbasid caliph al Ma'mun', *JESHO*, 36 (1993), 58–83.
- Foss, Clive, *Arab Byzantine coins: An introduction, with a catalogue of the Dumbarton Oaks Collection*, Cambridge, MA, 2009.
- Heidemann, Stefan, 'The development of the representation of the early Islamic empire and its religion on coin imagery', in Angelika Neuwirth, Nicolai Sinai and Michael Marx (eds.), *The Qur'an in context: Historical and literary investigations into the Qur'anic milieu*, Leiden, 2009, 149–95.
- 'Die Entwicklung der Methoden in der Islamischen Numismatik im 18. Jahrhundert: War Johann Jacob Reiske ihr Begründer?', in Hans Georg Ebert and Thoralf Hanstein (eds.), *Johann Jacob Reiske, Persönlichkeit und Wirkung*, Beiträge zur Leipziger Universitäts- und Wissenschaftsgeschichte, series B, no. 6, Leipzig, 2006, 147–202.

- ‘Die frühe Münzprägung von ar Raqqa/ar Rafiqā als Dokumente zur Geschichte der Stadt’, in Stefan Heidemann and Andrea Becker (eds.), *Raqqa*, vol. II: *Die islamische Stadt*, Mainz, 2003, 115–40.
- ‘Der Kleingeldumlauf in der Ġazīra in früh ‘abbasidischer Zeit und die Münzmissionen aus al Kufa’, in Stefan Heidemann and Andrea Becker (eds.), *Raqqa*, vol. II: *Die islamische Stadt*, Mainz, 2003, 141–60.
- ‘The merger of two currency zones in early Islam: The Byzantine and Sasanian impact on the circulation in former Byzantine Syria and northern Mesopotamia’, *Iran*, 36 (1998), 95–112.
- ‘Das Projekt, die Sylloge, der Bestand’, in Tobias Mayer, *Sylloge der Münzen des Kaukasus und Osteuropas im Orientalischen Münzkabinett Jena*, Orientalisches Münzkabinett Jena, 1, Wiesbaden, 2005, xi–xxii.
- Die Renaissance der Städte in Nordsyrien und Nordmesopotamien: Städtische Entwicklung und wirtschaftliche Bedingungen in ar Raqqa und Harran von der Zeit der beduinischen Vorherrschaft bis zu den Seldschuken*, Islamic History and Civilization, Studies and Texts 40, Leiden, 2002.
- Ilisch, Lutz, ‘Die Kupferprägung Nordmesopotamiens unter Harun ar Rašīd und seinen Söhnen (786–842 AD)’, in International Association of Professional Numismatists (eds.), *Numismatics: Witness to history*, IAPN publication 8, Basle, 1986, 101–21.
- ‘The Muhammad drachms and their relation to Umayyad Syria and northern Mesopotamia’, *Supplement of the Journal of the Oriental Numismatic Society*, 193 (Autumn 2007), 17–24.
- Review of *American Journal of Numismatics*, 1, *Der Islam*, 69 (1992), 381–2.
- ‘Stempelveränderungen an islamischen Münzen des Mittelalters als Quelle zur Münzstättenorganisation’, in Tony Hackens and Raymond Weiller (eds.), *Actes du 9ème congrès international de numismatique. Berne, Septembre 1979: Proceedings of the 9th International Congress of Numismatics, Berne, September 1979*, Louvain la Neuve and Luxembourg, 1982, 777–83, pl. 93–4.
- ‘Whole and fragmented dirhams in Near Eastern hoards’, in Kenneth Jonsson and Britta Malmer (eds.), *Sigtuna Papers: Proceedings of the Sigtuna symposium on Viking age coinage 1–4 June 1989, Stockholm*, Commentationes de nummis saeculorum in Suecia repertis, Nova Series 6, London, 1990, 121–8.
- Jamil, Nadia, ‘Caliph and Qutb: Poetry as a source for interpreting the transformation of the Byzantine cross on steps on Umayyad coinage’, in Jeremy Johns (ed.), *Bayt al Maqdis: Jerusalem and Early Islam*, Oxford Studies in Islamic Art 9, part 2, Oxford, 1999, 11–57.
- Mochiri, Malek Iraj, ‘A Pahlavi forerunner of the Umayyad reformed coinage’, *JRAS* (1981), 168–72.
- Morony, Michael G., ‘Economic boundaries? Late Antiquity and early Islam’, *JESHO*, 47 (2004), 166–94.
- Nicol, Norman Douglas, ‘Early ‘Abbasid administration in the central and eastern provinces, 132–218 AH/750–833 AD’, Ph.D. thesis, University of Washington, 1979.
- Oddy, Andrew, ‘Whither Arab Byzantine numismatics? A review of fifty years’ research’, *Byzantine and Modern Greek Studies*, 28 (2004), 121–52.
- Pottier, Henri, *Le monnayage de la Syrie sous l’occupation perse (610–630)/Coinage in Syria under Persian rule (610–630)*, Cahiers Ernest Babelon 9, Paris, 2004.

- Pottier, Henri, Ingrid Schulze and Wolfgang Schulze, 'Pseudo Byzantine coinage in Syria under Arab rule (638 c. 670): Classification and dating', *Revue numismatique belge*, 154 (2008), 87–155.
- Quchani, 'Abd Allah, 'The territory of Abu al Nadjm Badr b. Hasanuyah based on his coins', *Iranian Journal of Archaeology and History*, 8, 2 (1994), 46–65 (in Persian).
- Robinson, Chase F., *Empire and elites after the Muslim conquest: The transformation of northern Mesopotamia*, Cambridge Studies in Islamic Civilization, Cambridge, 2000.
- Sears, Stuart, 'A hybrid imitation of early Muslim coinage struck in Sijistan by Abu Bardha'a', *American Journal of Numismatics*, 1 (1989), 137–69.
- 'A monetary history of Iraq and Iran, ca. CE 500 to 750', Ph.D. thesis, University of Chicago, 1997.
- 'The Sasanian style drachms of Sistan', *Yarmouk Numismatics*, 11 (1999), 18–28.
- Shamma, Samir, *Aḥdath 'aṣr al Ma'mun kama tarwiha al nuqūd*, Irbid, 1995.
- Treadwell, W. Luke, *The chronology of the pre reform copper coinage of early Islamic Syria*, Supplement to Oriental Numismatic Society Newsletter 162, London, 2000.
- '"Mihrab and 'Anaza" or "sacrum and spear"? A reconsideration of an early Marwanid silver drachm', *Muqarnas*, 30 (2005), 1–28.
- 'Notes on the mint at Samarra', in Chase Robinson (ed.), *A medieval Islamic city reconsidered: An interdisciplinary approach to Samarra*, Oxford Studies in Islamic Art 14, Oxford, 2001, 141–56.
- 'The "orans" drachms of Bishr ibn Marwan and the figural coinage of the early Marwanid period', in Jeremy Johns (ed.), *Bayt al Maqdis: Jerusalem and Early Islam*, Oxford Studies in Islamic Art 9, part 2, Oxford, 1999, 223–69.
- Udovitch, Avram L., *Partnership and profit in medieval Islam*, Princeton, 1970.
- Vasmer, Richard, 'Zur Chronologie der Gāstaniden und Sallariden', *Islamica*, 3 (1927), 165–86, 482–5.

Chapter 17: Archaeology and material culture

Practical suggestions for further reading

- Creswell, K., *A short account of early Muslim architecture*, rev. and suppl. James Allan, Aldershot, 1989.
- Hodges, Richard, and David Whitehouse, *Mohammed, Charlemagne and the origins of Europe: Archaeology and the Pirenne thesis*, London, 1983.
- Hoyland, Robert, 'New documentary texts and the early Islamic state', *BSOAS*, 69, 3 (2006), 395–416.
- Johns, Jeremy, 'Archaeology and the history of early Islam: The first seventy years', *JESHO*, 46, 4 (2003), 411–36.
- Kennedy, Hugh, 'From polis to madina: Urban change in Late Antique and early Islamic Syria', *Past and Present*, 106 (February 1985), 3–27.
- Kennet, Derek, 'On the eve of Islam: Archaeological evidence from eastern Arabia', *Antiquity*, 79 (2005), 107–18.
- King, Geoffrey, and Averil Cameron (eds.), *The Byzantine and early Islamic Near East*, vol. II: *Land use and settlement patterns*, Studies in Late Antiquity and Early Islam 1, Princeton, 1994.

Secondary sources

- Adams, Robert, *Land behind Baghdad: A history of settlement on the Diyala plains*, Chicago and London, 1965.
- Almagro, Antonio, and Pedro Jiménez, 'The Umayyad mosque on the citadel of Amman', *Annual of the Department of Antiquities of Jordan*, 44 (2000), 459–76.
- Blackburn, M., and D. M. Metcalf (eds.), *Viking age coinage in northern lands*, BAR International Series 122, Oxford, 1981.
- Daiber, Verena, and Andrea Becker (eds.), *Raqqa III: Baudenkmäler und Paläste I*, Mainz am Rhein, 2004.
- Daryaei, Touraj, 'The Persian Gulf trade in Late Antiquity', *Journal of World History*, 14, 1 (March 2003), 1–16.
- Farooq, Abdul Aziz, 'Excavations at Mansurah (13th season)', *Pakistan Archaeology*, 10–12 (1974–86), 3–35.
- Finster, Barbara, 'Die Reiseroute Kufa–Sa'udi Arabien in frühislamische Zeit', *Baghdader Mitteilungen*, 9 (1978), 53–91.
- Gayraud, Roland Pierre, 'Fostat: Évolution d'une capitale arabe du VIIe au XIIe siècle d'après les fouilles d'Istabl 'Antar', in Roland Pierre Gayraud (ed.), *Colloque international d'archéologie islamique, IFAO, Le Caire, 3–7 février 1993*, Textes arabes et études islamiques 36, Cairo, 1999, 435–60.
- Gelichi, Sauro, and Marco Milanese, 'Problems in the transition toward the medieval in Ifriqiya: First results from the archaeological excavations at Uchi Maius (Teboursouk, Béja)', in M. Khanoussi, P. Ruggieri and C. Vismara (eds.), *L'Africa Romana: Atti del XII Convegno di Studio*, Sassari, 1998, 457–84.
- Genequand, Denis, 'Ma'an, an early Islamic settlement in southern Jordan: Preliminary report on the survey in 2002', *Annual of the Department of Antiquities of Jordan*, 47 (2003), 25–35.
- 'Umayyad castles: The shift from Late Antique military architecture to early Islamic palatial building', in Hugh Kennedy (ed.), *Muslim military architecture in Greater Syria: From the coming of Islam to the Ottoman Period*, History of Warfare 35, Leiden and Boston, 2006, 3–25.
- Glick, Thomas, 'Hydraulic technology in al Andalus', in S. Jayyusi (ed.), *The legacy of Muslim Spain*, Leiden, 1992, 974–86.
- Hearn, Maxwell, and Judith Smith (eds.), *Arts of the Sung and Yüan*, New York, 1996.
- Heidemann, Stefan, 'The history of the industrial and commercial area of 'Abbasid al Raqqa, called *al Raqqa al Muhtariqa*', *BSOAS*, 69, 1 (2006), 33–52.
- Henderson, Julian, et al., 'Experiment and innovation: Early Islamic industry at al Raqqa, Syria', *Antiquity*, 79 (2005), 130–45.
- Johns, Jeremy, 'The "House of the Prophet" and the concept of the mosque', in Jeremy Johns (ed.), *Bayt al Maqdis: Jerusalem and early Islam*, Oxford Studies in Islamic Art 9, part 2, Oxford, 1999, 59–112.
- Karev, Yuri, 'Samarqand in the eighth century: The evidence of transformation', in Donald Whitcomb (ed.), *Changing social identity with the spread of Islam: Archaeological perspectives*, Oriental Institute Seminars 1, Chicago, 2004, 51–66.
- Kennet, Derek, *Sasanian and Islamic pottery from Ras al Khaimah: Classification, chronology and analysis of trade in the western Indian Ocean*, BAR International Series 1248, Oxford, 2004.

- Khamis, Elias, 'Two wall mosaic inscriptions from the Umayyad market place in Bet Shean/Baysan', *BSOAS*, 64 (2001), 159–76.
- Khan, F., *Banbhore: A preliminary report on the recent archaeological excavations at Banbhore*, 4th edn, Karachi, 1976.
- King, Geoffrey, 'The distribution of sites and routes in the Jordanian and Syrian deserts', *Proceedings of the Seminar for Arabian Studies*, 20 (1987), 91–105.
- Kromann, Anne, and Else Roesdahl, 'The Vikings and the Islamic lands', in K. von Folsach *et al.* (eds.), *The Arabian journey: Danish connections with the Islamic world over a thousand years*, Aarhus, 1996, 9–17.
- Leone, Anna, 'Late Antique North Africa: Production and changing use of buildings in urban areas', *al Masaq*, 15, 1 (March, 2003), 21–33.
- Mason, Robert, *Shine like the sun: Lustre painted and associated pottery from the medieval Middle East*, Toronto and Costa Mesa, 2004.
- McNicol, Anthony, *et al.*, *Pella in Jordan*, 2 vols., Mediterranean Archaeology Supplements 2, Sydney, 1992.
- Northedge, Alastair, *The historical topography of Samarra*, Samarra Studies 1, London, 2005.
- Studies on Roman and Islamic 'Amman*, vol. I: *History, site and architecture*, British Academy Monographs in Archaeology 3, Oxford and New York, 1992.
- Rashid, Sa'd ibn 'Abd al 'Aziz, *al Rabadhah: A portrait of early Islamic civilization in Saudi Arabia*, Harlow, 1986.
- Rawson, Jessica, Michael Tite and M. Hughes, 'The export of Tang sancai wares: Some recent research', *Transactions of the Oriental Ceramics Society*, 52 (1987–8), 39–61.
- Sack, Dorothee, *Resafa IV: Die Grosse Moschee von Resafa Ruşafat Hisam*, Mainz, 1996.
- Safar, Fuad, *Wāsiṭ: The sixth season's excavations*, Cairo, 1945.
- Vogt, C., *et al.*, 'Notes on some of the Abbasid amphorae of Istabl 'Antar Fustat (Egypt)', *BASOR*, 326 (2002), 65–80.
- Watson, Andrew, *Agricultural innovation in the early Islamic world: The diffusion of crops and farming techniques*, Cambridge Studies in Islamic Civilization, Cambridge, 1983.
- Whitehouse, David, 'Chinese stoneware from Siraf: The earliest finds', in N. Hammond (ed.), *South Asian archaeology*, Park Ridge, NJ, 1973, 241–55.
- 'East Africa and the maritime trade of the Indian Ocean, AD 800–1500', in B. Amoretti (ed.), *Islam in East Africa: New sources*, Rome, 2001, 411–24.
- Siraf III: The congregational mosque and other mosques from the ninth to the twelfth centuries*, London, 1980.
- Wilkinson, J., 'Darb Zubayda architectural documentation program. B. Darb Zubayda 1979: The water resources', *Atlatl*, 4 (1980), 51–68.
- Wilkinson, T. J., 'Sohar ancient fields project: Interim report no. 1', *Journal of Oman Studies*, 1 (1975), 159–64.
- Williamson, Andrew, 'Regional distribution of mediaeval Persian pottery in the light of recent investigations', in James Allan and Caroline Roberts (eds.), *Syria and Iran: Three studies in medieval ceramics*, Oxford Studies in Islamic Art 4, Oxford, 1987, 11–22.
- www.islamicawareness.org/History/Islam/Inscriptions/, accessed 15 April 2007.

Conclusion: From formative Islam to classical Islam

Practical suggestions for further reading

- Calder, N., *Studies in early Muslim jurisprudence*, Oxford, 1993.
- Cooperson, M., and S. Toorawa (eds.), *Arabic literary culture, 500–925*, *Dictionary of Literary Biography*, vol. CCCXI, Detroit, 2005.
- Crone, P., *Medieval Islamic political thought*, Edinburgh, 2004.
- Crone, P., and M. Hinds, *God's caliph: Religious authority in the first centuries of Islam*, Cambridge, 1986.
- Donner, F. M., *Narratives of Islamic origins: The beginnings of Islamic historical writing*, Princeton, 1998.
- van Ess, J., *Theologie und Gesellschaft im 2. und 3. Jahrhundert Hidschra: Eine Geschichte des religiösen Denkens im frühen Islam*, 6 vols., Berlin, 1991–7.
- Gutas, D., *Greek thought, Arabic culture: The Graeco Arabic translation movement in Baghdad and early 'Abbasid society (2nd–4th/8th–10th centuries)*, London and New York, 1998.
- Halm, H., *Shi'ism*, 2nd edn, Edinburgh, 2004.
- Loveday, H., *Islamic paper: A study of the ancient craft*, London, 2001.
- Melchert, C., *The formation of the Sunni schools of law, 9th–10th centuries CE*, Leiden, 1997.
- Robinson, C. F., *Islamic historiography*, Cambridge, 2003.

Secondary sources

- Agha, S. S., 'A viewpoint on the Murji'a in the Umayyad period: Evolution through application', *Journal of Islamic Studies*, 8 (1997), 1–42.
- Cook, M., 'Activism and quietism in Islam: The case of the early Murji'a', in A. Cudsi and A. E. Dessouki (eds.), *Islam and power*, London, 1981, 15–23.
- 'Anan and Islam: The origins of Karaite scripturalism', *JSAI*, 9 (1987), 169–82.
- 'Early Islamic dietary law', *JSAI*, 7 (1986), 217–77.
- Crone, P., 'Jahili and Jewish law: The *qasama*', *JSAI*, 4 (1984), 153–201.
- Roman, provincial and Islamic law: The origins of the patronate*, Cambridge, 1987.
- Friedmann, Y., *Tolerance and coercion in Islam: Interfaith relations in the Muslim tradition*, Cambridge, 2003.
- Graham, W., 'Traditionalism in Islam: An essay in interpretation', *Journal of Interdisciplinary History*, 23 (1993), 495–522.
- Hurvitz, N., *The formation of Hanbalism: Piety into power*, London, 2002.
- Juynboll, G. H. A., 'Some new ideas on the development of *sunna* as a technical term in early Islam', *JSAI*, 10 (1987), 97–118.
- Kennedy, H., 'Central government and provincial elites in the early 'Abbasid caliphate', *BSOAS*, 44 (1981), 26–38.
- Kohlberg, E., 'Some Imami Shi'i views on the *ṣaḥāba*', *JSAI*, 5 (1984), 143–75.
- Madelung, W., 'The early Murji'a in Khurasan and Transoxiana and the spread of Hanafism', *Der Islam*, 59 (1982), 32–9.
- McMullen, D., *State and society in T'ang China*, Cambridge, 1989.
- Melchert, C., *Ahmad ibn Hanbal*, Oxford, 2006.
- Mitter, U., 'Origin and development of the Islamic patronate', in J. Nawas and M. Bernards (eds.), *Patronate and patronage in early and classical Islam*, Leiden, 2005, 70–133.

Bibliography

- Modarressi, H., *Crisis and consolidation in the formative period of Shi'ite Islam: Abu Ja'far ibn Qiba al Razi and his contribution to Imamite Shi'ite thought*, Princeton, 1993.
- 'Early debates on the integrity of the Qur'an: A brief survey', *SI*, 77 (1993), 5–39.
- Motzki, H., 'The role of non Arab converts in the development of early Islamic law', *Islamic Law and Society*, 6 (1999), 293–317.
- Nawas, J., 'A profile of the *mawali* 'ulama', in J. Nawas and M. Bernards (eds.), *Patronate and patronage in early and classical Islam*, Leiden, 2005, 454–80.
- Rissanen, S., *Theological encounter of Oriental Christians with Islam during early Abbasid rule*, Turku, 1993.
- Smith, W. C., 'Arkan', in D. P. Little (ed.), *Essays on Islamic civilization presented to Niyazi Berkes*, Leiden, 1976, 303–16.
- Toorawa, S., *Ibn Abi Ṭahir Ṭayfur and Arabic writerly culture*, London and New York, 2005.

THE NEW CAMBRIDGE HISTORY OF ISLAM

General Editor

Michael Cook, Class of 1943 University Professor of Near Eastern Studies,
Princeton University

The New Cambridge History of Islam offers a comprehensive history of Islamic civilisation, tracing its development from its beginnings in seventh-century Arabia to its wide and varied presence in the globalised world of today. Under the leadership of the Prophet Muḥammad, the Muslim community coalesced from a scattered, desert population and, following his death, emerged from Arabia to conquer an empire which, by the early eighth century, stretched from India in the east to Spain in the west. By the eighteenth century, despite political fragmentation, the Muslim world extended from West Africa to South-East Asia. Today, Muslims are also found in significant numbers in Europe and the Americas, and make up about one-fifth of the world's population.

To reflect this geographical distribution and the cultural, social and religious diversity of the peoples of the Muslim world, *The New Cambridge History of Islam* is divided into six volumes. Four cover historical developments, and two are devoted to themes that cut across geographical and chronological divisions – themes ranging from social, political and economic relations to the arts, literature and learning. Each volume begins with a panoramic introduction setting the scene for the ensuing chapters and examining relationships with adjacent civilisations. Two of the volumes – one historical, the other thematic – are dedicated to the developments of the last two centuries, and show how Muslims, united for so many years in their allegiance to an overarching and distinct tradition, have sought to come to terms with the emergence of Western hegemony and the transition to modernity.

The time is right for this new synthesis reflecting developments in scholarship over the last generation. *The New Cambridge History of Islam* is an ambitious enterprise directed and written by a team combining established authorities and innovative younger scholars. It will be the standard reference for students, scholars and all those with enquiring minds for years to come.

CAMBRIDGE
UNIVERSITY PRESS
www.cambridge.org

ISBN 978-0-521-83823-8



9 780521 838238 >